

V. A. Widner

July 28, 1980

Georgia Power

*the southern electric system*

U. S. Nuclear Regulatory Commission  
Office of Inspection and Enforcement  
Region II - Suite 3100  
101 Marietta Street, NW  
Atlanta, Georgia 30302

REFERENCE:  
RII: JPO  
50-321/50-366  
I&E Bulletin 80-17

ATTENTION: Mr. James P. O'Reilly

Gentlemen:

The following information is submitted in response to I&E Bulletin 80-17:

In accordance with Item 2 of the Bulletin, manual and automatic scrams were performed for Unit 1 on July 20, 1980 and July 21, 1980, respectively. The scram discharge volume responded properly, and no problems were noted. The data requested are given in Attachment 1.

In accordance with Item 3, SDV vent lines were verified to be functional at the conclusion of the above tests. In addition, significant amounts of residual water were not found to be present in the SDV and associated piping.

In accordance with Items 4a through 4d, necessary changes to the plant emergency operating procedures of both units have been completed and reviewed by Georgia Power Company and General Electric Company.

In accordance with Item 6a, notification as requested began on July 12, 1980, for both units. In addition, the requirements of Item 6b have been incorporated into the necessary procedures for both units.

Should you have any questions in this regard, please contact this office.

Very truly yours,

*J. S. Beckwith*  
for W. A. Widner

REB/mb  
Enclosure

Sworn to and subscribed before me this 28th day of July, 1980.

*W. H. Battle*

Notary Public

Notary Public, Georgia, State at Large  
My Commission Expires Sept. 20, 1983

A001  
s  
1/1

xc: Director of the Office of Inspection and Enforcement  
✓ Director of the Division of Operating Reactors, Office of Nuclear Reactor Regulation

ATTACHMENT 1  
HATCH UNIT 1 SCRAM TEST RESULTS

| Bulletin<br>80-17<br>Item # | Description   | Manual<br>Scram | Auto<br>Scram |
|-----------------------------|---|-----------------|---------------|
| 2a                          | All rod insert time, sec  | apx. 3          | apx 7.6       |
|                             | North HCU bank (14 rods):<br>(individual rod scram times):                    |                 |               |
|                             | avg. 90% insertion time, sec  | 2.460           | 2.425         |
|                             | max. 90% insertion time, sec  | 2.936           | 2.952         |
|                             | min. 90% insertion time, sec  | 2.242           | 2.208         |
|                             | South HCU bank (14 rods):   |                 |               |
|                             | avg. 90% insertion time, sec  | 2.541           | 2.605         |
|                             | max. 90% insertion time, sec  | 3.169           | 4.175         |
|                             | min. 90% insertion time, sec  | 2.202           | 2.217         |
| 2b                          | Scram solenoid valve solenoids<br>deenergized upon receipt of<br>scram signal | yes             | yes           |
| 2c                          | Scram air relieved through<br>backup valves                                   | yes             | yes           |
|                             | Backup valves remained open<br>during presence of scram signal                | yes             | yes           |
| 2d                          | Time for scram initiation to: (sec)   |                 |               |
|                             | closure of not drained alarm switch   | 40.5            | 40.8          |
|                             | closure of rod withdrawal block switch  | 60.65           | 59.5          |
|                             | closure of reactor scram switch (avg)   | 14.76           | 14.93         |
| 2e                          | (measured on 7-22-80)   |                 |               |
|                             | vent valve F010A opening time, sec  | 32.1            |               |
|                             | vent valve F010B opening time, sec  | 5.5             |               |
|                             | drain valve F011 opening time, sec  | 24.7            |               |
|                             | vent valve F010A closing time, sec  | 42.4            |               |
|                             | vent valve F010B closing time, sec  | 45.75           |               |
|                             | drain valve F011 closing time, sec  | 49.6            |               |
| 2f                          | Delay from scram initiation to closure of:                                    |                 |               |
|                             | vent valve F010A  | 43.45           | 43.95         |
|                             | vent valve F010B  | 41.05           | 40.95         |
|                             | drain valve F011  | 49.85           | 48.58         |
| 2g                          | SDV water analysis results:   |                 |               |
|                             | turbidity, NTU  | 13              | 12            |
|                             | filterable solids, ppm  | 50              | 20            |
|                             | SiO <sub>2</sub> , ppb  | 136             | 292           |
| 2h                          | time from scram reset to: (min: sec)  |                 |               |
|                             | North SDV bank scram switches clear   | 8:15            | 8:24.2        |
|                             | South SDV bank scram switches clear   | 12:17.3         | 12:34.4       |

|    |  |     |     |
|----|--|-----|-----|
| 2i | SDV & associated piping free of residual water following scram | yes | yes |
| 2j | 10 sec delay on scram reset functioning properly               | yes | yes |
| 2k | Comparison of results  | OK  | OK  |