

UNITED STATES NUCLEAR REGULATORY COMMISSION REGION III 799 ROOSEVELT ROAD GLEN ELLYN. ILLINOIS 50137

'JUL' 3 1980

Docket No. 50-440 Docket No. 50-441

The Cleveland Electric Illuminating Company ATTN: Mr. Dalwyn R. Davidson Vice President - Engineering P. O. Box 5000 Cleveland, OH 44101

Gentlemen:

This enclosed IE Bulletin No. 80-17, is forwarded to you for information. No written response is required. If you desire additional information regarding this matter, please contact this office.

Sincerely,

James G. Kepp Director

Enclosure: IE Bulletin No. 80-17

6

cc w/encl: Central Files Director, NRR/DPM Director, NRR/DOR PDR Local PDR NSIC TIC Harold W. Kohn, Power Siting Commission Mr. Daniel D. Wilt, Attorney Helen Evans, State of Ohio

8008060 504

SSINS No.: 6820 Accession No.: 8005050076

UNITED STATES NUCLEAR REGULATORY COMMISSION OFFICE OF INSPECTION AND ENFORCEMENT

JULY 3, 1980

IE BULLETIN NO. 80-17

FAILURE OF 76 OF 185 CONTROL RODS TO FULLY INSERT DURING A SCRAM AT A BWR

Description of Circumstances:

On June 28, 1980, 76 of the 185 control rods failed to fully insert during a routine shutdown at TVA's Browns Ferry Unit No. 3 located at Athens, Alabama. The reactor was manually scrammed from about 30 percent power in accordance with routine shutdown procedures. The shutdown was initiated to repair the feedwater system. The 76 control rods that failed to fully insert were all on the east side of the core.

Following scram discharge volume (SDV) high level bypass and a short drain period of the SDV, a second manual scram was initiated and all partially inserted rods were observed to drive inward, but 59 remained partially withdrawn. A third manual scram was made, again following high level in the SDV and bypassing for another short drain of the SDV, with the result that 47 rods remained partially withdrawn. Following a longer drain of the SDV, an automatic scram occurred that was initiated by a scram discharge volume tank high water level signal when the scram reset switch was placed in "Normal"; with this scram all remaining rods fully inserted. The total time elapse from the initial scram to the time that all rods were inserted was approximately 15 minutes. Core coclant flow, temperature and pressure remained normal for plant conditions. The unit is now shutdown and additional testing indicates that a possible cause of the malfunction was the retention of a significant amount of water in the east bank scram discharge volume. In view of these interim findings and pending results of continued investigation, the following actions are to be taken.

Actions To Be Taken By Licensees:

All General Electric Boiling Water Reactors with operating licenses which are operating at any power on the date of this Bulletin shall perform the following steps in the time state perform the following steps prion

 Within 3 days from the date tests to verify that there Discharge Volume (SDV) and are operable and vent syste

DUPLICATE DOCUMENT
Entire document previously entered into system under:
ANO 8005050076
No. cf pages: 5