JUL 25 1977

Docket No.: 50-302

Florida Power Corporation ATTN: Mr. J. T. Rodgers, Assistant Vice President and Nuclear Project Manager P.O. Box 14042 St. Petersburg, Florida 33733

Gentlemen:

RE: CRYSTAL RIVER UNIT NO. 3

DISTRIBUTION: Docket NRC PDR L PDR ORB#4 Rdg. RWReid RIngram CNelson JWetmore Attorney, OELD 01&E(3) DEisenhut TBAbernathy JRBuchanan ACRS (16) TCarter Gray file

A large number of PWR High Pressure and Low Pressure Safety Injection Systems (HPSI and LPSI) utilize a common low pressure and a common high pressure header to feed the several cold (and in some cases not) leg injection points. Maintenance of proper flow resistance and pressure drop in the piping system to each injection point is necessary to:

(1) prevent total pump flow from exceeding runout conditions when the system is in its minimum resistance configuration; (2) provide a proper flow split between injection points in accordance with the assumptions used in the ECCS-LOCA analyses, and (3) provide an acceptable level of total ECCS flow to all injection points equal to or above that assumed in the ECCS-LOCA analyses. Many plants have either manual or motor operated valve(s) in the lines to each injection point that have electrical or mechanical stops which have been adjusted during preoperational testing of the plant to ensure that these flow requirements are satisified.

In view of the safety function associated with the proper setting of valves used to throttle flow in these systems, we consider it appropriate that periodic verification be made of these valve positions. Accordingly, we request that you determine if throttle valves are used to obtain the required flow distribution in the HPSI or LPSI systems. If throttle valves are used, we request that you propose changes to your technical specifications to incorporate the surveillance requirements given in the enclosure.

In the event valves are not utilized to throttle flow in your systems, you should advise us of this fact and no further action will be required.

ECCS

The above action should be completed within 60 days of receipt of this letter. In the event you should desire further discussion of this matter, please contact us.

Sincerely,

Robert W. Reid, Chief Operating Reactors Branch #4 Division of Operating Reactors

Enclosure: Technical Specifications

cc w/enclosure: See next page

POOR ORIGINAL

		STCL				
OFFICE >	ORB#4:DOR	ORB#S PORA)	C-ORB#4:DOR			- HARAN
SURNAME	CNedson:dn		RWReid		***************************************	
DATE	7/25/77	7/25/72	7/-3/77	***************************************		

Florida Power Curporation

Cc: Mr. S. A. Brandimore
 Vice President and Genera?
 Counsel
 P. O. Box 14042
 St. Petersburg, Florida 33733

Crystal River Public Library Crystal River, Florida 32629

POOR ORIGINAL

PWR HPSI AND LPSI SYSTEM THROTTLE VALVE STOPS

- The correct position of each electrical and/or mechanical position stop for the following throtale valves shall be verified:
 - a. Within 4 hours following completion of each valve stroking operation or maintenance on the valve when the HPSI or LPSI System is required to be operable.
 - b. At least once per 18 months.

HPSI System	LPSI System		
Valve Number	Valve Number		
1	1		
3.	3.		
5.	5		

 A flow balance test shall be performed during shutdown to confirm the following minimum injection flow rates following completion of HPSI or LPSI system modifications that alter system flow characteristics:

HPSI System - Single Pump	LPSI System - Single Pump			
Injection Leg Inject	Injection Leg Inject			

Bases

The purpose of these surveillance requirements is to provide assurance that proper ECCS flows will be maintained in the event of a LOCA. Maintenance of proper flow resistance and pressure drop in the piping system to each injection point is necessary to: (1) prevent total pump flow from exceeding runout conditions when the system is in its minimum resistance configuration, (2) provide the proper flow split between injection points in accordance with the assumptions used in the ECCS-LOCA analyses, and (3) provide an acceptable level of total ECCS flow to all injection points equal to or above that assumed in the ECCS-LOCA analyses.