



UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D. C. 20555

NRC/PDR

FEB - 0 1981

Docket No. 50-483

Mr. John K. Bryan
Vice President
Union Electric Company
1901 Gratiot Street
Post Office Box 149
St. Louis, Missouri 63166



Dear Mr. Bryan:

SUBJECT: PRESERVICE INSPECTION AND TESTING OF SNUBBERS - CALLAWAY PLANT, UNIT 1

The Office of Inspection and Enforcement has requested that preservice inspection and test requirements for snubbers be included in the licensing process. Based on this request and the long history of snubber problems as documented by Licensee Event Reports on the subject of inoperable and incorrectly installed snubbers, it is requested that the enclosed requirements to insure snubber operability be implemented at the Callaway Plant, Unit 1.

Sincerely,

Robert L. Tedesco, Assistant Director
for Licensing
Division of Licensing

Enclosure:
As stated

cc w/enclosure:
See next page

8103034087

Mr. J. K. Ryan
Vice President - Nuclear
Union Electric Company
P. O. Box 149
St. Louis, Missouri 63166

cc: Mr. Nicholas A. Petrick
Executive Director - SNUPPS
5 Choke Cherry Road
Rockville, Maryland 20850

Mr. William Hansen
Resident Inspector/Callaway NPS
c/o USNRC
Steedman, Missouri 65077

Gerald Charnoff, Esq.
Shaw, Pittman, Potts &
Trowbridge
1800 M Street, N. W.
Washington, D. C. 20036

Mr. J. E. Birk
Assistant to the General Counsel
Union Electric Company
P. O. Box 149
St. Louis, Missouri 63166

Dr. Vern Starks
Route 1, Box 863
Ketchikan, Alaska 99901

Ms. TrevaHearn, Assistant General
Counsel
Missouri Public Service Commission
P. O. Box 360
Jefferson City, Missouri 65102

Mr. D. F. Schnell
Manager-Nuclear Engineering
Union Electric Company
P. O. Box 149
St. Louis, Missouri 63166

TO ALL APPLICANTS:

Due to a long history of problems dealing with inoperable and incorrectly installed snubbers, and due to the potential safety significance of failed snubbers in safety related systems and components, it is requested that maintenance records for snubbers be documented as follows:

Pre-service Examination

A pre-service examination should be made on all snubbers listed in tables 3.7-4a and 3.7-4b of Standard Technical Specifications 3/4.7.9. This examination should be made after snubber installation, but not more than six months prior to initial system pre-operational testing, and should as a minimum verify the following:

- (1) There are no visible signs of damage or impaired operability as a result of storage, handling, or installation.
- (2) The snubber location, orientation, position setting, and configuration (attachments, extensions, etc.) are according to design drawings and specifications.
- (3) Snubbers are not seized, frozen or jammed.
- (4) Adequate swing clearance is provided to allow snubber movement.
- (5) If applicable, fluid is to the recommended level and is not leaking from the snubber system.
- (6) Structural connections such as pins, fasteners and other connecting hardware such as lock nuts, tabs, wire, cotter pins are installed correctly.

If the period between the initial pre-service examination and initial system pre-operational test exceeds six months due to unexpected situations, re-examination of items 1, 4, and 5 shall be performed. Snubbers which are installed incorrectly or otherwise fail to meet the above requirements must be repaired or replaced and re-examined in accordance with the above criteria.

Pre-Operational Testing

During pre-operational testing, snubber thermal movements for systems whose operating temperature exceeds 250° F should be verified as follows:

- (a) During initial system heatup and cooldown, at specified temperature intervals for any system which attains operating temperature, verify the snubber expected thermal movement.
- (b) For those systems which do not attain operating temperature, verify via observation and/or calculation that the snubber will accommodate the projected thermal movement.
- (c) Verify the snubber swing clearance at specified heatup and cooldown intervals. Any discrepancies or inconsistencies shall be evaluated for cause and corrected prior to proceeding to the next specified interval.

The above described operability program for snubbers should be included and documented by the pre-service inspection and pre-operational test programs.

The pre-service inspection must be a prerequisite for the pre-operational testing of snubber thermal motion. This test program should be specified in Chapter 14 of the FSAR.