

TABLE 3.3.2-2 (Continued)

ISOLATION ACTUATION INSTRUMENTATION SETPOINTS

<u>TRIP FUNCTION</u>	<u>TRIP SETPOINT</u>	<u>ALLOWABLE VALUE</u>
5. <u>REACTOR CORE ISOLATION COOLING SYSTEM ISOLATION</u>		
a. RCIC Steam Line Flow - High	< 290" H ₂ O**	< 298.5" H ₂ O**
b. RCIC Steam Supply Pressure - Low	> 50 psig	> 55 psig
c. RCIC Turbine Exhaust Diaphragm Pressure - High	< 10 psig	< 20 psig
d. RCIC Equipment Room Ambient Temperature - High	< 143.4°F	< 145.9°F
e. RCIC Equipment Room Δ Temperature - High	< 70.9°F # 37.25°F #	< 72.2°F # 39°F #
f. Main Steam Line Tunnel Ambient Temperature - High	< 154.4°F**	< 158.9°F**
g. Main Steam Line Tunnel Δ Temperature - High	< 103.6°F**	< 107.4°F**
h. Main Steam Line Tunnel Temperature Timer	< 29 minutes	< 30 minutes
i. RHR Equipment Room Ambient Temperature - High	< 157.4°F	< 159.9°F
j. RHR Equipment Room Δ Temperature - High	< 50.65°F	< 52.4°F
k. RCIC Steam Flow High Timer	3 seconds ≤ t ≤ 13 seconds	3 seconds ≤ t ≤ 13 seconds
l. Drywell Pressure - High	< 1.68 psig	< 1.88 psig
m. Manual Initiation	NA	NA

This Amendment
←

PERRY - UNIT 1

9002010341 900126
PDR ADDCK 05000440
PDC

3/4 3-19

Amendment No. 7

TABLE 3.3.2-2 (Continued)

ISOLATION ACTUATION INSTRUMENTATION SETPOINTS

<u>TRIP FUNCTION</u>	<u>TRIP SETPOINT</u>	<u>ALLOWABLE VALUE</u>
6. <u>RHR SYSTEM ISOLATION</u>		
a. RHR Equipment Area Ambient Temperature - High	$\leq 157.4^{\circ}\text{F}$	$\leq 159.9^{\circ}\text{F}$
b. RHR Equipment Area Δ Temperature - High	$\leq 50.65^{\circ}\text{F}$	$\leq 52.4^{\circ}\text{F}$
c. RHR/RCIC Steam Line Flow - High	$\leq 105^{\circ}\text{ H}_2\text{O}^{\text{**}}$	$\leq 114^{\circ}\text{ H}_2\text{O}^{\text{**}}$
d. Reactor Vessel Water Level - Low, Level 3	≥ 177.7 inches*	≥ 177.1 inches
e. Reactor Vessel (RHR Cut-in Permissive) Pressure - High	≤ 135 psig	≤ 150 psig
f. Drywell Pressure - High	≤ 1.68 psig	≤ 1.68 psig
g. Manual Initiation	NA	NA

*See Bases Figure B 3/4 3-1.

**Initial setpoint. Final setpoint to be determined during startup test program. Any required change to this setpoint shall be submitted to the Commission within 90 days of test completion.

These values are in effect until lake temperatures exceed 55°F.

This amendment
←