## JIN 1 7 1981

Docket No. 50-395

fir. T. C. Nichols, Jr.
Vice President & Group Executive
Nuclear Operations
South Carolina Electric & Gas Company
P. O. Box 764
Columbia, South Carolina 29218

Dear Mr. Nichols:

DISTREBUTION
Docket File
LB#4 Rdg
DEisenhut
TKenyon
MRushbrook
RTedesco
WKane
RVollmer
TMurley
RMattson
RHartfield, MPA
VNoonan
OELD
OIE (3)

bcc: TERA/NSIC/TIC NRC/PDR L/PDR ACRS (16)



SUBJECT: TMI-2 ACTION PLAN ITEM I.G.1 - SPECIAL LOW POWER TESTING

NUREG-0737 "Clarification of TMI Action Plan Requirements" and NUREG-0694 "TMI Related Requirements for New Operating Licenses", Item I.G.1, calls for the implementation of "a special low power testing program approved by MRC to be conducted at power levels no greater than 5 percent for the purposes of providing meaningful technical information beyord that obtained in the normal startup test program and to provide supplemental training". Some PWR applicants have committed to a series of natural circulation tests. To date such tests have been performed at the Sequovah 1, North Anna 2, and Salem 2 facilities. Based on the success of the programs at these plants. the staff has concluded that augmented natural circulation training should be performed for all future PWR operating licenses. This is to be implemented by including descriptions of natural circulation tests in your FSAP (Chapter 14 - Initial Test Program). If they are not already included in your FSAR, the natural circulation tests and associated training should be included either by modifying existing or adding new test descriptions in accordance with Regulatory Guide 1.70, Paragraph 14.2.12. The tests should fulfill the following objectives:

## Training

Each licensed reactor operator (RO or SRO who performs RO or SRO duties, respectively) should participate in the initiation, maintenance and recovery from natural circulation mode. Operators should be able to recognize when natural circulation has stabilized, and should be able to control saturation margin, RCS pressure, and heat removal rate without exceeding specified operating limits.

## Testing

The tests should demonstrate the following plant characteristics: length of time required to stabilize natural circulation, core flow distribution, ability to establish and maintain natural circulation with and without

8106290 219

AC SCHIR SIR TO EST NACH SEAD

onsite and offsite power, the ability to uniformly borate and cool down to hot shutdown conditions using natural circulation, and subcooling monitor performance.

If these tests have been performed at a comparable prototype plant, they need be repeated only to the extent necessary to accomplish the above training objectives.

## Procedure Validation

The tests should make maximum practical use of written plant procedures to validate the completeness and accuracy of the procedures.

The natural circulation tests require a source of actual or simulated decay heat. The tests may be performed during initial startup using nuclear heat to simulate decay heat, or may be performed later in the initial fuel cycle when actual decay heat is adequate to permit meaningful testing. If the test objectives are not compromised, pump heat during forced circulation operation could provide an acceptable source of simulated decay heat (e.g., the Loss-of-Onsite and Offsite A/C Test performed at North Anna 2).

Applicants who perform a natural circulation boron-mixing and cooldown test to demonstrate compliance with Branch Technical Position RSB BTP 5-1 may use that test to accomplish some or all of the above training and testing objectives.

This guidance is provided for all PWR CL applicants and supersedes that dated hovember 14, 1980. Regulatory Guide 1.68 and/or the Standard Review Plan will be revised at a future date to include natural circulation testing and the associated training. OL applicants should submit test descriptions in accordance with Regulatory Guide 1.70, Paragraph 14.2.12, as part of their FSAR or an amendment thereto. Detailed test procedures should be made available for MRC review 60 days prior to scheduled test performance (see Regulatory Guide 1.68, Appendix 8). When required by 10 CFR 50.59, a safety analysis must be prepared and distributed in accordance with the requirements stated therein.

Sincerely,

Criginal signed by

Robert L. Tedesco, Assistant Director for Licensing Division of Licensing

cc: See next page

DL:LB#1 WKane:eb

EATT > 6/1 /81

BJYDDINGD1 6/\S81

DL: ANYL

BJYbargblood RTedesco.

16/81

POOR ORIGINAL

Mr. T. C. Nichols, Jr.
Vice President & Group Executive
Nuclear Operations
South Carolina Electric & Gas Company
P. O. Box 764
Columbia, South Carolina 29218

cc: Mr. Henry Cyrus
Senior Vice President
South Carolina Public Service Authority
223 North Live Oak Drive
Moncks Corner, South Carolina 29461

J. B. Knotts, Jr., Esq. Debevoise & Liberman 1200 17th Street, N. W. Washington, D. C. 20036

Mr. Mark B. Whitaker, Jr.
Group Manager - Nuclear Engineering & Licensing
South Carolina Electric & Gas Company
P. O. Box 764
Columbia, South Carolina 29218

Mr. Brett Allen Bursey Route 1, Box 93C Little Mountain, South Carolina 29076

Resident Inspector/Summer NPS c/o U. S. NRC Route 1, Box 64 Jenkinsville, South Carolina 29065

Dr. John Ruoff Post Office Box 96 Jenkinsville, South Carolina 29065