CHAIS NELSON Lainas 2001.

#### BUR OWNERS' GROUP

T. J. Dente

P.O. Box 1551 - Roleigh North Corollino 27602 - (919) 836-6584 P.O. Box 270, Hartford, CT 06101

BWROG-8148

July 1, 1981

U. S. Nuclear Regulatory Commission Division of Licensing Office of Nuclear Reactor Regulation Washington, D.C. 20555

sel

Attention: Darrell G. Eisenhut, Director

SUBJECT: Transmittal of Preliminary Data From Generic BWR

Safety/Relief Valve (S/RV) Test Program

Gentlemen:

In response to NUREG-0737, Item II.D.1, this letter transmits the preliminary generic BWR S/RV test program results. These attached results are provided as preliminary data sheets and demonstrate the operational adequacy of the SRV's used by the plants listed in Table 1. The final test report documenting the test results will be provided by October 1, 1981, per the NUREG-0737 requirement.

Yours

aly,

T. J. Dente, Chairman BWR Owners' Group

TJD: PWM

Enclosures

cc: BWR Owners' Group

P. W. Marriott (GE)

S. J. Stark (GE)

M. W. Hodges (NRC)

J. A. Olshinksi (NRC)

D. M. Verrelli (NRC)

6001

#### TABLE 1 PARTICIPATING UTILITIES NUREG-0737, II.D.1

This report applies to the following plants, whose owners participated in the report's development.

Niagara Mohawk Power

Jersey Central Power & Light

Northeast Utilities

Commonwealth Edison Co.

Northern States Power

Boston Edison Co.

Vermont Yankee

Iowa Electric Light & Power

Nebraska Public Power District

Tennessee Valley Authority

Carolina Power & Light

Philadelphia Electric Co.

Power Authority of the State

of New York

Long Island Lighting Company

Public Service Electric & Gas

Pennsylvania Power & Light

Detroit Edison Co.

Georgia Power Co.

Nine Mile Point 1, Nine Mile Point 2

Oyster Creek

Millstone

Dresden 2, Dresden 3,

Quad Cities 1, Quad Cities 2,

La Salle 1, La Salle 2

Monticello

Pilgrim

Vermont Yankee

Duane Arnold

Co per

owns Ferry 1, 2, & 3

martsville 1, 2, 3 & 4

Phipps Bend 1 & 2

Brunswick 1, Brunswick 2

Peach Bottom 2, Peach Bottom 3,

Limerick 1, Limerick 2

Fitzpatrick

Shorenam

Hope Creek 1, Hope Creek 2

Susquehanna 1, Susquehanna 2

Fermi 2

Hatch 1, Hatch 2

Cincinnati Gas & Electric

Washington Public Power Supply System

Public Service of Oklahoma

Mississippi Power & Light

Gulf States Utilities

Illinois Power Company

Cleveland Electric Illuminating

Company

Houston Light & Power

Zimmer 1

Hanford 2

Black Fox 1, Black Fox 2

Grand Gulf 1, Grand Gulf 2

River Bend 1, River Bend 2

Clinton 1, Clinton 2

Perry 1, Perry 2

Allens Creek 1, Allens Creek 2

DATE TESTED 2-13-81	RUN/TEST NO006
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSBY 8R10
TYPE OF TEST STEAM, SATURATED,	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV TLUID TEST CONDITIONS	
FLUID TEMPERATURE	555° F
INLET PRESSURE	1080 PS1G
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	26 mSec
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	RUN/TEST NO. 007	
	S/RV MANUFACTURER CROSBY 8R10	
TYPE OF TEST  WATER, 150F SUBCOOLED	LOADS I SUPPORTS	
TEST RESULTS S/RV OFENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS	190°F	
FLUID TEMPERATURE	190°F	
INLET PRESSURE	252 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	240mSec at 0 PSIS	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY 14SPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE * NOT APPLICABLE		

DATE TESTED 2-14-81	RUN/TEST NO008
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSBY 8R10
TYPE OF TEST STEAM, SATURATED,	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555 <sup>0</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	24mSec
VAL SE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY LEMONSTRATED	YES
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE	

DATE TESTED 2-14-81	RUN/TEST NO. 009
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSBY 8R10
TYPE OF TEST  WATER, 500F SUBCOOLED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS FLUID TEMPERATURE	157 <sup>0</sup> F
INLET PRESSURE	253 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISE LIFT TIME)	300mSec at 0 PSIG
VALVE INTEGRITY DEMONSTRATED 51:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE	

DATE TESTED 2-26-81	RUN/TEST NO021
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)  TYPE OF TEST  STEAM, SATURATED	S/RV MANUFACTURER CROSBY 8R10  LOADS I SUPPORTS
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555°F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	24mSec
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE	

DATE TESTED 2-26-81	RUN/TEST NO. 022	_
S/RV MODEL NO. HB-65-DF S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSBY 8P10	-
TYPE OF TEST WATER, 150F SUBCOOLED	LOADS I SUPP	ORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/AV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLU'D TEMPERATURE	215 <sup>0</sup> F	
INLET PRESSURF	281 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	*	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	-
POST-TEST HYDRO+	YES	
POST-TEST DISASSEMBLY INSPECTION+	YES	
FACILITY INTEGRITY DEMONSTRATED	YES	

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> OPEN PRIOR TO TEST

DATE TESTED 2-21-81	RUN/TEST NO. 013
S/RV MODEL NO. HB-65-DF	S/RV MANUFACTURERCROSBY_8RT
S/RV SERIAL NOQV5 (GE ENGR. TEST UNIT)	
TYPE OF TEST  STEAM, SATURATED	LOADS I SUPPORTS
TEST PESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555 <sup>6</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	21mSec
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE	

DATE TESTED 2-24-81	RUN/TEST NO. 016
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSBY 8R10
TYPE OF TEST  WATER, 150 F SUBCOOLED	LOADS II SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS FLUID TEMPERATURE	201 <sup>0</sup> F
INLET PRESSURE	296 PSIG
S/RV FLOW RATE	1 .ER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	**
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* NOT APPLICABLE
- \*\* OPEN PRIOR TO TEST

DATE TESTED 2-25-81	RUN/TEST NO. 017
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UMIT)	S/RV MANUFACTURER CROSBY 8R10
TYPE OF TEST  STEAM, SATURATED,	LOADS II SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS FLUID TEMPERATURE	555 <sup>0</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	24mSec
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE	

DATE TESTED 2-25-81	RUN/TEST NO018
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSBY 8R10
TYPE OF TEST  WATER, 150F SUBCOOLED	LOADS II SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS FLUID TEMPERATURE	208 <sup>0</sup> F
INLET PRESSURE	282 PSIG
S/RY FLOW RATE	LATER
S/R. OPENING TIME (MAIN DISK LIFT TIME)	350mSec at 0 PSIG
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* NOT APPLICABLE

DATE TESTED 2-25-81	RUN/TEST NO. 019
S/RV MODEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSEY 8R10
TYPE OF TEST  STEAM, SATURATED	LOADS II SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS  FLUID TEMPERATURE	555 <sup>0</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	25mSec
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* NOT APPLICABLE

DATE TESTED 2-26-81	RUN/TEST NO. 020	
S/RV MCDEL NO. HB-65-DF  S/RV SERIAL NO QV5 (GE ENGR. TEST UNIT)	S/RV MANUFACTURER CROSBY 8R10	
TYPE OF TEST  WATER, 50°F SUBCOOLED	LOADS II SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	175°F	
INLET PRESSURE	275 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)		
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO*	YES	
POST-TEST DISASSEMBLY INSPECTION+	YES	
FACILITY INTEGRITY DEMONSTRATED	YES	
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE		

\* OPEN PRIOR TO TEST

DATE TESTED 3-3-81	RUN/TEST NO. 101	
S/RV MODEL NO. 6.471-6/125.04	S/RV MANUFACTURER DIKKERS	
S/RV SERIAL NO. 160814	3R10	
TYPE OF TEST	T CHANGE	
STEAM, SATURATED	LOADS I SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	555°F	
INLET PRESSURE	1080 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	63mSec	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 3-3-81	RUN/TEST NO102
S/RV MODEL NO. G.471-6/125.04	S/RV MANUFACTURER DIKKERS
S/RV SERIAL NO. 160814	8R10
TYPE OF TEST	LOADS I SUPPORTS
WATER, 15°F SUBCOOLED	
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	207°F
INLET PRESSURE	250 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	**
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

<sup>\*\*</sup> OPEN PRIOR TO TEST

DATE TESTED 3-4-81	RUN/TEST NO103	
S/RV MODEL NO. G.471-6/125.04	S/RV MANUFACTURER DIKKERS 8R10	
S/RV SERIAL NO. 160814		
TYPE OF TEST		
STLAM, SATURATED	LOADS I SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	<u>'/ES</u>	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	555°F	
INLET PRESSURE	1080 PSIG	
S/RV FLOW RATE	LATER	
S/RV CPENING TIME (MAIN DISK LIFT TIME)	5°mSec	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE		

DATE TESTED 3-4-81	RUN/TEST NO	
S/RV MODEL NO. G.471-6/125.04	S/RV MANUFACTURER DIKKERS	
S/RV SERIAL NO. 160814	8R10	
TYPE OF TEST WATER, 15°F SUBCOOLED	LOADS I SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	195° F	
INLET PRESSURE	266 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	610mSec_at_0_PS1	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+		
FACILITY INTEGRITY DEMONSTRATED	YES	
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE		

DATE TESTED 3-4-81	RUN/TEST NO. 105	
5/RV MODEL NO. G.471-6/125.04	S/RV MANUFACTURER DIKKERS	
S/RV SERIAL NO. 160814	8R10	
TYPE OF TEST		
STEAM, SATURATED	LOADS I SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOTED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	555°F	
INLET PRESSURE	1080 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	56mSec	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	

DATE TESTED 3-4-81	RUN/TEST NO. 106
S/RV MODEL NO. G.471-6/125.04	S/RV MANUFACTURER DIKKERS
S/RV SERIAL NO. 160814	8R10
TYPE OF TEST	LOADS I SUPPORTS
WATER, 50°F SUBCOOLED	EUADS 1 SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	177°F
INLET PRESSURE	247 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	YES
POST-TEST DISASSEMBLY INSPECTION+	YES
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> OPEN PRIOR TO TEST

DATE TESTED 3-10-81	RUN/TEST NO. 202
S/RV MODEL NO. 7467F	S/RV MANUFACTURER TARGET ROCK
S/RV SERIAL NO.181	3-STACE 6R10
TYPE OF TEST	
STEAM, SATURATED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555°F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 3-11-81	RUN/TEST NO
S/RV MODEL NO. 7467F	S/RV MANUFACTURER TARGET ROCK
S/RV SERIAL NO.181	3-STAGE 6R10
TYPE OF TEST	
STEAM, SATURATED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555°F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RY OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* MOT APPLICABLE

DATE TESTED 3-11-81	RUN/TEST NO2	06
S/RV MODEL NO. 7467F	S/RV MANUFACTURER	TARGET ROCK
S/RV SERIAL NO.181		3-STAGE 6R10
TYPE OF TEST		
STEAM, SATURATED	'LOADS I	SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS	555°F	
FLUID TEMPERATURE		
INLET PRESSURE	1080 P	SIG
S/RV TLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE		

DATE TESTED 3-30-81	RUN/TEST NO. 209
S/RV MODEL NO. 7467F	S/RV MANUFACTURER TARGET ROC
S/RV SERIAL NO.181	3-STAGE 6R10
TYPE OF TEST	
WATER, 15°F SUBCOOLED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
G/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	195 <sup>0</sup> F
INLET PRESSURE	288 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME,	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICAPLE

DATE TESTED 3-30-81	RUN/TEST NO. 210
S/RV MODEL NO. 7467F	S/RV MANUFACTURER TARGET ROCK
S/RV SERIAL NO.181	3-STAGE 6R10
TYPE OF TEST  WATER, 15°F SUBCOOLED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	193 <sup>o</sup> F
INLET PRESSURE	269 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO*	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE	

DATE TESTED 3-30-81	RUN/TEST NO. 211
S/RV MODEL NO. 7467F	S/RV MANUFACTURER TARGET ROCK
S/RV SERIAL NO.181	3-STAGE 6R10
TYPE OF TEST	
WATER, 50°F SUBCOOLED	LOADS T SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RY CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	195 <sup>0</sup> F
INLET PRESSURE	253 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	YES
POST-TEST DISASSEMBLY INSPECTION+	YES
FACILITY INTEGRITY DEMONSTRATED	YES
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE	

DATE TESTED 3-17-81	RUN/TEST NO301	
S/RV MODEL NO. 7567-F000	S/RV MAMUFACTURER TARGET-ROCK	
S/RV SERIAL NO. 1062	2-STAGE 6R10	
TYPE OF TEST		
STEAM, SATURATED	LOADS I SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	555°F	
INLET PRESSURE	1080 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (M'IN DISK LIFT TIME)	LATER	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	

+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE-

DATE TESTED 3-17-81	RUN/TEST NO. 303
S/RV MODEL NO. 7567-F000	S/RV MANUFACTURER TARGET-ROCK
S/RV SERIAL NO. 1062	2-STAGE 6R10
TYPE OF TEST	LOADS
WATER, 15°F SUBCOOLED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	241° F
INLET PRESSURE	272 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 3-17-81	RUN/TEST NO. 304	
S/RV MODEL NO. 7567-F000	S/RV MANUFACTURER TARGET-	ROCK
S/PV SERIAL NO. 1062	2-STAGE 6R10	
TYPE OF TEST		
STEAM, SATURATED	LOADS I SUPPOR	RIS
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	555 <sup>0</sup> F	
INLET PRESSURE	1080 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* NOT APPLICABLE

DATE TESTED 3-18-81 RUN/TEST NO. 305	
S/RV MODEL NO. 7567-F000	S/RV MANUFACTURER TARGET-ROCK
S/RV SERIAL NO. 1062	2-STAGE 6R10
TYPE OF TEST	LOADS I SUPPORTS
WATER, 15°F SUBCOOLED	LONDS 1 SOFFORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	274 <sup>0</sup> F
INLET PRESSURE	278 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY CNCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 3-18-81	RUN/TEST NO. 306	
S/RV MODEL NO. 7567-F000	S/RV MANUFACTURER TARGET-ROCK	
S/RV SERIAL NC. 1062	2-STAGE SR10	
TYPE OF TEST	LOADS I SUPPORTS	
STEAM, SATURATED	LOADS - SOFFORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	555 <sup>C</sup> F	
INLET PRESSURE	1080 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	

+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

DATE TESTED 3-18-81	RUN/TEST NO. 307	
S/RV MODEL NO. 7557-F000	S/RV MANUFACTURER TARGET-ROCK	
S/RV SERIAL NO. 1062	6R10	
TYPE OF TEST	I	
WATER, 50°F SUBCOOLED	LOADS I SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	215°F	
INLET PRESSURE	262 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	A/N	
FACILITY INTEGRITY DEMONSTRATED	YES	

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

RUN/TEST NO. 308
S/RV MANUFACTURER TARGET-ROCK
2-STAGE 6R10
LOADS I SURDOUTS
LOADS I SUPPORTS
YES
YES
284 <sup>o</sup> F
113 PSIG
LATER
LATER
YES
YES
YES
YES

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* EQUIVALEN: TO 15°F SUBCOOLED WATER, 50PSI OPENING PRESSURE

DATE TESTED 3-24-81	RUN/TEST NO. 402
S/RV MODEL NO. HB-65-BP-FN	S/RV MANUFACTURER CROSBY
S/RV SERIAL NO. N63580-00-0019	6R10
TYPE OF TEST	LOADS I SUPPORTS
STEAM SATURATED	LOADS - SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555 <sup>0</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	25mSec
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 3-24-81	RUN/TEST NO. 403
S/RV MODEL NO. HB-65-BP-FN	S/RV MANUFACTURER CROSBY
S/RV SERIAL NO. N63580-00-0019	6R10
TYPE OF TEST  WATER, 15°F SUBCOOLED	LOADS I SUPPORTS
TEST RESULTS	
S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	206°F
INLET PRESSURE	262 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	**
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO*	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

<sup>\*\*</sup> OPEN 'RIOR TO TEST

DATE TESTED 3-24-81  S/RV MODEL NO. HB-65-BP-FN  S/RV SERIAL NO. N63580-00-0019	S/RV MANUFACTURER CROSBY 6R10
TYPE OF TEST  STEAM, SATURATED	LOADS I SUPPORTS
TEST RESULTS S/RV OPLNED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555°F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	25mSec
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 3-25-81	RUN/TEST NO.	105
S/PY MODEL NO. HB-65-BP-FN	S/RV MANUFACTURER	CROSBY 6R1
S/RV SERIAL NO. N63580-00-0019		
TYPE OF TEST		
WATER, 15°F SUBCOOLED	LOADS I	SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	210 <sup>o</sup> F	
INLET PRESSURE	250PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT (IME)	**	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	

+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

\* NOT APPLICABLE

\*\* OPEN PRIOR TO TEST

DATE TESTED 3-25-81	RUN/TEST NO406	
S/RV MODEL NO. HB-65-BP-FN	S/RV MANUFACTURER CROSBY	
S/RV SERIAL NO. N63580-00-0019	6R10	
TYPE OF TEST		
STEAM, SATURATED	LOADS I SUPPORTS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	555 <sup>0</sup> F	
INLET PRESSURE	1080 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	24mSec	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 3-25-81	RUN/TEST NO. 407
S/RV MODEL NO. HB-65-BP-FN S/RV SERIAL NO. N63580-00-0019	S/RV MANUFACTURER CROSBY 6R10
TYPE OF TEST  WATER, 50°F SUBCOOLED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS FLUID TEMPERATURE	555°F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	*
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRU+	YES
POST-TEST DISASSEMBLY INSPECTION+	YES
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> OPEN PRIOR TO TEST

DATE TESTED 4-15-81	RUN/TEST NO602
S/RV MODEL NO. 1525VX	S/RV MANUFACTURER DRESSER
S/RV SERIAL NO. BK-7061	ELECTROMATI 6R8
TYPE OF TEST  STEAM, SATURATED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555 <sup>0</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* NOT APPLICABLE

DATE TESTED 4-15-81	RUN/TEST NO604
S/RV MODEL NO. 1525VX	S/RV MANUFACTURER DRESSER
S/RV SERIAL NO. BK-7061	ELECTROMATI 6R8
TYPE OF TEST  WATER, 15°F SUBCOOLED	LOADS I SUPPORTS
TEST RESULTS	
S/RV GPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	193 <sup>0</sup> F
INLET PRESSURE	230 P°IG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

DATE TESTED 4-16-81	RUN/TEST NO. 606	
S/RV MODEL NO. 1525VX	S/RV MANUFACTURER DRESSER	
TYPE OF TEST	ELECTROMATI 6R8	
	LOADS I SUPPORTS	
WATER, 15°F SUBCOOLED	LUADS 1 SUFFORIS	
TEST RESULTS S/RV OPENED ON COMMAND	YES	
S/RV CLOSED ON COMMAND	YES	
S/RV FLUID TEST CONDITIONS		
FLUID TEMPERATURE	198 <sup>o</sup> F	
INLET PRESSURE	274 PSIG	
S/RV FLOW RATE	LATER	
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER	
VALVE INTEGRITY DEMONSTRATED BY:		
VISUAL INSPECTION	YES	
POST-TEST HYDRO+	N/A*	
POST-TEST DISASSEMBLY INSPECTION+	N/A	
FACILITY INTEGRITY DEMONSTRATED	YES	
+ ONLY ONCE PER VALVE AT END OF TEST SEQUENCE		

DATE TESTED 4-16-81	RUN/TEST NO607
S/RV MODEL NO. 1525VX	S/RV MANUFACTURER DRESSER
S/RV SERIAL NO. BK-7061	ELECTROMATI 6R8
TYPE OF TEST	
STEAM, SATURATED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555 <sup>0</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	N/A*
POST-TEST DISASSEMBLY INSPECTION+	N/A
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> NOT APPLICABLE

RUN/TEST NO. 608
S/RV MANUFACTURER DRESSER
ELECTROMATIC 6R8
LOADS I SUPPORTS **
LOADS I SUPPORTS
YES
YES
162 <sup>0</sup> F
263 PSIG
LATER
LATER
YES
N/A*
N/A
YES

- + ONLY ONCE PER VALVE AT END OF TEST SEQUENCE
- \* NOT APPLICABLE
- \*\* CHANGED OUT FIRST SNUBBER 20K

DATE TESTED 4-16-81	RUN/TEST NO609
S/RV MODEL NO. 1525VX	S/RV MANUFACTURER DRESSER
S/RV SERIAL NO. BK-7061	ELECTROMATI 6R8
TYPE OF TEST  STEAM, SATURATED	LOADS I SUPPORTS
TEST RESULTS S/RV OPENED ON COMMAND	YES
S/RV CLOSED ON COMMAND	YES
S/RV FLUID TEST CONDITIONS	
FLUID TEMPERATURE	555 <sup>0</sup> F
INLET PRESSURE	1080 PSIG
S/RV FLOW RATE	LATER
S/RV OPENING TIME (MAIN DISK LIFT TIME)	LATER
VALVE INTEGRITY DEMONSTRATED BY:	
VISUAL INSPECTION	YES
POST-TEST HYDRO+	YES
POST-TEST DISASSEMBLY INSPECTION+	YES
FACILITY INTEGRITY DEMONSTRATED	YES

<sup>+</sup> ONLY ONCE PER VALVE AT END OF TEST SEQUENCE

<sup>\*</sup> CHANGED OUT FIRST SNUBBER - 20K