

James W Cook Vice President - Projects, Engineering and Construction

General Offices: 1945 West Parnall Road, Jackson, MI 49201 • (517) 788-0453

September 30, 1981

Harold R Denton, Director Office of Nuclear Reactor Regulation US Nuclear Regulatory Commission Washington, DC 20555

MIDLAND PROJECT DOCKET NOS 50-329, 50-330 SUBMITTAL OF THE AUXILIARY BUILDING DYNAMIC MODEL, SERVICE WATER PUMP STRUCTURE DYNAMIC MODEL AND DESCRIPTION OF SOILS SETTLEMENT REMEDIAL FIX FOR THE AUXILIARY BUILDING FILE 0485.16, B3.0.1 SERIAL 14110



-1

- REFERENCES: (1) JWCook Letter to HRDenton, Serial 11625 Dated March 23, 1981 (2) JWCook Letter to HRDenton, Serial 13738 Dated August 26, 1981 ENCLOSURES: (1) Service Water Pump Structure Seismic Model (2) Auxiliary Building Seismic Model

 - (3) Technical Report on Underpinning the Auxiliary Building and Feedwater Isolation Valve Pits

In our previous correspondence of August 26, 1981 (Reference 2) construction permit level design information relating to the remedial actions for the service water pump structure was provided to the staff. Enclosed are iwentyfive (25) copies of the report (Enclosure 1) entitled "Service Water Pump Structure Seismic Model" which is based upon the design information already forwarded to the NRC. In addition, we are providing twenty-five (25) copies each of two reports, Enclosures 2 and 3. Enclosure 2 describes the seismic model for the auxiliary building for computing the building response to seismic loading as well as to generate instructure response spectra. Enclosure 3 represents the construction permit level of design information for the auxiliary building remedial actions. All three of the enclosed documents are provided to complete commitments contained in the "Statement of Agreement" from the ASLB Prehearing Conference Order of May 5, 1981.

The seismic model reports for the service water pump structure and the auxiliary building include the following information: (1) model description, (2) soilstructure interaction considerations; (3) the dynamic model properties; and (4) fundamental frequencies and mode shapes. The auxiliary building model includes full underpinning of the control tower and electrical penetration areas, integrally tied to the main auxiliary building at Column Line H. The service water pump structure model includes ful, underpinning of the northern

B001

portion of the building originally supported by the fill. The models reflect the underpinning currently planned and, therefore, are subject to possible revision after the final building structural analysis and NRC staff review is completed. We believe that the enclosed reports combined with our scheduled meeting with the staff during the week of September 30, 1981 provides sufficient information to permit the NRC to review and provide its concurrence with the proposed remedial actions. Your expeditious review and approval would be most appreciated to support the hearings and construction of the remedial work.

5

2

play for JW Gok JWC/RLT/bh

CC Atomic Safety and Licensing Appeal Board, w/o CBechhoefer, ASLB, w/o MMCherry, Esq, w/o RJCook, Midland Resident Inspector, w/o RSDecker, ASLB, w/o DHood, NRC, w/a (2) DFJudd, B&W, w/o JDKane, NRC, w/a FJKelley, Esq, w/o RBLandsman, NRC Region III, w/a WHMarshall, w/o WOtto, US Army Corps of Engineers, w/a WDPaton, Esq, w/o IRinaldi, NRC, w/a HSingh, Army Corps of Engineers, w/a BStamiris, w/o FPCowan, w/o

BCC RCBauman/TRThiruvengadam, P-14-400, w/a WRBird, P-14-418A, w/a JEBrunner, M-1079, w/a AJBoos, Bechtel, w/a WJCloutier, P-24-611, w/a BDhar, Bechtel, w/a BFHenley, P-14-100, w/a RWHuston, Washington, w/a GSKeeley, P-14-113B, w/a DBMiller, Midland, w/a MIMiller, IL&B, w/a KBRazdan, P-13-220, w/a JARutgers, Bechtel, w/a SLSobkowski, Bechtel, w/a TJSullivan/DMBudzik, P-24-517, w/o NRC Correspondence File, w/a