

5.5 Programs and Manuals

5.5.9 Steam Generator (SG) Program

A Steam Generator Program shall be established and implemented to ensure that SG tube integrity is maintained. In addition, the Steam Generator Program shall include the following:

- a. Provisions for condition monitoring assessments. Condition monitoring assessment means an evaluation of the "as found" condition of the tubing with respect to the performance criteria for structural integrity and accident induced leakage. The "as found" condition refers to the condition of the tubing during an SG inspection outage, as determined from the inservice inspection results or by other means, prior to the plugging [or repair] of tubes. Condition monitoring assessments shall be conducted during each outage during which the SG tubes are inspected, plugged, [or repaired] to confirm that the performance criteria are being met.
- b. Performance criteria for SG tube integrity. SG tube integrity shall be maintained by meeting the performance criteria for tube structural integrity, accident induced leakage, and operational LEAKAGE.
 1. Structural integrity performance criterion: All in-service steam generator tubes shall retain structural integrity over the full range of normal operating conditions (including startup, operation in the power range, hot standby, and cool down), all anticipated transients included in the design specification, and design basis accidents. This includes retaining a safety factor of 3.0 against burst under normal steady state full power operation primary-to-secondary pressure differential and a safety factor of 1.4 against burst applied to the design basis accident primary-to-secondary pressure differentials. Apart from the above requirements, additional loading conditions associated with the design basis accidents, or combination of accidents in accordance with the design and licensing basis, shall also be evaluated to determine if the associated loads contribute significantly to burst or collapse. In the assessment of tube integrity, those loads that do significantly affect burst or collapse shall be determined and assessed in combination with the loads due to pressure with a safety factor of 1.2 on the combined primary loads and 1.0 on axial secondary loads.
 2. Accident induced leakage performance criterion: The primary to secondary accident induced leakage rate for any design basis accident, other than a SG tube rupture, shall not exceed the leakage rate assumed in the accident analysis in terms of total leakage rate for all SGs and leakage rate for an individual SG. Leakage is not to exceed [1 gpm] per SG [, except for specific types of degradation at specific locations as described in paragraph c of the Steam Generator Program].

5.5 Programs and Manuals

5.5.9 Steam Generator (SG) Program (continued)

3. The operational LEAKAGE performance criterion is specified in LCO 3.4.13, "RCS Operational LEAKAGE."
- c. Provisions for SG tube plugging [or repair] criteria. Tubes found by inservice inspection to contain flaws with a depth equal to or exceeding [40%] of the nominal tube wall thickness shall be plugged [or repaired].

-----REVIEWER'S NOTE-----
Alternate tube plugging [or repair] criteria currently permitted by plant technical specifications are listed here. The description of these alternate tube plugging [or repair] criteria should be equivalent to the descriptions in current technical specifications and should also include any allowed accident induced leakage rates for specific types of degradation at specific locations associated with tube plugging [or repair] criteria.

[The following alternate tube plugging [or repair] criteria may be applied as an alternative to the 40% depth based criteria:

1. ...]
- d. Provisions for SG tube inspections. Periodic SG tube inspections shall be performed. The number and portions of the tubes inspected and methods of inspection shall be performed with the objective of detecting flaws of any type (e.g., volumetric flaws, axial and circumferential cracks) that may be present along the length of the tube, from the tube-to-tubesheet weld at the tube inlet to the tube-to-tubesheet weld at the tube outlet, and that may satisfy the applicable tube plugging [or repair] criteria. The tube-to-tubesheet weld is not part of the tube. [Portions of the tube below [14.01] inches from the top of the tubesheet are excluded from this requirement.] In addition to meeting the requirements of d.1, d.2, and d.3 below, the inspection scope, inspection methods, and inspection intervals shall be such as to ensure that SG tube integrity is maintained until the next SG inspection. A degradation assessment shall be performed to determine the type and location of flaws to which the tubes may be susceptible and, based on this assessment, to determine which inspection methods need to be employed and at what locations.

5.5 Programs and Manuals

5.5.9 Steam Generator (SG) Program (continued)

-----REVIEWER'S NOTE-----

Plants are to include the appropriate Frequency (e.g., select the appropriate Item 2.) for their SG design. The first Item 2 is applicable to SGs with Alloy 600 mill annealed tubing. The second Item 2 is applicable to SGs with Alloy 600 thermally treated tubing. The third Item 2 is applicable to SGs with Alloy 690 thermally treated tubing.

1. Inspect 100% of the tubes in each SG during the first refueling outage following SG installation.
- [2. After the first refueling outage following SG installation, inspect 100% of the tubes in each steam generator at least every 24 effective full power months, which defines the inspection period, or at least every refueling outage (whichever results in more frequent inspections). In addition, inspect 100% of the tubes at sequential periods of 60 effective full power months beginning after the first refueling outage inspection following SG installation. Each 60 effective full power month inspection period may be extended up to 3 effective full power months to include a SG inspection outage in an inspection period and the subsequent inspection period begins at the conclusion of the included SG inspection outage. If a degradation assessment indicates the potential for a type of degradation to occur at a location not previously inspected with a technique capable of detecting this type of degradation at this location and that may satisfy the applicable tube repair criteria, the minimum number of locations inspected with such a capable inspection technique during the remainder of the inspection period may be prorated. The fraction of locations to be inspected for this potential type of degradation at this location at the end of the inspection period shall be no less than the ratio of the number of times the SG is scheduled to be inspected in the inspection period after the determination that a new form of degradation could potentially be occurring at this location divided by the total number of times the SG is scheduled to be inspected in the inspection period.
- [2. After the first refueling outage following SG installation, inspect 100% of the tubes in each SG at least every 7248 effective full power months, which defines the inspection period, or at least every other refueling outage (whichever results in more frequent inspections). In addition, the minimum number of tubes inspected at each scheduled inspection shall be the number of tubes in all SGs divided by the number of SG inspection outages scheduled in each inspection period as defined in a, b, and c below. If a degradation assessment indicates the potential for a type of degradation to occur at a location not previously inspected with a technique capable of detecting this type of degradation at this location and that may satisfy the applicable tube repair criteria, the

minimum number of locations inspected with such a capable inspection technique during the remainder of the inspection period may be prorated. The fraction of locations to be inspected for this potential type of degradation at this location at the end of the inspection period shall be no less than the ratio of the number of times the SG is scheduled to be inspected in the inspection period after the determination that a new form of degradation could potentially be occurring at this location divided by the total number of times the SG is scheduled to be inspected in the inspection period. Each inspection period ~~defined below~~ may be extended up to 3 effective full power months to include a SG inspection outage in an inspection period and the subsequent inspection period begins at the conclusion of the included SG inspection outage.

~~Reviewer's Note~~

~~A licensee may elect to retain historical and existing inspection period lengths in order to not revise those inspection periods.~~

- ~~a) After the first refueling outage following SG installation, inspect 100% of the tubes during the next 120 effective full power months. This constitutes the first inspection period;~~
- ~~b) During the next 96 effective full power months, inspect 100% of the tubes. This constitutes the second inspection period; and~~
- ~~c) During the remaining life of the SGs, inspect 100% of the tubes every 72 effective full power months. This constitutes the third and subsequent inspection periods.~~

- [2. After the first refueling outage following SG installation, inspect 100% of the tubes in each SG at least every 96/72 effective full power months, which defines the inspection period or at least every third refueling outage (whichever results in more frequent inspections). In addition, the minimum number of tubes inspected at each scheduled inspection shall be the number of tubes in all SGs divided by the number of SG inspection outages scheduled in each inspection period ~~as defined in a, b, c and d below~~. If a degradation assessment indicates the potential for a type of degradation to occur at a location not previously inspected with a technique capable of detecting this type of degradation at this location and that may satisfy the applicable tube repair criteria, the minimum number of locations inspected with such a capable inspection technique during the remainder of the inspection period may be prorated. The fraction of locations to be inspected for this potential type of degradation at this location at the end of the inspection period shall be no less than the ratio of the number of times the SG is scheduled to be inspected in the inspection period after the determination that a new form of degradation could potentially be occurring at this location divided by the total number of times the SG is scheduled to be inspected in the inspection period. Each inspection

period ~~defined below~~ may be extended up to 3 effective full power months to include a SG inspection outage in an inspection period and the subsequent inspection period begins at the conclusion of the included SG inspection outage.

~~Reviewer's Note~~

~~A licensee may elect to retain historical and existing inspection period lengths in order to not revise those inspection periods.~~

- ~~a) After the first refueling outage following SG installation, inspect 100% of the tubes during the next 144 effective full power months. This constitutes the first inspection period;~~
- ~~b) During the next 120 effective full power months, inspect 100% of the tubes. This constitutes the second inspection period;~~
- ~~c) During the next 96 effective full power months, inspect 100% of the tubes. This constitutes the third inspection period; and~~
- ~~d) During the remaining life of the SGs, inspect 100% of the tubes every 72 effective full power months. This constitutes the fourth and subsequent inspection periods.~~

3. If crack indications are found in any SG tube, then the next inspection for each affected and potentially affected SG for the degradation mechanism that caused the crack indication shall be at the next not exceed 24 effective full power months or one refueling outage (whichever results in more frequent inspections). If definitive information, such as from examination of a pulled tube, diagnostic non-destructive testing, or engineering evaluation indicates that a crack-like indication is not associated with a crack(s), then the indication need not be treated as a crack.

- e. Provisions for monitoring operational primary to secondary LEAKAGE.

5.5 Programs and Manuals

5.5.9 Steam Generator (SG) Program (continued)

- [f. Provisions for SG tube repair methods. Steam generator tube repair methods shall provide the means to reestablish the RCS pressure boundary integrity of SG tubes without removing the tube from service. For the purposes of these Specifications, tube plugging is not a repair. All acceptable tube repair methods are listed below.

-----REVIEWER'S NOTE-----

Tube repair methods currently permitted by plant technical specifications are to be listed here. The description of these tube repair methods should be equivalent to the descriptions in current technical specifications. If there are no approved tube repair methods, this section should not be used.

1. . . .]

5.5.10 Secondary Water Chemistry Program

This program provides controls for monitoring secondary water chemistry to inhibit SG tube degradation and low pressure turbine disc stress corrosion cracking. The program shall include:

- a. Identification of a sampling schedule for the critical variables and control points for these variables,
- b. Identification of the procedures used to measure the values of the critical variables,
- c. Identification of process sampling points, which shall include monitoring the discharge of the condensate pumps for evidence of condenser in leakage,
- d. Procedures for the recording and management of data,
- e. Procedures defining corrective actions for all off control point chemistry conditions, and
- f. A procedure identifying the authority responsible for the interpretation of the data and the sequence and timing of administrative events, which is required to initiate corrective action.