


---

**Turbine Building  
Yankee Nuclear Power Station  
Structural Analysis Report**

**For: Yankee Atomic Electric Company  
By: Cygna Energy Services**

---



December 29, 1982 Rev. 1

8301170533 830111  
PDR ADOCK 05000029  
P PDR


Job No. 80023  
Report No. EY-YR-80023-9  
December, 1982  
Rev. 1

Turbine Building and Turbine Pedestal  
Yankee Nuclear Power Station  
Rowe, Massachusetts

Prepared by: Miguel T. de Guzman 12/29/82  
Miguel DeGuzman

Reviewed by: J. Vallenar 12/29/82  
Jose Vallenar

Approved by: Eric van Stijgeren  
Eric van Stijgeren



## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
I. EXECUTIVE SUMMARY.....	1
1.1 Purpose.....	1
1.2 Scope .....	1
1.3 Conclusions.....	1
II. BUILDING DESCRIPTIONS.....	2
2.1 Turbine Building.....	2
2.2 Turbine Pedestal.....	5
III. PERFORMANCE CRITERIA.....	6
3.1 Materials.....	6
3.1.1 Reinforced Concrete Walls.....	6
3.1.2 Reinforced Concrete Frame Members.....	6
3.1.3 Steel Frame Members.....	6
3.1.4 Unreinforced Concrete Masonry Walls.....	6
3.1.5 Allowable Soil Pressures.....	7
3.2 Loadings.....	7
3.2.1 Dead Loads.....	7
3.2.2 Live Loads.....	7
3.2.3 Earthquake Loads.....	7
3.2.4 Load Combinations.....	8



TABLE OF CONTENTS (cont'd.)

<u>Section</u>	<u>Page</u>
IV. ANALYSIS PROCEDURES.....	9
4.1 General.....	9
4.2 Computer Programs.....	9
4.3 Assumptions.....	10
4.4 Horizontal Models.....	10
4.4.1 Turbine Building.....	10
4.4.2 Turbine Pedestal.....	12
4.5 Vertical Models.....	12
4.5.1 Turbine Building.....	12
4.5.2 Turbine Pedestal.....	13
V. ANALYSIS RESULTS.....	15
5.1 Structural Characteristics.....	15
5.1.1 Turbine Building.....	15
5.1.2 Turbine Pedestal.....	16
5.2 Analytical Results.....	17
5.2.1 Turbine Building.....	17
5.2.1.1 YCS Loads.....	17
5.2.1.2 NRC Spectrum Loads.....	19
5.2.2 Turbine Pedestal.....	20
5.2.2.1 YCS Loads.....	20
5.2.2.2 NRC Spectrum Loads.....	21
VI. GENERATION OF THE ARS.....	23




TABLE OF CONTENTS (cont'd.)

<u>Section</u>	<u>Page</u>
VII. SUMMARY OF THE REVIEW.....	25
7.1 Turbine Building.....	25
7.2 Turbine Pedestal.....	26
7.3 Attached Office Building.....	26
VIII. RECOMMENDED MODIFICATIONS.....	27

APPENDICES

- A. Contract Drawings
- B. Computer Models
- C. Earthquake Response Spectra
- D. Table of Dynamic Characteristics
- E. Results of Analysis
- F. Amplified Response Spectra
- G. References



## I. EXECUTIVE SUMMARY

### 1.1 Purpose

The purpose of this report is to summarize the results of the structural analyses performed by Cygna Energy Services\* (Cygna) for Yankee Atomic Electric Company (YAEC). The results described in this report pertain to the Turbine Building and Turbine Pedestal at the Yankee Nuclear Power Station (YNPS), Rowe, Massachusetts.

### 1.2 Scope


As requested by YAEC, Cygna has performed detailed structural analyses of the two structures. The analyses described in this report were based on the following input data for YNPS:

1. Study of the existing structural drawings of the two structures (see Appendix A).
2. Design Criteria (see Section III).
3. Seismic ground motion specified by the Yankee Composite Spectrum (YCS) and the NRC Spectrum.

### 1.3 Conclusions

- The Turbine Building does not comply with the established criteria and minimum strengthening of the structure will be necessary for the Yankee Composite Spectrum.
- The Turbine Pedestal does comply with the criteria for both the YCS and NRC Spectrum. No modification of the existing structure is required.

\*Cygna Energy Services is the new name for EES, Inc. Ownership, philosophy and staffing of the firm remains the same.



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1


## II. BUILDING DESCRIPTIONS

### 2.1 Turbine Building

The Turbine Building is rectangular in plan and measures 115.5 ft. in the north-south direction and 159.0 ft. in the east-west direction. It serves various functions, and it is comprised of the Turbine Room at the north end, the Heating and Boiler Room at the south-east corner, the Control Room, Switchgear Room, and Boiler Feed Pump area at the south end of the building (Figures A.1-A.8).

The Turbine Room is a five-story steel frame structure located at the north end of the building. Its plan dimensions are 77 ft. in the north-south direction and 159 ft. in the east-west direction, and it is 81 ft. in height. Lateral load resistance is provided by four diagonally braced perimeter frames, in which normally only 1 bay in each frame is braced at a given story level (Figures A.13 and A.14). Diagonal braces are typically two steel channels of section C 10 x 20 laced together to form an open box section. Only one built-up brace is provided in a braced bay. The working points of braces are typically at beam flange to column face intersections. Interior columns support a light metal grating floor at the second floor and a 5 to 7 inch concrete slab on steel framing at the third floor (Figures A.9 and A.10). The third and fourth stories above are completely open, which allows for the removal and installation of turbine machinery. The roof is supported by north-south trusses at 22 to 27 ft. spacing. Lateral bracing of the main trusses are provided by two sway braces in the east-west direction. The roof diaphragm is stiffened by horizontal cross-bracing composed of steel double-angle sections (Figure A.12).

Fascia on the north, east, and west sides are provided by non-load bearing concrete masonry walls at the ground level, and insulated metal paneling above (Figures A.5 - A.8).



At the fifth floor, a movable crane is supported by heavy girders in the east-west direction, which are in turn independently supported by columns offset from the east-west perimeter frames.

The Turbine Room exterior columns are supported by spread footings. Grade beams connecting footing pedestals exist along the west frame line and along a portion of the north and east frame lines (Figure A.15).

The portion of the building housing the Heating and Boiler Room is 38.5 ft. (north-south) by 44 ft. (east-west). It is a two-story steel frame structure 31 ft. high. Its east perimeter frame is an extension of the east frame at the Turbine Room, and it shares three common columns with the Turbine Room south perimeter frame. The roof is constructed of light steel decking. At the second floor, a 5 inch concrete slab floor exists on the west half of the room; the east half is completely open up to the roof. Masonry walls separate this room from adjacent areas. Lateral support is provided by its attachment to the turbine room.

The structure housing the Control Room, Switch Gear Room, and Boiler Feed Pump area is three stories high, and its dimensions are 38.5 ft. (north-south) by 115 ft. (east-west) by 49.5 ft. tall. An 8.5 ft. high masonry wall penthouse 67 ft. by 14 ft. in plan containing cable trays is supported on the roof.

The vertical load carrying system of this part of the building is composed of bearing walls and columns. Floor loads are carried by simply-supported north-south steel girders at 22 to 27 ft. spacing (Figure A.11). These girders frame into common columns shared with the turbine room at the north side, and are supported at the south by grouted beam pockets in the 3 to 4 ft. thick reinforced concrete shield wall. At the roof level precast inverted T-beams with 9 inches of cast-in-place concrete cover span from the shield wall to the common columns (Figure A.16).




There are 3 ft. thick concrete shield walls at the east and west ends of the control room between the third floor and the roof (Figures A.17-A.19). However, these walls do not continue below the third floor. They are end-supported at the third floor by the south shield wall and 3 ft. square concrete columns. 12 inch thick masonry walls serve as partition or exterior walls below that level.

In general, nonstructural masonry walls can be found at all levels of this part of the building, serving as exterior curtain walls and interior partition walls.

A strip footing supports the south shield wall, but otherwise spread footings have been used. At the west end of the building, a grade beam ties the individual spread footing pedestals on grid line 13 to the shield wall strip footing (Figure A.15).

The footings at grid lines C and G support twin columns carrying loads from the Control Room to the South and the Turbine Room to the North. In addition, at the third floor a continuous concrete floor slab will act as a rigid horizontal diaphragm connecting the building together in its response to seismic loads. In end result the building acts as a coupled shear wall and braced frame system.

Review of design details show that concrete floor slabs are supported by bearing only, and that no positive connections exist for the transfer of seismic lateral loads from the floor diaphragms into vertical structural elements. Such connections will have to be provided in order to tie the building together and allow for the full participation of all lateral load resisting elements.



## 2.2 Turbine Pedestal


The Turbine Pedestal is located approximately in the middle of the Turbine Room. This structure is a reinforced concrete moment-resisting frame 34.5 ft. high. It is supported by eight rectangular columns whose cross-sectional dimensions range from 5.5 ft. to 11.5 ft. The frame has 1 bay in the transverse north-south direction, with centerline to centerline spans ranging from 21 to 27 ft. In the east-west direction, there are three bays ranging from 21 to 36 ft. for a total centerline length of 92 ft. Girder depths are roughly 8 to 10 ft (See Figures A.20-A.27).

The top of the Pedestal is level with the third floor of the Turbine Room. However, the Pedestal is structurally separated from the Turbine Building because a 1 inch joint isolates the pedestal from the surrounding concrete slab at this level.

The turbine is continuously anchored to the top of the Pedestal by bolts, and this effectively acts as a rigid diaphragm which ties the frame together horizontally.

An intermediate level concrete slab on beams framing into the four west end columns supports the generator.

The Pedestal is supported by a 4.5 ft. thick reinforced concrete mat foundation.



### III. PERFORMANCE CRITERIA

#### 3.1 Materials

##### 3.1.1 Reinforced Concrete Walls

The concrete for shield walls was specified to have a 28-day compressive strength of 2500 psi. As shown in Figures A.17 - A.19, the reinforced concrete walls have very small height to depth ratios. Accordingly, their ultimate strength is primarily controlled by shear strength. The ultimate shear strength as per ACI 318-77 is:

$$v_u = 2 \sqrt{f'_c} = 2 \sqrt{2500} = 100 \text{ psi.}$$

##### 3.1.2 Reinforced Concrete Frame Members


With the exception of footings, cast-in-place concrete for frame members and floor slabs was specified to have a 28-day strength of 3000 psi. The ultimate strength of axial and flexural members was determined as per Chapter 10 of ACI 318-77.

##### 3.1.3 Steel Frame Members

The structural steel for the Turbine Building was specified to conform to ASTM A7, which has a yield strength of 33 ksi. Stresses up to code allowables as given in Part 1 of the AISC Specifications are allowed.

##### 3.1.4 Unreinforced Concrete Masonry Walls

The allowable ultimate strength of unreinforced concrete masonry walls is given in Section 7.0 of the Seismic Reevaluation and Retrofit Criteria [1]. The compressive strength of masonry,  $f'_m$ , has been determined to be



1000 psi and 600 psi on net section for ASTM C-90 and C-129 block units, respectively.

### 3.1.5 Allowable Soil Pressures

The bearing capacity for the soil underneath all footings is 8 ksf if earthquake loads are not considered and 10.6 ksf if they are included.

## 3.2 Loadings

### 3.2.1 Dead Loads

Design dead loads and their related member forces were considered in the evaluation. For the Turbine Building, no internal beam moments were generated at beam-column joints because all beam-column connections are of the simple shear type.

### 3.2.2 Live Loads

For the Turbine Building, live loads and their related member forces were also included in the evaluation. There was no consideration of live load for the Turbine Pedestal.

### 3.2.3 Earthquake Loads

The earthquake loads were specified by the YCS and NRC Spectrum (Figure C.1). Equivalent viscous damping of 7% was assumed in accordance with Table D-3 of the Criteria [1].



### 3.2.4 Load Combinations

The load combinations considered in this evaluation are as follows:

$$(1) D + L + T_0 + R_0 + P_0 + (E \text{ or } W \text{ or } M)$$

$$(2) D - E$$

where:

D = Dead loads

L = Live loads

E = Earthquake loads

T<sub>0</sub> = Thermal loads


R<sub>0</sub> = Pipe reactions

P<sub>0</sub> = Pressure equivalent static loads

W = Wind loads

M = Missile Loads

and in equation (2), earthquake induced member forces are assumed to act opposite to dead loads.



## IV. ANALYSIS PROCEDURES

### 4.1 General

Both the Turbine Building and Turbine Pedestal were analyzed based on linear elastic theory. Dynamic properties of the structures were evaluated in terms of characteristic mode and frequency information.


For the stress evaluation of the structures, the response spectrum method of dynamic analysis was used. The combination of individual modal displacements, member forces, and stresses was carried out by the square root of the sum of squares (SRSS) procedure. In order to account for the multi-directional nature of seismic input, results from the three orthogonal directions were combined by the SRSS method.

For the Turbine Building, as-built details of ten selected steel brace connections to beam-column joints were obtained from field investigations. The stresses in these joints and their connectors due to YCS and NRC Spectrum loads were evaluated. Based on the performance of these representative joints, general conclusions were drawn regarding the behavior of all joints.

For the generation of floor level acceleration time histories, individual modal displacements were superposed for each time step of the total response (See Sect. VI).

### 4.2 Computer Programs

Three computer programs were utilized in the analyses. The program BATS [5] was used to perform the modal extraction and response spectrum analyses. MOST [6] and INSPEC [7] were employed to generate floor acceleration time histories and the corresponding floor-amplified response spectra (ARS), respectively.



### 4.3 Assumptions

The computer program BATS assumes that each floor level of a structure can be modeled as a set of horizontal diaphragms rigid in plane. Each diaphragm is attached to one or more substructures which provide vertical and lateral support. A diaphragm has two horizontal and one torsional degrees of freedom which thus define the lateral displacements of all of its attached substructures. A consequent result of the rigid diaphragm modeling is the further assumption that beam elements do not deform axially nor bend in the plane of the diaphragm. However, horizontal flexible links can be used to connect individual diaphragms and elastically couple their degrees of freedom. Thus, a structure is modeled as a three-dimensional system of vertical frame or wall substructures supporting horizontal rigid diaphragms. Inertia properties of the structure are lumped at the floor diaphragms. The computer program BATS further reduces this system to an equivalent lumped mass and stick model prior to frequency and mode shape analysis.

### 4.4 Horizontal Models

#### 4.4.1 Turbine Building

The Turbine Building is characterized by several open floors in the Turbine Room area. Accordingly, in order to adequately model the relative motion of structural frames, the Turbine Building was discretized into several diaphragms and substructures (Figure B.1, B.2, and B.9).

The Control and Switchgear Room area have concrete slabs at all floor and roof levels, and therefore it was modeled as a single substructure and diaphragm bounded by grid lines 7, 13, J and G. Lateral resistance is provided by the 3 to 4 foot thick concrete shield walls along grid lines 8, 13, and J, and by the braced frame on grid line G.




The north, east, and west braced perimeter frames of the Turbine Room area were each modeled as individual substructures. At the top level all the frames, including the frame on line G, were connected to a single diaphragm representing the cross-brace stiffened roof system (Figure B.7). At elevation 1052'-8", the concrete slab is significantly perforated. Therefore, two diaphragms were used in the turbine area connected to each other and to the Control Room diaphragm by flexible links (Figure B.4). The stiffness properties of these links were derived from the actual area of continuous steel reinforcement and beams. At all other elevations, the individual planar braced frames were separated and free to move relative to each other (Figures B.3, B.5, and B.6).

At elevation 1037'-8", the Turbine Building provides partial lateral support for the Service Building in the north-south direction, and the Office Building in both directions. These attached buildings were modeled as equivalent mass-spring systems (Figure B.8). The springs in these models represented the stiffnesses of vertical X-bracing and flexible roof diaphragms.

Bracing was assumed in grid line A to achieve stability for the Office Building in the E-W direction. It was also assumed to be self-stabilized in the N-S direction in the mass-spring model generated.

The calculated seismic weight of the Turbine Building included structural deadweight, architectural elements and facades, partition and shield walls, the deadweight of the movable crane at elevation 1082'-8", and the possible laydown weight of turbine machinery at elevation 1052'-8". For the Service and Office Buildings, the design roof deadweight of 20 psf was used increased by an additional 5 psf to account for steel frames, architectural finishes and attachments, and mechanical attachments.



#### 4.4.2 Turbine Pedestal

The Turbine Pedestal was modeled as a one-story moment-resisting space frame with a single rigid diaphragm at the top level, elevation 1052'-8" (Figure B.10). All member properties were based on uncracked concrete sections, neglecting the contribution of steel reinforcement. Beam-column joints were assumed to act as rigid-bodies.

The seismic weight of the Turbine Pedestal included structural deadweight and the weights of the supported turbine and generator.


### 4.5 Vertical Models

#### 4.5.1 Turbine Building

In general, substructures are not coupled in the vertical direction. Floor diaphragms are flexible in the out-of-plane direction, and since beam connections are of the shear type, no bending moments are induced in beams by relative vertical displacements.

Accordingly, three separate models were developed to reflect the different vertical load carrying systems of the building. Equivalent lumped mass and spring mechanical models were utilized. The effective floor masses were represented by concentrated masses, and the combined stiffnesses of supporting walls, columns, and braces were represented by elastic springs. In addition, the truss-supported turbine area roof and the 4-foot thick Control Room roof are much stiffer than the floor diaphragms. In the vertical models, these elements were assumed to act as rigid-body masses.

The Control and Switch Gear Rooms constituted the first model (Figure B.11). Masses were supported by springs representing the shield wall on



the south side of the building and the steel braced frame on grid line G. Five masses connected by six springs were used. The purpose of this model was to generate ARS for piping supported by the south concrete shield wall.

The second vertical model represented the turbine area (Figure B.12). The equivalent mechanical system was composed of two parallel systems of four masses linked at the top to a common rigid body mass representing the turbine area roof. One series of masses and springs incorporated the mass tributary to grid line C and the supporting columns and braces, and the remaining mass and stiffness were lumped into the parallel system. The results of the analysis of this model was used to determine the column and brace forces caused in the turbine area by vertical ground acceleration.

The third vertical model represented a typical column in grid line G (Figure B.13). These columns are characterized by the fact that they support vertical loads from the control room roof and floor slabs as well as the turbine room. The equivalent mechanical system for one of these columns was a series of five masses and springs. This model was used to generate ARS and determine column forces in grid line G caused by vertical ground acceleration.

#### 4.5.2 Turbine Pedestal

The Turbine Pedestal was modeled in two dimensions in the vertical direction. The axial stiffnesses of columns in the north-south bays were added, and the flexural properties of east-west beams were added. Mass was lumped at the four beam-column joints of the two-dimensional east-west frame and the ARS location point. Thus, a total of five degrees of freedom were defined in the vertical direction. This resulted in a model of the Pedestal in the east-west direction analogous to a beam supported by multiple elastic springs, i.e., the columns (Figure B.14).



This approach correctly considered the stiffness-coupling effect of the Turbine Pedestal beams. Since the Pedestal is symmetric about its east-west centerline axis, no generality was lost by two-dimensional modeling. The analyses of this system resulted in ARS for supported piping and the Turbine Pedestal column loads caused by vertical acceleration.



## V. ANALYSIS RESULTS

### 5.1 Structural Characteristics

#### 5.1.1 Turbine Building

The first 31 modes of the Turbine Building were included in the calculation of dynamic response to horizontal ground motion. Table D.1 summarizes the frequencies, periods and modal masses of each of these modes. The sum of these modal masses in the north-south and east-west directions was greater than 90% of the total mass. The selection of the first 31 modes was therefore adequate to determine the dynamic response of the structure.

In the north-south direction, dynamic response was predominantly governed by the third mode, which had a frequency of 2.24 cps. This mode defined the response of 69% of the mass of the Turbine Building.

In the east-west direction, the majority of the mass of the Turbine Building was governed by three modes. The fourth mode, which had a frequency of 2.34 cps, characterized 18% of the total mass of the Turbine Building. It was associated with the east-west vibration of the Turbine Room steel frames. The 25th mode, which had a frequency of 12.34 cps, characterized 32% of the total mass of the Turbine Building. It was associated with the east-west vibration of the Office Building. The 26th mode, which had a frequency of 12.64 cps, characterized 24% of the total mass. It was associated with the east-west vibration of the Turbine Room steel frame at Line C. All other modes individually contributed less than 12% of the total combined mass of the Turbine Building, Service Building, and Office Building.



The characteristic frequencies of the Turbine Building in the vertical direction were different among the three models developed for this purpose. Because of the limited number of degrees of freedom in these models, all modes were taken into consideration.

The first model, representing the Control and Switchgear Rooms, was relatively stiff due to the concrete shield walls. The predominant frequency of this model was 26.4 cps, and the corresponding mode included 92% of the total mass of the model.

The second model, representing the turbine room, had a predominant frequency of 18.6 cps. The mode associated with this frequency contained 87% of the total mass.


The third model, representing a typical column on line G, had a predominant frequency of 10.3 cps. The mode associated with this frequency contained 96% of the total mass.

#### 5.1.2 Turbine Pedestal

In the horizontal direction, the Turbine Pedestal was modeled as a one-story three-dimensional space frame with a single rigid diaphragm. Accordingly, the response of this structure was governed by three modes (Table D.2). All three were considered in calculating dynamic response.

The first mode was associated with the translation of the structure in the east-west direction. It had a frequency of 7.42 cps and included 100% of the total mass in the east-west direction.

The second mode was associated with the translation of the structure in the north-south direction. It had a frequency of 8.64 cps, and it included 94.5% of the total mass in the north-south direction.



The third mode was primarily torsional, and to a certain extent translational in the north-south direction. It had a frequency of 10.2 cps, and it included 5.5% of the total mass in the north-south direction.

All five modes of the Turbine Pedestal were used to determine its response in the vertical direction. As expected, the Pedestal was found to be very stiff. The predominant mode, the first, had a frequency of 29.5 cps. It included 50.8% of the total mass. The second mode had a frequency of 30.9 cps. It included 25.9% of the total mass. The third mode had a frequency of 41.1 cps. It included 19.3% of the total mass. The fourth mode had a frequency of 47.6 cps, and it included 4.0% of the total mass. The fifth mode was not significant.

## 5.2 Analytical Results

As stated in Section 4.4.1, modal contributions to structural response were combined by the square root of the sum of squares (SRSS) procedure. The individual results from earthquake loading applied in the three orthogonal directions were combined by the SRSS method.

### 5.2.1 Turbine Building

#### 5.2.1.1 YCS Loads

The loads, displacements, and member forces produced in the building by the YCS ground motion are summarized in Tables E.1 to E.4.

Table E.1 presents an overall summary of the seismic base shears and resulting maximum displacements at elevation 1052'-8". In the north-south direction, the shear produced in the attached Turbine Building, Service Building, and Office Building was



1548 kips, or 14.6% of their total combined weight. In the east-west direction, the shear produced in these three buildings was 923 kips, or 8.7% of their weight. The maximum displacements at elevation 1052'-8" were 0.26 inches and 0.04 inches in the north-south and east-west directions, respectively.

Table E.2 summarizes the axial loads and stresses produced in diagonal braces of the two north-south steel frames. No significant overstress occurred for YCS loading.


The results of the stress analysis of ten representative brace to beam-column joints are given in Table E.3. No overstress occurred.

Maximum and minimum loads produced in individual footings are shown in Table E.4. Neither overstress nor uplifting occurred in any footings.

The steel frame columns themselves were adequate for the maximum vertical loads produced by dead, live, and seismic loads.

Overstress and hence cracking occurred in concrete shield wall on Grid Line J. The extreme fiber stress was 630 psi which exceeds concrete's modulus of rupture of 410 psi. Since this wall is under-reinforced, its ultimate moment capacity is less than its crack moment. Development of the flexural cracks in the wall may significantly reduce its moment capacity.

Floor slab connections as given by the contract drawings of the Turbine Building were examined. No connections were provided for the transfer of seismic inertia loads from floor slabs into structural frames and walls. Such connection must be provided in order to engage these structural systems.



#### 5.2.1.2 NRC Spectrum Loads

The loads, displacements and member forces in the building are summarized in Tables E.5 to E.8.

Table E.5 presents an overall summary of the seismic base shears and resulting maximum displacements at Elev. 1052'-8". In the N-S direction, the shear produced in the three attached buildings was 2863 kips, or 27.0% of their total weight. In the E-W direction, the shear produced was 1520 kips, or 14.3% of the total weight. The maximum displacements at El. 1052'-8" were 0.51 and 0.08 inches in the N-S and E-W directions, respectively.

Table E.6 summarizes the axial force developed in the diagonal braces of the two N-S and two E-W steel frames. The compression forces developed in three braces located in Frame Line 5, two braces in Frame Line G and four braces in Frame Line C exceeded the corresponding allowable buckling forces. Since the diagonal braces are the only lateral force resistance mechanism of the steel frames, buckling of these braces will significantly reduce the lateral load resistance capacity of the frames.

The results of the stress analysis of the brace to beam-column connections are given in Table E.7. Overstresses occurred in five connections. The maximum overload ratio was 1.5.

The maximum and minimum loads produced in individual footings are shown in Table E.8. Seismic load in conjunction with dead and live loads produce excessive soil bearing pressures at Footings G-8, G-5, C-11 and C-8. The maximum overstress was 17%, which occurred at Footing G-8. Seismic load acting opposite to dead load also produced net uplift forces at eight footings. The



maximum uplift force was 226 kips at Footing G-8. Since a large part of the footing shear resistance comes from the friction force developed between the footing and soil, presence of the uplift force will eliminate the friction force and consequently reduce the shear resistance capacity of the footing.

The steel columns were adequate.

Overstress and cracking occur in the concrete shield wall on Grid Line J. The extreme fiber tensile stress for out-of-plane bending was 1310 psi, which exceeded the modulus of rupture of concrete, 410 psi.

## 5.2.2 Turbine Pedestal

### 5.2.2.1 YCS Loads

The loads, displacements, and member forces produced in the Turbine Pedestal by the dead load and YCS loads are summarized in Tables E.9 to E.11.

The beam and column stress resultants produced by vertical acceleration were only about 2% or less of the stress resultants due to horizontal acceleration. Thus, they were negligible in the SRSS combination of the results of the three orthogonal directions.

Table E.9 presents an overall summary of the seismic base shears and resulting maximum displacements at elevation 1052'-8". In the north-south direction, the base shear was 893 kips, or 17.2% of the total weight. In the east-west direction, the shear produced was 979 kips, or 18.9% of the total weight. The maximum



displacements at elevation 1052'-8" were .02 inches and .03 inches in the north-south and east-west directions, respectively.

Table E.10 summarizes the column forces produced by the YCS loads. These structural elements were subjected to axial loads and biaxial moments. Interaction effects on capacity were evaluated by the load contour method. All results of the load contour interaction equation were less than 1.0, indicating that the columns were acceptable for the YCS. In addition, service dead loads in the columns were never exceeded by the upward loads produced by the YCS loads.

Table E.11 shows the beam bending moments and shear forces. The applied forces and moments were less than 0.41 of the corresponding ultimate strengths of these members.

The maximum soil pressure of the Turbine Support Mat Foundation under dead load plus YCS applied in two horizontal directions and the vertical direction is 4.06 KSF, which is smaller than the allowable pressure, 10.6 KSF.

The absolute sum of the maximum displacement of the Turbine Building and Turbine Pedestal at elevation 1052'-8" was 0.28 inches. This was less than the gap of 1.0 inch separating the two structures.

#### 5.2.2.2 NRC Spectrum Loads

The loads, displacements and member forces produced in the Turbine Pedestal by the dead load and NRC spectrum loads are shown in Tables E.12 to E.14. The negligible beam and column forces due to the vertical NRC spectrum were also excluded in the



SRSS combination of the results of the three orthogonal directions.

Table E.12 shows an overall summary of the seismic base shears and resulting maximum displacements at Elev. 1052'-8". In the N-S direction, the base shear was 1645 kips, or 31.8% of the total weight. In the E-W direction, the base shear was 1427 kips, or 27.5% of the total weight. The maximum displacements at Elev. 1052'-8" were 0.04 inches and 0.06 inches in the N-S and E-W directions, respectively.

Table E.13 summarizes the column forces produced by the YCS loads. As shown in this table, all results of the load contour interaction equation were less than 1.0, indicating that the columns were acceptable for the NRC Spectrum loads. In addition, service dead loads in the columns were never exceeded by the upward loads produced the NRC Spectrum loads.

Table E.14 shows the beam bending moments and shear forces. The applied forces and moments were less than 0.66 of the corresponding ultimate strengths of these members.

The maximum soil pressure of the Turbine Support Mat Foundation under dead load plus NRC Spectrum applied in two horizontal directions and the vertical direction is 5.00 KSF, which is smaller than the allowable pressure, 10.6 KSF.

The absolute sum of the maximum displacement of the Turbine Building and Turbine Pedestal at Elev. 1052'-8" was 0.55 inches. This was less than the gap of 1.0 inch separating the two structures.



## VI. GENERATION OF THE ARS

The amplified response spectra (ARS) were generated for the analyses of piping systems supported by the Turbine Building and the Turbine Pedestal. There are three support points for which ARS were determined. Two of these are located on the Turbine Building at elevation 1037'-8" and 1052'-8". The ARS for these points were labeled ARS PT. 1 and ARS PT. 2. These points are shown in Figure F.1. The remaining point, ARS PT. 106, was located on the Turbine Pedestal at elevation 1052'-8". This point is shown in Figure F.14.

The generation of each ARS proceeded along the following methodology:

For each of the three orthogonal directions, a statistically independent synthetic ground acceleration time history was developed using the program NRCQUAKE [8]. These time histories were verified to match the YCS or NRC Spectrum according to the criteria specified in the USNRC Standard Review Plan Section 3.7.1. For the vertical acceleration time history, a scale factor of two-thirds was applied. The dynamic characteristics of the structure were obtained as described in Sect. V.1. The mode shape ordinates, given at the center of mass of each floor diaphragm, were transformed via rigid-body constraint equations to the ARS support point. The acceleration time histories of the ARS support point could then be calculated by the superposition of the acceleration time-histories of individual modes, when subjected to the input ground motions. This superposition was computed by the program MOST [6], using the assumed structural damping of 7% of critical damping.

The response of the structures into vertical ground acceleration was independent of the response to horizontal ground acceleration. Thus, the vertical acceleration time history of the ARS support point was computed separately.



These support point acceleration time histories were then input to the response spectrum calculation program, INSPEC [7]. These were calculated for the two horizontal directions and the one vertical direction. The peaks in their spectra were broadened by 15%. The resultant spectra give the maximum accelerations experienced by supported subsystems.

For the ARS located in the Turbine Building, two critical damping ratios, 2% and 3% were used. The ARS corresponding to the YCS loads and NRC Spectrum loads are shown in Figs. F.2 to F.7 and Figs. F.8 to F.13, respectively. All these ARS are identified by the location point and direction.

For the ARS located in the Turbine Pedestal, only 3% critical damping ratio was used. The ARS corresponding to the YCS loads and NRC spectrum loads are shown in Figs. F.15 to F.17 and Figs. F.18 to F.20, respectively.



## VII. SUMMARY OF REVIEW

### 7.1 Turbine Building

1. The steel columns have adequate capacity to resist the axial force produced by a combination of dead load, live load plus either YCS loads or NRC Spectrum loads.
2. The diagonal braces have adequate capacity to resist YCS loads except for one diagonal brace located in Grid Line 5. Under NRC Spectrum loads, however, three braces located in Grid Line 5, two braces located in Grid Line G and four braces located in Grid Line C are overstressed in compression. Consequent buckling of these braces will result in a reduction of the lateral load resistance capacity in the three frames.
3. The brace to beam-column connections have adequate capacity to transfer YCS loads. Under NRC spectrum loads, however, five connections are overstressed.
4. Due to a combination of dead load and YCS loads, the soil has adequate bearing capacity and all footings will not be subjected to uplift force. If YCS loads were replaced by NRC Spectrum loads, the soil under four footings are overstressed in bearing by less than 17%. Eight of the footings are also subjected to the uplift force which could reduce the shear resistance of the footings.
5. Due to dead load plus either YCS loads or NRC Spectrum loads, the flexural tensile stress developed in the 3'-0" thick shield wall located in Grid Line J will exceed the modulus of rupture of the concrete. Since the shield wall is under-reinforced, development of the flexural cracks in the wall may significantly reduce its flexural capacity.




6. Connections for the transfer of seismic shear forces from concrete floor slab to structural frames and walls are lacking.
7. The absolute sum of the maximum displacements of the Turbine Building and Turbine Pedestal at Elev. 1052'-8" are 0.28 inches and 0.55 inches under YCS loads and NRC Spectrum loads, respectively. These displacements are less than the 1.0 inch gap separating the two structures.

### 7.2 Turbine Pedestal

1. Reinforced concrete columns are adequate to resist combined axial loads and biaxial bending moments resulting from dead load and YCS loads or NRC Spectrum loads. Also, service dead loads in columns are not exceeded by upward loads imposed by YCS loads or NRC Spectrum loads.
2. Reinforced concrete beams are adequate to resist shear forces and bending moments imposed by dead load and YCS loads or NRC Spectrum loads.
3. The bearing strength of soil underlying the mat foundation of the Turbine Pedestal is not exceeded under dead load and YCS loads or NRC Spectrum loads.

### 7.3 Attached Office Building

The Office Building does not have sufficient lateral load resistance capacity to take either YCS loads or NRC Spectrum loads.



## VIII. RECOMMENDED MODIFICATIONS

1. Modifications are necessary for the Turbine Building against YCS loads or NRC Spectrum loads, as follows:
  - a) Additional braces and shear walls should be installed in order to redistribute seismic lateral forces. This would relieve the stresses in existing braces, connections and shield wall at Grid Line J.
  - b) Installation of additional braces and shear walls will also lessen the effects of seismic overturning moments. In general, the number of braced bays in lower stories should be increased. This modification will decrease the seismic uplift on the end columns of these bays.
  - c) Positive connections must be provided for shear transfer from concrete floor slabs to the lateral load resisting system.
2. No modifications are necessary for the Turbine Pedestal.



**APPENDIX A**

**CONTRACT DRAWINGS**



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1

## APPENDIX A

### CONTRACT DRAWINGS

#### I. TURBINE BUILDING

<u>FIG.</u>	<u>STONE &amp; WEBSTER DWG. 9699-</u>
A.1 - A.4	FA-1A to 1D
A.5 - A.8	FA-2A to 2D
A.9 - A.11	FS-3A, 3B, & 4A
A.12	FS-5A
A.13 - A.14	FS-6B & 6C
A.15	FC-1A
A.16	FC-15A
A.17 - A.19	FC-17A to 17C


#### II. TURBINE PEDESTAL

<u>FIG.</u>	<u>STONE &amp; WEBSTER DWG. 9699-</u>
A.20 - A.23	FC-19A to 19D
A.24 - A.27	FC-20A to 20D





9699 FA-1B



PLAN EL. 1037'-8"  
SCALE 1/4" = 1'-0"




NO.	DATE	BY	CHKD.	DESCRIPTION
1	10/1/50	J. H. ...	...	...
2	10/1/50	J. H. ...	...	...
3	10/1/50	J. H. ...	...	...
4	10/1/50	J. H. ...	...	...
5	10/1/50	J. H. ...	...	...
6	10/1/50	J. H. ...	...	...
7	10/1/50	J. H. ...	...	...
8	10/1/50	J. H. ...	...	...
9	10/1/50	J. H. ...	...	...
10	10/1/50	J. H. ...	...	...

MEZZANINE FLOOR TURBINE AREA  
 POWER STATION  
 BATTERY ROOM  
 TURBINE ROOM  
 YANKEE ATOMIC ELECTRIC COMPANY  
 9699 FA-1B


Fig. A.2

Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1





01 VJ 16/16




NO.	DESCRIPTION	DATE	BY	CHECKED
1	DESIGNED	11/15/54	J. J. ...	...
2	REVISION	...	...	...
3	...	...	...	...
4	...	...	...	...
5	...	...	...	...
6	...	...	...	...
7	...	...	...	...
8	...	...	...	...
9	...	...	...	...
10	...	...	...	...
11	...	...	...	...
12	...	...	...	...
13	...	...	...	...
14	...	...	...	...
15	...	...	...	...
16	...	...	...	...
17	...	...	...	...
18	...	...	...	...
19	...	...	...	...
20	...	...	...	...


ROOF PLAN  
TURBINE AREA  
POWER STATION  
YANKEE ATOMIC ELECTRIC COMPANY  
DOWE, MASS.

STATION & WEATHER INSTRUMENTATION OBSERVATION  
9699 FA ID

FIG. A.4

Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1





NORTH ELEVATION  
SCALE: 1/8" = 1'-0"





NO.	REVISION	DATE	BY	CHKD.
1	ISSUED FOR PERMITS	10/1/58	J. J. ...	J. J. ...
2	REVISED PER PERMITS	10/1/58	J. J. ...	J. J. ...
3	REVISED PER PERMITS	10/1/58	J. J. ...	J. J. ...
4	REVISED PER PERMITS	10/1/58	J. J. ...	J. J. ...
5	REVISED PER PERMITS	10/1/58	J. J. ...	J. J. ...

NORTH ELEVATION  
POWER STATION  
YANKEE ATOMIC ELECTRIC COMPANY  
ANDOVER, MASS.  
OFFICE & WORKING ENGINEERING ORGANIZATION  
SCALE: 1/8" = 1'-0"  
9699 FA-2A

Fig. A.5

Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1





NO.	DESCRIPTION	QTY	UNIT	PRICE	TOTAL
1	AS BUILT EXPANDED	1	SQ FT	1.00	1.00
2	EXPOSED FORM FILLING	1	SQ FT	1.00	1.00
3	THREE DOUBLE CHAINED WIRE	1	SQ FT	1.00	1.00
4	BRICKING WITH CLAY	1	SQ FT	1.00	1.00
5	REPAIRING BRICK WITH AN AREA	1	SQ FT	1.00	1.00
6	BRICKING BRICK	1	SQ FT	1.00	1.00
7	DESCRIPTION				


Fig. A.6

EAST ELEVATION  
 POWER STATION  
 YANKEE ATOMIC ELECTRIC COMPANY  
 ROWE, MASS.  
 STONE & WEBSTER ENGINEERING CORPORATION  
 DRAWING NO. 6690-FA-2B



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1





WEST ELEVATION  
SCALE: 1/4" = 1'-0"

NO.	DESCRIPTION	DATE	BY	CHKD.
1	AS BUILT DRAWING	12/15/57	W.S.	W.S.
2	OFFICE ELEVATION BY F.M.L.	12/15/57	F.M.L.	W.S.
3	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.
4	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.
5	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.
6	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.
7	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.
8	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.
9	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.
10	REVISIONS: CORR. WINDOW & DOOR	12/15/57	F.M.L.	W.S.

Fig. A.8


WEST ELEVATION  
POWER STATION  
YANKEE ATOMIC ELECTRIC COMPANY  
ROWE, MASS.

STUPE & WHEATON ENGINEERING CORPORATION  
DRAWING NUMBER 9699 FA-21




Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1







Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1













Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1





ROOF PLAN-TURBINE ROOM  
SCALE 1/4" = 1'-0"



-NOTES-  
 1. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 2. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 3. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 4. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 5. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 6. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 7. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 8. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 9. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.  
 10. ALL REINFORCING BARS SHALL BE UNLESS NOTED OTHERWISE TO BOTTOM OF RAISED.

NO.	DESCRIPTION	QTY	UNIT	REMARKS
1	...	...	...	...
2	...	...	...	...
3	...	...	...	...
4	...	...	...	...
5	...	...	...	...
6	...	...	...	...
7	...	...	...	...
8	...	...	...	...
9	...	...	...	...
10	...	...	...	...




TURBINE ROOM ROOF  
 POWER STATION  
 YANKEE ATOMIC ELECTRIC COMPANY  
 ROWE, MASS.

STONE & WEBSTER ENGINEERING CORPORATION  
 DRAWING NUMBER 9699-FS-5A

Fig. A.12



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1



NOTES:

1. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
2. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
3. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
4. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
5. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
6. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
7. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
8. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
9. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.
10. CRANE STOP TO BE CHECKED FOR WELDING REQUIREMENTS.

OPERATING PL. EL. 1032'-0"

WELD FL. EL. 1037'-0"

GROUND FL. EL. 000'-0"

CRANE STOP

TOP OF CRANE RAIL EL. 1022'-0"

TOP OF BEAM EL. 1040'-0"

SPILLER LINE 2 ALBA. CRANE RAIL

WELD FL. EL. 1037'-0"

GROUND FL. EL. 000'-0"

CRANE STOP

TOP OF CRANE RAIL EL. 1022'-0"

TOP OF BEAM EL. 1040'-0"

SPILLER LINE 2 ALBA. CRANE RAIL

WELD FL. EL. 1037'-0"



GROUND FL. EL. 000'-0"

Fig. A.13

T.R. ELEV. C & G LINE  
 POWER STATION  
 YANKEE ATOMIC ELECTRIC COMPANY  
 ROWE, MASS.  
 STONE & WEBSTER ENGINEERING CORPORATION  
 9699-FS-6B



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1



-NOTES-  
 SHOP DRILLS 1/2\"/>

NO.	DESCRIPTION	DATE	BY	CHECKED
1	AS BUILT DRAWING	7/22/54	J.E.M.	J.E.M.
2	DEAN ELEVATION CHANGED	8/2/54	J.E.M.	J.E.M.
3	ORIGINAL DRAWING FOR WELL HEAD & BRACKET	7/22/54	J.E.M.	J.E.M.
4	REVISION	7/22/54	J.E.M.	J.E.M.

TR 11155-08131145  
 POWER STATION  
**YANKEE ATOMIC ELECTRIC COMPANY**  
 ROWE, MASS.  
 STONE & WEBSTER ENGINEERING CORPORATION  
 DRAWING NUMBER 9699-FS-6C

Fig. A.14



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1








Fig. A.16



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1




PLAN AT TOP OF WALL



SECTION X-X


SECTION Y-Y




SECTION Z-Z



SECTION T-T



SECTION U-U



SECTION V-V

NOTES

1. See drawing for details of connection of wall shield to floor slab.

2. See drawing for details of connection of wall shield to wall.

3. See drawing for details of connection of wall shield to wall.

4. See drawing for details of connection of wall shield to wall.

5. See drawing for details of connection of wall shield to wall.

6. See drawing for details of connection of wall shield to wall.

7. See drawing for details of connection of wall shield to wall.

8. See drawing for details of connection of wall shield to wall.

9. See drawing for details of connection of wall shield to wall.

10. See drawing for details of connection of wall shield to wall.



POWER STATION  
**YANKEE ATOMIC ELECTRIC COMPANY**  
 BOSTON & WENDELL ENGINEERING CORPORATION  
 BOSTON, MASS.  
 DRAWING NO. 9699 FC-17A

NO.	DATE	BY	CHKD.	APP.
1	10/1/54	J. H. ...	J. H. ...	J. H. ...
2	10/1/54	J. H. ...	J. H. ...	J. H. ...
3	10/1/54	J. H. ...	J. H. ...	J. H. ...
4	10/1/54	J. H. ...	J. H. ...	J. H. ...
5	10/1/54	J. H. ...	J. H. ...	J. H. ...
6	10/1/54	J. H. ...	J. H. ...	J. H. ...
7	10/1/54	J. H. ...	J. H. ...	J. H. ...
8	10/1/54	J. H. ...	J. H. ...	J. H. ...
9	10/1/54	J. H. ...	J. H. ...	J. H. ...
10	10/1/54	J. H. ...	J. H. ...	J. H. ...

Fig. A.17

Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1









Fig. A.19

Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1




CONTROL ROOM  
 WALL SHIELD DETAILS SHEET 3  
 YANKEE ATOMIC ELECTRIC COMPANY  
 ROWE, MASS.

ENGINE & VEHTER ENGINEERING CORPORATION  
 BOSTON - 9699 FC-17C

NO.	DESCRIPTION	DATE
1	AS BUILT	1954
2	REVISION	
3	REVISION	
4	REVISION	
5	REVISION	
6	REVISION	
7	REVISION	
8	REVISION	
9	REVISION	
10	REVISION	
11	REVISION	
12	REVISION	
13	REVISION	
14	REVISION	
15	REVISION	
16	REVISION	
17	REVISION	
18	REVISION	
19	REVISION	
20	REVISION	
21	REVISION	
22	REVISION	
23	REVISION	
24	REVISION	
25	REVISION	
26	REVISION	
27	REVISION	
28	REVISION	
29	REVISION	
30	REVISION	







NOTE A -  
 CONCRETE SURFACES UNDER BEARING PLATES  
 SHOULD BE CARRIED BY ABOVE DIMENSION  
 SHOWN ON DRAWING AND CHIPPED BACK TO  
 DEMONSTRATE CONCRETE FOR GOOD BEARINGS.

NOTES  
 SCALE 1/4"=1'-0"  
 CONCRETE ULTIMATE COMPRESSIVE STRENGTH AT 28 DAYS  
 TO BE 3000 LBS PER SQUARE INCH  
 FOR SECTIONS AND DETAILS NOT SHOWN ON THIS DRAWING  
 SEE DIMENSIONS FC 19A, FC 19B & FC 19C  
 FOR REINFORCEMENT SEE DIMENSIONS FC 19A TO FC 19C  
 FOR TURBINE SUPPORT FOUNDATION AND LAYOUT OF STUB  
 COLS SEE DIMENSIONS FC  
 FOR DETAILS OF ELECTRICAL EQUIPMENT, INSERTS ETC  
 SEE ELECTRICAL DRAWING  
 FOR DETAILS OF MECHANICAL EQUIPMENT, DIMS ETC  
 SEE MECHANICAL DIMS



APPROVED: [Signature]  
 PROFESSIONAL ENGINEER - TEST  
 STATE OF MASSACHUSETTS


TURBINE SUPPORT OUTLINE SHEET 3

POWER STATION  
 YANKEE ATOMIC ELECTRIC COMPANY  
 ROWE, MASS.


BYRNE & WARDNER ENGINEERING CORPORATION  
 9699 FC-19C

NO.	DESCRIPTION	DATE	BY	CHKD.
1	ISSUED FOR CONSTRUCTION	10/11/58	W.W.	W.W.
2	REVISION NO. 01 FOR CONSTRUCTION	11/11/58	W.W.	W.W.
3	REVISION NO. 02 FOR CONSTRUCTION	12/11/58	W.W.	W.W.
4	REVISION NO. 03 FOR CONSTRUCTION	1/11/59	W.W.	W.W.
5	REVISION NO. 04 FOR CONSTRUCTION	2/11/59	W.W.	W.W.
6	REVISION NO. 05 FOR CONSTRUCTION	3/11/59	W.W.	W.W.
7	REVISION NO. 06 FOR CONSTRUCTION	4/11/59	W.W.	W.W.
8	REVISION NO. 07 FOR CONSTRUCTION	5/11/59	W.W.	W.W.
9	REVISION NO. 08 FOR CONSTRUCTION	6/11/59	W.W.	W.W.
10	REVISION NO. 09 FOR CONSTRUCTION	7/11/59	W.W.	W.W.
11	REVISION NO. 10 FOR CONSTRUCTION	8/11/59	W.W.	W.W.
12	REVISION NO. 11 FOR CONSTRUCTION	9/11/59	W.W.	W.W.
13	REVISION NO. 12 FOR CONSTRUCTION	10/11/59	W.W.	W.W.
14	REVISION NO. 13 FOR CONSTRUCTION	11/11/59	W.W.	W.W.
15	REVISION NO. 14 FOR CONSTRUCTION	12/11/59	W.W.	W.W.
16	REVISION NO. 15 FOR CONSTRUCTION	1/11/60	W.W.	W.W.
17	REVISION NO. 16 FOR CONSTRUCTION	2/11/60	W.W.	W.W.
18	REVISION NO. 17 FOR CONSTRUCTION	3/11/60	W.W.	W.W.
19	REVISION NO. 18 FOR CONSTRUCTION	4/11/60	W.W.	W.W.
20	REVISION NO. 19 FOR CONSTRUCTION	5/11/60	W.W.	W.W.
21	REVISION NO. 20 FOR CONSTRUCTION	6/11/60	W.W.	W.W.
22	REVISION NO. 21 FOR CONSTRUCTION	7/11/60	W.W.	W.W.
23	REVISION NO. 22 FOR CONSTRUCTION	8/11/60	W.W.	W.W.
24	REVISION NO. 23 FOR CONSTRUCTION	9/11/60	W.W.	W.W.
25	REVISION NO. 24 FOR CONSTRUCTION	10/11/60	W.W.	W.W.
26	REVISION NO. 25 FOR CONSTRUCTION	11/11/60	W.W.	W.W.
27	REVISION NO. 26 FOR CONSTRUCTION	12/11/60	W.W.	W.W.
28	REVISION NO. 27 FOR CONSTRUCTION	1/11/61	W.W.	W.W.
29	REVISION NO. 28 FOR CONSTRUCTION	2/11/61	W.W.	W.W.
30	REVISION NO. 29 FOR CONSTRUCTION	3/11/61	W.W.	W.W.
31	REVISION NO. 30 FOR CONSTRUCTION	4/11/61	W.W.	W.W.
32	REVISION NO. 31 FOR CONSTRUCTION	5/11/61	W.W.	W.W.
33	REVISION NO. 32 FOR CONSTRUCTION	6/11/61	W.W.	W.W.
34	REVISION NO. 33 FOR CONSTRUCTION	7/11/61	W.W.	W.W.
35	REVISION NO. 34 FOR CONSTRUCTION	8/11/61	W.W.	W.W.
36	REVISION NO. 35 FOR CONSTRUCTION	9/11/61	W.W.	W.W.
37	REVISION NO. 36 FOR CONSTRUCTION	10/11/61	W.W.	W.W.
38	REVISION NO. 37 FOR CONSTRUCTION	11/11/61	W.W.	W.W.
39	REVISION NO. 38 FOR CONSTRUCTION	12/11/61	W.W.	W.W.
40	REVISION NO. 39 FOR CONSTRUCTION	1/11/62	W.W.	W.W.
41	REVISION NO. 40 FOR CONSTRUCTION	2/11/62	W.W.	W.W.
42	REVISION NO. 41 FOR CONSTRUCTION	3/11/62	W.W.	W.W.
43	REVISION NO. 42 FOR CONSTRUCTION	4/11/62	W.W.	W.W.
44	REVISION NO. 43 FOR CONSTRUCTION	5/11/62	W.W.	W.W.
45	REVISION NO. 44 FOR CONSTRUCTION	6/11/62	W.W.	W.W.
46	REVISION NO. 45 FOR CONSTRUCTION	7/11/62	W.W.	W.W.
47	REVISION NO. 46 FOR CONSTRUCTION	8/11/62	W.W.	W.W.
48	REVISION NO. 47 FOR CONSTRUCTION	9/11/62	W.W.	W.W.
49	REVISION NO. 48 FOR CONSTRUCTION	10/11/62	W.W.	W.W.
50	REVISION NO. 49 FOR CONSTRUCTION	11/11/62	W.W.	W.W.
51	REVISION NO. 50 FOR CONSTRUCTION	12/11/62	W.W.	W.W.
52	REVISION NO. 51 FOR CONSTRUCTION	1/11/63	W.W.	W.W.
53	REVISION NO. 52 FOR CONSTRUCTION	2/11/63	W.W.	W.W.
54	REVISION NO. 53 FOR CONSTRUCTION	3/11/63	W.W.	W.W.
55	REVISION NO. 54 FOR CONSTRUCTION	4/11/63	W.W.	W.W.
56	REVISION NO. 55 FOR CONSTRUCTION	5/11/63	W.W.	W.W.
57	REVISION NO. 56 FOR CONSTRUCTION	6/11/63	W.W.	W.W.
58	REVISION NO. 57 FOR CONSTRUCTION	7/11/63	W.W.	W.W.
59	REVISION NO. 58 FOR CONSTRUCTION	8/11/63	W.W.	W.W.
60	REVISION NO. 59 FOR CONSTRUCTION	9/11/63	W.W.	W.W.
61	REVISION NO. 60 FOR CONSTRUCTION	10/11/63	W.W.	W.W.
62	REVISION NO. 61 FOR CONSTRUCTION	11/11/63	W.W.	W.W.
63	REVISION NO. 62 FOR CONSTRUCTION	12/11/63	W.W.	W.W.
64	REVISION NO. 63 FOR CONSTRUCTION	1/11/64	W.W.	W.W.
65	REVISION NO. 64 FOR CONSTRUCTION	2/11/64	W.W.	W.W.
66	REVISION NO. 65 FOR CONSTRUCTION	3/11/64	W.W.	W.W.
67	REVISION NO. 66 FOR CONSTRUCTION	4/11/64	W.W.	W.W.
68	REVISION NO. 67 FOR CONSTRUCTION	5/11/64	W.W.	W.W.
69	REVISION NO. 68 FOR CONSTRUCTION	6/11/64	W.W.	W.W.
70	REVISION NO. 69 FOR CONSTRUCTION	7/11/64	W.W.	W.W.
71	REVISION NO. 70 FOR CONSTRUCTION	8/11/64	W.W.	W.W.
72	REVISION NO. 71 FOR CONSTRUCTION	9/11/64	W.W.	W.W.
73	REVISION NO. 72 FOR CONSTRUCTION	10/11/64	W.W.	W.W.
74	REVISION NO. 73 FOR CONSTRUCTION	11/11/64	W.W.	W.W.
75	REVISION NO. 74 FOR CONSTRUCTION	12/11/64	W.W.	W.W.
76	REVISION NO. 75 FOR CONSTRUCTION	1/11/65	W.W.	W.W.
77	REVISION NO. 76 FOR CONSTRUCTION	2/11/65	W.W.	W.W.
78	REVISION NO. 77 FOR CONSTRUCTION	3/11/65	W.W.	W.W.
79	REVISION NO. 78 FOR CONSTRUCTION	4/11/65	W.W.	W.W.
80	REVISION NO. 79 FOR CONSTRUCTION	5/11/65	W.W.	W.W.
81	REVISION NO. 80 FOR CONSTRUCTION	6/11/65	W.W.	W.W.
82	REVISION NO. 81 FOR CONSTRUCTION	7/11/65	W.W.	W.W.
83	REVISION NO. 82 FOR CONSTRUCTION	8/11/65	W.W.	W.W.
84	REVISION NO. 83 FOR CONSTRUCTION	9/11/65	W.W.	W.W.
85	REVISION NO. 84 FOR CONSTRUCTION	10/11/65	W.W.	W.W.
86	REVISION NO. 85 FOR CONSTRUCTION	11/11/65	W.W.	W.W.
87	REVISION NO. 86 FOR CONSTRUCTION	12/11/65	W.W.	W.W.
88	REVISION NO. 87 FOR CONSTRUCTION	1/11/66	W.W.	W.W.
89	REVISION NO. 88 FOR CONSTRUCTION	2/11/66	W.W.	W.W.
90	REVISION NO. 89 FOR CONSTRUCTION	3/11/66	W.W.	W.W.
91	REVISION NO. 90 FOR CONSTRUCTION	4/11/66	W.W.	W.W.
92	REVISION NO. 91 FOR CONSTRUCTION	5/11/66	W.W.	W.W.
93	REVISION NO. 92 FOR CONSTRUCTION	6/11/66	W.W.	W.W.
94	REVISION NO. 93 FOR CONSTRUCTION	7/11/66	W.W.	W.W.
95	REVISION NO. 94 FOR CONSTRUCTION	8/11/66	W.W.	W.W.
96	REVISION NO. 95 FOR CONSTRUCTION	9/11/66	W.W.	W.W.
97	REVISION NO. 96 FOR CONSTRUCTION	10/11/66	W.W.	W.W.
98	REVISION NO. 97 FOR CONSTRUCTION	11/11/66	W.W.	W.W.
99	REVISION NO. 98 FOR CONSTRUCTION	12/11/66	W.W.	W.W.
100	REVISION NO. 99 FOR CONSTRUCTION	1/11/67	W.W.	W.W.
101	REVISION NO. 100 FOR CONSTRUCTION	2/11/67	W.W.	W.W.
102	REVISION NO. 101 FOR CONSTRUCTION	3/11/67	W.W.	W.W.
103	REVISION NO. 102 FOR CONSTRUCTION	4/11/67	W.W.	W.W.
104	REVISION NO. 103 FOR CONSTRUCTION	5/11/67	W.W.	W.W.
105	REVISION NO. 104 FOR CONSTRUCTION	6/11/67	W.W.	W.W.
106	REVISION NO. 105 FOR CONSTRUCTION	7/11/67	W.W.	W.W.
107	REVISION NO. 106 FOR CONSTRUCTION	8/11/67	W.W.	W.W.
108	REVISION NO. 107 FOR CONSTRUCTION	9/11/67	W.W.	W.W.
109	REVISION NO. 108 FOR CONSTRUCTION	10/11/67	W.W.	W.W.
110	REVISION NO. 109 FOR CONSTRUCTION	11/11/67	W.W.	W.W.
111	REVISION NO. 110 FOR CONSTRUCTION	12/11/67	W.W.	W.W.
112	REVISION NO. 111 FOR CONSTRUCTION	1/11/68	W.W.	W.W.
113	REVISION NO. 112 FOR CONSTRUCTION	2/11/68	W.W.	W.W.
114	REVISION NO. 113 FOR CONSTRUCTION	3/11/68	W.W.	W.W.
115	REVISION NO. 114 FOR CONSTRUCTION	4/11/68	W.W.	W.W.
116	REVISION NO. 115 FOR CONSTRUCTION	5/11/68	W.W.	W.W.
117	REVISION NO. 116 FOR CONSTRUCTION	6/11/68	W.W.	W.W.
118	REVISION NO. 117 FOR CONSTRUCTION	7/11/68	W.W.	W.W.
119	REVISION NO. 118 FOR CONSTRUCTION	8/11/68	W.W.	W.W.
120	REVISION NO. 119 FOR CONSTRUCTION	9/11/68	W.W.	W.W.
121	REVISION NO. 120 FOR CONSTRUCTION	10/11/68	W.W.	W.W.
122	REVISION NO. 121 FOR CONSTRUCTION	11/11/68	W.W.	W.W.
123	REVISION NO. 122 FOR CONSTRUCTION	12/11/68	W.W.	W.W.
124	REVISION NO. 123 FOR CONSTRUCTION	1/11/69	W.W.	W.W.
125	REVISION NO. 124 FOR CONSTRUCTION	2/11/69	W.W.	W.W.
126	REVISION NO. 125 FOR CONSTRUCTION	3/11/69	W.W.	W.W.
127	REVISION NO. 126 FOR CONSTRUCTION	4/11/69	W.W.	W.W.
128	REVISION NO. 127 FOR CONSTRUCTION	5/11/69	W.W.	W.W.
129	REVISION NO. 128 FOR CONSTRUCTION	6/11/69	W.W.	W.W.
130	REVISION NO. 129 FOR CONSTRUCTION	7/11/69	W.W.	W.W.
131	REVISION NO. 130 FOR CONSTRUCTION	8/11/69	W.W.	W.W.
132	REVISION NO. 131 FOR CONSTRUCTION	9/11/69	W.W.	W.W.
133	REVISION NO. 132 FOR CONSTRUCTION	10/11/69	W.W.	W.W.
134	REVISION NO. 133 FOR CONSTRUCTION	11/11/69	W.W.	W.W.
135	REVISION NO. 134 FOR CONSTRUCTION	12/11/69	W.W.	W.W.
136	REVISION NO. 135 FOR CONSTRUCTION	1/11/70	W.W.	W.W.
137	REVISION NO. 136 FOR CONSTRUCTION	2/11/70	W.W.	W.W.
138	REVISION NO. 137 FOR CONSTRUCTION	3/11/70	W.W.	W.W.
139	REVISION NO. 138 FOR CONSTRUCTION	4/11/70	W.W.	W.W.
140	REVISION NO. 139 FOR CONSTRUCTION	5/11/70	W.W.	W.W.
141	REVISION NO. 140 FOR CONSTRUCTION	6/11/70	W.W.	W.W.
142	REVISION NO. 141 FOR CONSTRUCTION	7/11/70	W.W.	W.W.
143	REVISION NO. 142 FOR CONSTRUCTION	8/11/70	W.W.	W.W.
144	REVISION NO. 143 FOR CONSTRUCTION	9/11/70	W.W.	W.W.
145	REVISION NO. 144 FOR CONSTRUCTION	10/11/70	W.W.	W.W.
146	REVISION NO. 145 FOR CONSTRUCTION	11/11/70	W.W.	W.W.
147	REVISION NO. 146 FOR CONSTRUCTION	12/11/70	W.W.	W.W.
148	REVISION NO. 147 FOR CONSTRUCTION	1/11/71	W.W.	W.W.
149	REVISION NO. 148 FOR CONSTRUCTION	2/11/71	W.W.	W.W.
150	REVISION NO. 149 FOR CONSTRUCTION	3/11/71	W.W.	W.W.
151	REVISION NO. 150 FOR CONSTRUCTION	4/11/71	W.W.	W.W.
152	REVISION NO. 151 FOR CONSTRUCTION	5/11/71	W.W.	W.W.
153	REVISION NO. 152 FOR CONSTRUCTION	6/11/71	W.W.	W.W.
154	REVISION NO. 153 FOR CONSTRUCTION	7/11/71	W.W.	W.W.
155	REVISION NO. 154 FOR CONSTRUCTION	8/11/71	W.W.	W.W.
156	REVISION NO. 155 FOR CONSTRUCTION	9/11/71	W.W.	W.W.
157	REVISION NO. 156 FOR CONSTRUCTION	10/11/71	W.W.	W.W.
158	REVISION NO. 157 FOR CONSTRUCTION	11/11/71	W.W.	W.W.
159	REVISION NO. 158 FOR CONSTRUCTION	12/11/71	W.W.	W.W.
160	REVISION NO. 159 FOR CONSTRUCTION	1/11/72	W.W.	W.W.
161	REVISION NO. 160 FOR CONSTRUCTION	2/11/72	W.W.	W.W.
162	REVISION NO. 161 FOR CONSTRUCTION	3/11/72	W.W.	W.W.
163	REVISION NO. 162 FOR CONSTRUCTION	4/11/72	W.W.	W.W.
164	REVISION NO. 163 FOR CONSTRUCTION	5/11/72	W.W.	W.W.
165	REVISION NO. 164 FOR CONSTRUCTION	6/11/72	W.W.	W.W.
166	REVISION NO. 165 FOR CONSTRUCTION	7/11/72	W.W.	W.W.
167	REVISION NO. 166 FOR CONSTRUCTION	8/11/72	W.W.	W.W.
168	REVISION NO. 167 FOR CONSTRUCTION	9/11/72	W.W.	W.W.
169	REVISION NO. 168 FOR CONSTRUCTION	10/11/72	W.W.	W.W.
170	REVISION NO. 169 FOR CONSTRUCTION	11/11/72	W.W.	W.W.
171	REVISION NO. 170 FOR CONSTRUCTION	12/11/72	W.W.	W.W.
172	REVISION NO. 171 FOR CONSTRUCTION	1/11/73	W.W.	W.W.
173	REVISION NO. 172 FOR CONSTRUCTION	2/11/73	W.W.	W.W.
174	REVISION NO. 173 FOR CONSTRUCTION	3/11/73	W.W.	W.W.
175	REVISION NO. 174 FOR CONSTRUCTION	4/11/73	W.W.	W.W.
176	REVISION NO. 175 FOR CONSTRUCTION	5/11/73	W.W.	W.W.
177	REVISION NO. 176 FOR CONSTRUCTION	6/11/73	W.W.	W.W.
178	REVISION NO. 177 FOR CONSTRUCTION	7/11/73	W.W.	W.W.
179	REVISION NO. 178 FOR CONSTRUCTION	8/11/73	W.W.	W.W.
180	REVISION NO. 179 FOR CONSTRUCTION	9/11/73	W.W.	W.W.
181	REVISION NO. 180 FOR CONSTRUCTION	10/11/73	W.W.	W.W.
182	REVISION NO. 181 FOR CONSTRUCTION	11/11/73	W.W.	W.W.
183	REVISION NO. 182 FOR CONSTRUCTION	12/11/73	W.W.	W.W.
184	REVISION NO. 183 FOR CONSTRUCTION	1/11/74	W.W.	W.W.
185	REVISION NO. 184 FOR CONSTRUCTION	2/11/74	W.W.	W.W.
186	REVISION NO. 185 FOR CONSTRUCTION	3/11/74	W.W.	W.W.
187	REVISION NO. 186 FOR CONSTRUCTION	4/11/74		





SECTION 'A-A'



PLAN  
ELEV 1052-8'

REINFORCEMENT SCHEDULE (CONT)				REINFORCEMENT SCHEDULE			
BAR	NO	SIZE	SPACING	REMARKS	BAR	NO	SIZE
1	1	1/2"	18"	IN HAIR	1	1	1/2"
2	2	1/2"	18"	IN HAIR	2	2	1/2"
3	3	1/2"	18"	IN HAIR	3	3	1/2"
4	4	1/2"	18"	IN HAIR	4	4	1/2"
5	5	1/2"	18"	IN HAIR	5	5	1/2"
6	6	1/2"	18"	IN HAIR	6	6	1/2"
7	7	1/2"	18"	IN HAIR	7	7	1/2"
8	8	1/2"	18"	IN HAIR	8	8	1/2"
9	9	1/2"	18"	IN HAIR	9	9	1/2"
10	10	1/2"	18"	IN HAIR	10	10	1/2"
11	11	1/2"	18"	IN HAIR	11	11	1/2"
12	12	1/2"	18"	IN HAIR	12	12	1/2"
13	13	1/2"	18"	IN HAIR	13	13	1/2"
14	14	1/2"	18"	IN HAIR	14	14	1/2"
15	15	1/2"	18"	IN HAIR	15	15	1/2"
16	16	1/2"	18"	IN HAIR	16	16	1/2"
17	17	1/2"	18"	IN HAIR	17	17	1/2"
18	18	1/2"	18"	IN HAIR	18	18	1/2"
19	19	1/2"	18"	IN HAIR	19	19	1/2"
20	20	1/2"	18"	IN HAIR	20	20	1/2"
21	21	1/2"	18"	IN HAIR	21	21	1/2"
22	22	1/2"	18"	IN HAIR	22	22	1/2"
23	23	1/2"	18"	IN HAIR	23	23	1/2"
24	24	1/2"	18"	IN HAIR	24	24	1/2"
25	25	1/2"	18"	IN HAIR	25	25	1/2"
26	26	1/2"	18"	IN HAIR	26	26	1/2"
27	27	1/2"	18"	IN HAIR	27	27	1/2"
28	28	1/2"	18"	IN HAIR	28	28	1/2"
29	29	1/2"	18"	IN HAIR	29	29	1/2"
30	30	1/2"	18"	IN HAIR	30	30	1/2"
31	31	1/2"	18"	IN HAIR	31	31	1/2"
32	32	1/2"	18"	IN HAIR	32	32	1/2"
33	33	1/2"	18"	IN HAIR	33	33	1/2"
34	34	1/2"	18"	IN HAIR	34	34	1/2"
35	35	1/2"	18"	IN HAIR	35	35	1/2"
36	36	1/2"	18"	IN HAIR	36	36	1/2"
37	37	1/2"	18"	IN HAIR	37	37	1/2"
38	38	1/2"	18"	IN HAIR	38	38	1/2"
39	39	1/2"	18"	IN HAIR	39	39	1/2"
40	40	1/2"	18"	IN HAIR	40	40	1/2"
41	41	1/2"	18"	IN HAIR	41	41	1/2"
42	42	1/2"	18"	IN HAIR	42	42	1/2"
43	43	1/2"	18"	IN HAIR	43	43	1/2"
44	44	1/2"	18"	IN HAIR	44	44	1/2"
45	45	1/2"	18"	IN HAIR	45	45	1/2"
46	46	1/2"	18"	IN HAIR	46	46	1/2"
47	47	1/2"	18"	IN HAIR	47	47	1/2"
48	48	1/2"	18"	IN HAIR	48	48	1/2"
49	49	1/2"	18"	IN HAIR	49	49	1/2"
50	50	1/2"	18"	IN HAIR	50	50	1/2"

REINFORCEMENT SCHEDULES DO NOT REPRESENT THE FINAL REINFORCEMENT IN THE TURBINE SUPPORT FOR THE TOWER. REINFORCEMENT SEE ALL UNLIDED SHEET NUMBER ON PLANS AND SECTIONS.



NOTES:  
SCALE 1/4"=1'-0"  
ESTIMATE COMPRESSION STRENGTH OF CONCRETE AT 28 DAYS TO BE 3000 PSI PER SQ IN. COMPRESSIVE TO TOP OF FACE OF CONCRETE AND CLEAR UNLIDED. CONTIGUOUS REINFORCING BARS TO BE LAPPED WITH 40 DIA AT UNLIDED OR AS NOTED. DESIGN BARS IN NEW TYPE DETACHED REINFORCING BARS (CONCRETE) TO BE WITH 5/8" DIA. A BAR.  
FOR TURBINE SUPPORT OUTLINES SEE DRAWING NO. 1052-8' FOR TOWER. FOR SECTION AND DETAILS NOT SHOWN ON THIS SHEET SEE DRAWING NO. 1052-8' FOR ALL OTHERS. CLEAR DISTANCES FROM FACE OF CONCRETE TO BE AS SHOWN. BARS AND CTS. ST. SLABS TOP BOTTOM WALLS AND HAIRYETS AT ALL DETACHED CONNECTIONS ARE TO BE OUT OF BARS.  
ALL LETTERED SECTIONS ARE DETAILED ON SHEETS CALLING FOR THEM. ALL NUMBERED SECTIONS ARE DETAILED IN OTHER DRAWINGS. SEE REFERENCE AT SECTION INDICATIONS.



NO.	DATE	DESCRIPTION
1	10/1/58	ISSUED FOR CONSTRUCTION
2	10/1/58	REVISED FOR CONSTRUCTION
3	10/1/58	REVISED FOR CONSTRUCTION
4	10/1/58	REVISED FOR CONSTRUCTION
5	10/1/58	REVISED FOR CONSTRUCTION
6	10/1/58	REVISED FOR CONSTRUCTION
7	10/1/58	REVISED FOR CONSTRUCTION
8	10/1/58	REVISED FOR CONSTRUCTION
9	10/1/58	REVISED FOR CONSTRUCTION
10	10/1/58	REVISED FOR CONSTRUCTION

TURBINE SUPPORT REINFORCING SHEET  
POWER STATION  
YANKEE ATOMIC ELECTRIC COMPANY  
ROWE, MASS.  
WINTERS & WINTERS ENGINEERING CORPORATION  
DRAWING NO. 9699-FC-20A


Fig. A.24



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1













**REINFORCING SCHEDULE**

NO.	NO. & SIZE	LENGTH	SPACING	REMARKS
101	4 #4 @ 27" O.C.			LOWER LAYER
102	3 #4 @ 30" O.C.			UPPER LAYER
103	1 #4 @ 17" O.C.			LOWER LAYER
104	1 #4 @ 30" O.C.			
105	3 #4 @ 30" O.C.			UPPER LAYER
106	3 #4 @ 30" O.C.			UPPER LAYER
107	14 #4 @ 30" O.C.			LOWER LAYER
108	4 #4 @ 30" O.C.			UPPER LAYER
109	4 #4 @ 30" O.C.			UPPER LAYER
110	24 #4 @ 30" O.C.			UPPER LAYER
111	8 #4 @ 25" O.C.			UPPER LAYER
112	8 #4 @ 15" O.C.			UPPER LAYER
113	1 #4 @ 30" O.C.			UPPER LAYER
114	4 #4 @ 30" O.C.			UPPER LAYER
115	1 #4 @ 30" O.C.			UPPER LAYER




REINFORCING SCHEDULES DO NOT EXTEND TO TOTAL DIMENSIONS OF THE STRUCTURE UNLESS INDICATED OTHERWISE. FOR TOTAL DIMENSIONS SEE ARCHITECTURAL DRAWINGS ON PLANS AND SECTIONS.

**NOTES:**  
 SCALE 1/4"=1'-0" EXCEPT AS NOTED OTHERWISE.  
 ULTIMATE COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS, BUT NOT LESS THAN 4000 PSI.  
 DIMENSIONS TO BEING FROM FACE OF CONCRETE, UNLESS OTHERWISE INDICATED.  
 CONTINUOUS REINFORCING BARS TO BE LAPPED WITH 40 DIA. AT TOPS OR AS NOTED.  
 DESIGN BASED ON NEW TYPE DEFORMED REINFORCING BARS, CONFORMING TO A.S.T.M. A630, SPC. 6, SDC.  
 FOR TURBINE SUPPORT FOUNDATION SEE CIVIL DRAWING 10-10-100-100.  
 FOR OTHERS AND DETAILS AND DIMENSIONS SEE CIVIL DRAWING 10-10-100-100.  
 MINIMUM CLEAR DISTANCE FROM FACE OF CONCRETE TO REINFORCING BARS AND TIES SHALL BE 7/8" BUT NOT LESS THAN 1 1/2".  
 ALL BENDING DIMENSIONS ARE SHOWN TO CENTER OF BAR.  
 ALL LETTERED SECTIONS ARE DETAIL IN SHEETS CALLING FOR THEM.  
 ALL DIMENSIONED SECTIONS ARE DETAIL IN OTHER DRAWINGS, SEE REFERENCE AT SECTION INDICATIONS.

NO.	REVISION	DATE	BY	CHKD.
1	ISSUED FOR CONSTRUCTION	11/17/54	AW	WMC
2	ORIGINAL SUBMITTED FOR CONCRETE CURING	11/17/54	AW	WMC
3	DESCRIPTION	11/17/54	AW	WMC

**TURBINE SUPPORT REINFORCING-SH. 4**  
**POWER STATION**  
**YANKEE ATOMIC ELECTRIC COMPANY**  
**ROWE, MASS.**  
 STONE & WEBSTER ENGINEERING CORPORATION  
 DRAWING NUMBER 9699-FC-200

Fig. A.27



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9; Rev. 1

APPENDIX B  
COMPUTER MODELS



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1

## APPENDIX B

### LIST OF FIGURES

#### I. HORIZONTAL MODELS

##### I.1 Turbine Building

- B.1 General Layout Plan
- B.2 Substructure Modeling
- B.3 Substructures at Elevation 1037'-8"
- B.4 Interconnected Floor Diaphragms  
at Elevation 1052'-8"
- B.5 Substructures at Elevation 1066'-0"
- B.6 Substructures at Elevation 1082'-8"
- B.7 Substructures at Elevation 1096'
- B.8 Modeling of Attached Buildings
- B.9 Schematic Representation -  
Turbine Building Stick Model

##### I.2 Turbine Pedestal

- B.10 Three Dimensional Model for Lateral Analysis


#### II. VERTICAL MODELS

##### II.1 Turbine Building

- B.11 Mechanical Model 1 for Vertical Analysis
- B.12 Mechanical Model 2 for Vertical Analysis
- B.13 Mechanical Model 3 for Vertical Analysis

##### II.2 Turbine Pedestal

- B.14 Stick Model for Vertical Analysis of  
Turbine Pedestal






FIG. B.1 GENERAL LAYOUT PLAN  
TURBINE BUILDING



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. B.2 SUBSTRUCTURE MODELING  
TURBINE BUILDING



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1




FIG. B.3 SUBSTRUCTURES AT ELEVATION 1037'-8"  
TURBINE BUILDING



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1





FIG. B.4 INTERCONNECTED FLOOR DIAPHRAGMS  
AT ELEVATION 1052'-8"



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1



**FIG. B.5 SUBSTRUCTURES AT ELEVATION 1066'-0"**  
**TURBINE BUILDING**



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1

LEGEND: (TYPICAL)

XXX DIAGONAL BRACES




FIG. B.6 SUBSTRUCTURES AT ELEVATION 1082'-8"  
TURBINE BUILDING



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1

LEGEND: (TYPICAL)

XXXX DIAGONAL BRACES






FIG. B.7 SUBSTRUCTURES AT ELEVATION 1096'  
TURBINE BUILDING



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1



PLAN VIEW  
ARRANGEMENT OF ATTACHED BUILDINGS




PLAN VIEW  
EQUIVALENT MODELING

FIG. B.8 MODELING OF ATTACHED BUILDINGS



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1



LEGEND: (TYPICAL)

— DIAPHRAGM LINK


○ DIAPHRAGMS

⚡ 1 DIMENSIONAL SPRING

FIG. B.9 SCHEMATIC REPRESENTATION  
TURBINE BUILDING STICK MODEL



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1





Column	X (ft.)	Y (ft.)
1	3.75	31.25
2	3.75	4.25
3	25.00	31.25
4	25.00	4.25
5	61.00	31.25
6	61.00	4.25
7	96.17	31.25
8	96.17	4.25



FIG. B.10 THREE DIMENSIONAL MODEL FOR LATERAL ANALYSIS OF TURBINE PEDESTAL



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1



SECTION "A" - PLAN

FIG. B.11 MECHANICAL MODEL 1 FOR VERTICAL ANALYSIS OF TURBINE BUILDING



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1





FIG. B.12 MECHANICAL MODEL 2 FOR VERTICAL ANALYSIS OF TURBINE BUILDING



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. B.13 MECHANICAL MODEL 3 FOR VERTICAL ANALYSIS OF TURBINE BUILDING



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1

Z - MODEL





FIG. B.14 STICK MODEL FOR VERTICAL ANALYSIS OF TURBINE PEDESTAL



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1

APPENDIX C  
EARTHQUAKE RESPONSE SPECTRA



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1

APPENDIX C

LIST OF FIGURES

C.1 Earthquake Response Spectrum



- ① NRC SPECTRUM,
- ② YANKEE COMPOSITE SPECTRUM,

PGA = 0.19G, DAMPING = 7%

PGA = 0.10G, DAMPING = 7%





FIG. C.1 EARTHQUAKE SPECTRA



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1

**APPENDIX D**  
**TABLE OF DYNAMIC CHARACTERISTICS**



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1

**APPENDIX D**

LIST OF TABLES

- D.1 Dynamic Characteristics - Turbine Building
- D.2 Dynamic Characteristics - Turbine Pedestal



TABLE D.1

## DYNAMIC CHARACTERISTICS - TURBINE BUILDING

Mode	F (Hz)	T (sec's)	Modal Mass k-s <sup>2</sup> /ft		Remarks
			X (EW)	Y (NS)	
1	1.56	0.641	0.0	1.1	Office Building, NS
2	1.77	0.564	0.9	0.0	Office Building, EW
3	2.24	0.447	0.8	18.9	Frame on Line 5, NS
4	2.34	0.427	4.9	3.5	Steel Frame Line C, EW
5	3.35	0.298	0.0	2.0	Turbine Building, NS
6	3.59	0.278	0.4	0.2	
7	4.25	0.235	0.1	0.0	
8	4.48	0.223	0.0	0.2	
9	4.72	0.212	0.5	0.0	Frame on Line 13, EW
10	4.80	0.209	0.0	0.0	
11	4.93	0.203	0.9	0.0	Frame on Line 13, EW
12	5.26	0.190	0.1	0.0	
13	5.49	0.182	0.0	0.0	
14	6.43	0.156	0.0	0.0	
15	6.66	0.150	0.0	0.0	
16	7.26	0.138	0.1	0.0	
17	7.33	0.136	0.0	0.0	
18	7.88	0.127	0.0	0.0	
19	7.96	0.126	0.0	0.0	
20	8.46	0.118	0.0	0.0	
21	8.92	0.112	0.0	0.0	
22	9.21	0.109	0.0	0.0	
23	9.94	0.101	0.1	0.0	Frame on Line 13, EW
24	10.23	0.098	0.0	0.0	
25	12.34	0.081	8.8	0.0	Office Building, EW
26	12.64	0.079	6.6	0.0	Steel Frame Line C, EW
27	14.02	0.071	0.4	0.0	
28	14.82	0.068	0.1	0.1	
29	15.30	0.065	0.3	1.1	Turbine Building, NS
30	15.64	0.064	0.0	0.0	
31	16.57	0.060	0.6	0.0	Steel Frame Line C, EW



TABLE D.2

DYNAMIC CHARACTERISTICS - TURBINE PEDESTAL

Natural Frequencies

Mode	F (Hz)	T (sec's)	Modal Mass k-s <sup>2</sup> /ft		Remarks
			X (EW)	Y (NS)	
1	7.42	.135	100.	0.	E-W Mode
2	8.64	.116	0.	94.5	N-S Mode
3	10.2	.098	0.	5.5	Torsional Mode



**APPENDIX E**  
**RESULTS OF ANALYSIS**



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1

## APPENDIX E

### LIST OF TABLES

#### I. TURBINE BUILDING - EVALUATION FOR YCS

- E.1 Summary Information
- E.2 Stresses in Diagonal Braces
- E.3 Evaluation of Brace to Beam-Column  
Joint Connections
- E.4 Foundation Load Summary

#### II. TURBINE BUILDING - EVALUATION FOR NRC SPECTRUM

- E.5 Summary Information
- E.6 Stresses in Diagonal Braces
- E.7 Evaluation of Brace to Beam-Column Joint Connections
- E.8 Foundation Load Summary

#### III. TURBINE PEDESTAL - EVALUATION FOR NRC SPECTRUM

- E.9 Summary Information
- E.10 Evaluation of Columns
- E.11 Evaluation of Beams

#### IV. TURBINE PEDESTAL - EVALUATION FOR NRC SPECTRUM

- E.12 Summary Information
- E.13 Evaluation of Columns
- E.14 Evaluation of Beams



**TABLE E.1**

SUMMARY INFORMATION - TURBINE BUILDING  
 EVALUATION FOR YANKEE COMPOSITE SPECTRUM 7% DAMPING

Structure	Turbine Building			
Model	Building without fixes, no block walls			
Structural Materials	Reinforced Concrete Walls	$f'_c$	= 2500 psi	
	Steel Braces	$F_y$	= 33 ksi (existing)	
			= 36 ksi (new)	
	Unreinforced Concrete	$f'_m$	= 1000 psi (ASTM C-90)	
	Masonry Walls, not grouted	$f'_m$	= 440 psi (ASTM C-129) Type N Mortar	
Clearance	1.0 in X and Y directions around Turbine Pedestal at Elevation 1052'-8".			
Maximum Displacement (YCS) (Approximate)	X (EW): 0.04 Y (NS): 0.26	$\frac{CL.}{Max. Displ.}$	= X: 25.0 Y: 3.83	
Dynamic Properties	Total Mass	330.0 K-S /FT		
	Total Weight	10626 K		
	Seismic Base Shears (YCS SPECTRUM)	X (EW):	923 K = 8.7%W	
		Y (NS):	1548 K = 14.6%W	
	Predominant Natural Periods:	X (EW):	0.081 sec.	
Y (NS):		0.447 sec.		



TABLE E.2

EVALUATION OF DIAGONAL BRACES - TURBINE BUILDING

(YCS SPECTRUM 7% DAMPING)

Story	Frame	Column	P Seismic (kips)	f <sub>a</sub> (ksi)	F <sub>A</sub> per AISC Part I (ksi)	$\frac{f_a}{F_A}$
1096'	5	C-D	75.	6.4	17.1	.37
1096'	5	G-F	56.	4.8	17.1	.28
1082'-8"	5	D-F	143.4	9.8	18.6	.53
1066'-0"	5	D-F	161.	11.0	18.6	.59
1052'-8"	5	F-G	220.	18.7	18.2	1.03
1037'-8"	5	D-E	131.	11.1	22.6	.49
1037'-8"	5	E-F	131.	11.1	22.6	.49
1096'-0"	G	9-8	127.	11.8	18.9	0.57
1082'-8"	G	8-7	146.	12.4	19.4	0.64
1052'-8"	G	12-11	38.	3.2	19.4	0.17
1037'-8"	G	11-10	24.	2.0	19.4	0.11
1096'	13	C-D	57.1	4.9	17.1	.29
1096'	13	F-G	52.	4.4	17.1	.27
1082'-8"	13	D-F	124.	8.4	18.6	.45
1066'-0"	13	D-F	132.	9.0	18.6	.48
1052'-8"	13	F-G	106.	9.0	18.2	.49
1037'-8"	13	F-G	108.3	9.2	18.0	.51
1096'-0"	C	12-11	83.	7.1	17.3	0.41
1082'-8"	C	11-10	158.	13.4	18.0	0.75
1066'-0"	C	10-9	154.	13.1	18.0	0.73
1052'-8"	C	9-8	118.	10.0	18.4	0.55
1037'-8"	C	8-9	127.	10.8	18.4	0.59



TABLE E.3

EVALUATION OF BRACE TO BEAM-COLUMN JOINT CONNECTIONS  
TURBINE BUILDING

LOADS IN BRACE TO BEAM-COLUMN JOINT CONNECTION  
LOADING: YANKEE COMPOSITE SPECTRUM 7% DAMPING

Connection Level Above	Frame Line	Column ID At Top	Braced Load P <sub>seismic</sub>	Connection Capacity As Per AISC Sect. 1.5.2	Remarks
1096'	13	C	75.	201	OK - original design for wind controls
1096'	G	9	127.	167	OK
1082' -8"	13	F	124.	436	OK - original design for wind controls
1082' -8"	G	8	146.	235	OK
1066' -0"	5	F	161.	235	OK
1066' -0"	C	10	155.	302	OK
1052' -8"	13	F	106.	302	OK
1037' -8"	5	E	131.	176	OK
1037' -8"	5	E	131.	176	OK
1037' -8"	13	F	108.3	302	OK




TABLE E.4

FOUNDATION LOAD SUMMARY - TURBINE BUILDING  
EVALUATION FOR YCS SPECTRUM 7% DAMPING

Ftg. Id.	Dead Load 1			Live Load, 2	Seismic Load, 3	Combination		Ftg. Capacity
	Col.	Ftg.	Overlying Soil			1+2+3	1-3	
C-13	39	31	41	277	36	424	75	678
D-13	81	25	26	247	75	454	57	623
F-13	81	22	19	247	66	435	56	623
G-13/RC	268+264	88	79	355	211	1265	488	1781
G-12	561	76	53	638	61	1389	629	1830
G-11	566	63	46	625	9	1309	666	1621
G-10	566	76	53	625	13	1333	682	1830
G-9	566	86	104	625	82	1463	674	1921
G-8/RC	278+264	111	107	630	508	1898	252	2035
G-7	126	45	34	550	85	840	120	1145
G-5	101	21	29	379	151	681	0	797
J-8/RC	28+2313	252	262	82+221	497	3655	2358	6455
J-7	28	8	6	82	0	124	42	215
J-5	29	6	5	56	0	96	40	170
F-5	108	30	25	301	140	604	23	848
E-5	7	4	4	22	0	37	15	130
D-5	108	41	43	301	176	669	16	954
C-5	32	25	23	250	47	377	33	596
C-12	87	38	35	419	54	633	106	742
C-11	87	36	33	419	40	615	116	795
C-10	87	60	62	419	22	650	187	848
C-9	87	78	100	419	45	729	220	1272
C-8	87	54	56	419	130	746	67	919
C-7	87	62	61	419	0	629	210	795
J-13	2313	229	262	221	386	3411	2418	6074

- NOTES: 1. Col. dead and live loads are from S&W Dwg. #FS-2B.  
 2. Ftg. wt. includes concrete pedestal and grade beam, if any.  
 3. Overlying soil wt =  $0.1 \text{ ksf} \times (A_{\text{ftg}} - A_{\text{pedestal}} + \text{grade beam}) \times (1022'-8'' - \text{T.O. Ftg Elev.})$



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1

TABLE E.5

SUMMARY INFORMATION - TURBINE BUILDING  
EVALUATION FOR NRC SPECTRUM 7% DAMPING

Structure	Turbine Building			
Model	Building without fixes, no block walls			
Structural Materials	Reinforced Concrete Walls	$f'_C$	= 2500 psi	
	Steel Braces	$F_y$	= 33 ksi (existing)	
			= 36 ksi (new)	
	Unreinforced Concrete	$f'_m$	= 1000 psi (ASTM C-90)	
	Masonry Walls, not grouted	$f'_m$	= 440 psi (ASTM C-129) Type N Mortar	
Clearance	1.0 in X and Y directions around Turbine Pedestal at Elevation 1052'-8".			
Maximum Displacement (Approximate)	X (EW): 0.08"	$\frac{CL.}{Max. Displ.} =$	X: 12.5	
	Y (NS): 0.51"		Y: 2.0	
Dynamic Properties	Total Mass	330.0 K-S <sup>2</sup> /FT		
	Total Weight	10626 K		
	Seismic Base Shears	X (EW):	1520 K = 14.3%W	
		Y (NS):	2863 K = 27.0%W	
	Predominant Natural Periods:	X (EW):	0.081 sec.	
Y (NS):		0.447 sec.		




TABLE E.6

EVALUATION OF DIAGONAL BRACES - TURBINE BUILDING  
 STRESSES IN DIAGONAL BRACES  
 LOADING: NRC SPECTRUM 7% DAMPING

Story	Frame	Column	P Seismic (kips)	f <sub>a</sub> (ksi)	F <sub>A</sub> per AISC Part I (ksi)	$\frac{f_a}{F_A}$
1096'	5	C-D	147.	12.5	17.1	.73
1096'	5	G-F	112.	9.6	17.1	.56
1082'-8"	5	D-F	285.	19.4	18.6	1.04
1066'-0"	5	D-F	318.	21.6	18.6	1.16
1052'-8"	5	F-G	427.	36.3	18.2	1.99
1037'-8"	5	D-E	254.	21.6	22.6	.96
1037'-8"	5	E-F	254.	21.6	22.6	.96
1096'-0"	G	9-8	252.	21.4	18.9	1.13
1082'-8"	G	8-7	290.	24.7	19.4	1.27
1052'-8"	G	12-11	74.	6.3	19.4	0.32
1037'-8"	G	11-10	75.	6.4	19.4	0.33
1096'	13	C-D	114.	9.7	17.1	.57
1096'	13	G-F	105.	9.0	17.1	.53
1082'-8"	13	F-D	249.	16.9	18.6	.91
1066'-0"	13	D-F	263.	17.9	18.6	.96
1052'-8"	13	F-G	207.	17.6	18.2	.97
1037'-8"	13	F-G	212.	18.1	18.2	1.00
1096'-0"	C	12-11	165.	14.0	17.3	0.81
1082'-8"	C	11-10	311.	26.4	18.0	1.47
1066'-0"	C	10-9	304.	25.8	18.0	1.44
1052'-8"	C	9-8	229.	19.5	18.4	1.06
1037'-8"	C	8-9	246.	20.9	18.4	1.14



TABLE E.7

EVALUATION OF BRACE TO BEAM-COLUMN JOINT CONNECTIONS  
 TURBINE BUILDING  
 LOADS IN BRACE TO BEAM-COLUMN JOINT CONNECTION  
 LOADING: NRC SPECTRUM 7% DAMPING

Connection Level Above	Frame Line	Column ID At Top	Braced Load (kips) P <sub>seismic</sub>	Connection Capacity As Per AISC Sect. 1.5.2	Remarks
1096'	13	C	114.	201	OK - original design for wind controls
1096'	G	9	252.	167	Overstressed
1082'-8"	13	F	248.	436	OK - original design for wind controls
1082'-8"	G	8	290.	235	Overstressed
1066'-0"	5	F	318.	235	Overstressed
1066'-0"	C	10	305.	302	OK
1052'-8"	13	F	207.	302	OK
1037'-8"	5	E	254.	176	Overstressed
1037'-8"	5	E	254.	176	Overstressed
1037'-8"	13	F	212.	302	OK




TABLE E.8

FOUNDATION LOAD SUMMARY - TURBINE BUILDING  
EVALUATION FOR NRC SPECTRUM 7% DAMPING

Ftg. Id.	Dead Load 1			Live Load, 2	Seismic Load, 3	Combination		Ftg. Capacity
	Col.	Ftg.	Overlying Soil			1+2+3	1-3	
C-13	39	31	41	277	72	460	39	678
D-13	81	25	26	247	150	529	-18	623
F-13	81	22	19	247	137	506	-15	623
G-13/RC	268+264	88	79	355	475	1529	224	1781
G-12	561	76	53	638	120	1448	570	1830
G-11	566	63	46	625	17	1317	658	1621
G-10	566	76	53	625	25	1345	670	1830
G-9	566	86	104	625	163	1544	593	1921
G-8/RC	278+264	111	107	630	986	2376	-226	2035
G-7	126	45	34	550	170	925	35	1145
G-5	101	21	29	379	293	823	-142	797
J-8/RC	28+2313	252	262	82+221	964	4122	1891	6455
J-7	28	8	6	82	0	124	42	215
J-5	29	6	5	56	0	96	40	170
F-5	108	30	25	301	280	744	-117	848
E-5	7	4	4	22	0	37	15	130
D-5	108	41	43	301	345	838	-153	954
C-5	32	25	23	250	93	423	-13	596
C-12	87	38	35	419	107	686	53	742
C-11	87	36	33	419	80	811	76	795
C-10	87	60	62	419	43	671	166	848
C-9	87	78	100	419	87	771	178	1272
C-8	87	54	56	419	255	1068	-58	919
C-7	87	62	61	419	0	629	210	795
J-13	2313	229	262	221	757	3782	2047	6074

- NOTES: 1. Col. dead and live loads are from S&W Dwg. #FS-2B.  
 2. Ftg. wt. includes concrete pedestal and grade beam, if any.  
 3. Overlying soil wt =  $0.1 \text{ ksf} \times (A_{\text{ftg}} - A_{\text{pedestal}} + \text{grade beam}) \times (1022' - 8'' - \text{T.O. Ftg Elev.})$



TABLE E.9

SUMMARY INFORMATION - TURBINE PEDESTAL  
EVALUATION FOR YANKEE COMPOSITE SPECTRUM 7% DAMPING)

Structure	Turbine Pedestal		
Model	Three-Dimensional Space Frame		
Structural Materials	Concrete	$f'_c$	= 3000 psi
	Steel Reinforcement	$F_y$	= 40 ksi (existing)
Clearance	1.0 in X and Y directions at Elevation 1052'-8".		
Maximum Displacement (Approximate)	X (EW): 0.03"	CL. =	X: 33
	Y (NS): 0.02"	Max. Displ.	Y: 50
Dynamic Properties	Total Mass	160.9 K-S <sup>2</sup> /FT	
	Total Weight	5182 K	
	Seismic Base Shears	X (EW):	979 K = 18.9%W
		Y (NS):	893 K = 17.2%W
	Predominant Natural Periods:	X (EW):	0.135 sec.
		Y (NS):	0.116 sec.



TABLE E.10

EVALUATION OF COLUMNS - TURBINE PEDESTAL  
 STRESS RESULTANTS IN COLUMNS  
 SEISMIC LOADING: YANKEE COMPOSITE SPECTRUM  
 7% DAMPING

Column Id.	Member Loads Combined Dead and Seismic			Ultimate Strengths Under Axial Load P		Result of* Biaxial Moment Interaction Eq. < 1.0
	P (kips)	Mns (ft-kips)	Mew (ft-kips)	Mns (ft-kips)	Mew (ft-kips)	
C1, C2	423	1390	420	6000	4390	.03
C3, C4	878	1540	1090	6220	8480	.06
C5, C6	745	3020	1940	7200	13800	.07
C7, C8	244	2420	2680	7420	8360	.12

\*Biaxial Moment Interaction Equation:

$$\left(\frac{M_x}{M_{ox}}\right)^n + \left(\frac{M_y}{M_{oy}}\right)^n < 1.0$$

where:

- n = 2.4 for Columns C1, C2, C5, and C6
- n = 2.2 for Columns C3 and C4
- n = 2.5 for Columns C7 and C8




TABLE E.11

EVALUATION OF BEAMS - TURBINE PEDESTAL  
 STRESS RESULTANTS IN BEAMS  
 SEISMIC LOADING: YANKEE COMPOSITE SPECTRUM 7% DAMPING

Beam	SHEAR (KIPS)					MOMENT (KT-KIPS)				
	Dead Load $V_D$	Seismic (SRSS) $V_E$	Sum $V_D + V_E$	Concrete Ultimate Strength $\phi V_C$	Load Ultimate Strength	Dead Load $M_d$	Seismic (SRSS) $M_e$	Sum $M_e + M_d$	Ultimate Strength $\phi M_u$	Load Ultimate Strength
B1	33	134	167	583	.29	529	736	1265	7450	.17
B2	103	166	169	779	.22	1291	999	2290	11900	.19
B3	138	136	274	1060	.26	1438	1622	3060	13900	.22
B4	33	134	167	583	.29	529	736	1265	7450	.17
B5	103	66	169	779	.22	1291	999	2290	11900	.19
B6	138	136	274	1060	.26	1438	1622	3060	13900	.22
B7	27	35	62	414	.15	156	331	487	4530	.11
B8	2	99	101	670	.15	248	936	1184	9610	.12
B9	0	258	258	628	.41	114	1612	1726	8160	.22
B10	0	264	264	919	.29	68	1652	1584	9730	.16




TABLE E.12

SUMMARY INFORMATION - TURBINE PEDESTAL  
EVALUATION FOR NRC SPECTRUM 7% DAMPING

Structure	Turbine Pedestal		
Model	Three-Dimensional Space Frame		
Structural Materials	Concrete	$f'_c$	= 3000 psi
	Steel Reinforcement	$F_y$	= 40 ksi
Clearance	1.0 in X and Y directions around Turbine Pedestal at Elevation 1052'-8".		
Maximum Displacement (Approximate)	X (EW): 0.06"	CL. =	X: 17
	Y (NS): 0.04"	Max. Displ. =	Y: 25
Dynamic Properties	Total Mass	160.9 K-S <sup>2</sup> /FT	
	Total Weight	5182 K	
	Seismic Base Shears	X (EW):	1645 K = 31.7%W
		Y (NS):	1427 K = 27.5%W
	Predominant Natural Periods:	X (EW):	0.135 sec.
		Y (NS):	0.116 sec.



TABLE E.13

EVALUATION OF COLUMNS - TURBINE PEDESTAL  
 STRESS RESULTANTS IN COLUMNS  
 SEISMIC LOADING: NRC SPECTRUM 7% DAMPING

Column Id.	Member Loads. Combined Dead and Seismic			Ultimate Strengths Under Axial Load P		Result of* Biaxial Moment Interaction Eq. < 1.0
	P (kips)	Mns (ft-kips)	Mew (ft-kips)	Mns (ft-kips)	Mew (ft-kips)	
C1, C2	517	2300	620	6300	4600	0.11
C3, C4	950	2510	1670	6400	8600	0.15
C5, C6	583	3460	4590	6790	13160	0.25
C7, C8	67	3950	4260	6810	7700	0.44

\*Biaxial Moment Interaction Equation:

$$\left(\frac{M_x}{M_{ox}}\right)^n + \left(\frac{M_y}{M_{oy}}\right)^n < 1.0$$

where:

- n = 2.4 for Columns C1 through C4
- n = 2.5 for Columns C5 and C6
- n = 2.65 for Columns C7 and C8




TABLE E.14

EVALUATION OF BEAMS - TURBINE PEDESTAL  
 STRESS RESULTANTS IN BEAMS  
 SEISMIC LOADING: NRC SPECTRUM 7% DAMPING

Beam	SHEAR (KIPS)					MOMENT (KT-KIPS)				
	Dead Load $V_D$	Seismic (SRSS) $V_E$	Sum $V_D + V_E$	Concrete Ultimate Strength $\phi V_C$	Load Ultimate Strength	Dead Load $M_d$	Seismic (SRSS) $M_e$	Sum $M_e + M_d$	Ultimate Strength $\phi M_u$	Load Ultimate Strength
B1	33	223	256	583	0.44	529	1230	1759	7450	0.24
B2	103	110	213	779	0.27	1291	1663	2954	11900	0.25
B3	138	227	365	1060	0.34	1438	2715	4153	13900	0.30
B4	33	223	256	583	0.44	529	1230	1759	7450	0.24
B5	103	110	213	779	0.27	1291	1663	2954	11900	0.25
B6	138	227	365	1060	0.34	1438	2715	4153	13900	0.30
B7	27	56	83	414	0.2	156	527	683	4530	0.15
B8	2	157	159	670	0.24	248	1494	1742	9610	0.18
B9	0	412	412	628	0.66	114	2576	2690	8160	0.33
B10	0	422	422	919	0.46	68	2639	2707	9730	0.28



**APPENDIX F**  
**AMPLIFIED RESPONSE SPECTRA**



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1

## APPENDIX F

### LIST OF FIGURES

#### I. TURBINE BUILDING

- F.1 ARS Location Key Plan
- F.2 PT. 1 ARS N-S 2% and 3% Damping, YCS
- F.3 PT. 1 ARS E-W 2% and 3% Damping, YCS
- F.4 PT. 1 ARS Vertical 2% and 3% Damping, YCS
- F.5 PT. 2 ARS N-S 2% and 3% Damping, YCS
- F.6 PT. 2 ARS E-W 2% and 3% Damping, YCS
- F.7 PT. 2 ARS Vertical 2% and 3% Damping, YCS
- F.8 PT. 1 ARS N-S 2% and 3% Damping, NRC Spectrum
- F.9 PT. 1 ARS E-W 2% and 3% Damping, NRC Spectrum
- F.10 PT. 1 ARS Vertical 2% and 3% Damping, NRC Spectrum
- F.11 PT. 2 ARS N-S 2% and 3% Damping, NRC Spectrum
- F.12 PT. 2 ARS E-W 2% and 3% Damping, NRC Spectrum
- F.13 PT. 2 ARS Vertical 2% and 3% Damping, NRC Spectrum

#### II. TURBINE PEDESTAL

- F.14 ARS Location Key Plan
- F.15 PT. 106 ARS N-S 3% Damping, YCS
- F.16 PT. 106 ARS E-W 3% Damping, YCS
- F.17 PT. 106 ARS Vertical 3% Damping, YCS
- F.18 PT. 106 ARS N-S 3% Damping, NRC Spectrum
- F.19 PT. 106 ARS E-W 3% Damping, NRC Spectrum
- F.20 PT. 106 ARS Vertical 3% Damping, NRC Spectrum






FIG. F.1 ARS LOCATION KEY PLAN  
TURBINE BUILDING



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.2



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.3






FIG. F.4






FIG. F.5






FIG. F.6







FIG. F.7






FIG. F.8



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.9



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.10



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.11






FIG. F.12






FIG. F.13






FIG. F.14



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.15



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.16



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.17






FIG. F.18



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.19



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1




FIG. F.20



Yankee Atomic Electric Company  
 Turbine Building and Turbine Pedestal  
 80023; Report No. EY-YR-80023-9, Rev. 1

**APPENDIX G**

**REFERENCES**



Yankee Atomic Electric Company  
Turbine Building and Turbine Pedestal  
80023; Report No. EY-YR-80023-9; Rev. 1

## APPENDIX G

### REFERENCES

1. "Seismic Reevaluation and Retrofit Criteria for Yankee Nuclear Power Station, Rowe, Massachusetts," Cygna Energy Services, Rev. 2, August 1982.
2. "Manual of Steel Construction," Fifth Edition, AISC, 1954.
3. "Manual of Steel Construction," Eighth Edition, AISC, 1980.
4. "Building Code Requirements for Reinforced Concrete," AC1318-77, American Concrete Institute, 1977.
5. Ozdemir, H., and P. Lau, "BATS, A Computer Program for Analysis of Multistory Frame and Shear Wall Building Systems," Earthquake Engineering Systems, Inc., February, 1980.
6. Ozdemir, H., and P. Lau, "MOST, A Computer Program for Mode Superposition Time-History Analysis," Earthquake Engineering Systems, Inc., October, 1980.
7. Ozdemir, H. and P. Lau, "INSPEC, A Computer Program for Calculating Spectra," Earthquake Engineering Systems, Inc., November, 1979.
8. "NRCQUAKE, A Computer Program for Generating Synthetic Time-Histories," Cygna Energy Services, 1980.

