

6. With one standby gas treatment system circuit inoperable:

a. During Power Operation:

- (1) Verify the operability of the other standby gas treatment system circuit within 2 hours. If testing is required to demonstrate operability and significant painting, fire, or chemical release has taken place in the reactor building within the previous 12 hours, then demonstration by testing shall take place within 1 hour of the expiration of the 12 hour period, and
- (2) Continue to verify the operability of the standby gas treatment system circuit once per 24 hours until the inoperable standby gas treatment circuit is returned to operable status.
- (3) Restore the inoperable standby gas treatment circuit to operable status within 7 days or be subcritical with reactor coolant temperature less than 212°F within the next 36 hours.

b. During Refueling:

- (1) Verify the operability of the other standby gas treatment system within 2 hours. If testing is required to demonstrate operability and significant painting, fire, or chemical release has taken place in the reactor building within the previous 12 hours, then demonstration by testing shall take place within 1 hour of the expiration of the 12 hour period, and
- (2) Continue to verify the operability of the redundant standby gas treatment system once per 7 days until the inoperable system is returned to operable status.
- (3) Restore the inoperable standby gas treatment system to operable status within 30 days or cease all spent fuel handling, core alterations or operation that could reduce the shutdown margin (excluding reactor coolant temperature changes).

7. If Specifications 3.5.B.5 and 3.5.B.6 are not met, reactor shutdown shall be initiated and the reactor shall be in the cold shutdown condition within 24 hours and the condition of Specification 3.5.B.1 shall be met.

OYSTER CREEK

3.5-7 Amendment No.: 14,18,32,74,103,167,168

9404010235 940328  
PDR ADOCK 05000219  
P PDR