


Georgia Power Company
40 Inverness Center Parkway
Post Office Box 1295
Birmingham, Alabama 35201
Telephone 205 877-7122

C. K. McCoy
Vice President, Nuclear
Vogtle Project



March 31, 1994

LCV-0210-B

Docket Nos. 50-424
50-425

TAC Nos. M80515
M80516

U. S. Nuclear Regulatory Commission
ATTN: Document Control Desk
Washington, D. C. 20555

Gentlemen:

VOGTLE ELECTRIC GENERATING PLANT
DIFFERENTIAL SETTLEMENT OF BURIED PIPE ADDITIONAL INFORMATION

The August 23, 1991, letter from the NRC to Mr. W. G. Hairston, III transmitted the Safety Evaluation Report (SER) regarding the VEGP settlement monitoring program. In section 2.4 of the SER, "Differential Settlement of Buried Pipe," the staff questioned the validity of the piping analyses. A January 8, 1993, letter from Mr. C. K. McCoy to the NRC responded to the SER concern regarding the validity of the piping analyses by reporting the evaluation of all safety related buried piping.

During an June 15, 1993, telephone conference to discuss this submitted evaluation data, further questions were asked by the staff. Enclosure 1 is our responses to these questions. Also, the staff requested additional data which are provided as Enclosures 2, 3a, 3b, and 4.

Should you have any additional questions, please inquire.

Sincerely,

C.K. McCoy
C. K. McCoy

CKM/JLL/gmb

cc: (See next page)

9404130174 940331
PDR ADDCK 05000424
P PDR

ADD 1/1

U. S. Nuclear Regulatory Commission

Page 2

cc: Georgia Power Company
Mr. J. B. Beasley, Jr.
Mr. M. Sheibani
NORMS

U. S. Nuclear Regulatory Commission
Mr. S. D. Ebnetter, Regional Administrator
Mr. D. S. Hood, Licensing Project Manager, NRR
Mr. B. R. Bonser, Senior Resident Inspector, Vogtle

LCV-0210B

ENCLOSURE 1

1. QUESTION:

What is the definition of "actual differential settlement"?

ANSWER:

The "actual differential settlement" of the buried pipe is the total amount of differential settlement (at the marker where pipe enters the structure) from the time the pipe/support (as applicable) was installed until the settlement reading at the time of the engineering evaluation.

A detailed explanation of the methodology for determining the "actual differential settlement" for buried pipe, including our conservative assumptions, is contained in section 1 on page 2 of our letter ELV-03975 dated January 8, 1993.

2. QUESTION:

Provide the settlement data and the calculations of "actual differential settlement" for the following locations:

<u>Line Number</u>	<u>Marker Number</u>
1-1202-029-6"	196
1-2403-044-4"	132-R
1-2403-043-4"	132-R
1-2403-066-3"	145-R
1-2403-043-4"	145-R
2-1202-030-6"	260-R

ANSWER:

Copies of the relevant pages of the survey data sheets have been previously provided with Mr. C. K. McCoy's letter dated January 7, 1994 (LCV-0210). The civil calculation are provided as Enclosure 2.

3. QUESTION:

Provide the stress/support analysis and model for line numbers 1-1202-029-6" and 2-1202-030-6".

ANSWER:

Copies of relevant pages of the stress/support calculations and model are Enclosures 3a and 3b.

ENCLOSURE 1 (CONTINUED)

4. QUESTION:

The "actual differential settlement" value for line number 2-1202-030-6" at marker 260-R is approximately 77 percent of the design differential settlement. Was the approach for reviewing similar cases which exceed 75 percent, as outlined on the Settlement Monitoring Program Flow Chart, used in conjunction with this line?

ANSWER:

The Settlement Monitoring Program Flow Chart outlines the design methodology used to monitor the differential settlement of interconnecting pipes between buildings. The criteria for comparison of the "actual differential settlement" to 75 percent of the design differential settlement was established as an early indicator to identify any interconnecting pipes which might require closer monitoring or modification to the pipe/support to prevent an overstressed condition from occurring.

As we have previously stated, buried pipe is not addressed by our normal settlement monitoring program and regular engineering reviews have not been conducted. However, the method outlined in the flow chart was used during this evaluation process of the buried pipe, including line 2-1202-030-6'.

Although the "actual differential settlement" of this buried pipe was higher than the 75 percent early indicator used for future settlement of interconnecting pipes, the amount was evaluated and it was determined not to be a concern based on engineering judgment. In addition the 75 percent early indicator was not considered a valid concern in the case of this buried pipe because of the probability of settlement of the compacted backfill. Since the "actual differential settlement" is based on our conservative assumption (zero settlement for compacted backfill), a high value may appear to be of concern but the real value is likely to be considerably less.

In the process of preparing the responses to these questions, a field walk down was performed to visually inspect the critical support on this line. This inspection confirmed that a gap still exists between the pipe and the support strap (the controlling component of the support), thereby verifying the fact that no stresses have been induced into the support strap by differential settlement. The result of this walkdown (i.e. the existence of a gap between pipe and strap) confirms that our assumption is overly conservative and appears to substantiate our original position that the compacted backfill will settle at approximately the same magnitude as the structures, thereby producing minimal differential settlement.

ENCLOSURE 1 (CONTINUED)

5. QUESTION:

The Settlement Monitoring Program Flow Chart has no provisions when the "actual differential settlement" still exceeds the design differential settlement after the process has been completed. Modify the flow chart to reflect this comment.

ANSWER:

The flow chart has been revised. The revised flow chart is Enclosure 4.

6. QUESTION:

For line 2-1202-030-6" at marker 260-R, explain why the allowable differential settlement submitted in the January 8, 1993 letter ELV-03975 to the NRC is different from that submitted previously.

ANSWER:

The "allowable differential settlement" for this line was based on the support being the controlling factor. During the latest evaluation, more refined analyses were performed for those cases where the support is controlling. In the process of performing these analyses, a design input error was found in the original analysis. Reanalysis corrected the error and resulted in a lower allowable value for the support.

ENCLOSURE 2

Calculation X2A30.1.6

Project VOGTLE	Prepared By R. FLOWERS	Date 6-15-92
Subject/Title SETTLEMENT MONITORING PROGRAM	Reviewed By H. (S. N. AMIN)	Date 6-17-92
DIFFERENTIAL SETTLEMENT OF BURIED PIPE	Calculation Number XZCA30.1.6	Sheet 1 of 77

SHEET 1a Follows

PURPOSE OF CALCULATION

THIS CALCULATION IS REQUIRED TO DETERMINE THE ACTUAL DIFFERENTIAL SETTLEMENT FOR THE FOLLOWING SAFETY RELATED BURIED PIPES : SEE FOLLOWING PAGE SHEET 1a.

1-1202-029-6"	2-1202-029-6"	ZAF 7-14-92 JOC 9/10/92
1-2403-044-4"	2-1202-030-6"	
1-2403-053-2"	2-2403-053-2"	
1-2403-043-4"	2-2403-043-4"	
1-2403-066-3"		
1-2403-069-2"		

ASSUMPTIONS

- 1) NO SETTLEMENT WILL OCCUR IN THE SOIL
- 2) SETTLEMENT OF THE STRUCTURE AT THE TIME OF INSTALLATION FOR THE PIPE AND/OR SUPPORT WILL BE DETERMINED BY USING A STRAIGHT LINE INTERPOLATION OF THE DATA.
- 3) DATA USED FOR TOTAL SETTLEMENT WAS TAKEN USING THE DATES PREVIOUSLY SUBMITTED TO THE NRC* (i.e. DURING MAY & JUNE 1989).

REFERENCES

- 1) QUANTITY TRACKING SYSTEM (QTS) PIPE LOG LISTING
- 2) QTS SUPPORT STATUS LOG
- 3) QTS WELD LOG LISTING
- 4) SETTLEMENT SURVEYING DATA

*THIS DATA WAS ISSUED TO THE NRC BY LETTER ELV-01376 WRITTEN ON MARCH 19, 1990 BY MR W. G. HANSTON, III.

Project VOGTLE	Prepared By R. Flowers	Date 9-2-92
Subject/Title SETTLEMENT MONITORING PROGRAM	Reviewed By J. Chaffin	Date 9/10/92
DIFFERENTIAL SETTLEMENT OF BURIED PIPE	Calculation Number XZCA30.1.6	Sheet 1a of 77

SHEET 1b FOLLOWS

LIST OF SAFETY RELATED BURIED PIPE AND INTERFACING
STRUCTURE :

Line No.	Interface
1-1202-029-6"	NSCW Valvehouse Train A
1-1202-030-6"	NSCW Valvehouse Train A
1-1202-029-6"	Tunnel 1T2B
1-1202-030-6"	Tunnel 1T2B
1-2403-044-4"	Diesel Generator Building
1-2403-066-3"	Diesel Generator Building
1-2403-053-2"	Diesel Generator Building
1-2403-051-2"	Diesel Generator Building
1-2403-068-3"	Diesel Generator Building
1-2403-043-4"	Diesel Generator Building
1-2403-044-4"	DFOST Pumphouse
1-2403-044-4"	DFOST Pumphouse Footing (See note 1)
1-2403-066-3"	DFOST Pumphouse
1-2403-053-2"	DFOST Pumphouse
1-2403-069-2"	DFOST Pumphouse
1-2403-069-2"	DFOST Pumphouse Footing (See note 1)
1-2403-051-2"	DFOST Pumphouse
1-2403-068-3"	DFOST Pumphouse
1-2403-043-4"	DFOST Pumphouse
2-1202-029-6"	NSCW Valvehouse Train A
2-1202-030-6"	NSCW Valvehouse Train A
2-1202-029-6"	Tunnel 2T2B
2-1202-030-6"	Tunnel 2T2B
2-2403-044-4"	Diesel Generator Building
2-2403-066-3"	Diesel Generator Building
2-2403-053-2"	Diesel Generator Building
2-2403-051-2"	Diesel Generator Building
2-2403-068-3"	Diesel Generator Building
2-2403-043-4"	Diesel Generator Building
2-2403-044-4"	DFOST Pumphouse
2-2403-044-4"	DFOST Pumphouse Footing (See note 1)
2-2403-066-3"	DFOST Pumphouse
2-2403-053-2"	DFOST Pumphouse
2-2403-069-2"	DFOST Pumphouse
2-2403-069-2"	DFOST Pumphouse Footing (See note 1)
2-2403-051-2"	DFOST Pumphouse
2-2403-068-3"	DFOST Pumphouse
2-2403-043-4"	DFOST Pumphouse

Notes: 1. This interface is at the DFOST Pumphouse Footing and has soil adjacent to the footing both inside and outside of the structure.

Project VOGTLE	Prepared By R. FLOWERS	Date 9-9-92
Subject/Title SETTLEMENT MONITORING PROGRAM	Reviewed By J. Chaffin	Date 9/10/92
DIFFERENTIAL SETTLEMENT OF BURIED PIPE	Calculation Number YZCA30.1.6	Sheet 16 of 77

SHEET 2 FOLLOWS

PURPOSE OF CALCULATION (CONT.)

THIS CALCULATION ALSO DOCUMENTS THE INFORMATION LISTED IN THE TABLES ISSUED IN LETTERS SG-11455, DATED JULY 29, 1992, AND SG-11622, DATED SEPTEMBER 3, 1992.

APPENDIX A PROVIDES SUMMARY SHEETS OF EACH PIPE LINE LISTED SHOWING THE ASSOCIATED STRESS CALCULATION, THE INFORMATION EXTRACTED FROM THE STRESS CALC. USED IN DETERMINING THE MAXIMUM PERMISSIBLE ALLOWABLE DIFFERENTIAL SETTLEMENT, EFFECTED SUPPORTS, ETC.

APPENDIX B SUMMARIZES THE INFORMATION EXTRACTED FROM THE ASSOCIATED PIPE SUPPORT CALCULATIONS IN DETERMINING THE MAXIMUM PERMISSIBLE ALLOWABLE DIFFERENTIAL SETTLEMENT WITH RESPECT TO THE SUPPORTS.

Project	Vogtle Electric Generating Plant	Prepared By R. FLOWERS	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By ↓ (S.N. AMIN)	Date 6-17-92
Differential Settlement of Buried Pipe		Calculation Number X2CA30.1.6	Sheet 2 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-1202-029-6

Isometric 1K5-1202-029-06 Latest Revision 11

Nearest Support V1-1202-029-H007 Latest Support Revision 2

Interfacing Structure IT2B TUNNEL

Nearest Settlement Marker 196

INSTALLATION DATES

The following information was obtained from the Quantity Tracking System (QTS) Pipe Log Listing, Support Status Report, Weld Log Listing, etc. (see Attachment 1).

Pipe Installation Date:

Revision of Isometric at Installation Date —

Spool Piece ID 029-S-28 Installation Date 12-23-84

Weld ID 029-W-26 Installation Date 12-23-84

Support Installation Date:

Revision of Support drawing on Installation Date 1

Support Installation Date 1-13-85

Comments:

Project	Vogtle Electric Generating Plant	Prepared By R. Flowers	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By B. N. Amin	Date 6-17-92
Differential Settlement of Buried Pipe		Calculation Number XZCA30.1.6	Sheet 3 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTUREPipe Line No. 1-1202-029-6Interfacing Structure IT2B TUNNELNearest Settlement Marker 196SETTLEMENT OF STRUCTURE AT INSTALLATION DATE

This information is taken from the settlement surveying data (see Attachment 2) and a straight line interpolation was used to calculate the settlement on the installation date.

Pipe

Date 9-27-84 Settlement 0.022 Ft.Date 1-10-85 Settlement 0.020 Ft.Date 12-23-84 Settlement 0.020 Ft. ← Installation Date

Support

Date 1-10-85 Settlement 0.020 Ft.Date 4-16-85 Settlement 0.024 Ft.Date 1-13-85 Settlement 0.020 Ft. ← Installation DateTOTAL SETTLEMENT OF STRUCTURE AT MARKER

This information is taken from the settlement surveying data (see Attachment 2).

Date 5-10-89 Settlement 0.051 Ft.DIFFERENTIAL SETTLEMENT INDUCED IN PIPE AND SUPPORT

(Current Total Settlement) - (Settlement on Installation Date)

Pipe 0.031 Ft. = 0.37 inchesSupport 0.031 Ft. = 0.37 inches

Project	Vogtle Electric Generating Plant	Prepared By R. Flowers	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By 1- B.N. Amin	Date 6-17-92
Differential Settlement of Buried Pipe		Calculation Number X2CA30.1.6	Sheet 4 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-044-4"
Isometric 1K5-2403-044-02 Latest Revision 15
Nearest Support N/A Latest Support Revision N/A
Interfacing Structure DIESEL GENERATOR BUILDING
Nearest Settlement Marker 132-R

INSTALLATION DATES

The following information was obtained from the Quantity Tracking System (QTS) Pipe Log Listing, Support Status Report, Weld Log Listing, etc. (see Attachment 1).

Pipe Installation Date:

Revision of Isometric at Installation Date —
Spool Piece ID 044-S-06 Installation Date 1-22-84
Weld ID 044-W-06D Installation Date 3-11-84

Support Installation Date:

Revision of Support drawing on Installation Date N/A
Support Installation Date N/A

Comments:

PIPE IS EMBEDDED IN BUILDING SLAB. NO DIFFERENTIAL
SETTLEMENT INDUCED IN SUPPORT.
USE WELD INSTALLATION DATE FOR PIPE.

Project	Vogtle Electric Generating Plant	Prepared By R. FLOWERS	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. (S.N. AHIN)	Date 6-17-92
Differential Settlement of Buried Pipe		Calculation Number Y2CA30-1.6	Sheet 5 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-044-4"
 Interfacing Structure DIESEL GENERATOR BUILDING
 Nearest Settlement Marker 132-R

SETTLEMENT OF STRUCTURE AT INSTALLATION DATE

This information is taken from the settlement surveying data (see Attachment 2) and a straight line interpolation was used to calculate the settlement on the installation date.

Pipe

Date N/A Settlement N/A Ft.
 Date 4-26-84 Settlement 0.0 Ft.
 Date 3-11-84 Settlement 0.0 Ft. ← Installation Date

Support

Date N/A Settlement N/A Ft.
 Date N/A Settlement N/A Ft.
 Date N/A Settlement N/A Ft. ← Installation Date

TOTAL SETTLEMENT OF STRUCTURE AT MARKER

This information is taken from the settlement surveying data (see Attachment 2).

Date 5-2-89 Settlement 0.045 Ft.

DIFFERENTIAL SETTLEMENT INDUCED IN PIPE AND SUPPORT

(Current Total Settlement) - (Settlement on Installation Date)

Pipe 0.045 Ft. = 0.54 inches
 Support N/A Ft. = N/A inches

Project	Vogtle Electric Generating Plant	Prepared By R. FLOWERS	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. N. AMIN	Date 6-17-92
Differential Settlement of Buried Pipe		Calculation Number X2CA30.1.6	Sheet 8 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-043-4"
Isometric 1K5-2403-043-02 Latest Revision 12
Nearest Support N/A Latest Support Revision N/A
Interfacing Structure DIESEL GENERATOR BUILDING
Nearest Settlement Marker 132-R

INSTALLATION DATES

The following information was obtained from the Quantity Tracking System (QTS) Pipe Log Listing, Support Status Report, Weld Log Listing, etc. (see Attachment 1).

Pipe Installation Date:

Revision of Isometric at Installation Date —
Spool Piece ID 043-S-07 Installation Date 3-11-84
Weld ID 043-W-07 Installation Date 1-27-85

Support Installation Date:

Revision of Support drawing on Installation Date N/A
Support Installation Date N/A

Comments:

PIPE IS EMBEDDED IN BUILDING SLAB. NO DIFFERENTIAL
SETTLEMENT INDUCED IN SUPPORT.
USE WELD INSTALLATION DATE FOR PIPE.

Project	Vogtle Electric Generating Plant	Prepared By P. FLOWERS	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. N. AMIN	Date 6-17-92
	Differential Settlement of Buried Pipe	Calculation Number X2CA30.1.6	Sheet 9 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-043-4

Interfacing Structure DIESEL GENERATOR BUILDING

Nearest Settlement Marker 132-R

SETTLEMENT OF STRUCTURE AT INSTALLATION DATE

This information is taken from the settlement surveying data (see Attachment 2) and a straight line interpolation was used to calculate the settlement on the installation date.

Pipe

Date 1-2-85 Settlement 0.019 Ft.

Date 4-25-85 Settlement 0.025 Ft.

Date 1-27-85 Settlement 0.020 Ft. ← Installation Date

Support

Date N/A Settlement N/A Ft.

Date N/A Settlement N/A Ft.

Date N/A Settlement N/A Ft. ← Installation Date

TOTAL SETTLEMENT OF STRUCTURE AT MARKER

This information is taken from the settlement surveying data (see Attachment 2).

Date 5-2-89 Settlement 0.045 Ft.

DIFFERENTIAL SETTLEMENT INDUCED IN PIPE AND SUPPORT

(Current Total Settlement) - (Settlement on Installation Date)

Pipe 0.025 Ft. = 0.30 inches

Support N/A Ft. = N/A inches

Project	Vogtle Electric Generating Plant	Prepared By R. FLOWERS	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. N. AMIN	Date 6-17-92
Differential Settlement of Buried Pipe		Calculation Number X2CA30.1.6	Sheet 10 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-066-3"

Isometric 125-2403-058-01 Latest Revision 10

Nearest Support V1-2403-066-4001 Latest Support Revision 2

Interfacing Structure DIESEL FUEL OIL STORAGE TANK

Nearest Settlement Marker 145-R *

INSTALLATION DATES

The following information was obtained from the Quantity Tracking System (QTS) Pipe Log Listing, Support Status Report, Weld Log Listing, etc. (see Attachment 1).

Pipe Installation Date:

Revision of Isometric at Installation Date —

Spool Piece ID 066-S-15 Installation Date 5-27-84

Weld ID 066-W-02 Installation Date 11-11-84

Support Installation Date:

Revision of Support drawing on Installation Date 1

Support Installation Date 2-3-85

Comments:

USE WELD INSTALLATION DATE FOR PIPE

* NEAREST MARKER IS 1000-R ; HOWEVER , THIS MARKER WAS INSTALLED AFTER SOME SETTLEMENT OF THE STRUCTURE HAD OCCURRED. USING DATA FROM MARKER 145-R WILL RESULT IN MORE ACCURATE RESULTS.

Project	Vogtle Electric Generating Plant	Prepared By R. FLOWERS	Date 6-15-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. N. AMIN	Date 6-17-92
Differential Settlement of Buried Pipe		Calculation Number X2CA30.1.6	Sheet 11 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-066-3"
 Interfacing Structure DIESEL FUEL OIL STORAGE TANK
 Nearest Settlement Marker 145-R

SETTLEMENT OF STRUCTURE AT INSTALLATION DATE

This information is taken from the settlement surveying data (see Attachment 2) and a straight line interpolation was used to calculate the settlement on the installation date.

Pipe

Date 4-28-84 Settlement 0.0 Ft.
 Date 12-18-84 Settlement 0.012 Ft.
 Date 11-11-84 Settlement 0.010 Ft. ← Installation Date

Support

Date 12-18-84 Settlement 0.012 Ft.
 Date 3-7-85 Settlement 0.014 Ft.
 Date 2-3-85 Settlement 0.013 Ft. ← Installation Date

TOTAL SETTLEMENT OF STRUCTURE AT MARKER

This information is taken from the settlement surveying data (see Attachment 2).

Date 5-1-89 Settlement 0.041 Ft.

DIFFERENTIAL SETTLEMENT INDUCED IN PIPE AND SUPPORT

(Current Total Settlement) - (Settlement on Installation Date)

Pipe 0.031 Ft. = 0.37 inches
 Support 0.028 Ft. = 0.34 inches

Project	Vogtle Electric Generating Plant	Prepared By R. Flowers	Date 5-26-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. Chaffin	Date 7/9/92
	Differential Settlement of Buried Pipe	Calculation Number X2CA30.1.6	Sheet 46 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-043-4"
Isometric 1K5-2403-043-01 Latest Revision 10
Nearest Support VI-2403-043-H002 Latest Support Revision 3
Interfacing Structure DIESEL FUEL OIL STORAGE TANK
Nearest Settlement Marker 145-R

INSTALLATION DATES

The following information was obtained from the Quantity Tracking System (QTS) Pipe Log Listing, Support Status Report, Weld Log Listing, etc. (see Attachment 1).

Pipe Installation Date:

Revision of Isometric at Installation Date —
Spool Piece ID 043-S-01 Installation Date 10-21-84
Weld ID 043-W-02 Installation Date 10-14-84

Support Installation Date:

Revision of Support drawing on Installation Date 0
Support Installation Date 12-16-84

Comments:

USE SPOOL PIECE INSTALLATION DATE FOR PIPE.

Project	Vogtle Electric Generating Plant	Prepared By <u>R. Flowers</u>	Date <u>6.26.92</u>
Subject/Title	Settlement Monitoring Program	Reviewed By <u>J. Chaffin</u>	Date <u>7/9/92</u>
	Differential Settlement of Buried Pipe	Calculation Number <u>X2CA30.1.6</u>	Sheet <u>47</u> of <u>77</u>

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 1-2403-043-4"
 Interfacing Structure DIESEL FUEL OIL STORAGE TANK
 Nearest Settlement Marker 145-R

SETTLEMENT OF STRUCTURE AT INSTALLATION DATE

This information is taken from the settlement surveying data (see Attachment 2) and a straight line interpolation was used to calculate the settlement on the installation date.

Pipe

Date 4-28-84 Settlement 0.0 Ft.
 Date 12-18-84 Settlement 0.012 Ft.
 Date 10-21-84 Settlement 0.009 Ft. ← Installation Date

Support

Date 4-28-84 Settlement 0.0 Ft.
 Date 12-18-84 Settlement 0.012 Ft.
 Date 12-16-84 Settlement 0.012 Ft. ← Installation Date

TOTAL SETTLEMENT OF STRUCTURE AT MARKER

This information is taken from the settlement surveying data (see Attachment 2).

Date 5-1-89 Settlement 0.041 Ft.

DIFFERENTIAL SETTLEMENT INDUCED IN PIPE AND SUPPORT

(Current Total Settlement) - (Settlement on Installation Date)

Pipe 0.032 Ft. = 0.38 inches
 Support 0.029 Ft. = 0.35 inches

Project	Vogtle Electric Generating Plant	Prepared By R. FLOWERS	Date 5-27-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. Chaffin	Date 7/9/92
	Differential Settlement of Buried Pipe	Calculation Number XZCA30.1.6	Sheet 50 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 2-1202-030-6"
Isometric 2K5-1202-030-03 Latest Revision 6
Nearest Support VZ-1202-030-H022 Latest Support Revision 2
Interfacing Structure NSCW VALVEHOUSE TRAIN A
Nearest Settlement Marker 260-R

INSTALLATION DATES

The following information was obtained from the Quantity Tracking System (QTS) Pipe Log Listing, Support Status Report, Weld Log Listing, etc. (see Attachment 1).

Pipe Installation Date:

Revision of Isometric at Installation Date —
Spool Piece ID 030-S-25 Installation Date 9-7-86
Weld ID 030-W-28A Installation Date 10-16-86

Support Installation Date:

Revision of Support drawing on Installation Date 1
Support Installation Date 2-1-87

Comments:

USE WELD INSTALLATION DATE FOR PIPE

Project	Vogtle Electric Generating Plant	Prepared By R. Flowers	Date 6-26-92
Subject/Title	Settlement Monitoring Program	Reviewed By J. Chaffin	Date 7/9/92
	Differential Settlement of Buried Pipe	Calculation Number XZCA 30.1.6	Sheet 51 of 77

DIFFERENTIAL SETTLEMENT BETWEEN BURIED PIPING AND STRUCTURE

Pipe Line No. 2-1202-030-6"
 Interfacing Structure NSCW VALVEHOUSE TRAIN A
 Nearest Settlement Marker 260-R

SETTLEMENT OF STRUCTURE AT INSTALLATION DATE

This information is taken from the settlement surveying data (see Attachment 2) and a straight line interpolation was used to calculate the settlement on the installation date.

Pipe

Date 8-28-86 Settlement 0.021 Ft.
 Date 10-31-86 Settlement 0.023 Ft.
 Date 10-16-86 Settlement 0.023 Ft. ← Installation Date

Support

Date 1-5-87 Settlement 0.032 Ft.
 Date 4-7-87 Settlement 0.037 Ft.
 Date 2-1-87 Settlement 0.033 Ft. ← Installation Date

TOTAL SETTLEMENT OF STRUCTURE AT MARKER

This information is taken from the settlement surveying data (see Attachment 2).

Date 6-15-89 Settlement 0.052 Ft.

DIFFERENTIAL SETTLEMENT INDUCED IN PIPE AND SUPPORT

(Current Total Settlement) - (Settlement on Installation Date)

Pipe 0.029 Ft. = 0.35 inches
 Support 0.019 Ft. = 0.23 inches

ENCLOSURE 3a

**Stress / Support Analysis
Line 1-1202-029-6"**

ME101

INPUT CARD IMAGES

```

INPUT CARD
SEQ 1 11 21 31 41 51 61 71 80
+ + + + + + + +
1 *** NSCW BUILDING ( FILE NAME=NEWBS)
2 *** FROM NSCW TRANSFER PUMP A LOCATED IN TOWER B TO DISCH IN TOWER A
3 *** LINE NO 1202-029-6" ISOMETRIC 1K5-1202-029-06
4 *** AND 1K5-1202-029-07
5 *** SIMILAR LINE
6 *** LINE NO 1202-030-6" ISOMETRIC 1K5-1202-030-05
7 *** AND 1K5-1202-030-06
8 ***
9 *** 1. THIS MODEL REFLECTS USING NEW BUILDING SETTLEMENT VALUE AT THE
10 *** INTERFACE OF TUNNEL/SOIL PENETRATION.
11 *** NEW BUILDING SETTLEMENT DISPLACEMENT CONSIDER AT N.P 150=-0.5"
12 ***
13 HED
14
15
16
17
18
19
20 ***RUN
21 ***RUN
22 RUN
23 ***RUN
24 ***RUN
25 ***RUN
26 *** ISO. 1K5-1202-029-06
27 SAP 1400.00 211-9.313 0.00
28 ***
29 *** D.P. 140 IS A VIRTUAL ANCHOR
30 ***
31 ANC 140
32 ANC 140
33 ANC 140 0.00
34
35
36
37
38
39
40
41
42
43 *** BURIED PIPING/TUNLS BULDG. SETTLEMENT &
44
45
46 145 7-2-1/2 L
47 150-3-11-1/4
48 RAD 150 1
49
50 RAD 150 1
51 153-11-5-15/16 L
52 155 2-3
53 RAD 1551
54 RAD 155 1

```

```

TIT=NSCW TRANSFER LINES,
PROJNO=17553800,
UNITS=2,EDIT=0,
PROBNO=1K5120202906,
USER=V.R.PATEL,
MODES=40,PERIOD=.028,
EIGEN=1,SYNTH=4,
LDCASE=WT1 (A),
LDCASE=THRM1 (T),
LDCASE=THRMBS (S),
LDCASE=SAMSS (A),
LDCASE=SEISOB (A),
LDCASE=SEISSS (A),

```

REV 

1K5-1202-029-06
CALC. NO. _____ SHT. 6A OF 15

AUTHOR V.R. Patel DATE 1/13/92

CHECKER JS DATE 3-13-92

*A TAG NOT USED - CARD IGNORED
*T TAG NOT USED - CARD IGNORED
*S THRMBS

*S THRMBS
*T TAG NOT USED - CARD IGNORED

*A TAG NOT USED - CARD IGNORED
*A TAG NOT USED - CARD IGNORED

*S THRMBS

*5

• *S.*

*S

*S

•

*2

* 2

*5

*§

•

★

2

★

Rev. $\triangle 5$

1K5-1102-019-019
CALC. NO. _____ SHT. 6B OF 15
AUTHOR VR Patel DATE 3-13-92
CHECKER JS DATE 3/13-92

TAG NOT USED - CARD IGNORED
TAG NOT USED - CARD IGNORED
THRMBS

```

115 . EQA
116 . ACE
117 . ACE
118 . ACE
119 . ***
120 . ACE
121 . .01, .39, .03, .39, .045, .48, .05, .64, .064, .64, .27, 1.78, 5.0, 1.78,
122 . ***
123 . ACE
124 . .01, .27, .03, .27, .043, .34, .14, 1.16, 5.0, 1.16,
125 . EQA
126 . ***
127 . ***CMB
128 . ***CMB
129 . ***CMB
130 . ***CMB
131 . ***CMB
132 . ***CMB
133 . ***CMB
134 . ***
135 . ***CMB
136 . ***CMB
137 . ***CMB
138 . ***
139 . ***CMB
140 . ***CMB
141 . ***CMB
142 . ***CMB
143 . ***CMB
144 . ***STD
145 . ***RLS
146 . ***
147 . ***SLA
148 . ***OLA
149 . ***OLA
150 . ***OLA
151 . ***TEA
152 . END

```

X2CR5-13 SSE HOR ACCEL DAMP=2%
 X2CR5-14 SSE VER AACCEL DAMP=2%
 LOAD COMBINATIONS PER DC-1017 REV. 4

TITLE=CAT I TUNNEL SSE,
 LDNAME=SEISSS,
 TYPE=1, COEF=CS4,
 DIRXON=X+Z,
 DIRXON=Y,
 ZERO=0*WT1,
 SAMOB=0.70*SAMSS,
 THRMPO=THRM1&ZERO,
 THRMNE=THRM1#ZERO,
 NEWWT=0.75*WT1,
 SEISMX=SEISSS&SEISOB,
 SEITHM=SEISMX+THRMPO+SAMSS+
 ABS (THRMBS),
 SETHWT=SEITHM+WT1,
 SETHIW=SEITHM+NEWWT,
 THRMSE=THRMNE-SEISMX-SAMSS-
 ABS (THRMBS),
 THWTSE=WT1+THRMSE,
 LOADPO=SEISMX&SETHWT&SETHIW,
 MAXLOD=1.15*LOADPO,
 LOADNE=THRMSE#THWTSE,
 MINLOD=1.15*LOADNE,
 LIST=NONE,
 LIST=WT1+THRM1+THRMBS+SAMSS
 SEISOB+SEISSS+MAXLOD+MINLOD
 INCLUD=WT1,
 INCLUD=WT1+SEISOB, LEVEL=B,
 INCLUD=WT1+SEISOB, LEVEL=C,
 INCLUD=WT1+SEISSS, LEVEL=D,
 INCLUD=THRM1+SAMOB,

REL 5

K5-1202-029-06
 CALC. NO. _____ SHT. 100 OF 15
 AUTHOR V.R. Patel DATE 3-13-92
 CHECKER JS DATE 3-13-92

152 CARDS IN INPUT DECK
 145 CARDS IN LOAD CASE THRMBS

0 WARNINGS
 0 ERRORS
 0 FATAL ERRORS


ME101DK	VERSION M8	STOP ON 03/12/92 AT 12:20:34,	CPU=	3.44,	BIO=	110,	DIO=	101,	PGF=	1103
ME101DK	VERSION M8	EXECUTION TIMES	CPU=	1.89,	BIO=	16,	DIO=	43,	PGF=	340
FORTRAN STOP										
ME101I	VERSION M8	START ON 03/12/92 AT 12:20:35,	CPU=	4.16,	BIO=	134,	DIO=	115,	PGF=	1278

Project	125TLE NUCLEAR PLANT, UNIT-1	Prepared By	L R Porel	Date	3-16-92
Subject/Title	PIPE STRESS EVALUATION	Reviewed By	<i>James Smith</i>	Date	3-23-92
		Calculation Number	K5-1202-029-06	Sheet	5A of 5

PURPOSE:- TO EVALUATE THE PIPING INTEGRITY PER BUILDING SETTLEMENT MONITORING PROGRAM (CONSIDER $\pm .5"$ DIFFERENTIAL BUILDING SETTLEMENT AT TUNNEL/SOIL)

REFERENCE:- 1. DG1017 REV G.
 2. ME101 RUN & CL2031, DATED 03/12/92.
 (THIS MODEL ENVELOPES AND SUPERSEDES THE 3 CASES IDENTIFIED ON SHT 4A FOR BUILDING SETTLEMENT CASES)

EVALUATION:-



DIFFERENTIAL BUILDING SETTLEMENT DISPLACEMENT

- 1) TUNNEL (IT2B) / SOIL PENETRATION (BURIED) $\approx .5"$
- 2) TUNNEL (IT2B) / TUNNEL (IT2B) $\approx -0.3"$
- 3) TUNNEL (IT2B) / VALVE HOUSE $\approx -0.5"$

Project VOGTLE NUCLEAR PLANT, UNIT-1	Prepared By I R Patel	Date 3-16-92
Subject/Title PIPE STRESS EVALUATION	Reviewed By <i>[Signature]</i>	Date 3-23-92
	Calculation Number 105-202-029-06/5	Sheet 78 of 15

AS A CONSERVATIVE CASE (WORST CASE) BUILDING SETTLEMENT DISPLACEMENTS ARE CONSIDER AT N.P 150 = $-.5''$ AND AT N.P 225 = $-.5''$

$$\text{MAX PIPE STRESS} = 14510 \text{ PSI} < 3S_c = 3 \times 15700 = 47100 \text{ PSI}$$

$$\therefore \text{INTERACTION} = 14510/47100 \approx .31$$

CONCLUSION: THE ANALYSIS HAS BEEN REVIEWED AT REVISED DIFFERENTIAL BUILDING SETTLEMENT CONDITION AND FOUND SATISFACTORY FOR $.5''$ INLIEU OF $.3''$ AT TUNNEL / SOIL INTERFACE.

Note: DC-1017 Rev. 6 is currently involved in the DMCN change to reflect new differential settlement value of $.5''$ for line # 1-1202-029-6 at the tunnel / soil interface.

Project LOGTLE NUCLEAR PLANT UNIT-1	Prepared By V.R. Patel	Date 6/19/92
Subject/Title BUILDING SETTLEMENT	Reviewed By <i>[Signature]</i>	Date 06/19/92
MONITORING PROGRAM	Calculation Number X4CPS-0167	Sheet 04 of 10

PURPOSE:- TO CALCULATE A RESERVE LOAD CAPACITY AND MAXIMUM PERMISSIBLE ALLOWABLE DIFFERENTIAL SETTLEMENT OF FOLLOWING PIPE SUPPORT

- 1) VI-2403-066-4001, ISO-1K5-2403-058-01
- 2) VI-1202-029-4007, ISO-1K5-1202-029-06

- REFERENCE:-
- 1) PIPE STRESS CALC & 1K5-2403-058-01 2/3
 - 2) PIPE SUPPORT CALC & VI-2403-066-4001 R/S (INCLUDING PIPESAN)
 - 3) PIPE STRESS CALC & X4CP-7162
 - 4) CCN & 1 OF S/R VI-1202-029-4007
 - 5) CCN & 1 OF X4CP-R1512
 - 6) PIPE RACK CALC & R1512

EVALUATION:- 1) VI-2403-066-4001
 MAX. CRITICAL WELD I R
 $= .91$ AT N/4 LOADS / N/4 ALLOWABLE FROM SRT 1A OF 8 REF.
 AND $= .93$ AT FAULTED LOAD / FAULTED ALLOWABLE

DESIGN LOAD CONSIDERED IN SUPPORT EVALUATION
 $= +1381^k$ FAULTED (REF-2)
 $= 1051^k$ UPSET

∴ MAX PERMISSIBLE SUPPORT LOAD
 FAULTED $= 1(I R) 1381 / .93(I R) = 1485^k$
 UPSET $= 1(I R) (1051) / .91(I R) = 1155^k$

∴ RESERVE LOAD CAPACITY, FAULTED $= 1485 - 1381 = 104^k$ SAY 90
 UPSET $= 1155 - 1051 = 104^k$ SAY 90

AND MAX PERSSIBLE BUILDING SETTLEMENT LOAD
 $=$ EXIST BUILD. SETTLE. LOAD + RESERVE LOAD

Project	VOGTLE NUCLEAR PLANT, UNIT-1	Prepared By	J R Patel	Date	6/19/92
Subject/Title	BUILDING SETTLEMENT MONITORING	Reviewed By	Yof Jini	Date	06/19/92
PROGRAM		Calculation Number	XCCPS-5167	Sheet	03 of 10

$$\begin{aligned}
 & \text{--- SHT. 14 OF 15, REF. 1 AT .5" DEFF. BUILDING SETTLEMENT} \\
 & = 566^{\#} + 90^{\#} \\
 & = 656^{\#}
 \end{aligned}$$

$\therefore$ MAX. PERMISSIBLE ALLOWABLE DIFFERENTIAL SETTLEMENT

$$= \frac{656}{566} \times .5 \approx \boxed{.59''}$$

SUMMARY:- RESERVE LOAD CAPACITY = $\boxed{90^{\#}}$
 $\frac{1}{2}$ MAX PERMISSIBLE DIFFERENTIAL SETTLEMENT = $\boxed{0.58''}$

(2) VI-1202-029-H007

MAX. I.R. OF 'T1' PLATE (V_y) = $5058/6000 = .84$ @ JOINT 10
 (REF 5, SHT 6 OF 6)

AND MAX. I.R. OF Moment (M_x) OF 'T1' PLATE = $\frac{74460}{84000} \approx .89$

(REF 5, SHT 6 OF 6)

$\therefore$ PERMISSIBLE ADDITIONAL MOMENT = $84000 - 74460 = 9540^{\#}$ INCH

$$\therefore V_{y\max} = (9540)(.84^2) / (.66^2)(18) = 858^{\#} \text{ FOR LOAD FACTOR} = 1.0$$

$\therefore$ RESERVE LOAD CAPACITY = $858^{\#}$, SAY $450^{\#}$

AND MAX. PERMISSIBLE BUILDING SETTLEMENT LOAD

= EXIST BS LOAD + RESERVE LOAD

$$\begin{aligned}
 & \text{--- SHT 14 OF 15, REF 3 AT .5" DEFF. BUILDING SETTLEMENT} \\
 & = 2184^{\#} + 450^{\#} = 2634^{\#}
 \end{aligned}$$

$\therefore$ MAX. PERMISSIBLE ALLOWABLE DIFF. SETTLEMENT

$$= \left(\frac{2634}{2184} \right) (.5) \approx .60''$$

SUMMARY:- RESERVE LOAD CAPACITY = $\boxed{450^{\#}}$; $\frac{1}{2}$ MAX. PERMISSIBLE DIFF. SETTLEMENT = $\boxed{.60''}$

FORM 25, DS

Line No.	Stress Calculation No.	Bldg. Loc.	Exist. Sett. (DC-1017)	Issued Calc. Rev
1-1202-029-6"	1K5-1202-029-06 (Rev. 4)	TUNNEL	Δ ES .3	5

Sact	Sallow	Δ MPAp	Prop. Sett. (DC-1017) Δ PS	By	Chk	Comments
10575	47100	1.34	.50	<i>Y. J. [Signature]</i>	JS	08/05/92 8-6-92

Parameters:

- Δ ES = The Design Criteria differential settlement used in the analysis per DC-1017 Rev. 6
- Sact = The actual pipe stress resulting from Δ ES
- Sallow = The ASME Code allowable stress
- Δ MPAp = The maximum permissible allowable differential settlement value where: Δ MPAp = (Sallow / Sact) x (Δ ES)
- Δ PS = The propo - settlement value for DMCN to the current DC-1017

Effectuated Pipe Supports

V1-1202-029-H006
V1-1202-029-H007

PSDL

See Attached
See Attached

TITLE : NSCW TRANSFER LINES
PROJECT NUMBER : 9510-001
PROBLEM NUMBER : NACP-2112
USER : EYG
LOAD CASE : ASDL REV. 4

CALC NO: NACP 7162 SHEET 18 OF 15
ORIGINATOR : EYG DATE 2-8-86
CHECKER : [Signature] DATE 2-2-86
ISO NO : 1K5-1202-029-06

CALC. REV. 5 BY: V.R Patel 3-15-92
CKD: JS 3-23-92

REV. 3

60001
(type 353)

DATA TYPE LOAD TITLE FX FY FZ GLOBAL FORCES (LBS) GLOBAL MOMENTS (FT-LBS) DISPLACEMENT (IN)

140 ANC

VIRTUAL ANCHOR

WT	THRM1	THRM2	SAMSS	SEISSR	SEISSS	MAXLOD	MINLOD	FX	FY	FZ	GLOBAL FORCES (LBS)	GLOBAL MOMENTS (FT-LBS)	DISPLACEMENT (IN)
1	140	-140	-3	-143	147	1	3577	0	0	0	-36	0	0
10	10	-80	-7	5146.2	293.2	54	3162	0	0	0	0	0	0
66	66	283	13.5	293.2	166	166	221	0	0	0	0	0	0
46	46	27	77	170	8072	8072	1739	0	0	0	0	0	0
81	81	1289	1675	9107	-8934	-8934	-1011	0	0	0	0	0	0
1349	1349	-875	-1571	-1845	-3953	-3953	-1011	0	0	0	0	0	0

150 RAD

VI-1202-029-M009

SEE NOTE BELOW

WT	THRM1	THRM2	SAMSS	SEISSR	SEISSS	MAXLOD	MINLOD	FX	FY	FZ	GLOBAL FORCES (LBS)	GLOBAL MOMENTS (FT-LBS)	DISPLACEMENT (IN)
1	1	-425	-445	0	0	0	0	0	0	0	0	0	0
10	10	1020	184	0	0	0	0	0	0	0	0	0	0
66	66	477	0	0	0	0	0	0	0	0	0	0	0
46	46	77	0	0	0	0	0	0	0	0	0	0	0
81	81	115	120	0	0	0	0	0	0	0	0	0	0
1349	1349	2450	1420	0	0	0	0	0	0	0	0	0	0
1349	1349	-1042	-2319	0	0	0	0	0	0	0	0	0	0

150 RAD

WT	THRM1	THRM2	SAMSS	SEISSR	SEISSS	MAXLOD	MINLOD	FX	FY	FZ	GLOBAL FORCES (LBS)	GLOBAL MOMENTS (FT-LBS)	DISPLACEMENT (IN)
1	1	0	0	0	0	0	0	0	0	0	0	0	0
10	10	0	0	0	0	0	0	0	0	0	0	0	0
66	66	0	0	0	0	0	0	0	0	0	0	0	0
46	46	0	0	0	0	0	0	0	0	0	0	0	0
81	81	0	0	0	0	0	0	0	0	0	0	0	0
1349	1349	0	0	0	0	0	0	0	0	0	0	0	0
1349	1349	0	0	0	0	0	0	0	0	0	0	0	0

155 RAD

WT	THRM1	THRM2	SAMSS	SEISSR	SEISSS	MAXLOD	MINLOD	FX	FY	FZ	GLOBAL FORCES (LBS)	GLOBAL MOMENTS (FT-LBS)	DISPLACEMENT (IN)
1	1	0	0	0	0	0	0	0	0	0	0	0	0
10	10	0	0	0	0	0	0	0	0	0	0	0	0
66	66	0	0	0	0	0	0	0	0	0	0	0	0
46	46	0	0	0	0	0	0	0	0	0	0	0	0
81	81	0	0	0	0	0	0	0	0	0	0	0	0
1349	1349	0	0	0	0	0	0	0	0	0	0	0	0
1349	1349	0	0	0	0	0	0	0	0	0	0	0	0

* LOAD INCREASED (W/O 15% MARGIN)

WT & SEISMIC LOADS IN SHT 14 THRU 14B PER NF-426, 11-19-86, 14

7162
 SHEET 15 OF 15
 DATE 2-6-84
 DATE 3-5-84
 ISD No. JK5-1208-089-010

THE UNIVERSITY OF CHICAGO

DATE 02-28-86

PAGE 149

CALC. REV. 5 BY: V.R.Patel 3-13-92
SKD: JS 3-23-92

Rev. 3

CASE 2
(AF 331)

~~ASDL-REV 4~~

[illegible]

15% MAD

10/19/86 X 5 11-20-86

V1-1202-029-11004

MYI
 VMPI
 VMPI
 VMPI
 VMPI

SELSOR 172 306
SELSOR 172 306
MARLO 172 306
MARLO 172 306

NOTE:- SEE NOTE-1 ON SAT 14 OF 15

* LOAD INCREASED (W/O 15% INCREASE)

CUT 14A CONTAMINATED CUT 14B

ENCLOSURE 3b

**Stress / Support Analysis
Line 2-1202-030-6"**

ME101

INPUT CARD IMAGES

INPUT CARD SEQ	1	11	21	31	41	51	61	71	80	LOAD CASE(S)
1	+	+	+	+	+	+	+	+	+	
2	***	FILE NAME=EF01730.INP								
3	***	CREATED FROM WESTDYNE CK.PKG FILE ANILOHA DATED 8-19-87								
4	***	(PARTIAL PIPING)								
5	***	ISO:-2K5-1202-030-03								
6	***									
7	***									
8	CTL									
9	HED									
10		MTABLE=B,								
11		TITLE=NSCW SYSTEM(1202),								
12		PROJNO=17553800,								
13		PROBNO=EF01730,								
14		USER=V.R.PATEL,								
15		UNIT=2,								
16		MODES=30, PERIOD=.03, EIGEN=1,								
17	***	SYNTH=4,								
18	***	EDIT=0,								
19	***	WT1=DEAD WEIGHT								
20	***	THRM1=DESIN TEMP=150								
21	***	THRM2=MIN. ENV. TEMP=40								
22	***	THRMBS=BUILDING SETTLEMENT								
23	***	SEISOB=OBE INERTIA								
24	***	SEISSS=SSS INERTIA								
25	***	SAMSS=SSSAM								
26	RUN	LDCase=WT1 (B),								
27	RUN	LDCase=THRM1 (A),								
28	RUN	LDCase=THRM2 (C),								
29	RUN	LDCase=THRMBS (D),								
30	RUN	LDCase=SAMSS (F),								
31	RUN	LDCase=SEISOB (B),								
32	***	LDCase=SEISSS (B),								
33	ANC	118	ISO:-2K5-1202-030-03							
34	ANC	118								
35	ANC	118								
36	ANC	118	-0.3							
37	***	SAM VALUES PER DC-1005 (NSCW VALVE HOUSE/SOIL)								
38	ANC	118	PHASE=BURIED, DX=.143,							
39			DY=.143, DZ=.143,							
40			OD=6.625, TH1=.280,							
41			LBS/FT=31.48,							
42			E=28.3K6,							
43			MAT=SA312-TP304L,							
44			TEMP=150,							
45			EXP=-0.31,							
46			TEMP=70,							
47			SC=15700, SH=15700,							
48			CODE=SC374, CLASS=2,							
49			DPRESS=100, PPRESS=100,							
50		199 2.1213	2.1213							
51		122 0.7071	0.7071	L						
52		123	1.521							
53		124	1.521							
54		125	1.521	L						

MTABLE=B,
TITLE=NSCW SYSTEM(1202),
PROJNO=17553800,
PROBNO=EF01730,
USER=V.R.PATEL,
UNIT=2,
MODES=30, PERIOD=.03, EIGEN=1,
SYNTH=4,
EDIT=0,

LDCase=WT1 (B),
LDCase=THRM1 (A),
LDCase=THRM2 (C),
LDCase=THRMBS (D),
LDCase=SAMSS (F),
LDCase=SEISOB (B),
LDCase=SEISSS (B),

*B WT1 SEISOB SEISSS
*A THRM1
*C THRM2
*D THRMBS
*F SAMSS
*F SAMSS
*A THRM1
*C THRM2
*D THRMBS

3
CALC. NO. EF-01-730 SHT. 60 OF 15

AUTHOR V.R. Patel DATE 7-10-92

CHECKER JS DATE 7-15-92

INPUT CARD IMAGES

ME101/MS GRC/GTP70

(2K4042) 07/02/92 2K4042 PAGE

2

55		126	-1.2705		1.2705				
56		127	-1.2705		1.2705			DTITLE=21202030H022,	
57		127		1.0				AA=1.0E6,	
58	RAD	127	-.7071		-.7071			AA=1.0E6,	
59	RAD	128	-2.4528		2.4528			SIF=1.9,	
60		129	-2.2871		2.2871				
61		131	-2.2871		2.2871		L		
62		132		2.0					
63		134		2.042			L		
64		135	0.86		0.7884			DTITLE=21202030H023,	
65	RAD	135		1.0				AA=1.0E6,	
66	RAD	135	-.6757		0.7372			AA=1.0E6,	
67		136	2.9896		2.7404				
68		137	2.9896		2.7404				
69		138	2.9396		2.7404			DTITLE=21202030H024,	
70	ANC	138						AA=1.0E6, AB=1.0E6, AC=1.0E6,	
71								ARA=1.0E8, ARB=1.0E8, ARC=1.0E8,	
72								COSAX= .7372, COSAZ= .6757,	
73								COSCX= -.6757, COSCZ= .7372,	
74		138139	0.6066		0.5561			SIF=1.9,	
75		141	0.3072		0.2816			DTITLE=PEN.N-FACE,	
76		142	1.4743		1.3515			DTITLE=PEN.S-FACE,	
77		143	2.7925		2.5598				
78		144	2.7925		2.5598				
79		147	2.7925		2.5598			DTITLE=21202030H025,	
80	RAD	147		1.0				AA=1.0E6,	
81	***							DISP= .5	*D THRMBS
82								PHASE=TOWER, DY= .4,	*F SAMSS
83								AA=1.0E6,	
84	RAD	147	-0.6757		0.7372			PHASE=TOWER, DX= .4, DZ= .4,	*F SAMSS
85									
86		148	1.8237		1.6717				
87		150	1.8237		1.6717		L		
88		151		-1.0				SIF=1.9,	
89		152		-.25				OD=12.5, THI=2.94, LBS/FT=0.0,	
90								ADDWT=60,	
91		154		-.25					
92	***							OD=6.625, THI= .28, LBS/FT=0.0,	
93		199200	1" O.D BRANCH LINE	-0.276				SIF=2.55,	
94								OD=1.315, THI= .133,	
95		201		-0.146				LBS/FT=3.36, SIF=2.1,	
96								SIF=2.1,	
97		202		-0.25				DTITLE=VALVE-XA04,	
98		203		-0.123				OD=1.97, THI= .27, LBS/FT=0.0,	
99								ADDWT=14,	
100		204		-0.4	0.4			SIF=2.1,	
101		203206		-0.333				OD=1.315, THI= .133,	
102		207		-0.594				LBS/FT=3.36, SIF=2.3,	
103								LDNAME=SEISOB,	
104	ACE							TITLE=OBE PVRC NSCW BLDG,	
105	ACE							TYPE=1, COEF=CS4,	
106	ACE							DIRXON=X+Z,	
107	ACE								
108			0.010, 0.251,	0.030, 0.253,	0.050, 0.465,				
109			0.069, 0.498,	0.070, 0.508,	0.071, 0.499,				
110			0.098, 0.766,	0.100, 0.745,	0.394, 0.744,				
111			0.399, 0.742,	0.411, 0.730,	0.507, 0.730,				
112			1.023, 0.438,	2.046, 0.280,	3.959, 0.103,				
113			4.991, 0.060,	5.000, 0.060,					
114	ACE							DIRXON=Y,	

3
 CALC. NO. EF-01-730 SHT. 6E OF 11
 AUTHOR VRP Date 7-10-92
 CHECKED JS 7-15-92

INPUT CARD IMAGES

ME101/M8 GRO/GTP70

(2K4042) 07/02/92 2K4042 PAGE

3

115 . 0.010,0.251, 0.030,0.251, 0.050,0.464,
 116 . 0.069,0.499, 0.070,0.514, 0.097,0.736,
 117 . 0.098,0.745, 0.100,0.714, 0.291,0.712,
 118 . 0.296,0.710, 0.799,0.321, 1.310,0.203,
 119 . 5.000,0.060,

120 . EQA
 121 . ACE
 122 . ACE
 123 . ACE
 124 . ACE

LDNAME=SEISSS,
 TITLE=SSE PVRC NSCW BLDG,
 TYPE=1,COEF=CS4,
 DIRXON=X+Z,

125 . 0.010,0.390, 0.030,0.390, 0.045,0.478,
 126 . 0.050,0.637, 0.064,0.551, 0.094,0.729,
 127 . 0.098,0.766, 0.099,0.755, 0.100,0.759,
 128 . 0.273,1.305, 0.483,1.301, 1.279,0.754,
 129 . 5.000,0.071,

130 . ACE

DIRXON=Y,

131 . 0.010,0.268, 0.030,0.263, 0.032,0.276,
 132 . 0.050,0.464, 0.052,0.469, 0.079,0.598,
 133 . 0.097,0.736, 0.098,0.745, 0.100,0.714,
 134 . 0.112,0.714, 0.155,0.835, 0.392,0.844,
 135 . 1.008,0.403, 1.122,0.375, 4.773,0.065,
 136 . 5.000,0.060,

137 . EQA

138 . CMB

139 . CMB

140 . CMB

141 . CMB

142 . CMB

143 . CMB

144 . CMB

145 . CMB

146 . CMB

147 . CMB

148 . CMB

149 . CMB

150 . CMB

151 . CMB

152 . CMB

153 . CMB

154 . CMB

155 . CMB

156 . CMB

157 . CMB

158 . CMB

159 . CMB

160 . STD

161 . RLS

162 .

163 .

164 .

165 . SLA

166 . OLA

167 . OLA

168 . OLA

169 . TEA

170 . END

ZERO=0*WT1,
 THRMPO=THRM1&THRM2&ZERO,
 THRMNE=THRM1#THRM2#ZERO,
 NEWWT=0.75*WT1,
 BS=ABS(THRMBS),
 SAMOB=0.70*SAMSS,
 N1=THRMPO+NEWWT+BS,
 N2=THRMNE+WT1-BS,
 NORMP=N1&ZERO,
 NORMN=N2#ZERO,
 U1=NEWWT+SEISOB+BS+SAMOB,
 U2=U1+THRMPO,
 U3=WT1-SEISOB-BS-SAMOB,
 U4=U3+THRMNE,
 UPSETP=U1&U2&ZERO,
 UPSETN=U3#U4#ZERO,
 F1=NEWWT+SEISSS+BS+SAMSS,
 F2=F1+THRMPO,
 F3=WT1-SEISSS-BS-SAMSS,
 F4=F3+THRMNE,
 FAULTP=F1&F2&ZERO,
 FAULTN=F3#F4#ZERO,
 LIST=NONE,
 LIST=WT1+THRM1+THRM2+BS
 +SAMOB+SAMSS+SEISOB+SEISSS
 +NORMP+NORMN+UPSETP
 +UPSETN+FAULTP+FAULTN,
 INCLUD=WT1,
 INCLUD=WT1+SEISOB,LEVEL=B,
 INCLUD=WT1+SEISOB,LEVEL=C,
 INCLUD=WT1+SEISSS,LEVEL=D,
 INCLUD=THRM1+THRM2+SAMOB,

3
 CALC. NO. EF-01-730 - SHT. 6F OF 15
 AUTHOR VR Fateh DATE 7-10-92
 CHECKER JS DATE 7-15-92

FORM 8, BS ***** (V2-1202-030-H022 to be deleted in future)

Line No.	Stress Calculation No.	Bldg. Loc.	Exist. Sett. (DC-1017) Δ ES	Issued Calc. Rev.
2-1202-030-6"	EF-01-730 (Rev. 2)	NSCW	.3	3 See Note

Sact	Sallow	Δ MPAp	Prop. Sett. (DC-1017) Δ PS	By	Chk	Comments
10975 See Note 1	47100	1.29	.30	VRP 7-15-92	JS 7-15-92	

NOTES: 1. Completely reanalyzed due to input error.
Sact = 10975 from reanalysis per calc. EF-01-730 Rev. 3.

Parameters:

Δ ES = The Design Criteria differential settlement used in the analysis per DC-1017 Rev. 6

Sact = The actual pipe stress resulting from Δ ES

Sallow = The ASME Code allowable stress

Δ MPAp = The maximum permissible allowable differential settlement value
where: Δ MPAp = (Sallow / Sact) x (Δ ES)

Δ PS = The propose settlement value for DMCN to the current DC-1017

Effected Pipe Supports

V2-1202-030-H022
V2-1202-030-H023

PSDL

See Attached
See Attached

RESTRAINT LOAD SUMMARY

3

ME101/M8 GRO/GTP70 (2K4042) 07/02/92 2K4042 PAGE 177

TITLE : NSCW SYSTEM(1202)
PROJECT NUMBER : 17553800
PROBLEM NUMBER : EP01730
USER : V.R.PATEL
LOAD CASE :

CALC. NO. EF-01-730 SHT. 14AN OF 15

AUTHOR VR Patel DATE 7-10-92

CHECKER _____ DATE _____

DATA TYPE PT	LOAD	TITLE	GLOBAL FORCES (LB)			GLOBAL MOMENTS (FT-LB)			DISPLACEMENT (IN)		
			FX	FY	FZ	MX	MY	MZ	DX	DY	DZ
118	ANC										
		WT1	-24.	-193.	4.	316.	-83.	-305.	0.000	0.000	0.000
		THRM1	217.	-382.	-319.	376.	1014.	-1249.	0.000	0.000	0.000
		THRM2	-75.	132.	110.	-129.	-349.	430.	0.000	0.000	0.000
		BS	67.	2409.	483.	6347.	796.	4781.	0.000	0.300	0.000
		SAMOB	228.	821.	325.	2142.	852.	1718.	0.100	0.100	0.100
		SAMSS	326.	1172.	464.	3059.	1217.	2455.	0.143	0.143	0.143
		SEISOB	99.	143.	154.	80.	604.	546.	0.000	0.000	0.000
		SEISSS	130.	165.	177.	85.	692.	626.	0.000	0.000	0.000
		NORMP	266.	2396.	595.	6960.	1748.	4982.	0.000	0.300	0.000
		NORMN	-166.	-2985.	-798.	-6160.	-1227.	-6334.	0.000	-0.300	0.000
		UPSETP	593.	3360.	1074.	9182.	3204.	7246.	0.100	0.400	0.100
		UPSETN	-494.	-3949.	-1277.	-8382.	-2683.	-8598.	-0.100	-0.400	-0.100
		FAULTP	722.	3732.	1236.	10104.	3657.	8063.	0.143	0.443	0.143
		FAULTN	-623.	-4321.	-1439.	-9304.	-3137.	-9415.	-0.143	-0.443	-0.143

127	RAD	V21202030H022									
		WT1	0.	-373.	0.	0.	0.	0.	0.000	0.000	0.000
		THRM1	0.	303.	0.	0.	0.	0.	0.007	0.000	-0.007
		THRM2	0.	-104.	0.	0.	0.	0.	-0.002	0.000	0.002
		BS	0.	2987.	0.	0.	0.	0.	0.093	0.003	0.094
		SAMOB	0.	1010.	0.	0.	0.	0.	0.049	0.001	0.050
		SAMSS	0.	1442.	0.	0.	0.	0.	0.070	0.001	0.071
		SEISOB	0.	185.	0.	0.	0.	0.	0.023	0.000	0.023
		SEISSS	0.	212.	0.	0.	0.	0.	0.026	0.000	0.026
		NORMP	0.	3011.	0.	0.	0.	0.	0.100	0.003	0.097
		NORMN	0.	-3464.	0.	0.	0.	0.	-0.096	-0.003	-0.101
		UPSETP	0.	4205.	0.	0.	0.	0.	0.172	0.004	0.169
		UPSETN	0.	-4659.	0.	0.	0.	0.	-0.168	-0.005	-0.173
		FAULTP	0.	4665.	0.	0.	0.	0.	0.197	0.005	0.194
		FAULTN	0.	-5119.	0.	0.	0.	0.	-0.193	-0.005	-0.197

127	RAD	V21202030H022									
		WT1	15.	0.	15.	0.	0.	0.	0.000	0.000	0.000
		THRM1	2.	0.	2.	0.	0.	0.	0.007	0.000	-0.007
		THRM2	-1.	0.	-1.	0.	0.	0.	-0.002	0.000	0.002
		BS	341.	0.	341.	0.	0.	0.	0.093	0.003	0.094
		SAMOB	276.	0.	276.	0.	0.	0.	0.049	0.001	0.050
		SAMSS	395.	0.	395.	0.	0.	0.	0.070	0.001	0.071
		SEISOB	65.	0.	65.	0.	0.	0.	0.023	0.000	0.023
		SEISSS	100.	0.	100.	0.	0.	0.	0.026	0.000	0.026
		NORMP	355.	0.	355.	0.	0.	0.	0.100	0.003	0.097
		NORMN	-328.	0.	-328.	0.	0.	0.	-0.096	-0.003	-0.101
		UPSETP	696.	0.	696.	0.	0.	0.	0.172	0.004	0.169
		UPSETN	-669.	0.	-669.	0.	0.	0.	-0.168	-0.005	-0.173
		FAULTP	849.	0.	849.	0.	0.	0.	0.197	0.005	0.194
		FAULTN	-822.	0.	-822.	0.	0.	0.	-0.193	-0.005	-0.197

2K5-1202-030-03

SEE SHT. 14AN OF 15

RESTRAINT LOAD SUMMARY

3

CALC. NO. EF-01-730-SHT. 144N OF 15

ME101/MB GRO/GTP70 (2K4042) 07/02/92 2K4042 PAGE 180

TITLE : NSCW SYSTEM(1202)
PROJECT NUMBER : 17553800
PROBLEM NUMBER : EF01730
USER : V.R.PATEL
LOAD CASE :

AUTHOR VR Patel DATE 7-10-91

CHECKER _____ DATE _____

DATA TYPE PT	LOAD	TITLE	LOCAL FORCES (LB)			LOCAL MOMENTS (FT-LB)		DIRECTION COSINES									
			FA	FB	FC	MA	MB	MC	COS AX	COS AY	COS AZ	COS BX	COS BY	COS BZ	COS CX	COS CY	COS CZ
118	ANC																
	WT1		-24	-193	4	316	-83	-305	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	THRM1		217	-382	-319	376	1014	-1249	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	THRM2		75	132	110	-129	-349	430	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	BS		67	2409	483	6347	796	4781	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	SAMOB		228	821	325	2142	852	1718	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	SAMSS		326	1172	464	3059	1217	2455	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	SEISOB		99	143	154	80	504	546	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	SEISSS		130	165	177	85	492	626	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	NORMP		266	2396	595	6960	1748	4982	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	NORMN		-166	-2985	-798	-6160	-1227	-6334	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	UPSETP		593	3360	1074	9182	3204	7246	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	UPSETN		-494	-3949	-1277	-8382	-2683	-8598	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	PAULTP		722	3732	1236	10104	3657	8063	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
	PAULTN		-623	-4321	-1439	-9304	-3137	-9415	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	1.00
127	RAD	V21202030H022															
	WT1		-373	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	THRM1		303	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	THRM2		-104	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	BS		2987	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	SAMOB		1010	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	SAMSS		1442	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	SEISOB		185	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	SEISSS		212	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	NORMP		3011	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	NORMN		-3464	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	UPSETP		4205	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	UPSETN		-4659	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	PAULTP		4665	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	PAULTN		-5119	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
127	RAD	V21202030H022															
	WT1		-21	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	THRM1		-3	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	THRM2		1	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	BS		483	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	SAMOB		391	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	SAMSS		558	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	SEISOB		92	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	SEISSS		141	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	NORMP		468	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	NORMN		-506	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	UPSETP		951	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	UPSETN		-989	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	PAULTP		1164	0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00
	PAULTN			0	0	0	0	0	-0.71	0.00	-0.71	0.00	0.00	0.00	0.00	0.00	0.00

2K3-1202-030-03

25

RESTRAINT LOAD SUMMARY

3 CALC. NO. EF-01-730 SHT. 144 OF 15

ME101/MB GRO/GTP70 (2K4042) 07/02/92 2K4042 PAGE 178

TITLE : NSCW SYSTEM(1202)
PROJECT NUMBER : 17553800
PROBLEM NUMBER : EF01730
USER : V.R.PATEL
LOAD CASE :

AUTHOR VR Patel DATE 7-10-92

CHECKER DATE

DATA TYPE	LOAD	TITLE	FX	FY	FZ	MX	MY	MZ	DX	DY	DZ
PT											
135	RAD	V21202030H023									
40		WT1	0.	-446.	0.	0.	0.	0.	0.000	0.000	0.000
		THRM1	0.	66.	0.	0.	0.	0.	-0.081	0.000	-0.074
		THRM2	0.	-23.	0.	0.	0.	0.	0.028	0.000	0.025
		BS	0.	643.	0.	0.	0.	0.	0.000	0.001	0.000
		SAMOB	0.	243.	0.	0.	0.	0.	0.000	0.000	0.000
		SAMSS	0.	348.	0.	0.	0.	0.	0.000	0.000	0.000
		SEISOB	0.	118.	0.	0.	0.	0.	0.000	0.000	0.000
		SEISSS	0.	128.	0.	0.	0.	0.	0.001	0.000	0.000
		NORMP	0.	374.	0.	0.	0.	0.	0.028	0.000	0.025
		NORMN	0.	-1112.	0.	0.	0.	0.	-0.081	-0.001	-0.074
		UPSETP	0.	735.	0.	0.	0.	0.	0.029	0.001	0.026
		UPSETN	0.	-1473.	0.	0.	0.	0.	-0.082	-0.001	-0.074
		FAULTP	0.	850.	0.	0.	0.	0.	0.029	0.001	0.026
		FAULTN	0.	-1588.	0.	0.	0.	0.	-0.082	-0.002	-0.075

135	RAD	V21202030H023	SEE SHT. 144 OF 15								
40		WT1	15.	0.	-16.	0.	0.	0.	0.000	0.000	0.000
		THRM1	-258.	0.	281.	0.	0.	0.	-0.081	0.000	-0.074
		THRM2	89.	0.	-97.	0.	0.	0.	0.028	0.000	0.025
		BS	215.	0.	235.	0.	0.	0.	0.000	0.001	0.000
		SAMOB	206.	0.	225.	0.	0.	0.	0.000	0.000	0.000
		SAMSS	294.	0.	321.	0.	0.	0.	0.000	0.000	0.000
		SEISOB	113.	0.	124.	0.	0.	0.	0.000	0.000	0.000
		SEISSS	144.	0.	157.	0.	0.	0.	0.001	0.000	0.000
		NORMP	315.	0.	504.	0.	0.	0.	0.028	0.000	0.025
		NORMN	-458.	0.	-347.	0.	0.	0.	-0.081	-0.001	-0.074
		UPSETP	634.	0.	852.	0.	0.	0.	0.029	0.001	0.026
		UPSETN	-777.	0.	-696.	0.	0.	0.	-0.082	-0.001	-0.074
		FAULTP	753.	0.	982.	0.	0.	0.	0.029	0.001	0.026
		FAULTN	-896.	0.	-825.	0.	0.	0.	-0.082	-0.002	-0.075

138	ANC	V21202030H024	SEE SHT. 144 OF 15								
45		WT1	-5.	-413.	-2.	0.	5.	2.	0.000	0.000	0.000
		THRM1	39.	14.	35.	-330.	2.	-362.	0.000	0.000	0.000
		THRM2	-13.	-5.	-12.	114.	-1.	124.	0.000	0.000	0.000
		BS	99.	264.	94.	2134.	93.	2238.	0.000	0.000	0.000
		SAMOB	175.	141.	179.	1247.	1454.	1310.	0.000	0.000	0.000
		SAMSS	250.	202.	255.	1782.	2077.	1872.	0.000	0.000	0.000
		SEISOB	317.	103.	302.	286.	176.	284.	0.000	0.000	0.000
		SEISSS	488.	109.	466.	328.	227.	327.	0.000	0.000	0.000
		NORMP	134.	0.	128.	2288.	98.	2364.	0.000	0.000	0.000
		NORMN	-117.	-681.	-108.	-2504.	-89.	-2598.	0.000	-0.001	0.000
		UPSETP	625.	212.	609.	3820.	1728.	3958.	0.000	0.000	0.001
		UPSETN	-609.	-925.	-590.	-4037.	-1718.	-4193.	0.000	-0.001	-0.001
		FAULTP	872.	278.	849.	4397.	2402.	4562.	0.001	0.000	0.001
		FAULTN	-855.	-992.	-830.	-4614.	-2393.	-4796.	-0.001	-0.001	-0.001

2 K5-1207-030-03

RESTRAINT LOAD SUMMARY

TITLE : NSCW SYSTEM(1202)
PROJECT NUMBER : 17553800
PROBLEM NUMBER : EF01730
USER : V.R.PATEL
LOAD CASE :

AUTHOR : V.R.Patel DATE 7-10-92
CHECKER : DATE

DATA TYPE PT	LOAD	TITLE	LOCAL FORCES (LB)			LOCAL MOMENTS (FT-LB)			DIRECTION COSINES											
			FA	FB	FC	MA	MB	MC	AX	COS AX	COS AY	COS AZ	COS BX	COS BY	COS BZ	COS CX	COS CY	COS CZ		
135	RAD	WT1	-446	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM1	56	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM2	-23	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		BS	643	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMOB	243	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMSS	348	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISOB	118	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISSS	128	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMP	374	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMN	-1112	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETP	735	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETN	-1473	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTP	850	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTN	-1588	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
135	RAD	WT1	-22	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM1	381	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM2	-131	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		BS	318	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMOB	305	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMSS	436	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISOB	168	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISSS	212	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMP	683	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMN	-471	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETP	1156	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETN	-944	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTP	1332	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTN	-1119	0	0	0	0	0	0	0.68	0.00	0.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
135	RAD	WT1	-5	-413	2	1	5	1	1	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM1	52	14	0	-488	2	-43	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM2	-18	-5	0	705	-1	15	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		BS	106	264	30	391	93	2389	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMOB	195	141	156	559	1454	1419	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMSS	135	202	223	391	2077	2027	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISOB	336	103	101	213	176	191	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISSS	519	109	156	246	227	218	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMP	155	0	31	874	98	2405	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMN	-129	-681	28	-1192	-89	-2432	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETP	586	212	288	1478	1728	4015	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETN	-561	-925	-286	-1796	-1718	-4041	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTP	809	278	410	1678	2402	4650	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTN	-809	-278	-410	-1678	-2402	-4650	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
138	ANC	WT1	-5	-413	2	1	5	1	1	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM1	52	14	0	-488	2	-43	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		THRM2	-18	-5	0	705	-1	15	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		BS	106	264	30	391	93	2389	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMOB	195	141	156	559	1454	1419	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SAMSS	135	202	223	391	2077	2027	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISOB	336	103	101	213	176	191	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		SEISSS	519	109	156	246	227	218	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMP	155	0	31	874	98	2405	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		NORMN	-129	-681	28	-1192	-89	-2432	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETP	586	212	288	1478	1728	4015	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		UPSETN	-561	-925	-286	-1796	-1718	-4041	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTP	809	278	410	1678	2402	4650	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00
		FAULTN	-809	-278	-410	-1678	-2402	-4650	0	0.74	0.00	0.68	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00

2K5-1202-030-03

RESTRAINT LOAD SUMMARY

TITLE : NSCW SYSTEM (1202)
PROJECT NUMBER : 17553800
PROBLEM NUMBER : EF01730
USER : V.R. PATEL
LOAD CASE :

AUTHOR V R Patel DATE 7-10-92

CHECKER _____ DATE _____

DATA PT	TYPE	LOAD	TITLE	FX	FY	PZ	MX	MY	MZ	DISPLACEMENT (IN)	DZ
										DX	DY
147	RAD		V21202030H025								
(50)		WT1		0.	-490.	0.	0.	0.	0.	0.000	0.000
		THRM1		0.	0.	0.	0.	0.	0.	0.097	0.089
		THRM2		0.	0.	0.	0.	0.	0.	-0.033	-0.031
		BS		0.	199.	0.	0.	0.	0.	0.000	0.000
		SAMOB		0.	111.	0.	0.	0.	0.	0.189	0.206
		SAMSS		0.	159.	0.	0.	0.	0.	0.270	0.295
		SEISOB		0.	124.	0.	0.	0.	0.	0.000	0.000
		SEISSS		0.	130.	0.	0.	0.	0.	0.001	0.001
		NORMP		0.	0.	0.	0.	0.	0.	0.097	0.089
		NORMN		0.	-689.	0.	0.	0.	0.	-0.033	-0.031
		UPSETP		0.	66.	0.	0.	0.	0.	0.287	0.296
		UPSETN		0.	-924.	0.	0.	0.	0.	-0.223	-0.237
		FAULTP		0.	120.	0.	0.	0.	0.	0.368	0.384
		FAULTN		0.	-978.	0.	0.	0.	0.	-0.304	-0.326
147	RAD		V21202030H025								
(50)		WT1		0.	0.	0.	0.	0.	0.	0.000	0.000
		THRM1		0.	0.	0.	0.	0.	0.	0.097	0.089
		THRM2		0.	0.	0.	0.	0.	0.	-0.033	-0.031
		BS		1.	0.	1.	0.	0.	0.	0.000	0.000
		SAMOB		75.	0.	82.	0.	0.	0.	0.189	0.206
		SAMSS		108.	0.	118.	0.	0.	0.	0.270	0.295
		SEISOB		84.	0.	92.	0.	0.	0.	0.000	0.000
		SEISSS		130.	0.	142.	0.	0.	0.	0.001	0.001
		NORMP		1.	0.	1.	0.	0.	0.	0.097	0.089
		NORMN		-1.	0.	-1.	0.	0.	0.	-0.033	-0.031
		UPSETP		160.	0.	175.	0.	0.	0.	0.287	0.296
		UPSETN		-160.	0.	-175.	0.	0.	0.	-0.223	-0.237
		FAULTP		238.	0.	260.	0.	0.	0.	0.368	0.384
		FAULTN		-238.	0.	-260.	0.	0.	0.	-0.304	-0.326

SEE SHT. 14AR OF 15

2 KS-1202-030-03

3 CALC. NO. EF-01-730SHT. 1442 OF 15

TITLE : MSCW SYSTEM (1202)
PROJECT NUMBER : 17553800
PROBLEM NUMBER : EF01730
USER : V.R. PATIL
LOAD CASE :

AUTHOR V.R. Patil DATE 7-10-92

CHECKER DATE

DATA PT	TYPE	LOAD	TITLE	LOCAL FORCES (LB)			LOCAL MOMENTS (FT-LB)			DIRECTION COSINES											
				FA	FB	FC	MA	MB	MC	AX	AY	AZ	BX	BY	BZ	CX	CY	CZ			
149	RAD	V	21202030H025	-490	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			WT1	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			THRM1	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			THRM2	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			BS	199	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SAMEX	111	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SAMSS	159	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SEISOB	124	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SEISSS	130	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			NORMP	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			NORMN	-689	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			UPSETP	66	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			UPSEIN	-924	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			FAULTP	120	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			FAULTN	-978	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
147	RAD	V	21202030H025	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			WT1	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			THRM1	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			THRM2	0	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			BS	1	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SAMEX	112	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SAMSS	159	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SEISOB	125	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			SEISSS	192	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			NORMP	1	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			NORMN	-1	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			UPSETP	237	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			UPSEIN	-237	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			FAULTP	352	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			FAULTN	-352	0	0	0	0	0	0.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
			VERSION M8	STOP ON 07/02/92 AT 11:50:01,				48.78, BIO=	1075, DIO=	10785, PGF=				10785, PGF=				11248			
			VERSION M8	EXECUTION TIMES				12.01, BIO=	255, DIO=	3571, PGF=				3571, PGF=				414			
			VERSION M8	START ON 07/02/92 AT 11:50:02,				49.02, BIO=	1089, DIO=	10788, PGF=				10788, PGF=				11337			

2 K5-1202-030-03

50

ME1011C
ME1011C
ME101SA

Project	VOGTLE NUCLEAR PLANT, UNIT-2	Prepared By	V. R Patel	Date	7-13-92
Subject/Title	PIPE STRESS EVALUATION	Reviewed By	<i>J. J. Jhoni</i>	Date	7-15-92
		Calculation Number	EF-01-730	Sheet	7E of 15

PURPOSE:- TO RECONCILE THE DISCREPANCY IN THE ANALYSIS OF DIFF BUILDING SETTLEMENT AND SEISMIC ANCHOR MOTION LOAD CONDITION FOR PIPING 180 2KS-1202-030-03 FROM BURIED PIPE (VIRTUAL ANCHOR) TO NSCW TOWER TRAIN "A".

REFERENCE: 1) PIPE STRESS CALC & EF-01-730 REV. 2.
2) ME101 RUN # "2K4042" DATED 07/02/92

EVALUATION: PIPING OF THE 180 2KS-1202-030-03 FROM BURIED PIPING (VIRTUAL ANCHOR) TO NSCW TOWER TRAIN "A" IS REANALISED PER REF-2 AND THE RESULTS ARE ACCEPTABLE AS BELOW

EQ 8 STRESS = 1584 PSI < 15700 PSI (REF 2)
@ D.P 147

EQ 9 STRESS (LVL B) = 2345 PSI < 18840 PSI (SEE SHT 84 OF 15)
@ D.P 138

EQ 9 STRESS (LVL D) = 2474 PSI < 28260 PSI (SEE SHT 84 OF 15)
@ D.P 138

EQ 10 STRESS = 1183 PSI < 23550 PSI (REF 2)
@ D.P 139

B-S STRESS = 10975 PSI < 3XSL = 47100 PSI
@ D.P 128 (REF-2)

VALVE END LOAD: SEE SHT 106 OF 15,
VALVE ACCELERATION (SHT 134 OF 15), FLANGE LOAD (SHT 84 OF 15),
AND PENETRATION DISPLACEMENT (SHT 120, 121 & 122 OF 15) HAS
INSIGNIFICANT EFFECT.

CONCLUSION:

PIPE STRESS ANALYSIS IS FOUND SATISFACTORY, THEREFORE
THE DEVIATION IS ACCEPTED.

ENCLOSURE 4

Settlement Monitoring Flow Chart

SETTLEMENT MONITORING PROGRAM

FLOW CHART

