

Docket No. 50-336  
B14393

Attachment 1

Millstone Nuclear Power Station, Unit No. 2

Proposed Revision to Technical Specifications  
Remote Shutdown Monitoring Instrumentation

Marked-Up Technical Specifications

April 1994

9404290271 940422  
PDR ADOCK 05000336  
P PDR

INDEX

LIMITING CONDITIONS FOR OPERATION AND SURVEILLANCE REQUIREMENTS

<u>SECTION</u>	<u>PAGE</u>
<u>3/4.2 POWER DISTRIBUTION LIMITS</u>	
3/4.2.1 LINEAR HEAT RATE.....	3/4 2-1
3/4.2.2 Deleted	
3/4.2.3 TOTAL INTEGRATED RADIAL PEAKING FACTOR - $F_r^T$ .....	3/4 2-9
3/4.2.4 AZIMUTHAL POWER TILT.....	3/4 2-10
3/4.2.5 Deleted	
3/4.2.6 DNB MARGIN.....	3/4 2-13
<u>3/4.3 INSTRUMENTATION</u>	
3/4.3.1 REACTOR PROTECTIVE INSTRUMENTATION.....	3/4 3-1
<del>3/4.3.2</del> ENGINEERED SAFETY FEATURE ACTUATION SYSTEM	
3/4.3.2 INSTRUMENTATION.....	3/4 3-10
3/4.3.3 MONITORING INSTRUMENTATION.....	3/4 3-26
Radiation Monitoring.....	3/4 3-26
Incore Detectors.....	3/4 3-30
Seismic Instrumentation.....	3/4 3-32
Meteorological Instrumentation.....	3/4 3-36
<del>Chlorine Detection Systems.....</del>	<del>3/4 3-42</del>
Fire Detection Instrumentation.....	3/4 3-43
Accident Monitoring.....	3/4 3-46
Radioactive Liquid Effluent Monitoring Instrumentation.	3/4 3-50
Radioactive Gaseous Effluent Monitoring Instrumentation	3/4 3-56
<u>3/4.4 REACTOR COOLANT SYSTEM</u>	
3/4.4.1 COOLANT LOOPS AND COOLANT CIRCULATION.....	3/4 4-1
Startup and Power Operation.....	3/4 4-1
Hot Standby.....	3/4 4-1a
Shutdown.....	3/4 4-1b

111

MILLSTONE - UNIT 2

3/4 3-40

TABLE 3.3-9

REMOTE SHUTDOWN MONITORING INSTRUMENTATION

<u>INSTRUMENT</u>	<u>READOUT</u>	<u>MEASUREMENT RANGE</u>	<u>MINIMUM CHANNELS OPERABLE</u>
1. Wide Range Logarithmic Neutron Flux Monitor	Hot Shutdown Panel	$10^{-8}$ - $10^4$ cps 10 <sup>-8</sup> % - 100%	1
2. Reactor Trip Breaker Indication	Reactor Trip Switchgear (Q03)	OPEN-CLOSE	1/trip breaker
3. Reactor Cold Leg Temperature	Hot Shutdown Panel (C-21)	0-600°F	1
4. Pressurizer Pressure	Hot Shutdown Panel (C-21)	0-1600 psia	1
a. Low Range		1500-2500 psia	1
b. High Range			
5. Pressurizer Level	Hot Shutdown Panel (C-21)	0-100%	1
6. Steam Generator Pressure	Hot Shutdown Panel (C-21)	0-1200 psia	1/steam generator
7. Steam Generator Level	Hot Shutdown Panel (C-21)	0-100%	1/steam generator

August 1, 1975

Amendment No.

Docket No. 50-336  
B14393

Attachment 2

Millstone Nuclear Power Station, Unit No. 2

Proposed Revision to Technical Specifications  
Remote Shutdown Monitoring Instrumentation

Retyped Technical Specifications

April 1994

INDEX

LIMITING CONDITIONS FOR OPERATION AND SURVEILLANCE REQUIREMENTS

<u>SECTION</u>		<u>PAGE</u>
<u>3/4.2 POWER DISTRIBUTION LIMITS</u>		
3/4.2.1	LINEAR HEAT RATE . . . . .	3/4 2-1
3/4.2.2	Deleted	
3/4.2.3	TOTAL INTEGRATED RADIAL PEAKING FACTOR - $F_r^T$ . . . . .	3/4 2-9
3/4.2.4	AZIMUTHAL POWER TILT . . . . .	3/4 2-10
3/4.2.5	Deleted	
3/4.2.6	DNB MARGIN . . . . .	3/4 2-13
 <u>3/4.3 INSTRUMENTATION</u>		
3/4.3.1	REACTOR PROTECTIVE INSTRUMENTATION . . . . .	3/4 3-1
3/4.3.2	ENGINEERED SAFETY FEATURE ACTUATION SYSTEM INSTRUMENTATION . . . . .	3/4 3-10
3/4.3.3	MONITORING INSTRUMENTATION . . . . .	3/4 3-26
	Radiation Monitoring . . . . .	3/4 3-26
	Incore Detectors . . . . .	3/4 3-30
	Seismic Instrumentation . . . . .	3/4 3-32
	Meteorological Instrumentation . . . . .	3/4 3-36
	Remote Shutdown Instrumentation . . . . .	3/4 3-39
	Fire Detection Instrumentation . . . . .	3/4 3-43
	Accident Monitoring . . . . .	3/4 3-46
	Radioactive Liquid Effluent Monitoring Instrumentation . . . . .	3/4 3-50
	Radioactive Gaseous Effluent Monitoring Instrumentation . . . . .	3/4 3-56
 <u>3/4.4 REACTOR COOLANT SYSTEM</u>		
3/4.4.1	COOLANT LOOPS AND COOLANT CIRCULATION . . . . .	3/4 4-1
	Startup and Power Operation . . . . .	3/4 4-1
	Hot Standby . . . . .	3/4 4-1a
	Shutdown . . . . .	3/4 4-1b

TABLE 3.3-9

REMOTE SHUTDOWN MONITORING INSTRUMENTATION

<u>INSTRUMENT</u>	<u>READOUT LOCATION</u>	<u>MEASUREMENT RANGE</u>	<u>MINIMUM CHANNELS OPERABLE</u>
1. Wide Range Logarithmic Neutron Flux Monitor	Hot Shutdown Panel (C-21)	10 <sup>-8</sup> % - 100%	1
2. Reactor Trip Breaker Indication	Reactor Trip Switchgear (Q03)	OPEN-CLOSE	1/trip breaker
3. Reactor Cold Leg Temperature	Hot Shutdown Panel (C-21)	0-600°F	1
4. Pressurizer Pressure	Hot Shutdown Panel (C-21)	0-1600 psia	1
a. Low Range		1500-2500 psia	1
b. High Range			
5. Pressurizer Level	Hot Shutdown Panel (C-21)	0-100%	1
6. Steam Generator Pressure	Hot Shutdown Panel (C-21)	0-1200 psia	1/steam generator
7. Steam Generator Level	Hot Shutdown Panel (C-21)	0-100%	1/steam generator