Docket No. 50-298

Mr. J. M. Pilant, Director Licensing & Quality Assurance Nebraska Public Power District P. O. Box 499 Columbus, Nebraska 68601 Distribution:
Docket File JHeltemes
NR C PDR
Local PDR
ORB #2 Rdg
DEisenhut
OELD
ELJordan
JMTaylor
BSiegel
SNorris
NSIC
ACRS (10)

Dear Mr. Pilant:

Subject: NUREG-0737 Item II.B.1, Reactor Coolant System High Point Vents

Re: Cooper Nuclear Station

We have completed our review of the subject action item for your facility. Our review encompassed your previous submittals and other pertinent correspondence as referenced in the enclosed Safety Evaluation. We find that the venting capability at your facility is acceptable, and, thus, consider the subject item resolved.

Please note that our review addressed only the subject action item and should not be considered to be an evaluation of your compliance with 10 CFR 50.44. Additionally, our review did not address automatic depressurization system valve accumulator capacity, as that review is being performed under NUREG-0737 Action Item II.K.3.28.

Sincerely,

ORIGINAL SIGNED BY

Domenic B. Vassallo, Chief Operating Reactors Branch #2 Division of Licensing

Enclosures:

1. Safety Evaluation

2. Technical Evaluation

cc w/encls: See next page

8211040108 821014 PDR ADDCK 05000298

-			1101	 	
OFFICE SURNAME	DL:ORB#2 SNorris	DL:ORB#2 BSiegel ms	DL:ORB#2 DBVassallo	 	
	10/14/82	10//182	10/14/82	 *******************	

Mr. J. M. Pilant Nebraska Public Power District

cc:

Mr. G. D. Watson, General Counsel Nebraska Public Power District P. O. Box 499 Columbus, Nebraska 68601

Mr. Arthur C. Gehr, Attorney Srell & Wilmer 3100 Valley Center Phoenix, Arizona 85073

Cooper Nuclear Station
ATTN: Mr. L. Lessor
Station Superintendent
P. O. Box 98
Brownville, Nebraska 68321

Director Nebraska Dept. of Environmental Control P. O. Box 94877, State House Station Lincoln, Nebraska 68509

Mr. William Siebert, Commissioner Nemaha County Board of Commissioners Nemaha County Courthouse Auburn, Nebraska 68305

Mr. Dennis Dubois USNRC Resident Inspector P. O. Box 218 Brownville, NE 68321

U. S. Environmental Protection Agency Region VII Office Regional Radiation Representative 324 East 11th Street Kansas City, MO 64106 John T. Collins Regional Administrator, Region IV U.S. Nuclear Regulatory Commission 611 Ryan Plaza Drive, Suite 1000 Arlington, Texas 76011



UNITED STATES NUCLEAR REGULATORY COMMISSION WASHINGTON, D. C. 20555

SAFETY EVALUATION BY THE OFFICE OF NUCLEAR REACTOR REGULATION

FOR NUREG-0737, ITEM II.B.1

REACTOR COOLANT SYSTEM HIGH POINT VENTS

COOPER NUCLEAR STATION

1.0 Introduction

NUREG-0737, Item II.B.1, "Reactor Coolant System Vents" states that each licensee shall install reactor coolant system (RCS) vents to vent non-condensible gases which may inhibit core cooling during natural circulation. By submittals as referenced in the enclosed Technical Evaluation Report (TER), the licensee endorsed the BWR Owner's Group position and provided certain, additional plant-specific information.

2.0 Evaluation

Lawrence Livermore Laboratory, our contractor for this item, has reviewed the design of existing systems at Cooper Nuclear Station and concluded that the existing systems are sufficient to vent noncondensible gases from the RCS and meet the requirements of NUREG-0737 Item II.B.1. We have reviewed the TER and the existing systems and conclude that these systems will vent, or are available to vent, the RCS.

Two confirmatory items were noted by our contractor in its TER. Resolution of these items is discussed in the following paragraphs.

Since operator responses to indications of inadequate core cooling, such as low core water level, are the same for both steam and non-condensible gases, we conclude that explicit instructions in the operating procedures for venting non-condensible gases are not necessary.

The existing technical specifications for the Automatic Depressurization System (ADS) valves require that the valves be operable as a condition for RCS pressurization. The ADS valve accumulator capacity is currently under review (TMI Action Plan Item II.K.3.28) to verify that each valve may be opened at least 5 times. Pending satisfactory resolution of Item II.K.3.28, we find the existing technical specifications on ADS valve operability sufficient to cover the use of ADS valves as vents.

Therefore, based on our contractor's recommendation that the venting capability be found acceptable with satisfactory resolution of the confirmatory items described in the TER, and our review, as described above, we find the Cooper Nuclear Station venting capability acceptable.

Dated:

Principal Contributors: G. Alberthal, B. L. Siegel