Attachment 1

Millstone Nuclear Power Station, Unit No. 3 Proposed Revision to Technical Specifications

Cycle 4

SURVEILLANCE REQUIREMENTS (Con't)

Valve Number		Valve Function	Valve Position
1.	V304(Z-)	Primary Grade Water	Closed
2.	V120(Z-) V147(Z-)	to CVCS Moderating Hx Outlet BTRS Outlet	Closed Closed
4.	V797(Z-)	Failed Fuel Monitoring	Closed
5.	V100(Z-)	Resin Sluice, CVCS Cation Bed Demineralizer	Closed
6.	V571(Z-)	Resin Sluice, CVCS Cation Bed Demineralizer	Closed
7.	V111(Z-)	Resin Sluice, CVCS Cation Bed Demineralizer	Closed
8.	V112(Z-)	Resin Sluice, CVCS Cation Bed Demineralizer	Closed
9.	V98(Z-)/V99(Z-)	Resin Sluice, CVCS Mixed Bed Demineralizer	Closed
10.	V569(Z-)/V570(Z-)	Resin Sluice, CVCS Mixed Bed Demineralizer	Closed
11.	V107(Z-)/V109(Z-)	Resin Sluice, CVCS Mixed	Closed
12.	V108(Z-)/V110(Z-)	Bed Demineralizer Resin Sluice, CVCS Mixed Bed Demineralizer	Closed