FACILITY OPERATING LICENSE NO. DPR-65

DOCKET NO. 50-336

Replace the following page of the Appendix A Technical Specifications with the enclosed page. The revised page is identified by amendment number and contains vertical lines indicating the areas of change.

Remove

Insert

3/4 8-4

3/4 8-4

ELECTRICAL POWER SYSTEMS

SURVEILLANCE REQUIREMENT (Continued)

- Verifying that on the safety injection actuation signal, all diesel generator trips, except engine overspeed, generator differential current, voltage restraint overcurrent, and low lube oil pressure (2 out of 3) are automatically bypassed.
- Verifying the diesel generator operates for > 60 minutes while loaded to > 2750 kw.
- Verifying that the auto-connect loads to each diesel generator do not exceed the 2000 hour rating of 3000 kw.
- 8. Verifying that on an actual or simulated Safety Injection Actuation Signal (SIAS) without a loss of offsite power:
 - The diesel generator starts on the auto-start signal
 - and operates on Standby for greater than 5 minutes; The generator frequency and voltage shall reach 58.8 to 61.2 Hertz, and 3740 to 4580 VAC, and be maintained during this test;
 - c. The diesel start time (time to reach 90% of rated speed and 97% of rated voltage) shall be less than or equal to 15 seconds.