

(2)

SAFETY RELATED ELECTRICAL EQUIPMENT ANCHORAGE

8302170321 830207
PDR ADOCK 05000409
P PDR



NUCLEAR ENERGY SERVICES, INC.

DOCUMENT NO. 81A0041 REV. 3

PAGE 1 OF 4

RECEIVED JAN 1 1981

SAFETY-RELATED ELECTRICAL
EQUIPMENT ANCHORAGES
FOR THE
LACROSSE BOILING WATER REACTOR

Project Application 5101-063	Prepared By <i>R. E. Rumpf T. Strnad</i> R. E. Rumpf/T. Strnad	Date 4/6/81
APPROVALS		
TITLE/DEPT.	SIGNATURE	DATE
Struct. Analysis Manager	<i>J. Bal Husaini</i>	4-6-81
Project Manager	<i>Richard Milos</i>	4-6-81
V.P. Engineering	<i>Albert J. ...</i>	4-6-81
O.A. Manager	<i>V. J. Potent</i>	4-6-81
CONTROLLED COPY		
VALID ONLY IF THIS STAMP IS RED		




TABLE OF CONTENTS

STEEL NOTES.....3


LIST OF FIGURES & DRAWINGS

3	1.	LACBWR - Generator Battery Rack Modification.....	SK-5101-063-2, Rev. 1
	2.	LACBWR - Compressed Gas Tank Brackets.....	SK-5101-063-3, Rev. 0
3	1	3. LACBWR - 480 V. Essential Bus. Modification.....	SK-5101-063-4, Rev. 2
	4.	LACBWR - Reactor Battery Rack Modification.....	SK-5101-063-6, Rev. 0
3		5. IACBWR - Battery Charger Modifications.....	SK-5101-063-7, Rev. 1
3		6. Superseded by SK-5101-063-14	
3	2	7. LACBWR - 1-A Diesel Starting Battery Rack Modification.....	SK-5101-063-8, 1-2, Rev. 1 2-2, Rev. 1
3	2	8. LACBWR - 1-B Diesel Gen. Control Panel Modification.....	SK-5101-063-9, Rev. 1
3	2	9. LACBWR - 1-B Diesel Gen. Bldg. Electrical Equipment Modification.....	SK-5101-063-10, 1-4, Rev. 1 2-4, Rev. 1 3-4, Rev. 0 4-4, Rev. 0
3	2	10. Deleted	
3	2	11. LACBWR - Reactor Water Level Transmitters #1, #2 Modification.....	SK-5101-063-12, Rev. 1
3		12. LACBWR - Aux. Dist. Panel for 125-V DC.....	SK-5101-063-13, 1-2, Rev. 0 2-2, Rev. 0
3		13. LACBWR - Electrical Equipment Room Modifications.....	SK-5101-063-14, 1-7, Rev. 0 5-7, Rev. 0 2-7, Rev. 0 6-7, Rev. 0 3-7, Rev. 0 7-7, Rev. 0 4-7, Rev. 0

STEEL NOTES

1. Dimensions and tolerances are to be interpreted in accordance with ANSI Y14-5-1973.
2. All welding is to be performed in accordance with AWS standard D1.1. (1980). All welding is to be performed by welders who are qualified in accordance with Section IX of the ASME BPVC. 
3. Material: All structural steel except tube sections per ASTM A36. Material certs are required. All bolts and nuts per ASTM A325 unless specified otherwise. 
4. All structural carbon steel shall be protected from corrosion by painting with one (1) coat of a D.P.C.-approved rust-inhibiting primer. 
5. Install "WEJ-IT" expansion anchor bolts in concrete at hole locations noted. Installation, drilling, etc. must be performed in accordance with the manufacturer's recommended procedure.
6. All expansion bolts are to be standard "WEJ-IT" type with standard "WEJ-IT" washers unless noted.
7. All structural tubing as per ASTM A500 Grade B. Material certs are required.
8. Where base plates require shimming or leveling, a non-shrink grout shall be used and shall be approved by owner.
9. All steel fabrication shall be in accordance with AISC.

0






NUCLEAR ENERGY SERVICES

BY TS DATE 3-9-81 PROJ. 5101 TASK 063
CHKD. RR DATE 4-9-81 PAGE 11 OF
LACBWR

1-A DIESEL STARTING BATTERIES AND RACK



REF.



SECTION A-A

1-B DIESEL GENERATOR CONTROL PANEL

REF.



1-B DIESEL GENERATOR CONTROL PANEL




NUCLEAR ENERGY SERVICES

BY TS DATE 3-5-92 PROJ. 5101 TASK 302
CHKD. RR DATE 3-15-92 PAGE 1 OF 4
LACIQUIR ELECT. EQUIP

1-B CIP FLOOR - ELECT. EQUIP PANELS

REF.






NUCLEAR ENERGY SERVICES

BY RS DATE 2/15/82 PROJ. 3701 TASK 063
CHKD. RR DATE 3/15/82 PAGE 2 OF 4
LABOUR ELEC. EQUIP.

1-12 DIESEL BLDG - ELECT. PANELS


REF.




$\frac{1}{2}$ " R — $\frac{13}{16}$ " ϕ HOLES FOR $\frac{3}{4}$ " ϕ BOLTS

DETAIL A

$\frac{13}{16}$ " ϕ HOLE FOR $\frac{3}{4}$ " ϕ BOLT



DETAIL B



TYPICAL CONNECTION
DETAIL AT END
OF ANGLE




NUCLEAR ENERGY SERVICES


BY TS DATE 3-15-82 PROJ. 5101 TASK 063
CHKD. R.R DATE 3/15/82 PAGE 3 OF 4
LAOSWR FLEET EQUIP.

1-B GEN BLDG - ELECT. EQUIP. PANELS

REF.



PLAN VIEW



SECTION B-B



NUCLEAR ENERGY SERVICES


BY TD DATE 3-15-72 PROJ. 5101 TASK 063

CHKD. R.P. DATE 3/15/72 PAGE 4 OF 4


EFFICIENT ELECT. EQUIP.

1-B GFN BLDS - ELECT. EQUIP. PANELS

REF.




PLAN VIEW




SECTION C-C

REACTOR WATER LEVEL TRANSMITTERS #1, #2


REF.






AUX. DIST. PANEL FOR 125V DC GEN PLANT BUS

REF.



SECTION A-A




± 7/8" Ø HOLES
 FOR 3/4" x 6" LONG WES-ITS

SECTION B-B


ELECTRICAL EQUIPMENT ROOM


REF.



NOTE: FIELD VERIFY ALL DIMENSIONS PRIOR TO FABRICATION


ELECTRICAL EQUIPMENT ROOM PLAN






ELECT. EQUIP. PANELS


REF.



SECTION B-B





SECTION C-C




GENERATOR DC PANEL

REF.




UNDERVOLTAGE RELAY CABINET

REF.



PLAN



ELEVATION

④ END SUPPORT UPPER SHELF

SCALE 3/4"=1'-0"

NOTES

1. ALL STRUCTURAL TUBING PER ASTM A500 GRADE E.
2. ALL OTHER STEEL PER ASTM A36

CONTROLLED
COPY



FOR
YR


EE
FOR

LF

B

A

EM	QTY	CODE IDENT	PART NUMBER	DESCRIPTION	
PARTS LIST					
SIGNATURES		DATE		 AUTOMATION INDUSTRIES, INC. NUCLEAR ENERGY SERVICES	
RAWN	T. STRNAD	3-9-81			
CHECKED	R. Rumpf	4-6-81			
TITLE				LACBWR  GENERATOR BATTERY RACK MOD.	
		SIZE	CODE IDENT NO.	DRAWING NO.	REV
		D		SK-5101-063-2	1
APPROVED		SCALE NOTED	PROJECT 5101-063	SHEET 1 OF 1	



3" x 1/2" PL x 1'-0" LG. - TYP


SECTION A-A

SCALE: 3" = 1'-0"

CTIONS

CONTROLLED
COPY

SK-5101-063-3 B

ITEM	QTY	CODE IDENT	PART NUMBER	DESCRIPTION	
PARTS LIST					
SIGNATURES		DATE		 AUTOMATION INDUSTRIES, INC. NUCLEAR ENERGY SERVICES	
DRAWN	<i>J. J. Lunn</i>	3-11-81			
CHECKED	<i>R. Rumpf</i>	4-6-81			
TITLE					
LACBWR COMPRESSED GAS TANK BRACKETS					
APPROVED		SIZE	CODE IDENT NO.	DRAWING NO.	REV
		D		SK-5101-063-3	0
SCALE NOTED		PROJ. NO. 5101-063		SHEET 1 OF 1	

A

JAN 10 1983

B

CONTROLLED COPY

ITEM	QTY	CODE IDENT	PART NUMBER	DESCRIPTION
PARTS LIST				

SIGNATURES	DATE
DRAWN <i>J. F. Fields</i>	3-11-81
CHECKED R RUMPF	4-6-81

A AUTOMATION INDUSTRIES, INC.
NUCLEAR ENERGY SERVICES

TITLE
LACBWR ² ³
480V. ESSENTIAL BUS.
MODIFICATION


SIZE D	CODE IDENT NO.	DRAWING NO. SK-5101-063-4	REV 2
------------------	----------------	------------------------------	----------

APPROVED

SCALE NOTED	5101-063	SHEET 1 OF 1
-------------	----------	--------------

A

JAN 10 1983



SECTION I-I

SCALE: 3"=1'-0"

NOTE: FIELD VERIFY ALL DIMENSIONS PRIOR TO FABRICATION

SK-5101-063-6 B

CONTROLLED COPY

EM	QTY	CODE IDENT	PART NUMBER	DESCRIPTION
----	-----	------------	-------------	-------------

PARTS LIST

SIGNATURES	DATE	A	AUTOMATION INDUSTRIES, INC.		
RAWN TJ FIELDS	3-20-81		NUCLEAR ENERGY SERVICES		
CHECKED T. STRNAD	4-6-81	TITLE	LACBWR REACTOR BATTERY RACK MOD.		
		SIZE	CODE IDENT NO.	DRAWING NO.	REV
		D		SK-5101-063-6	0
APPROVED		SCALE NOTED		PROJ. NO. 5101-063	SHEET 1 OF 1

A

JAN 10 1983



B

A

CONTROLLED COPY

#	QTY	CODE IDENT	PART NUMBER	DESCRIPTION
---	-----	------------	-------------	-------------


PARTS LIST

SIGNATURES		DATE	 AUTOMATION INDUSTRIES, INC. NUCLEAR ENERGY SERVICES	TITLE LACBWR  BATTERY CHARGER MODIFICATIONS	
OWN	R RUMPF	3-31-81			
DRAWN	T. STRNAD	4-6-81			
APPROVED					
ENGINEER					
		SIZE	CODE IDENT NO.	DRAWING NO.	REV
		D		SK-5101-063-7	1
		SCALE NOTED	PROJECT 5101-063	SHEET 1 OF 1	

JAN 10 1983

(3)

SUPPORTING CALCULATIONS FOR ITEM 2




NUCLEAR ENERGY SERVICES

BY TS DATE 7-10-81 PROJ. 5701 TASK 043
CHKD. AB DATE 8-7-81 PAGE 11 OF
CALCUL

1-D GEN. BLDG BATTERY RACK

REF.



ELEVATION

H W V D
 BATTERIES: 15 1/4 x 10 1/4 x 6.59" ASSUME WT: 90 LBS EACH
 1/2" EXT. POLYST. BETWEEN BATTERIES ✓
 REFERENCE DRWG: CD BATTERIES M-655Z





NUCLEAR ENERGY SERVICES

BY TS DATE 7-10-81 PROJ. 501 TASK 063
CHKD. CS DATE 8-7-81 PAGE 12 OF _____
CACB/R

1-B GEN. BLDG. BATTERY RACK

REF.





NUCLEAR ENERGY SERVICES


BY 10 DATE 10-81 PROJ. 301 TASK 600

CHKD. AZ DATE 8-7-81 PAGE 13 OF

LAUBER

1-B GEN 1200 BATTERY RACK

REF.




SECTION A-A



NUCLEAR ENERGY SERVICES

1-E GEN. BLDG BATTERY RACK

REF.



STRADYNE MODEL




NUCLEAR ENERGY SERVICES

BY LS DATE 1-2-81 PROJ. 1101 TASK 100
CHKD. BS DATE 9-7-81 PAGE 15 OF
CACB.WR

1-B RLBG BATTERY RACK

REF.

STAR DYNE MODEL






NUCLEAR ENERGY SERVICES

BY TS DATE 7-13-81 PROJ. 5701 TASK 053
CHKD. CSJ DATE 8-7-81 PAGE 16 OF
LACDWR

REF.

1-B BATTERY RACK




STATIC MEMBER PROPERTIES

REF.

#1 $\angle -2 \times 2 \times \frac{3}{16}$

$A = 0.715 \text{ in}^2$ / $I_2 = I_3 = 0.272 \text{ in}^4$ ✓

$SF_2 = SF_3 = 0.5$ ✓



$J = \frac{1}{3} \sum b t^3$ ✓

$J = (\frac{1}{3})(\frac{3}{16})(2 + 2 - \frac{3}{16}) = 0.0084 \text{ in}^4$ ✓

$CTORS = 0.1875$ ✓


#3 $1\frac{1}{2} \times 1\frac{3}{8}$ UNISTRUT P-1000 ✓

12 GA. $t = 0.1046$ ✓

$A = 0.555 \text{ in}^2$ ✓

$I_2 = 0.186 \text{ in}^4$ ✓

$I_3 = 0.239 \text{ in}^4$ ✓



$SF_2 = \frac{2 \times 1.625 \times 0.1046}{0.555} = 0.613$ ✓

$SF_3 = \frac{1.625 \times 0.1046}{0.555} = 0.306$ ✓

$J = \frac{1}{3} (3 \times 1.625 - 2 \times 0.1046)(0.1046)^3 = 0.0018 \text{ in}^4$ ✓


$CTORS = 0.1046$ ✓

REF: "UNISTRUT METAL FRAMING FOR MECHANICAL SUPPORT SYSTEMS"
 MC-1 PG. 23.

STAINLESS STEEL MEMBER PROPERTIES

REF.

#2 $1\frac{5}{8} \times \frac{3}{8}$ UNISTRUT P-330 ✓
 12 GA ✓ t = 0.1046 ✓



$A = 0.397 \text{ IN}^2$ ✓
 $I_2 = 0.197 \text{ IN}^4$ ✓
 $I_3 = 0.090 \text{ IN}^4$ ✓


$SF_2 = \frac{1.625 \times 0.1046}{0.397} = 0.428$ ✓

$SF_3 = \frac{2 \times 0.875 \times 0.1046}{0.397} = 0.461$ ✓

$J = \frac{1}{3} (2 \times 0.875 + 1.625 - 2 \times 0.1046) (0.1046)^3 = 0.0012 \text{ IN}^4$ ✓

CTORS = 0.1046" ✓

#4 $1\frac{1}{2} \times \frac{3}{16}$ BAR



$A = 0.281 \text{ IN}^2$ ✓

$I_2 = 0$ ✓

$I_3 = \frac{1}{12} (1.5 \times 0.1875)^3 = 0.053 \text{ IN}^4$ ✓

$SF_2 = SF_3 = 0.85$ ✓

$J = \frac{1}{3} (1.5 \times 0.1875)^3 = 0.003$ ✓


CTORS = 0.1875" ✓

$SSF_2 = SSF_3 = 1.5$ ✓

STAR DYNE MEMBER PROPERTIES

REF.

SHEAR STRESS FACTORS




$\angle 2 \times 2 \times \frac{3}{8}$ Bm # 1

$$\tau_{MAX} = \frac{VQ}{It} = \frac{V[(1.431)^2/2 \times 0.1875]}{(0.272)(0.1875)} = 3.76 \text{ V}$$

$$\tau_{AVG} = \frac{V}{A} = \frac{V}{0.715} = 1.4 \text{ V}$$

$$SSF2 = SSF3 = \frac{\tau_{MAX}}{\tau_{AVG}} = \frac{3.76 \text{ V}}{1.4 \text{ V}} = 2.69$$

13M $\angle 2$ $1\frac{5}{8} \times \frac{3}{4}$ UNISTRUT




$$X_2 = \frac{(1.625 \times 1.046)(0.8227) + 2(0.7709^2/2 \times 1.046)}{(0.397)}$$

$$X_2 = 0.509 \text{ inches}$$

$$\tau_{MAX} = \frac{V[2 \times (0.509^2/2 \times 0.1046)]}{(0.040 \times 2)(1.046)} = 3.24 \text{ V}$$

$$\tau_{AVG} = \frac{V}{0.397} = 2.52 \text{ V}$$

$$SSF2 = \frac{3.24 \text{ V}}{2.52 \text{ V}} = 1.29$$



$$\tau_{MAX} = \frac{V[(0.575 \times 1.046)(0.76) + (1.706^2/2 \times 1.046)]}{(0.547)(1.046)}$$

$$= 6.23 \text{ V}$$

$$SSF3 = \frac{6.23 \text{ V}}{2.52 \text{ V}} = 2.47$$




NUCLEAR ENERGY SERVICES

STADYNE MEMBER PROPERTIES

REF.

SHEAR STRESS FACTORS

ISM #3 1 5/8 x 1 3/4 UNISTRUT




$$x_3 = \frac{(1.625 \times .1096)(1.573) + 2(1.52/2 \times .1096)}{0.555}$$

$$x_3 = 0.917 \text{ "}$$

$$\tau_{MAX} = \frac{\sqrt{[2x(.917/2 \times .1096)]}}{(0.756)(2 \times .1096)} = 2.26 \text{ V}$$

$$\tau_{AVG} = \frac{V}{0.555} = 1.80 \text{ V}$$

$$SSF3 = \frac{2.26 \text{ V}}{1.80 \text{ V}} = 1.26 \text{ V}$$



$$\tau_{MAX} = \frac{\sqrt{[(1.625 \times .1096)(0.76) + (.708/2 \times .1096)]}}{(0.239)(.1096)}$$

$$= 6.22 \text{ V}$$

$$SSF2 = \frac{6.22 \text{ V}}{1.80 \text{ V}} = 3.45 \text{ V}$$



NUCLEAR ENERGY SERVICES

REF.

BATTERY LOADS

ASSUME BATTERY DIMENSIONS $H \times W \times L$
 $15\frac{1}{4} \times 10\frac{1}{4} \times 6.55$ ✓

$\frac{1}{2}$ " EXP. POLYSTYRENE BETWEEN BATTERIES ✓

ASSUME WT = 90# EACH ✓ 15/SHELF ✓

INST. LOAD = $\frac{90 \times 15}{209} = 12.69$ #/IN ✓

ASSUME HORIZONTAL ACCELERATION = 1.5 X PEAK g FROM ✓
SITE RESPONSE SPECTRA = $1.5 \times 0.21g = 0.315g$ ✓

VERTICAL ACCELERATION = $\frac{2}{3} \times \text{HORIZ. } g = \frac{2}{3} \times 0.315g = 0.21g$ ✓

DEAD LOAD

$\frac{12.69}{2} = 6.34$ #/IN - BEAMS # 59-66 ✓
77-84 ✓

HORIZ. ACCEL. + X2 DIR.

$12.69 \frac{\#}{IN} \times 0.315g = 4.0$ #/IN BEAMS # 55-58 ✓
73-76 ✓


-X2 DIR. 4.0 #/IN BEAMS # 50-53 ✓
68-71 ✓

HORIZ. ACCEL. X1 DIR

15 BATTERIES $\times 90 \# \times 1350 \times 0.315g = 425.25$ # - BEAM # 54 ✓
72 ✓

VERTICAL ACCEL X3 DIR

$6.34 \frac{\#}{IN} \times 0.21g = 1.33$ #/IN - BEAMS # 55-66 ✓
77-84 ✓



NUCLEAR ENERGY SERVICES


STRESS SUMMARY	REF.
<p style="text-align: right;">STARDYNE 3, D PRINTOUT 5640068 *</p> <p><u>C 2x2x 3/16</u></p> <p>M_{MAX} IN B3M #19 @ NODE 17 FOR $DL + \sqrt{x_1^2 + (-x_2)^2 + x_3^2}$ M12 = 3.13 in-h / M13 = 0.011 in-h ✓</p> <p>$\frac{f_{bx2}}{F_{bx2}} + \frac{f_{bx3}}{F_{bx3}} \leq 1.0$ ✓ $F_{bx2} = F_{bx3} = 0.65y = 22 \text{ ksi}$ ✓</p> <p>$f_{bx2} = \frac{(3.13)(1.431)}{0.272} = 16.47 \text{ ksi}$ ✓</p> <p>$f_{bx3} = \frac{(0.011)(1.431)}{0.272} = 0.06 \text{ ksi}$ ✓</p> <p>16.47 + 0.06 = 16.53 ksi < 22 ksi (O.K.) ✓</p> <p>MAX AXIAL LOAD IN B3M #25 FOR $DL + \sqrt{x_1^2 + (-x_2)^2 + x_3^2}$ ✓ P = 0.86 k / A = 0.715 in² / L = 9" / r_{min} = 0.394 ✓</p> <p>$f_a = \frac{0.86}{0.715} = 1.20 \text{ ksi}$ ✓</p> <p>$K/L/r = \frac{9}{.394} = 10.15$ ✓ $F_a = 21.15 \text{ ksi}$ ✓</p> <p>1.20 < 21.15 ksi (O.K.) ✓</p> <p>* NES COMPUTER OUTPUT BINDER S-64</p>	

STRESS SUMMARY

REF.

1 7/8 x 1/8 UNISTRUT P-1000

MAX MOMENT @ NODE 19. $M_2 = 1.63 \text{ in-k}$
 $M_3 = 0.68 \text{ in-k}$



$I_2 = 0.186 \text{ in}^4$
 $I_3 = 0.239 \text{ in}^4$

$F_b = 25 \text{ ksi}$


$f_{bx2} = \frac{(1.63)(0.912)}{.186} = 8.03 \text{ ksi}$

$f_{bx3} = \frac{(0.68)(.8125)}{.239} = 2.31 \text{ ksi}$

$8.03 + 2.31 = 10.34 \text{ ksi} < 25 \text{ ksi} \quad (\text{OK})$

1 5/8 x 7/8 UNISTRUT P-3300

MAX MOMENT .13M⁵⁴ OR 72. $M_3 = \frac{(.925)(19)}{4} = 1.49 \text{ in-k}$




$f_{bx3} = \frac{(1.49)(0.5128)}{0.040} = 19.1 \text{ ksi} < 25 \text{ ksi}$
 (O.K.)

1-B GEN BUS BATTERY RACK

REF.

OVERTURNING



$\sum M_O = 0 \quad 0.315W \times 15.25'' + 0.315W \times 33.25'' = 15.28W \checkmark$

$M_{RESIST.} = 0.79W(8'' + 22'') = 23.7W \checkmark$

FACTOR OF SAFETY = $\frac{23.7W}{15.28W} = 1.55 > 1.50 \checkmark$ (O.K)



NUCLEAR ENERGY SERVICES

BY TS DATE 5-6-81 PROJ. 5701 TASK 063
CHKD. P.17 DATE 8-17-81 PAGE 25 OF
CACIBUR 1-13 GEN BLDG BATTERY RACK

STRESS SUMMARY

REF.

ANCHOR BOLT @ NODE 31

STARDYME 3.0
PIZINTUT 56700HZ

	X1	X2	X3
DL	0.022 ✓	-0.013 ✓	-0.19 ✓
X1 DIR	0.138 ✓	-0.023 ✓	-0.246 ✓
+X2 DIR	-0.019 ✓	0.073 ✓	0.264 ✓
-X2 DIR	0.022 ✓	-0.097 ✓	-0.3 ✓
X3 DIR	0.005 ✓	-0.003 ✓	-0.041 ✓
$\sqrt{x1^2+x2^2+x3^2}$	0.139 ✓	0.077 ✓	0.363 ✓
$\sqrt{x1^2+(-x2)^2+x3^2}$	0.140 ✓	0.052 ✓	0.39 ✓

X1 - DL ± $\sqrt{x1^2+(-x2)^2+x3^2} = 0.022 ± 0.140 = 0.162^k$ ✓ } SHEAR

X2 - DL ± $\sqrt{x1^2+x2^2+x3^2} = -0.013 ± 0.077 = -0.09^k$ ✓ }

X3 - DL ± $\sqrt{x1^2+(-x2)^2+x3^2} = -0.19 ± 0.39 = 0.20^k$ TENSION

RESULTANT SHEAR = $\sqrt{0.162^2 + (-0.09)^2} = 0.185^k$ ✓

TENSION = 0.20^k ✓

EXISTING BOLTS 3/8" RED HEAD SELF DRILLING ANCHORS

~~USE 1/4" x 3" WES IT ANCHOR BOLTS~~

RED HEAD
CATALOG
F-1000

ULTIMATE CAPACITY : TENSION = ~~2973~~ ✓ 5670
SHEAR = ~~3316~~ ✓ 3370

ALLOWABLE CAPACITY TENSION = ~~2973/4 = 618~~ ✓ 5670/5 = 1134
SHEAR = ~~3316/4 = 829~~ ✓ 3370/5 = 674

~~$\frac{200}{618} + \frac{185}{829} < 1.0$
 $0.324 + 0.224 = 0.548 < 1.0$
1/4" 3" WES-175 (O.K.)~~

$\frac{200}{1134} + \frac{185}{674}$
 $0.18 + 0.27 = 0.45 < 1.0$
EXISTING BOLTS (O.K.)

Revised
2/18/82
TS


REF.

CONCLUSION

THE 1-B GENERATOR BLDG BATTERY RACK
 IS CAPABLE OF WITHSTANDING SEISMIC
 LOADS WITHOUT MODIFICATION. HOWEVER
 ANCHOR BOLTS MUST BE PROVIDED IF
 RACK IS NOT PRESENTLY BOLTED TO FLOOR.

BOLT CAPACITY REQUIRED: 210⁰⁰ TENSION ✓
 185⁰⁰ SHEAR ✓

~~1/4" x 3" LG RED-HEAD ANCHOR BOLTS ADEQUATE ✓~~
~~2 BOLTS PER FRAME ✓~~



ANCHOR
 BOLTS
 REQUIRED

- 1. PROVIDE $\frac{3}{8}$ " BOLTS IN EXISTING RED HEAD
 SELF DRILLING ANCHORS



NUCLEAR ENERGY SERVICES

BY TS DATE 7/3/81 PROJ. 5101 TASK 063

CHKD. P.P. DATE 9-6-81 PAGE 1 OF

LACBWR

GENERATOR BATTERY RACK

SK-5101-063-Z

REF.


⑥ CROSS BEAM

FRAME SPACING $\approx 11'-0"$

BATTERY WT = 190# EACH

ASSUME 2g ACCELERATION

BEAM LOAD = $190 \times 2g \times \frac{12}{8.5} = 395$ $\frac{lb}{ft}$ ✓



$M_{max} = \frac{1}{8}(0.395)(11.0)^2 = 5.97$ $ft-k$ ✓

FOR TUBE $F_y = 96$ ksi

$F_b = 0.66 F_y = 30.36$ ksi ✓

$S_{REQ} = \frac{5.97 \times 12}{30.36} = 2.36$ in^3 ✓

TUBE 3x3x $\frac{5}{16}$ $S_x = 2.39$ in^3 ✓

BOLT CONNECTION

FOR A 307 BOLT $\frac{3}{4}$ ϕ $F_t = 10.0$ ksi

$f_t = \frac{2.17}{10.492} = 0.207$ $ksi < 10.0$ (0.2K) ✓



8TH
S 20
AISC
5-24

8ED
AISC
4-5

GENERATOR BATTERY RACK

REF.

3 CENTER FRAME (CARRY REACTION FROM 2-CROSS BEAMS)



$F_{AC} = 13.5 \text{ k (C)} \checkmark$
 $F_{AC} = 11.69 \text{ k (T)} \checkmark$

$M_{MAX} = (2.91)(16) = 38.6 \text{ k-in}$

MEMBER AC TUBE $3 \times 3 \times \frac{5}{16}$ $A = 3.11 \text{ in}^2$ $S = 2.39 \text{ in}^3$

$f_c = \frac{11.69}{3.11} = 3.76 \text{ ksi } \checkmark$

$f_b = \frac{38.6}{2.39} = 16.15 \text{ ksi } \checkmark$

$\frac{f_c}{0.6F_y} + \frac{f_b}{F_b} \leq 1.0 \quad \frac{3.76}{0.6(46)} + \frac{16.15}{30.36} = 0.67 < 1.0 \text{ (O.K.)}$

AISC
1.6.2

MEMBER AB TUBE $2 \times 2 \times \frac{1}{4}$ $A = 2.09 \text{ in}^2$ $r_g = 0.742 \text{ in}$

$L = 39.72 \text{ in}$ $KL/r_g = \frac{117(39.72)}{0.742} = 53.53 \checkmark$ $F_c = 22.24 \text{ ksi } \checkmark$

AISC
1.5.1.3



$f_c = \frac{13.5}{2.09} = 6.46 \text{ ksi (O.K.)}$

GENERATOR BATTERY RACK

REF.

③ CENTER FRAME


BASE TB - MEMBER AB



WITH 2 $\frac{3}{4}$ " BOLTS SHEAR = $\frac{6.75}{2} = 3.38$ k/BOLT ✓

SHEAR CAPACITY = $\frac{27.6 \times 0.9}{4} = 6.21$ k/BOLT ✓

BASE TB - MEMBER AC



USE 4- $\frac{3}{8}$ " WES-IT BOLTS

TENSION = $\frac{11.69}{4} = 2.93$ k/BOLT ✓

SHEAR = $\frac{1.93}{4} = 0.48$ k/BOLT ✓

BOLT CAPACITY

TENSION = 4.89 k/BOLT ✓

SHEAR = 6.21 k/BOLT ✓





PLATE THICKNESS

$$M = 2 \times 2.93 \times 2.25 = 13.2 \text{ k}$$

$$t = \sqrt{\frac{(13.2)(6)}{(27)(10)}} = 0.54 \text{ inches}$$

USE $\frac{3}{4}$ " PL



NUCLEAR ENERGY SERVICES

BY 1-2 DATE 5-7-81 PROJ. 3101 TASK 400-3

CHKD. R.P. DATE 4-7-81 PAGE 7 OF

LACBWR

GENERATOR BATTERY RACK

REF.

CHECK PRYING

$$T = 2.93 \text{ k/BOLT}$$

$$a = 1.25 \text{ "}$$

$$b = 2.25 \text{ "}$$

$$d = 0.75 \text{ "}$$

$$d' = 0.8125 \text{ "}$$

$$p = 5 \text{ "}$$

$$t_f = 0.75 \text{ "}$$

$$b' = b - d/2 = 2.25 - 0.75/2 = 1.875 \text{ " } \checkmark$$

$$a' = a + d/2 = 1.25 + 0.75/2 = 1.625 \text{ " } \checkmark$$

$$\delta = 1 - d'/p = 1 - \frac{0.8125}{5} = 0.8375 \text{ "}$$

$$m = p t_c^2 F_j / 8 = (5.0)(.75)^2 (36) / 8 = 12.66 \text{ " } \checkmark$$

$$\alpha = (Tb/m - 1) / \delta = [(2.93)(2.25) / 12.66 - 1] / 0.8375 = -0.57 \text{ " } \checkmark$$

$\alpha < 0 \therefore$ PRYING FORCE = 0

$$\frac{2.93 \text{ k}}{4.84 \text{ k}} + \frac{0.48 \text{ k}}{6.21 \text{ k}} = 0.68 < 1.0 \quad 4 \cdot \frac{3}{4} \text{ " BOLTS OK. } \checkmark$$


3th
ED.
AISC
1998
-4-90

GENERATOR BATTERY RACK

REF.

END SUPPORT UPPER SHELF

(4)



HORIZONTAL LOAD = 30 BAT. x 190# x 2g = 8.9 k ✓

SHEAR FORCE ON BOLTS = 8.9 x 0.707 = 5.99 k ✓

WITH 2 - 3/4" Ø BOLTS

SHEAR FORCE = 2.97 k / BOLT ✓

SHEAR CAPACITY = $\frac{27.6 \times 0.9}{4} = 6.21$ k / BOLT ✓ CATALOG #466-B

WITH 2 - 1/2" Ø BOLTS

SHEAR CAPACITY = $\frac{22.6 \times 0.9}{4} = 5.09$ k / BOLT > 2.97 k (O.K.)

CATALOG #466-B

USE 2 - 5/8" Ø x 4 1/2" LG WES-IT ANCHOR BOLTS

EMBEDMENT = 3 1/4"

FROM WES-IT CATALOG #1182 INTERPOLATE CAPACITY FOR $f_c' = 3500$ psi

f_c'	ULT. SHEAR
3000 psi	10719 LBS
3500	14367
4000	15583

Revised
1/5/83
TSS

ALLOWABLE SHEAR CAPACITY = $\frac{14367}{4} = 3592$ k > 2.97 k (O.K.)

ACTUAL SHEAR FORCE / BOLT = $\frac{5.99}{2} = 2.97$ k ✓



GENERATOR BATTERY RACK

REF.

⑤ END SUPPORT LOWER SHELF

REVISED BOLT SIZE

USE 1.5 x PEAK G = 1.5 x 0.794 = 1.129'



SEISMIC

HORIZONTAL LOAD = 30 BATT. x 140[#] x 1.129 = 4.70^k

SHEAR FORCE ON BOLTS = 4.7 x 0.707 = 3.32^k

USE 4 - 1/2" WES-IT'S


SHEAR / BOLT = 3.32 / 4 = 0.83^k / BOLT

WES-IT CATALOG #98/
 ALLOWABLE SHEAR
 CAPACITY =
 $\frac{9.55}{4} = 2.46$ ^k / BOLT

DEAD LOAD 3x3x5/16 TUBE - 10.58[#] / I

W = 10.58 x 2' x 1' = 21.16[#] = 254[#]

BENDING, TORSIONAL MOMENTS = 254 x 0.707 = 180[#]




1/2" WES-IT
 2 1/4" EMBEDMENT
 ALLOWABLE
 TENSION = $\frac{5.71}{4}$
 = 1.30^k

TENSION IN BOLT

180 = 2T x 8.75"
 T = 10.3[#] / BOLT


$\frac{0.01}{1.30} + \frac{0.84}{4.91} = 0.18 < 1.0$




(4) 1/2" x 3 1/2" CG
 WES-IT'S O.K.

SHEAR IN BOLT

4(5.30) = 150
 V = 5.5[#] / BOLT






GENERATOR BATTERY RACK

REF.

② END SUPPORT - LOWER SHELF




$$F_{AB} = \frac{8.4}{\sin 30} = 16.8 \text{ k (C)}$$

$$F_{AC} = 16.8 \times \cos 30 = 14.5 \text{ k (T)}$$

BASE PLATE - AC USE 4 - 3/4" ϕ WED-ITS

$$\text{LOAD/BOLT} = 14.5/4 = 3.64 \text{ k}$$



TENSION CAPACITY = 9.89 k/BOLT

PLATE THICKNESS $M = 2 \times 2.25 \times 3.64 = 16.4 \text{ k}$

$$t = \sqrt{\frac{(16.4)(6)}{(27)(10)}} = 0.60 \text{ inch} \checkmark \text{ USE } 3/4 \text{ PLATE} \checkmark$$

WELD CAPACITY

$$12 \times 1/4 \times 0.707 \times 21 \text{ ksi} = 99.5 \text{ k} > 14.5 \text{ k (OK)}$$

BASE PLATE - MEMBER AB


$$\text{SHEAR} = 8.4 \text{ k} \checkmark \text{ USE } 2 \text{ } 3/4 \text{ } \phi \text{ WED-ITS } \cdot 4.2 \text{ k/BOLT}$$

$$\text{SHEAR CAPACITY} = 6.21 \text{ k/BOLT}$$


GENERATOR BATTERY RACK

REF.

① END SUPPORT - TOP SHELF



REVISED TS
5/3/82
SEE PAGE 9



$\phi = 11 \frac{3}{4} \times 3 \frac{3}{4} \times 1 \frac{1}{2}$

USE 4 - $\frac{3}{16}$ " ϕ A307 BOLTS
8 LB

BOLT CAPACITY
 TENSION: $\frac{25720.9}{4} = 572^k$
 SHEAR: $\frac{32 \times 0.9}{4} = 72^k$

SECT A-A

ASSUME RIGID BASE

ΣM EDGE R

$$2T_1(10.25) + 2T_2(1.5) = (8.4^k)(8.75") \quad T_2 = 0.16T_1$$

$$20.94T_1 = 73.5$$

$$T_1 = 3.59^k/\text{ROLT} \checkmark$$


$$\text{SHEAR: } 8.4^k/4 = 2.1^k/\text{ROLT} \checkmark$$

$$\frac{3.59}{5.72} + \frac{2.1}{72} = 0.92 < 1.0 \checkmark (O.K.)$$


GENERATOR BATTERY RACK

REF.

① END SUPPORT - TOP SHELF REVISED BOLT SIZE



USE 1.5 X PEAK G MEZZ. BR.
 $1.5 \times 0.744g = 1.12g \checkmark$
 HORIZ. LOAD =
 $30 \text{ BAT.} \times 190 \text{ lb} \times 1.12g = 4.70 \text{ k} \checkmark$



$E = 11 \frac{3}{4} \times \frac{3}{4} \times 1 \frac{1}{2}$
 USE 4 $\frac{3}{8}$ " ϕ UES-IT BOLTS
 6" LG. UES-IT CAP. #981
 BOLT CAPACITY - $F_c = 3500 \text{ PSI}$
 TENSION: $\frac{19377}{4} = 4.84 \text{ k} \checkmark$
 SHEAR: $\frac{19634}{4} = 4.91 \text{ k} \checkmark$

SECT A-A

ASSUME RIGID BASE

EM EDGE R

$$2T_1(10.25) + 2T_2(1.5) = (4.7 \text{ k})(8.75 \text{ in}) \quad T_2 = 0.46T_1$$

$$20.94 T_1 = 41.125 \text{ k-in}$$

$$T_1 = 2.02 \text{ k/ROLT} \checkmark$$

SHEAR: $4.7 / 4 = 1.18 \text{ k/ROLT} \checkmark$

$$\frac{2.02}{4.84} + \frac{1.18}{4.91} = 0.66 < 1.0 \text{ (O.K.)}$$



NUCLEAR ENERGY SERVICES

NITROGEN TANK BRACKET, SK-5101-063-3



REF.

Assume:

Maximum G will be upper floor spectra EL 701


PEAK G-LEVEL = 4.13 G (FIGURE G.14) GULF UNITED REPORT SS-1162

SECTION PROPERTIES FOR
PLATE $10\frac{3}{4} \times 3 \times \frac{1}{2}$



$$I = \frac{bh^3}{12}$$

$$S = \frac{bd^2}{6} = \frac{3 \times 5^2}{6} = 0.125 \text{ in}^3$$



$$W = 177 \text{ # FULL}$$

$$\frac{57''}{2} = 28.5''$$

$$R_1 + R_2 = W \times 4.13$$

$$\sum M_{R_2} = 0$$

$$4.13W(28.5 - 18) = R_1(42 - 18)$$

$$R_1 = 319.82 \text{ #}$$

$$R_2 = 411.19 \text{ #}$$


$$\text{Tension} = \frac{411.19 \times 4}{5} = 329 \text{ ksi}$$

$$\text{STRESS} = \frac{329}{5} = 65.8 \text{ ksi}$$

$$M_{\text{MAX}} = 411.19 \times \frac{9.5}{2} = 1953 \text{ in-#}$$

$$F_b = \frac{M}{S} = \frac{1953}{0.125} = 15,624 \text{ ksi}$$

$$\text{MAX STRESS} = \sqrt{0.293^2 + 15.62^2} = 15.62 \text{ ksi}$$



NUCLEAR ENERGY SERVICES

NITROGEN TANK BRACKETS

SK-5101-063-3

REF.

CHECK WELDS

$SW = bd = 3 \times .5 = 1.5$ ✓

$F_w = \frac{M}{S_w} = \frac{1.95}{1.5} = 1.3 \text{ ksi}$ ✓


BENDING STRESS = $\frac{1.3 \text{ ksi}}{.707 \times .25 \times 1} = 7.36 \text{ ksi}$ ✓

SHEAR STRESS = $\frac{.411}{.707 \times .25 \times 3 \times 2} = 0.388 \text{ ksi}$ ✓

TENSION STRESS = $\frac{P}{A} = \frac{.411}{.707 \times .25 \times 3 \times 2} = 0.389 \text{ ksi}$ ✓

RESULTANT STRESS = $\sqrt{7.36^2 + 2(.388)^2} = \sqrt{54.47} = 7.38 \text{ ksi} < 21.0 \text{ ksi}$ ✓

BRACE PLATE



$M_{max} = \frac{(0.41)(9.5)}{4} = 0.97 \text{ k-in}$ ✓

$S = \frac{1}{6}(3 \times .25)^2 = .031 \text{ in}^3$ ✓

$f_b = \frac{.97}{.031} = 31.3 \text{ ksi}$ ✓


$F_b = 0.75 F_y = 27.0 \text{ ksi}$ ✓

FOR SSE $F_b = 1.6 \times 27.0 = 43.2 > 36 \text{ ksi}$


USE $F_b = 36 \text{ ksi}$ ✓

3/4" WES-IT ANCHOR BOLTS

2 BOTTLE RACK



$T = 0.41 \text{ k/BOLT}$ ✓



$\Sigma M = 0$

$22.25 T = (2 \times .41)(5)$

$T = 0.18 \text{ k/BOLT}$ ✓

$V = 0.41 \text{ k/BOLT}$ ✓

3/4" 4 x 6" LG WES-ITS

SRSS $T = \sqrt{.41^2 + .18^2} = 0.45 \text{ k}$ ✓

ULT. CAP.

TENSILE 19.3 k SHEAR 27.8 k

1/2 CAP (FS=4)

45.4 k 6.21 k

$\frac{0.45}{45.4} + \frac{0.41}{6.21} =$

$0.16 < 1.0$ ✓



NUCLEAR ENERGY SERVICES

480 ESSENTIAL BUSS (PENETRATION ROOM)

REF.

SK-5101-063-4


ASSUME WT = 3000 ^{lb}

HORIZONTAL G-VALUE
= .21 x 1.5 = 0.315 ✓

VERTICAL G-VALUE =
 $\frac{2}{3}$ HORIZONTAL = 0.21 ✓

$F_H = 0.315 \times 3 = 0.945$ ^{kl} ✓

$F_V = 0.21 \times 3 = 0.63$ ^{kl} ✓



ΣM_A

$M_B = 0.945 \times \frac{96}{2} = 42.53$ ^{in-k} ✓

$M_S = (3.0 - 0.63) \frac{36}{2} = 42.66$ ✓

F.S. = $\frac{M_S}{M_B} = \frac{42.66}{42.53} = 1.003$ ✓


USE BRACKET TO ENSURE STABILITY
SINCE WEIGHT IS ONLY ESTIMATED.



NUCLEAR ENERGY SERVICES

480 ESSENTIAL BUS (PENETRATION ROOM)

REF.



$$1k \left(\frac{3}{2} + 2 + 2 \right) = F_T 1.5 \checkmark$$

$$F_T = 3.67 \text{ k} / 2 \text{ BOLTS} \checkmark$$

$$F_T = 1.84 \text{ k} / \text{BOLT}$$

USE $\frac{3}{4}$ WES-11
ANCHOR BOLTS
6"

$$F_{\text{all}} = \frac{20.45}{4} = 5.1 \text{ k} / \text{BOLT} \checkmark$$

CHECK BEAM W6x16

$$M = \left(1 \times \frac{3}{2} + 2 \right) = 3.5 \text{ k-ft} \checkmark$$


$$S_{\text{REQ}} = \frac{3.5 \times 12}{2.16} = 1.95 \text{ in}^3 \quad S_{xx} = 10.2 \text{ in}^3 \text{ OK}$$



NUCLEAR ENERGY SERVICES


480 V ESSENTIAL BUS (PENETRATION RM)

REF.



$\sum M_0 = 0$

$125T_5 + 4.5T_4 + 13T_3 + 16.25T_2 + 24.5T_1 = 70.25(1k) -$



$\frac{T_1}{24.5} = \frac{T_2}{16.25} = \frac{T_3}{13} = \frac{T_4}{4.5} = \frac{T_5}{125} -$
 $T_2 = 0.663 T_1$ $T_4 = 0.184 T_1$
 $T_3 = 0.531 T_1$ $T_5 = 0.051 T_1$

$125(0.051T_1) + 4.5(0.184T_1) + 13(0.531T_1) + 16.25(0.663T_1) + 24.5T_1 = 70.25 -$

$43.069 T_1 = 70.25$

$T_1 = 1.63 \text{ k/BOLT}$

3/4" x 6" LG WES-IT CAPACITY

FOR BOLT SPACING = 3.95"

CATALOG #951 FOR $f'_c = 3500 \text{ psi}$
 INTERPOLATE BETWEEN $f'_c = 2000, 4000 \text{ psi}$

CAPACITY: $\frac{3.95}{7.5} = 0.527$

NET CAPACITY ALLOWABLE (FSCA)

MAXIMUM CAPACITY =


TENSION 1938 484
 FOR BOLT SPACING $\geq 10 \times \text{DIAMETER}$

$484 \times 0.527 = 2.55 \text{ k/BOLT}$
 ACTUAL LOAD: 1.63 k/BOLT

REACTOR BATTERY RACK SK-5101-063-6

REF.


STARDYNE MODEL FOR COMPUTER PROGRAM
NES COMPUTER BINDER S-60 =



REACTOR BATTERY RACK

REF.

BEAM PROPERTIES - STARDYNE BPROPI, BPROPZ



$$A = 2.59 \text{ in}^2$$

$$I_x = I_y = 3.16 \text{ in}^4$$

$$J = 5.19 \text{ in}^4$$

SHEAR SHAPE FACTORS


$$SF_2, SF_3 = 0.50$$

CTORS

$$\frac{T \times \text{CTORS}}{J} = \frac{T}{2At}$$

$$\text{CTORS} = \frac{J}{2At} = \frac{5.19}{(2)(2.75)^2(0.25)} = 1.373 \text{ in} \checkmark$$

SHEAR STRESS FACTOR SSF2, SSF3



$$\tau_{\text{MAX}} = \frac{VQ}{Ib}$$

$$Q = (3)(.25)(1.375) + 2(1.25)(.75)(0.625)$$

$$Q = 1.42 \text{ in}^2 \checkmark$$

$$\tau_{\text{MAX}} = \frac{V(1.42)}{(3.16)(2)(.25)} = 0.90 \text{ V} \checkmark$$

$$\tau_{\text{AVG}} = \frac{V}{2.59} = 0.386 \text{ V}$$

$$SSF_2 = SSF_3 = \frac{0.90 \text{ V}}{0.386 \text{ V}} = 2.33 \checkmark$$

REACTOR BATTERY RACK

REF.


BATTERIES

WT - 85# EACH ✓
 WIDTH = 4 7/8" DEPTH = 10 1/2"
 15 / SHELF ✓


LOAD IN X1 DIRECTION

CONC. LOAD = $\frac{85}{10.5} \times 29 \times 15 = 2.55 \text{ k} \checkmark$

UPPER SHELF



LOWER SHELF



LOADS IN X2 DIRECTION

UPPER SHELF - BEAM 26 LOADED

DIST. LOAD = $\frac{85 \times 29}{4.625 + 0.5} \times 2 \text{ ROWS} = 0.066 \text{ k/in} \checkmark$

LOWER SHELF - BEAMS 28, 30 LOADED

DIST. LOAD = $\frac{85 \times 29}{5.125} = 0.033 \text{ k/in} \checkmark$

$M_{MAX} = \frac{wL^2}{8} = \frac{(0.066)(79.75)^2}{8} = 52.47 \text{ in-k}$

TS - 3x3x1/4 S = 2.10 IN³ $f_b = \frac{52.47}{2.10} = 25 \text{ ksi}$

GENERATOR BATTERY RACK

REF.

BASE PLATE DETAILS - END FRAME

$$\sqrt{(X1 DIR)^2 + (X2 DIR)^2}$$

	<u>FX1</u>	<u>FX2</u>	<u>FX3</u>
<u>END FRAME</u> <u>NODE 8</u>	0.59 ^k ✓	2.80 ^k ✓	4.88 ^k ✓

LOADS FROM POST RUN PAGE 4

END NODE 8 SHEAR = $\sqrt{(0.59)^2 + 2.8^2} = 2.86^k$ ✓
 TENSION = 4.88^k

USE 2 $\frac{3}{4}$ " ϕ WES-IT BOLTS

SHEAR = 1.43^k/BOLT ✓
 TENSION = 2.44^k/BOLT ✓

BOLT CAPACITY:

TENSION = $\frac{21.53 \times 0.9}{4} = 4.84^k$ ✓
 SHEAR = $\frac{27.61 \times 0.9}{4} = 6.21^k$ ✓

$\frac{2.44}{4.84} + \frac{1.43}{6.21} = 0.73 < 1.0$

2 - $\frac{3}{4}$ " ϕ BOLTS OK




PLATE THICKNESS REQ'D

$m = 2.44^k \times 2.25" = 5.49^k$ ✓

$t = \sqrt{\frac{(5.49)(6)}{(27)(15)}} = 0.49$ ✓

USE $\frac{3}{4}$ " PL

GENERATOR BATTERY RACK

REF.

BASE PLATE - BRACING STRUT

	F_{x1}	F_{x2}	F_{x3}	
2 BRACING STRUTS				
NODE 11	2.89 ✓	0.16 ✓	4.89 ✓	$\sqrt{(X1 DIR)^2 + (X2 DIR)^2}$
NODE 12	2.88	0.16	4.83	
REVISED - USE 1 STRUT	5.78 ^k ✓	0.32 ^k ✓	9.68 ^k ✓	

USE 4 - 3/4" ϕ WES-ITS

SHEAR = $\sqrt{5.78^2 + 0.32^2} = 5.79^k = 1.45^k / \text{BOLT}$

TENSION = 9.68^k = 2.42^k / BOLT ✓

BOLT CAPACITY = TENSION = 4.84^k ✓
 SHEAR = 6.21^k ✓

$\frac{2.42}{4.84} + \frac{1.45}{6.21} = 0.73 < 1.0$ 4 BOLTS (O.K.)




PLATE THICKNESS

$M = 2.42^k \times 2 \times 2.25^k = 10.89^k$

$t = \sqrt{\frac{(10.89)(6)}{(27)(10)}} = 0.49^k$ ✓


USE 3/4" PL

REACTOR BATTERY RACK

REF.

SUMMARY OF TUBE STRESSES 3x3x1/4

FROM STADYNIC POST RUN $\sqrt{\frac{x_1^2}{D_{IR}} + \frac{x_2^2}{D_{IR}}}$ ✓



MAX. BENDING STRESS IN END FRAME IN $3M^{-2}$ ✓

$M_2 = 5.46 \text{ ksi} / M_3 = 7.56 \text{ ksi}$ ✓

AXIAL STRESS = $2.09 \text{ ksi} / l = 16.8''$ $KQ/C = \frac{(1)(16.8)}{1.10} = 15.26$ ✓

$\frac{F_y}{F_a} = \frac{2.09}{20.88} = 0.10 < 0.15$ ✓ $F_a = 20.88 \text{ ksi}$ ✓


USE EQ. 1.6.2

$\frac{2.09}{20.88} + \frac{7.56}{24} + \frac{5.46}{24} = 0.64 < 1.0$ (O.K.) ✓

8TH
ED
AISC
1.6.1

BRACING STRUT

BRACES #11, #12 REPLACED BY ONE STRUT




∴ ADD AXIAL STRESSES TOGETHER

AXIAL STRESS = $2 \times 2.17 \text{ ksi} = 4.34 \text{ ksi}$ ✓

$l = 38.64''$ $KQ/C = \frac{38.64}{1.10} = 35.2$ ✓

$F_a = 19.56 \text{ ksi} \rightarrow 4.34 \text{ ksi}$ ✓
(O.K.)




NUCLEAR ENERGY SERVICES

BATTERY CHARGERS SK-5101-063-7

REF.


GEN. PLANT BATTERY CHARGER WT. 500# DENSITY: $\frac{500}{72 \times 29 \times 15} = 0.026 \frac{\text{WT}}{\text{IN}^3}$
 ESTIMATE WT REACTOR PLANT CHARGER = $0.026 \frac{\text{WT}}{\text{IN}^3} \times (60 \times 32 \times 22) = 1100 \#$

HORIZONTAL ACCELERATION: 2g
 VERTICAL ACCELERATION: $\frac{2}{3} \times 2g = 1.33g$




ASSUME EXIST. ANCHOR BOLTS IN BASE CARRY BASE SHEAR

X DIRECTION



$\sum M_A = 0$
 $(2200)(30) = 60T$
 $T = 1100 \#$

Z-DIRECTION




$\sum M_B = 0$
 $T = 1100 \#$
 $M_y = 1100 \# \times 29.5 = 27 \text{ IN-K}$

BATTERY CHARGER'S

REF.

Y-DIRECTION



$$M_z = 29.5'' \times .239 \times 1100 = 8.9 \text{ } \checkmark$$

W6 x 15 $A = 4.43 \text{ in}^2$ $S_x = 9.72 \text{ in}^3$ $S_y = 3.11 \text{ in}^3$


TENSION: $f_T = \frac{.1 \text{ }^k}{4.43} = 0.25 \text{ ksi } \checkmark$

BENDING: $f_{Bz} = \frac{8.9}{9.72} = 0.92 \text{ ksi } \checkmark$

$f_{By} = \frac{27}{3.11} = 8.68 \text{ ksi } \checkmark$

RSS TENSION STRESS: $\sqrt{0.25^2 + 0.92^2 + 8.68^2} = 8.73 \text{ ksi } \checkmark$

ANCHOR BOLTS



X-DIR

TENSION = $1 \frac{1}{4}$ BOLTS = $0.275 \text{ }^k \checkmark$

Y-DIR

TENSION = $\frac{8.9 \text{ }^k}{8.5''} = 1.05 \text{ }^k / 2 \text{ BOLTS} = 0.52 \text{ }^k \checkmark$

SHEAR = $0.363 \text{ }^k / 4 \text{ BOLTS} = 0.09 \text{ }^k \checkmark$

Z-DIR

TENSION = $\frac{27}{(8.5 \times 2)} = 1.60 \text{ }^k / \text{BOLT } \checkmark$

SHEAR = $1 \frac{1}{4} = 0.275 \text{ }^k / \text{BOLT } \checkmark$

RSS FORCES

TENSION = $\sqrt{0.275^2 + 0.52^2 + 1.60^2} = 1.70 \text{ }^k \checkmark$

SHEAR = $\sqrt{0.09^2 + 0.275^2} = 0.29 \text{ }^k \checkmark$

BATTERY CHARGERS

REF.

USE 4-3/4" WED-ITS

BOLT CAPACITY - TENSION = 9.89 k/BOLT CATALOG #468-B
 ALLOWABLE (FS=4) SHEAR = 6.21 k/BOLT

$$\frac{170^k}{9.89^k} + \frac{0.29^k}{6.21^k} = 0.90 \leq 1.0 \text{ (O.K.) } \checkmark$$

EXISTING ANCHORAGE IN BASE: 4-1/4" WEDGE EXPANSION BOLTS

ASSUME CARRY BASE SHEAR

$$RSS \text{ SHEAR FORCE} = \sqrt{1100^2 + 1100^2} = 1556^k / 4 \text{ BOLTS} = 389^k \checkmark$$

ULTIMATE CAPACITY - SHEAR = 2325 k - RED HEAD CAT. F-1000-P56

$$ALLOWABLE \text{ CAPACITY - SHEAR} = \frac{2325}{4} = 581 \leq 7389^k \text{ (O.K.) } \checkmark$$

REACTOR PLANT BATT. CHARGER



1/2" φ BOLTS CHARGER TO C4x7.25

$$RSS \text{ SHEAR FORCE} = \sqrt{2 \times 1100^2} = 1555.6^k = 389^k / \text{BOLT}$$

$$f_v = \frac{389}{126} = 3.09 \text{ ksi}$$

5/8" φ BOLTS CONNECTING C4x7.25'S

$$f_v = \frac{389}{202} = 1.93 \text{ ksi}$$



ASSUME WELDED AND BOLTED CONNECTION EACH CARRY 1/2 OF SHEAR

$$WELD \text{ STRESS } f_v = \frac{777.8}{(12 \times .707)(\frac{3}{16})} = 0.5 \text{ ksi}$$

$$BOLT \text{ STRESS } f_v = \frac{777.8}{2(126)} = 3.08 \text{ ksi}$$




NUCLEAR ENERGY SERVICES


BATTERY CHARGERS

REF.

GENERATOR PLANT CHARGER WT = 800[#]



X AND Z DIRECTIONS



$$\Sigma M_A = 0$$

$$(1600 \times 36) = 72T$$


$$T = 800\# \checkmark$$

AT BASE PLATE $T = 800\#$ (X-DIR) ✓

(Z-DIR) $M_y = 800\# \times 28.75 = 23\# \cdot \text{ft}$ ✓

Y-DIRECTION

$$M_z = 28.75 \times .33 \times 800\# = 7.59\# \cdot \text{ft} \checkmark$$



AT WALL; M_y , M_x AND TENSION FORCE FOR GENERATOR CHARGER ARE SMALLER THAN THOSE FOR REACTOR CHARGER. SINCE W6X15 AND BASE R DETAILS THE SAME, CALCULATIONS WILL NOT BE REPEATED

5/8" BOLTS 2X22" TO W6X15

SRESS SHEAR = $\sqrt{2 \times 800} = 1131.5\# \cdot 282.8\#/\text{BOLT}$


$f_v = \frac{282.8}{202} = 1.4 \text{ ksi}$ ✓

1-A DIESEL BATTERY RACK

SK-5101-063-8

REF.

BATTERY - 19" LONG, 11" HIGH, 9" WIDE ASSUME WT. = 75# EACH
 HORIZ. ACCELERATION = $0.21g \times 1.5 = 0.312g$
 VERT " " = $\frac{2}{3} \times 0.312g = 0.21g$ } FROM HRC SITE SPECIFIC GROUND SPECTRA



$$\sum M_A = 0$$

$$(46.8 \times 42.5) - (118.5)(L) = 32T$$


$$T = 40.0 \# \checkmark$$

USE 2 $\frac{3}{4}$ " WES-IT ANCHOR BOLTS \checkmark

$\frac{1}{2}$ " ϕ x $3\frac{1}{2}$ " LG ALLOWABLE CAPACITY = 1.3 $\frac{L}{BOLT}$ TENSION \checkmark


1-A DIESEL BATTERY RACK

REF.



REVISED 10/1/82
TS

X DIR



$$M_{max} = 9 \frac{1}{2} \times 23.4 = 222 \text{ in} \cdot \text{lb} \checkmark$$


$$f_s = \frac{222}{0.03125} = 7.11 \text{ ksi} \checkmark$$

$$f_T = \frac{23.4}{(3)(.25)} = 0.031 \text{ ksi} \checkmark$$

$$S = \frac{bd^2}{6} \cdot \frac{(3)(.25)^2}{6} = 0.03125 \text{ in}^3$$

ANCHOR BOLTS
TENSION = 23.4 #/BOLT ✓

Z DIR



$$M_{max} = 46.8 \times 5.75 = 269 \text{ in} \cdot \text{lb} \checkmark$$

$$f_s = \frac{269}{0.03125} = 8.61 \text{ ksi} \checkmark$$

ANCHOR BOLTS

$$S/M_0 = 0$$

$$46.8 \times 5.75 = 125 \text{ T} \checkmark$$

$$T = 215.3 \text{ #/BOLT} \checkmark$$

$$V = 46.8 \text{ #/BOLT} \checkmark$$

Checked DLS
10/6/82



NUCLEAR ENERGY SERVICES

BY TS DATE 10/1/82 PROJ. 5701 TASK 063

CHKD. DW DATE 10/6/82 PAGE 3 OF 3

LACBWR ELECT. EQUIP

1-A DIESEL BATTERY RACK

REF.

ANCHOR BOLTS

RSS FORCES

$$TENSION = \sqrt{23.4^2 + 215.3^2} = 216.5 \# \checkmark$$

$$SHEAR = 46.8 \#$$

$\frac{1}{2}$ " ϕ X $3\frac{1}{2}$ LG. WES-IT ANCHOR BOLTS

$F_c = 3500$ PSI CATALOG # 981

$2\frac{1}{2}$ " EMBEDMENT

	ULTIMATE CAPACITY	ALLOWABLE CAPACITY
TENSION	5.21 kJ	1.30 kJ
SHEAR	9.85 kJ	2.46 kJ

$$\frac{.217}{1.30} + \frac{.05}{2.46} = 0.187 < 1.0$$


1-B DIESEL GENERATOR CONTROL PANEL

REF.

H x W x D SK-5101-063-9
 6'-0" 2'-6" 1'-1"


1.5 x PEAK HORIZ. ACCELERATION FROM NRC SITE SPECIFIC
 GROUND SPECTRA = $1.5 \times 0.21g = 0.315g$

VERTICAL ACCELERATION = $\frac{2}{3} \times 0.315g = 0.21g$



$\Sigma M_A = 0$
 $M_{RESIST} = 0.79W \times \frac{13}{2} = 5.135W$
 $M_{OVER} = 0.315W \times \frac{72}{2} = 11.34W$
 OVERTURNING
FIX REQUIRED


ASSUME WEIGHT = 1000 #



$\Sigma M_A = 0$
 $790 \times \frac{13}{2} + 77T = 315 \times \frac{72}{2}$
 $T = 80.6 \#$

1-B DIESEL GENERATOR CONTROL PANEL

REF.



$$M_{max} = \frac{(1.0806 \text{ k})(10.625)}{4} = 0.21 \text{ in-k} \checkmark$$

FOR $3 \times \frac{1}{4}$ BAR $s = \frac{1}{6}(\pi)(.25)^2 = .03125 \text{ V}$

$$f_b = \frac{.21}{.03125} = 6.72 \text{ ksi} < 27 \text{ ksi} \checkmark$$

$\frac{1}{2}$ " ϕ \times $3 \frac{1}{2}$ " LG WES-IT ANCHOR BOLTS

$2 \frac{1}{2}$ " EMBEDMENT $f'_c = 3500 \text{ psi}$ CATALOG #981

f'_c	WT CAP #	TENSION
4000	5789	
3500	5210	
2000	3473	

ULT. CAPACITY: 5.21 k

ALLOWABLE CAPACITY: 1.30 k $>$ 0.04 k \checkmark

1-B GENERATOR BLDG ELECT. EQUIP?


REF.

② 125 V DC DIESEL BLDG MAIN DIST BUS.

③ MCC 480-V

SK-5101-063-10

RESTRAINT @ TOP



ASSUME WT = 2000 #

$\Sigma M_A = 0$

$$(0.79)(2000)(10) + 92T = (0.315)(2000)\left(\frac{92}{2}\right)$$

$$T = 143 \# \checkmark$$

USE $\angle 3 \times 3 \times \frac{1}{4}$ $A = 1.44 \text{ IN}^2$ $f_{MIN} = 0.592 \# \checkmark$

g-LEVEL

1.5 X PEAK HORIZ. ACCELERATION FROM NRC SITE SPECIFIC GROUND SPECTRA

$$0.21g \times 1.5 = 0.315g \checkmark$$


$$\text{VERTICAL g-LEVEL} = \frac{2}{3} \times 0.315g = 0.21g \checkmark$$



NUCLEAR ENERGY SERVICES

1-13 DIESEL BLDG - ELECT. PANELS

REF.



USE $3 \times 3 \times \frac{1}{4}$ $S = 0.577 \text{ in}^2$

MOMENT @ PT B $\cdot 145 \times 14.69 = 2130 \text{ in}^2$

$$f_b = \frac{2130 \cdot k}{0.577} \therefore 3.69 \text{ ksi} < 22 \text{ ksi}$$

MAX. COMPRESSIVE CAPACITY

$$K_{1,2} = \frac{67.5}{(1)(65.625)} = 114.02 \quad F_c = 11.13$$

$$F_c = 11.56 \text{ ksi}$$

$$P_n = 11.56 \times 1.94 \text{ in}^2 = 22.43 \text{ k}$$

$$16.03 \text{ k}$$

ALL CONNECTIONS $\cdot \frac{3}{4}$ " A325 BOLTS


SHEAR CAPACITY = 7.7 k/BOLT

APPLIED LOADS ARE SMALL COMPARED TO MEMBER CAPACITY

1-B DIESEL BLDG - ELECT. EQUIP. PANELS

REF.

CONNECTION TO MCC 480-V BUS



REVISED
1/11/83
TS

$$M_{MAX} = \frac{150(22)}{4} = 825 \text{ in-lb}$$

$$C4x5.4 \quad S_x = \frac{1.93 \text{ in}^3}{2.29} \quad f_b = \frac{0.825}{2.29} = 0.360 \text{ ksi} < 22 \text{ ksi}$$

1/2" BOLTS - A307

$$SHEAR = 150/4 = 37.5 \text{ lb/BOLT} \quad F_v = \frac{\pi}{4} (.5)^2 (10.0 \text{ ksi}) = 196 \text{ lb}$$



1/4" BOLTS - A307

$$SHEAR = 150/16 = 9.375 \text{ lb/BOLT} \quad F_v = \frac{\pi}{4} (.25)^2 (10) = 0.49 \text{ lb/BOLT}$$

1-B DIESEL BLDG - ELECT. EQUIP. PANELS

REF.

CONNECTION TO 125-V DC BUS



REVISED
11/1/83
TS

$$M_{max} = \frac{(150 \text{ lbs})(22.125 \text{ in})}{4} = 830 \text{ in-lb}$$

$$S_x = \frac{2.29}{1.93} \text{ in}^3 \quad f_b = \frac{.83}{1.93} = 0.43 \text{ ksi} < 22 \text{ ksi}$$

BOLT LOAD

RESULTANT SHEAR = 75 #/BOLT


1/2" A307 BOLT $F_u = 10 \text{ ksi}$

$$\text{SHEAR CAPACITY} = \frac{F_u}{4} (.5)^2 \times 1.0 = 1.96 \text{ k} > 0.075 \text{ k}$$

(OK)

REACTOR WATER LEVEL TRANSMITTERS #1, 2 SK-5101-063-12

REF.



ASSUME WEIGHT EACH TRANSMITTER = 50 lb V

SSE g-LEVEL = 2.58g HORIZONTAL CEL 667' GULF UNITED REPORT 55-1162


$\frac{2}{3} \times 2.58g = 1.72g$ - VERTICAL ✓

X-DIR.

$F_x = 2.58g \times 1.5 \times 0.050^k = 0.194^k$ / TRANSMITTER ✓

$M_z = 0.194^k \times 6'' = 1.16^{in-k}$ / TRANS. ✓

$M_y = 0.194^k \times 2'' = 0.39^{in-k}$ / TRANS. ✓




PLAN

$\Sigma M = 0 \quad 42T = (4 \times 0.39^{in-k}) + (4 \times 1.16^{in-k}) 4''$

$T = 0.11^k \quad 0.037^k$ / BOLT V

$V_x = 2 \times 1.16^k = .39^k = .13^k$ / BOLT



ELEVATION

$\Sigma M = 0$



$42V_y = 4 \times 1.16^{in-k}$

$V_y = 0.11^k \quad 0.037^k$ / BOLT V

RX. TRANSMITTERS #1, #2

REF.

Y-DIR DL + SEISMIC $50'' + 50''(1.72g \cdot 1.5) = 0.18'' \checkmark$
 $m_2 = .18'' \times 2'' = 0.36'' \checkmark$



END SUPPORT
ELEVATION



$$M_x = 0.72'' \text{ k} + 4 \times 0.36'' \text{ k} = 2.16'' \text{ k}$$

$$V_y = 0.36'' \text{ k} = 0.12'' \text{ k/BOLT}$$

$$F_z = 0.194'' \text{ k}$$

$$M_x = 6'' \times 0.194'' \text{ k} = 1.16'' \text{ k}$$


Z-DIR



0.75' FORCE $T = .13'' \text{ k/BOLT}$

RY. WATER LEVEL TRANSMITTER #1, #2

REF.



$$\frac{by^2}{2} = A_1(7-y) + A_2(4-y) \checkmark$$

$$\bar{y}^2 = 0.11(7-y) + 0.196(4-y)$$

$$\bar{y}^2 = 1.554 - 0.306\bar{y}$$

$$\bar{y}^2 + 0.306\bar{y} + 0.153^2 = 1.554 + 0.153^2$$

$$(\bar{y} + 0.153)^2 = 1.577$$

$$\bar{y} + 0.153 = \pm 1.256$$

$$\bar{y} = 1.103 \checkmark$$

$$I = \frac{2}{3}\bar{y}^3 + A_1(7-\bar{y})^2 + A_2(4-\bar{y})^2$$

$$I = \frac{2}{3}(1.103)^3 + 0.11(7-1.103)^2 + 0.196(4-1.103)^2$$

$$I = 0.855 + 3.83 + 1.69$$

$$I = 6.37 \text{ in}^4$$

$$\bar{T}_{3/8} = \frac{m(7-1.103)}{6.36} \times 0.11 = 0.102 \text{ m}$$

$$\bar{T}_{1/2} = \frac{m(4-1.103)}{6.36} \times 0.196 = 0.089 \text{ m}$$

REF: M. GUIRE -
STEEL STRUCTURES
 PRENTICE-HALL, 1968
 Pg 840-842



NUCLEAR ENERGY SERVICES

BY TS DATE 12/26/82 PROJ. 5701 TASK 063
CHKD. D.L. Sumner DATE 1/11/83 PAGE OF
LABOR ELECT. EQUIP.

RX. WATER LEVEL FRAMES #1, #2

REF.

BOLT TENSION

X-DIR

$$T_{3/8} = T_{1/2} = .037^k \checkmark$$

Y-DIR $M_x = 2.16^{k \cdot ft} \checkmark$

$$T_{3/8} = 2.16 \times .102 = 0.22^k \checkmark$$

$$T_{1/2} = 2.16 \times .089 = 0.19^k \checkmark$$

Z-DIR $M_x = 2.32^{k \cdot ft} \checkmark$

$$T_{3/8} = .13^k + 2.32 \times .102 = 0.37^k \checkmark$$

$$T_{1/2} = .13^k + 2.32 \times .089 = 0.34^k \checkmark$$

SRSS TENSION

$$T_{3/8} = \sqrt{.037^2 + .22^2 + .37^2} = 0.43^k \checkmark$$

$$T_{1/2} = \sqrt{.037^2 + .19^2 + .34^2} = 0.39^k \checkmark$$

SRSS SHEAR

$$V_x = .13^k$$

$$V_y = \sqrt{.037^2 + .12^2} = .13^k \checkmark$$

$$\text{RESULTANT SHEAR} = \sqrt{.13^2 + .13^2} = 0.18^k \checkmark$$



NUCLEAR ENERGY SERVICES

BY DATE 12/1/82 PROJ TASK 003

CHKD. DL Summer DATE 1/1/82 PAGE OF

LACQWR ELECT. EQUIP

RX WATER LEVEL TRANSMITTERS #1, #2

REF.

3/8 x 2 3/4" WEJ-1T 2 1/2" EMBEDMENT

INTERPOLATE FOR $f'_c = 3500$ PSI CATALOG #1182

EMBED = 2"

	TENSION	SHEAR
ULTIMATE CAPACITY	3771# ✓	4981# ✓
ALLOWABLE CAPACITY (F.S. = 4)	943# ✓	1245# ✓

$$\frac{0.93}{1.942} + \frac{.18}{1.295} = 0.60 < 1.0 \checkmark$$

1/2" RED HEAD SELF DRILLING ANCHOR.

	TENSION	SHEAR
ULTIMATE CAPACITY	850#	6720#
ALLOWABLE CAPACITY (F.S. = 5)	170#	1344#

$$\frac{.39}{1.70} + \frac{.18}{1.344} = 0.363 < 1.0 \checkmark$$

125V DC MAX DC PANEL

REF.

SRSS LOADS

$$F_x = F_z = 0.056 \text{ k} \quad \checkmark \quad F_y = 0.0375 \text{ k} \quad \checkmark$$

$$M_x = 4.34 \text{ ''-k} \quad \checkmark$$

$$M_y = 1.13 \text{ ''-k} \quad \checkmark$$

$$M_z = \sqrt{4.34^2 + 0.75^2} = 4.40 \text{ ''-k} \quad \checkmark$$

DL+SRSS

$$F_x = F_z = 0.056 \text{ k} \quad \checkmark \quad F_y = -0.0875 \text{ k} \quad \checkmark$$

$$M_x = 4.34 \text{ ''-k} \quad \checkmark \quad M_y = 1.13 \text{ ''-k} \quad \checkmark \quad M_z = 5.41 \text{ ''-k} \quad \checkmark$$

W6x15 $S_x = 9.72 \text{ in}^3 \quad \checkmark \quad S_y = 3.11 \text{ in}^3 \quad \checkmark \quad A = 4.43 \text{ in}^2 \quad \checkmark$

$$f_{b_z} = \frac{5.41}{9.72} = 0.56 \text{ ksi} \quad \checkmark \quad f_{b_x} = \frac{4.34}{3.11} = 1.40 \text{ ksi} \quad \checkmark$$

$$f_y = \frac{0.0875}{4.43} = 0.020 \text{ ksi} \quad \checkmark$$

ANCHOR BOLT LOADS

TENSION

$$2T \times 8.5'' = 4.34 \text{ k} \quad \checkmark \quad T = 0.26 \text{ k} \quad \checkmark$$

$$2T \times 8.5'' = 5.41 \text{ k} \quad \checkmark \quad T = 0.32 \text{ k} \quad \checkmark$$

TENSION = 0.58 k/BOLT \checkmark

SHEAR



$$6.01 F \times 4 = 1.13 \text{ ''-k} \quad \checkmark \quad F = 0.097 \text{ k/BOLT} \quad \checkmark$$

$$F_x = F_z = \frac{0.097}{\sqrt{2}} = 0.033 \text{ k} \quad \checkmark$$

$$\text{RESULTANT} = \sqrt{2 \times (0.056 + 0.033)^2} = 0.126 \text{ k/BOLT} \quad \checkmark$$

$\frac{3}{4}'' \times 6''$ WES-1T 9" EMBED $F_c = 35 \text{ WPI}$ CATALOG #981
 ULT. CAPACITY ALLOWABLE

TENSION	19.32 k \checkmark	4.85 k	$\frac{0.58}{4.55} + \frac{0.126}{4.91} = 0.145 < 0.15$
SHEAR	19.63 k \checkmark	4.91 k	(O.K)

125V DC AUX. DC PANEL SK-5101-063-13



REF.

ASSUME PANEL WT = 50 LBS

PEAK g MEZZANINE FLR.
SPECTRA = 0.744g

HORIZONTAL ACCELERATION = $0.744g \times 1.5 = 1.12g$

VERTICAL ACCELERATION = $\frac{2}{3} \times 1.12g = 0.75g$



AT BASE

DEAD LOAD

$$M_z = 0.050k \times 20.13 = 1.01 \text{ ''-k } \downarrow$$

$$F_y = 0.050k \downarrow$$

SEISMIC LOADS

X-DIRECTION

$$M_z = 1.12g \times 0.05k \times 77.5 = 4.34 \text{ ''-k } \downarrow$$

$$F_x = 0.056k \downarrow$$

Y-DIRECTION

$$M_z = 0.75g \times 0.050k \times 20.13 = 0.75 \text{ ''-k } \downarrow$$

$$F_y = 0.0375k \downarrow$$

Z-DIRECTION


$$F_z = 0.056k \downarrow$$

$$M_y = 1.12g \times 0.050k \times 20.13 = 1.13 \text{ ''-k } \downarrow$$


$$M_x = 1.12g \times 0.05k \times 77.5 = 4.34 \text{ ''-k}$$

TR MCC 1A, METER PANEL, REACTOR DC PANEL SK-5101-067-14

REF.



PANELS BOLTED TOGETHER - ASSUME RIGID




$$\sum M_D = 0$$

$$0.24W(91/2) = 0.73W(21/2) + 91T$$

$$T = \frac{W}{91}(10.92 - 7.67)$$

$$T = 0.036W = 0.234K \checkmark$$



$$W6x15 \quad S_y = 3.11 \text{ IN}^3$$

$$f_y = \frac{8.66}{3.11} = 2.78 \text{ KSI} < 27.0 \text{ KSI}$$


$$TUBE \ 3x2x\frac{1}{4} \quad S_y = 1.15 \text{ IN}^3 \quad F_y = 46 \text{ KSI}$$

$$f_y = \frac{8.66}{1.15} = 7.53 \text{ KSI} < 30.36 \text{ KSI} \checkmark$$


TB MCC 1A METER PANEL, REACTOR DC PANEL

REF.

CONNECTION DETAILS



WELD




$$M_y = 8.66 \text{ in-k}$$

$$\text{WELD } S_y = 4 \times \left(\frac{1}{2} \times 1\right) \times (6)^2 = 24 \text{ in}^2 \checkmark$$

$$f_b = \frac{8.66}{24} = 0.361 \text{ k/in} \checkmark$$

$$\frac{3}{16} \text{ WELD CAPACITY: } \left(\frac{3}{16}\right) \times (.707) \times (21.0) = 2.78 \text{ k/in} \checkmark$$

BOLT LOAD



$$\frac{11.5 \bar{y}^2}{2} = 2 \times 0.442 \left[(1.25 - \bar{y}) + (6.75 - \bar{y}) \right]$$

$$\bar{y}^2 = 0.154 [8 - 2\bar{y}]$$

$$(\bar{y} + 1.54)^2 = 1.256$$

$$\bar{y} = 0.967 \text{ in} \checkmark$$

$$I = \frac{(11.5 \times 0.967)^2}{3} + 2 \times 0.442 \left[(1.25 - 0.967)^2 + (6.75 - 0.967)^2 \right]$$

$$I = 33.10 \text{ in}^4 \checkmark$$

$$T = \frac{(8.66 \times (6.75 - 0.967))}{33.1} \times 0.442 = 0.67 \text{ k/BOLT} \checkmark$$



NUCLEAR ENERGY SERVICES

BY TS DATE 1/20/82 PROJ. 5101 TASK 061
CHKD. DLS DATE 1/20/82 PAGE 3 OF 3
LACBWR ELECT. EQUIP. ROOM

TB MCC 1A, METER PANEL, REACTOR DC PANEL

REF.

$$T_2 = \frac{(F66)(125 - 0.967)}{33.1} \times 0.442 = 0.033 \text{ k/BOLT } \checkmark$$

$$2(0.67 + 0.033) \cdot \frac{1}{2}(0.967)(11.5) f_p$$

$$f_p = 0.253 \text{ ksi } \checkmark$$

$$\text{DIRECT TENSION} = 0.239/4 = 0.06 \text{ k/BOLT } \checkmark$$

$$\text{TOTAL BOLT LOAD} = 0.67 \text{ k} + 0.06 = 0.73 \text{ k } \checkmark$$

$$\text{TENSION CAPACITY A325 BOLT } - 3/4" \phi = 19.4 \text{ k } \checkmark$$


ETH
AISC
P4-3




NUCLEAR ENERGY SERVICES

GENERATOR DC PANEL 5101-063-17

REF.



PANEL HEIGHT = 91"
 ASSUME WT = 4000 #




$$\Sigma M_0 = 0$$

$$0.24W(91/2) = 0.73W(21/2) + 91T$$

$$T = \frac{W}{91}(10.92 - 7.67)$$

$$T = 0.036W = 0.144 \text{ k}$$



$$S_y = 3.11 \text{ in}^3$$

$$f_{by} = \frac{1.44}{3.11} = 0.46 \text{ ksi}$$

$$S_y = 1.15 \text{ in}^3$$


$$f_{by} = \frac{1.44}{1.15} = 1.25 \text{ ksi}$$

$$M = 0.144 \text{ k} \times 10'' = 1.44 \text{ k-in}$$

0.144 k


GENERATOR DC PANEL

REF.



$$f_x = \frac{13.1}{9.72} = 1.35 \text{ ksi}$$

BASE DETAILS - WELD



$$A_w = 6 \times 6 = 36 \text{ in}^2$$

$$S_w = 2(6 \times 6) + \frac{6^2}{3} = 84 \text{ in}^2$$

$$J_w = \frac{2(6^3) + 6(6 \times 6^2) + 6^3}{6} = 324 \text{ in}^3$$

MOMENT

$$f_t = \frac{13.1}{84} = 0.16 \text{ k/in}$$

SHEAR -

TORSION $M = 1.49 \text{ inch-k}$

$$f_h = f_v = \frac{(1.49)(3)}{324} = 0.01 \text{ k/in}$$

$$\text{RESULTANT} = \sqrt{.01^2 + .01^2} = 0.014 \text{ k/in}$$

$$\text{WELD RESULTANT} = \sqrt{0.16^2 + 0.014^2} = 0.16 \text{ k/in}$$

$$\text{USE } \frac{1}{4} \text{ WELD CAPACITY} = (\frac{1}{4})(.707)(21.0) = 3.71 \text{ k/in}$$

ANCHOR BOLTS

$$\text{TENSION } T = \frac{13.1}{(2)(7.25)} = 0.90 \text{ k/BOLT}$$




GENERATOR DC PINEL

REF.

SHEAR

HORIZONTAL SHEAR = $\frac{0.144^k}{4} = 0.036^k / \text{BOLT}$ ✓

TORSION



$F \times 6.01'' = \frac{1.44}{4}$

$F = 0.060^k$ ✓

$f_v - f_h = 0.707 \times 0.060 = 0.042^k$ ✓

SHEAR RESULTANT = $\sqrt{(0.036 + 0.042)^2 + 0.042^2} = 0.089^k / \text{BOLT}$ ✓

USE $\frac{3}{4}'' \times 6''$ LONG WES-ITS 4" EMBED $f_u = 35 \text{ WPS}$ CATALOG #581

	ULT. CAPACITY	ALLOWABLE (FS=4)
TENSION	19.38 ^k ✓	4.84 ^k ✓
SHEAR	19.63 ^k ✓	4.91 ^k ✓

$\frac{0.90}{4.84} + \frac{0.089}{4.91} = 0.204 < 1.0$ (O.K.) ✓



NUCLEAR ENERGY SERVICES

BY 1- DATE 7-10-66 PROJ. 101 TASK 46.5


CHKD. JC DATE 4/20/72 PAGE 4 OF 4

LABOR ELECT EQUIP.

GENERATOR DC PANEL

REF.

WBX15 - REMOVE FLANGE - DOWN 16" FROM TOP/COLUMN



	A	d	Ad	Ad ²	I ₀
FLANGE (6x.26)	1.56	0.13	0.203	0.026	0
WEB (4.58x.23)	1.15	2.75	3.163	8.697	2.367

ΣA = 2.71 in² ΣAd = 3.366 ΣAd² = 8.723 ΣI₀ = 2.367

ΣA = 2.71 in² ΣAd = 3.366 ΣAd² = 8.723 ΣI₀ = 2.367


$$y_{CG} = \frac{\Sigma Ad}{\Sigma A} = \frac{3.366}{2.71} = 1.24''$$

$$I_A = \Sigma I_0 + \Sigma Ad^2 = 11.09 \text{ in}^4$$

$$I_{CG} = I_A - Ad^2 = 11.09 - (2.71)(1.24)^2 = 6.923 \text{ in}^4$$


$$S_{TOP} = \frac{6.923}{4} = 1.731 \text{ in}^3$$

$$S_{BOT} = \frac{6.923}{1.24} = 5.583 \text{ in}^3$$



$$M = 16 \times 0.144^2 = 2.304 \text{ in}^2 \cdot \text{k}$$

$$f_s = \frac{2.304}{1.731} = 1.33 \text{ ksi}$$



NUCLEAR ENERGY SERVICES


BY _____ DATE 1/22/82 PROJ. 1-1-1 TASK 1-1

CHKD. DLJ DATE 1/22/82 PAGE 1 OF 2

CACBWR

SCRAM RELAY PANEL SK-5101-063-14

REF.



MEZZANINE FLOOR

$$\text{HORIZ. ACCEL.} = 0.16g \times 1.5 = 0.24g$$

$$\text{VERT. ACCEL.} = 0.18g \times 1.5 = 0.27g$$

Z-DIRECTION

$$M_{\text{OVERTURNING}} = 0.24W \times 40" = 9.6W$$

$$M_{\text{RESISTING}} = 0.73W \times 30" = 21.9W$$

$$F.S. = \frac{21.9W}{9.6W} = 2.28 > 1.5 \quad \text{NO OVERTURNING}$$

NO BOLTS REQUIRED

X-DIRECTION


$$M_{\text{RESISTING}} = 0.73W \times 11" = 8.03W < 9.6W \quad \therefore \text{ANCHOR BOLTS REQUIRED}$$

$$\sum M_0 = 0 \quad (2.4W \times 40") = (0.73W \times 11") + 17.5 T_1 \times 2 + 4.5 T_2 \times 2$$

$$37.31 T_1 = 1.57W$$

$$T_1 = 0.042W$$

$$T_2 = 0.011W$$




$$\frac{T_1}{17.5} = \frac{T_2}{4.5}$$

$$T_2 = \frac{4.5}{17.5} T_1$$

ASSUME $W = 3000 \# \quad T_1 = 126 \#$

$T_2 = 33 \#$




NUCLEAR ENERGY SERVICES

SCRAM RELAY PANEL


REF.

USE $E \times 4 \times \frac{1}{4}$ ANGLES, $\frac{1}{2}$ " WES-ITS

REVISED
12/6/82
TJS



BOLTS - ANGLE TO PANEL -
 (3) $\frac{1}{2} \times 2 \frac{1}{2}$ " LG GR 5



$$\frac{V_3}{16} = \frac{V_2}{11} \quad V_2 = 0.69V_3$$

$$\frac{V_2}{16} = \frac{V_1}{6} \quad V_1 = 0.38V_3$$

$\Sigma M_0 = 0$

$$(0.29W)(40) = (0.73W)(11) + (2V_1)(6) + (2V_2)(11) + (2V_3)(16)$$

$$4.56V_3 + 15.18V_3 + 32V_3 = 1.57W$$

FOR $W = 3000 \#$ $V_2 = 91 \#$ $V_3 = 65 \#$ $V_1 = 35 \#$

$$f_v = \frac{0.91 \#}{0.126} = 0.722 \text{ ksi}$$

CHECK PRYING - $\alpha > 0$ FOR PRYING ACTION

$$\alpha = \left[\frac{Tb'}{m} - 1 \right] / 8 > 0 \quad T \frac{b'}{m} - 1 > 0 \Rightarrow T \frac{b'}{m} > m$$

$$T = 0.126 \text{ k}$$

$$b' = 4.5 - \frac{.57}{2} = 4.25 \text{ inches}$$

$$m = \frac{(F)(.75)^2(36)}{8} = \frac{3.52}{2.25} \text{ inches}$$

$$T \frac{b'}{m} = (126)(0.25) = 0.54 \text{ inches} < \frac{3.52}{2.25} \text{ inches} \quad \text{NO PRYING}$$

PLATE BENDING

$$S = \frac{1}{6} (8)(.75)^2 = 0.130 \text{ in}^3$$

$$M = 0.126 \times 4.75 = 0.60 \text{ inch-k}$$

$$f_b = \frac{0.60}{0.130} = \frac{4.62}{2.18} \text{ ksi} < 27.0 \text{ ksi (OK)}$$

BOLT SHEAR - RSS. SHEAR FORCE = $\sqrt{(2.9W)^2 + (2.9W)^2} = 0.34W$

$$\text{FORCE/BOLT} = \frac{0.34 \times 3000}{4} = 255 \text{ lbs}$$

USE $\frac{1}{2}$ " ϕ $\times 3 \frac{1}{2}$ " LONG WES-IT BOLTS

CATALOG #981

TENSION

SHEAR

$2 \frac{1}{4}$ " EMBED.

ULT. CAPACITY 5.21 k

9.85 k

$f_c = 3500 \text{ psi}$

ALL. CAPACITY 1.30 k

2.46 k

$$\frac{0.126}{1.30} + \frac{0.255}{2.46} = 0.20 < 1.0 \text{ (OK)}$$



ETH
AISC
174-89

ETH
AISC
15.19.3

UNDER VOLTAGE RELAY CABINET SK-5101-063-14

REF.

PANEL HEIGHT = 91" ASSUME WT = 3000 LBS
 USE (4) 1/2" x 3 1/2" LG WES-IT ANCHOR BOLTS



$$\Sigma M_o = 0$$

$$(0.24W)(91/2) = (0.73W)(21/2) + 2T(27.875)$$

$$T = \frac{3.26W}{45.75} = 0.071W$$

$$T = 213.8 \text{ LBS/BOLT}$$

CHECK PRYING $\alpha > 0$ FOR PRYING ACTION

$$\alpha = \left[\frac{TB'}{M} - 1 \right] / \delta > 0 \quad \frac{TB'}{M} - 1 > 0 \Rightarrow TB' > M$$

$$T = 0.214^k$$

$$b' = 1.625 - 5/2 = 1.375 \text{ inches}$$

$$M = (6.125)(0.25)^2(26)/8 = 1.72 \text{ inch-k}$$

$$TB' = (0.214)(1.375) = 0.294 \text{ inch-k} < 1.72 \text{ inch-k} \quad \text{NO PRYING}$$

PLATE BENDING

$$S = \frac{1}{2}(6.125)(.25)^2 = 0.064 \text{ in}^3$$

$$M = 0.214^k \times 1.875 = 0.40 \text{ inch-k}$$

$$f_b = \frac{0.40}{0.064} = 6.27 \text{ ksi} < .75F_y = 27.0 \text{ ksi}$$

87ED
 AISC
 154-59

UNDERVOLTAGE RELAY CABINET

REF.

ANCHOR BOLT SHEAR

ASSUME 13 BOLTS RESIST SHEAR FORCE FROM ADJACENT PANELS ALSO (W = 6500 #)

TOTAL SHEAR FORCE = (6500 + 3000)(0.24g) = 225 k ✓

PERPENDICULAR DIRECTION SHEAR FORCE = (3000)(0.24g) = 0.72 k ✓


RESULTANT SHEAR = $\sqrt{2.25^2 + .72^2} = 2.39 k$ 0.60 k/BOLT

1/2" x 3 1/2" LG WES-ITS 2 1/4" EMBEDMENT $f_c = 3500 psi$ CATALOG #981

	ULT CAPACITY	ALLOWABLE (FS=4)
TENSION	5.21 k	1.30 k ✓
SHEAR	9.85 k	2.46 k ✓

$\frac{0.24 k}{1.30} + \frac{0.60}{2.46} = 0.41 < 1.0$ ✓

1/2" Ø BOLTS ANGLE TO PANEL



$\Sigma M_o = 0$

$(0.24W)(9 1/2) = (0.73W)(2 1/2) + 2V \times 21"$

$V = \frac{3.26W}{42} = 0.078W$

$W = 3000 \# \quad V = 2325 \# / BOLT$

$f_v = \frac{2325 k}{0.126} = 1.85 ksi$ ✓

(4)

STATIC PULL TEST SUMMARY SHEETS



NUCLEAR ENERGY SERVICES

BY R RUMPE DATE 3-9-81 PROJ. 5101 TASK 063
CHKD. I.H. DATE 3-9-81 PAGE 1 OF 3
LACBWR

REF.

TEST PROCEDURE FOR SAFETY RELATED
ELECTRICAL EQUIPMENT

1. CALCULATE WEIGHT OF EQUIPMENT.
2. FIND APPROPRIATE APPLIED REACTION FORCE, GIVEN IN LOAD CHART.
3. LOCATE APPROXIMATE CENTROID OF EQUIPMENT.
4. APPLY APPROPRIATE REACTION FORCE AT CENTROID IN 4 DIRECTION (TWO HORIZONTAL AND 2 VERTICAL DIRECTIONS) ALONG PERPENDICULAR AXES.
5. CHECK VISUALLY TO SEE IF ANY DAMAGE WAS INCURRED BY THE LOAD.



NUCLEAR ENERGY SERVICES

BY K. RUMPE DATE 3-9-81 PROJ. 5101 TASK 06
 CHKD. J.H DATE 3-9-81 PAGE 2 OF 3
LACBWR

LOAD CHART
(FOR REACTOR BLDG)

FIGURE	TITLE	APPLIED REACTION LOAD	REF.
G-2	FOUNDATION LEVEL (EL 621'-0")	2.16 W	0.88 ₂
G-6	LOWER FLOOR (EL 642'-9")	3.58 W	1.46 ₂
G-10	INTERMEDIATE FLOOR (EL 667'-0")	6.32 W	2.58 ₂
G-14	UPPER FLOOR SPECTRA (EL 701'-0")	10.12 W	4.14 ₂
G-18	CRANE SUPPORT SPECTRA (EL 729'-6")	13.16 W	5.38 ₂
G-22	WATER TANK SPECTRA (EL 745'-0")	14.95 W	6.11 ₂
G-26	REACTOR BASE SUPPORT (EL 648'-0")	4.36 W	1.75 ₂
G-30	REACTOR BOTTOM (EL 650'-0")	5.64 W	2.21 ₂
G-34	REACTOR MIDDLE (EL 670'-0")	4.34 W	1.78 ₂
G-38	REACTOR TOP (EL 684'-0")	7.18 W	2.93 ₂

$$\text{REACTION FORCE} = 1.5 \sqrt{F_x^2 + F_y^2 + F_z^2} W$$

FACTOR TO ACCOUNT FOR
MULTIPLE FREQUENCY = 1.5

$$F_x = F_y$$

$$F_z = \frac{2}{3} F_x$$

$$R = 1.5 \sqrt{2.66 F_x^2} W$$

$$R = 2.45 F_x W$$

F_x = PEAK G VALUE
FROM FIGURE

EXAMPLE AT EL 621'-0" FIGURE G-2
PEAK G-VALUE = 0.88 G

$$R = 2.45 \times 0.88 \times W = 2.16 W$$



NUCLEAR ENERGY SERVICES

BY K. KUMPI- DATE 5-7-01 PROJ. 5101 TASK 063
CHKD. I.H DATE 5-9-01 PAGE 3 OF 3
LACBWR

REF.

EXAMPLE PROBLEM

GIVEN:

WEIGHT OF SOLENOID = 5 lbs


LOCATION: ON WALL EL 701
OF REACTOR BLDG.

USING LOAD CHART FOR
EL 701 SPECTRA G-14

REACTION FORCE = 10.12 W

$$R = 10.12 \times 5 = 50.6 \#$$

GO TO TEST PROCEDURE AND
APPLY REACTION FORCE IN
FOUR DIRECTIONS.







FIG. G. 2 - FOUNDATION LEVEL SPECTRA, SSE SEISMIC INPUT (EL 621')

□ NODE POINT 2, 24 EQUIPMENT DAMPING

FIG. G.6 -- LOWER FLOOR SPECTRA, SSE SEISMIC INPUT (EL 642.9")



MODE POINT 5, 2% EQUIPMENT DAMPING




FIG.G.10 - INTERMEDIATE FLOOR SPECTRA, SSE SEISMIC INPUT (EL 667')

□ — □ NODE POINT 9. 2X EQUIPMENT DAMPING




FIG. G. 14 - UPPER FLOOR SPECTRA, SSE SEISMIC INPUT (EL 701')




FIG. G.18 - CRANE SUPPORT SPECTRA, SSE SEISMIC INPUT (EL 729'-6")




FIG. G. 22 - WATER TANK SPECTRA, SSE SEISMIC INPUT. (EL 745)

NOTE POINT 13, 2X EQUIPMENT DAMPING





FIG. C. 26 - REACTOR BASE SUPPORT SPECTRA, SSE SEISMIC INPUT (EL 648)

○ — ○ — ○ NODE POINT 17, 21 EQUIPMENT DAMPING



□ NODE POINT 23. 2Z EQUIPMENT DAMPING

FIG.G.30 - REACTOR BOTTOM SPECTRA, SSE SEISMIC INPUT (EL 650')





FIG.G.34 - REACTOR MIDDLE SPECTRA, SSE SEISMIC INPUT (EL 668')



□ — NODE POINT 28, 2X EQUIPMENT DRAWING

FIG. G.38 — REACTOR TOP SPECTRA, SSE SEISMIC INPUT (EL 685')

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT BUILDING PRESSURE TRANSMITTER

EQUIPMENT IDENTIFICATION NO. 37-35-301


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PIPE TUNNEL 629'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 32 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v\bar{v} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_y =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_v =$	<u>15.0</u>	<u>45</u>	<u>No</u>
$F_v\bar{v} =$	<u>15.0</u>	<u>45</u>	<u>No</u>

PERFORMED BY Robert J. Dege APPROVED BY A. Gomez

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT BUILDING PRESSURE TRANSMITTER

EQUIPMENT IDENTIFICATION NO. 37-35-302


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PIPE TUNNEL 629'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 32 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_y =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_v =$	<u>15.0</u>	<u>45</u>	<u>No</u>
$F_v^- =$	<u>15.0</u>	<u>45</u>	<u>No</u>

PERFORMED BY Robert D. Deard APPROVED BY A. J. Jones

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT BUILDING LEVEL TRANSMITTER

EQUIPMENT IDENTIFICATION NO. 37-42-301


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PIPE TUNNEL 629'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 32 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_y =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_v =$	<u>15.0</u>	<u>45</u>	<u>No</u>
$F_{\bar{v}} =$	<u>15.0</u>	<u>45</u>	<u>No</u>

PERFORMED BY *Robert D. [unclear]* APPROVED BY *A. James*

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT BUILDING LEVEL TRANSMITTER

EQUIPMENT IDENTIFICATION NO. 37-42-302


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PIPE TUNNEL 629'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 32 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_y =$	<u>22.7</u>	<u>60</u>	<u>No</u>
$F_v =$	<u>15.0</u>	<u>45</u>	<u>No</u>
$F_v^- =$	<u>15.0</u>	<u>45</u>	<u>No</u>

PERFORMED BY *Robert P. DeLeon* APPROVED BY *A. Gierman*

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT BUILDING PRESSURE SWITCH

EQUIPMENT IDENTIFICATION NO. 37-35-701


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PENETRATION ROOM 640'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 2.5 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v\bar{v} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>1.775</u>	<u>10</u>	<u>No</u>
$F_y =$	<u>1.775</u>	<u>10</u>	<u>No</u>
$F_v =$	<u>1.18</u>	<u>10</u>	<u>No</u>
$F_v\bar{v} =$	<u>1.18</u>	<u>10</u>	<u>No</u>

PERFORMED BY Robert O. DeYoung APPROVED BY A. G. Jones

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT BUILDING PRESSURE SWITCHES

EQUIPMENT IDENTIFICATION NO. 37-35-703


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PENETRATION ROOM 640'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 2.5 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>1.775</u>	<u>10</u>	<u>No</u>
$F_y =$	<u>1.775</u>	<u>10</u>	<u>No</u>
$F_v =$	<u>1.18</u>	<u>10</u>	<u>No</u>
$F_{\bar{v}} =$	<u>1.18</u>	<u>10</u>	<u>No</u>

PERFORMED BY Robert A. Alamed APPROVED BY A. G. Gimes

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT BUILDING PRESSURE SWITCH

EQUIPMENT IDENTIFICATION NO. 37-35- 702


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PENETRATION ROOM 640'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 2.5 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>1.775</u>	<u>10</u>	<u>No</u>
$F_y =$	<u>1.775</u>	<u>10</u>	<u>No</u>
$F_v =$	<u>1.18</u>	<u>10</u>	<u>No</u>
$F_v^- =$	<u>1.18</u>	<u>10</u>	<u>No</u>

PERFORMED BY *Robert O. ...* APPROVED BY *A. ...*

DATE MAY 28, 1981

EQUIPMENT NOMENCLATURE 1A POWER TO FLOW TRANSMITTER

EQUIPMENT IDENTIFICATION NO. 50-37-301


LOCATION:

BUILDING CONTAINMENT

ELEVATION 633'

PEAK G LEVEL 1.15 g. Ref. 3

MASS OF EQUIPMENT 28 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v\bar{v} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>78.7</u>	<u>79</u>	<u>No</u>
$F_y =$	<u>78.7</u>	<u>79</u>	<u>No</u>
$F_v =$	<u>52.5</u>	<u>59</u>	<u>No</u>
$F_v\bar{v} =$	<u>52.5</u>	<u>59</u>	<u>No</u>

PERFORMED BY Robert Adams APPROVED BY A. Finney

DATE MAY 28, 1981

EQUIPMENT NOMENCLATURE 2A POWER TO FLOW TRANSMITTER

EQUIPMENT IDENTIFICATION NO. 50-37-302


LOCATION:

BUILDING CONTAINMENT

ELEVATION 633'

PEAK G LEVEL 1.15 g. Ref. 3

MASS OF EQUIPMENT 28 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>78.7</u>	<u>79</u>	<u>No</u>
$F_y =$	<u>78.7</u>	<u>79</u>	<u>No</u>
$F_v =$	<u>52.5</u>	<u>59</u>	<u>No</u>
$F_{\bar{v}} =$	<u>52.5</u>	<u>59</u>	<u>No</u>

PERFORMED BY Robert L. Dwyer APPROVED BY A. Simms

DATE MAY 28, 1981

EQUIPMENT NOMENCLATURE 1B POWER TO FLOW TRANSMITTER

EQUIPMENT IDENTIFICATION NO. 50-37-304


LOCATION:

BUILDING CONTAINMENT

ELEVATION 633'

PEAK G LEVEL 1.15 g. Ref. 3

MASS OF EQUIPMENT 28 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>78.7</u>	<u>79</u>	<u>No</u>
$F_y =$	<u>78.7</u>	<u>79</u>	<u>No</u>
$F_v =$	<u>52.5</u>	<u>59</u>	<u>No</u>
$F_{\bar{v}} =$	<u>52.5</u>	<u>59</u>	<u>No</u>

PERFORMED BY Robert J. Olego APPROVED BY A. Gomez

DATE 7/22/82

EQUIPMENT NOMENCLATURE EMERGENCY CORE SPRAY (HIGH PRESSURE)
LPCS INLET VALVE SOLENOID

EQUIPMENT IDENTIFICATION NO. 53-25-005


LOCATION:

BUILDING CONTAINMENT

ELEVATION 677'

PEAK G LEVEL 3.237 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>31.7</u>	<u>40</u>	<u>No</u>
$F_y =$	<u>31.7</u>	<u>40</u>	<u>No</u>
$F_v =$	<u>21.1</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>21.1</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Dennis

DATE 7/22/82

EQUIPMENT NOMENCLATURE EMERGENCY CORE SPRAY (HIGH PRESSURE)

EQUIPMENT IDENTIFICATION NO. 53-25-006


LOCATION:

BUILDING CONTAINMENT

ELEVATION 677'

PEAK G LEVEL 3.237g. ref. 3

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>35.4</u>	<u>75</u>	<u>No</u>
$F_y =$	<u>55.4</u>	<u>75</u>	<u>No</u>
$F_v =$	<u>36.9</u>	<u>55</u>	<u>No</u>
$F_v^- =$	<u>36.9</u>	<u>55</u>	<u>No</u>

PERFORMED BY George Miles

APPROVED BY A. [Signature]

DATE 7/22/82

EQUIPMENT NOMENCLATURE VENT & GASEOUS WASTE

EQUIPMENT IDENTIFICATION NO. 55-25-013


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 2.017 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>19.7</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>19.7</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>13.2</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>13.2</u>	<u>30</u>	<u>No</u>

PERFORMED BY Deora Miles APPROVED BY A. James

DATE MAY 27, 1981

EQUIPMENT NOMENCLATURE OFFGAS VENT HEADER SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 55-25-014


LOCATION:

BUILDING TURBINE BUILDING

ELEVATION PIPE TUNNEL 635'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 6 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>4.26</u>	<u>20</u>	<u>No</u>
$F_y =$	<u>4.26</u>	<u>20</u>	<u>No</u>
$F_v =$	<u>2.8</u>	<u>20</u>	<u>No</u>
$F_v^- =$	<u>2.8</u>	<u>20</u>	<u>No</u>

PERFORMED BY Robert W. Deegan APPROVED BY A. J. James

DATE 7/22/82

EQUIPMENT NOMENCLATURE VENT & GASEOUS WASTE

EQUIPMENT IDENTIFICATION NO. 55-25-022


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 2.017 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>19.7</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>19.7</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>13.2</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>13.2</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY H. James

DATE 7/22/82

EQUIPMENT NOMENCLATURE DECAY HEAT REMOVAL

EQUIPMENT IDENTIFICATION NO. 56-25-002


LOCATION:

BUILDING CONTAINMENT

ELEVATION 638'

PEAK G LEVEL 1.596 g. ref. 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>18.2</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>18.2</u>	<u>30</u>	<u>No</u>

PERFORMED BY Derry Miles

APPROVED BY A. Simley

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE MSIV SOLENOID

EQUIPMENT IDENTIFICATION NO. 61-22-005(B)


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.70g. ref. 3

MASS OF EQUIPMENT 6 POUNDS



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>24.9</u>	<u>25</u>	<u>No</u>
$F_y =$	<u>24.9</u>	<u>25</u>	<u>No</u>
$F_v =$	<u>16.6</u>	<u>20</u>	<u>No</u>
$F_v^- =$	<u>16.6</u>	<u>20</u>	<u>No</u>

PERFORMED BY Robert C. Cleveland APPROVED BY A. J. [Signature]

DATE JULY 22, 1982

EQUIPMENT NOMENCLATURE SHUTDOWN CONDENSER

EQUIPMENT IDENTIFICATION NO. 62-25-006


LOCATION:

BUILDING CONTAINMENT

ELEVATION 725'

PEAK G LEVEL 5.258 g. ref. 2

MASS OF EQUIPMENT 6.25 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v\bar{v} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>80.3</u>	<u>85</u>	<u>No</u>
$F_y =$	<u>80.3</u>	<u>85</u>	<u>No</u>
$F_v =$	<u>53.6</u>	<u>70</u>	<u>No</u>
$F_v\bar{v} =$	<u>53.6</u>	<u>70</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY R. James

DATE 7/22/82

EQUIPMENT NOMENCLATURE SHUTDOWN CONDENSER

EQUIPMENT IDENTIFICATION NO 62-25-007


LOCATION:

BUILDING CONTAINMENT

ELEVATION 716'

PEAK G LEVEL 4.879 ref 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>83.5</u>	<u>90</u>	<u>No</u>
$F_y =$	<u>83.5</u>	<u>90</u>	<u>No</u>
$F_v =$	<u>55.7</u>	<u>60</u>	<u>No</u>
$F_v^- =$	<u>55.7</u>	<u>60</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. James

DATE 7/22/82

EQUIPMENT NOMENCLATURE SHUTDOWN CONDENSER

EQUIPMENT IDENTIFICATION NO. 62-25-008


LOCATION:

BUILDING CONTAINMENT

ELEVATION 716'

PEAK G LEVEL 4.879 g. ref. 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>83.5</u>	<u>90</u>	<u>No</u>
$F_y =$	<u>83.5</u>	<u>90</u>	<u>No</u>
$F_v =$	<u>55.7</u>	<u>60</u>	<u>No</u>
$F_{\bar{v}} =$	<u>55.7</u>	<u>60</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Bunker

DATE JULY 22, 1982

EQUIPMENT NOMENCLATURE SHUTDOWN CONDENSER

EQUIPMENT IDENTIFICATION NO. 62-25-009


LOCATION:

BUILDING CONTAINMENT

ELEVATION 725'

PEAK G LEVEL 5.258 g. ref. 2

MASS OF EQUIPMENT 6.25 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>80.3</u>	<u>85</u>	<u>No</u>
$F_y =$	<u>80.3</u>	<u>85</u>	<u>No</u>
$F_v =$	<u>53.6</u>	<u>70</u>	<u>No</u>
$F_v^- =$	<u>53.6</u>	<u>70</u>	<u>No</u>

PERFORMED BY George Mills APPROVED BY A. G. Jones

DATE 7/22/82

EQUIPMENT NOMENCLATURE SHUTDOWN CONDENSER

EQUIPMENT IDENTIFICATION NO. 62-25-010


LOCATION:

BUILDING CONTAINMENT

ELEVATION 716'

PEAK G LEVEL 4.879 g. ref. 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>83.5</u>	<u>90</u>	<u>No</u>
$F_y =$	<u>83.5</u>	<u>90</u>	<u>No</u>
$F_v =$	<u>55.7</u>	<u>60</u>	<u>No</u>
$F_v^- =$	<u>55.7</u>	<u>60</u>	<u>No</u>

PERFORMED BY George Mills

APPROVED BY A. [Signature]

DATE 7/22/82

EQUIPMENT NOMENCLATURE SHUTDOWN CONDENSER

EQUIPMENT IDENTIFICATION NO. 62-25-015


LOCATION:

BUILDING CONTAINMENT

ELEVATION 719'

PEAK G LEVEL 5.005 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v\bar{ } = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>48.9</u>	<u>90</u>	<u>No</u>
$F_y =$	<u>48.9</u>	<u>90</u>	<u>No</u>
$F_v =$	<u>32.6</u>	<u>60</u>	<u>No</u>
$F_v\bar{ } =$	<u>32.6</u>	<u>60</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Kinney

DATE 7/22/82

EQUIPMENT NOMENCLATURE SHUTDOWN CONDENSER

EQUIPMENT IDENTIFICATION NO. 62-25-016


LOCATION:

BUILDING CONTAINMENT

ELEVATION 719'

PEAK G LEVEL 5.005 g. ref. 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>85.7</u>	<u>90</u>	<u>No</u>
$F_y =$	<u>85.7</u>	<u>90</u>	<u>No</u>
$F_v =$	<u>57.1</u>	<u>60</u>	<u>No</u>
$F_{\bar{v}} =$	<u>57.1</u>	<u>60</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY R. Simon

DATE 7/22/82

EQUIPMENT NOMENCLATURE MAIN STEAM (BYPASS VALVE)

EQUIPMENT IDENTIFICATION NO. 64-25-002


LOCATION:

BUILDING CONTAINMENT

ELEVATION 638'

PEAK G LEVEL 1.596 g. ref. 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>18.2</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>18.2</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. [Signature]

DATE 7/22/82

EQUIPMENT NOMENCLATURE MAIN STEAM (BYPASS VALVE)

EQUIPMENT IDENTIFICATION NO. 64-25-003


LOCATION:

BUILDING CONTAINMENT

ELEVATION 638'

PEAK G LEVEL 1.596 g. ref. 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>18.2</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>18.2</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Brown

DATE 7/22/82

EQUIPMENT NOMENCLATURE DEMINERALIZED WATER

EQUIPMENT IDENTIFICATION NO. 67-25-002


LOCATION:

BUILDING CONTAINMENT

ELEVATION 638'

PEAK G LEVEL 1.596 g. ref. 2

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>27.3</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>18.2</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>18.2</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. James

DATE 7/22/82

EQUIPMENT NOMENCLATURE DEMINERALIZED WATER

EQUIPMENT IDENTIFICATION NO. 67-25-003


LOCATION:

BUILDING CONTAINMENT

ELEVATION 638'

PEAK G LEVEL 1.2 g Ref. 3

MASS OF EQUIPMENT 7 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>20.5</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>20.5</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>13.7</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>13.7</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Giermer

DATE 7/22/82

EQUIPMENT NOMENCLATURE OVERHEAD STORAGE TANK (OHST)

EQUIPMENT IDENTIFICATION NO. 69-25-002


LOCATION:

BUILDING CONTAINMENT

ELEVATION 706'

PEAK G LEVEL 4.458 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>43.6</u>	<u>60</u>	<u>No</u>
$F_y =$	<u>43.6</u>	<u>60</u>	<u>No</u>
$F_v =$	<u>29.1</u>	<u>40</u>	<u>No</u>
$F_v^- =$	<u>29.1</u>	<u>40</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Jimenez

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-003


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.7g. ref. 3

MASS OF EQUIPMENT 6.25 POUNDS



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>20</u>	<u>No</u>
$F_{\bar{v}} =$	<u>17.3</u>	<u>20</u>	<u>No</u>

PERFORMED BY *Richard D. DeLeon* APPROVED BY *A. J. ...*

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-004


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.70g. ref. 3

MASS OF EQUIPMENT 6.25 POUNDS



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>20</u>	<u>No</u>
$F_{\bar{v}} =$	<u>17.3</u>	<u>20</u>	<u>No</u>

PERFORMED BY *Robert L. Deyan* APPROVED BY *A. James*

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-007


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.7 g. Ref. 3

MASS OF EQUIPMENT 6.25 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>25.9</u>	<u>29</u>	<u>No</u>
$F_y =$	<u>25.9</u>	<u>29</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>24</u>	<u>No</u>
$F_{\bar{v}} =$	<u>17.3</u>	<u>24</u>	<u>No</u>

PERFORMED BY Robert L. Deegan APPROVED BY R. James

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-008


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.70g. ref. 3

MASS OF EQUIPMENT 6.25 POUNDS



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>20</u>	<u>No</u>
$F_v^- =$	<u>17.3</u>	<u>20</u>	<u>No</u>

PERFORMED BY Robert A. Olegard APPROVED BY A. Jensen

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-016


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 170g. ref. 3

MASS OF EQUIPMENT 6.25 POUNDS



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>20</u>	<u>No</u>
$F_v^- =$	<u>17.3</u>	<u>20</u>	<u>No</u>

PERFORMED BY Robert D. DeLeon APPROVED BY A. J. Jones

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-017


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.70g. ref. 3

MASS OF EQUIPMENT 6.25 POUNDS



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v = F_{\bar{v}} = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>20</u>	<u>No</u>
$F_{\bar{v}} =$	<u>17.3</u>	<u>20</u>	<u>No</u>

PERFORMED BY Robert Z. Odegal APPROVED BY A. Dennis

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-018


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.7 g. Ref. 3

MASS OF EQUIPMENT 6.25 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5) :$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>25.9</u>	<u>29</u>	<u>No</u>
$F_y =$	<u>25.9</u>	<u>29</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>24</u>	<u>No</u>
$F_v^- =$	<u>17.3</u>	<u>24</u>	<u>No</u>

PERFORMED BY Robert J. O'Connell APPROVED BY A. Dennis

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION SOLENOID VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-019


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.70g. ref. 3

MASS OF EQUIPMENT 6.25 POUNDS



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>26.0</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>17.3</u>	<u>20</u>	<u>No</u>
$F_v^- =$	<u>17.3</u>	<u>20</u>	<u>No</u>

PERFORMED BY *Robert A. Deegan* APPROVED BY *A. J. [Signature]*

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION INLET VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-001 used with 73-25-003 & -016


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.7 g. Ref. 3

MASS OF EQUIPMENT 12.5 lbs. (SOV's)



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_y =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_v =$	<u>34.6</u>	<u>39</u>	<u>No</u>
$F_{\bar{v}} =$	<u>34.6</u>	<u>39</u>	<u>No</u>

PERFORMED BY *Robert J. O'Connell* APPROVED BY *A. James*

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION EXHAUST VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-005 used with 73-25-007 & -018


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.7 g. Ref. 3

MASS OF EQUIPMENT 12.5 lbs. (SOV's)



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_y =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_v =$	<u>34.6</u>	<u>39</u>	<u>No</u>
$F_{\bar{v}} =$	<u>34.6</u>	<u>39</u>	<u>No</u>

PERFORMED BY Robert L. [Signature] APPROVED BY A. James

DATE MAY 22, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION INLET VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-002 used with 73-25-004 & -017


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.7 g. Ref. 2

MASS OF EQUIPMENT 12.5 lbs. (SOV's)



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_y =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_v =$	<u>34.6</u>	<u>39</u>	<u>No</u>
$F_v^- =$	<u>34.6</u>	<u>39</u>	<u>No</u>

PERFORMED BY Robert L. Dege APPROVED BY A. B. Boney

DATE MAY 26, 1981

EQUIPMENT NOMENCLATURE CONTAINMENT VENTILATION EXHAUST VALVE

EQUIPMENT IDENTIFICATION NO. 73-25-006 used with 73-25-008 & -019


LOCATION:

BUILDING CONTAINMENT

ELEVATION 648'

PEAK G LEVEL 1.7 g. Ref. 3

MASS OF EQUIPMENT 12.5 lbs. (SOV's)



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_y =$	<u>51.9</u>	<u>54</u>	<u>No</u>
$F_v =$	<u>34.6</u>	<u>54</u>	<u>No</u>
$F_v^- =$	<u>34.6</u>	<u>54</u>	<u>No</u>

PERFORMED BY Robert L. Dejean APPROVED BY A. G. Jones

DATE 7/22/82

EQUIPMENT NOMENCLATURE HIGH PRESSURE SERVICE WATER (HPSW)

EQUIPMENT IDENTIFICATION NO. 75-25-003


LOCATION:

BUILDING CONTAINMENT

ELEVATION 638'

PEAK G LEVEL 1.596 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>15.6</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>15.6</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>10.4</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>10.4</u>	<u>30</u>	<u>No</u>

PERFORMED BY Darryl Miles

APPROVED BY A. Simon

DATE 7/22/82

EQUIPMENT NOMENCLATURE HIGH PRESSURE SERVICE WATER (HPSW)

EQUIPMENT IDENTIFICATION NO. 75-25-004


LOCATION:

BUILDING CONTAINMENT

ELEVATION 638'

PEAK G LEVEL 1.596 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>15.6</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>15.6</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>10.4</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>10.4</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. James

DATE 6/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE (METERING VALVE)

EQUIPMENT IDENTIFICATION NO. 84-22-001


LOCATION:

BUILDING TURBINE BUILDING (PIPE TUNNEL)

ELEVATION 635'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 5 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>3.5</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>3.5</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>2.4</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>2.4</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. James

DATE 6/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE

EQUIPMENT IDENTIFICATION NO. 84-25-001


LOCATION:

BUILDING CONTAINMENT (BASEMENT 635')

ELEVATION 640'

PEAK G LEVEL 1.35 g. ref. 3

MASS OF EQUIPMENT 28 LBS.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>92.4</u>	<u>100</u>	<u>No</u>
$F_y =$	<u>92.4</u>	<u>100</u>	<u>No</u>
$F_v =$	<u>61.6</u>	<u>80</u>	<u>No</u>
$F_v^- =$	<u>61.6</u>	<u>80</u>	<u>No</u>

PERFORMED BY Deorg Miles

APPROVED BY A. Senior

DATE 6/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-002


LOCATION:

BUILDING TURBINE (PIPE TUNNEL)

ELEVATION 635'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 28 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>19.9</u>	<u>50</u>	<u>No</u>
$F_y =$	<u>19.9</u>	<u>50</u>	<u>No</u>
$F_v =$	<u>13.2</u>	<u>50</u>	<u>No</u>
$F_v^- =$	<u>13.2</u>	<u>50</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Guinier

DATE 6/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-003


LOCATION:

BUILDING TURBINE BUILDING (PIPE TUNNELS)

ELEVATION 640'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>2.8</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>2.8</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>1.9</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>1.9</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles

APPROVED BY A. James

DATE 5/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-004


LOCATION:

BUILDING TURBINE BUILDING (PIPE TUNNEL)

ELEVATION 640'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 10.5 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>7.4</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>7.4</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>5.0</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>5.0</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. James

DATE 6/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-005


LOCATION:

BUILDING TURBINE BUILDING (PIPE TUNNEL)

ELEVATION 640'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>2.8</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>2.8</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>2.8</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>2.8</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Mills APPROVED BY R. James

DATE 6/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-006


LOCATION:

BUILDING TURBINE BUILDING (PIPE TUNNEL)

ELEVATION 635'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 10.5 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>7.4</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>7.4</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>5.0</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>5.0</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles

APPROVED BY A. Bimes

DATE 6/23/82

EQUIPMENT NOMENCLATURE LIQUID SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-007


LOCATION:

BUILDING TURBINE BUILDING (PIPE TUNNEL)

ELEVATION 635'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 10.5 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>7.4</u>	<u>30</u>	<u>No</u>
$F_y =$	<u>7.4</u>	<u>30</u>	<u>No</u>
$F_v =$	<u>5.0</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>5.0</u>	<u>30</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Brimes

DATE 6/15/81

EQUIPMENT NOMENCLATURE AIR SAMPLE

EQUIPMENT IDENTIFICATION NO. 84-25-013


LOCATION:

BUILDING CONTAINMENT

ELEVATION 680'

PEAK G LEVEL 3.364 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>32.9</u>	<u>50</u>	<u>No</u>
$F_y =$	<u>32.9</u>	<u>50</u>	<u>No</u>
$F_v =$	<u>21.9</u>	<u>50</u>	<u>No</u>
$F_v^- =$	<u>21.9</u>	<u>50</u>	<u>No</u>

PERFORMED BY Robert L. O'Connell APPROVED BY A. James

DATE 6/15/81

EQUIPMENT NOMENCLATURE AIR SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-014


LOCATION:

BUILDING TURBINE BUILDING (ELECTRICAL PENETRATION)

ELEVATION 650'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>2.8</u>	<u>40</u>	<u>No</u>
$F_y =$	<u>2.8</u>	<u>40</u>	<u>No</u>
$F_v =$	<u>1.9</u>	<u>30</u>	<u>No</u>
$F_v^- =$	<u>1.9</u>	<u>40</u>	<u>No</u>

PERFORMED BY Robert L. Dege APPROVED BY A. J. [Signature]

DATE 6/23/82

EQUIPMENT NOMENCLATURE AIR SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-015


LOCATION:

BUILDING TURBINE BUILDING (ELECTRICAL PENETRATION ROOM)

ELEVATION 650'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>2.9</u>	<u>50</u>	<u>No</u>
$F_y =$	<u>2.8</u>	<u>50</u>	<u>No</u>
$F_v =$	<u>1.9</u>	<u>50</u>	<u>No</u>
$F_v^- =$	<u>1.9</u>	<u>50</u>	<u>No</u>

PERFORMED BY George Miles

APPROVED BY A. James

DATE 6/23/82

EQUIPMENT NOMENCLATURE AIR SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-016


LOCATION:

BUILDING TURBINE BUILDING (ELECTRICAL PENETRATION ROOM)

ELEVATION 650'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>2.8</u>	<u>50</u>	<u>No</u>
$F_y =$	<u>2.8</u>	<u>50</u>	<u>No</u>
$F_v =$	<u>1.9</u>	<u>50</u>	<u>No</u>
$F_v^- =$	<u>1.9</u>	<u>50</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. James

DATE 6/15/81

EQUIPMENT NOMENCLATURE AIR SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-017


LOCATION:

BUILDING TURBINE BUILDING (ELECTRICAL PENETRATION ROOM)

ELEVATION 650'

PEAK G LEVEL .29 g. Ref. 1

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>2.8</u>	<u>40</u>	<u>No</u>
$F_y =$	<u>2.8</u>	<u>40</u>	<u>No</u>
$F_v =$	<u>1.9</u>	<u>30</u>	<u>No</u>
$F_{\bar{v}} =$	<u>1.9</u>	<u>40</u>	<u>No</u>

PERFORMED BY Robert C. O'Connell APPROVED BY A. James

DATE 6/15/81

EQUIPMENT NOMENCLATURE AIR SAMPLE

EQUIPMENT IDENTIFICATION NO. 84-25-018


LOCATION:

BUILDING CONTAINMENT

ELEVATION 680'

PEAK G LEVEL 3.364 g. ref. 2

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v^- = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>32.9</u>	<u>50</u>	<u>No</u>
$F_y =$	<u>32.9</u>	<u>50</u>	<u>No</u>
$F_v =$	<u>21.9</u>	<u>50</u>	<u>No</u>
$F_v^- =$	<u>21.9</u>	<u>50</u>	<u>No</u>

PERFORMED BY Robert L. Adams APPROVED BY A. G. Jones

DATE 6/23/82

EQUIPMENT NOMENCLATURE AIR SAMPLE (SOL. VALVE)

EQUIPMENT IDENTIFICATION NO. 84-25-019


LOCATION:

BUILDING TURBINE BUILDING (ELECTRICAL PENETRATION ROOM)

ELEVATION 650'

PEAK G LEVEL .29 g Ref. 1

MASS OF EQUIPMENT 4 lbs.



$$F_x = F_y = (\text{Mass}) (\text{Peak G For Elevation}) (1.63) (1.5)$$

$$F_v\bar{ } = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>2.8</u>	<u>50</u>	<u>No</u>
$F_y =$	<u>2.8</u>	<u>50</u>	<u>No</u>
$F_v =$	<u>1.9</u>	<u>50</u>	<u>No</u>
$F_v\bar{ } =$	<u>1.9</u>	<u>50</u>	<u>No</u>

PERFORMED BY George Miles APPROVED BY A. Brimer

DATE 6/23/82

EQUIPMENT NOMENCLATURE HOPE CAST IRON JB H3229

EQUIPMENT IDENTIFICATION NO. RP-72


LOCATION:

BUILDING CONTAINMENT (MAIN RELIEF VALVES)

ELEVATION 684'

PEAK G LEVEL 2.93 g Ref. 1

MASS OF EQUIPMENT 41 lbs.



NOTE: $F_w = 293.72$

$F_h = 2/3 F_w = 195.85$

$F_x = F_y = 1/4 F_w$

$F_v = F_{\bar{v}} = 1/4 F_h$

Each anchor was individually pulled on, in two different planes. On each pull the anchor was observed and did not move

$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$

$F_{\bar{v}} = F_v = 2/3 F_x$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>73.43</u>	<u>90</u>	<u>No</u>
$F_y =$	<u>73.43</u>	<u>90</u>	<u>No</u>
$F_v =$	<u>48.95</u>	<u>90</u>	<u>No</u>
$F_{\bar{v}} =$	<u>48.95</u>	<u>90</u>	<u>No</u>

PERFORMED BY George Miles

APPROVED BY [Signature]

DATE 7/14/82

EQUIPMENT NOMENCLATURE KILLARC CAST ALUM. DBS10106

EQUIPMENT IDENTIFICATION NO. RP-16

LOCATION:

BUILDING CONTAINMENT

ELEVATION 672'

PEAK G LEVEL 3.027 g. ref. 2


MASS OF EQUIPMENT 16 lbs.

Note: $F_w = 118.4$

$F_h = 2/3 F_w = 78.9$

$F_x = F_y = 1/4 F_w$

$F_v = F_v^- = 1/4 F_h$



$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$ Each anchor was individually pulled or

$F_v^- = F_v = 2/3 F_x$

in the different planes. On each pull the anchor was observed and did not move.

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>29.6</u>	<u>50</u>	<u>No</u>
$F_y =$	<u>29.6</u>	<u>50</u>	<u>No</u>
$F_v =$	<u>19.7</u>	<u>50</u>	<u>No</u>
$F_v^- =$	<u>19.7</u>	<u>50</u>	<u>No</u>

PERFORMED BY George Miles

APPROVED BY A. [Signature]

DATE 7/22/82

EQUIPMENT NOMENCLATURE ELECTRICAL JUNCTION BOX

EQUIPMENT IDENTIFICATION NO. J.B. DR-2


LOCATION:

BUILDING 1B DIESEL BUILDING

ELEVATION 641'

PEAK G LEVEL 0.29 g. Ref. 1

MASS OF EQUIPMENT 30 lbs.



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

Maximum force 21.3 lb.

Use four 3/8" WEJ-IT to anchor junction box to diesel building wall. Torque to required valve Tensile and shear stress of anchors far exceed the maximum anticipated force. (See attached data.)

PERFORMED BY George Miles APPROVED BY A. Gentry

WEJ-IT

500 Alter Street
Broomfield, Colo. 80020
Phone: 303-466-1822

TEST REPORT #1

ALLIED PRODUCTS CORPORATION

E-M

ANSI/ASTM E488
ICBO



**TENSION and SHEAR
TEST WEJ-IT
ANCHOR BOLTS IN
CONCRETE**



ENGINEERS & ASSOCIATES, INC.

223 South Lipan, Denver, Colorado 80223 303-956-3423

Conducted and Prepared By
H-S ADNAN, P.E.
W. TOPPING
J. KALMES
J. P. SPRINGER

TEST OF 1/2" DIA. 58X5W
ANCHOR BOLT IN CONCRETE

1/2" DIA.

9

2

1

0

TESTING PROCEDURES

Electric drill model 1RH-90 (800W BA 110V 60cycle 230 R.P.M.) was utilized. Drill bits utilized were of Wej-It manufacture, and ranged in diameter from 0.264 inches through 1.540 inches.

The testing equipment consisted of a mobile gantry fitted with a five ton capacity motor driven hoist, and two tension and shear assemblies, equipped with "TL" Series Load Cell transducers connected to a SC 11 J/PH Signal Conditioner, manufactured by Precision Force Measurement, Inc. The two assemblies have a loading capacity of 20,000 pounds for the small assembly and a capability of 100,000 pounds applied load for the larger. The steel frame assembly is connected to a hydraulic pump system; (refer accompanying photographs). The pressure regulating valve permits the hydraulic ram of the fixture to move upward and downward and is regulated by a low-high speed valve. Loads are applied by the hydraulic system and are recorded on an "OmniScribe" X-Y recording graph produced by Houston Instrument. The graph revealed both displacement and applied loading. The vertical stand legs for tension pull-out testing and the assembly for shear testing were designed to conform to the requirements of the E.A.M.I. Test Standard.

The direction of loading for all tensile testing was co-axial with the embedded test anchors.

The SC 11 J/PH is a completely solid state strain gauge transducer conditioning system with Signal Peak Holding circuitry.

TESTING PROCEDURES

The concrete slab of a designated strength was placed in position directly below the gantry assembly. Holes were drilled by unskilled workers using no excessive pressure, to depths equal to the full length of the representative Wej-It bolt specimen. Holes were drilled perpendicular to the concrete test specimen surface and the drill tool was raised and lowered to remove dust and reduce binding. Upon completion of drilling, the holes were cleaned in accordance with the manufacturers published recommendation. Test holes were measured with a micrometer dialed instrument and recorded on the accompanying tabulations of engineering data. Typical arrangement of drilled holes for the tension pullout and shear tests are shown on diagrams "A", "B", "C" and "D", and on accompanying photographs.

The specimen Wej-It bolt was inserted into a drilled hole that was measured within the minimum-maximum tolerances shown below; and tapped down with the fixture in place. The Wej-It was then lightened by means of a torque wrench to manufacturers specified table of applied load torque in foot pounds. Torque was found to approximate 2-3 turns of the nut from finger tight.

DIAMETER OF WEJ-IT	TORQUE ft/lbs	HOLE DIAMETER	
		Min.	Max.
1/4"	4-5	.260	.268
3/8"	15-20	.390	.398
1/2"	30-35	.520	.530
5/8"	50-75	.650	.660
3/4"	75-100	.775	.787
1"	150-260	.9030	1.042
1 1/4"	260-330	1.285	1.300
1 1/2"	330-650	1.535	1.550

Specifications and

labor saving data for estimators

Comparison of in-place costs, among a variety of concrete anchors is often neglected. There is a dramatic difference when proper analysis is made. And any difference is substantial when you figure labor costs.

1. Estimators know the high cost of correcting misplaced cast-in-place anchor bolts, for instance.
2. They know the high cost of correcting misaligned Shield-type anchors such as self-drills, lead shields, lag shields, etc. . . . plus the high cost of gathering separate nuts, washers, and bolts to accommodate these out-dated anchors.
3. They also know about the high cost of correcting concrete "spall-outs" often experienced with "floating wedge" type stud anchors.

With superior Wej-it expansion anchor bolts, these costs are eliminated because the Wej-it design is exclusively patented. There is no other bolt designed to duplicate its inherent, superior design characteristics . . . which make it possible to keep "in-place costs" down, as low as possible . . . at the greatest degree of SAFETY.

drilling procedure

1. Use carbide-tip, solid bits, whenever possible. Tip diameters to ANSI standard B94.12-1977.
2. Don't use excessively worn bits.
3. Keep the drill in a perpendicular line while drilling.
4. Let the drill do the work. Don't apply excessive pressure.
5. Lift up and down, to remove dust and reduce "binding."
6. DRILL HOLE TO A DEPTH EQUAL TO THE FULL LENGTH OF THE WEJ-IT.
7. Blow out the dust from the hole. Cleaning adds to the holding values of the WEJ-IT.

TIME GUIDE — DRILLING/INSERTING/TIGHTENING ONE WEJ-IT

Size	Min. Sec.	Size	Min. Sec.	Size	Min. Sec.	
1/4 x	1 1/4	13	3 1/2	45	1/2 x 8	
	1 3/4	16	5	49		10
	2 1/4	24	6	58		12
	3	26	7	1 10	1 x 8	
3/8 x	1 1/2	17	3 1/2	48	10	
	2	24	4 1/2	50	12	
	3	32	5	53	1 1/2 x 8	
1/2 x	1 1/2	19	5 1/2	56	10	
	2	26	6	1 8	12	
	2 3/4	29	7	1 20	1 1/4 x 8	
	3 1/2	39	8	1 51	10	
5/8 x	2	46	5	55	12	
	3	50	6	1 15	1 1/2 x 8	
	4	28	7	1 28	10	
	2 1/4	35	10	1 42	12	

*Using Electric Roto-Hammers. In 3750 psi concrete, 28 day cure, 1:3:2 mix.

Installation information

SPACING AND HOLE TOLERANCES

Wej-it Diameter	Recommended Hole Diameter		Edge Distance	Bolt-to-nearest-bolt spacing
	Minimum Inches	Maximum Inches		
1/2	.260	.268	5 bolt diameters (For 100% efficiency)*	10 bolt diameters (For 100% efficiency)**
3/4	.327	.335		
1	.390	.398		
1 1/4	.520	.530		
1 1/2	.650	.660		
1 3/4	.775	.787		
2	.905	.917		
2 1/4	1.030	1.042		
2 3/4	1.160	1.175		
3	1.285	1.300		
3 1/2	1.535	1.550		

NOTE: *The edge distance spacing may be reduced to a 50% efficiency rating using 2 1/2" diameter placement from the edge. **Bolt-to-nearest-bolt spacing may be reduced to a 50% efficiency rating using 5 diameter spacing. MEETS E.A.A.I. TEST STANDARD.

TYPICAL DESIGN-SPECIFICATION TERMINOLOGY

Contractors shall furnish and install _____ size Wej-It Concrete Anchors as manufactured by Wej-It Corporation of Broomfield, Colorado, or equal. The anchor shall be the Double-Wedge Expansion Type, made of cold drawn steel having the accredited pullout and shear values as published by WEJ-IT.

CHOICE OF METALS

Steel: Cold rolled, 84,000 PSI, Brinnell 156. Minimum Yield 70,000 PSI. Elongation—15% in two inches. Area reduction 55%. Finish: Rust resistant zinc coating with final clear acetate coating which exceeds U.S. Government ASTM salt spray test (B-117), and in accordance with Fed. Spec. QQZ-325, Type 1, Class 3.
Stainless Steel: Routinely available in types 303, 304. Type 316 by special request.

Hot-Dipped Galvanized: Available on request.

Aluminum: Routinely available — Type 2024 — T6. Other types by request.

SPECIAL ASTM'S, IN STEEL — available on request.

A-307 grades 1-5
A-325
A-354 grade BB

A-354 grade BC
A-354 grade 5.1
A-354 grade 8

A-354 grade BD
A-449
A-490

Load data for WEJ-ITS

HOW MUCH TORQUE TO APPLY

2-3 turns of the nut is sufficient on normal installations, where average concrete exists, at about 28-day cure. The number of turns required, however, may be less, depending on the strength of concrete. Where abnormally high ranges of concrete are experienced, for example 6000-7000 psi concrete, 1-2 turns may only be necessary. Wej-its need not, and should not, be forced excessively, into clamp load modes, through overtorquing. It is not necessary with Wej-its. Torque valves upon request.

THREAD CLASSIFICATION

National Coarse, Class 2A fit on Standard Wej-its and nose cone Wej-its.

Expansion Screws only are National fine on $\frac{1}{4}$ ". National coarse on $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ".

MEETS O.S.H.A. REQUIREMENTS


Section No. 1910.212(b)

Choosing the size

Selection of any anchor is not absolutely scientific because much depends on these factors:

1. Diameter of the hole already in the fixture or equipment.
2. Depth, mix, strength and age of concrete.
3. Tensile or Shear Values desired.
4. Safety Factor required.

The diagram below can be helpful for choosing the minimum length desired.



TENSILE AND SHEAR VALUES

Applies to all Steel Standard and Nose Cone WEJ-ITS, 5000 PSI

As Tested in 5000 PSI Concrete at these Minimum Embedments					
Wej-it Diameter and Hole Diameter	Wej-it Length	Hole Size to Drill Hole	Tensile Strength	Shear Strength	28-day cure
Inches	Inches	Inches	Lbs.	Lbs.	Inches
$\frac{1}{4}$	1 $\frac{1}{4}$	Drill Hole to a Depth Equal to the Full Shank Length of the Wej-it	1450	2316	1
	1 $\frac{3}{8}$		1760	2316	1 $\frac{1}{4}$
	2 $\frac{1}{4}$		2331	2316	1 $\frac{3}{8}$
	3		2473	2316	1 $\frac{1}{2}$
$\frac{3}{8}$	1 $\frac{1}{2}$	" "	2402	2500	1
	2		2742	2500	1 $\frac{1}{4}$
	3		3185	2500	1 $\frac{3}{8}$
$\frac{1}{2}$	1 $\frac{1}{2}$	" "	3198	4807	1 $\frac{1}{4}$
	2		3580	4807	1 $\frac{3}{8}$
	2 $\frac{1}{4}$		3834	4807	1 $\frac{1}{2}$
	3 $\frac{1}{2}$		4022	4807	2
	5		4399	4807	3 $\frac{1}{2}$
$\frac{5}{8}$	6	" "	4650	4807	4
	2		5645	22597	1 $\frac{1}{2}$
	2 $\frac{1}{4}$		5717	22597	2
	3 $\frac{1}{2}$		5789	22597	2 $\frac{1}{4}$
$\frac{3}{4}$	5	" "	6411	22597	3 $\frac{1}{2}$
	6		7213	22597	4
	7		8015	22597	5
	8 $\frac{1}{2}$		8284	25674	2
	4 $\frac{1}{2}$		1185	25674	3
$\frac{1}{4}$	5	" "	12636	25674	3 $\frac{1}{2}$
	5 $\frac{1}{2}$		13893	25674	3 $\frac{3}{4}$
	6		14372	25674	4
	7		15299	25674	4 $\frac{1}{2}$
	4		19299	27607	3
$\frac{3}{8}$	5	" "	20415	27607	3 $\frac{1}{2}$
	6		21530	27607	4
	7		22593	27607	5
	10		25740	27607	7
$\frac{1}{2}$	8	" "	25444	32000	4 $\frac{1}{2}$
	10		27115	32000	5 $\frac{1}{2}$
	12		28320	32000	7
1	8	" "	27252	47903	5 $\frac{1}{2}$
	10		28490	47903	6
	12		29728	47903	7
1 $\frac{1}{4}$	8	" "	33844	48000	5 $\frac{1}{2}$
	10		34934	48000	6 $\frac{1}{4}$
	12		36023	48000	7
1 $\frac{1}{2}$	8	" "	40436	48827	5 $\frac{1}{2}$
	10		41377	48827	6
	12		42317	48827	7
1 $\frac{1}{2}$	8	" "	53951	58000	5 $\frac{1}{2}$
	10		55698	58000	6 $\frac{1}{2}$
	12		57444	58000	8

As Tested in 5000 PSI Concrete at these Minimum Embedments

Test Report available on request

ANSI/ASTM E488

ICBO Report #1821

SOURCE: AA Engineers & Associates, Inc., Denver, Colorado. Recommended safe working load is one-fourth Tensile and Shear values shown. Conversion to 2000 psi, multiply by .75 for 1/4", 5/16", 3/8" and 60 for other diameters.

CONCRETE BLOCK AND LIGHTWEIGHT CONCRETE LOAD DATA

Wej-it and Hole Diameter	2000 psi Concrete Block (Idealite) Tensile	5000 psi Lightweight Concrete (Idealite)	
		Tensile	Shear
$\frac{1}{4}$	545 lbs.	1861 lbs.	2316 lbs.
$\frac{3}{8}$	852 lbs.	2493 lbs.	3562 lbs.
$\frac{1}{2}$	1277 lbs.	3125 lbs.	4807 lbs.
$\frac{3}{4}$	2025 lbs.	4778 lbs.	22597 lbs.
$\frac{1}{4}$	---	6455 lbs.	25674 lbs.
$\frac{3}{8}$	---	17293 lbs.	27607 lbs.
1	---	21616 lbs.	47903 lbs.

DATE JUNE 2, 1981

EQUIPMENT NOMENCLATURE MINERAL INSULATED CABLE FASTENERS

EQUIPMENT IDENTIFICATION NO. N/A


LOCATION:

BUILDING VARIOUS

ELEVATION VARIOUS

PEAK G LEVEL MOST LIMITING G LEVEL, 5.005 g. 719' IN CONTAINMENT REF. 2

MASS OF EQUIPMENT 3 POUNDS/6 FEET FOR MI CABLE



$$F_x = F_y = (\text{Mass})(\text{Peak G For Elevation})(1.63)(1.5)$$

$$F_{\bar{v}} = F_v = 2/3 F_x$$

	Applied Force		Yield or Deformed
	Required	Actual	
$F_x =$	<u>36.7</u>	<u>60</u>	<u>No</u>
$F_y =$	<u>36.7</u>	<u>60</u>	<u>No</u>
$F_v =$	<u>24.5</u>	<u>60</u>	<u>No</u>
$F_{\bar{v}} =$	<u>24.5</u>	<u>60</u>	<u>No</u>

PERFORMED BY Robert A. Odegar APPROVED BY A. Dennis

(5)

ATTACHMENT 2 OF DPC LETTER,
LINDER TO CRUTCHFIELD, LAC-7484
DATED APRIL 23, 1981

ATTACHMENT 2

ANCHORAGE OF SAFETY RELATED COMPONENTS WITHIN
PANELS, CABINETS, AND ENCLOSURES

1.0 PURPOSE

To provide assurance that internal components of safety related cabinets, panels, and enclosures are positively anchored or restrained in the event of an earthquake at the LACBWR site.

2.0 SCOPE

Those safety related components required to mitigate the consequences of an accident shall be visually inspected for loose or improperly secured mountings. Devices that supply vital power, indication or control functions shall be included in this review.

3.0 FINDING

This review was conducted during a plant shutdown on 3/10/81 and 3/11/81. The components inspected include these major categories:

- (1) Switchgear,
- (2) Inverter and Battery Chargers, and
- (3) Various Distribution and Instrument Panels.

3.1 The following switchgear internals were visually inspected:

- (1) 1B Essential 480V
- (2) 19 480V Diesel Building MCC
- (3) 1B 125 VDC Diesel Building
- (4) 1A Essential 480V
- (5) Turbine Building 480V MCC 1A
- (6) Reactor Plant 125 VDC
- (7) Generator Plant 125 VDC MCC

All of the breakers used in the above switchgear are positively secured in one of two ways. The original Allis-Chalmers switchgear breakers are screwed into their normal operating position and additionally held by a spring tensioned latch. In order to remove the breakers, both mechanisms must be operated. Much of the equipment added after the original construction is locked into place with two tabs that are fastened with screws. All of the switchgears have door covers that are secured by at least two screws.

The transformers, bus bars, and instrument portions of the switchgear are firmly bolted to the frame or door panels.

3.2 The internals of the following inverters and battery chargers were visually inspected.

- (1) 1B Inverter
- (2) 1B Diesel Building Battery Charger
- (3) 1A Diesel Battery Charger Assembly and Output Breaker
- (4) Reactor Plant Battery Charger
- (5) Generator Plant Battery Charger

The internal components of the inverters and battery chargers are substantially anchored. The major items such as the transformers, rectifiers, and bus bars are bolted to the frame of the housing. The metering, switches, and control circuits are bolted to the frame or doors of the equipment. Access to these cabinets is secured by screws or heavy door latch mechanisms.

3.3 A variety of panels required inspection. They are listed in related groups to simplify the presentation of inspection results.

(1) Distribution Panels:

- (a) 125 VDC Diesel Building Distribution
- (b) 125 VDC Reactor Plant Distribution
- (c) 125 VDC Generator Plant Distribution
- (d) 1A Non-Interruptible 120V Bus
- (e) 1B Non-Interruptible 120V Bus
- (f) 1A Non-Interruptible 120V Bus Fuse Panel
- (g) Auxiliary Distribution Panel 125 VDC Generator Plant
- (h) 120V Turbine Building MCC1A

The circuit breakers in these applications snap into place and are held by screws or a cover plate secured by screws. The close fit between components allows no room for movement.

(2) Relay Panels:

- (a) Reactor Relay Cabinet
- (b) 480V Essential Bus Undervoltage Relay Cabinet

The internal components and relays are bolted or screwed to the internal framework of the cabinets. Several undervoltage relays are door mounted with bolts. These components are adequately secured.

(3) Instrument Panels

- (a) Benchboards D and E
- (b) 1B Diesel Generator Control Panel
- (c) Control Room Panels A, C, D, E, F, and G

Due to the diversity of instruments and switches, no uniform method of mounting was used. The majority of the metering is bolted to the panels or drawers. Switches are mounted on the panels and retained by flush mounting nuts. Most instrument modules (power suppliers, amplifiers, square root converters, relays, etc.) are mounted to the internal panel framework with one or more screws. Depending on the size, recorders are bolted into the vertical panels at two or four locations. Panel mounted drawers are secured by screws or rear mounted latches.

4.0 SUMMARY

The anchorage of the equipment inspected is reasonably assured to remain in place during a seismic event. At the maximum, assumed ground acceleration of .12 G, the existing mounting, if properly connected after maintenance or calibration, will sufficiently restrain the motion of internal components. As a result of this inspection a list of outstanding safety related, and non-safety related equipment was identified. This equipment will be modified as soon as possible to provide the added assurance of its anchorage during a seismic event.

(6)

NES TRANSMITTAL 5101-803,
DATED JUNE 2, 1982



JCLEAR
ENERGY
SERVICES, INC.

June 2, 1982
Reference No.: 5101-803

Mr. Richard E. Shimshak
Dairyland Power Cooperative
LaCrosse Boiling Water Reactor
P. O. Box 135
Genoa, WI 54632

Subject: Emergency Power Equipment Anchorages -
Transmittal of Calculations

Dear Mr. Shimshak:

Per your request, we are forwarding copies of calculations performed by NES for the subject task relating to items for which no modifications were required. The items in this category for which calculations are enclosed are as follows:

- Turbine Building 120-V Bus. Aux. Dist. Panel
- Solatron for Turbine Bldg. Reg. Bus.
- Transformer for Turbine Bldg. 120-V Bus. 480-240/120-V
- 1-B Emergency Diesel Generator
- 1-B Diesel Fuel Oil Day Tank
- 1-B Emergency Diesel Gen. Starting Batteries and Racks
- 1-B 480-V Ess. Bus.
- 1-B Static Inverter
- 1-B Diesel Building Battery Charger
- ACS Valve DC Motor Starter
- ACS Flow Transmitter
- Reactor Water Level No. 3 Transmitter
- HPCS Motor 1A
- HPCS Motor 1B
- 1C Static Inverter
- 1A 1 KVA Inverter
- 1A Inverter Input and Output Breakers
- 1A Inverter Meter Panel
- 120-V AC Non-Int. Bus. 1A
- 120-V AC Non-Int. Bus. 1A Fuse Panel


Mr. Richard E. Shimshak
5101-803

page 2

Based on discussions held between Tom Strnad, Paul Sampson and Bob Brimer, documentation for the remainder of the items analyzed (those requiring modifications) will be completed as follows. NES will forward additional copies of all previously transmitted drawings and sketches of required or proposed modifications to DPC. LACBWR personnel will modify these drawings as necessary to reflect the as-built condition and return the drawings to NES. NES will evaluate any deviations from the original modification recommendation and will update the calculations as required. Backup calculations corresponding to the actual installation details will then be forwarded to DPC.

Very truly yours,

NUCLEAR ENERGY SERVICES, INC.
NES Division



Craig F. Finnan,
Project Engineer

/al
enclosures

cc: W. Manion
R. Brimer
P. Sampson
J. Taylor

ENCLOSURE

BACKUP CALCULATIONS FOR ITEMS
REQUIRING NO MODIFICATION



NUCLEAR ENERGY SERVICES


BY TS DATE 2-9-81 PROJ. 5101 TASK 063
CHKD. JC DATE 12-17-81 PAGE 1 OF 1
CACBWR

TURBINE BLDG 120V BUS AUX. DIST. PANEL

REF.

H x W x D
16" x 10 1/2" x 4" ✓
ASSUME WT = 50 ✓

ATTACHMENT: 4 - 3/8" ✓
BOLTS CONNECTED TO ✓
SHEET METAL CABINET



HORIZONTAL ACCELERATION = 2g ✓

VERTICAL ACCELERATION = 3/3 x 2g = 1.33g ✓

X-DIR

SHEAR = $\frac{2 \times 50}{4} = 25 \text{ "/BOLT}$ ✓

TENSION = 0 ✓

Y-DIR

SHEAR = $\frac{2.33 \times 50}{4} = 29 \text{ "/BOLT}$ ✓

TENSION = 0 ✓

Z-DIR

TENSION = $\frac{2 \times 50}{4} = 25 \text{ "/BOLT}$ ✓

RSS FORCES - SHEAR = $\sqrt{25^2 + 29^2} = 38.3 \text{ "/BOLT}$ ✓

TENSION = 25 "/BOLT ✓

ASSUME A307 UNFINISHED BOLTS

E = 20 ksi ✓ F_v = 10 ksi ✓

CAPACITY: TENSION = $20 \times \frac{\pi}{4} (\frac{3}{8})^2 = 2.21 \text{ k}$ ✓

SHEAR = $10 \times \frac{\pi}{2} (\frac{3}{8})^2 = 1.10 \text{ k}$ ✓

$\frac{0.25}{2.21} + \frac{0.383}{1.10} = 0.496 < 1.0$ (O.K.) ✓

NO FIX REQUIRED




NUCLEAR ENERGY SERVICES

BY TS DATE 3-31-81 PROJ. 5101 TASK 06-
CHKD. R.P. DATE 4-9-81 PAGE 1 OF 1
LACRWR

SOLATRON FOR TURBINE BLDG REG. BUS

REF.

ASSUME: HORIZONTAL ACCELERATION = 2g
VERTICAL ACCEL. = $\frac{2}{3} \times 2g = 1.33g$
ASSUMED WEIGHT = 500 #
4 - $\frac{1}{2}$ " RED HEAD BOLTS



Z DIR

SHEAR: $\frac{2g \times 500}{4} = 250 \# / \text{BOLT} \checkmark$

TENSION: $\frac{2g \times 500}{4} = 250 \#$ $\frac{1000 \times 8.5}{2T \times 12} T = 359 \# / \text{BOLT} \checkmark$

Y DIR

SHEAR = 250 # / BOLT

TENSION: $1165 \times 0.5 = 2T \times 15 T = 330 \# / \text{BOLT} \checkmark$

X DIR

TENSION: $\frac{2g \times 500}{4} = 250 \# / \text{BOLT} \checkmark$

RSS FORCES TENSION: $\sqrt{359^2 + 330^2 + 250^2} = 545 \# \checkmark$

SHEAR: $\sqrt{250^2 + 250^2} = 354 \# \checkmark$

CAPACITY $\frac{1}{2}$ RED HEAD EXP. ANCHORS

TENSION = 1975 # SHEAR = 2100 # FS = 4

$\frac{545}{1975} + \frac{354}{2100} = 0.59 < 1.0 \text{ (OK)} \checkmark$ No fix required



NUCLEAR ENERGY SERVICES

BY LD DATE 3-1-81 PROJ. 3101 TASK 06
CHKD. R.R DATE 4-5-81 PAGE 1 OF 1
LACRWR

TRANSFORMER FOR TURBINE BLDG 120V BUS 480-240/120V


REF.

ASSUME: HORIZONTAL ACCELERATION = $2g$ ✓

VERTICAL ACCEL. = $\frac{1}{3} \times 2g = 1.33g$ ✓

ASSUMED WEIGHT = $500^{\#}$ ✓

ATTACHMENT = 4 $\frac{1}{2}^{\#}$ RED HEAD BOLTS



S.M.D

$$1000 \times 6.5 = 2T \times 8.75$$

$$T = 507 \text{ LBS/BOLT} \checkmark$$

$$\text{SHEAR} = \frac{1000}{4} = 250 \text{ LBS/BOLT} \checkmark$$

Y-DIR

$$\text{TENSION} = \frac{0.33 \times 500}{4} = 41 \text{ LBS/BOLT} \checkmark$$

RSS FORCES

$$\text{TENSION} = \sqrt{507^2 + 250^2 + 41^2} = 567 \text{ LBS/BOLT} \checkmark$$


$$\text{SHEAR} = \sqrt{250^2 + 250^2} = 354 \text{ LBS/BOLT} \checkmark$$

CAPACITY = 4 RED HEAD EXPANSION BOLTS

$$\text{TENSION} = \frac{5900}{4} = 1475 \text{ LBS} \checkmark$$

$$\text{SHEAR} = \frac{8900}{4} = 2225 \text{ LBS} \checkmark$$

$$\frac{567}{1475} + \frac{354}{2225} = 0.55 < 1.0 \text{ (O.K.)} \quad \therefore \text{No Fix Required!}$$



NUCLEAR ENERGY SERVICES

BY LS DATE 1-15-21 PROJ. 3101 TASK 06
CHKD. RR DATE 4-8-81 PAGE 1 OF 2
CALBWR SAFETY RELATED EQUIP.

WALL PANELS - ELECT. EQUIP. RM

REF.

ANCHOR BOLTS

4- $\frac{1}{2}$ " RED HEAD WEDGE ANCHORS

FOR ITEMS 5 FOR THE FOLLOWING EQUIPMENT.

1. I-I-C STATIC INVERTER
2. 7A 1 KVA INVERTER
3. 1A INVERTER INPUT & OUTPUT BREAKERS
4. 1A INVERTER METER PANEL
5. 120V AC NONINTERRUPTIBLE BUS 1A



6. 120V AC NONINTERRUPTIBLE BUS 1A FUSE PANEL

FOR ELECTRICAL EQUIPMENT ROOM

ASSUME: $2g$ HORIZ. ACCELERATION VERT. ACCEL. $\frac{1}{3} \times 2g = 1.33g$

MAXIMUM EQUIPMENT WEIGHT = 100 LBS

X DIR

$$F_x = 2 \times 100 = 200 \text{ lb}$$

$$\text{SHEAR} = \frac{200}{4} = 50 \text{ lb/bolt} \quad \text{TENSION} = 0$$

Z DIR

$$F_z = 2 \times 33 \times 100 = 660 \text{ lb}$$

$$\text{SHEAR} = \frac{660}{4} = 165 \text{ lb/bolt} \quad \text{TENSION} = 0$$

E DIR

$$\text{SHEAR} = 0 \quad \text{TENSION} = \frac{100}{4} = 25 \text{ lb/bolt}$$

RSS FORCES

$$\text{SHEAR} = \sqrt{50^2 + 165^2} = 172 \text{ lb/bolt} \quad \text{TENSION} = 25$$

BOLT CAPACITY

FOR A307 BOLT $F_u = 26 - 1.8 f_v \leq 20$ (AISC TABLE 1.6.3)

$$f_v = \frac{0.077}{0.196} = 0.393 \text{ ksi}$$

$$F_u = 26 - (1.8 \times 0.393) = 25.29 > 20 \Rightarrow F_u = 20 \text{ ksi}$$

$$\text{BOLT CAPACITY} = 20 \text{ ksi} \times 0.156 = 3.12 \text{ k} > 0.050 \text{ k} \quad (OK)$$



NUCLEAR ENERGY SERVICES

BY TS DATE 8-24-81 PROJ. 5/01 TASK 06
CHKD. R.R DATE 9/11/81 PAGE 1 OF 1
LCBWR

1-B DIESEL GENERATOR

REF.

ANCHORAGE DETAIL: 12 - 1" BOLTS

GENERATOR WEIGHT = 18,500 LBS ✓

HORIZ. ACCEL. = 1.5 x PEAK g FROM GROUND SPECTRA = 0.21g x 1.5 =

VERTICAL ACCEL. = $\frac{2}{3} \times 0.315g = 0.21g$ ✓

0.315g ✓

CHECK SHEAR

HORIZONTAL FORCE = 18,500 x 0.315g = 5828 ✓

EACH DIRECTION ✓

SHEAR FORCE / BOLT = $\frac{5828}{12} = 486$ LBS ✓

RESULTANT SHEAR FORCE = $\sqrt{486^2 + 486^2} = 687$ LBS / BOLT ✓

ANCHOR CAPACITY - 1" RED HEAD WEDGE ANCHORS

ULTIMATE SHEAR CAPACITY: 35,400 LBS ✓

PG. 6 RED HEAD
CAT. F-1000


ALLOWABLE CAPACITY = $\frac{35,400}{4} = 8850$ LBS ✓

8850 > 687 ✓ (O.K.)

NO FIX REQUIRED ✓

H13 DIESEL STARTING BATTERIES

REF.



ASSUME HORIZONTAL ACCELERATION = $1.5 \times 0.21g = 0.315g$ ✓
 VERTICAL ACCELERATION = $\frac{2}{3} \times 0.315g = 0.21g$ ✓

$\Sigma M_0 = 0$


OVERTURNING MOMENT = $10.5 \times 0.315W = 3.31W$ ✓

RESISTING MOMENT = $4.5 \times 0.79W = 3.56W$ ✓

FACTOR OF SAFETY = $\frac{3.56W}{3.31W} = 1.08$ ✓

Z RACKS STRAPPED TOGETHER

NO FIX REQUIRED



$\Sigma M_0 = 0$

OVERTURNING MOMENT = $2 \times (10.5 \times 0.315W) = 6.62W$ ✓

RESISTING MOMENT = $0.79 \times (4.5 + 13.5) = 14.22W$

FACTOR OF SAFETY = $14.22W / 6.62W = 2.15 > 1.5$ (O.K.) ✓




NUCLEAR ENERGY SERVICES

BY ME DATE 1/20/62 PROJ. 5701 TASK:
CHKD. TS DATE 5/28/62 PAGE 2 OF 2
LACBWR

DAY FUEL TANK ANCHORS - 1B

FULL WEIGHT $F_w = 3177 \text{ lbs}$ ✓
LATERAL FORCE $F_x = F_y = 3177 \times .315\% = 1000 \text{ lbs}$ ✓
VERTICAL FORCE $F_z = 3177 \times .21\% = 667 \text{ lbs}$ ✓

REF.
DRAW
S/L
M-10



CHECK FOR OVERTURNING ABOUT A-A AXIS

$$\Sigma M_{A \text{ OVERTURNING}} = 26(F_x) = 26000 \text{ in-lbs} \quad FS = \frac{45180}{26000}$$

$$\Sigma M_{A \text{ RESISTING}} = 18(F_w - F_z) = 45180 \text{ in-lbs} \quad = 1.74 \checkmark$$

SINCE RESISTING MOMENT IS GREATER THAN OVERTURNING MOMENT, ANCHOR BOLTS ARE NOT IN TENSION DUE TO OVERTURNING.



NUCLEAR ENERGY SERVICES


BY ATC DATE 3/13/84 PROJ. 1121 TASK 100
 CHKD. TS DATE 5/18/84 PAGE 3 OF 5
LABOUR

DAY FUEL TANK ANCHORS - 1/B

REF.

X-DIRECTION EARTHQUAKE

SIDESWAY



CHECK TENSION IN ANCHOR BOLTS
DUE TO LATERAL FORCE

$$\sum M_B = 18(F_x/2) - 5(2F_c) - 1(2F_0) = 0$$

$$\Rightarrow -9000 = 10F_c + 2F_0$$

ALSO WE HAVE:

$$\frac{1}{5} = \frac{F_0}{F_c} \Rightarrow F_0 = \frac{1}{5} F_c$$

SUBSTITUTING ABOVE

$$10.4F_c = 9000 \Rightarrow F_c = \underline{\underline{865 \text{ lbs TEN}}}$$

$$\text{AND } F_0 = \underline{\underline{173 \text{ lbs TEN}}}$$

SHEAR FORCE IN EACH BOLT:

$$\frac{F_x}{2} \div 4 \text{ bolts} = \frac{1000}{2} \div 4 = \underline{\underline{125 \text{ lbs SHEAR}}}$$



NUCLEAR ENERGY SERVICES

BY: HE DATE: 5/14/84 PROJ: S701 TASK: 063
CHKD: TS DATE: 6/1/82 PAGE: 4 OF: 5
LACBWR

DAY FUEL OIL TANK ANCHORS - 1B

REF.

$$F_x = F_y = 3177 \times .315g = 1000 \text{ lbs}$$

$$F_z = 3177 \times .21g = 667 \text{ lbs}$$

$$F_w = 3177 \text{ lbs}$$


SHEAR FORCE

$$\Sigma F_y = 1000$$

$$\frac{1000 \text{ lbs}}{8 \text{ bolts}} = 125 \text{ lbs/bolt}$$

⇒ SHEAR FORCE
is 125 lbs/bolt

Y-DIRECTION EARTHQUAKE



OVERTURNING

OVERTURNING MOMENT:


$$M_A = 26'' \times 1000 = 26000 \text{ in-lb}$$

RESISTING MOMENT:

$$15.5'' \times (3177 - 667) = 38,905 \text{ in-lb}$$

$$FS = \frac{38905}{26000} = 1.50$$

NO OVERTURNING DUE Y-DIR. EARTHQUAKE



NUCLEAR ENERGY SERVICES

BY ME DATE 5/15/82 PROJ. 5701 TASK 02
CHKD. TS DATE 6/1/82 PAGE 5 OF 5
CALC/BWR

1-B DIESEL FUEL OIL DAY TANK ANCHOR BOLTS

REF.

RSS MAXIMUM STRESSES

$$F_{\text{SHEAR}} = \sqrt{125^2 + 125^2} = 177 \text{ lbs SHEAR} \checkmark$$

DUE TO OVERSIZE HOLES THE ANCHOR BOLTS MAY NOT BE ABLE TO DEFORM SUFFICIENTLY SO THAT ALL EIGHT BOLTS COULD BE COUNTED UPON TO CARRY THE SHEAR LOAD. THEREFORE WE ASSUME ONLY FOUR BOLTS WILL CARRY THE LOAD SO THE SHEAR FORCE WILL BE:

$$177 \times 2 = 354 \text{ lbs/Bolt} \checkmark$$

$$F_{\text{TEN}} = 865 \text{ LBS} \checkmark$$

P.87

STRUCTURAL DETAILS IN INDUSTRIAL BUILDINGS SEE REF BELOW

ASSUME A36 STEEL - ANCHOR BOLTS
FROM AISC 8TH ED. PG. 4-5 ALLOWABLE SHEAR FORCE
PER BOLT IS $9.96 \times 3068 = 3040 \text{ lbs} \checkmark$ SHEAR

$$354 < 3040 \text{ lbs/bolt SHEAR} \checkmark$$

•• ALLOWABLE SHEAR FORCE IS NOT EXCEEDED.

FROM AISC 8TH ED. PG. 4-3 ALLOWABLE TENSILE FORCE
PER BOLT IS 5900 lbs/BOLT TEN.

$$865 < 5900 \checkmark$$

•• ALLOWABLE TENSILE FORCE IS STEEL BOLT IS

$$\text{NOT EXCEEDED. } \frac{F_t}{F_t} + \frac{F_v}{F_v} = \frac{865}{5900} + \frac{354}{3040} = 0.26 < 1.0 \text{ O.K.} \checkmark$$

FROM ENGINEERING JOURNAL/AISC, "STRUCTURAL DETAILS IN INDUSTRIAL BUILDINGS" P85,86 THIRD QUARTER 1981.

$\phi = .7$ ULTIMATE HOOK STRENGTH = $\phi f_c d L' = 3937 \text{ lbs/bolt} \checkmark$
 $f_c = 3000 \text{ psi}$ ASSUME LOAD FACTOR = 1.7. ALLOWABLE CAPACITY = 2316 LBS
 $d = 5/8$ $865 < 2316 \checkmark$
 $L' = 3"$ •• PULL OUT STRENGTH IS NOT EXCEEDED

CONCLUSION: ANCHOR BOLTS ARE ADEQUATE.

NO FIX REQUIRED.



NUCLEAR ENERGY SERVICES


I-B GENERATOR BLDG - ELECTRICAL EQUIPMENT

REF.

THE FOLLOWING PANELS ARE INCLUDED IN THIS CALCULATION

1. I-B 480-V ESS. BUS
2. I-B STATIC INVERTER
3. I-B DIESEL BUILDING BATTERY CHARGER

ISX NR SITE SPECIFIC
 PEAK HORIZ ACCELERATION FROM GROUND SPECTRA = $0.21g \times 1.5 = 0.315g$
 VERTICAL ACCELERATION = $\frac{1}{3} \times 0.315g = 0.105g$



$\Sigma MA = 0$

$M_{RESIST} = 0.79W \times \frac{D}{2}$

$M_{OVER} = 0.315W \times \frac{H}{2}$

FOR $M_{RESIST} = M_{OVER}$

$0.79W \times \frac{D}{2} = 0.315W \times \frac{H}{2}$

$\frac{H}{D} = 2.51 \checkmark$

FOR $H/D < 2.51$ NO OVERTURNING ✓



1-B GENERATOR BLDG - ELECTRICAL EQUIPMENT

REF.

1. 1-B 480-V. ESS. BUS

W	x	D	x	H	
WIDTH		DEPTH		HEIGHT	
6'-6"	x	4'-8"	x	7'-8"	$\sqrt{H/D} = \frac{92}{56} = 1.65$ NO OVERTURNING

NO FIX REQUIRED

2. 1-B STATIC INVERTER

4'-7 1/2"	x	3'-0"	x	6'-6"	$\sqrt{H/D} = \frac{78}{36} = 2.17$ NO OVERTURNING
-----------	---	-------	---	-------	--

NO FIX REQUIRED

3. 1-B DIESEL BLDG. BATTERY CHARGER


4'-0"	x	3'-0"	x	6'-6"	$\sqrt{H/D} = \frac{78}{36} = 2.17$ NO OVERTURNING
-------	---	-------	---	-------	--

NO FIX REQUIRED

ACS VALVE DC MOTOR STARTER

ANCHORAGE : 4-1/4" RED HEAD WEDGE ANCHORS ✓
 WEIGHT = 40 LBS ✓

ASSUME : 2g HORIZONTAL ACCELERATION
 VERTICAL ACCEL. = 2/3 x 2g = 1.33g



X DIRECTION

$F_x = 2 \times 40 = 80$ ✓

SHEAR = $80 / 4 = 20$ / BOLT ✓

Y- DIR.

$F_y = 1.33 \times 40 = 53.2$ ✓ SHEAR = $93.2 / 4 = 23.3$ / BOLT ✓

Z- DIR.

$F_z = 80$ ✓ TENSION = 20 / BOLT ✓

RSS FORCES SHEAR = $\sqrt{20^2 + 23.3^2} = 30.7$ ✓ TENSION = 20 ✓

ULTIMATE BOLT CAPACITY

TENSION = 2400 ✓ } for $f_c = 3500$ PSI F-100 PS. 6
 SHEAR = 2325 ✓ } ✓ RED HEAD CATALOG

ALLOWABLE CAPACITY

FACTOR OF SAFETY = 4 TENSION = $2400 / 4 = 600$ ✓
 SHEAR = $2325 / 4 = 581$ ✓

$\frac{20}{600} + \frac{30.7}{581} \leq 1.0$

0.086 < 1.0 ✓ (O.K.)


4-1/4 RED HEAD WEDGE ANCHORS ADEQUATE NO FIX REQUIRED



NUCLEAR ENERGY SERVICES

WATER LEVEL TRANSMITTER #3

REF.



* ASSUME WT = 50^{lb}

G-VALUE = 2.58
 C EL 66.7

X-DIRECTION CONSIDERATION

$$F = 2.58 \times .05 \times 1.5$$

$$F = 0.194 \text{ K}$$

$$d = 12''$$

$$M = Fd = 0.194 \times 12$$

$$M = 2.33 \text{ IN-K}$$

$$A_b = \pi \frac{d^2}{4} = 0.196$$

FORCE IN BOLT =

$$F_b = \frac{M}{d} = \frac{2.33}{12} = 0.388 \text{ K}$$

$$\text{Tension Stress } f_t = \frac{0.194}{0.196} = 0.98 \text{ KSI}$$

$$f_v = \frac{0.05}{0.196 \times 4} = 0.063 \text{ KSI}$$

NEGLECT

Y-DIRECTION CONSIDERATION

$$\text{TORQUE DUE TO } y \text{ DIRECTION} = 0.194 \times 9 = 1.75 \text{ IN-K}$$

$$M_z \text{ MOMENT} = 0.194 \times 12 = 2.33 \text{ IN-K}$$

SECTION AT BASE = 6x1/2

$$S = \frac{bd^2}{6} = \frac{6(1.5)^2}{6} = 0.25$$

$$f_b \text{ BENDING STRESS} = \frac{2.33}{0.25} = 9.32 \text{ KSI}$$

$$\tau = \frac{3T}{bt^2} = \frac{3 \times 1.75}{6 \times 1.5^2} = 3.5 \text{ KSI}$$



NUCLEAR ENERGY SERVICES

BY K.K DATE 3-2-81 PROJ. S101 TASK 2
 CHKD. FS DATE 9-7-81 PAGE 2 C. 3
LACBWR

WATER LEVEL TRANSMITTER #3

REF.


Z - DIRECTION CONSIDERATION

$$M_z = 0.194 \times 12 - 2.33 \text{ in-k} \checkmark$$

SECTION MODULUS

$$S = \frac{bd^2}{6} = \frac{1.2 \times 6^2}{6}$$

$$S = 3 \text{ in}^3 \checkmark$$



$$f_b = \frac{M}{S} = \frac{2.33}{3} = 0.78 \text{ KSI} \checkmark$$

RSS RESULTANT STRESS

$$f_b = \sqrt{2 \times 0.78^2 + 9.32^2} \checkmark$$

$$f_b = 9.39 \text{ KSI} \checkmark$$

CHECK BOLTS (NOTE DIRECT ADDITION OF ALL FORCES WAS USED CONSERVATIVE)

$$M_y = 2.33 \text{ in-k} + 2.33 = 4.66 \text{ in-k} \checkmark$$

$$M_z = 2.33 \text{ in-k} = 2.33 \text{ in-k} \checkmark$$

$$F_T = \frac{3M}{2d} = \frac{4.66 \times 3}{6 \times 2} = 1.16 \text{ k/2 BOLTS} = 0.58 \text{ k/BOLT} \checkmark$$

$$X-DIR \quad F_{T2} = \frac{0.194}{4 \text{ BOLTS}} = 0.0485 \checkmark$$

$$\text{TOTAL TENSION/BOLT} = 0.629 \text{ k} \checkmark$$

$$\text{SHEAR} = F_x + F_z = 2 \times 0.194 = 0.388 \text{ k} / 4 \text{ BOLTS} = 0.097 \text{ k/BOLT} \checkmark$$

FOR RED HEAD 1/2 EXP BOLTS

5900# TENSILE = 1975
 8900# SHEAR = 2100
 F.S. = 4



NUCLEAR ENERGY SERVICES

BY K.K. DATE 3-22-81 PROJ. 5101 TASK 0
CHKD. TS DATE 4-2-81 PAGE 3 OF 3
LACBWR

WATER LEVEL TRANSMITTER #3

REF.

$$\frac{\text{APPLIED TENSILE LOAD}}{\text{TENSION CAPACITY}} + \frac{\text{APPLIED SHEAR}}{\text{SHEAR LOAD CAPACITY}} \leq 1$$

$$\frac{0.423}{1.475} + \frac{0.096}{2.100} = 0.47 \leq 1 \quad \text{OK} \quad \checkmark$$

HPCS PUMP 1A, 1B

REF.


HORIZONTAL, VERTICAL ACCELERATION = 0.25g

REF: GULF UNITED REPORT - FIG. 6.10 - INT. FLOOR SPECTRA, SSE EVENT - FOR HIGH FREQUENCY STRUCTURE

MOTOR WT = 1100#

PUMP WT = 1900#

4 - 3/16" ϕ ANCHOR BOLTS



X-DIR

$\Sigma M_A = 0$

OVERTURNING MOMENT = $18 \times 532 + 27 \times 308 = 16,099 \text{ in} \cdot \text{lb}$

RESISTING MOMENT = $13 (792 + 1368) = 28,080 \text{ in} \cdot \text{lb}$

FS OVERTURNING = $\frac{28,080}{16,099} = 1.75 \checkmark$

SHEAR = $\frac{308 + 532}{4} = 210 \text{ lb/BOLT} \checkmark$

Z-DIR

SHEAR 210 lb/BOLT

RESULTANT SHEAR = $\sqrt{210^2 + 210^2} = 297 \text{ lb/BOLT} \checkmark$

BOLT MATERIAL: ASSUME A36 : $F_v = 0.17 F_u = (0.17)(58) = 9.9 \text{ ksi}$

$f_v = \frac{0.3}{0.299} = 1.21 \text{ ksi} < 9.9 \text{ ksi (O.K.)}$

8th
7th
4-5



NUCLEAR ENERGY SERVICES


BY JS DATE 1-21 PROJ. 3701 TASK 5

CHKD. JC DATE 12-28-81 PAGE 1 OF 3

LACBWR

ALT. CORE SPRAY FLOW TRANSMITTER.

REF.




TRANSMITTER WT = 30 LBS EACH
 ASSUME HORIZONTAL ACCELERATION = 2g
 VERTICAL ACCELERATION = 5.2g = 1.33g
 TRANSMITTER TO CHANNEL CONNECTION

SECT A-A



X-DIR



$6 \times 60 = 6.5V$
 $V = 55.4 \text{ LBS}$

RESISTANT SHEAR = $\sqrt{55.4^2 + 30^2} = 63 \text{ LBS}$

Y-DIR

SHEAR = $\frac{30 \times 2.33g}{2} = 35 \text{ LBS}$

Z-DIR

$EM = 0$
 $60 \times 6 = 2 \times 2T$

RSS FORCES

$T = 120 \text{ LBS}$

SHEAR = $\sqrt{63^2 + 35^2} = 72 \text{ LBS}$

TENSION = 120 LBS

ACS FLOW TRANSMITTER


FOR $\frac{3}{8}$ " BOLT ✓ FOR A36 $F_u = 58 \text{ ksi}$ ✓
 $f_v = \frac{7\%}{0.110} = 0.65 \text{ ksi}$ ✓ $F_v = 0.17 F_u = 9.86 \text{ ksi}$ ✓ (OK)
 $F_t = \frac{12\%}{0.110} = 1.09 \text{ ksi}$ ✓ $F_t = 19.1 \text{ ksi}$ ✓ (OK)

REF.

 ETHEC
 AISC
 B4-3
 4-5


CHANNEL ANCHOR BOLTS

X-DIR



$F_H = \frac{5 \times 60}{2} = 150 \text{ "/BOLT}$ ✓ $\text{SHEAR} = \sqrt{150^2 + 20^2} = 151 \text{ "/BOLT}$ ✓
 $F_V = \frac{5 \times 360}{89} = 20 \text{ "/BOLT}$ ✓

Y-DIR



$M_0 = 0$ $(70 \times 6.75)(5) = 2T \times 2$ ✓
 $T = 590 \text{ "/BOLT}$ ✓
 $\text{SHEAR} = \frac{5 \times 70}{2} = 175 \text{ "/BOLT}$ ✓

Z-DIR

$M_0 = 0$
 $(60 \times 8)(5) = 2T \times 2$ ✓
 $T = 600 \text{ "/BOLT}$ ✓

RSS FORCES

$\text{SHEAR} = \sqrt{151^2 + 175^2} = 231 \text{ "/BOLT}$ ✓
 $\text{TENSION} = \sqrt{600^2 + 590^2} = 841 \text{ "/BOLT}$ ✓



NUCLEAR ENERGY SERVICES

BY TS DATE 7-9-81 PROJ. 5101 TASK C
CHKD. JL DATE 12-28-81 PAGE 3 OF 3
LECBWR

ACS FLOW TRANSMITTER

REF.

FOR $\frac{5}{8}$ " RED HEAD WEDGE ANCHOR

ULTIMATE CAPACITY

TENSION = 7825# ✓

SHEAR = 12,000# ✓

ALLOWABLE CAPACITY - TENSION $\frac{7825}{4} = 1956\#$ ✓

SHEAR $\frac{12,000}{4} = 3,000\#$ ✓

$\frac{891}{1956} + \frac{231}{3000} < 1.0$ ✓

$0.43 + 0.08 = 0.51 < 1.0$ ✓ $\frac{5}{8}$ " ANCHORS O.K.

NO FIX REQUIRED

(7)


NES TRANSMITTAL 5101-832,
DATED JANUARY 17, 1983

INVESTIGATION OF STABILITY OF CONTAINMENT BUILDING

REF.

INVESTIGATION OF STABILITY OF CONTAINMENT BUILDING

NRC Concern #
(1)(b)



FROM "SEISMIC AND STRESS ANALYSIS OF THE LACBWR CONTAINMENT BUILDING", P. B 244

VERTICAL LOAD DUE TO DEAD LOAD = $W_s = 17.08 \times 10^3 \text{ K}$

VERTICAL LOAD DUE TO SRSS EARTHQUAKE
 $= E_v = 1.51 \times 10^3 \text{ K}$

RESTORING MOMENT ABOUT A = M

$$M = (W_s - E_v) 30 = (17.08 \times 10^3 - 1.51 \times 10^3) 30$$

$$= 4.671 \times 10^5 \text{ K-ft}$$

$$= 5.61 \times 10^6 \text{ K-m}$$

INVESTIGATION OF STABILITY OF CONTAINMENT BUILDING

REF.

$$\text{MAX. MOMENT} = \sqrt{M_{X_1}^2 + M_{X_2}^2}$$

$$M_{X_1} = \text{MOMENT IN } X_1\text{-DIRN.} = 1.7522 \times 10^6 \text{ K-in}$$

$$M_{X_2} = \text{MOMENT IN } X_2\text{-DIRN.} = 2.6038 \times 10^6 \text{ K-in}$$

$$M_{\text{MAX}} = \sqrt{1.7322^2 + 2.6038^2} \quad (10^6)$$

$$= 3.13 \times 10^6 \text{ K-in.}$$

FACTOR OF SAFETY AGAINST TIPPING:

$$= \frac{5.61 \times 10^6}{3.13 \times 10^6}$$

$$= 1.79$$

Page.

6-244