



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D. C. 20555

ARKANSAS POWER & LIGHT COMPANY

DOCKET NO. 50-313

ARKANSAS NUCLEAR ONE, UNIT NO. 1

AMENDMENT TO FACILITY OPERATING LICENSE

Amendment No. 75  
License No. DPR-51

1. The Nuclear Regulatory Commission (the Commission) has found that:
  - A. The application for amendment by Arkansas Power & Light Company (the licensee) dated May 20, 1982, as modified January 14, 1983, complies with the standards and requirements of the Atomic Energy Act of 1954, as amended (the Act) and the Commission's rules and regulations set forth in 10 CFR Chapter I;
  - B. The facility will operate in conformity with the application, the provisions of the Act, and the rules and regulations of the Commission;
  - C. There is reasonable assurance (i) that the activities authorized by this amendment can be conducted without endangering the health and safety of the public, and (ii) that such activities will be conducted in compliance with the Commission's regulations;
  - D. The issuance of this amendment will not be inimical to the common defense and security or to the health and safety of the public; and
  - E. The issuance of this amendment is in accordance with 10 CFR Part 51 of the Commission's regulations and all applicable requirements have been satisfied.


2. Accordingly, the license is amended by changes to the Technical Specifications as indicated in the attachment to this license amendment, and paragraph 2.c.(2) of Facility Operating License No. DPR-51 is hereby amended to read as follows:

Technical Specifications

The Technical Specifications contained in Appendices A and B, as revised through Amendment No. 75, are hereby incorporated in the license. The licensee shall operate the facility in accordance with the Technical Specifications.

3. This license amendment is effective as of the date of its issuance.

FOR THE NUCLEAR REGULATORY COMMISSION



John F. Stolz, Chief  
Operating Reactors Branch #1  
Division of Licensing

Attachment:  
Changes to the Technical  
Specifications

Date of Issuance: April 4, 1983

ATTACHMENT TO LICENSE AMENDMENT NO. 75

FACILITY OPERATING LICENSE NO. DPR-51

DOCKET NO. 50-313

Replace the following pages of the Appendix "A" Technical Specifications with the enclosed pages. The revised pages are identified by Amendment number and contain vertical lines indicating the area of change.

Remove Pages

67

67a

Insert Pages

67

67a

#### 4 SURVEILLANCE STANDARDS

Specified surveillance intervals may be adjusted plus or minus 25 percent to accommodate normal test and surveillance schedules. The maximum combined interval for any 3 consecutive tests shall not exceed 3.25 times the specified surveillance interval. Surveillance requirements are not applicable when the plant operating conditions are below those requiring operability of the designated component. However, the required surveillance must be performed prior to reaching the operating conditions requiring operability. For example, instrumentation requiring twice per week surveillance when the reactor is critical need not have the required surveillance when the reactor is shutdown.

Failure to perform a Surveillance Requirement within the specified time interval shall constitute a failure to meet the OPERABILITY requirements for a Limiting Condition for Operation. Exceptions to these requirements are stated in the individual specifications. Surveillance Requirements do not have to be performed on inoperable equipment.

##### 4.1 OPERATIONAL SAFETY ITEMS

###### Applicability

Applies to items directly related to safety limits and limiting conditions for operation.

###### Objective

To specify the minimum frequency and type of surveillance to be applied to unit equipment and conditions.

###### Specification

- a. The minimum frequency and type of surveillance required for reactor protective system and engineered safeguards system instrumentation when the reactor is critical shall be as stated in Table 4.1-1.
- b. Equipment and sampling test shall be performed as detailed in Tables 4.1-2 and 4.1-3.
- c. Discrepancies noted during surveillance testing will be corrected and recorded.
- d. A power distribution map shall be made to verify the expected power distribution at periodic intervals at least every 10 effective full power days using the incore instrumentation detector system.

### Bases

The provisions of this specification set forth the criteria for determination of compliance with the OPERABILITY requirements of the Limiting Conditions for Operation. Under these criteria, equipment, systems or components are assumed to be OPERABLE if the associated surveillance activities have been satisfactorily performed within the specified time interval. Nothing in this provision is to be construed as defining equipment, systems or components OPERABLE, when such items are found or known to be inoperable although still meeting the Surveillance Requirements.

### Check

Failures such as blown instrument fuses, defective indicators, faulted amplifiers which result in "upscale" or "downscale" indication can be easily recognized by simple observation of the functioning of an instrument or system. Furthermore, such failures are, in many cases, revealed by alarm or annunciator action. Comparison of output and/or state of independent channels measuring the same variable supplements this type of built-in surveillance. Based on experience in operation of both conventional and nuclear plant systems, when the plant is in operation, the minimum checking frequency stated is deemed adequate for reactor system instrumentation.

### Calibration

Calibration shall be performed to assure the presentation and acquisition of accurate information. The nuclear flux (power range) channels shall be calibrated at least twice weekly (during steady state operating conditions) against a heat balance standard to compensate for instrumentation drift. During nonsteady state operation, the nuclear flux channels shall be calibrated daily to compensate for instrumentation drift and changing rod patterns and core physics parameters.



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D. C. 20555

ARKANSAS POWER & LIGHT COMPANY

DOCKET NO. 50-368

ARKANSAS NUCLEAR ONE, UNIT NO. 2

AMENDMENT TO FACILITY OPERATING LICENSE

Amendment No. 42  
License No. NPF-6

1. The Nuclear Regulatory Commission (the Commission) has found that:
  - A. The application for amendment by Arkansas Power & Light Company (the licensee) dated May 28, 1982, as modified January 14, 1983, complies with the standards and requirements of the Atomic Energy Act of 1954, as amended (the Act) and the Commission's rules and regulations set forth in 10 CFR Chapter I;
  - B. The facility will operate in conformity with the application, the provisions of the Act, and the rules and regulations of the Commission;
  - C. There is reasonable assurance (i) that the activities authorized by this amendment can be conducted without endangering the health and safety of the public, and (ii) that such activities will be conducted in compliance with the Commission's regulations;
  - D. The issuance of this amendment will not be inimical to the common defense and security or to the health and safety of the public;  
and
  - E. The issuance of this amendment is in accordance with 10 CFR Part 51 of the Commission's regulations and all applicable requirements have been satisfied.


2. Accordingly, the license is amended by changes to the Technical Specifications as indicated in the attachment to this license amendment, and paragraph 2.C.(2) of Facility Operating License No. NPF-6 is hereby amended to read as follows:

Technical Specifications

The Technical Specifications contained in Appendices A and B, as revised through Amendment No. 42, are hereby incorporated in the license. The licensee shall operate the facility in accordance with the Technical Specifications.

3. This license amendment is effective as of the date of its issuance.

FOR THE NUCLEAR REGULATORY COMMISSION



Robert A. Clark, Chief  
Operating Reactors Branch #3  
Division of Licensing

Attachment:  
Changes to the Technical  
Specifications

Date of Issuance: April 4, 1983

ATTACHMENT TO LICENSE AMENDMENT NO. 42

FACILITY OPERATING LICENSE NO. NPF-6

DOCKET NO. 50-368

Replace the following page of the Appendix "A" Technical Specifications with the enclosed page. The revised page is identified by Amendment number and contains vertical lines indicating the area of change. The corresponding overleaf page is provided to maintain document completeness.

Remove Page

3/4 0-2

Insert Page

3/4 0-2

## 3/4 LIMITING CONDITIONS FOR OPERATION AND SURVEILLANCE REQUIREMENTS

### 3/4.0 APPLICABILITY

#### LIMITING CONDITION FOR OPERATION

3.0.1 Limiting Conditions for Operation and ACTION requirements shall be applicable during the OPERATIONAL MODES or other conditions specified for each specification.

3.0.2 Adherence to the requirements of the Limiting Condition for Operation and/or associated ACTION within the specified time interval shall constitute compliance with the specification. In the event the Limiting Condition for Operation is restored prior to expiration of the specified time interval, completion of the ACTION statement is not required.

3.0.3 In the event a Limiting Condition for Operation and/or associated ACTION requirements cannot be satisfied because of circumstances in excess of those addressed in the specification within 1 hour, action shall be initiated to place the unit in a mode in which the specification does not apply by placing it, as applicable, in at least HOT STANDBY within 6 hours, in at least HOT SHUTDOWN within the next 6 hours, and in at least COLD SHUTDOWN within the following 24 hours unless corrective measures are completed that permit operation under the permissible ACTION statements for the specified time interval as measured from initial discovery or until the reactor is placed in a MODE in which the specification is not applicable. Exceptions to these requirements shall be stated in the individual specification.

3.0.4 Entry into an OPERATIONAL MODE or other specified applicability condition shall not be made unless the conditions of the Limiting Condition for Operation are met without reliance on provisions contained in the ACTION statements unless otherwise excepted. This provision shall not prevent passage through OPERATIONAL MODES as required to comply with ACTION statements.

3.0.5 When a system, subsystem, train, component or device is determined to be inoperable solely because its emergency power source is inoperable, or solely because its normal power source is inoperable, it may be considered OPERABLE for the purpose of satisfying the requirements of its applicable Limiting Condition for Operation, provided: (1) its corresponding normal or emergency power source is OPERABLE; and (2) all of its redundant system(s), subsystem(s), train(s), component(s), and device(s) are OPERABLE, or likewise satisfy the requirements of this specification. Unless both conditions (1) and (2) are satisfied within 2 hours, action shall be initiated to place the unit in a MODE in which the applicable Limiting Condition for Operation does not apply by placing it, as applicable, in at least HOT STANDBY within 6 hours, in at least HOT SHUTDOWN within the next 6 hours, and in at least COLD SHUTDOWN within the following 24 hours. This specification is not applicable in MODES 5 or 6.

## SURVEILLANCE REQUIREMENTS

4.0.1 Surveillance Requirements shall be applicable during the OPERATIONAL MODES or other conditions specified for individual Limiting Conditions for Operation unless otherwise stated in an individual Surveillance Requirement.

4.0.2 Each Surveillance Requirement shall be performed within the specified time interval with:

- a. A maximum allowable extension not to exceed 25% of the surveillance interval, and
- b. A total maximum combined interval time for any 3 consecutive surveillance intervals not to exceed 3.25 times the specified surveillance interval.

4.0.3 Failure to perform a Surveillance Requirement within the specified time interval shall constitute a failure to meet the OPERABILITY requirements for a Limiting Condition for Operation. Exceptions to these requirements are stated in the individual specifications. Surveillance Requirements do not have to be performed on inoperable equipment.

4.0.4 Entry into an OPERATIONAL MODE or other specified applicability condition shall not be made unless the Surveillance Requirement(s) associated with the Limiting Condition for Operation have been performed within the stated surveillance interval or as otherwise specified.

4.0.5 Surveillance Requirements for inservice inspection and testing of ASME Code Class 1, 2 and 3 components shall be applicable as follows:

- a. During the time period:
  1. From issuance of the Facility Operating License to the start of facility commercial operation, inservice testing of ASME Code Class 1, 2 and 3 pumps and valves shall be performed in accordance with Section XI of the ASME Boiler and Pressure Vessel Code 1974 Edition, and Addenda through Summer 1975, except where specific written relief has been granted by the Commission.
  2. Following start of facility commercial operation, inservice inspection of ASME Code Class 1, 2 and 3 components and inservice testing of ASME Code Class 1, 2 and 3 pumps and valves shall be performed in accordance with Section XI of the ASME Boiler and Pressure Vessel Code and applicable Addenda as required by 10 CFR 50, Section 50.55a(g), except where specific written relief has been granted by the Commission pursuant to 10 CFR 50, Section 50.55a(g)(6)(i).