


SOUTH TEXAS PROJECT ELECTRIC GENERATING STATION

SPECIFICATION
 FOR
 ALTERNATE VALVE PACKING AND LIVE LOAD DESIGN
 HOUSTON LIGHTING & POWER CO.

SPECIFICATION NO. 5L749TS1018

RPE CERTIFICATIONS

REV.	DATE	BY
ms		
ms		
ms	94	



ASME SECTION III RPE CERTIFICATION REQUIRED YES NO

THIS IS TO CERTIFY THAT THIS DOCUMENT HAS BEEN REVIEWED BY ME, THE UNDERSIGNED, AND IS CORRECT, COMPLETE, AND IN COMPLIANCE WITH THE _____ EDITION, WITH ADDENDA UP TO AND INCLUDING THE _____ ADDENDUM, OF THE ASME CODE SECTION III, DIVISION 1 PARAGRAPH NCA-3252 (CONTENTS OF DESIGN SPECIFICATIONS).

 ⊖ N/A / N/A N/A N/A
 REV. NO. SIGNATURE/DATE PRINT NAME RPE NO.

REV	DATE	REVISION DESCRIPTION	RE	REW	SE	NA	PE
0	6/25/90	Issued for Purchase/Construction	ms	ms	ms	ms	ms
1	7/20/90	Revised Spec. No. from 5L749TS1017 to Correct Duplicate Sequence No.	ms	ms	ms	ms	ms

STP 3259C (06/93)
REV 4

SOUTH TEXAS PROJECT ELECTRIC GENERATING STATION
PCF AMENDMENT FORM

090911

T40534 (Page 1 of 3)

940179
PCF NUMBER

1. Affected Document 5L749TS1018 Rev. 1 Unit 1 & 2 2. Amendment 1
Key Document Yes No Page 1 of 3

3. Description of the change (Identify affected pages for Vendor Manual, specifications, DBD's, etc.).

Revise Section 5.1 and Figure 2 of specification no. 5L749TS1018 as shown on the attached pages to allow the use of Chesterton Style 5800 wedge type packing set.

Quoc V. Huynh 15/24/94 J. Starks 15-25-94 s. 7-25-94
ENGINEER DATE REVIEWER DATE DC ISSUE DATE

INSERT G: (FROM DCN # MS-62)

5.1 The following manufacturers and model numbers are acceptable:

5.1.1 Braided End Rings

A. Chesterton Style 1

B. Argo Style 524

5.1.2 Die Formed Square Graphite Rings


A. Chesterton Style 5300

B. Argo Style 6300

5.1.3 EPRI Wedge Die Formed Graphite Rings

A. Chesterton Style 5350 OR CHESTERTON STYLE 5800 WEDGE

THIS
PCF



5.1.4 Split Carbon Bushings

A. Chesterton Style 5100

B. Argo Style 5005

5.1.5 Live Loading Assemblies

A. Chesterton Style 5150


B. Argo Style 6250

5.1.6 Composite End Rings

A. Argo Style 6000

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER REV PAGE
SL749TB1018 1 11



NOTE:

CHESTERTON STYLE 5800 WEDGE may be used as an alternate packing set for the EPRI wedge packing set, CHESTERTON STYLE 5350. STYLE 5800 WEDGE is a five-ring graphite packing set which consists of two die-formed end rings, two inside diameter sealing rings and one outside diameter sealing ring.

EPRI WEDGE PACKING SET

FIGURE 2

D6864

STP 627 (02/93)

SOUTH TEXAS PROJECT ELECTRIC GENERATING STATION

2. DCN NO. M5-94

REV 1
DEP-6 030

DOCUMENT CHANGE NOTICE

PAGE 1 OF 3

17. QUALITY RELATED

CHANGE YES NO

PRIORITY 4 PRI. AUTH. _____

1. DOCUMENT TYPE/TITLE: SPECIFICATION FOR ALTERNATE VALVE PACKING AND LIVE LOAD DESIGN. SYSTEM VARIOUS CORRESP. UNIT DCN. N/A

4. DOCUMENT NO./REV. NO. 52749TS1018 REV. 1 7. KEY DRAWING YES NO 3. UNIT 1 2 BOTH

DOCUMENT NO./REV. NO. _____ KEY DRAWING YES NO 18. DC ISSUE DATE 2/5/93

ADDITIONAL AFFECTED DOCUMENTS LISTED ON PAGE N/A

8. RE/REQUESTOR DATE

B. J. Mower 2-4-93

9. REVIEWER DATE


J. Starks 2-4-93

10. OTHER DISCIPLINE(S) APPROVAL DATE

N/A

5. REASON FOR CHANGE: TO ADD VENDOR RECOMMENDATIONS TO SPECIFICATION FOR PACKING ADJUSTMENT OF ALTERNATE AND/OR LIVE LOADED VALVES.

6. CHANGE DESCRIPTION: ADD SECTION 4.13 TO PAGE 6 AS PER ATTACHED. INCORPORATION REQUIRED YES NO



11. PED CONCURRENCE DATE
(REQ. FOR KEY DWGS AND FOR SETPOINT CHANGES)

N/A

12-31 REQUIRED? YES NO

12. RPE SIGNATURE DATE

N/A

ENG. NOTIFICATION REQ. FOLLOWING INSTALLATION? YES NO PCF/ECNP/MOD PACKAGE REQ. PRIOR TO INSTALLATION? YES NO

15. ADDITIONAL INFORMATION: YES NO YES NO
A. NPOD PROG./PROC. POTENTIALLY IMPACTED C. PLANT LABELING CHANGE
B. 10CFR50.59 EVALUATION ATTACHED D. MED. CHANGE FORM NO. N/A

IF NO, PROVIDE PRELIMINARY SCREENING JUSTIFICATION:

14. HL&P SE OR A/E SE OR DED APPROVAL DATE

J. Brown 2/4/93

16. PLANT LABELING COORD. CONCUR. (IF APPLICABLE)

N/A 1
DATE

4.13 Packing Adjustment FOR VALVES REPACKED WITH CHESTERTON PRODUCTS

- 4.13.1 If valve develops a leak tighten gland nut to the torque value which was specified.
- 4.13.2 If leakage continues torque value may be increased by as much as 20%.
- 4.13.3 Increase torque in increments of 5% until leakage is stopped.
- 4.13.4 If leakage continues valve may have to be repacked.

10CFR50.59 SCREENING FORM

(TYPICAL)

PAGE 3 OF 3
ESM
2-1-93

UNIT #1 PROCEDURE PLANT MODIFICATION ECNP DCM

UNIT #2

BOTH UFSAR CN OTHER _____

ORIGINATING DOCUMENT NO.: 5L749TS1018 REV. NO.: 1

DESCRIPTION OF CHANGE: ADD VENDOR RECOMENDATIONS FOR PACKING ADJUSTMENTS OF ALTERNATE AND/OR LIVE LOADED VALVES

REASON FOR CHANGE: TO PROVIDE DIRECTION AND/OR RECOMEN-DATIONS IF VALVES INCUR PACKING LEAKS

PRELIMINARY SCREENING

- | | YES | NO |
|---|-------------------------------------|-------------------------------------|
| 1. Does the proposed change represent a change to the Plant Technical Specifications? | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| 2. If an Unreviewed Safety Question is known to be associated with the subject change, then further screening is not required; refer to IP-1.190.
If "Yes" refer to IP-1.190. Further screening is not required. | | |
| Does the proposed change represent: | YES | NO |
| 3. A change to correct a typographical, editorial or drafting error? | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| 4. A change which is identical to and addressed in its entirety by an existing approved 10CFR50.59 Screening/USQE? | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| 5. A procedure change in which the format or text changed without changing actions or intent? | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| 6. A spare or replacement part/component change with an equivalent part/component? (see Section 3.16 for a definition of equivalent) | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

If all answers to the above questions are "No" perform the final screening and mark N/A in the approval blocks below.

If the answer to any question (3) through (6) is "Yes" a final screening is not necessary. Sign approval blocks below and discard pages 2 thru 4.

Provide an explanation/justification and references if any of items (3) through (6) are answered "Yes".

#3 THE CHANGE TO THE SPECIFICATION IS EDITORIAL IN NATURE AS DURING INCEPTION OF THE SPECIFICATION DIRECTION AND/OR RECOMMENDATIONS WERE NOT SPECIFIED IN THE EVENT THAT VALVES REPACKED IN ACCORDANCE WITH THE SPECIFICATION INCURRED LEAKAGE.

Prepared by: B. S. Mower Originator

2-4-93
Date

Approved by: [Signature] Section Supervisor

2/4/93
Date

0692

STP 627 (02/93)
RE / 1

SOUTH TEXAS PROJECT ELECTRIC GENERATING STATION

2. DCN NO. MS-112

OEP-6 03Q

DOCUMENT CHANGE NOTICE

PAGE 1 OF 2 TRM 9
8-6-93

17. QUALITY RELATED CHANGE YES NO

PRIORITY 4B PRI. AUTH. N/A

1. DOCUMENT TYPE/TITLE: SPECIFICATION / ALTERNATE VALVE PACKING... SYSTEM VARIOUS CORRESP. UNIT DCN. N/A

4. DOCUMENT NO./REV. NO. 5L749TS1018 / REV. 1 7. KEY DRAWING YES NO 3. UNIT 1 2 BOTH

DOCUMENT NO./REV. NO. N/A KEY DRAWING YES NO 18. DC ISSUE DATE 8/27/93

ADDITIONAL AFFECTED DOCUMENTS LISTED ON PAGE N/A


8. RE/REQUESTOR Carl Engelken DATE 8/4/93
CARL ENGELKEN MTS-N x7583

5. REASON FOR CHANGE: ALLOW ALTERNATE TEST METHODS FOR THE DETERMINATION OF DENSITY AND SULFER CONTENT. CORRECT TYPOGRAPHICAL ERROR FOR ASH CONTENT LIMIT.

9. REVIEWER R. W. Ricum DATE 8-6-93

10. OTHER DISCIPLINE(S) APPROVAL DATE
N/A

6. CHANGE DESCRIPTION: INCORPORATION REQUIRED YES NO
INCORPORATE THE CHANGES SHOWN ONE PAGES 2 AND 3 OF THIS DCN.



11. PED CONCURRENCE (REQ. FOR KEY DWGS AND FOR SETPOINT CHANGES) DATE
N/A
ZE - 31 REQUIRED? YES NO

ENG. NOTIFICATION REQD. FOLLOWING INSTALLATION? YES NO PCF/ECNP/MOD PACKAGE REVIEWED PRIOR TO INSTALLATION? YES NO

12. RPE SIGNATURE DATE
N/A

15. ADDITIONAL INFORMATION: YES NO YES NO
A. NPOD PROG./PROC. POTENTIALLY IMPACTED C. PLANT LABELING CHANGE
B. 10CFR50.59 EVALUATION ATTACHED D. MED CHANGE FORM NO. N/A

IF NO, PROVIDE PRELIMINARY SCREENING JUSTIFICATION:

14. HL&P SE OR A/E SE OR DED APPROVAL DATE
Dwight C. Huynh 6/23/93

16. PLANT LABELING COORD. CONCUR. (IF APPLICABLE)

N/A / 1 / DATE

TITLE
 ALTERNATE VALVE PACKING
 AND LIVE LOAD DESIGN

NUMBER **REV** **PAGE**
 5L749T51018 1 9

CHEMICAL AND PHYSICAL PROPERTIES

<u>PROPERTY</u>	<u>BRAIDED RINGS</u>	<u>DIE-FORMED RINGS</u>	<u>TEST METHOD</u>
CARBON % min.	97	97	ASTM-D-3178-84 PARA.4.2.3.2
ASH % ^{MAX} min.	3	3	ASTM-C-561-85 PARA.4.2.3.2
MOISTURE % max.	3	3	ASTM-C-562-85 PARA.4.2.3.2
DENSITY g/cc 1.4 min.			ASTM-C-135-76 PARA.4.2.3.3
DENSITY g/cc		1.30-1.50	WATER IMMERSION OR DENSITY FORMULA SHOWN BELOW **
WATER LEACHABLE CHLORIDES ppm max.	100	50	ASTM-D-512-81 METHOD D OR ION CHROMATOGRAPHY
WATER LEACHABLE FLUORIDES ppm max.	100	50	ASTM-D-1179-80 METHOD B OR ION CHROMATOGRAPHY
TOTAL CHLORINE ppm max.	200	200	ASTM-D-808-81 OR ION CHROMATOGRAPHY
TOTAL FLUORINE ppm max.	200	200	ASTM-D-3761-84 OR ION CHROMATOGRAPHY
ACTIVE SULPHUR ppm max.	700	700	ASTM-D-129-78, ASTM C 816-85 OR ION CHROMATOGRAPHY
TOTAL HEAVY METALS ppm max.	200	200	ATOMIC ABSORPTION
INDIVIDUAL HEAVY METAL* ppm max.	150	150	ATOMIC ABSORPTION

* ANTIMONY, ARSENIC, BISMUTH, CADMIUM, COPPER, GALLIUM, INDIUM, LEAD, MERCURY, SILVER, TIN, & ZINC

** DENSITY FORMULA (FOR DIE-FORMED RINGS ONLY):

$$DENSITY \left(\frac{g}{cm^3} \right) = \frac{WEIGHT (g)}{\left[\pi \left(\frac{OD (cm)}{2} \right)^2 - \pi \left(\frac{ID (cm)}{2} \right)^2 \right] \times HEIGHT (cm)}$$

TABLE 2

10CFR50.59 SCREENING FORM

(TYPICAL)

PAGE 1 of 1

UNIT #1 PROCEDURE PLANT MODIFICATION ECNP DCN
 UNIT #2
 BOTH UFSAR CN OTHER _____

ORIGINATING DOCUMENT NO.: DCN-MS-112 REV. NO. NA

DESCRIPTION OF CHANGE: Incorporation of alternate methods to calculate material density and to test Sulphur content in Graphite. Correction of editorial error regarding max. ash content.

REASON FOR CHANGE: Allow alternate methods for the determination of density and Sulphur content. Correct typographical error for ash content limit.

PRELIMINARY SCREENING

- | | YES | NO |
|---|-------------------------------------|-------------------------------------|
| 1. Does the proposed change represent a change to the Plant Technical Specifications? | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| 2. If an Unreviewed Safety Question is known to be associated with the subject change, then further screening is not required; refer to IP-1.190. | | |
| If "Yes" refer to IP-1.190. Further screening is not required. | | |
| Does the proposed change represent: | | |
| 3. A change to correct a typographical, editorial or drafting error? | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| 4. A change which is identical to and addressed in its entirety by an existing approved 10CFR50.59 Screening/USQE? | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| 5. A procedure change in which the format or text changed without changing actions or intent? | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| 6. A spare or replacement part/component change with an equivalent part/component? (see Section 3.16 for a definition of equivalent) | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

If all answers to the above questions are "No" perform the final screening and mark N/A in the approval blocks below.

If the answer to any question (3) through (6) is "Yes" a final screening is not necessary. Sign approval blocks below and discard pages 2 thru 4.

Provide an explanation/justification and references if any of items (3) through (6) are answered "Yes".
This is a paper change only. An obvious typographical error was corrected to limit the ash content to 3% maximum and an alternate method to determine material density by calculation instead of the cumbersome submersion method was added. Also added to the procedure was an ASTM approved combustion-iodometric Titration method for determination of Sulphur content in Graphite (ASTM C 816-85). This new method is a substitute for the old method using an explosive device. The updating will ensure that correct replacement parts are used for valve packings. There is no change in the intent of this specification. Form, fit and function of the valve packings are not changed in any way by this DCN.

Prepared by: R. M. Bice
 Originator

8-6-93
 Date

Approved by: Quoc K. Huong
 Section Supervisor

8/23/93
 Date

06773

SIP 627 (10/91)
SEP-6.030

SOUTH TEXAS PROJECT ELECTRIC GENERATING STATION

2. DCN NO. MS-02
PAGE 1 OF 48
PRIORITY 2 PRL AUTH. 1RE04
5/7/92

DOCUMENT CHANGE NOTICE

17. QUALITY RELATED CHANGE YES NO

1. DOCUMENT TYPE/TITLE: SPEC/ALTERNATE VALVE PACKING SYSTEM VARIOUS CORRESP. UNIT DCN. N/A

4. DOCUMENT NO./REV. NO. 5L749TS1018/1 7. KEY DRAWING YES NO 3. UNIT 1 2 BOTH
DOCUMENT NO./REV. NO. _____ KEY DRAWING YES NO 18. DC ISSUE DATE 5/8/92

8. RE/REQUESTOR DATE

Quoc K. Huynh 5-8-92

9. REVIEWER DATE

J. Harris 5-6-92

10. OTHER DISCIPLINE(S) APPROVAL DATE

R. M. Landry 5/8/92
(REL. DCN EP-176)

5. REASON FOR CHANGE: (REF. RFA 91-1420 & SPR 910322 R7)
TO ALLOW ALTERNATE VALVE PACKING DESIGN.
(ARGO). THIS CHANGE WILL IMPROVE MATERIALS
DELIVERY AND PROVIDES FLEXIBILITY FOR MAINTENANCE.

11. PED CONCURRENCE DATE
(REQ. FOR KEY DWGS, FOR SETPOINT CHANGES, AND FOR WD DCNs)

N/A

2E-31 REQUIRED? YES NO

12. RPE SIGNATURE DATE

N/A

6. CHANGE DESCRIPTION: INCORPORATION REQUIRED YES NO

REVISE PAGES 3, 5, 6 AND 7 & ADD FIGURE 7.
SEE ATTACHED FOR DETAILS.

BUDGETARY AUTH
(FOR WD DCNs ONLY)

N/A

MAINT MGR DATE

N/A

DED MGR DATE

WORK DOC. (WD) DCN? YES NO WORK DOC. NO. N/A

ENG. NOTIFICATION REQ. FOLLOWING INSTALLATION? YES NO ECNP/MOD PACKAGE REQ. PRIOR TO INSTALLATION? YES NO

13. NUCLEAR ASSURANCE DATE
(REQ. FOR G-RELATED P&IDs, ONE-LINES, SPECS, DES CRT, AND WD DCNs)

A. R. Montenegro 5-8-92

15. ADDITIONAL INFORMATION: YES NO YES NO

A. NPOD PROG./PROC. IMPACTED C. PLANT LABELING CHANGE
B. 10CFR50.59 EVALUATION ATTACHED D. WED. CHANGE REQ. NO. N/A

IF NO, PROVIDE PRELIMINARY SCREENING JUSTIFICATION:

14. H&AP SE OR A/E SE OR DED APPROVAL DATE

M. P. Kamin 5/7/92


14A. PLANT MANAGER (FOR WD DCNs ONLY)
(THIS APPROVAL AUTHORIZES INSTALLATION)

N/A

14B. WD DCN INSTALLATION
INSTALLATION IS IN PROGRESS OR COMPLETE

ENTERED BY N/A DATE _____

16. PLANT LABELING COORD. CONCUR. (IF APPLICABLE)



N/A / _____ DATE _____

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER REV PAGE
SL749TS1018 1 3

1.0 Scope

- 1.1 This specification provides alternate valve stem packing design approved for installation as a maintenance activity in place of the vendor designed packing, at the option of the Cognizant Engineer or Responsible Maintenance Authority (RMA).
- 1.2 This specification provides alternate design to include live loading on packing gland studs as a maintenance activity at the option of the Cognizant Engineer or RMA.
- 1.3 The following valve types and sizes are covered by this specification: gate, globe, angle, stop check, and angle stop check from 1" to 36" NPS; with manual, air, motor, or hydraulic operators. INSERT A
- 1.4 Packing on the Feed Water Isolation Valve hydraulic actuators is specifically included in the scope of this specification. Packing on other hydraulic cylinders is not included in the scope of this specification.
- 1.5 The following items are not included in the scope of this specification:
 - 1.5.1 Main turbine throttle & governor valves
 - 1.5.2 Main turbine reheat intercept & stop valves
 - 1.5.3 All code safety relief valves
 - 1.5.4 ~~All~~ rotary stem valves (except butterfly & ball)
 - 1.5.5 Solenoid valves
 - 1.5.6 FPT throttle & governor valves
 - 1.5.7 AFPT governor valve
 - 1.5.8 Packless Metal Diaphragm valves
 - 1.5.9 Bellows Sealed valves

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER REV PAGE
5L749T81018 1 5

4.2 The following packing designs are acceptable per this specification, for valves without lantern rings,

INSERT B

4.2.1 Two braided end rings and three die-formed graphite rings. (Figure 1)

4.2.2 Two braided end rings and seven EPRI wedge shaped die-formed graphite rings. (Figure 2)

4.2.3 Two braided end rings and two die-formed graphite rings. (Figure 3)

INSERT C

4.3 Excess space below the packing set shall be eliminated by insertion of a spacer, if required to provide adequate clearance of the gland, flange and stuffing box. Minimum clearance before compression is 1.5 times the height of one packing ring.

INSERT D

~~4.4 If the bottom of the stuffing box is beveled, the bottom of the spacer shall be beveled to match.~~

4.5 Two or more tapped & threaded holes may be added to the top of the spacer to insert packing tools for removal of spacer.

INSERT E

~~4.6 Valves with operable leak-off connections and lantern rings shall be repacked with two braided end rings and two die formed square graphite rings above the lantern rings, and two braided end rings and seven EPRI wedge die formed graphite rings below the lantern rings. A carbon spacer shall be installed below the bottom rings, if required to eliminate excess space. This configuration is shown in Figure 4.~~

INSERT F

~~4.7 Valves which have plugged leak-off connections and lantern rings shall be repacked with the lantern ring removed, per one of configurations in 4.2. Split carbon spacers shall be installed below the packing set. The total height of carbon spacers should set the packing set above the leak-off connection.~~

4.8 The required packing gland nut torque shall be provided by the packing supplier for the actual configuration. The torque shall be sufficient to apply a pressure of a nominal 1.75 times the system operating pressure or at least 2000 psi for initial installation of square packing sets. Initial torque for EPRI wedge packing sets shall be per the packing

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER REV PAGE
SL749TS1018 1 6

supplier's recommendation. The maximum pressure shall not exceed the capacity of the packing installed.

- 4.9 Square packing ring size shall be determined after physical measurement of the valve stem and stuffing box diameter. Dimensional tolerances on die formed packing rings are:

ID= STEM OD (+0.005 in., -0.000 in.)
OD= Stuffing Box ID (+0.000 in., -0.010 in.)

- 4.10 Packing height before compression shall be below or flush with the top of the stuffing box.
- 4.11 Live load spring packs, where required, shall be supplied by the vendor to provide for additional inservice consolidation. The configuration shall be designed by the vendor to provide a minimum inservice consolidation of 3% of the uncompressed packing height, unless the space available does not allow sufficient live load stack height. In this case, 2% inservice consolidation is acceptable.
- 4.12 The additional height required to accommodate the live loading spring packs may require replacement of the existing gland studs with longer studs. This is acceptable provided the material specified on the valve bill of materials is used for the replacement studs. This also applies to eyebolts, carriage bolts, and other types of gland bolts.

5.0 Materials

- 5.1 The following manufacturers and model numbers are acceptable:

INSERT G

- ~~5.1.1 Braided end rings
Chesterton Style 1~~
- ~~5.1.2 Die Formed Square Graphite Rings
Chesterton Style 5300~~
- ~~5.1.3 EPRI Wedge Die Formed Graphite Rings
Chesterton Style 5350~~
- ~~5.1.4 Spacers
Chesterton Style 5100 Split Carbon Sleeve~~

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER REV PAGE
5L749781018 1 7

INSERT 6
(CONT'D)

~~5.1.5 Live Loading Assemblies
Chesteron Style E150~~

- 5.2 Valves with existing stainless steel spacers may retain the S.S. spacer in lieu of adding a new split carbon spacer. This type spacer is frequently used on Valtek valves.
- 5.3 All live loading assemblies, spacers, and packing rings furnished for Safety Related valves shall be supplied in accordance with a Quality Assurance Program that meets the applicable portions of 10CFR50, Appendix B.
- 5.4 All packing and spacer materials supplied for Safety Related valves shall be lot certified to meet the requirements in Tables 1 and 2.

INSERT A: (add to section 1.3)

The following types and sizes of rotary stem valves are also included within the scope of this specification: butterfly and ball valves (including control valve variations such as "Vee Ball" and "U-Ball") from 2" to 96" NPS, with manual, air, motor, or hydraulic operators.

INSERT B: (add to section 4.2)

The specific configuration shall be selected by the Cognizant Engineer or RMA per the recommendations of the packing vendor:

INSERT C: (add)

4.2.4 Alternate packing configurations using flexible graphite / amorphous carbon composite end rings shall be in accordance with configurations A through F of the Figure 7 .

INSERT D: (revise section 4.4)

If the bottom of the stuffing box is angled, a braided or composite end ring should be installed below the bushing, per the packing vendor's recommendation. Alternates such as use of a metal junk ring are acceptable with Engineering approval.

INSERT E: (revise section 4.6)

Valves with operable leak-off connections and lantern rings shall be repacked with one of the illustrations shown in Figure 4 and Figure 7 (configurations G through M). The packing arrangement using composite end rings in Figure 7 is preferred.

INSERT F: (revise section 4.7)

Valves with plugged leak-off connections and lantern rings shall be repacked with the lantern rings removed or dropped to the bottom of the stuffing box, per one of configurations in 4.2. Split carbon spacer(s) or graphite bushing(s) shall be installed above and/or below the packing set. Under no circumstances should the packing materials be placed over the inactive leak-off port.

INSERT G: (revise section 5.1 per attached page)

INSERT H: (add attached Figure 7 to the specification)

INSERT 6:

5.1 The following manufacturers and model numbers are acceptable:

5.1.1 Braided End Rings

- A. Chesterton Style 1
- B. Argo Style 524

5.1.2 Die Formed Square Graphite Rings

- A. Chesterton Style 5300
- B. Argo Style 6300

5.1.3 EPRI Wedge Die Formed Graphite Rings

- A. Chesterton Style 5350

5.1.4 Split Carbon Bushings

- A. Chesterton Style 5100
- B. Argo Style 5005

5.1.5 Live Loading Assemblies

- A. Chesterton Style 5150
- B. Argo Style 6250

5.1.6 Composite End Rings


- A. Argo Style 6000

FIGURE 7


ALTERNATE VALVE PACKING CONFIGURATION
USING COMPOSITE END RINGS

DCN NO. MS-62
PAGE 8 OF 9


CONFIGURATION WITHOUT LANTERN RING




A



B



C



D




E



F

CONFIGURATION WITH LANTERN RING



G




H



I



J




K




L



M



N



TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER
SL749TS1018

REV PAGE
1 2

TABLE OF CONTENTS

<u>SECTION NUMBER</u>	<u>TITLE</u>	<u>PAGE NUMBER</u>
1.0	SCOPE	3
2.0	GENERAL INFORMATION	4
3.0	APPLICABLE DOCUMENTS	4
4.0	REQUIREMENTS	4
5.0	MATERIALS	6
 <u>TABLE NUMBER</u>		
1	EXTERNAL ENVIRONMENTAL CONDITIONS	8
2	CHEMICAL AND PHYSICAL PROPERTIES	9
 <u>FIGURE NUMBER</u>		
1	FIVE RING PACKING SET	10
2	EPRI WEDGE PACKING SET	11
3	FOUR RING PACKING SET	12
4	PACKING SET WITH LANTERN RING	13
5	CONVENTIONAL LOADING VS. LIVE LOADING	14
6	DISC SPRING ARRANGEMENTS	15
 <u>APPENDIX NUMBER</u>		
A	INDIVIDUAL VALVE SURVEY SHEET	16

1.0 Scope

- 1.1 This specification provides alternate valve stem packing design approved for installation as a maintenance activity in place of the vendor designed packing, at the option of the Cognizant Engineer or Responsible Maintenance Authority (RMA).
- 1.2 This specification provides alternate design to include live loading on packing gland studs as a maintenance activity at the option of the Cognizant Engineer or RMA.
- 1.3 The following valve types and sizes are covered by this specification: gate, globe, angle, stop check, and angle stop check from 1" to 36" NPS; with manual, air, motor, or hydraulic operators.
- 1.4 Packing on the Feed Water Isolation Valve hydraulic actuators is specifically included in the scope of this specification. Packing on other hydraulic cylinders is not included in the scope of this specification.
- 1.5 The following items are not included in the scope of this specification:
 - 1.5.1 Main turbine throttle & governor valves
 - 1.5.2 Main turbine reheat intercept & stop valves
 - 1.5.3 All code safety relief valves
 - 1.5.4 All rotary stem valves
 - 1.5.5 Solenoid valves
 - 1.5.6 FPT throttle & governor valves
 - 1.5.7 AFPT governor valve
 - 1.5.8 Packless Metal Diaphragm valves
 - 1.5.9 Bellows Sealed valves

- 1.6 The removal of lantern rings and leak off connections which are shown piped to a drain tank on a P&ID is not included in this specification. Changes to valve packing and addition of live loading to these valves is included in the scope of this specification.
- 1.7 The scope of this specification includes both Safety Related and non-safety related valves.

2.0 General Information

- 2.1 Recent research has proven the effectiveness and life of valve stem packing can be improved by using spacers to reduce the number of packing rings and use of grafoil packing materials to replace asbestos-graphite braid and other packing materials.
- 2.2 This research and industry experience has also proven that addition of live loading to the packing gland adjustment can virtually eliminate the need for periodic packing adjustment. See Figures 5 & 6 for general information on configuration of live load equipment.
- 2.3 Final dimensions of valve packing design & live load design as specified herein depends on accurate field measurements of valve dimensions not generally available in design documents. Therefore, this specification provides the process for determining final dimensions of packing and live loading equipment instead of specific packing dimensions, etc.

3.0 Applicable Documents

- 3.1 Electric Power Research Institute (EPRI) NP-5697, Valve Stem Packing Improvements.

4.0 Requirements

- 4.1 Data necessary for determination of packing details shall be recorded on a data sheet similar to Appendix A, when first repacked in accordance with this specification. The completed data sheet shall be retained by Maintenance as a record of the installed configuration, and for use in future repacking or packing adjustment.

- 4.2 The following packing designs are acceptable per this specification, for valves without lantern rings:
- 4.2.1 Two braided end rings and three die-formed graphite rings. (Figure 1)
 - 4.2.2 Two braided end rings and seven EPRI wedge shaped die-formed graphite rings. (Figure 2)
 - 4.2.3 Two braided end rings and two die-formed graphite rings. (Figure 3)
- 4.3 Excess space below the packing set shall be eliminated by insertion of a spacer, if required to provide adequate clearance of the gland, flange and stuffing box. Minimum clearance before compression is 1.5 times the height of one packing ring.
- 4.4 If the bottom of the stuffing box is beveled, the bottom of the spacer shall be beveled to match.
- 4.5 Two or more tapped & threaded holes may be added to the top of the spacer to insert packing tools for removal of spacer.
- 4.6 Valves with operable leak-off connections and lantern rings shall be repacked with two braided end rings and two die formed square graphite rings above the lantern rings, and two braided end rings and seven EPRI wedge die formed graphite rings below the lantern rings. A carbon spacer shall be installed below the bottom rings, if required to eliminate excess space. This configuration is shown in Figure 4.
- 4.7 Valves which have plugged leak-off connections and lantern rings shall be repacked with the lantern ring removed, per one of configurations in 4.2. Split carbon spacers shall be installed below the packing set. The total height of carbon spacers should set the packing set above the leak off connection.
- 4.8 The required packing gland nut torque shall be provided by the packing supplier for the actual configuration. The torque shall be sufficient to apply a pressure of a nominal 1.75 times the system operating pressure or at least 2000 psi for initial installation of square packing sets. Initial torque for EPRI wedge packing sets shall be per the packing

supplier's recommendation. The maximum pressure shall not exceed the capacity of the packing installed.

- 4.9 Square packing ring size shall be determined after physical measurement of the valve stem and stuffing box diameter. Dimensional tolerances on die formed packing rings are:

ID= STEM OD (+0.005 in., -0.000 in.)
OD= Stuffing Box ID (+0.000 in., -0.010 in.)

- 4.10 Packing height before compression shall be below or flush with the top of the stuffing box.
- 4.11 Live load spring packs, where required, shall be supplied by the vendor to provide for additional inservice consolidation. The configuration shall be designed by the vendor to provide a minimum inservice consolidation of 3% of the uncompressed packing height, unless the space available does not allow sufficient live load stack height. In this case, 2% inservice consolidation is acceptable.
- 4.12 The additional height required to accommodate the live loading spring packs may require replacement of the existing gland studs with longer studs. This is acceptable provided the material specified on the valve bill of materials is used for the replacement studs. This also applies to eyebolts, carriage bolts, and other types of gland bolts.

5.0 Materials


- 5.1 The following manufacturers and model numbers are acceptable:
- 5.1.1 Braided end rings
Chesterton Style 1
 - 5.1.2 Die Formed Square Graphite Rings
Chesterton Style 5300
 - 5.1.3 EPRI Wedge Die Formed Graphite Rings
Chesterton Style 5350
 - 5.1.4 Spacers
Chesterton Style 5100 Split Carbon Sleeve

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER
SL749TS1010


REV PAGE
1 7

- 5.1.5 Live Loading Assemblies
Chesterton Style 5150
- 5.2 Valves with existing stainless steel spacers may retain the S.S. spacer in lieu of adding a new split carbon spacer. This type spacer is frequently used on Valtek valves.
- 5.3 All live loading assemblies, spacers, and packing rings furnished for Safety Related valves shall be supplied in accordance with a Quality Assurance Program that meets the applicable portions of 10CFR50, Appendix B.
- 5.4 All packing and spacer materials supplied for Safety Related valves shall be lot certified to meet the requirements in Tables 1 and 2.




EPRI WEDGE PACKING SET

FIGURE 2




FOUR RING PACKING SET

FIGURE 3




PACKING SET WITH LANTERN RING

FIGURE 4




CONVENTIONAL LOADING VS. LIVE LOADING


FIGURE 5





6 IN SERIES



2 IN PARALLEL,
3 IN SERIES



NESTED



4 IN PARALLEL

DISC SPRING ARRANGEMENTS

FIGURE 6

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER _____ **REV** _____ **PAGE** _____
 SL749TS1018 1 16

DATE _____

INDIVIDUAL VALVE SURVEY SHEET

DISTRIBUTOR _____ COMPLETED BY _____
 SPECIALIST _____ REVIEWED BY _____
 UTILITY _____ PLANT _____ VALVE NO. _____ PAGE NO. _____

VALVE DATA

EN: _____ DWG. NO: _____
 MFG: _____ MODEL NO: _____
 SIZE: _____ TYPE: _____
 SYSTEM PRESSURE: _____ TEMP: _____
 LOCATION:
 SYSTEM: _____
 AREA: _____
 CONTAINMENT Inside outside
 SAFETY RELATED: yes no
 PROCEDURE NO _____
 ACTUATION: power manual
 FREQUENCY OF ACTUATION: _____

PACKING DATA

STYLE 3300/GTPE
 ID: _____ OD: _____ HT: _____
 QTY: _____ ITEM # _____
 STYLE ONE-CL
 ID: _____ OD: _____ HT: _____
 QTY: _____ ITEM # _____
 SEQUENCE: _____


BUSHING DATA

ID: _____ OD: _____ HT: _____
 QTY: _____ ITEM NO _____

STUFFING BOX DATA

STEM O.D.: _____ , BOX I.D.: _____
 BOX DEPTH: _____
 LANTERN RING: _____
 yes
 no
 HT _____
 PIPED
 PLUGGED

LANTERN RING



DATE PACKED: _____

 COMMENTS: _____

STUD DATA

SWING BOLT: **FIGURE 1 QTY:** _____
BOLT DIAMETER: _____
 ALL THREAD: **FIGURE 2 QTY:** _____
BOLT DIAMETER: _____




FIGURE 1





FIGURE 2

BELLEVILLE WASHER DATA



A STUD DIAMETER _____
B AVAILABLE LENGTH _____
C AXIAL CLEARANCE: _____
D RADIAL CLEARANCE: _____
E OVERALL STUD LENGTH _____
***ASSEMBLY FREE WT. _____ QTY/STUD _____**
ARRANGEMENT _____ TORQUE _____
***COMP. SPRING ASSEMBLY WT. _____**
ITEM NO. _____
 *Approximate Value Only

TITLE
ALTERNATE VALVE PACKING
AND LIVE LOAD DESIGN

NUMBER
5L749TS1018

REV PAGE
1 8

EXTERNAL ENVIRONMENTAL CONDITIONS

TEMPERATURE	UP TO 350 °F
RADIATION	UP TO 1.6×10^8 RADS, BETA + GAMMA
PRESSURE	UP TO 60 PSIG
CHEMICAL SPRAY	4.5 to 10.5 pH, 2000-4000 ppm of H_3BO_3 , NaOH, and/or Na_3PO_4

PROCESS CONDITIONS

TEMPERATURE	32 °F to 650 °F
RADIATION	1.8×10^8 RADS BETA, 1.0×10^8 RADS GAMMA
PRESSURE	FULL VACUUM to 3100 PSIG
PROCESS FLUIDS	WATER STEAM BORIC ACID (6%) HYDRAULIC FLUID (TRI-ESTER PHOSPHATE) DIESEL FREON LUBE OIL HYDROGEN CARBON DIOXIDE ANHYDROUS AMMONIA AIR SODIUM HYDROXIDE (40%) AMMONIUM HYDROXIDE SODIUM HYPOCHLORITE HYDRAZINE BRINE NITROGEN SULFURIC ACID (CONCENTRATED AND DILUTE)


TABLE 1

CHEMICAL AND PHYSICAL PROPERTIES

<u>PROPERTY</u>	<u>BRAIDED RINGS</u>	<u>DIE-FORMED RINGS</u>	<u>TEST METHOD</u>
CARBON % min.	97	97	ASTM-D-3178-84 PARA.4.2.3.2
ASH % min.	3	3	ASTM-C-561-85 PARA.4.2.3.2
MOISTURE % max.	3	3	ASTM-C-562-85 PARA.4.2.3.2
DENSITY g/cc	1.4 min.		ASTM-C-135-76 PARA.4.2.3.3
DENSITY g/cc		1.30-1.50	WATER IMMERSION
WATER LEACHABLE CHLORIDES ppm max.	100	50	ASTM-D-512-81 METHOD D OR ION CHROMATOGRAPHY
WATER LEACHABLE FLUORIDES ppm max.	100	50	ASTM-D-1179-80 METHOD B OR ION CHROMATOGRAPHY
TOTAL CHLORINE ppm max.	200	200	ASTM-D-808-81 OR ION CHROMATOGRAPHY
TOTAL FLUORINE ppm max.	200	200	ASTM-D-3761-84 OR ION CHROMATOGRAPHY
ACTIVE SULPHUR ppm max.	700	700	ASTM-D-129-78 OR ION CHROMATOGRAPHY
TOTAL HEAVY METALS ppm max.	200	200	ATOMIC ABSORPTION
INDIVIDUAL HEAVY METAL* ppm max.	150	150	ATOMIC ABSORPTION

* ANTIMONY, ARSENIC, BISMUTH, CADMIUM, COPPER, GALLIUM, INDIUM, LEAD, MERCURY, SILVER, TIN, & ZINC

TABLE 2



FIVE RING PACKING SET

FIGURE 1

TO: Ed Halpin, TSE Administrator
 FROM: Brian Ratté *BDR*
 SUBJECT: DRAIN VALVES INSTALLED BACKWARDS

6/7/93

The following SRs are written against the subject valves:

<u>VALVE</u>	<u>SR</u>	<u>VALVE</u>	<u>SR</u>
N1MDLV7925	308901	N2MDLV7925	308915
N1MDLV7926	308902	N2MDLV7926	308916
N1MDLV7927	308903	N2MDLV7927	308917
N1MDLV7928	308904	N2MDLV7928/	308918
N1MTFV7962	308905	N2MTFV7962	162593
N1MTFV7977	308906	N2MTFV7977	146934
N1MTFV7979	308907	N2MTFV7979	308919
N1MTFV7981	308908	N2MTFV7981	308920
N1MTFV7984	308909	N2MTFV7984	162594
N1MTFV7985/	179321	N2MTFV7985	146933
N1MTFV7986	308910	N2MTFV7986	308921
N1MTFV7987	179322		
N1MTFV7900	308911		
N1MTFV7901	308912		
N1MTFV7902	308913		
N1MTFV7903	308914		

Since several pre-existing SRs are written against Unit 2 valves, care should be exercised to ensure consistent results for all PCF dispositions. Attached are copies of the typical SR and PCF written for SR numbers 308901-308921. Note that I ask for the flow arrow to be removed from the valve (if it does not point in the direction of flow) to preclude future questions.

If there are any questions or comments concerning the above, please call me at X-7636.

SECTION 1: COMPONENT INFORMATION

TAG/TPNS	SERVICE DESCRIPTION	BLDG ROOM	ELEV
7C101NCP101A	CONTAINMENT POLAR CRANE	RCB C501	83

OTHER LOCATION INFORMATION: ROOF OF RCB

SECTION 2 : ACTIVITY DESCRIPTION

PM ACTIVITY: LUBE/INSPECT | NPRDS: N

FREQUENCY: P1 | RECOMMENDED MODE: 56

EQ RELATED: N | QUALITY RELATED: Y

EOL REPLACEMENT: N RDD: | ASME SEC. XI TRVL. REQUIRED: N

SECTION 3: WORK START APPROVAL

TECHNICAL SPECIFICATIONS SECTIONS(S):

TIME WHEN SYSTEM MUST BE RETURNED TO SERVICE <u>Prior to Mode 4</u> TIME DATE	AUTHORITY: Reactor Operations <u>[Signature]</u> SIGNATURE	<u>6-21/93</u> DATE
---	--	------------------------

SECTION 4: POST MAINTENANCE TESTING

TEST REQUIRED: NO TEST REQUIREMENTS INCLUDED IN:

OOS
OTL# 1-93-0065

PMT COMPLETED: [YES] [NO] [NA] TP# NA

SECTION 5: WORK COMPLETED CERTIFICATION/ACKNOWLEDGMENT

SR TAG REMOVED [YES] [NO] [NA]

CLEARANCES/PERMITS RELEASED [YES] [NO] [NA]

<u>[Signature]</u> WORK SUPERVISOR CERTIFICATION	<u>7-7-93</u> DATE	<u>[Signature]</u> WORK START AUTHORITY ACKNOWLEDGMENT	<u>7-11-93</u> DATE
--	-----------------------	--	------------------------

SECTION 6: PACKAGE REVIEW

<u>[Signature]</u> PM PLANNER REVIEW	<u>9-9-93</u> DATE	<u>[Signature]</u> PLANT ENG DEPT REVIEW	<u>9-7-93</u> DATE
---	-----------------------	---	-----------------------

SECTION 7 : SPARE PARTS / MATERIAL USED

HL&P PART NUMB	INVENTORY SEQ NUMB	QCE QCP	IN MPL	QTY UOM	HL&P PART NUMBER DESCRIPTION	MAF NUMBER	QTY USED
559-30099	N/A	7S 9	NO	1	OIL, PARAFFIN BASE TYPE, COM CN POUNDED WITH ANTIRUST, ANTIO XIDATION	N/A	
501-35456	N/A	7S 7	NO	1	LUBRICANT, GEAR, HEAVY BODIE CN D, DILUENT TYPE, BLACK -QTY 0 CN	N/A	
501-18810	N/A	7S 9	NO	1	OIL, HYDRAULIC, AW, ISO 68, CN 5 GAL CN/35 LB PAIL	N/A	
559-30011	N/A	7S 9	NO	1	SUPERCEDED BY CLASS-BIN 5014 TB 3241 01/26/93	N/A	
501-43241	RIR 930072	7S 4	NO	1	GREASE, MULTI-PURPOSE, EXTRE TB ME PRESSURE (EP), POLYUREA A ND	30275	
501-26180					WASHER LOCK W/S	30277	12 EA.
501-80689	N/A				GASKET STEEL	30277	2 FT.
501-16019	92022015				BOLT, HEX HD.	30277	12 EA.
501-80999	930527018				WASHER, FMT	30277	12 EA.
501-V1668					NUT 3/8 in -16	30277	12 EA.

SECTION 8: PERMITS/DOCUMENTATION

HOUSEKEEPING ZONE	IV	N/A	RADIATION WORK PERMIT	Y	93-1-21
CLEANLINESS CLASS	N/A	N/A	EQUIPMENT CLEARANCE	Y	1-93-1-1818 IF REQ. ON 8/1/93
CONFINED SPACE	N	N/A	ADDITIONAL SECURITY REQ	N	N/A
FIRE HAZARD EVAL	N	N/A	AFFECT CHARCOAL FILTER	N	N/A
HOT WORK PERMIT	N	N/A	SCAFFOLDING REQUIRED	N	N/A
INSULATION REQ.	N	N/A	ASME SECTION XI TRAV.	N	N/A
HAZARD SYS BREACH	N	N/A	CONTAMINATED SYS BREACH	N	N/A

SECTION 9: M&TE USED

DESCRIPTION	ID NO.	CAL -DUE-
0-1 IN. MICROMETER +/- .001 IN. ACCY.	N/A	N/A
1-2 IN. MICROMETER +/- .001 IN. ACCY.	N/A	N/A
6 IN DIAL CALIPER	100-02705-015	8-12-93

SECTION 10: PERSONNEL PERFORMING MAINTENANCE

NAME	CRAFT	CREW	SIGNATURE	HOURS	DATE
Sidney Story	m/m	Sun	Sidney Story	10	6-21-93
Mike Cole	m/m	Sun	Mike Cole	10	6-21-93
WAYNE HUSE	M/M	WHITING	Wayne Huse	10	6-21-93
Stan Doudle	m/m	HLP	Stan Doudle	10	6-21-93
Stan Doudle	m/m	HLP	Stan Doudle	10	6-22-93
Mike Cole	m/m	Sun	Mike Cole	10	6-22-93
Sidney Story	M/M	Sun	Sidney Story	10	6-22-93
WAYNE HUSE	M/M	WHITING	Wayne Huse	10	6-22-93
Stan Doudle	m/m	HLP	Stan Doudle	10	6-23-93
WAYNE HUSE	M/M	WHITING	Wayne Huse	10	6-23-93
Mike Cole	m/m	Sun	Mike Cole	10	6-23-93
Sidney Story	M/M	Sun	Sidney Story	10	6-23-93
Stan Doudle	m/m	HLP	Stan Doudle		6-24-93
Sidney Story	M/M	Sun	Sidney Story	10	6-24-93
Mike Cole	m/m	Sun	Mike Cole	10	6-24-93
WAYNE HUSE	MM	WHITING	Wayne Huse	10	6-24-93
WAYNE HUSE	MM	WHITING	Wayne Huse	10	6-24-93
Stan Doudle	m/m	HLP	Stan Doudle	10	6-25-93
Story Sidney	M/M	Sun	Sidney Story	10	6-25-93
Mike Cole	m/m	Sun	Mike Cole	10	6-25-93
Jeff Irwin	M/M	Whiting	Jeff Irwin	10	6-25-93
Stan Doudle	m/m	HLP	Stan Doudle	10	6-28-93
Jeff Irwin	m/m	Whiting	Jeff Irwin	10	6-28-93
Mike Cole	m/m	Sun	Mike Cole	10	6-28-93
Sidney Story	m/m	Sun	Sidney Story	10	6-28-93
WAYNE HUSE	MM	WHITING	Wayne Huse	10	6-28-93
WAYNE HUSE	MM	WHITING	Wayne Huse	10	6-29-93
Jeff Irwin	m/m	Whiting	Jeff Irwin	10	6-29-93
Mike Cole	m/m	Sun	Mike Cole	10	6-29-93

SECTION 11: PREVENTIVE MAINTENANCE WORK INSTRUCTION

PM.ACTIVITY: LUBE/INSPECT

TAG NUMBER | SERVICE DESCRIPTION | QAQC | EQ

7C101NCP101A CONTAINMENT POLAR CRANE 7S N

1.0 PREREQUISITES

1.01 GENERAL

1.01.01 OBTAIN THE LUBRICANTS LISTED IN STEP 1.03 OR THEIR EQUIVALENTS IN ACCORDANCE WITH OPGP03-ZM-0004 (LUBRICATION PROGRAM).

1.01.02 OBTAIN A WORKING COPY OF OPMP04-JC-0002 (POLAR CRANE INSPECTION).

1.02 SPECIAL TOOLS / EQUIPMENT

CAL REQ

1.02.01	SUITABLE DRAIN PAN	N
1.02.02	FUNNEL	N
1.02.03	GREASE GUN	N
1.02.04	APPROVED WIPES	N
1.02.05	CLEANING SOLVENT	N
1.02.06	0-1 IN. MICROMETER +/- .001 IN. ACCY.	Y
1.02.07	1-2 IN. MICROMETER +/- .001 IN. ACCY.	Y

1.03 REQUIRED SPARE PARTS

	CLASS-BIN	DESCRIPTION	QTY	UOM
1.03.01	559-30099	OIL, PARAFFIN BASE TYPE, COMPOUNDED WITH	0	CN
1.03.02	501-35456	OIL, GEAR, HEAVY GODIED, 5 GAL PAIL	0	CN
1.03.03	501-18810	OIL, HYDRAULIC, AW GRADE 68, 5 GAL CN/35	0	CN
1.03.04	559-30011	SUPERCEDED BY CLASS-BIN 50143241 01/26/93	0	TB
1.03.05	501-43241	GREASE, MULTI-PURPOSE, EXTREME PRESSURE (0	TB

1.04 PERMITS AND INDICATORS

1.04.01 MAINTAIN HOUSEKEEPING ZONE IV.

1.04.02 A RADIATION WORK PERMIT IS REQUIRED FOR PERFORMANCE OF THIS ACTIVITY.

1.04.03 AN EQUIPMENT CLEARANCE IS REQUIRED FOR PERFORMANCE OF THIS ACTIVITY.

2.0 PRECAUTIONS

2.01 FOLLOW PRECAUTIONS LISTED IN OPMP4-JC-0002 (POLAR CRANE INSPECTION).

3.0 WORK INSTRUCTIONS

3.01 LUBRICATE AND INSPECT POLAR CRANE IN ACCORDANCE WITH OPMP04-JC-0002 (POLAR CRANE INSPECTION).

3.02 CLEAN THE "MAIN" AND "AUXILLARY" HOOKS, (FOR INSPECTION).

SECTION 11: PREVENTIVE MAINTENANCE WORK INSTRUCTION

PM.ACTIVITY: LUBE/INSPECT

4.0 REFERENCES

4.01 IMPLEMENTING REFERENCES

4.01.01 OPMP04-JC-0002 POLAR CRANE INSPECTION

4.02 SOURCE DOCUMENTS

4.02.01 4013-01001-WG WHITING CORP. MANUAL

4.02.02 ESR NO. 87-J2-003

5.0 DOCUMENTATION - NONE

SECTION 12: AS FOUND CONDITION

NOTE: ONE QUOTE FOR COPY MADE. RN 6-21-93

Phase 5, Pbx packed in North-South position.

N/A

SECTION 13: AS LEFT CONDITIONS

ECO Released Released. Ready for Service.

Note: Duplicate copy was destroyed. 7-2-93

N/A

SECTION 14: SUMMARY OF WORK PERFORMED

STAN DOWDE is work Group Supervisor. JARYL BOWEN, Day 6-21-93
Received job from MORTON & Reviewed. Obtained tools needed to perform. PM Obtain
worksheet. Coordinated with HPS on scope of work. Performed steps 5.1 & 5.3 & 5.1 of
OPREP-JC-0002. Performed step 5.4 thru 5.4.4 for "A" GROUND Left, "A" GROUND Right, & "B" GROUND
Also step 5.4.6 thru 5.4.10 for "A-L", "A-R", & "B-RT". IAW Section 5.4.3 "A-L" had slight burr
on pinion and 1st intermediate gear. Per vendor its nothing to be concerned with.
IAW ^{Section} 5.4.4 oil was SAT for "A-R", "A-L", & "B-RT". GEARCASES, COVER GASKETS WERE ALL SAT.
GASKET BEADERS WERE SAT. Step 5.4.11 was SAT. Step 5.4.13 was SAT. 5.4.14 & 5.4.15
was SAT. Replaced couplings GASKETS on Body Drives and mixer Drive couplings. 55%

SECTION 15: COG SYSTEM ENGINEER CONTACTED: YES [NO] [NA]

PARTS NEEDED FOR ROOT CAUSE: [YES] [NO] NA
PARTS TO BE REBUILT: [YES] [NO] NA
PARTS DISCARDED: [YES] [NO] NA

SR NO: N/A
MAP NO: N/A

AREA CLEAN: YES [NO] [NA] | INSULATION REMOVED: [YES] [NO] NA
TOOLS REMOVED: YES [NO] [NA] | INSULATION REINSTALLED: [YES] [NO] NA
HARDWARE RESTORED: YES [NO] [NA] | SCAFFOLDING REMOVED: YES [NO] [NA]

WORK COMPLETED: Raymond J. [Signature] 7-2-93 1500 HRS
CRAFTSMAN DATE TIME

ADDITIONAL SHEETS ATTACHED & NUMBERED NO YES # SHEETS: 12

Found on "A" that motor coupling had been rubbing coupling guard for some time. Holes need to be drilled for guard to be corrected. Zero speed switch coupling also rubbing cover. Also needs to be removed. Also missing one bolt on cover. On "A" Bl. micro Drive clutch rubbing cover. Additional holes need to be drilled for cover to fit right.

On "B" R coupling half at blades wheel has part of O-ring extruding & come out. Needs to be evaluated. Stan Durdle 6-21-93

Performed steps 5.4.1 thru 5.4.4 & 5.4.6 thru 5.4.15. Section 5.4.5 was not done. ^{oil was sat.} Section 5.4.6 was not done per vendor. Brake's didn't need adjustment. Micro-Drive Drive Coupling will also need to be modified because cover was rubbing. According to M. Pruitt (planning) work to correct coupling guards can be worked under SR# TC-152316 with instructions from vendor. Lowered covers to floor and assured each was latched. Waiting for HP support to clear out covers to be corrected.

Vendor said Hirst drum groove as requested in step 5.4.28. No straight edge or calipers were available. Vendor checked drum groove ^{visual and 2.0001} and found SAT by checking depth of cable on drum. Performed

steps 5.5.1 thru 5.5.3 & 5.5.6 thru 5.5.8. Step 5.5.9 could not be performed because this was a sealed bearing. Performed 5.5.11 & 5.5.12. Was advised by HKS that covers were clean & could be brought to maint. stop for modification/correction. Check Alice Run out of time. Stan Durdle for R. 6-27-93

Note: Main Hirst & Aux Hirst Guard For inspection covers were replaced.

PA 5.4.6 & 5.5.2, & 5.5.9 std

Performed steps 5.5.4 & 5.5.5. Obtained guards from R. Taylor who corrected all associated guards which were mentioned & installed each in their proper place. Released ECD. and

lowered hook. CK'd out hoist, bearings, ect. Heard squeaking noise possibly from micro-drive clutch support bearing will investigate.

~~6:23:33~~ ^{6:23:33} RAISED hook. Ran out of time. Stan Duda
6:23:33 Stan Duda

Was contacted by MSSD THAT SATEM was installed to lubricate Bredas wheels. Lubricated each as per vendor's instruction JAN steps 5.4.18 Inspected wheels as per steps 5.4.19 ~~thru~~ ^{thru} 5.4.19.2 AND WAS SAT per vendor. Step 5.4.19.1 cannot be performed due to lack of proper cross tools. Step 5.4.20 was N/A because they wouldn't accept grease. Steps 5.4.21 thru 5.4.23 was SAT. 5.4.24 needs to be locked at by Ray Asbury. Some signs appear to be missing Performed 5.6.19 & found SAT. 5.6.20 could not be done because block has to be disconnected & PC. RAN out of time. Raised Both Hooks Cleared Area. Stan Duda 6:24:33
S.D.D.

Performed steps 5.4.25 ^{SAT} thru ^{SAT} approx 30 FASTENERS were appearing to be loosened. See Attached drawing FOR NUMBER OF FASTENERS. As per 5.4.26 VACUUMED APPROX. 2/3 OF TRACK. WILL FINISH MONDAY
Step 5.4.27 was SAT. AS PER VENDOR. Step 5.4.29 was SAT.
Steps 5.6.1 thru 5.6.3 was performed 5.6.4 was N/A because Rope was SAT. 5.6.5 thru 5.6.9 was SAT. 5.6.10 was N/A per R. Asbury. 5.6.11, 5.6.12, 5.6.13, ~~thru~~ ^{SAT} 5.6.14 was performed & 5.6.15 was SAT. 5.6.16 & 5.6.17 was SAT per visual per R. Asbury. 5.6.18 was not required. 5.6.20 was performed & found SAT. NDE Report 13 attached. 5.6.21 was N/A. NOT REQUIRED 5.6.22 was N/A ^{FOR Aux Hook, etc} NO Lube points 5.6.23 was SAT. 5.6.24 was SAT FOR Aux Hook. Main Hook upper Sheaves was inaccessible. 5.6.26 was N/A per Ray Asbury. 5.6.27 was N/A. 5.6.28 Guna Limits Only. 5.6.29 was SAT. Step 5.6.22 was

performed Fed main Hook. Lubricated open drive gears. Checked area. Stan Dault 6.25.93

Finished vacuuming last 1/2 of track. Removed vacuum from Polar Crane. Checked polar crane rail belts. Attached is a copy of the list of rail belts to be suspected of being loose. While checking Rail Belts while in knowl Jett I noticed the bridge drive couplings were jumping/fixing when the polar crane was started up. The gearbox fasteners on some were suspected to be loose also. This unusual incidence has been addressed on SR# 157971 that was initiated after the discovery. An SR was also wrote on the Rail Belts to Inspect/Repair/Replace Belts This # is 157969. Wiped down tracky tracks & also did shims in supports to see if there were problems there were none. Results are attached in etc on Attachment 3. Removed host from Polar Crane. Stan Dault 6.28.93

Went on Polar with R. Asbury to perform insp. of gearbox problem. Ray wants m/m to write PCT on gearbox problem. Wayne got with ELECTRICAL and picked ^{up} PKG. for Review.

RECEIVED PKG FROM STAN DOWDIE. NOTIFIED ELECTRICAL MAINT OF NEED TO PERFORM STEPS 5.7.1 THRU 5.7.17 AND 5.8.1 THRU 5.8.2 AS REQUIRED IN PREREQUISITES SECTION STEP 3.6 IN OPMP04-JC-0002. WORKED JOINTLY WITH JERRY DIEGLE EM TO ^{wait} PERFORM OPERATIONAL TESTING REQUIRED IN OPMP04-JC-0002 AS WELL AS EM-1-JC-86013487. DUE TO QUESTIONS ARISING FROM ELECT. PM'S THIS TASK WILL HAVE TO BE COMPLETED TOMORROW.

WAYNE HUSE 7-1-93

COMPLETED SECTIONS 57 AND 5.8 OF 8PMP04-JC-0002 IN ^{with 7293} ~~CONSTRUCTION~~
CONJUNCTION WITH ELECT DEPT AND EM-1-JC-86013487. ALL SAT. WAYNE HUBB
RAY ASBURY WILL WITNESS OPERATIONAL TEST FROM 60' ELE. WA 7293 ^{Wayne Hubb 7293}

ELECTRICAL DEPT. REPLACED 2 TOWER RELAYS ON THE POLAR CRANE
ON 7.7.93. CRANE WAS PUT THROUGH RUN TEST AND WAS SAT.
7.7.93 *St. Duke J. Duke*

PERMIT/DOCUMENT RECORD

REFERENCE GROUP-29-0008
OPPOJ-24-0028

PERSONNEL PERFORMING MAINTENANCE

NAME (PRINT)	SIGNATURE	HRS WKO	DATE
Sidney Story	<i>[Signature]</i>	10	6-29-93
Stan Dondle	<i>[Signature]</i>	10	6-29-93
WAYNE HUSE	<i>[Signature]</i>	3	7-1-93
JEFF IRWIN	<i>[Signature]</i>	3	7-1-93
MIKE COLE	<i>[Signature]</i>	3	7-1-93
SIDNEY STORY	<i>[Signature]</i>	3	7-1-93
Sidney Story	<i>[Signature]</i>	2	7-2-93
MIKE COLE	<i>[Signature]</i>	2	7-2-93
WAYNE HUSE	<i>[Signature]</i>	2	7-2-93
JEFF IRWIN	<i>[Signature]</i>	2	7-2-93
Stan Dondle	<i>[Signature]</i>	1	7-6-93
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE
NAME (PRINT)	SIGNATURE	HRS WKO	DATE

COMPLETED RECORDS FOR QUALITY RELATED ITEMS WILL BE RETAINED FOR FIVE YEARS
 COMPLETED RECORDS FOR NON-QUALITY RELATED ITEMS WILL BE RETAINED FOR ONE YEAR

DATA SHEET
OPMP04-JC-0002-1
(Page 1 of 2)

5.1 BR/EM No. 001-1-JC-86013835

5.2 Unit No. 1

3.1

WORK SUPERVISOR SHALL MARK SECTIONS TO BE PERFORMED OR ENTER N/A			
<input checked="" type="checkbox"/>	5.4	Bridge Lubrication and Inspection	<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/>	5.5	Trolley Lubrication and Inspection	<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/>	5.6	Moist Lubrication and Inspection	
			5.7 Operational Inspection
			5.8 Operation of Bridge

3.2

MEASURING AND TEST EQUIPMENT		
DESCRIPTION	STPEGS I.D. NUMBER	CALIBRATION DUE DATE
DIAL CALIPER N/A	100-02705-015 N/A	8-12-93 N/A

5.4.4 Checked oil in gearcase: SAT. UNSAT.

5.4.5 Changed oil in ^{chd. 18EAS} gearcase: Roller yr. changeout Oil was UNSAT N/A

5.4.28 Hoist drum groove wear percentage - SAT ⁶⁻²⁵⁻⁹³ Method: Visual

5.6.1 Notified cranes and hoists system engineer or designee. [Signature] 1 6-25-93
Mech. Sign Date

5.6.2 Measurements of main hoist wire rope O.D.
1.270 in. 1.272 in. 1.272 in.

5.6.3 Measurements of auxiliary hoist wire rope O.D.
.500 in. .502 in. .502 in.

ENP 5.6.11 Lubrication inspection of wire ropes: SAT UNSAT
[Signature] 6-25-93
System Engineer or Designee Sign Date

ENP 5.6.12 Cranes and hoists system engineer or designee determined wire ropes are to be replaced. YES NO
[Signature] 6-25-93
System Engineer or Designee Sign Date

This FORM, when completed, shall be retained for the life of the plant.

AG of 12

DATA SHEET
OPMP04-JC-0002-1
(Page 2 of 2)

5.1 BR/PH No. 100-1-JC-86013835

5.2 Unit No. 1

5.6.13 Throat gage measurement on auxiliary hook. 6 1/2 in.

5.6.14 Throat gage measurement on main hook. 23 1/2 in. 23 1/2 in.

5.6.16 Measured twist of auxiliary hook. N/A deg.

5.6.17 Measured twist of main hook. N/A deg.

} VISUAL OK
PER R. ASBURY
deb 6-25-93
1513 HRS

ENP 5.6.26 Cranes and hoists system engineer or designee determined auxiliary and main hoist requires lubrication.

YES NO

[Signature]
System Engineer or Designee Sign

6-25-93
DATE

5.9 Crane operates satisfactory: ✓ Yes No

Comments:

 N/A

PERFORMED BY: [Signature] 7-7-93
MECHANIC DATE

REVIEWED BY: [Signature] 7-7-93
WORK SUPERVISOR DATE

MAGNETIC PARTICLE EXAMINATION REPORT

WORK DOC NO PM: MM (30) 13018885	COMPONENT DESCRIPTION 15 TON Aux. Hook 500 TON PALM CRANE HOOK	TPNS/COMPONENT ID NO 7C101NCP101A	DATE OF INSPECTION 6-24/6-25/93
		REPORT NO NDE 93-1235	

LOCATION ROOM NO 201 OTHER INFORMATION	UNIT NO 1 ELEVATION 68' N/A	BLDG NO R03	ADDITIONAL INFORMATION N/A
--	-----------------------------------	-------------	-------------------------------

DWC NO <input checked="" type="checkbox"/> N/A	MATERIAL C/S
--	-----------------

IS EXAMINATION AREA PAINTED <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	MT PROCEDURE NO NDEP 7.0 ²
PAINT THICKNESS <input checked="" type="checkbox"/> N/A	ACCEPTANCE STD <input type="checkbox"/> A <input checked="" type="checkbox"/> B
DRY FILM GAGE ID N/A	DUE DATE
APPENDIX NO 6 <input type="checkbox"/> OTHER	

CURRENT TYPE <input checked="" type="checkbox"/> AC <input type="checkbox"/> HWDC	MAGNETIZING METHOD <input checked="" type="checkbox"/> CONTINUOUS <input type="checkbox"/> RESIDUAL	EQUIPMENT USED MFG MAGNAFLUX MOD Y-6 SER NO 02 CAL BLOCK ID MT-005	EXAMINATION MEDIUM <input type="checkbox"/> BLACK POWDER NO 3A <input type="checkbox"/> RED POWDER NO 8A <input checked="" type="checkbox"/> GRAY POWDER NO 1 <input type="checkbox"/> MAGNAQLO NO 14AM (WET)
---	---	---	---

<input type="checkbox"/> SOIL AMP TURNS <input checked="" type="checkbox"/> NA	<input type="checkbox"/> PRODS AMPERAGE <input checked="" type="checkbox"/> NA	<input checked="" type="checkbox"/> YOKE LIFT VERIFICATION <input checked="" type="checkbox"/> BEFORE AND AFTER INSPECTION <input checked="" type="checkbox"/> 20 LBS <input type="checkbox"/> 40 LBS	LIGHT LEVEL VERIFICATION (SAF) <input checked="" type="checkbox"/> ILLUMINATION <input type="checkbox"/> ULTRAVIOLET SURF TEMP <input type="checkbox"/> < 135 F (WET) <input checked="" type="checkbox"/> < 600 F (DRY)
--	--	--	--

WELD NO., PART NO., OF SERIAL NO	ACC	REJ	REMARKS	SKETCH OR DRAWING
15 TON CRANE HOOK	✓			N/A
500 TON CRANE HOOK	✓			

COMMENTS

100% OF ACCESSABLE SURFACES MT'D ON BOTH HOOKS

INSPECTOR Ronald S Busby II	CERT LEVEL NDE-32	DATE 6-25-93	SUPV/LEVEL III REVIEW M. H. [Signature]	DATE 6/25/93
--------------------------------	----------------------	-----------------	--	-----------------

AS of 12

^{MM-1-25-93}
^{AND 5.4.5}
STEP 5.4.1A VISUAL INSPECTION OF OIL PROVED OK PER WHITING VENDOR WITH CONCURRENCE OF RAY ASBURY

STEP 5.5.3 REFERENCES BACK TO STEP 5.4.8, AUX HOIST GEARBOX INPUT OIL SEALS LEAKING SF# JZ-102557 ADDRESSES THIS ISSUE AND A FIX IS BEING INVESTIGATED.

STEP 5.4.2B VISUAL INSPECTION OF DRUM PROVED OK PER WHITING VENDOR WITH CONCURRENCE OF RAY ASBURY

STEP 5.4.2D BRIDGE AND TOWER END TRUCK CONNECTING PINS WOULD NOT ACCEPT LUBE, THESE PINS ARE HEAVILY LUBED AT INSTALLATION AND SHOULD NOT NEED LUBE FOR THE LIFE OF CRANE THIS STEP NOT NEEDED IN PROCEDURE PER WHITING VENDOR REP.

STEP 5.6.16 & 5.6.17 HOOK TWIST WAS CHECKED VISUALLY AND SAT PER WHITING VENDOR REP. WITH CONCURRENCE OF RAY ASBURY.

STEP 5.6.22 NO LUBE POINTS ON AUX HOIST BLOCK SHAFTS

WAYNE HUSE WHITING VENDOR REP *Wayne Huse* 6-25-93


~~N/A~~

COMMENT SHEET

24

PREPARED BY	
DATE	

MM-1-JC-9601993




THIS IS A REFERENCE SKETCH FOR BRIDGE DE LOCATIONS

NOT TO SCALE

SKETCH 1

Attachment 1
A10 of 12

MM-1-JC-96018835



A AND B BOLTS ARE IN THE ROUND HOLES

C AND D BOLTS ARE IN THE SLOTTED HOLES

LOOSE SHIMS NOTED ON INSIDE OF RADIUS LEFT OR RIGHT FACING THE WALL.

(NONE FOUND TO BE LOOSE)

Attachment

2

All of 12

Jeff Irwin
Whiting Services

MM-1-JC-9601716

Azimuth	Unit # 1 Polar Crane				Girder Left Shim	Bolting Right Shim
	A	B	C	D		
1	Old	New	Old	Old	OK	OK
2	Old	? Old	New	New	OK	OK
3	Old	? Old	New	New	OK	OK
4	New	New	New	New	OK	OK
5	Old	Old	Old	Old	OK	OK
6	Old	Old	New	? New	OK	OK
7	New	? New	Old	? Old	OK	OK
8	Old	Old	? New	Old	OK	OK
9	Old	? Old	Old	Old	OK	OK
10	? Old	? Old	? Old	Old	OK	OK
11	Old	? Old	Old	Old	OK	OK
12	Old	? Old	Old	Old	OK	OK
13	Old	Old	? New	Old	OK	OK
14	New	New	? Old	? Old	OK	OK
15	Old	Old	Old	Old	OK	OK
16	Old	Old	? Old	Old	OK	OK
17	New	? New	Old	? Old	OK	OK
18	Old	Old	Old	Old	OK	OK
19	Old	Old	Old	Old	OK	OK
20	Old	Old	Old	Old	OK <small>None</small>	OK <small>None</small>
21	Old	? Old	Old	Old	OK	OK
22	Old	Old	Old	Old	OK	OK
23	New	? Old	Old	Old	OK	OK
24	Old	Old	Old	Old	OK	OK

- A - Round Hole
- B - Round Hole
- C - Slotted Hole
- D - Slotted Hole

All locations determined by facing wall.

Attachment
3
8/2 of 12

7.22

WIN: 93022692 PERMIT: 001

UNIT: 1 BLDG: ROB ROOM: C501 ELEVATION: 141 SYS/TRAIN: JC
TAG/IDG: T001NCP1011 DRAWING NUMBER: NA LINE NUMBER: NA

*** DETAILED DESCRIPTION OF SCAFFOLD REQUIREMENTS ***

ELEVATION OF WORK PLATFORM: 135' LOCATION DRAWING NUMBER: Q5007

UNIT 1

ACCESS REQUIREMENTS/SPECIAL CONSIDERATIONS:
CONSTRUCT SCAFFOLD TO ALLOW INSPECTION AND LUBRICATION OF TRUCK BEARINGS ON THE POLAR CRANE. SCAFFOLD TO BE CONSTRUCTED BETWEEN GIRDERS FROM 350 A2 TO 5 A2 IN THE ROB. CONTACT JOHN HENFOLCHSEN AT 7711 FOR FURTHER INFO.

REQUEST INITIATOR: _____
BY PLANNER: 16346 / 06/21/93
PRINT DATE

*** SCAFFOLD PLANNING ***

IS A CONFINED SPACE ENTRY REQ'D: [X] NO [] YES	IS AREA SEISMIC II/I: [] NO [X] YES	REQ NO: <u>555 Clean 21 CONTN</u>
IS SCAFFOLD STANDARD: [X] NO [] YES	IS AN ECO REQ'D: [] NO [X] YES	ECO ID: <u>1-93-1930</u>
IS AREA CRITICAL: [X] NO [] YES	CONCRETE EXPANSION JOINTS REQ'D: [X] NO [] YES	<u>1944</u>
DES APPROVAL: <u>Ten Holson</u> <u>16/21/93</u> RESPONSIBLE ENGINEER DATE	PERMIT REVIEW: <u>Keith Branch</u> <u>16/21/93</u> PLANNER DATE	

*** INSTALLATION RELEASE ***

NOTE: IF SCAFFOLD IS TO BE INSTALLED IN A SEISMIC OR CRITICAL AREA, SHIFT SUPERVISORS SIGNATURE IS REQUIRED

PERMIT START: J. Henfolsen 16/27/93
DATE
PROPERLY BUILT AND TAGGED: Keith Branch 16-24-93
WORK SUPERVISOR DATE

PERSONNEL PERFORMING SCAFFOLD INSTALLATION:

<u>J. Henfolsen</u> <u>1</u> NAME HOURS	<u>NA</u> <u>1</u> NAME HOURS	<u>NA</u> <u>1</u> NAME HOURS
<u>John Smith</u> <u>13</u> NAME HOURS	<u>Keith Branch</u> <u>13</u> NAME HOURS	<u>Keith Branch</u> <u>13</u> NAME HOURS

COMMENTS: NA

*** REMOVAL RELEASE ***

MAINTENANCE WORK IS COMPLETE. POST MAINTENANCE TESTING IS COMPLETE AND SCAFFOLD IS RELEASED FOR REMOVAL. REMOVE AS PER REQUEST OF JOHN HENFOLCHSEN

PERSONNEL PERFORMING SCAFFOLD REMOVAL:

<u>M. Johnson</u> <u>12 1/2</u> NAME HOURS	<u>C. Branch</u> <u>12 1/2</u> NAME HOURS	<u>H. Mahan</u> <u>2 1/2</u> NAME HOURS
<u>T. W. Bruce</u> <u>12 1/2</u> NAME HOURS	<u>R. SEGURIN</u> <u>12 1/2</u> NAME HOURS	<u>J. L. Smith</u> <u>12 1/2</u> NAME HOURS

VERIFICATION THAT SCAFFOLD IS REMOVED, TOOLS/MATERIALS ARE REMOVED, AREA IS CLEAN AND ALL CLEARANCES ARE RELEASED:
M. Johnson 16-25-93
WORK SUPERVISOR DATE

*** PERMIT CLOSURE ***

Robert W. Kraft 16/28/93
PLANNER DATE
TOTAL MEN: 16 TOTAL HOURS: 94

REMAIN WITH THE ORIGINAL REFERENCED DOCUMENT

Fire Watch Program

OPGP03-ZF-0013
Rev. 4
Page 8 of 11

ADDENDUM 1
FIRE WATCH LOG
(TYPICAL)
(Page 1 of 2)

CHSA 93-41

- Impairment, Breach, or other Initiating Condition 0 - -
Stg of wood in RCB-1 + MAB
Unit: 1 Bldg.: RCB Elev.: 68' From Room: N/A To Room: N/A
- Is the watch due to OPGP03-ZF-0018 requirements? Yes No
- Continuous Hourly
- Fire Watch Assigned By: JF Boothroyd 06/22/93 17:46
Date Time
- Special Instructions for Fire Watch Personnel: Start continuous fire watch when wood is taken into the plant. Stop fire watch when wood is removed from the plant. Have an extra fire extinguisher with the fire watch
(ALSO SEE "BASIC INSTRUCTIONS FOR FIRE WATCHES")
IN CASE OF EMERGENCY CALL: Extension 2111 Extension 2222
- Fire Watch Personnel: SIGN OR INITIAL times in AND out for continuous fire watches OR SIGN OR INITIAL at least hourly for hourly fire watches skipping no lines on this log.

Fire Watch	Date	Time	Comments	Fire Watch	Date	Time	Comments
M.D.	6-23-93	1430	IN	F2	6/24/93	0559	IN
S.M.	6-23-93	1533	OUT	F2	6/24/93	0525	OUT
M.Y.	6-23-93	1532	IN	CANC	6/24/93	0524	IN
M.V.	6-23-93	1228	OUT	CANC	6/24/93	0646	OUT
M.A.	6-23-93	1727	IN	F2	6-24-93	0646	IN
M.D.	6-23-93	1287	OUT	F2	6-24-93	0707	OUT
M.Y.	6-23-93	1926	IN	CANC	6/24/93	0726	IN
M.A.S.Y.	6-23-93	2150	OUT	CANC	6/24/93	0810	OUT
M.D.	6-23-93	2129	IN	F2	6/24/93	0811	IN
M.D.	6-23-93	2253	OUT	F2	6/24/93	0833	OUT
CANC	6/23/93	10:52	22:52 IN	CANC	6/24/93	0802	IN
CANC	6/24/93	1:01	OUT	F2	6/24/93	0853	OUT
F2	6/24/93	1:00 PM	IN	CANC	6/27/93	10:01	TR-OUT CANC
F2	6/24/93	02:35	OUT	F2	6/24/93	10:02	OUT IN CANC
CANC	6/24/93	03:34	IN	F2	6/24/93	11:04	OUT IN CANC
CANC	6/24/93	04:00	OUT	CANC	6/27/93	11:03	OUT IN CANC

- Permission to discontinue the fire watch SHALL be documented by the Fire Protection Coordinator (or designee) or Shift Supervisor (as applicable) on the Fire Protection Impairment Form or Permit to Breach Fire Barrier. The Fire Protection Coordinat (or designee) OR Shift Supervisor SHALL sign the last page of this log.

ADDENDUM 2
EXAMPLE INSTRUCTION PAGE
(Page 1 of 1)

BASIC INSTRUCTIONS FOR FIRE WATCHES

1. Read the entries in sections 1, 3, and 5 to help you understand the reason for this fire watch.
2. Pay particular attention to whether this is a continuous fire watch or an hourly fire watch, section 3 on the log.
3. If you are performing a continuous fire watch:
 - a. Initial or sign in section 6 when you enter the area for your watch. Enter the date and time you begin your watch. Remain in the area until you are relieved.
 - b. Initial or sign in section 6 when you end your watch. Enter the date and time you end your watch. Ensure that the person relieving you signs in per part a. above, or that the fire watch is being discontinued by the Fire Protection Coordinator or Shift Supervisor, prior to leaving the area.
4. If you are performing an hourly roving fire watch, pass through the area(s) covered by the fire watch and initial or sign the log at least once in every 60 minutes. Indicate the date and time in the space provided.
 - a. Contact the Shift Supervisor or the Fire Protection Coordinator immediately if a watch or an hourly round is missed or is more than 15 minutes late for any reason to ensure that the problem is documented and corrective action is taken if necessary.
 - b. Indicate on the log the reason why you were late, or use the Missed Fire watch Report.
 - c. Hourly Fire watch shall switch rounds hourly to prevent boredom, when ever possible. (NRC Enforcement Action 88-216).

ADDENDUM 3
MISSED FIRE WATCH REPORT
(TYPICAL)
(Page 1 of 1)

MISSED FIRE WATCH REPORT

INFORMATION	FIRE WATCH STATION: ___-___-___
DATE ___/___/___	TIME ___:___ MINUTES LATE ___
OTHER DETAILS	
	NAME _____ BADGE # _____ DATE ___/___/___
	SUPERVISOR _____ DATE ___/___/___
	NAME OF FPC OR BS CONTACTED _____ DATE ___/___/___
FIRE PROTECTION TRACKING	REASON CODE _____
REMARKS	
FPC _____	DATE ___/___/___

NOTE: Use this form when the fire watch round is missed (late by more than 15 minutes). Indicate "see attached" on all log sheets when using this form and attach this form to each log. Please be brief.

PERSONNEL PERFORMING WORK
(CONTINUATION SHEET)

BR # PA-MJ-1-VC 860128256
WAN #

PRO. JOB 6-23-93

STEPHEN E. TATE
NAME (PRINT)

03 /
CRAFT

Stephen E Tate
SIGNATURE

11 1/2
HRS WKD

6-23-93
DATE

R. Flores
NAME (PRINT)

03 /
CRAFT

R. Flores
SIGNATURE

11 1/2
HRS WKD

6-23-93
DATE

D. Peppas
NAME (PRINT)

03 /
CRAFT

D. Peppas
SIGNATURE

11 1/2
HRS WKD

6-23-93
DATE

M.T. ELLIOTT
NAME (PRINT)

03 /
CRAFT

M.T. Elliott
SIGNATURE

11 1/2
HRS WKD

6-23-93
DATE

Don Williams
NAME (PRINT)

04 /
CRAFT

Don Williams
SIGNATURE

11 1/2
HRS WKD

6-23-93
DATE

D.W. SPEAKER
NAME (PRINT)

03 /
CRAFT

D.W. SPEAKER
SIGNATURE

11 1/2
HRS WKD

6/24/93
DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

NAME (PRINT)

CRAFT

SIGNATURE

HRS WKD

DATE

SCAFFOLDING CHECKLIST

SR NO: PA-MN-1-JC-86013885 SEISMIC: YES NO
 PERMIT NO: #001 ¹⁻¹⁰⁻⁹³ STANDARD: YES NO N/A
 DATE: 6-24-93 INSPECTION: INITIAL: X SEMI-ANNUAL

ATTRIBUTE	ACCEPT	REJECT	N/A
1. ARE THE SCAFFOLD LADDERS VERTICALLY INSTALLED IN AN APPROPRIATE LOCATION, FOR SAFE ACCESS AND EXITING OF SCAFFOLD?	✓		
2. IS THE BOTTOM OF THE SCAFFOLD LADDER LESS THAN 12" OFF THE FLOOR?			✓
3. ARE THE SCAFFOLD LADDERS INSTALLED WITH A PROPER MANUFACTURER'S BRACKET?			✓
4. DO ALL SCAFFOLD LADDERS AND/OR EXTENSION LADDERS EXTEND A MINIMUM OF 36" ABOVE SCAFFOLD PLATFORM?	✓		
5. ARE SCAFFOLD LADDERS AND PLATFORM ACCESS POINTS FREE OF INTERFERENCES (EXCLUDING PERMANENT PLANT FEATURES WHICH CANNOT BE WORKED AROUND)?	✓		
6. ARE ANY EXTENSION LADDERS BEING USED FOR SCAFFOLD ACCESS PROPERLY SECURED AT TOP AND BOTTOM?			✓
7. ARE SCAFFOLD PLATFORMS PROVIDED FOR SCAFFOLD LADDERS AT 30 FOOT INTERVALS?			✓
8. ARE HANDRAILS INSTALLED ON ALL SCAFFOLDS HAVING WORKING PLATFORMS MORE THAN ONE BUCK HIGH?	✓		
9. ARE HANDRAILS INSTALLED ON ALL SCAFFOLDS WITH PLATFORMS LESS THAN 45" IN WIDTH AND WORKING PLATFORMS MORE THAN 4 FEET HIGH?	✓		
10. ARE HANDRAILS CONSTRUCTED OF 2"X4" LUMBER, 2" NOMINAL O.D. TUBING OR OF MATERIAL SUPPLIED BY THE MANUFACTURER?	✓		
11. IF INTERFERENCES EXIST SUCH THAT HANDRAILS CANNOT BE INSTALLED ON ALL OPEN SIDES OF A SCAFFOLD, IS A "SAFETY BELT REQUIRED" STICKER ATTACHED TO THE SCAFFOLD TAG?			✓
12. ARE THE GUARDRAILS (TOP HANDRAIL) INSTALLED NO LESS THAN 36" AND NO MORE THAN 42" ABOVE SCAFFOLD PLATFORM?	✓		
13. IS THE MIDRAIL (BOTTOM HANDRAIL) INSTALLED EVENLY BETWEEN THE TOEBOARD AND GUARDRAIL?			✓

SCAFFOLDING CHECKLIST

ATTRIBUTE	ACCEPT	REJECT	N/A
14. ARE HANDRAIL POSTS SPACED NO MORE THAN 8 FEET APART?			✓
15. FOR SCAFFOLD PLATFORMS GREATER THAN 1 BUCK HIGH, ARE TOEBOARDS INSTALLED?	✓		
16. ARE TOE BOARDS A MINIMUM OF 4" IN HEIGHT AND INSTALLED ON ALL FOUR SIDES OF SCAFFOLD PLATFORM?	✓		
17. ARE ALL TOE BOARDS SECURELY TIED OFF TO SCAFFOLD PLATFORMS? NOTE: NUMBER NINE WIRE MAY BE USED FOR SECURING TOEBOARDS.	✓		
18. IS WIRE MESH OR EQUIVALENT INSTALLED ON SCAFFOLDS MORE THAN 1 BUCK HIGH WHICH ARE OVER WALKWAYS OR AROUND SAFETY RELATED EQUIPMENT?			✓
19. IS ALL SCAFFOLD PLANKING "SCAFFOLD GRADE" OR EQUIVALENT?	✓		
20. IS SCAFFOLD WOOD PLANKING OVERLAPPED A MINIMUM OF 12"?			✓
21. DOES ALL WOOD PLANKING EXTEND MORE THAN 6" AND LESS THAN 18" OVER THEIR END SUPPORTS?			✓
22. IF THE SCAFFOLD PLATFORM IS MADE FROM 2"X8" (OR GREATER) SCAFFOLD PLANKS, ARE THE PLANKS SUPPORTED AT INTERVALS OF 8 FEET OR LESS?			✓
23. ARE THE UNSUPPORTED SPANS OF PLYWOOD DECKING EQUAL TO OR LESS THAN 34 INCHES?	✓		
24. ARE SCAFFOLD NAILS DOUBLE-HEADED AND DRIVEN TO THE FIRST HEAD? (SINGLE HEADED NAILS ARE ACCEPTABLE IF FULLY DRIVEN IN.)	✓		
25. ARE SCAFFOLD NAILS DRIVEN AT AN ANGLE WHERE THEY ARE NOT SUBJECTED TO A STRAIGHT PULL ON TOEBOARDS & HANDRAILS?	✓		
26. ARE SAFEWAY SCAFFOLD FRAMES CONNECTED TOGETHER WITH AN APPROPRIATE SCAFFOLD PIN (PIGTAILS)?			✓
27. ARE SAFEWAY SCAFFOLD FRAMES BRACED WITH APPROPRIATE X-BRACING?			✓
28. ARE TUBE & COUPLER SCAFFOLDS BRACED WITH VERTICAL, DIAGONAL AND HORIZONTAL BRACES PER SCAFFOLD PROCEDURE?			✓

SOUTH TEXAS PROJECT ELECTRIC GENERATING STATION
SCAFFOLDING CHECKLIST

ATTRIBUTE	ACCEPT	REJECT	N/A
29. DOES THE VERTICAL LEG SPACING MEET THE MAXIMUM SPACING FOR SEISMIC SCAFFOLD (5'X7') AND NON-SEISMIC SCAFFOLD (4'X10' OR 5'X7')?			✓
30. ARE SCAFFOLDS TIED-OFF PER PROCEDURAL REQUIREMENTS?	✓		
31. IS A PROPER PAD/SOFTENER PLACED UNDER EACH VERTICAL LEG?			✓
32. IS SCAFFOLD CONSTRUCTED OF MATERIAL FROM SIMILAR SCAFFOLD SYSTEM TYPES?	✓		
33. FOR NONSTANDARD SEISMIC SCAFFOLDING, HAS DED APPROVED THE NONSTANDARD DESIGN?	✓		
34. ARE CLEARANCES IN ACCORDANCE WITH DRAWING 3A01-0-S-10003 OR ARE APPROVED BY DED?	✓		
35. ARE THE NAIL HOLES IN THE ALUMINUM PLANKING ACCEPTABLE?			✓

INSPECTION RESULTS: SATISFACTORY UNSATISFACTORY

COMMENTS: _____

Keshal Bramer
INSPECTOR SIGNATURE

1 6-24-93
DATE

ORIGINAL

COMBUSTIBLE MATERIAL STORAGE AUTHORIZATION

COPY

OPGP03-ZF-0004-1

(Page 1 of 1)

AUTHORIZATION # 93-41 EXPIRES 07/09/93

Date

REQUESTING DEPARTMENT/DIVISION MSD / PAUL SVATEK

BUILDING RCB-1 ELEVATION 60' ROOM(S) 501 FIRE AREA/ZONE U2/2002

MATERIAL NAME/DESCRIPTION	UNITS	Btu/UNIT	QUANTITY	TOTAL Btu's
<u>WOOD (FIRE RETARDANT)</u>	<u>LBS.</u>	<u>8,000</u>	<u>1,000</u>	<u>8,000,000 BTU</u>

06/22/93

REQUIRED STORAGE CONDITIONS AND PRECAUTIONS See wood to be taken in only
when needed and shall be removed as soon as work
is complete. Continuous fire watch provided by craft
with a fire extinguisher, while wood is in RCB-1 or the
MAB-1. FHE 93-265

P
calculations

Evaluated: [Signature] 06/22/93
 Fire Protection Coordinator Date

Approved: [Signature] 6/23/93
 Management (DM or above) Date

cc: _____

PREVENTIVE MAINTENANCE PACKAGE 1.1 DOCUMENTATION CHECKLIST

PM NO: MM-2-5C88008526 WAN: 91045078 TOTAL PAGES 12
ATTACHMENTS A-6 pg

ORIGINAL RECORDS

- | | |
|--|---|
| <input type="checkbox"/> PREVENTIVE MAINTENANCE WORK ORDER (PM) | <input type="checkbox"/> CONTROLLED ACCESS PERSONNEL LOG |
| <input checked="" type="checkbox"/> PM ADDITIONAL SHEETS | <input type="checkbox"/> CONTROLLED ACCESS MATERIAL AND TOOL CONTROL |
| <input type="checkbox"/> LOST TIME RECORD | <input type="checkbox"/> CONFIGURATION CHANGE LOG |
| <input type="checkbox"/> ISLT POST-MAINTENANCE PRESSURE TEST TRAVELER | <input type="checkbox"/> DIVING OPERATIONS APPROVAL FORM |
| <input type="checkbox"/> PERMIT TO BREACH FIRE BARRIER | <input type="checkbox"/> CABLE TERMINATIONS DATA SHEET |
| <input type="checkbox"/> SCAFFOLDING PERMIT | <input type="checkbox"/> RAYCHEM APPLICATION DATA SHEETS |
| <input type="checkbox"/> INSULATION PERMIT | <input type="checkbox"/> TORQUING WORKSHEET |
| <input type="checkbox"/> SPECIFIC HOT WORK PERMIT | <input checked="" type="checkbox"/> PMP04-SERIES DATA SHEETS <u>JC-0002-1</u> |
| <input type="checkbox"/> PAINTING PERMIT | <input type="checkbox"/> PMP05-SERIES DATA SHEETS _____ |
| <input type="checkbox"/> EMERGENCY REQUEST AUTHORIZATION | <input type="checkbox"/> PMP07-SERIES DATA SHEETS _____ |
| <input type="checkbox"/> CONTROLLED ACCESS ADMITTANCE LIST | <input type="checkbox"/> PMP08-SERIES DATA SHEETS _____ |
| <input checked="" type="checkbox"/> OTHER <u>MAGNETIC PARTICLE EXAM REPORT</u> | |

COMMENTS _____

_____ STI-93-011227-94 _____

SECTION 1: COMPONENT INFORMATION

TAG/TPMS	SERVICE DESCRIPTION	BLDG ROOM	ELEV
7C102NCP201A	CONTAINMENT POLAR CRANE	RCB C501	141

OTHER LOCATION INFORMATION: RCB ROOF

SECTION 2: ACTIVITY DESCRIPTION

PM ACTIVITY: LUBRICATE/INSPECT NPRDS: N

FREQUENCY: P1 RECOMMENDED MODE: 56

EQ RELATED: N QUALITY RELATED: Y

EOL REPLACEMENT: N ASME SEC. XI TRVL. REQUIRED: N

SECTION 3: WORK START APPROVAL

TECHNICAL SPECIFICATIONS SECTIONS(S):

TIME WHEN SYSTEM MUST BE RETURNED TO SERVICE	AUTHORITY: Reactor Operations
<u>N/A</u> DATE	<u>[Signature]</u> DATE
TIME	SIGNATURE

SECTION 4: POST MAINTENANCE TESTING

TEST REQUIRED: NO TEST REQUIREMENTS INCLUDED IN:

PMT COMPLETED: YES NO NA TP# N/A

SECTION 5: WORK COMPLETED CERTIFICATION/ACKNOWLEDGMENT

BR TAG REMOVED YES NO NA

CLEARANCES/PERMITS RELEASED YES NO NA

WORK SUPERVISOR	WORK START AUTHORITY
<u>[Signature]</u> DATE	<u>[Signature]</u> DATE
CERTIFICATION	ACKNOWLEDGMENT

SECTION 6: PACKAGE REVIEW

PM PLANNER REVIEW	PLANT ENG DEPT REVIEW
<u>[Signature]</u> DATE	<u>[Signature]</u> DATE

PREVENTIVE MAINTENANCE
WORK ORDER

PM:MM-2-JC-88008526
WAN:91045078 REV:06.0

SECTION 7: SPARE PARTS / MATERIAL USED

HL&P PART NUMB	INVENTORY SEQ NUMB	QCE QCP	IN MPL	QTY UOM	HL&P PART NUMBER DESCRIPTION	MAP NUMBER	QTY USED
501-35456	N/A	7S 7	NO	0 CN	OIL, GEAR, HEAVY GODIED, 5 GAL PAIL -QTY 0 CN	N/A	0
559-30011 501-43241	MER 93011601	7S 9	NO	0 TB	GREASE, EXTREME PRESSURE ADDITIVE (EP), DARK GREEN IN COLOR	30043	342 oz
559-30099	MRR 9301-08004	7S 9	NO	0 CN	OIL, PARAFFIN BASE TYPE, COMPOUNDED WITH ANTIRUST, ANTIOXIDATION	30043	38 oz
501-18810	MRR 91122042	7S 9	NO	0 CN	OIL, HYDRAULIC, AW GRADE 68, 5 GAL CN/35 LB PAIL	08655	26 oz
566-30275	N/A				DIAPERS	SHOP SUPPLIES	4-DOS.

SECTION 8: PERMITS/DOCUMENTATION

HOUSEKEEPING DONE	IV	N/A	RADIATION WORK PERMIT	Y	93-2-0047
CLEANLINESS CLASS	D	N/A	EQUIPMENT CLEARANCE	Y	2-93-5027
CONFINED SPACE	N	N/A	ADDITIONAL SECURITY REQ	N	N/A
FIRE HAZARD EVAL	N	N/A	AFFECT CHARCOAL FILTER	N	N/A
HOT WORK PERMIT	N	N/A	SCAFFOLDING REQUIRED	N	N/A
INSULATION REQ.	N	N/A	ASME SECTION XI TRAV.	N	N/A
HAZARD SYS BREACH	N	N/A	CONTAMINATED SYS BREACH	N	N/A

SECTION 9: M&TE USED

DESCRIPTION
0-1 IN. MICROMETER +/- .001 IN. ACCY.
1-2 IN. MICROMETER +/- .001 IN. ACCY.
2-250 FT LBS TORQUE WRENCH / MICROMETER

CAL
--ID NO.-- --DUE--
100-02202-025 7-21-93
100-02203-22 3-23-93
100-03130-011 4-5-93

SECTION 10: PERSONNEL PERFORMING MAINTENANCE

NAME CRAFT CREW SIGNATURE HOURS DATE

PREVENTIVE MAINTENANCE
WORK ORDER

PM:MM-2-JC-88008526
WAN:91045078 REV:06.0

Jeff Irwin	m/m	Whiting	Jeff Irwin	1	3-2-93
Andrew Palmer	m/m	Whiting	Andrew Palmer	1	3-2-93
		N/A			
Bennie Thomas	MM	Whiting	Bennie Thomas	4	3-2-93
Francis SHAMPINE	M.M.	WHITING	FR. Shampine	4	3-3-93
ORVAL Knight	M/M	SUN	Orval Knight	4	3-3-93
Jim Biggs	M.M.	SUN	Jim Biggs	3	3-3-93
Thomas W. Camp Jr	m/m	S/G	Thomas W. Camp Jr	2	3-3-93
WAYNE ROSE	M/M	WHITING	Wayne Rose	2	3-3-93
Dewan Carruth	m/m	SUN	Dewan Carruth	12	3-3-93
ORVAL Knight	M/M	SUN	Orval Knight	3	3-3-93
Jim Biggs	MM	SUN	Jim Biggs	12	3-3-93
Francis SHAMPINE	M.M.	WHITING	FR. Shampine	3	3-3-93
KENNETH SCIBA	MM	WHITING	Kenneth Sciba	6	3/5/93
Sidney Story	M/M	Whiting	Sidney Story	6	3/5/93
KENNETH POLK	M/M	Whiting	Kenneth Polk	6	3/5/93
Andrew Palmer	M/M	Whiting	Andrew Palmer	6	3-5-93
Mike Cole	M/M	Whiting	Mike Cole	6	3-5-93 MC
Charles Teutsch	M/M	Whiting	Charles Teutsch	6	3-5-93
Jeff Irwin	M/M	Whiting	Jeff Irwin	6	3-5-93
ORVAL Knight	M/M	SUN	Orval Knight	12	3-5-93
Jim Biggs	M/M	SUN	Jim Biggs	12	3-5-93
Bruce O'Boyle	M/M	SUN	Bruce O'Boyle	10	3-5-93
Dewan Carruth	M/M	SUN	Dewan Carruth	12	3-5-93
FRANK SHAMPINE	M/M	WHITING	FR. Shampine	12	3-5-93
WAYNE ROSE	M/M	Whiting	Wayne Rose	12	3-5-93

SECTION 11: PREVENTIVE MAINTENANCE WORK INSTRUCTION

PM ACTIVITY: LUBRICATE/INSPECT

TAG NUMBER	SERVICE DESCRIPTION	QAQC	EQ
------------	---------------------	------	----

7C102MCP201A	CONTAINMENT POLAR CRANE		7S
--------------	-------------------------	--	----

1.0 PREREQUISITES

1.01 GENERAL

1.01.01 OBTAIN THE LUBRICANTS LISTED IN STEP 1.03 OR THEIR EQUIVALENTS IN ACCORDANCE WITH OPGP03-ZM-0004 (LUBRICATION PROGRAM).

1.01.02 OBTAIN A WORKING COPY OF OPMP04-JC-0002 (POLAR CRANE INSPECTION).

1.02 SPECIAL TOOLS / EQUIPMENT

1.02.01 SUITABLE DRAIN PAN

1.02.02 FUNNEL

1.02.03 GREASE GUN

1.02.04 APPROVED WIPES

1.02.05 CLEANING SOLVENT

1.02.06 0-1 IN. MICROMETER +/- .001 IN. ACCY.

1.02.07 1-2 IN. MICROMETER +/- .001 IN. ACCY.

CAL REQ

N
N
N
N
N
Y
Y

1.03 REQUIRED SPARE PARTS

CLASS-BIN	DESCRIPTION	QTY	UOM
1.03.01	559-30099 OIL, PARAFFIN BASE TYPE, COMPOUNDED WITH	0	CN
1.03.02	501-35456 OIL, GEAR, HEAVY GODIED, 5 GAL PAIL	0	CN
1.03.03	501-18810 OIL, HYDRAULIC, AW GRADE 68, 5 GAL CN/35	0	CN
1.03.04	559-30011 GREASE, EXTREME PRESSURE ADDITIVE (EP), D	0	TB

1.04 PERMITS AND INDICATORS

1.04.01 MAINTAIN HOUSEKEEPING BONE IV.

1.04.02 MAINTAIN CLASS D SYSTEM CLEANNESS.

1.04.03 A RADIATION WORK PERMIT IS REQUIRED FOR PERFORMANCE OF THIS ACTIVITY.

1.04.04 AN EQUIPMENT CLEARANCE IS REQUIRED FOR PERFORMANCE OF THIS ACTIVITY.

2.0 PRECAUTIONS

2.01 FOLLOW PRECAUTIONS LISTED IN OPMP4-JC-0002 (POLAR CRANE INSPECTION).

3.0 WORK INSTRUCTIONS

3.01 LUBRICATE AND INSPECT POLAR CRANE IN ACCORDANCE WITH OPMP04-JC-0002 (POLAR CRANE INSPECTION).

3.02 CLEAN THE "MAIN" AND "AUXILLARY" HOOKS, (FOR INSPECTION).

SECTION 11: PREVENTIVE MAINTENANCE WORK INSTRUCTION

PM ACTIVITY: LUBRICATE/INSPECT

4.0 REFERENCES

4.01 IMPLEMENTING REFERENCES

4.01.01 OPMP04-JC-0002 POLAR CRANE INSPECTION

4.02 SOURCE DOCUMENTS

4.02.01 8013-C1001-WG WHITING CORP. MANUAL

4.02.02 STPEGS LUBRICATION STANDARD

4.02.03 ESR NO. 87-JE-003

4.02.04 FEEDBACK FORMS 27682, 28588.

5.0 DOCUMENTATION - NONE

NA

SECTION 12:

AS FOUND CONDITION

Daily Check Performed, Peter Crane Operable / 3-3-93 WORKING AROUND SCAFFOLDING

PERSONNEL - "A" GIRDER LEFT DR. BRG CAPSULE DAMAGED COUPLING AWARD ROBBING SHAFT - "A" G. BRG

RIGHT CRANE BOLT LOSS, MISSING OVERHOLE COVR. OIL LEAK, EXCESSIVELY LOW OIL "B" GIRDER LOW OIL LEAK, LOW

SECTION 13:

AS LEFT CONDITIONS

PM COMPLETE READY FOR PMT WORKHOUSE WORK NUM 6 MAR 93

N/A

SECTION 14:

SUMMARY OF WORK PERFORMED

HOWARD ATKINS JR

John J. Bigger - 3-2-93

RALPH HARVEY IS DESIGNATED WORK GROUP SUPERVISOR FOR THIS JOB

Held Pre Job Briefing, Obtained Work Start, lowered Main & Aux. Hook
checked and measured both hooks. NDE Results attached and Sat.

Performed 561 - 563 of OPMP04-JC-0002 received and data
sheets attached

Jeff Irwin Off Cr 3-2-93

3-3-93 RECEIVED WORK PACKAGE FROM DAY SHIFT, DECIDED WORK SCOPE, HAD

M/M FISMAN SIGN OVER ECO. CHECKED BRIDGE DRINK BEAR BY OIL LEVELS. NEED TO

ADD OIL TO "A" GIRDER RIGHT AND "B" GIRDER LEFT AND RIGHT (SEE CONTINUATION SHEET)

SECTION 15:

COG SYSTEM ENGINEER CONTACTED: YES NO NA

PARTS NEEDED FOR ROOT CAUSE: YES NO NA
PARTS TO BE REBUILT: YES NO NA
PARTS DISCARDED: YES NO NA

SR NO: NA
MRM NO: NA

AREA CLEAN: YES NO NA | INSULATION REMOVED: YES NO NA
TOOLS REMOVED: YES NO NA | INSULATION REINSTALLED: YES NO NA
HARDWARE RESTORED: YES NO NA | SCAFFOLDING REMOVED: YES NO NA

WORK COMPLETED: Wayne D...
CRAFTSMAN

11 MAR 93
DATE

0825
TIME

ADDITIONAL SHEETS ATTACHED & NUMBERED

NO YES

SHEETS: 6

NEED TO BRING APPROX. 5 GAL OF OIL.

WAYNE AVSC Waynesburg 3 MARCH 1993

RECEIVED PKG FROM NIGHT SHIFT HELD PREJOB MEETING.

Completed the following steps of the IN HAND section 3.0 - 5.9.9 OK,
5.9.5 - 5.9.5.3 NA, 5.9.6 - 5.9.17 OK, 5.9.21 - 5.9.22 OK, 5.9.26 -
5.9.29 OK, 5.5.9 - 5.6.9 OK, 5.6.19 - 5.6.21 OK, 5.6.24 - 5.6.25 OK

The following steps not completed due to 5.9.18 - 5.9.20 need the crane rotated
to the platform for access, 5.9.23 - 5.9.24 need Remv. Cap, 5.9.25 need
to rotate crane for access, 5.5 - 5.5.3 need trolley located at opp. end,
5.6.10 - 5.6.18 need hooks lowered, 5.6.22 also needs hooks lowered,
5.6.27 - 5.6.29 need hoist to run to check. Removal All covers on both Hoist
drives, inspected & lubed then started installing covers. Added oil to A Gider
Right & B Gider, left and Right Bridge Drive Gear Boxes.

Jeff Irwin Jeff Irwin 3-4-93

RECEIVED PKG FROM DAY SHIFT, OBTAINED TURNOVER FROM JEFF IRWIN

HELD PREJOB MEETING REINSTALLED COVERS THAT WERE REMOVED.

WAYNE AVSC Waynesburg 4 MARCH 1993

Held Pre Job meeting inspected Trolley Drive Gear Box, lubed Drive Shafts
Checked Oil Levels in Brake & Drive Gear Box, lub OK, Cleaned
platforms, Drive shafts, Gear Boxes. Jeff Irwin Jeff Irwin 3-5-93

RECEIVED PKG FROM DAY SHIFT, OBTAINED TURNOVER FROM JEFF IRWIN

HELD PREJOB MEETING FINISHED COUPLING BOLTING ON "B" GIRDER LEFT
END, INSTALLED COVER, "A" GIRDER RIGHT END COUPLING, INSTALLED MISSING
BELT AND VERIFIED TORQUE ALSO TORQUED BELTS ON "A" "B" GIRDER LEFT
BELTS TORQUED TO 150 FT LBS CAL DUC DATE 09-05-93 20" HO-012-011

MASE Ux03593 ROTATED BRIDGE AND CHECKED ALL IDLER
WHEEL BRGS. LUBED WHEEL BRGS AT THIS TIME FOUND NO DETECTABLE
DAMAGE BUT DID FIND A IMPROPER LUBC PROCEDURE, BRGS WERE LOW
(SEE CONTINUATION SHEET)

~~NEED TO BRING APPROX. 5 GAL OF OIL. u# 3-6-93~~

~~WATER HOSE ~~Way-Hum~~ 3-6-93~~

ON LUBE. Performed PM on orbital bridge the grease zerk on the top pivot point would not take any grease. Removed Tools AND TRASH FROM CRANE. Way-Hum 3-6-93

3-6-93 PERFORMED OPERATION TEST OF ALL MOTIONS OF CRANE.

TESTED OPERATION AT ALL SPEEDS OF ALL MOTIONS. MAIN HOIST

TESTED USING SPARE ^{DBZ} 3/6/93 RADIO CONTROL BOARD FROM AUX HOIST

CIRCUIT FOR ^{DBZ} ~~FOR~~ PURPOSE OF TROUBLESHOOTING AND TESTING OF MECHANICAL COMPONENTS. NO MECHANICAL DISCREPANCIES NOTED.

LOOSED GIRDER BOLTS AND TIGHTENED TEN BOLTS Daniel B. Zimfel

3-9-93 INSTALLED NEW RELAY CIRCUIT CARD UNDER SR# JC 17956.

PERFORMED FULL OPERATIONAL TEST ON ALL MOTIONS OF CRANE. MEASURED

AND RECORDED MAIN HOIST HOOK OPENING & TWIST. PERFORMED WALK

DOWN INSPECTION OF ENTIRE CRANE. FOUND OIL LEAKS ON MAIN & AUX

HOISTS CAUSED BY STRIPPED BOLTS IN THE INSPECTION COVERS. RAV

ASHBURY, SYSTEM ENGINEER WILL GENERATE THE SR TO ADDRESS

THIS PROBLEM. CLEANED ALL LEAKING OIL OFF TROLLEY DECK.

REMOVED ALL TOOLS & MATERIALS FROM CRANE. Daniel B. Zimfel 3/6/93

N/A

PERSONNEL PERFORMING MAINTENANCE

MM-2-JC-8000RSZ
MAN # 91045078

Name (Print)	Signature	Hrs Wkd	Date
PAUL B. ZIMBRICH	<i>Paul B. Zimlich</i>	6.0	3-9-93
Mike Cole	<i>Mike Cole</i>	6.0	3-9-93
Sidney Story	<i>Sidney Story</i>	6.0	3-9-93
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date
Name (Print)	Signature	Hrs Wkd	Date

Polar Crane Inspection

OPMP04-JC-0002

Rev. 5

Page 21 of 22

DATA SHEET
OPMP04-JC-0002-1
(Page 1 of 2)

5.1 SR/PH No. MM-Z-3C-88008524

5.2 Unit No. 2

3.1

WORK SUPERVISOR SHALL MARK SECTIONS TO BE PERFORMED OR ENTIR. N/A	
<input checked="" type="checkbox"/> 5.4 Bridge Lubrication and Inspection	<input checked="" type="checkbox"/> 5.7 Operational Inspection
<input checked="" type="checkbox"/> 5.5 Trolley Lubrication and Inspection	<input checked="" type="checkbox"/> 5.8 Operation of Bridge
<input checked="" type="checkbox"/> 5.6 Hoist Lubrication and Inspection	

3.2

MEASURING AND TEST EQUIPMENT		
DESCRIPTION	STPEGS I.D. NUMBER	CALIBRATION DUE DATE
0-1 MIC	100-02302-025	7-21-93
1-2 MIC	100-02303-22	3-23-93
TORQUE WRENCH	100-03130-011	4-5-93

5.4.4 Checked oil in gearcase: DBZ SAT. _____ UNSAT.

5.4.5 Changed oil in gearcase: _____ 4 yr. changeout _____ Oil was UNSAT N/A

5.4.28 Hoist drum groove wear percentage - NO WEAR NOTED - Method: STRAIGHT EDGE

5.6.1 Notified cranes and hoists system engineer or designee. [Signature] 13-2-93
Mech. Sign Date

5.6.2 Measurements of main hoist wire rope O.D.
R- 1.252 in. R- 1.252 in. R- 1.252 in.
L- 1.253 in. L- 1.252 in. L- 1.250 in.

5.6.3 Measurements of auxiliary hoist wire rope O.D.
.486 in. .500 in. .500 in.

ENP 5.6.11 Lubrication inspection of wire ropes: SAT UNSAT
Daniel B Zimbrich DANIEL B ZIMBRICH
 System Engineer or Designee Sign Date 3-3-93

ENP 5.6.12 Cranes and hoists system engineer or designee determined wire ropes are to be replaced. YES NO
Daniel B Zimbrich DANIEL B ZIMBRICH
 System Engineer or Designee Sign Date 3-3-93

ROPE IS SAT.

This FORM, when completed, shall be retained for the life of the plant.

DATA SHEET
OPMP04-JC-0002-1
(Page 2 of 2)

5.1 SR/PM No. MM-2-nd JC-88008526 5.2 Unit No. 2

5.6.13 Throat gage measurement on auxiliary hook. 6 ⁵/₈ in.

5.6.14 Throat gage measurement on main hook. 23 ¹/₂ in. 23 ¹/₂ in.

5.6.16 Measured twist of auxiliary hook. 0° deg.

5.6.17 Measured twist of main hook. 0° deg. 0° deg.

ENP 5.6.26 Cranes and hoists system engineer or designee determined auxiliary and main hoist requires lubrication. YES NO

Daniel B Zimbrak DANIEL B ZIMBRUK
System Engineer or Designee Sign

3-3-93
DATE
OIL LEVELS SAT

5.9 Crane operates satisfactory: PPZ Yes No

Comments: REPLACED DEFECTIVE RELAY OUTPUT CARD UNDER JC 179568

PERFORMED BY: Daniel B Zimbrak MECHANIC 3-9-93 DATE

REVIEWED BY: John S. Snijder WORK SUPERVISOR 3-9-93 DATE

MAGNETIC PARTICLE EXAMINATION REPORT

WORK DOC NO Pm P04-2-JC-280085Z Rev 60	COMPONENT DESCRIPTION UNIT 2 CRANE HOOKS	TPNS/COMPONENT ID NO 5-6-19 AUX Hook EL-20 main	DATE OF INSPECTION 3-2-93 REPORT NO NDE-93-0269
--	--	---	--

LOCATION UNIT NO 2 BLDG NO BCB ROOM NO <u>Containment</u> ELEVATION <u>N/A</u> OTHER INFORMATION <u>N/A</u>	ADDITIONAL INFORMATION DPmP04-JC-0052 Rev 5 TAG 7C102NCP201A
--	--

DWG NO <input checked="" type="checkbox"/> N/A	MATERIAL Carbon steel
--	--------------------------

IS EXAMINATION AREA PAINTED <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO PAINT THICKNESS <input checked="" type="checkbox"/> N/A DYE FILM GAGE ID <u>N/A</u> DUE DATE	MT PROCEDURE NO NDEP 7.0 Rev 2 ACCEPTANCE STD <input type="checkbox"/> INA APPENDIX NO <u>6</u> <input type="checkbox"/> OTHER
--	--

CURRENT TYPE <input checked="" type="checkbox"/> AC <input type="checkbox"/> HVDC	MAGNETIZING METHOD <input checked="" type="checkbox"/> CONTINUOUS <input type="checkbox"/> RESIDUAL	EQUIPMENT USED MFG <u>MAGNAFLUX</u> MOD <u>YL</u> SER NO <u>4</u> CAL BLOCK ID <u>MT 005</u>	EXAMINATION MEDIUM <input type="checkbox"/> BLACK POWDER NO 3A <input checked="" type="checkbox"/> RED POWDER NO 8A <input type="checkbox"/> GRAY POWDER NO 1 <input type="checkbox"/> MAGNAGLO NO 14AM (WET)
---	---	--	---

<input type="checkbox"/> COIL AMP TURNS <input checked="" type="checkbox"/> NA	<input type="checkbox"/> PRODS AMPERAGE <input checked="" type="checkbox"/> NA SPACING <input checked="" type="checkbox"/> NA	<input checked="" type="checkbox"/> YOKE LIFT VERIFICATION <input checked="" type="checkbox"/> BEFORE AND AFTER INSPECTION <input checked="" type="checkbox"/> 10 LBS <input type="checkbox"/> 40 LBS	LIGHT LEVEL VERIFICATION (SAT) <input checked="" type="checkbox"/> ILLUMINATION <input type="checkbox"/> ULTRAVIOLET SURF TEMP <input type="checkbox"/> < 135 F (WET) <input checked="" type="checkbox"/> < 600 F (DRY)
--	---	--	--

WELD NO, PART NO, OR SERIAL NO	ACC	REJ	REMARKS	SKETCH OR DRAWING
500 Ton Pole Crane Lifting Hook	✓			N A
15 Ton Lifting Hook	✓			

COMMENTS
NONE

INSPECTOR <u>Dart Stufus</u>	CERT LEVEL <u>HH0177 II</u>	DATE <u>3-2-93</u>	SUPV/LEVEL III REVIEW	DATE
INSPECTOR <u>P. P. P.</u>	CERT LEVEL <u>HH0177 II</u>	DATE <u>3-2-93</u>		