## EMERGENCY CORE COOLING SYSTEMS

### SURVEILLANCE REQUIREMENTS (Continued)

greater than or equal to 245

- For the HPCI system, verifying that the system develops a flow of 2. at least 5000 gpm against a test line pressure of 200 8 16 psig when steam is being supplied to the turbine at 150 ± 15 psig.\*
- Performing a CHANNEL CALIBRATION of the CSS header AP instrumentation and verifying the setpoint to be < 1 psid.
- Verifying that the suction for the HPCI system is automatically transferred from the condensate storage tank to the suppression chamber on a condensate storage tank water level - low signal and on a suppression chamber - water level high signal.
- Performing a CHANNEL CALIBRATION of the condensate transfer pump discharge low pressure alarm instrumentation and verifying the ow pressure alarm setpoint to be > 113 psig.

#### the ADS: d.

- At least once per 31 days, performing a CHANNEL FUNCTIONAL TEST of the accumulator backup compressed gas system low pressure alarm system.
- 2. At least once per 18 months:
  - Performing a system functional test which includes simulated automatic actuation of the system throughout its emergency operating sequence, but excluding actual valve actuation.
  - Manually\*\* opening each ADS valve when the reactor steam b) dome pressure is greater than or equal to 100 psig\* and observing that either:
    - The control valve or bypass valve position responds accordingly, or
    - 2) There is a corresponding change in the measured steam
  - Performing a CHANNEL CALIBRATION of the accumulator backup compressed gas system low pressure alarm systems and verifying air alarm setpoint of 2070 + 35 psig on decreasing pressure.
- At least every 18 months the following shall be accomplished by any series of sequential, overlapping or total channel steps such that the entire channel is tested:

<sup>\*</sup>The provisions of Specification 4.0.4 are not applicable provided the surveillance is performed within 12 hours after reactor steam pressure is adequate to perform the test.

<sup>\*\*</sup>ADS solenoid energization shall be used alternating between ADS Division 1 and ADS Division 2.

# EMERGENCY CORE COOLING SYSTEMS

Greater than or equal to 245

# SURVEILLANCE REQUIREMENTS (Continued)

- 2.8 For the HPCI system, verifying that the system develops a flow of at least 5000 gpm against a test line pressure of 210 x 15 psig when steam is being supplied to the turbine at 150 ± 15 psig.\*
- 3. Performing a CHANNEL CALIBRATION of the CSS header  $\Delta P$  instrumentation and verifying the setpoint to be  $\leq 1$  psid.
- 4. Verifying that the suction for the HPCI system is automatically transferred from the condensate storage tank to the suppression chamber on a condensate storage tank water level - low signal and on a suppression chamber - water level high signal.
- Performing a CHANNEL CALIBRATION of the condensate transfer pump discharge low pressure alarm instrumentation and verifying the low pressure alarm setpoint to be > 113 psig.

#### d. For the ADS:

- At least once per 31 days, performing a CHANNEL FUNCTIONAL TEST of the accumulator backup compressed gas system low pressure alarm system.
- At least once per 18 months:
  - a) Performing a system functional test which includes simulated automatic actuation of the system throughout its emergency operating sequence, but excluding actual valve actuation.
  - b) Manually\*\* opening each ADS valve when the reactor steam dome pressure is greater than or equal to 100 psig\* and observing that either:
    - The control valve or bypass valve position responds accordingly, or
    - There is a corresponding change in the measured steam flow.

<sup>\*</sup>The provisions of Specification 4.0.4 are not applicable provided the surveillance is performed within 12 hours after reactor steam pressure is adequate to perform the test.

<sup>\*\*</sup>ADS solenoid energization shall be used alternating between ADS Division 1 and ADS Division 2.

<sup>#</sup>For the startup following the Third Requeling and Inspection Outage, this surveillance shall read as follows:

For the HPCI System, verifying that the system develops a flow of at least 4850 gpm against a test line pressure of 600 psig when steam is being supplied to the turbine at 150  $\pm$  15 psig.\*