

ATTACHMENT 3

PROPOSED TECHNICAL SPECIFICATIONS

Marked up Technical Specification Pages;

2-2
2-4
2-5
2-7
2-8
2-9
2-10

3/4 2-16
3/4 3-24
3/4 3-26
3/4 3-27
3/4 3-30

B 3/4 2-8

INSERT 'A' HERE




FIGURE 2.1-1
REACTOR CORE SAFETY LIMIT - THREE LOOPS IN OPERATION

INSERT A




Figure 2.1-1
Reactor Core Safety Limit - Three Loops in Operation

TABLE 2.2-1

REACTOR TRIP SYSTEM INSTRUMENTATION TRIP SETPOINTS

FUNCTIONAL UNIT	ALLOWANCE (TA)	Z	S	TRIP SETPOINT	ALLOWABLE VALUE
1. Manual Reactor Trip	N.A	N.A	N.A	N.A.	N.A.
2. Power Range, Neutron Flux					
a. High Setpoint	7.5	4.56	0.0	<109% of RTP**	<112.0% of RTP**
b. Low Setpoint	8.3	4.56	0.0	<25% of RTP**	<28.0% of RTP**
3. Intermediate Range, Neutron Flux	13.5	8.41	0.0	<25% of RTP**	<31.0% of RTP**
4. Source Range, Neutron Flux	13.9	10.01	0.0	<10 ⁵ cps	<1.4 x 10 ⁵ cps
5. Overtemperature ΔT	7.2	4.8	2.5	See Note 1	See Note 2
6. Overpower ΔT	5.3	3.1	2.0	See Note 3	See Note 4
7. Pressurizer Pressure-Low	4.5	1.12	1.4	>1835 psig	>1817 psig
8. Pressurizer Pressure-High	5.5	1.12	1.4	<2385 psig	<2403 psig
9. Pressurizer Water Level-High	8.0	6.8	4.0	<92% of instrument span	<92.2% of instrument span
10. Reactor Coolant Flow-Low	4.6	2.7	0.8	>90% of loop design flow*	>88.7% of loop design flow*
11. Steam Generator Water Level Low-Low	5.0	2.33	1.9	>15% of narrow range instrument span	>13.2% of narrow range instrument span

*Loop design flow = 89,500 gpm

**RTP = Rated Thermal Power

2.0% span for ΔT (RTDs) and 0.5% for pressurizer pressure




TABLE 2.2-1 (Continued)

REACTOR TRIP SYSTEM INSTRUMENTATION TRIP SETPOINTS

FUNCTIONAL UNIT	ALLOWANCE (TA)	Z	S	TRIP SETPOINT	ALLOWABLE VALUE
12. Steam/Feedwater Flow Mismatch Coincident With	20.0	3.67	7.3 ^{##}	Feed Flow <20% below steam flow	Feed Flow <23.9% below steam flow
Steam Generator Water Level-Low	5.0	2.77	2.0	>15% of narrow range instrument span	>13.2% of narrow range instrument span
13. Undervoltage - 4.16 kV Busses A and B	20.0	1.12	0.0	>70% bus voltage	>69% bus voltage
14. Underfrequency - Trip of Reactor Coolant Pump Breaker(s) Open	6.5	0.03	0.0	>56.1 Hz	>55.9 Hz
15. Turbine Trip					
a. Auto Stop Oil Pressure	2.6	1.0	0.0	>45 psig	>42 psig
b. Turbine Stop Valve Closure	N.A.	N.A.	N.A.	Fully Closed ^{***}	Fully Closed ^{***}
16. Safety Injection Input from ESF	N.A.	N.A.	N.A.	N.A.	N.A.
17. Reactor Trip System Interlocks					
a. Intermediate Range Neutron Flux, P-6	N.A.	N.A.	N.A.	Nominal 1×10^{-10} amp	$>6.0 \times 10^{-11}$ amps

***Limit switch is set when Turbine Stop Valves are fully closed.

1.7% span for steam line flow, 2.9% span for feedwater flow and 2.8% span for steam line pressure.

TABLE 2.2-1 (Continued)
TABLE NOTATIONS

NOTE 1: OVERTEMPERATURE ΔT

$$\Delta T \left\{ \frac{1 + \tau_1 S}{1 + \tau_2 S} \right\} \left(\frac{1}{1 + \tau_3 S} \right) \leq \Delta T_0 \left(K_1 - K_2 \frac{(1 + \tau_4 S)}{(1 + \tau_5 S)} \left[T \left(\frac{1}{1 + \tau_6 S} \right) - T' \right] + K_3 (P - P') - f_1 (\Delta I) \right)$$

Where: ΔT = Measured ΔT by RTD Instrumentation

$\frac{1 + \tau_1 S}{1 + \tau_2 S}$ = Lead/Lag compensator on measured ΔT ; $\tau_1 = 0s$, $\tau_2 = 0s$

$\frac{1}{1 + \tau_3 S}$ = Lag compensator on measured ΔT ; $\tau_3 = 0s$

ΔT_0 = Indicated ΔT at RATED THERMAL POWER

K_1 = 1.095 ; 1.25

K_2 = 0.0107 / $^{\circ}F$; 0.016

$\frac{1 + \tau_4 S}{1 + \tau_5 S}$ = The function generated by the lead-lag compensator for T_{avg} dynamic compensation;

τ_4, τ_5 = Time constants utilized in the lead-lag compensator for T_{avg} ; $\tau_4 = 25s$, $\tau_5 = 3s$;

T = Average temperature, $^{\circ}F$;

$\frac{1}{1 + \tau_6 S}$ = Lag compensator on measured T_{avg} ; $\tau_6 = 0s$

T' \leq 574.2 $^{\circ}F$ (Nominal T_{avg} at RATED THERMAL POWER);

K_3 = 0.000453 / psig; 0.0011

P = Pressurizer pressure, psig;

TABLE 2.2-1 (Continued)
 TABLE NOTATIONS (Continued)

NOTE 1: (Continued)

P' \geq 2235 psig (Nominal RCS operating pressure);

S = Laplace transform operator, s^{-1} ;

and $f_1(\Delta I)$ is a function of the indicated difference between top and bottom detectors of the power-range neutron ion chambers; with gains to be selected based on measured instrument response during plant startup tests such that:

- (1) For $q_t - q_b$ between -14% and $+10\%$, $f_1(\Delta I) = 0$, where q_t and q_b are percent RATED THERMAL POWER in the top and bottom halves of the core respectively, and $q_t + q_b$ is total THERMAL POWER in percent of RATED THERMAL POWER;
 - -46% (circled) points to -14%
 - $+2\%$ (circled) points to $+10\%$
- (2) For each percent that the magnitude of $q_t - q_b$ exceeds -14% , the ΔT Trip Setpoint shall be automatically reduced by 1.5% of its value at RATED THERMAL POWER; and
 - -46% (circled) points to -14%
- (3) For each percent that the magnitude of $q_t - q_b$ exceeds $+10\%$, the ΔT Trip Setpoint shall be automatically reduced by 1.5% of its value at RATED THERMAL POWER.
 - $+2\%$ (circled) points to $+10\%$
 - 2.3% (circled) points to 1.5%

NOTE 2: The channels maximum trip setpoint shall not exceed its computed setpoint by more than 1.5% of instrument span.

- 0.73% (circled) points to 1.5%

TABLE 2.2-1 (Continued)
 TABLE NOTATIONS (Continued)

NOTE 3: OVERPOWER ΔT

$$\Delta T \left\{ \frac{1 + \tau_1 S}{1 + \tau_2 S} \right\} \left(\frac{1}{1 + \tau_3 S} \right) \leq \Delta T_o \left[K_4 - K_5 \left(\frac{\tau_7 S}{1 + \tau_7 S} \right) \left(\frac{1}{1 + \tau_6 S} \right) T - K_6 \left[T \left(\frac{1}{1 + \tau_8 S} \right) - T'' \right] - f_2 (\Delta T) \right]$$

Where: ΔT = As defined in Note 1,

$\frac{1 + \tau_1 S}{1 + \tau_2 S}$ = As defined in Note 1,

$\frac{1}{1 + \tau_3 S}$ = As defined in Note 1,

ΔT_o = As defined in Note 1,

K_4 \leq 1.09 \leftarrow 1.10

K_6 \geq 0.02/ $^{\circ}$ F for increasing average temperature and 0 for decreasing average temperature,

$\frac{\tau_7 S}{1 + \tau_7 S}$ = The function generated by the rate-lag compensator for T_{avg} dynamic compensation,

τ_7 = Time constants utilized in the rate-lag compensator for T_{avg} , $\tau_7 \geq 10$ s,

$\frac{1}{1 + \tau_8 S}$ = As defined in Note 1,

TABLE 2.2-1 (Continued)
TABLE NOTATIONS (Continued)

NOTE 3: (Continued)

- K_4
 - = 0.00232 (circled) $\times 0.00068$ (boxed) $^{\circ}\text{F}$ for $T > T''$
 - = 0 for $T \leq T''$,
- T
 - = As defined in Note 1,
- T''
 - = Indicated T_{avg} at RATED THERMAL POWER (Calibration temperature for ΔT instrumentation, $\leq 574.2^{\circ}\text{F}$),
- S
 - = As defined in Note 1, and
- $f_2(\Delta I)$
 - = 0 for all ΔI

NOTE 4:

The channel's maximum trip setpoint shall not exceed its computed trip setpoint by more than 0.4% (circled) of instrument span.

POWER DISTRIBUTION LIMITS

3/4.2.5 DNB PARAMETERS

LIMITING CONDITION FOR OPERATION

3.2.5 The following DNB-related parameters shall be maintained within the following limits:

- a. Reactor Coolant System $T_{avg} \leq 576.6^{\circ}F$
- b. Pressurizer Pressure ≥ 2209 psig*, and
- c. Reactor Coolant System Flow $\geq 277,900$ gpm

APPLICABILITY: MODE 1.

ACTION:

With any of the above parameters exceeding its limit, restore the parameter to within its limit within 2 hours or reduce THERMAL POWER to less than 5% of RATED THERMAL POWER within the next 4 hours.

SURVEILLANCE REQUIREMENTS

INSERT 'B' HERE

4.2.5.1 ~~Each of the parameters shown above shall be verified to be within its limits at least once per 12 hours.~~

3 4.2.5.2 The RCS flow rate indicators shall be subjected to a CHANNEL CALIBRATION at least once per 18 months.

4 4.2.5.3 ~~The RCS flow rate shall be demonstrated by measurement once per 18 months.~~

INSERT (C) HERE

*Limit not applicable during either a THERMAL POWER ramp in excess of 5% of RATED THERMAL POWER per minute or a THERMAL POWER step in excess of 10% of RATED THERMAL POWER.

TURKEY POINT - UNITS 3 & 4

3/4 3-24

AMENDMENT NOS. 146 AND 141

TABLE 3.3-3 (Continued)
ENGINEERED SAFETY FEATURES ACTUATION SYSTEM
INSTRUMENTATION TRIP SETPOINTS

FUNCTIONAL UNIT	ALLOWANCE (TA)	Z	S	TRIP SETPOINT	ALLOWABLE VALUE#
Coincident with: Steam Generator Pressure--Low	13.0	1.16	2.3	>614 psig	>588 psig
or T _{avg} --Low	4.0	2.1	2.0	>543°F	>542.5°F
2. Containment Spray					
a. Automatic Actuation Logic and Actuation Relays	N.A.	N.A.	N.A.	N.A.	N.A.
b. Containment Pressure--High- High Coincident with: Containment Pressure--High	21.3	2.7	0.0	<20.0 psig	<22.6 psig
	13.3	10.3	0.0	< 4.0 psig	< 4.5 psig
3. Containment Isolation					
a. Phase "A" Isolation					
1) Manual Initiation	N.A.	N.A.	N.A.	N.A.	N.A.
2) Automatic Actuation Logic and Actuation Relays	N.A.	N.A.	N.A.	N.A.	N.A.
3) Safety Injection	see item 1			See Item 1 above for all Safety Injection Trip Setpoints and Allowable Values.	
b. Phase "B" Isolation					
1) Manual Initiation	N.A.	N.A.	N.A.	N.A.	N.A.

TABLE 3.3-3 (Continued)
ENGINEERED SAFETY FEATURES ACTUATION SYSTEM
INSTRUMENTATION TRIP SETPOINTS

FUNCTIONAL UNIT	ALLOWANCE (TA)	Z	S	TRIP SETPOINT	ALLOWABLE VALUE#
4. Steam Line Isolation (Continued)					
b. Automatic Actuation Logic and Actuation Relays	N.A.	N.A.	N.A.	N.A.	N.A.
c. Containment Pressure--High-High Coincident with: Containment Pressure--High	21.3	2.7	0.0	≤20.0 psig	≤22.6 psig
	13.3	10.3	0.0	≤4.0 psig	≤4.5 psig
d. Steam Line Flow--High	16.7	2.86	3.9	≤A function defined as follows: A Δp corresponding to 40% steam flow at 0% load increasing linearly from 20% load to a value corresponding to 120% steam flow at full load.	≤A function defined as follows: A Δp corresponding to 42.6% steam flow at 0% load increasing linearly from 20% load to a value corresponding to 122.6% steam flow at full load.
	13.0	1.16	2.3	≥614 psig	≥588 psig
Coincident with Steam Line Pressure--Low or T _{avg} --Low	4.0	2.1	1.0	≥543°F	≥542.5°F
5. Feedwater Isolation					
a. Automatic Actuation Logic and Actuation Relays	N.A.	N.A.	N.A.	N.A.	N.A.
b. Safety Injection	see item 1			See Item 1. above for all Safety Injection Trip Setpoints and Allowable Values.	
c. Steam Generator Water Level High-High	20.0	18.27	2.0	≤80% of narrow range instrument span.	≤81.9% of narrow range instrument span.

TABLE _____ (Continued)

ENGINEERED SAFETY FEATURES ACTUATION SYSTEM
INSTRUMENTATION TRIP SETPOINTS

TURKEY POINT - UNITS 3

3/4 3-27

AMENDMENT NOS. 146 AND 141

<u>FUNCTIONAL UNIT</u>	<u>ALLOWANCE (TA)</u>	<u>Z</u>	<u>S</u>	<u>TRIP SETPOINT</u>	<u>ALLOWABLE VALUE#</u>
6. Auxiliary Feedwater (3)					
a. Automatic Actuation Logic and Actuation Relays	N.A.	N.A.	N.A.	N.A.	N.A.
b. Steam Generator Water Level--Low-Low	5.0	2.77	2.0	10% >15% of narrow range instrument span.	≥ 8.9% <13% of narrow range instrument span.
c. Safety Injection		see item 1		See Item 1. above for all Safety Injection Trip Setpoints and Allowable Values.	
d. Bus Stripping		see item 7		See Item 7. below for all Bus Stripping Trip Setpoints and Allowable Values.	
e. Trip of All Main Feedwater Pump Breakers	N.A.	N.A.	N.A.	N.A.	N.A.
7. Loss of Power					
a. 4.16 kV Busses A and B (Loss of Voltage)	N.A.	N.A.	N.A.	N.A.	N.A.

TURKEY POINT - UNITS 3 & 4
3/4 3-30
AMENDMENT NOS. 146 AND 141

TABLE 3.3-3 (Continued)
ENGINEERED SAFETY FEATURES ACTUATION SYSTEM
INSTRUMENTATION TRIP SETPOINTS

FUNCTIONAL UNIT	ALLOWANCE (TA)	Z	S	TRIP SETPOINT	ALLOWABLE VALUE#
8. Engineering Safety Features Actuation System Interlocks					
a. Pressurizer Pressure	N.A.		N.A. N.A.	Nominal 2000 psig	<2018 psig
b. T _{avg} --Low	4.0	2.1	2.0 1.0	Nominal 543°F	>542.5 °F
9. Control Room Ventilation Isolation					
a. Automatic Actuation Logic and Actuation Relays	N.A.		N.A. N.A.	N.A.	N.A.
b. Safety Injection	see item 1			See Item 1. above for all Safety Injection Trip Setpoints and Allowable Values.	
c. Containment Radioactivity--High (1)	N.A.		N.A. N.A.	Particulate (R-11) <6.1 x 10 ⁵ CPM Gaseous (R-12) See (2)	Particulate (R-11) <6.8 x 10 ⁵ CPM Gaseous (R-12) See (2)
d. Containment Isolation Manual Phase A or Manual Phase B	N.A.		N.A. N.A.	N.A.	N.A.
e. Air Intake Radiation Level	N.A.		N.A. N.A.	≤ 2 mR/hr	≤ 2.83 mR/hr

TABLE NOTATIONS

(1) Either the particulate or gaseous channel in the OPERABLE status will satisfy this LCO.

POWER DISTRIBUTION LIMITS

BASES

3/4.2.4 QUADRANT POWER TILT RATIO

The QUADRANT POWER TILT RATIO limit assures that the radial power distribution satisfies the design values used in the power capability analysis. Radial power distribution measurements are made during STARTUP testing and periodically during power operation.

The limit of 1.02, at which corrective action is required, provides DNB and linear heat generation rate protection with x-y plane power tilts. A limit of 1.02 was selected to provide an allowance for the uncertainty associated with the indicated power tilt.

The 2-hour time allowance for operation with a tilt condition greater than 1.02 but less than 1.09 is provided to allow identification and correction of a dropped or misaligned control rod. In the event such action does not correct the tilt, the margin for uncertainty on $F_Q(Z)$ is reinstated by reducing the maximum allowed power by 3% for each percent of tilt in excess of 1.


For purposes of monitoring QUADRANT POWER TILT RATIO when one excore detector is inoperable, the movable incore detectors or incore thermocouple map are used to confirm that the normalized symmetric power distribution is consistent with the QUADRANT POWER TILT RATIO. The incore detector monitoring is done with a full incore flux map or two sets of four symmetric thimbles. The two sets of four symmetric thimbles is a unique set of eight detector locations. These locations are C-8, E-5, E-11, H-3, H-13, L-5, L-11, N-8.

3/4.2.5 DNB PARAMETERS

The limits on the DNB-related parameters assure that each of the parameters are maintained within the normal steady-state envelope of operation assumed in the transient and accident analyses. The limits are consistent with the initial FSAR assumptions and have been analytically demonstrated adequate to maintain a minimum DNBR above the applicable design limits throughout each analyzed transient. The indicated T_{avg} value of 576.6°F and the indicated pressurizer pressure value of 2209 psig correspond to analytical limits of 578.2°F and 2185 psig respectively, with allowance for measurement uncertainty.

The indicated RCS flow value of 277,900 gpm corresponds to an analytical limit of 268,500 gpm which is assumed to have a 3.5% measurement uncertainty. The above measurement uncertainty estimates assume that these instrument channel outputs are averaged to minimize the uncertainty.

The 12-hour periodic surveillance of these parameters through instrument readout is sufficient to ensure that the parameters are restored within their limits following load changes and other expected transient operation.



INSERT (B)

Reactor Coolant System T_{avg} and Pressurizer Pressure shall be verified to be within their limits at least once per 12 hours.

- 4.2.5.2 RCS flow rate shall be monitored for degradation at least once per 12 hours.

INSERT (C)

After each fuel loading, and at least once per 18 months, the RCS flow rate shall be determined by precision heat balance after exceeding 90% RATED THERMAL POWER. The measurement instrumentation shall be calibrated within 90 days prior to the performance of the calorimetric flow measurement. The provisions of 4.0.4 are not applicable for performing the precision heat balance flow measurement.

INSERT (D)

The 18-month periodic measurement of the RCS total flow rate is adequate to ensure that the DNB-related flow assumption is met and to ensure correlation of the flow indication channels with measured flow. Six month drift effects have been included for feedwater temperature, feedwater flow, steam pressure, and the pressurizer pressure inputs. The flow measurement is performed within ninety days of completing the cross-calibration of the hot surveillance on a 12-hour basis will provide sufficient verification that flow degradation has not occurred. A change in indicated percent flow which is greater than the instrument channel inaccuracies and parallax errors is an appropriate indication on RCS flow degradation.

ATTACHMENT 4

PROPRIETARY WCAP 13719, REV. 1

WESTINGHOUSE REVISED THERMAL DESIGN PROCEDURE
INSTRUMENT UNCERTAINTY METHODOLOGY

and

NON-PROPRIETARY WCAP 13718, REV. 1

WESTINGHOUSE REVISED THERMAL DESIGN PROCEDURE
INSTRUMENT UNCERTAINTY METHODOLOGY

Westinghouse Non-Proprietary Class 3

Westinghouse Energy Systems

