ATTACHMENT 4

PROPOSED TECHNICAL SPECIFICATION AMENDMENTS FOR CATAWBA

POWER DISTRIBUTION LIMITS

3/4.2.5 DNB PARAMETERS

LIMITING CONDITION FOR OPERATION

2. Within 24 hours of initially being within the region of prohibited operation specified on Figure 3.2-1, verify that the combination of THERMAL POWER and Reactor Coolant System total flow rate are restored to within the regions of restricted or permissible operation, or reduce THERMAL POWER to less than 5% of RATED THERMAL POWER within the next 2 hours.

SURVEILLANCE REQUIREMENTS

- 4.2.5.1 Each of the parameters of Table 3.2-1 shall be verified to be within their limits at least once per 12 hours.
- 4.2.5.2 The Reactor Coolant System total flow rate indicators shall be subjected to a CHANNEL CALIBRATION at least once per 18 months. The measurement-instrumentation shall be calibrated within 7 days prior to the performance of the flow measurement.
- 4.2.5.3 The Reactor Coolant System total flow rate shall be determined by measurement at least once per 18 months.