

2-51

Approvals
Richard A. Luffin
Date
2-27-89

Vogtle Electric Generating Plant
NUCLEAR OPERATIONS



Georgia Power

Procedure No.
24614-1
Revision No.
12
Page No.
1 of 74

FOR INFORMATION ONLY

SAFETY FEATURES SEQUENCER

TRAIN B

ANALOG CHANNEL

OPERATIONAL TEST

AND

CHANNEL CALIBRATION

9202190622 920116
PDR ADOCK 05000424
S PDR

TABLE OF CONTENTS

1.0	<u>PURPOSE</u>
2.0	<u>PRECAUTIONS AND LIMITATIONS</u>
3.0	<u>PREREQUISITES OR INITIAL CONDITIONS</u>
4.0	<u>MAIN BODY</u>
4.1	REMOVE FROM SERVICE
4.2	CHANNEL CALIBRATION
4.2.1	Analog Channel Operational Test
4.2.2	Channel Status Check (As Found)
4.2.3	Analog Isolator 1 Calibration
4.2.4	AC Transmitter 1 Calibration
4.2.5	Analog Isolator 2 Calibration
4.2.6	AC Transmitter 2 Calibration
4.2.7	Analog Isolator 3 Calibration
4.2.8	AC Transmitter 3 Calibration
4.2.9	Analog Isolator 4 Calibration
4.2.10	AC Transmitter 4 Calibration
4.2.11	A3-1 Bistable Module Calibration
4.2.12	A3-2 Bistable Module Calibration
4.2.13	A3-3 Bistable Module Calibration
4.2.14	A3-5 Bistable Module Calibration
4.2.15	A3-6 Bistable Module Calibration
4.2.16	A3-7 Bistable Module Calibration
4.2.17	A3-9 Bistable Module Calibration

VEGP

24614-1

12

3 of 74

4.2.18 A3-10 Bistable Module Calibration

4.2.19 A3-11 Bistable Module Calibration

4.2.20 A3-13 Bistable Module Calibration

4.2.21 A3-14 Bistable Module Calibration

4.2.22 A3-15 Bistable Module Calibration

4.2.23 Channel Status Check (As Left)

4.3 RESTORE TO SERVICE

5.0 ACCEPTANCE CRITERIA

6.0 REFERENCES

VEGP

24614-1

12

4 of 74

1.0 PURPOSE

1.1 The purpose of this procedure is to provide instructions for Analog Channel Operational Test and Channel Calibration of Safety Features Sequencer Train B.

1.2 Performance of this procedure satisfies the Safety Features Sequencer Train B Analog Channel Operational Test and/or Channel Calibration Surveillance Requirement of Technical Specification 4.3.2.1, Table 4.3-2, functional Unit 6d, 8a and 8b.

1.3 This procedure shall be performed at a minimum test interval of 18 months for Channel Calibration and 31 days for Analog Channel Operational Test.

1.4 SCOPE

1.4.1 When this procedure is performed for scheduled Analog Channel Operational Test, the following sections shall be used: 1.0, 2.0, 3.0, 5.0 and subsections 4.1, 4.2.1 and 4.3.

1.4.2 When this procedure is performed for scheduled Channel Calibration, the following sections shall be used: 1.0, 2.0, 3.0, 5.0 and subsections 4.1, 4.2.2 thru 4.2.23 and 4.3.

1.4.3 When this procedure is performed for unscheduled maintenance, the following sections shall be used: 1.0, 2.0, 3.0, 5.0, and appropriate subsections of 4.0.

2.0 PRECAUTIONS AND LIMITATIONS

2.1 All steps in this procedure are to be performed in sequence except as noted. []

2.2 Performance of procedure step, as identified by a double asterisk (*/*), shall be initialed on "Checklist" except when recording data on applicable Data Sheet. []

2.3 The instrument may be located in a radiation area, service a contaminated process fluid, or be contaminated. If so, follow instructions on "Radiation Work Permit". []

- 2.4 For Safety-Related systems, an Independent Restoration Verification shall be performed, after completion of Test/Calibration, and initialed in "Restoration Verification" section of "Checklist". []
- 2.5 Any calculations necessary for the performance of this procedure shall be shown on "Calculation Sheet". []
- 2.6 Ensure that each lead (wire) to be lifted is marked with a completed and installed jumper and lifted wire tag. Instead of "Control No.", the "Procedure No." should be identified on the tag. []
- 2.7 If this procedure is completed and temporary jumper(s) must remain installed and/or lifted wire(s) cannot be reconnected, a Jumper and Lifted Wire Clearance must be obtained per Procedure 00306-C, "Temporary Jumper And Lifted Wire Control". []
- 2.8 This procedure may be performed in any plant operational mode. []
- 2.9 If, during performance of this procedure, any of the following occur, immediately notify I&C Foreman:
 - 2.9.1 Any personnel error, procedure inadequacy, or malfunction is identified which could prevent fulfillment of "Acceptance Criteria". []
 - 2.9.2 Any test exceeds specified limits. []
- 3.0 PREREQUISITES OR INITIAL CONDITIONS
- 3.1 */* Notify Shift Supervisor, or designee, of work to be performed and obtain signature authorization. []
- 3.2 */* Notify Reactor Operator (RO) the following may be erratic or inoperable during performance of this procedure and obtain RO signature. []
 - 3.2.1 Sequencer Train B []
 - 3.2.2 Annunciator 37A01 "4160V SWGR 1BA03 TROUBLE" []
 - 3.2.3 Annunciator 37A04 "SEQ B TROUBLE" []
 - 3.2.4 Annunciator 37B03 "SEQ B PNL DOORS OPEN" []
 - 3.2.5 Annunciator 37B04 "SEQ B SAFETY EQUIP FAILED TO START" []

VEGP

24614-1

12

6 of 74

- 3.2.6 Annunciator 37C04 "RAT FDR BRKR TRN B FAILED TO OPEN" []
- 3.2.7 Annunciator 37D04 "SEQ B IN MANUAL TEST" []
- 3.3 TEST EQUIPMENT REQUIRED
- 3.3.1 Four (4) Fluke Model 8050A Digital Multimeters (DMM) or equivalent []
- 3.3.2 Transducer Calibrator Model 6444 or equivalent []
- 3.3.3 HP 5315A Frequency Counter or equivalent. []
- 3.3.4 Tektronix 2235 Ocilloscope or equivalent. []
- 3.4 Request RO to ensure the following alarm indications ILLUMINATE by performance of a lamp test:
- a. Annunciator 36A01 - "4160 SWGR 1AA02 TROUBLE" []
 - b. Annunciator 36A04 - "SEQ A TROUBLE" []
 - c. Annunciator 36B03 - "SEQ A PNL DOORS OPEN" []
 - d. Annunciator 36B04 - "SEQ A SAFETY EQUIP FAILED TO START" []
 - e. Annunciator 36C04 - "RAT FDR BRKR TRN A FAILED TO OPEN" []
 - f. Annunciator 36D04 - "SEQ A IN MANUAL TEST" []
 - g. Annunciator 37A04 - "SEQ B TROUBLE" []
- 3.5 Verify all Prerequisites or Initial Conditions are met. []
- */*
- 4.0 MAIN BODY
- 4.1 REMOVE FROM SERVICE
- 4.1.1 Verify that annunciators listed below are EXTINGUISHED. If an annunciator is ILLUMINATED notify I&C Foreman.
- */*

NOTE

When in modes 5 and 6, the annunciators listed below may be ILLUMINATED.

VEGP

24614-1

12

7 of 74

- a. 36A01 - "4160 SWGR 1AA02 TROUBLE" []
- b. 36A04 - "SEQ A TROUBLE" []
- c. 36B03 - "SEQ A PNL DOORS OPEN" []
- d. 36B04 - "SEQ A SAFETY EQUIP FAILED TO START" []
- e. 36C04 - "RAT FDR BRKR TRN A FAILED TO OPEN" []
- f. 36D04 - "SEQ A IN MANUAL TEST" []

4.2 CHANNEL CALIBRATION
(Commitments 000732, 000734 and 007950)

NOTE

Refer to Figure 1 and 2
for test connection points.

4.2.1 Analog Channel Operational Test
(Commitments 000728, 000733 and 000735)

4.2.1.1 Verify the following lamps ILLUMINATE when "Lamp Test"
toggle switch on panel A3 is depressed. (refer to
Figure 1)

- a. "SI Signal" []
- b. "U/V Signal" []
- c. "Undervoltage" []
- d. "Seq Logic Failure" []

4.2.1.2 Verify the following lamps are EXTINGUISHED:

- a. "SI Signal" []
- b. "U/V Signal" []
- c. "Undervoltage" []
- d. "Seq Logic Failure" []

4.2.1.3 Connect a DMM to A-1, TB1, terminals 1(+) and 2(-). []

4.2.1.4 Position and hold panel A1 "Operate/Test" switch in
"Test" position. (refer to Figure 1) []

VEGP

24614-1

12

8 of 74

NOTE

While adjusting the "Cal Adjust" pot the "Audible Alarm" will sound, the "Under Voltage Alarm" and "Seq. Logic Failure" bistables will ILLUMINATE on panel A3. The "Audible Alarm" can be silenced by pressing the ILLUMINATED bistable "Pushbutton".

- 4.2.1.5 */* Adjust "Cal Adjust" pot on A1 to the point at which DS1 on A3-1 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". (refer to Figure 2) []
- 4.2.1.6 */* Adjust "Cal Adjust" pot on A1 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.7 */* Adjust "Cal Adjust" pot on A1 to the point DS1 on A3-2 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.8 */* Adjust "Cal Adjust" pot on A1 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.9 */* Adjust "Cal Adjust" pot on A1 to point at which DS1 on A3-3 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.10 */* Adjust "Cal Adjust" on A1 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.11 Release A1 "Operate/Test" switch. []
- 4.2.1.12 */* Verify annunciator 37A04 "SEQ B TROUBLE" is ILLUMINATED. []

NOTE

Each bistable can be reset by depressing its ILLUMINATED pushbutton. When resetting bistables toggle switch "AT1 Reset" on card A5-16 must be depressed before "Seq. Logic Failure" bistable pushbutton can be reset.

- 4.2.1.13 */* Reset all bistables. []
- 4.2.1.14 Connect a DMM to A-2, TB1, terminals 1(+) and 2(-). []
- 4.2.1.15 Position and hold A2 "Operate/Test" switch in "Test" position. []
- 4.2.1.16 */* Adjust "Cal Adjust" pot on A2 to point at which DS1 on A3-5 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.17 */* Adjust "Cal Adjust" on A2 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.18 */* Adjust "Cal Adjust" pot on A2 to point at which DS1 on A3-6 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.19 */* Adjust "Cal Adjust" on A2 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.20 */* Adjust "Cal Adjust" pot on A2 to point at which DS1 on A3-7 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.21 */* Adjust "Cal Adjust" on A2 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.22 Release A2 "Operate/Test" switch. []
- 4.2.1.23 */* Reset all bistables. []
- 4.2.1.24 Connect a DMM to A-4, TB1, terminals 1(+) and 2(-). []
- 4.2.1.25 Position and hold A4 "Operate/Test" switch in "Test" position. []
- 4.2.1.26 */* Adjust "Cal Adjust" pot on A4 to point at which DS1 on A3-9 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []

PROCEDURE NO	REVISION	PAGE NO
VEGP 24614-1	12	10 of 74

- 4.2.1.27 */* Adjust "Cal Adjust" on A4 and record input reading at point bistable can be resec in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.28 */* Adjust "Cal Adjust" pot on A4 to point at which DS1 on A3-10 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.29 */* Adjust "Cal Adjust" on A4 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.30 */* Adjust "Cal Adjust" pot on A4 to point at which DS1 on A3-11 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.31 */* Adjust "Cal Adjust" on A4 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.32 Release A4 "Operate/Test" switch. []
- 4.2.1.33 */* Reset all bistables. []
- 4.2.1.34 Connect a DMM to A-5, TB1, terminals 1(+) and 2(-). []
- 4.2.1.35 Position and hold A5 "Operate/Test" switch in "Test" position. []
- 4.2.1.36 */* Adjust "Cal Adjust" pot on A5 to point at which DS1 on A3-13 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.37 */* Adjust "Cal Adjust" on A5 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.38 */* Adjust "Cal Adjust" pot on A5 to point at which DS1 on A3-14 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.39 */* Adjust "Cal Adjust" on A5 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []

VEGP

24614-1

12

11 of 74

- 4.2.1.40 */* Adjust "Cal Adjust" pot on A5 to point at which DS1 on A3-15 ILLUMINATES and record input reading in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.41 */* Adjust "Cal Adjust" on A5 and record input reading at point bistable can be reset in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.42 Release A5 "Operate/Test" switch. []
- 4.2.1.43 */* Reset all bistables. []
- 4.2.1.44 Connect frequency counter to pins 52(+) and 81(-) at rear of A4-7 card (6N368-1). []
- 4.2.1.45 */* Record clock output value in "As Found" section of "Analog Channel Operational Test Data Sheet 1". []
- 4.2.1.46 */* If As Found readings are within limits specified on "Analog Channel Operational Test Data Sheet 1" and more accurate readings are not desired, record readings in "As Left" section of "Analog Channel Operational Test Data Sheet 1" and proceed to subsection 4.3. []
- 4.2.1.47 If As Found readings are not within limits specified on "Analog Channel Operational Test Data Sheet 1" or more accurate values are desired, proceed as directed below:
- a. If Technical Specifications Allowable Limits have been exceeded notify OSOS and I&C Foreman, then proceed as directed. []
 - b. If Calibration Limits have been exceeded or more accurate values are desired, proceed to appropriate subsections. []
- 4.2.1.48 */* QC Hold Point
- Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.1.49 When individual calibration(s) is(are) complete, repeat subsection 4.2.1 "Analog Channel Operational Test" to obtain As Left readings. []
- 4.2.2 Channel Status Check (As Found)
- 4.2.2.1 Connect DMM to A-1, TB1, terminals 1 (+) and 2(-). []

VEGP

24614-1

12

12 of 74

- 4.2.2.2 Position and hold A1 "Operate/Test" switch in "Test" position. []

NOTE

While adjusting the "Cal Adjust" pot the "Audible Alarm" will sound, the "Under Voltage Alarm" and "Seq. Logic Failure" bistables will ILLUMINATE on panel A3. The "Audible Alarm" can be silenced by pressing the ILLUMINATED bistable "Pushbutton".

- 4.2.2.3 Adjust "Cal Adjust" pot on A1 to the point at which DS1 on A3-1 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". (refer to Figure 1 & 2) []

- 4.2.2.4 Adjust "Cal Adjust" on A1 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []

- 4.2.2.5 Adjust "Cal Adjust" pot on A1 to the point at which DS1 on A3-2 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []

- 4.2.2.6 Adjust "Cal Adjust" on A1 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []

- 4.2.2.7 Adjust "Cal Adjust" pot on A1 to the point at which DS1 on A3-3 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []

- 4.2.2.8 Adjust "Cal Adjust" on A1 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []

- 4.2.2.9 Release A1 "Operate/Test" switch. []

NOTE

Each bistable can be reset by depressing its ILLUMINATED pushbutton. When resetting bistables toggle switch "A11 Reset" on card A5-16 must be depressed before "Seq. Logic Failure" bistable pushbutton can be reset.

VEGP

24614-1

12

13 of 74

- 4.2.2.10 Verify annunciator 37A04 "SEQ B TROUBLE" is ILLUMINATED. []
/
- 4.2.2.11 Reset all bistables. []
/
- 4.2.2.12 Connect a DMM to A-2, TB1, terminals 1 (+) and 2 (-). []
- 4.2.2.13 Position and hold A2 "Operate/Test" switch in "Test" position. []
- 4.2.2.14 Adjust "Cal Adjust" pot on A2 to the point at which DS1 on A3-5 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
/
- 4.2.2.15 Adjust "Cal Adjust" on A2 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
/
- 4.2.2.16 Adjust "Cal Adjust" pot on A2 to the point at which DS1 on A3-6 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
/
- 4.2.2.17 Adjust "Cal Adjust" on A2 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
/
- 4.2.2.18 Adjust "Cal Adjust" pot on A2 to the point at which DS1 on A3-7 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
/
- 4.2.2.19 Adjust "Cal Adjust" on A2 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
/
- 4.2.2.20 Release A2 "Operate/Test" switch. []
- 4.2.2.21 Reset all bistables. []
/
- 4.2.2.22 Connect a DMM to A-4, TB1, terminals 1 (+) and 2 (-). []
- 4.2.2.23 Position and hold A4 "Operate/Test" switch in "Test" position. []
- 4.2.2.24 Adjust "Cal Adjust" pot on A4 to the point at which DS1 on A3-9 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
/
- 4.2.2.25 Adjust "Cal Adjust" on A4 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
/

VEGP

24614-1

12

.4 of 74

- 4.2.2.26 */* Adjust "Cal Adjust" pot on A4 to the point at which DS1 on A3-10 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
- 4.2.2.27 */* Adjust "Cal Adjust" on A4 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
- 4.2.2.28 */* Adjust "Cal Adjust" pot on A4 to the point at which DS1 on A3-11 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
- 4.2.2.29 */* Adjust "Cal Adjust" on A4 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
- 4.2.2.30 Release A4 "Operate/Test" switch. []
- 4.2.2.31 */* Reset all bistables. []
- 4.2.2.32 Connect a DMM to A-5, TB1, terminals 1 (+) and 2 (-). []
- 4.2.2.33 Position and hold A5 "Operate/Test" switch in "Test" position. []
- 4.2.2.34 */* Adjust "Cal Adjust" pot on A5 to the point at which DS1 on A3-13 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
- 4.2.2.35 */* Adjust "Cal Adjust" on A5 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
- 4.2.2.36 */* Adjust "Cal Adjust" pot on A5 to the point at which DS1 on A3-14 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
- 4.2.2.37 */* Adjust "Cal Adjust" on A5 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []
- 4.2.2.38 */* Adjust "Cal Adjust" pot on A5 to the point at which DS1 on A3-15 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 2". []
- 4.2.2.39 */* Adjust "Cal Adjust" on A5 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 2". []

PROCEDURE NO.	REVISION	PAGE NO
VEGP 24614-1	12	15 of 74
4.2.2.40	Release A5 "Operate/Test" switch.	[]
4.2.2.41	Reset all bistables.	[]
<u>*/*</u>		
4.2.2.42	Connect frequency counter to pins 52(+) and 81(-) at rear of A4-7 card (6N368-1).	[]
4.2.2.43	Record clock output value in "As Found" section of "Data Sheet 2".	[]
<u>*/*</u>		
4.2.3	Analog Isolator 1 Calibration Location: A1	
NOTE		
Refer to Figure 1.		
4.2.3.1	Open links AJ 4 and 5 in 1BA0300. (Independent Verification required)	[]
<u>*/*</u>		
4.2.3.2	Connect a DMM to the output of Analog Isolator terminals 8(+) and 9(-), and to input Analog Isolator terminals 12(+) and 11(-).	[]
4.2.3.3	Connect transducer calibrator to A-1, TB3, terminals 2 and 3.	[]
4.2.3.4	Adjust transducer calibrator to apply inputs listed and record output readings in "As Found" section of "Data Sheet 3".	[]
<u>*/*</u>		
4.2.3.5	If As Found readings are within limits specified on "Data Sheet 3", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 3" and proceed to appropriate subsection.	[]
<u>*/*</u>		
4.2.3.6	QC Hold Point	
<u>*/*</u>		
	Obtain QC authorization to proceed before continuing with procedure.	[]
4.2.3.7	If As Found readings are not within limits specified on "Data Sheet 3", or more accurate readings are desired, proceed as follows:	
	a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output	[]
	b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output.	[]
	c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed.	[]

PROCEDURE NO	REVISION	PAGE NO
VEGP 24614-1	12	16 of 74
4.2.3.8 <u>*/*</u>	Adjust transducer calibrator to apply inputs listed and record output readings in "As Left" section of "Data Sheet 3". []	
4.2.4	AC Transmitter 1 Calibration Location: A1	
NOTE		
Refer to Figure 1.		
4.2.4.1	Connect a DMM to the input of AC transmitter terminals 1 and 2. []	
4.2.4.2 <u>*/*</u>	Adjust transducer calibrator to apply inputs listed and record output readings in "As Found" section of "Data Sheet 4". []	
4.2.4.3 <u>*/*</u>	If As Found readings are within limits specified on "Data Sheet 4", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 4" and proceed to step 4.2.4.7. []	
4.2.4.4 <u>*/*</u>	QC Hold Point Obtain QC authorization to proceed before continuing with procedure. []	
4.2.4.5	If As Found readings are not within limits specified on "Data Sheet 4", or more accurate readings are desired, proceed as follows:	
	a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output. []	
	b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output. []	
	c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed. []	
4.2.4.6 <u>*/*</u>	Adjust transducer calibrator to apply inputs listed and record output readings in "As Left" section of "Data Sheet 4". []	
4.2.4.7	Remove all test equipment. []	
4.2.4.8	Close links AJ 4 and 5 in 1BA0300. []	
4.2.4.9 <u>*/*</u>	Reset all bistables. []	

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 24614-1	12	17 of 74
4.2.5	Analog Isolator 2 Calibration Location: A2	
NOTE		
Refer to Figure 1.		
4.2.5.1 <u>*/*</u>	Open links AJ 6 and 7 in 1BA0300. (Independent Verification required) []	
4.2.5.2	Connect a DMM to the output of Analog Isolator terminals 15(+) and 16(-), and to input of Analog Isolator terminals 12(+) and 11(-). []	
4.2.5.3	Connect transducer calibrator to A-2, TB3 terminals 2 and 3. []	
4.2.5.4 <u>*/*</u>	Adjust transducer calibrator to apply inputs listed and record output readings in "As Found" section of "Data Sheet 5". []	
4.2.5.5 <u>*/*</u>	If As Found readings are within limits specified on "Data Sheet 5", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 5" and proceed to appropriate subsection. []	
4.2.5.6 <u>*/*</u>	QC Hold Point Obtain QC authorization to proceed before continuing with procedure. []	
4.2.5.7	If As Found readings are not within limits specified on "Data Sheet 5", or more accurate readings are desired, proceed as follows:	
	a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output. []	
	b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output. []	
	c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed. []	
4.2.5.8 <u>*/*</u>	Adjust transducer calibrator to apply inputs listed and record output readings in "As Left" section of "Data Sheet 5". []	

4.2.6 AC Transmitter 2 Calibration
Location: A2

NOTE

Refer to Figure 1.

- 4.2.6.1 Connect a DMM to the input of AC transmitter terminals 1 and 2. []
- 4.2.6.2 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Found" section of "Data Sheet 6". []
- 4.2.6.3 */* If As Found readings are within limits specified on "Data Sheet 6", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 6" and proceed to step 4.2.6.7. []
- 4.2.6.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.6.5 If As Found readings are not within limits specified on "Data Sheet 6", or more accurate readings are desired, proceed as follows:
 - a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output. []
 - b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output. []
 - c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed. []
- 4.2.6.7 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Left" section of "Data Sheet 6". []
- 4.2.6.7 Remove all test equipment. []
- 4.2.6.8 Close links AJ 6 and 7 in 1BA0300. []
- 4.2.6.9 */* Reset all bistables. []

VEGP

24614-1

12

19 of 74

4.2.7 Analog Isolator 3 Calibration
Location: A4

NOTE

Refer to Figure 1.

- 4.2.7.1 */* Open links AJ 7 and 8 in 1BA0302. (Independent Verification required) []
- 4.2.7.2 Connect a DMM to the output of Analog Isolator terminals 8(+) and 9(-), and to the input of Analog Isolator terminals 12(+) and 11(-). []
- 4.2.7.3 Connect transducer calibrator to A-4, TB3 terminals 2 and 3. []
- 4.2.7.4 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Found" section of "Data Sheet 7". []
- 4.2.7.5 */* If As Found readings are within limits specified on "Data Sheet 7", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 7" and proceed to appropriate subsection. []
- 4.2.7.6 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.7.7 If As Found readings are not within limits specified on "Data Sheet 7", or more accurate readings are desired, proceed as follows:
- a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output. []
 - b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output. []
 - c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed. []
- 4.2.7.8 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Left" section of "Data Sheet 7". []

VEGP

24614-1

12

20 of 74

4.2.8 AC Transmitter 3 Calibration
Location: A4

NOTE

Refer to Figure 1.

- 4.2.8.1 Connect a DMM to the input of AC transmitter terminals 1 and 2. []
- 4.2.8.2 */* Adjust transducer calibrator to apply inputs listed and output record readings in "As Found" section of "Data Sheet 8". []
- 4.2.8.3 */* If As Found readings are within limits specified on "Data Sheet 8", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 8", and proceed to step 4.2.8.7. []
- 4.2.8.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.8.5 If As Found readings are not within limits specified on "Data Sheet 8", or more accurate readings are desired, proceed as follows:
- a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output. []
 - b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output. []
 - c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed. []
- 4.2.8.6 */* Adjust transducer calibrator to apply inputs listed and record output readings on "As Left" section of "Data Sheet 8". []
- 4.2.8.7 Remove all test equipment. []
- 4.2.8.8 Close links AJ 7 and 8 in 1BA0302. []
- 4.2.8.9 */* Reset all bistables. []

VEGP

24614-1

12

21 of 74

4.2.9 Analog Isolator 4 Calibration
Location: A5

NOTE

Refer to Figure 1.

- 4.2.9.1 */* Open links AJ 9 and 10 in 1BA0302. (Independent Verification required) []
- 4.2.9.2 Connect a DMM to the output of Analog Isolator terminals 15(+) and 16(-), and to input of Analog Isolator terminals 12(+) and 11(-). []
- 4.2.9.3 Connect transducer calibrator to A-5, TB3 terminals 2 and 3. []
- 4.2.9.4 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Found" section of "Data Sheet 9". []
- 4.2.9.5 */* If As Found readings are within limits specified on "Data Sheet 9", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 9" and proceed to appropriate subsection. []
- 4.2.9.6 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.9.7 If As Found readings are not within limits specified on "Data Sheet 9", or more accurate readings are desired, proceed as follows:
- a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output. []
 - b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output. []
 - c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed. []
- 4.2.9.8 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Left" section of "Data Sheet 9". []

VEGP

24614-1

12

22 of 74

4.2.10 AC Transmitter 4 Calibration
Location: A5

NOTE

Refer to Figure 1.

- 4.2.10.1 Connect a DMM to the input of AC transmitter terminals 1 and 2. []
- 4.2.10.2 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Found" section of "Data Sheet 10". []
- 4.2.10.3 */* If As Found readings are within limits specified on "Data Sheet 10", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 10" and proceed to step 4.2.10.7. []
- 4.2.10.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.10.5 If As Found readings are not within limits specified on "Data Sheet 10", or more accurate readings are desired, proceed as follows:
- a. Apply zero percent input and adjust "Zero" screw for 1.000V DC output. []
 - b. Apply 100 percent input and adjust "Span" screw for 5.000V DC output. []
 - c. Repeat "Zero" and "Span" adjustments until no further adjustments are needed. []
- 4.2.10.6 */* Adjust transducer calibrator to apply inputs listed and record output readings in "As Left" section of "Data Sheet 10". []
- 4.2.10.7 Remove all test equipment. []
- 4.2.10.8 Close links AJ 9 and 10 in 1BA0302. []
- 4.2.10.9 */* Reset all bistables. []

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 24614-1	12	23 of 74

- 4.2.11 A3-1 Bistable Module Calibration -
- 4.2.11.1 Connect a DMM to A-1, TB1, terminals 1(+) and 2(-). []
- 4.2.11.2 Position and hold A1 "Operate/Test" switch in "Test" position. []
- 4.2.11.3 */* Adjust "Cal Adjust" on A1, to the point at which DS1 on A3-1 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 11". []
- 4.2.11.4 */* Adjust "Cal Adjust" on A1 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 11". []
- 4.2.11.5 */* If As Found readings are within limits specified on "Data Sheet 11" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 11" and proceed to step 4.2.11.8. []
- 4.2.11.6 */* QC Hold Point
- Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.11.7 If As Found readings are not within limits specified on "Data Sheet 11", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point which DS1 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 11", record in "As Left" section of "Data Sheet 11" and proceed to step 4.2.11.7e. []
- d. */* If value is not within limits specified on "Data Sheet 11", repeat steps 4.2.11.7a and 4.2.11.7b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 11". []
- e. INCREASE input with "Cal Adjust" point at which bistable can be reset and trip the bistable []

VEGP

24614-1

12

24 of 74

- f. */* If value is within limits specified on "Data Sheet 11" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 11" and proceed to step 4.2.11.8. []
- g. */* If value is not within limits specified on "Data Sheet 11", adjust R44 and repeat step 4.2.11.7e and record final value obtained in "As Left" section of "Data Sheet 11". []
- 4.2.11.8 Connect DMM to A3-1, terminals J4(+) and J5(-). []
- 4.2.11.9 Adjust R33 to 0.500V DC under trip point voltage. []
- 4.2.11.10 Connect DMM to A3-1, terminals J3(+) and J5(-). []
- 4.2.11.11 Adjust R34 to 0.500V DC over trip point voltage. []
- 4.2.12 A3-2 Bistable Module Calibration
- 4.2.12.1 */* Adjust "Cal Adjust" on A1 to the point at which DS1 on A3-2 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 12". []
- 4.2.12.2 */* Adjust "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 12". []
- 4.2.12.3 */* If As Found readings are within limits specified on "Data Sheet 12" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 12" and proceed to step 4.2.12.6. []
- 4.2.12.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.12.5 If As Found readings are not within limits specified on "Data Sheet 12", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point which DS1 ILLUMINATES and reset bistable. []

- c. */* If value is within limits specified on "Data Sheet 12", record in "As Left" section of "Data Sheet 12" and proceed to step 4.2.12.5e. []
- d. */* If value is not within limits specified on "Data Sheet 12", repeat steps 4.2.12.5a and 4.2.12.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 12". []
- e. INCREASE input with "Cal Adjust", note point at which bistable can be reset and trip the bistable. []
- f. */* If value is within limits specified on "Data Sheet 12" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 12" and proceed to step 4.2.12.6. []
- g. */* If value is not within limits specified on "Data Sheet 12", adjust R44 and repeat step 4.2.12.5e and record final value obtained in "As Left" section of "Data Sheet 12". []
- 4.2.12.6 Connect DMM to A3-2, terminals J4(+) and J5(-). []
- 4.2.12.7 Adjust R33 to 0.500V DC below trip point voltage. []
- 4.2.12.8 Connect DMM to A3-2, terminals J3(+) and J5(-). []
- 4.2.12.9 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.13 A3-3 Bistable Module Calibration
- 4.2.13.1 */* Adjust "Cal Adjust" on A1 to the point at which DS1 on A3-3 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 13". []
- 4.2.13.2 */* Adjust "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 13". []
- 4.2.13.3 */* If As Found readings are within limits specified on "Data Sheet 13" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 13" and proceed to step 4.2.13.6. []
- 4.2.13.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []

4.2.13.5 If As Found readings are not within limits specified on "Data Sheet 13", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
 - b. Adjust "Cal Adjust", note point which DS1 ILLUMINATES and reset bistable. []
 - c. */* If value is within limits specified on "Data Sheet 13", record in "As Left" section of "Data Sheet 13" and proceed to step 4.2.13.5e. []
 - d. */* If value is not within limits specified on "Data Sheet 13", repeat steps 4.2.13.5a and 4.2.13.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 13". []
 - e. INCREASE "Cal Adjust", note point at which bistable can be reset and trip the bistable. []
 - f. */* If value is within limits specified on "Data Sheet 13" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 13" and proceed to step 4.2.13.6. []
 - g. */* If value is not within limits specified on "Data Sheet 13", adjust R44 and repeat step 4.2.13.5e and record final value obtained in "As Left" section of "Data Sheet 13". []
- 4.2.13.6 Connect DMM to A3-3, terminals J4(+) and J5(-). []
- 4.2.13.7 Adjust R33 to 0.500V DC below trip point voltage. []
- 4.2.13.8 Connect DMM to A3-3, terminals J3(+) and J5(-). []
- 4.2.13.9 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.13.10 */* Release A1 "Operate/Test" switch and reset all bistables. []
- 4.2.14 A3-5 Bistable Module Calibration
- 4.2.14.1 Connect a DMM to A-2, TB1, terminals 1(+) and 2(-). []

VEGP

24614-1

12

27 of 74

- 4.2.14.2 Position and hold A2 "Operate/Test" switch in "Test" position. []
- 4.2.14.3 */* Adjust "Cal Adjust" on A2 to the point at which DS1 on A3-5 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 14". []
- 4.2.14.4 */* INCREASE "Cal Adjust" on A2 and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 14". []
- 4.2.14.5 */* If As Found readings are within limits specified on "Data Sheet 14" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 14" and proceed to step 4.2.14.8. []
- 4.2.14.6 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.14.7 If As Found readings are not within limits specified on "Data Sheet 14", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 14", record in "As Left" section of "Data Sheet 14" and proceed to step 4.2.14.7e. []
- d. */* If value is not within limits specified on "Data Sheet 14", repeat steps 4.2.14.7a and 4.2.14.7b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 14". []
- e. INCREASE input with "Cal Adjust", note point bistable can be reset and trip the bistable []
- f. */* If value is within limits specified on "Data Sheet 14" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 14" and proceed to step 4.2.14.8. []

- g. */* If value is not within limits specified on "Data Sheet 14", adjust R44 and repeat step 4.2.14.7e and record final value obtained in "As Left" section of "Data Sheet 14". []
- 4.2.14.8 Connect DMM to A3-5, terminals J4(+) and J5(-). []
- 4.2.14.9 Adjust R33 to 0.500V DC under trip point voltage. []
- 4.2.14.10 Connect DMM to A3-5, terminals J3(+) and J5(-). []
- 4.2.14.11 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.15 A3-6 Bistable Module Calibration
- 4.2.15.1 */* Adjust "Cal Adjust" on A2 to the point at which DS1 on A3-6 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 15". []
- 4.2.15.2 */* INCREASE "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 15". []
- 4.2.15.3 */* If As Found readings are within limits specified on "Data Sheet 15" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 15" and proceed to step 4.2.15.6. []
- 4.2.15.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.15.5 If As Found readings are not within limits specified on "Data Sheet 15", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point []
- b. Adjust "Cal Adjust", note point at which DS2 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 15", record in "As Left" section of "Data Sheet 15" and proceed to step 4.2.15.5e. []

PROCEDURE NO.	REVISION	PAGE NO.
VEGP	24614-1	12 29 of 74
d. <u>*/*</u>	If value is not within limits specified on "Data Sheet 15", repeat steps 4.2.15.5a and 4.2.15.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 15".	[]
e.	INCREASE input with "Cal Adjust", note point bistable can be reset and trip the bistable.	[]
f. <u>*/*</u>	If value is within limits specified on "Data Sheet 15" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 15" and proceed to step 4.2.15.6.	[]
g. <u>*/*</u>	If value is not within limits specified on "Data Sheet 15", adjust R44 and repeat step 4.2.15.5e and record final value obtained in "As Left" section of "Data Sheet 15".	[]
4.2.15.6	Connect DMM to A3-6, terminals J4(+) and J5(-).	[]
4.2.15.7	Adjust R33 to 0.500V DC below trip point voltage.	[]
4.2.15.8	Connect DMM to A3-6, terminals J3(+) and J5(-).	[]
4.2.15.9	Adjust R34 to 0.500V DC above trip point voltage.	[]
4.2.16	A3-7 Bistable Module Calibration	
4.2.16.1 <u>*/*</u>	Adjust "Cal Adjust" on A2 to the point at which DS1 on A3-7 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 16".	[]
4.2.16.2 <u>*/*</u>	INCREASE "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 16".	[]
4.2.16.3 <u>*/*</u>	If As Found readings are within limits specified on "Data Sheet 16", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 16" and proceed to step 4.2.16.6.	[]
4.2.16.4 <u>*/*</u>	QC Hold Point Obtain QC authorization to proceed before continuing with procedure.	[]
4.2.16.5	If As Found readings are not within limits specified on "Data Sheet 16", or more accurate readings are desired, proceed as follows:	

VEGP

24614-1

12

30 of 74

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 16", record in "As Left" section of "Data Sheet 16" and proceed to step 4.2.16.5e. []
- d. */* If value is not within limits specified on "Data Sheet 16", repeat steps 4.2.16.5a and 4.2.16.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 16". []
- e. INCREASE input with "Cal Adjust", note point at which bistable can be reset and trip the bistable. []
- f. */* If value is within limits specified on "Data Sheet 16" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 16" and proceed to step 4.2.16.6. []
- g. */* If value is not within limits specified on "Data Sheet 16" adjust R44 and repeat step 4.2.16.5e and record final value obtained in "As Left" section of "Data Sheet 16". []
- 4.2.16.6 Connect DMM to A3-7, terminals J4(+) and J5(-). []
- 4.2.16.7 Adjust R33 to 0.500V DC below trip point voltage. []
- 4.2.16.8 Connect DMM to A3-7, terminals J3(+) and J5(-). []
- 4.2.16.9 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.16.10 */* Release A2 "Operate/Test" switch and reset all bistables. []
- 4.2.17 A3-9 Bistable Module Calibration
- 4.2.17.1 Connect a DMM and to A-4, TB1, terminals 1(+) and 2(-). []
- 4.2.17.2 Position and hold A4 "Operate/Test" switch in "Test" position. []

VEGP

24614-1

12

31 of 74

- 4.2.17.3 */* Adjust "Cal Adjust" on A4 to the point at which DS1 on A3-9 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 17". []
- 4.2.17.4 */* INCREASE input with "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 17". []
- 4.2.17.5 */* If As Found readings are within limits specified on "Data Sheet 17" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 17" and proceed to step 4.2.17.8. []
- 4.2.17.6 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.17.7 If As Found readings are not within limits specified on "Data Sheet 17", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 17", record in "As Left" section of "Data Sheet 17" and proceed to step 4.2.17.7e. []
- d. */* If value is not within limits specified on "Data Sheet 17", repeat steps 4.2.17.7a and 4.2.17.7b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 17". []
- e. INCREASE input with "Cal Adjust", point at which bistable can be reset and trip the bistable. []
- f. */* If value is within limits specified on "Data Sheet 17" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 17" and proceed to step 4.2.17.8. []
- g. */* If value is not within limits specified on "Data Sheet 17", adjust R44 and repeat step 4.2.17.7e and record final value obtained in "As Left" section of "Data Sheet 17". []

VEGP

24614-1

12

32 of 74

- 4.2.17.8 Connect DMM to A3-9, terminals J4(+) and J5(-). []
- 4.2.17.9 Adjust R33 to 0.500V DC below trip point voltage. []
- 4.2.17.10 Connect DMM to A3-9, terminals J3(+) and J5(-). []
- 4.2.17.11 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.18 A3-10 Bistable Module Calibration
- 4.2.18.1 */* Adjust "Cal Adjust" on A4 to the point at which DS1 on A3-10 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 18". []
- 4.2.18.2 */* INCREASE input with "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 18". []
- 4.2.18.3 */* If As Found readings are within limits specified on "Data Sheet 18", and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 18" and proceed to step 4.2.18.6. []
- 4.2.18.4 */* QC Hold Point
- Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.18.5 If As Found readings are not within limits specified on "Data Sheet 18", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 18", record in "As Left" section of "Data Sheet 18" and proceed to step 4.2.18.5e. []
- d. */* If value is not within limits specified on "Data Sheet 18", repeat steps 4.2.18.5a and 4.2.18.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 18". []

VEGP

24614-1

12

33 of 74

- e. INCREASE input with "Cal Adjust", note point at which bistable can be reset and trip the bistable. []
- f. */* If value is within limits specified on "Data Sheet 18" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 18" and proceed to step 4.2.18.6. []
- g. */* If value is not within limits specified on "Data Sheet 18", adjust R44 and repeat step 4.2.18.5e and record final value obtained in "As Left" section of "Data Sheet 18". []
- 4.2.18.6 Connect DMM to A3-10, terminals, J4(+) and J5(-). []
- 4.2.18.7 Adjust R33 to 0.500V DC below trip point voltage. []
- 4.2.18.8 Connect DMM to A3-10, terminals J3(+) and J5(-). []
- 4.2.18.9 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.19 A3-11 Bistable Module Calibration
- 4.2.19.1 */* Adjust "Cal Adjust" on A4 to the point at which DS1 on A3-11 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 19". []
- 4.2.19.2 */* INCREASE input with "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 19". []
- 4.2.19.3 */* If As Found readings are within limits specified on "Data Sheet 19" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 19" and proceed to step 4.2.19.6. []
- 4.2.19.4 */* QC Hold Point
- Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.19.5 If As Found readings are not within limits specified on "Data Sheet 19", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []

VEGP

24614-1

12

34 of 74

- c. */* If value is within limits specified on "Data Sheet 19", record in "As Left" section of "Data Sheet 19" and proceed to step 4.2.19.5e. []
- d. */* If value is not within limits specified on "Data Sheet 19", repeat steps 4.2.19.5a and 4.2.19.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 19". []
- e. INCREASE input with "Cal Adjust", note point at which bistable can be reset and trip the bistable. []
- f. */* If value is within limits specified on "Data Sheet 19" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 19" and proceed to step 4.2.19.6. []
- g. */* If value is not within limits specified on "Data Sheet 19", adjust R44 and repeat step 4.2.19.5e and record final value obtained in "As Left" section of "Data Sheet 19". []
- 4.2.19.6 Connect DMM to A3-11, terminals J4(+) and J5(-). []
- 4.2.19.7 Adjust R33 to 0.500V DC below trip point voltage. []
- 4.2.19.8 Connect DMM to A3-11, terminals J3(+) and J5(-). []
- 4.2.19.9 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.19.10 */* Release A4 "Operate/Test" switch and reset all bistables. []
- 4.2.20 A3-13 Bistable Module Calibration
- 4.2.20.1 Connect a DMM to A-5, TB1, terminals 1(+) and 2(-). []
- 4.2.20.2 Position and hold A5 "Operate/Test" switch in "Test" position. []
- 4.2.20.3 */* Adjust "Cal Adjust" on A5 to the point at which DS1 on A3-13 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 20". []
- 4.2.20.4 */* INCREASE input with "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 20". []
- 4.2.20.5 */* If As Found readings are within limits specified on "Data Sheet 20" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 20" and proceed to step 4.2.20.8. []

4.2.20.6 QC Hold Point

/

Obtain QC authorization to proceed before continuing with procedure. []

4.2.20.7 If As Found readings are not within limits specified on "Data Sheet 20", or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

a. INCREASE or DECREASE R40 for trip point. []

b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []

/ c. If value is within limits specified on "Data Sheet 20", record in "As Left" section of "Data Sheet 20" and proceed to step 4.2.20.7e. []

/ d. If value is not within limits specified on "Data Sheet 20", repeat steps 4.2.20.7a and 4.2.20.7b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 20". []

e. INCREASE input with "Cal Adjust", note point at which bistable can be reset and trip the bistable. []

/ f. If value is within limits specified on "Data Sheet 20" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 20" and proceed to step 4.2.20.8. []

/ g. If value is not within limits specified on "Data Sheet 20", adjust R44 and repeat step 4.2.20.7e and record final value obtained in "As Left" section of "Data Sheet 20". []

4.2.20.8 Connect DMM to A3-13, terminals J4(+) and J5(-). []

4.2.20.9 Adjust R33 to 0.500V DC below trip point voltage. []

4.2.20.10 Connect DMM to A3-13, terminals J3(+) and J5(-). []

4.2.20.11 Adjust R34 to 0.500V DC above trip point voltage. []

VEGP

24614-1

12

36 of 74

- 4.2.21 A3-14 Bistable Module Calibration -
- 4.2.21.1 */* Adjust "Cal Adjust" on A5 to the point at which DS1 on A3-14 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 21". []
- 4.2.21.2 */* INCREASE input with "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 21". []
- 4.2.21.3 */* If As Found readings are within limits specified on "Data Sheet 21" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 21" and proceed to step 4.2.21.6. []
- 4.2.21.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.21.5 If As Found readings are not within limits specified on "Data Sheet 21", or more accurate readings are desired proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 21", record in "As Left" section of "Data Sheet 21" and proceed to step 4.2.21.5e. []
- d. */* If value is not within limits specified on "Data Sheet 21", repeat steps 4.2.21.5a and 4.2.21.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 21". []
- e. INCREASE input with "Cal Adjust", note point at which bistable can be reset and trip the bistable. []

VEGP

24614-1

12

37 of 74

- f. */* If value is within limits specified on "Data Sheet 21" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 21" and proceed to step 4.2.21.6. []
- g. */* If value is not within limits specified on "Data Sheet 21", adjust R44 and repeat step 4.2.21.5e and record final value obtained in "As Left" section of "Data Sheet 21". []
- 4.2.21.6 Connect DMM to A3-14, terminals J4(+) and J5(-). []
- 4.2.21.7 Adjust R33 to 0.500V DC below trip point voltage. []
- 4.2.21.8 Connect DMM to A3-14, terminals J3(+) and J5(-). []
- 4.2.21.9 Adjust R34 to 0.500V DC above trip point voltage. []
- 4.2.22 A3-15 Bistable Module Calibration
- 4.2.22.1 */* Adjust "Cal Adjust" on A5 to the point at which DS1 on A3-15 ILLUMINATES and record input reading in "As Found" section of "Data Sheet 22". []
- 4.2.22.2 */* INCREASE input with "Cal Adjust" and record input reading at point bistable can be reset in "As Found" section of "Data Sheet 22". []
- 4.2.22.3 */* If As Found readings are within limits specified on "Data Sheet 22" and more accurate readings are not desired, record readings in "As Left" section of "Data Sheet 22" and proceed to step 4.2.22.6. []
- 4.2.22.4 */* QC Hold Point
Obtain QC authorization to proceed before continuing with procedure. []
- 4.2.22.5 If As Found readings are not within limits specified on "Data Sheet 22, or more accurate readings are desired, proceed as follows:

NOTE

Refer to Figure 2 for adjustments.

- a. INCREASE or DECREASE R40 for trip point. []
- b. Adjust "Cal Adjust", note point at which DS1 ILLUMINATES and reset bistable. []
- c. */* If value is within limits specified on "Data Sheet 22", record in "As Left" section of "Data Sheet 22" and proceed to step 4.2.22.5e. []

PROCEDURE NO	REVISION	PAGE NO
VEGP 24614-1	12	38 of 74
<u>d.</u> */*	If value is not within limits specified on "Data Sheet 22", repeat steps 4.2.22.5a and 4.2.22.5b until an acceptable value is obtained and record in "As Left" section of "Data Sheet 22".	[]
e.	INCREASE input with "Cal Adjust", note point at which bistable can be reset and trip bistable.	[]
<u>f.</u> */*	If value is within limits specified on "Data Sheet 22" and a more accurate value is not desired, record in "As Left" (Reset) section of "Data Sheet 22" and proceed to step 4.2.22.6.	[]
<u>g.</u> */*	If value is not within limits specified on "Data Sheet 22", adjust R44 and repeat step 4.2.22.5e and record final value obtained in "As Left" section of "Data Sheet 22".	[]
4.2.22.6	Connect DMM to A3-15, terminals J4(+) and J5(-).	[]
4.2.22.7	Adjust R33 to 0.500V DC below trip point voltage.	[]
4.2.22.8	Connect DMM to A3-15, terminals J3(+) and J5(-).	[]
4.2.22.9	Adjust R34 to 0.500V DC above trip point voltage.	[]
<u>4.2.22.10</u> */*	Release A5 "Operate/Test" switch and reset all bistables.	[]
4.2.23	Channel Status Check (As Left)	
<u>4.2.23.1</u> */*	QC Hold Point Obtain QC authorization to proceed before continuing with procedure. (Only if As Found readings on "Channel Status Check" are not within limits)	[]
4.2.23.2	Repeat subsection 4.2.2, "Channel Status Check", to obtain As Left readings.	[]
4.3	RESTORE TO SERVICE	
<u>4.3.1</u> */*	Remove all test equipment connected during the course of this procedure.	[]

VEGP

24614-1

12

39 of 74

- 4.3.2 If not already performed, reset all-bistables. []
/
- 4.3.3 If not already performed, place the following
"Operate/Test" switches to "Operate" position:
a. A1 []
b. A2 []
c. A4 []
d. A5 []
- 4.3.4 If not already performed, close the following links:
/
a. 1BA0302 AJ 7,8,9 and 10 []
b. 1BA0300 AJ 4,5,6 and 7 []
- 4.3.5 Toggle switch "AT1 Reset" on card A5-16 and verify that
/ AT1 continues to cycle from 00 to 71. []
- 4.3.6 Verify Annunciator 37A04 "SEQ B TROUBLE" is
/ EXTINGUISHED. []
- 4.3.7 Verify sequencer reflects current plant conditions
/ after it is restored to service. []
- 4.3.8 Have an Independent Restoration Verification performed
/ by designated personnel. []
- 4.3.9 Notify RO, Train B sequencer has been returned to
service. []
- 4.3.10 Notify Shift Supervisor, or designee, of completion
/ of work including test results and obtain signature on
completion sheet. []
- 5.0 ACCEPTANCE CRITERIA
- 5.1 The Acceptance Criteria for this procedure is that all
devices listed in the appropriate subsection below are
within limits specified on applicable Data Sheets.

VEGP

24614-1

12

40 of 74

5.1.1 Analog Channel Operational Test -

Bistable A3-1
Bistable A3-2
Bistable A3-3
Bistable A3-5
Bistable A3-6
Bistable A3-7
Bistable A3-9
Bistable A3-10
Bistable A3-11
Bistable A3-13
Bistable A3-14
Bistable A3-15

5.1.2 Channel Calibration

Bistable A3-1
Bistable A3-2
Bistable A3-3
Bistable A3-5
Bistable A3-6
Bistable A3-7
Bistable A3-9
Bistable A3-10
Bistable A3-11
Bistable A3-13
Bistable A3-14
Bistable A3-15
AC Transmitter 1
Analog Isolator 1
AC Transmitter 2
Analog Isolator 2
AC Transmitter 3
Analog Isolator 3
AC Transmitter 4
Analog Isolator 4

5.2 Satisfactory completion of this procedure has been met when I&C Foreman has evaluated data obtained per "Acceptance Criteria" of this procedure, reviewed, and signed Data Sheets provided.

VEGP


24614-1

12

41 of 74

- 6.0 REFERENCES
- 6.1 Elementary, 1X3D-BA-D03E
- 6.2 One Line, 1X3D-AA-D03A
- 6.3 Annunciator Engraving, 1X6AV01-263
- 6.4 Logic Diag. of Safety Features Sequencer Board,
AX3AE03-94, 10-4
- 6.5 Field Connected Terminal Arrangement 1X3AE03-66, 78,
79, 80, 81, 82
- 6.6 Technical Manual, AX3AE03-365
- 6.7 VEGP Technical Specification
- 6.8 Procedure 00306-C, "Temporary Jumper And Lifted Wire
Control"
- 6.9 VEGP Final Safety Analysis Report

END OF PROCEDURE TEXT



FRONT VIEW





FIGURE 1



FRONT VIEW

FIGURE 2

Procedure No.

VEGP

24614-1

Revision

12

Page No.

44 of 74

ANALOG CHANNEL OPERATIONAL TEST DATA SHEET 1

SHEET 1 OF 3

NOTES: N/A

	CLOCK OUTPUT	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	
		Hz	1000	1000	1050			
ACTION	Bistable A3-1	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	Setpoint	V DC	3.950	3.910	3.990			N/A
	Reset	V DC	3.990	3.950	4.030			N/A
ACTION	Bistable A3-2	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	Setpoint	V DC	3.854	3.814	3.894			≥ 3.806
	Reset	V DC	3.894	3.854	3.934			N/A
ACTION	Bistable A3-3	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	Setpoint	V DC	3.267	3.227	3.307			≥ 3.219
	Reset	V DC	3.307	3.267	3.347			N/A
ACTION	Bistable A3-5	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	Setpoint	V DC	3.950	3.910	3.990			N/A
	Reset	V DC	3.990	3.950	4.030			N/A
ACTION	Bistable A3-6	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	Setpoint	V DC	3.854	3.814	3.894			≥ 3.806
	Reset	V DC	3.894	3.854	3.934			N/A
ACTION	Bistable A3-7	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	Setpoint	V DC	3.267	3.227	3.307			≥ 3.219
	Reset	V DC	3.307	3.267	3.347			N/A

COMMENTS:

CHANNEL OPERATIONAL TEST DATA SHEET 1

ACTION	Setpoint	Reset	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC.	ALLOW.
	Setpoint	Reset	V DC	3.950	3.910	3.990				N/A
ACTION	Bistable A3-10		V DC	3.990	3.950	4.030				N/A
	Setpoint	Reset	UNITS	3.854	3.814	3.894				N/A
	Setpoint	Reset	V DC	3.894	3.854	3.934				N/A
	Setpoint	Reset	V DC	3.267	3.227	3.307				N/A
	Setpoint	Reset	UNITS	3.307	3.267	3.347				N/A
	Setpoint	Reset	V DC	3.950	3.910	3.990				N/A
	Setpoint	Reset	V DC	3.990	3.950	4.030				N/A
	Setpoint	Reset	UNITS	3.854	3.814	3.894				N/A
	Setpoint	Reset	V DC	3.894	3.854	3.934				N/A
	Setpoint	Reset	V DC	3.267	3.227	3.307				N/A
	Setpoint	Reset	UNITS	3.307	3.267	3.347				N/A
	Setpoint	Reset	V DC	3.950	3.910	3.990				N/A
	Setpoint	Reset	V DC	3.990	3.950	4.030				N/A
	Setpoint	Reset	UNITS	3.854	3.814	3.894				N/A
	Setpoint	Reset	V DC	3.894	3.854	3.934				N/A
	Setpoint	Reset	V DC	3.267	3.227	3.307				N/A
	Setpoint	Reset	UNITS	3.307	3.267	3.347				N/A
	Setpoint	Reset	V DC	3.950	3.910	3.990				N/A
	Setpoint	Reset	V DC	3.990	3.950	4.030				N/A
	Setpoint	Reset	UNITS	3.854	3.814	3.894				N/A
	Setpoint	Reset	V DC	3.894	3.854	3.934				N/A
	Setpoint	Reset	V DC	3.267	3.227	3.307				N/A
	Setpoint	Reset	UNITS	3.307	3.267	3.347				N/A
	Setpoint	Reset	V DC	3.950	3.910	3.990				N/A
	Setpoint	Reset	V DC	3.990	3.950	4.030				N/A
	Setpoint	Reset	UNITS	3.854	3.814	3.894				N/A
	Setpoint	Reset	V DC	3.894	3.854	3.934				N/A
	Setpoint	Reset	V DC	3.267	3.227	3.307				N/A
	Setpoint	Reset	UNITS	3.307	3.267	3.347				N/A
	Setpoint	Reset	V DC	3.950	3.910	3.990				N/A
	Setpoint	Reset	V DC	3.990	3.950	4.030				N/A
	Setpoint	Reset	UNITS	3.854	3.814	3.894				N/A
	Setpoint	Reset	V DC	3.894	3.854	3.934				N/A
	Setpoint	Reset	V DC	3.267	3.227	3.307				N/A
	Setpoint	Reset	UNITS	3.307	3.267	3.347				N/A

ANALOG CHANNEL OPERATIONAL TEST DATA SHEET 1

SHEET 2 OF 3

NOTES: N/A

ACTION	Bistable	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	A3-9							
	Setpoint	V DC	3.950	3.910	3.990			N/A
	Reset	V DC	3.990	3.950	4.030			N/A
ACTION	Bistable	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	A3-10							
	Setpoint	V DC	3.854	3.814	3.894			≥ 3.806
	Reset	V DC	3.894	3.854	3.934			N/A
ACTION	Bistable	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	A3-11							
	Setpoint	V DC	3.267	3.227	3.307			≥ 3.219
	Reset	V DC	3.307	3.267	3.347			N/A
ACTION	Bistable	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	A3-13							
	Setpoint	V DC	3.950	3.910	3.990			N/A
	Reset	V DC	3.990	3.950	4.030			N/A
ACTION	Bistable	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	A3-14							
	Setpoint	V DC	3.854	3.814	3.894			≥ 3.806
	Reset	V DC	3.894	3.854	3.934			N/A
ACTION	Bistable	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.
	A3-15							
	Setpoint	V DC	3.267	3.227	3.307			≥ 3.219
	Reset	V DC	3.307	3.267	3.347			N/A

COMMENTS:

Procedure No.

VEGP

Revision

24614-1

12

Page No.

46 of 74

ANALOG CHANNEL OPERATIONAL TEST DATA SHEET I SHEET 3 OF 3

COMMENTS:

TEST EQUIPMENT

I.D. NO.	MODEL NO.	CALIBRATION DUE DATE

PERFORMED BY: DATE

REVIEWED BY: DATE

APPROVED BY: DATE

Procedure No.

VEGP

24614-1

Revision

12

Page No.

DATA SHEET 2

47 of 74

SHEET 1 OF 3

NOTES: N/A

ACTION	CLOCK OUTPUT	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.	
Bistable A3-1		HZ	1000	1000					
	Setpoint	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT		
	Reset	V DC	3.950	3.910	3.990				
Bistable A3-2		V DC	3.990	3.950	4.030				
	Setpoint	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.	
	Reset	V DC	3.854	3.814	3.894			N/A	
Bistable A3-3		V DC	3.894	3.854	3.934				
	Setpoint	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.	
	Reset	V DC	3.267	3.227	3.307			≥ 3.806	
Bistable A3-5		V DC	3.307	3.267	3.347				
	Setpoint	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW.	
	Reset	V DC	3.950	3.910	3.990			≥ 3.219	
		V DC	3.990	3.950	4.030			N/A	
I.D. NO.	TEST EQUIPMENT	CALIBRATION DUE DATE		COMMENTS:					
	MODEL NO.								

DATA SHEET 2

NOTES: N/A

ACTION	CLOCK OUTPUT	UNITS	EXPECTED	LO LIMIT		HI LIMIT		AS FOUND		AS LEFT		TECH. SPEC. ALLOW.
				LO LIMIT	HI LIMIT	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	AS FOUND	AS LEFT	
		HZ	1000	1000		1050						
Bistable A3-1	Setpoint	V DC	3.950	3.910		3.990						N/A
	Reset	V DC	3.990	3.950		4.030						N/A
Bistable A3-2	Setpoint	V DC	3.854	3.814		3.894						≥ 3.806
	Reset	V DC	3.894	3.854		3.934						N/A
Bistable A3-3	Setpoint	V DC	3.267	3.227		3.307						≥ 3.219
	Reset	V DC	3.307	3.267		3.347						N/A
Bistable A3-5	Setpoint	V DC	3.950	3.910		3.990						N/A
	Reset	V DC	3.990	3.950		4.030						N/A

COMMENTS:

TEST EQUIPMENT

MODEL NO. CALIBRATION DUE DATE

DATA SHEET 2

SHEET 2 OF 3

NOTES: N/A

ACTION		UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC. ALLOW
Bistable A3-6	Setpoint	V DC	3.854	3.814	3.894			≥ 3.806
	Reset	V DC	3.894	3.854	3.934			N/A
Bistable A3-7	Setpoint	V DC	3.267	3.227	3.307			≥ 3.219
	Reset	V DC	3.307	3.267	3.347			N/A
Bistable A3-9	Setpoint	V DC	3.950	3.910	3.990			N/A
	Reset	V DC	3.990	3.950	4.030			N/A
Bistable A3-10	Setpoint	V DC	3.854	3.814	3.894			≥ 3.806
	Reset	V DC	3.894	3.854	3.934			N/A

TEST EQUIPMENT			COMMENTS:
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE	

Procedure No.

VEGP 24614-1

Revision

12

Page No.

49 of 74

DATA SHEET 2

SHEET 3 OF 3

NOTES: N/A

ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	TECH. SPEC.	ALLOW
Bistable A3-11	Setpoint	3.267	3.227	3.307			≥ 3.219	
	Reset	3.307	3.267	3.347			N/A	
Bistable A3-13	Setpoint	3.950	3.910	3.990			N/A	
	Reset	3.990	3.950	4.030			N/A	
Bistable A3-14	Setpoint	3.854	3.814	3.894			≥ 3.806	
	Reset	3.894	3.854	3.934			N/A	
Bistable A3-15	Setpoint	3.267	3.227	3.307			≥ 3.219	
	Reset	3.307	3.267	3.347			N/A	

TEST EQUIPMENT

MODEL NO. CALIBRATION DUE DATE

COMMENTS:

PERFORMED BY:

DATE

REVIEWED BY:

DATE

APPROVED BY:

DATE

Manufacturer Consolidated Controls

50 of 74

Serial No.

SHEET 1 OF 1

Model No.

COMMENTS:

NO.	TESTED		LO LIMIT		HI LIMIT		AS FOUND		AS LEFT	
	V DC	V DC	V DC	V DC	V DC	V DC	V DC	V DC	V DC	V DC
75	2.000	1.000								
100	3.000	2.000								
75	4.000	3.000	0.998		1.002					
50	5.000	4.000	1.998		2.002					
25	3.000	5.000	2.998		3.002					
0	2.000	4.000	3.998		2.002					
	1.000	3.000	4.998		3.002					
	2.000	3.998	3.998		4.002					
	1.000	2.998	2.998		5.002					
	1.000	1.998	1.998		4.002					
	0.998	0.998	3.002		3.002					
	2.002	2.002	1.002		1.002					

CALIBRATION DUE DATE

TEST EQUIPMENT
MODEL NO.

PERFORMED BY:
REVIEWED BY:
APPROVED BY:

DATE
DATE
DATE

Procedure No.	Revision	Page No.
VEGP 24614-1	12	51 of 74

DATA SHEET 4

SHEET 1 OF 1

Instr. No. N/A Location Al Serial No. _____
 Description AC Transmitter 1 Manufacturer Consolidated Controls Model No. _____

NOTES: N/A

INPUT	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	COMMENTS:
Z	V AC	V DC	V DC	V DC	V DC	
0	0.0	1.000	0.992	1.008		
25	37.5	2.000	1.992	2.008		
50	75.0	3.000	2.992	3.008		
75	112.5	4.000	3.992	4.008		
100	150.0	5.000	4.992	5.008		
75	112.5	4.000	3.992	4.008		
50	75.0	3.000	2.992	3.008		
25	37.5	2.000	1.992	2.008		
0	0.0	1.000	0.992	1.008		

TEST EQUIPMENT		
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE

PERFORMED BY:	DATE
REVIEWED BY:	DATE
APPROVED BY:	DATE

DATA SHEET 5

SHEET 1 OF 1

Instr. No. N/A Location A2 Serial No. _____

Description Analog Isolator 2 Manufacturer Consolidated Controls Model No. _____

NOTES: N/A

INPUT		EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	COMMENTS:	
Z	V DC	V DC	V DC	V DC	V DC	V DC		
0	1.000	1.000	0.998	1.002				
25	2.000	2.000	1.998	2.002				
50	3.000	3.000	2.998	3.002				
75	4.000	4.000	3.998	4.002				
100	5.000	5.000	4.998	5.002				
75	4.000	4.000	3.998	4.002				
50	3.000	3.000	2.998	3.002				
25	2.000	2.000	1.998	2.002				
0	1.000	1.000	0.998	1.002				
TEST EQUIPMENT								
I.D. NO.	MODEL NO.		CALIBRATION DUE DATE					
						PERFORMED BY:	DATE	
						REVIEWED BY:	DATE	
						APPROVED BY:	DATE	

DATA SHEET 6

SHEET 1 OF 1


Instr. No. N/A Location A2 Serial No.
 Description AC Transmitter 2 Manufacturer Consolidated Controls Model No.

NOTES: N/A

INPUT		EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	COMMENTS:
Z	V AC	V DC	V DC	V DC	V DC	V DC	
0	0.0	1.000	0.992	1.008			
25	37.5	2.000	1.992	2.008			
50	75.0	3.000	2.992	3.008			
75	112.5	4.000	3.992	4.008			
100	150.0	5.000	4.992	5.008			
75	112.5	4.000	3.992	4.008			
50	75.0	3.000	2.992	3.008			
25	37.5	2.000	1.992	2.008			
0	0.0	1.000	0.992	1.008			
TEST EQUIPMENT							
I.D. NO.	MODEL NO.		CALIBRATION DUE DATE				
PERFORMED BY:						DATE	
REVIEWED BY:						DATE	
APPROVED BY:						DATE	

OF 1

4 of 74



COMMENTS:

Consolidated
DATA SHEET 7
AA

location

Manufacturer

Analog Isolator 3

N/A

24614-1

Revision

VECP

Procedure No.

Instr. No.

Description

NOTES: N/A

INPUT	EXPECTED		LO LIMIT		HI LIMIT		AS FOUND		AS LEFT		CALIBRATION DUE DATE
	V	DC	V	DC	V	DC	V	DC	V	DC	
2	1.000	2.000	1.000	2.000	1.002	2.002	1.002	2.002	1.002	2.002	1.002
25	2.000	3.000	0.998	1.998	2.998	3.998	2.998	3.998	2.998	3.998	1.998
50	3.000	4.000	1.998	2.998	3.998	4.998	3.998	4.998	2.998	3.998	0.998
75	4.000	5.000	2.998	3.998	4.998	5.998	4.998	5.998	3.998	4.998	1.002
100	5.000	6.000	3.998	4.998	5.998	6.998	5.998	6.998	4.998	5.998	2.002
125	6.000	7.000	4.998	5.998	6.998	7.998	6.998	7.998	5.998	6.998	3.002
150	7.000	8.000	5.998	6.998	7.998	8.998	7.998	8.998	6.998	7.998	4.002
175	8.000	9.000	6.998	7.998	8.998	9.998	8.998	9.998	7.998	8.998	5.002
200	9.000	10.000	7.998	8.998	9.998	10.998	9.998	10.998	8.998	9.998	6.002
225	10.000	11.000	8.998	9.998	10.998	11.998	10.998	11.998	9.998	10.998	7.002
250	11.000	12.000	9.998	10.998	11.998	12.998	11.998	12.998	10.998	11.998	8.002
275	12.000	13.000	10.998	11.998	12.998	13.998	12.998	13.998	11.998	12.998	9.002
300	13.000	14.000	11.998	12.998	13.998	14.998	13.998	14.998	12.998	13.998	10.002
325	14.000	15.000	12.998	13.998	14.998	15.998	14.998	15.998	13.998	14.998	11.002
350	15.000	16.000	13.998	14.998	15.998	16.998	15.998	16.998	14.998	15.998	12.002
375	16.000	17.000	14.998	15.998	16.998	17.998	16.998	17.998	15.998	16.998	13.002
400	17.000	18.000	15.998	16.998	17.998	18.998	17.998	18.998	16.998	17.998	14.002
425	18.000	19.000	16.998	17.998	18.998	19.998	18.998	19.998	17.998	18.998	15.002
450	19.000	20.000	17.998	18.998	19.998	20.998	19.998	20.998	18.998	19.998	16.002
475	20.000	21.000	18.998	19.998	20.998	21.998	20.998	21.998	19.998	20.998	17.002
500	21.000	22.000	19.998	20.998	21.998	22.998	21.998	22.998	20.998	21.998	18.002
525	22.000	23.000	20.998	21.998	22.998	23.998	22.998	23.998	21.998	22.998	19.002
550	23.000	24.000	21.998	22.998	23.998	24.998	23.998	24.998	22.998	23.998	20.002
575	24.000	25.000	22.998	23.998	24.998	25.998	24.998	25.998	23.998	24.998	21.002
600	25.000	26.000	23.998	24.998	25.998	26.998	25.998	26.998	24.998	25.998	22.002
625	26.000	27.000	24.998	25.998	26.998	27.998	26.998	27.998	25.998	26.998	23.002
650	27.000	28.000	25.998	26.998	27.998	28.998	27.998	28.998	26.998	27.998	24.002
675	28.000	29.000	26.998	27.998	28.998	29.998	28.998	29.998	27.998	28.998	25.002
700	29.000	30.000	27.998	28.998	29.998	30.998	29.998	30.998	28.998	29.998	26.002
725	30.000	31.000	28.998	29.998	30.998	31.998	30.998	31.998	29.998	30.998	27.002
750	31.000	32.000	29.998	30.998	31.998	32.998	31.998	32.998	30.998	31.998	28.002
775	32.000	33.000	30.998	31.998	32.998	33.998	32.998	33.998	31.998	32.998	29.002
800	33.000	34.000	31.998	32.998	33.998	34.998	33.998	34.998	32.998	33.998	30.002
825	34.000	35.000	32.998	33.998	34.998	35.998	34.998	35.998	33.998	34.998	31.002
850	35.000	36.000	33.998	34.998	35.998	36.998	35.998	36.998	34.998	35.998	32.002
875	36.000	37.000	34.998	35.998	36.998	37.998	36.998	37.998	35.998	36.998	33.002
900	37.000	38.000	35.998	36.998	37.998	38.998	37.998	38.998	36.998	37.998	34.002
925	38.000	39.000	36.998	37.998	38.998	39.998	38.998	39.998	37.998	38.998	35.002
950	39.000	40.000	37.998	38.998	39.998	40.998	39.998	40.998	38.998	39.998	36.002
975	40.000	41.000	38.998	39.998	40.998	41.998	40.998	41.998	39.998	40.998	37.002
1000	41.000	42.000	39.998	40.998	41.998	42.998	41.998	42.998	40.998	41.998	38.002

PERFORM

APPROVE

DATE

DATA SHEET 7

SHEET 1 OF 1

Instr. No. N/A Location A4 Serial No.
 Description Analog Isolator 3 Manufacturer Consolidated Controls Model No.

NOTES: N/A

INPUT		EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	COMMENTS:
Z	V DC	V DC	V DC	V DC	V DC	V DC	
0	1.000	1.000	0.998	1.002			
25	2.000	2.000	1.998	2.002			
50	3.000	3.000	2.998	3.002			
75	4.000	4.000	3.998	4.002			
100	5.000	5.000	4.998	5.002			
75	4.000	4.000	3.998	4.002			
50	3.000	3.000	2.998	3.002			
25	2.000	2.000	1.998	2.002			
0	1.000	1.000	0.998	1.002			
TEST EQUIPMENT							
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE					
						PERFORMED BY:	DATE
						REVIEWED BY:	DATE
						APPROVED BY:	DATE

Procedure No.

VEGP 24614-1

Revision

12

Page No.

55 of 74

DATA SHEET 8

SHEET 1 OF 1

Instr. No. N/A Location A4 Serial No. _____

Description AC Transmitter 3 Manufacturer Consolidated Controls Model No. _____

NOTES: N/A

INPUT		EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	COMMENTS:
Z	V AC	V DC	V DC	V DC	V DC	V DC	
0	0.0	1.000	0.992	1.008			
25	37.5	2.000	1.992	2.008			
50	75.0	3.000	2.992	3.008			
75	112.5	4.000	3.992	4.008			
100	150.0	5.000	4.992	5.008			
75	112.5	4.000	3.992	4.008			
50	75.0	3.000	2.992	3.008			
25	37.5	2.000	1.992	2.008			
0	0.0	1.000	0.992	1.008			

TEST EQUIPMENT

I.D. NO.	MODEL NO.	CALIBRATION DUE DATE	PERFORMED BY: _____ DATE _____	
				REVIEWED BY: _____ DATE _____
				APPROVED BY: _____ DATE _____

Procedure No.

VEGP

Revision

24614-1

12

Page No.

56 of 74

DATA SHEET 9

SHEET 1 OF 1

Instr. No.

N/A

Location

A5

Serial No.

Description

Analog Isolator 4 Manufacturer Consolidated Controls Model No.

NOTES: N/A

Z	INPUT V DC	EXPECTED V DC	LO LIMIT V DC	HI LIMIT V DC	AS FOUND		AS LEFT		COMMENTS:
					V DC	V DC	V DC	V DC	
0	1.000	1.000	0.998	1.002					
25	2.000	2.000	1.998	2.002					
50	3.000	3.000	2.998	3.002					
75	4.000	4.000	3.998	4.002					
100	5.000	5.000	4.998	5.002					
75	4.000	4.000	3.998	4.002					
50	3.000	3.000	2.998	3.002					
25	2.000	2.000	1.998	2.002					
0	1.000	1.000	0.998	1.002					

TEST EQUIPMENT

I.D. NO. MODEL NO. CALIBRATION DUE DATE

PERFORMED BY: _____ DATE _____

REVIEWED BY: _____ DATE _____

APPROVED BY: _____ DATE _____

Procedure No. VEGP 24614-1	Revision 12	Page No. 57 of 74
--------------------------------------	-----------------------	-----------------------------

DATA SHEET 10

SHEET 1 OF 1

Instr. No. <u>N/A</u>	Location <u>A5</u>	Serial No. _____
Description <u>AC Transmitter 4</u>	Manufacturer <u>Consolidated Controls</u>	Model No. _____

NOTES: N/A

Z	INPUT	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT	COMMENTS:
	V AC	V DC	V DC	V DC	V DC	V DC	
0	0.0	1.000	0.992	1.008			
25	37.5	2.000	1.992	2.008			
50	75.0	3.000	2.992	3.008			
75	112.5	4.000	3.992	4.008			
100	150.0	5.000	4.992	5.008			
75	112.5	4.000	3.992	4.008			
50	75.0	3.000	2.992	3.008			
25	37.5	2.000	1.992	2.008			
0	0.0	1.000	0.992	1.008			

TEST EQUIPMENT

I.D. NO.	MODEL NO.	CALIBRATION DUE DATE	
			PERFORMED BY: _____ DATE _____
			REVIEWED BY: _____ DATE _____
			APPROVED BY: _____ DATE _____

Procedure No. VEGP 24614-1	Revision 12	Page No. 58 of 74
-------------------------------	----------------	----------------------

DATA SHEET 11

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-1</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
A3-1	Setpoint	V DC	3.950	3.910	3.990		
	Reset	V DC	3.990	3.950	4.030		

COMMENTS

TEST EQUIPMENT			PERFORMED BY:	Date
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE		
			REVIEWED BY:	Date
			APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 59 of 74
-------------------------------	----------------	----------------------

DATA SHEET 12

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-2</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-2	Setpoint	V DC	3.854	3.814	3.894
	Reset	V DC	3.894	3.854	3.934		

COMMENTS

TEST EQUIPMENT		
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE
		PERFORMED BY: _____ Date _____
		REVIEWED BY: _____ Date _____
		APPROVED BY: _____ Date _____

Procedure No. VEGP 24614-1	Revision 12	Page No. 60 of 74
-------------------------------	----------------	----------------------

DATA SHEET 13

SHEET 1 OF 1

Inst. No. N/A Location A3-3 Serial No. _____
 Description Bistable Manufacturer Condec Model No. _____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-3	Setpoint	V DC	3.267	3.227	3.307
	Reset	V DC	3.307	3.267	3.347		

COMMENTS

TEST EQUIPMENT			PERFORMED BY:	Date
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE		
			REVIEWED BY:	Date
			APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 61 of 74
-------------------------------	----------------	----------------------

DATA SHEET 14

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-5</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-5	Setpoint	V DC	3.950	3.910	3.990
	Reset	V DC	3.990	3.950	4.030		

COMMENTS:

TEST EQUIPMENT			PERFORMED BY:	Date
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE		
			REVIEWED BY:	Date
			APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 62 of 74
-------------------------------	----------------	----------------------

DATA SHEET 15

SHEET 1 OF 1

Inst. No. N/A Location A3-6 Serial No. _____
 Description Bistable Manufacturer Condec Model No. _____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-6	Setpoint	V DC	3.854	3.814	3.894
	Reset	V DC	3.894	3.854	3.934		

COMMENTS:

TEST EQUIPMENT		
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE

PERFORMED BY: _____ Date _____
 REVIEWED BY: _____ Date _____
 APPROVED BY: _____ Date _____

Procedure No. VEGP 24614-1	Revision 12	Page No. 63 of 74
-------------------------------	----------------	----------------------

DATA SHEET 16

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-7</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-7	Setpoint	V DC	3.267	3.227	3.307
	Reset	V DC	3.307	3.267	3.347		

COMMENTS:

TEST EQUIPMENT		
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE

PERFORMED BY:	Date
REVIEWED BY:	Date
APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 64 of 74
-------------------------------	----------------	----------------------

DATA SHEET 17

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-9</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-9	Setpoint	V DC	3.950	3.910	3.990
	Reset	V DC	3.990	3.950	4.030		

COMMENTS:

TEST EQUIPMENT			PERFORMED BY:	Date
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE		
			REVIEWED BY:	Date
			APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 65 of 74
-------------------------------	----------------	----------------------

DATA SHEET 18

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-10</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
A3-10	Setpoint	V DC	3.854	3.814	3.894		
	Reset	V DC	3.894	3.854	3.934		

COMMENTS:

TEST EQUIPMENT		
I.D. N..	MODEL NO.	CALIBRATION DUE DATE
		PERFORMED BY: _____ Date
		REVIEWED BY: _____ Date
		APPROVED BY: _____ Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 66 of 74
-------------------------------	----------------	----------------------

DATA SHEET 19

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-11</u>	Serial No.	<u> </u>
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	<u> </u>

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-11	Setpoint	V DC	3.267	3.227	3.307
	Reset	V DC	3.307	3.267	3.347		

COMMENTS:

TEST EQUIPMENT			PERFORMED BY:	Date
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE		
			REVIEWED BY:	Date
			APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 67 of 74
-------------------------------	----------------	----------------------

DATA SHEET 20

SHEET 1 OF 1

Inst. No. N/A Location A3-13 Serial No. _____
 Description Bistable Manufacturer Condec Model No. _____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-13	Setpoint	V DC	3.950	3.910	3.990
	reset	V DC	3.990	3.950	4.030		

COMMENTS:

TEST EQUIPMENT			PERFORMED BY:	Date
I D. NO.	MODEL NO.	CALIBRATION DUE DATE		
			REVIEWED BY:	Date
			APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 11	Page No. 68 of 74
-------------------------------	----------------	----------------------

DATA SHEET 21

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-14</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-14	Setpoint	V DC	3.854	3.814	3.894
	Reset	V DC	3.894	3.854	3.934		

COMMENTS:

TEST EQUIPMENT		
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE

PERFORMED BY:	Date
REVIEWED BY:	Date
APPROVED BY:	Date

Procedure No. VEGP 24614-1	Revision 12	Page No. 69 of 74
-------------------------------	----------------	----------------------

DATA SHEET 22

SHEET 1 OF 1

Inst. No.	<u>N/A</u>	Location	<u>A3-15</u>	Serial No.	_____
Description	<u>Bistable</u>	Manufacturer	<u>Condec</u>	Model No.	_____

NOTES: N/A

SWITCH NO.	ACTION	UNITS	EXPECTED	LO LIMIT	HI LIMIT	AS FOUND	AS LEFT
		A3-15	Setpoint	V DC	3.267	3.227	3.307
	Reset	V DC	3.307	3.267	3.347		

COMMENTS:

TEST EQUIPMENT			PERFORMED BY:	Date
I.D. NO.	MODEL NO.	CALIBRATION DUE DATE		
			REVIEWED BY:	Date
			APPROVED BY:	Date

Sheet 1 of 1

CALCULATION SHEET

Show all calculations performed during course of this procedure in the space below.

Completed by: _____ Date _____

Reviewed by: _____ Date _____

Approved by: _____ Date _____

CHECKLIST

SHEET 1 OF 3

3.1 Shift Supervisor Authorization

Signature _____

Date _____

3.2 Reactor Operator (RO) Notified

Signature _____

Date _____

Step Verification

Step/Substep	Initial	Step/Substep	Initial
3.5	Prerequisites met _____	4.2.5.1	Independent Verification _____
4.1.1	Train A annunciators not ILLUMINATED _____	4.2.5.6	QC Notified _____
4.2.1.12	ALB37A04 ILLUMINATED _____	4.2.6.4	QC Notified _____
4.2.1.13	Bistables reset _____	4.2.6.9	Bistables reset _____
4.2.1.23	Bistables reset _____	4.2.7.1	Links open 1BA0302 AJ 7 _____
4.2.1.33	Bistables reset _____		AJ 8 _____
4.2.1.43	Bistable reset _____	4.2.7.1	Independent Verification _____
4.2.1.48	QC Notified _____	4.2.7.6	QC Notified _____
4.2.2.10	ALB37A04 ILLUMINATED _____	4.2.8.4	QC Notified _____
4.2.2.11	Bistables reset _____	4.2.8.9	Bistables reset _____
4.2.2.21	Bistables reset _____	4.2.9.1	Links open 1BA0302 AJ 9 _____
4.2.2.31	Bistables reset _____		AJ 10 _____
4.2.2.41	Bistables reset _____	4.2.9.1	Independent Verification _____
4.2.3.1	Links open 1BA0300 AJ 4 _____	4.2.9.6	QC Notified _____
	AJ 5 _____	4.2.10.4	QC Notified _____
4.2.3.1	Independent Verification _____	4.2.10.9	Bistable reset _____
4.2.3.6	QC Notified _____	4.2.11.6	QC Notified _____
4.2.4.4	QC Notified _____	4.2.12.4	QC Notified _____
4.2.4.9	Bistables reset _____	4.2.13.4	QC Notified _____
4.2.5.1	Links open 1BA0300 AJ 6 _____	4.2.13.10	Bistables reset _____
	AJ 7 _____	4.2.14.6	QC Notified _____

CHECKLIST

SHEET 2 OF 3

Step Verification			
Step/Substep	Initial	Step/Substep	Initial
4.2.15.4	QC Notified	4.3.3	"Operate/Test" switches in "Operate" position
4.2.16.4	QC Notified		A1
4.2.16.10	Bistables reset		A2
4.2.17.6	QC Notified		A4
4.2.18.4	QC Notified		A5
4.2.19.4	QC Notified	4.3.4	Links closed as follows:
4.2.19.10	Bistables reset		a. 1BA0302
4.2.20.6	QC Notified		AJ 7
4.2.21.4	QC Notified		AJ 8
4.2.22.4	QC Notified		AJ 9
4.2.22.10	Bistables reset		AJ 10
4.2.23.1	QC Notified		b. 1BA0300
4.3.1	Test equipment removed		AJ 4
4.3.2	Bistables reset as follows:	4.3.5	AT1 continues to cycle
	A3-1	4.3.6	ALB3704
	A3-2		EXTINGUISHED
	A3-3	4.3.7	Reflect current plant conditions
	A3-5		
	A3-6		
	A3-7		
	A3-9		
	A3-10		
	A3-11		
	A3-13		
	A3-14		
	A3-15		

SHEET 3 OF 3

RESTORATION VERIFICATION			
	Initial		Initial
<p>1. Following Bistables reset</p> <p>A3-1 _____</p> <p>A3-2 _____</p> <p>A3-3 _____</p> <p>A3-5 _____</p> <p>A3-6 _____</p> <p>A3-7 _____</p> <p>A3-9 _____</p> <p>A3-10 _____</p> <p>A3-11 _____</p> <p>A3-13 _____</p> <p>A3-14 _____</p> <p>A3-15 _____</p>		<p>2. Links closed</p> <p>a. 1BA0302</p> <p>AJ7 _____</p> <p>AJ8 _____</p> <p>AJ9 _____</p> <p>AJ10 _____</p> <p>b. 1BA0300</p> <p>AJ4 _____</p> <p>AJ5 _____</p> <p>AJ6 _____</p> <p>AJ7 _____</p>	
Performed by: _____		Date: _____	
Reviewed by: _____		Date: _____	

COMPLETION SHEET

PROCEDURE TITLE

SAFETY FEATURES SEQUENCER TRAIN B ANALOG
CHANNEL OPERATIONAL TEST AND CHANNEL
CALIBRATION

TIME TEST STARTED _____ BY _____ DATE _____

DEFICIENCIES OCCURRED AND ACTIONS TAKEN

TEST RESULTS: ACCEPTABLE UNACCEPTABLE

CHANNEL RESTORED TO SERVICE

CHANNEL COMMITTED TO REPAIR

TEST COMPLETED BY _____ TIME _____ DATE _____

SHIFT SUPERVISOR NOTIFIED _____
Signature Time Date

REVIEWED BY: _____ DATE _____

APPROVED BY: _____ DATE _____

Southern Company Services, Inc.
Post Office Box 2625
Birmingham, Alabama 35202
Telephone 205 870-6011

05-52-90
SON-210



Southern Company Services

the southern electric system

W. C. Ramsey, Jr.
Project Engineering Manager—Vogtle

05-52-90

Plant Vogtle Units 1 & 2
Response to REA VG-9010
Loss of Decay Heat Removal
File: X7BD112 Log: SG-8011
Security Code: NC

Mr. J. P. Kane
Georgia Power Company
Inverness 40, 4th Floor
Birmingham, Ala.

Dear Mr. Kane,

Attached please find our response to the subject REA.

Attachment 1 provides our technical response and Attachment 2 provides engineering cost and schedule estimates for each item identified in the REA.

Per agreement with Mr. James Mintz of your organization, only engineering manhours are included in Attachment 2. Implementation cost estimates are not included. This was done to minimize the cost of developing this response. If you desire detailed implementation estimates for any of the items in the REA, we will be pleased to provide these under separate cover.

If you have any questions or require additional information, please contact James Bingham at extension 7127.

W. C. Ramsey, Manager
Nuclear Plant Support - Vogtle

JRB/WRN/WCR/dl
Attachment *

xc: A. L. Mosbaugh *
C. R. Myer *
D. P. Wilson
J. W. Wheless
R. J. Gross
W. Nicholson *
NPS-B Reading Files

J. A. Bailey
S. Pietrzyk *
J. Lowery
R. D. Kies
J. Mintz *
GPC Reading Files *
NORMS *

W. C. Ramsey
D. K. Searcy
R. E. Patrick
S. K. Owen
J. Bingham *
NPS-B Files *
7-8011

ATTACHMENT 1
TECHNICAL RESPONSE TO
REA VG-9010

0089-1

This response consists of three sections. Section I provides an evaluation of the four methods listed in Item 1 of the REA to measure Reactor Coolant System (RCS) level during mid-loop operation. Section II looks at meaningful Residual Heat Removal (RHR) system parameters which can be utilized to detect impending or actual loss of RHR function. Section III evaluates the merits of an intelligent man-machine interface to monitor Decay Heat Removal function during mid-loop operation.

Section I: Reactor Coolant System Level Measurement.

Mid-Loop Operation is a mode of operation typified by the following conditions. The RCS has been cooled and depressurized to Cold Shutdown (Mode 5) conditions. The inventory in the RCS must be reduced to allow maintenance or inspection of the Reactor Head, Steam Generators or Reactor Coolant Pump Seals. The level in the primary system is lowered to one foot above the midline of the hot and cold legs. At this water level the air/water interface is at close proximity to the RHR suction nozzles located on the hot legs of Loops 1 and 4, and care must be taken to avoid air entrainment into the RHR pump suction. Air ingestion by the RHR pump can cause loss of pump function and possible pump damage, therefore it is extremely important for the operator to ensure that the water level is at or above the midline of the hot legs.

The level measurement system currently used during RCS draining and mid-loop operation is described in plant procedures (References 1, 2, and 3) and is shown in the attached Figure 1. This system consists of two temporary differential pressure transmitters connected to the RCS hot legs via the connections for instruments LX-1310 and LX-1320. The wide range transmitter has a span 96 inches water gage and the narrow range transmitter has a span of 30 inches water gage. The signals from the wide range and narrow range transmitters are used to provide indication on the Main Control Board. The signal from the narrow range transmitter is also used to provide a low level alarm on a Main Control Board Annunciator. Clear plastic "Tygon" tubing is installed between an RCS drain line and the pressurizer vent line. This tygon tubing serves as a sight glass for the RCS Loop 1 cold leg. The tygon tubing and the Main Control Board Indicators are comparison checked at regular intervals during RCS draining and mid-loop operation.

With the current system, several factors can be identified which can lead to inaccuracies in the level indication. Differential pressure transmitters sense head and as such are subject to density differences between the sensing line fill fluid and the density

of the process fluid. In addition, temperature gradients within the process and within the surrounding environment will have an effect on the accuracy of the measurement. Static pressure changes will have no effect on the current configurations as the transmitters also sense the pressure in the pressurizer (and thus the hot leg air space pressure) and subtract this from the pressure sensed from the water space in the hot leg. The tygon tube is also a head sensing measurement device and suffers from density induced inaccuracies. Parallax error in reading the meniscus of the fluid in the tube can also cause measurement inaccuracies in the tygon tube. Because of the RCS drain line location used for sensing, the tygon tube shows cold leg level which may not be exactly the hot leg level under certain conditions, such as cold leg pressurization due to RHR system air ingestion.

Measuring level using large displacement head sensors, such as the tygon tube or a sight glass (option 1(b) of the REA), or a thermal dispersion level transmitter (option 1(c) of the REA) has an inherent drawback in that due to the piping runs necessary to satisfy ALARA concerns, time lags are built into the system. Time lags will also occur if the core becomes hydraulically dynamic (such as from boiling). This will tend to isolate the cold legs from the hot legs. These time delays will tend to reduce the time in which the operator can respond to decreases in the RCS level.

Measuring level on the hot legs using the differential pressure transmitters (option 1(a) of the REA) or using the ultrasonic level transmitter (option 1(d) of the REA) is impacted by the formation of vortices at the RHR pump suction nozzles. The vortices will cause erratic and erroneous level indications.

Because the operating range is small (within a few feet), it is extremely important that the reactor operator understand the limitations of particular level measurement system used and have confidence in the indications. Here, the sight glass or tygon tube shows its merits as a positive indication of level. Boiling in the core (and subsequent hydraulic isolation of the hot and cold legs) is not probable prior to a loss of RHR system function. The sight glass or tygon tube will not, however, indicate the presence of vortexing in the hot legs. Since differential pressure is used in a wide variety of level measurement applications throughout the plant, the operators are very familiar with the limitations of this type of measurement. An uncertainty analysis should be performed for these loops similar to Technical Specification indicator loops to establish the expected measurement inaccuracies. The thermal dispersion type level transmitter will have merits similar to the sight glass and can in fact

be incorporated into a configuration with a sight glass. The ultrasonic level transmitter is the most complex of the four options and is likely to find some operator concern over accuracy based on past operational problems with an ultrasonic level measurement device in the Back-flushable Filter System (BFS). The ultrasonic level measurement system being considered for this application does not have a configuration which would lead to problems similar to those associated with the BFS.

It appears from our evaluation that all four options are technically feasible. The differential pressure transmitters (option 1(a)) and the tygon tube (described in Reference 3) offer the least impact to existing procedures and plant hardware. In reference 4, section 3.1.2.1, the NRC staff states, "...ordinary plastic tubing [tygon] does not meet our concept of reliable instrumentation, and its use may not be accepted as a component in instrumentation systems." We concur with the staff position and recommend that a sight glass (option 1(b)) be used instead. We find that the separate hot leg taps for the differential pressure transmitters (one on Loop 1 and one on Loop 4) meet the intent of independence as described in Reference 4. Options 1(c) and 1(d) do not appear to have sufficient technical merits to justify their use on Plant Vogtle.

Section II: RHR System Performance Monitoring

Air ingestion in the RHR pumps can cause erratic pump behavior, loss of capacity, loss of flow and ultimately loss of RCS cooling with the potential for fuel damage and release of radioactivity.

The relative functional strengths of various RHR system parameters can be described as follows:

Pump motor current: This parameter is a very strong indicator of air entrainment in the pump. This parameter is particularly useful when trended due to the dynamic nature of instantaneous motor current readings. Indication and trending of RHR pump motor current is not available at the present time in the Main Control Room.

Pump noise: This parameter can be measured by acoustically reading the cavitation processes occurring inside the pump casing. This can be done fairly easily by mounting acoustic transducers on the pump casing or support structure. This parameter is also a strong indication of air entrainment in the system.

Pump suction and discharge pressure magnitude and flowrate: The magnitude of these parameters is only a weak indication of air entrainment; however, the time history of these parameters can provide a moderately strong indication that air entrainment has occurred. Pump suction pressure indication is currently only available on local pressure gages in the pump rooms. Pump discharge pressure and flowrate are available in the Main Control Room and are currently trended on the ERF Computer during RCS draining and mid-loop operation per Reference 1.

Unfortunately, the parameters listed above are only sufficient to indicate the presence of air already in the system. A system to detect the approach to conditions which are favorable to entraining air in the RHR system requires more than just these parameters, and will be discussed in the next section.

Of these parameters, it is noted that pump motor current (which provides one of the strongest indications of air ingestion) is not currently available in the Main Control Room. We feel it would be prudent engineering design to add the capability to monitor and trend this parameter on the ERF Computer. The motor current could then be trended alongside pump discharge pressure and flowrate measurements. The trends of these three parameters would be sufficient to alert the operator to take appropriate action in accordance with plant procedures (see Reference 5). We feel that pump noise monitoring and pump suction pressure indications are secondary indications and are not required to adequately monitor the system performance.

Section III: Decay Heat Removal Monitoring System (DHRMS).

This system is envisioned to consist of a man-machine interface with the capability to take several parameters associated with mid-loop operation and provide the operator with intelligent information regarding impending or actual loss of RHR system function. The primary purpose would be to alert the operator to take corrective action prior to significant air ingestion.

The DHRMS should provide additional time for operator action which will result in a decrease in the potential for loss of RHR transients, improved operator control of the primary system during draining and mid-loop operation and improved recovery from loss of RHR transients.

The improved and more consistent information displays may well lead to better operator trust of the instrumentation. The DHRMS can also provide historical trending for post-analysis of mid-loop transients.

The parameters that we recommend for inclusion in the DHRMS are RCS temperature, RCS level, RHR pump motor current, RHR pump discharge pressure and RHR system flowrate.

The development of the DHRMS can take many forms. The most cost effect approach seems to be to purchase functional algorithms which Westinghouse has developed for analyzing impending loss of RHR and implement these algorithms on the ERF Computer System. The software development should most probably be performed by the Georgia Power Company Engineering and Construction Services Department, which developed the ERF Computer operating system. As demonstrated on past software upgrades, this group is very qualified to develop the DHRMS. The DHRMS should be designed to be functional only during Mode 5 and only when requested by the Unit Shift Supervisor.

We feel that the DHRMS is a very useful plant upgrade, however, we do not feel that the implementation of this system is required at this time to meet technical or regulatory requirements. We feel it might be beneficial to model this type of system on the Plant Vogtle simulator on a trial basis in order to refine the specifications for the informational displays and alarms.

Section IV: Summary.

This section summarizes our response to this REA.

We feel that the most appropriate way to measure RCS level during draining and mid-loop operation is to implement item 1(a), differential pressure transmitters and item 1(b), sight glass at the earliest practical time. We do not recommend implementing item 1(c), thermal dispersion level transmitter or item 1(d), ultrasonic level transmitter at any time.

We recommend adding item 2(a), pump motor current indication and trending to the Main Control Room at the earliest practical time. We do not feel it is necessary to implement item 2(b), pump noise monitoring or item 2(c), pump suction pressure at any time.

We recommend that item 2(d), Decay Heat Removal Monitoring System (DHRMS) be implemented at some future date, perhaps after initial operator response testing utilizing the Plant Vogtle simulator.

References:

1. Plant Vogtle Procedure 13005-1, Reactor Coolant System Draining.
2. Plant Vogtle Procedure 23985-1, RCS Temporary Water Level System.
3. Plant Vogtle Procedure 54840-1, Installation and Removal Instructions for the RCS Temporary Level Indication Tygon Tube.
4. Nuclear Regulatory Commission, Generic Letter 88-17, Enclosure 2.
5. Plant Vogtle Abnormal Operating Procedure 18019-C, Loss of Residual Heat Removal.




FIGURE 1 (LOOPS 2 AND 3 OMITTED)
 CURRENTLY UTILIZED MID-LOOP LEVEL
 INSTRUMENTATION

ATTACHMENT 2

ENGINEERING ESTIMATES FOR . . .

REA VG-9010

WORK AUTHORIZATION REQUEST

VOGTLE UNIT 1
1989 OFF-SITE ENGINEERING
FILE: X78811

DATE: 5/24/89

FROM: W. C. RAMSEY
TO: S. H. CHESTNUT

INITIAL
 CHANGE

CC: EPC J. D. HATHAWAY
J. S. ALFORD/SHAWPE
EEO: D. P. SPERON
S. K. BEARDY

DCR/REA VG-9010	EPC/REB 3073-DU	DESCRIPTION MRC Generic Letter 88-17 Decay Heat Removal
--------------------	--------------------	---

WORK BY <input checked="" type="checkbox"/> EOR <input type="checkbox"/> EPC	CURRENT AUTHORIZATION \$	REQUESTED CHANGE \$	TOTAL REQUESTED AUTHORIZATION \$
---	-----------------------------	------------------------	-------------------------------------

DESCRIPTION OF WORK Determine cost and schedule for item 1 (a) of the subject REA. This item is summarized below: Provide permanent mounting, conduit and tubing for temporary RCS Mid-loop Level Transmitters.	REQUESTED CHANGE MEASURES CPL _____ 274 ELECT _____ 96 MID _____ 176 MECH _____ 432 OTHERS _____ 4 TOTAL _____ 982
---	--

WRN 5/24/89	RCP 5/30/89	QB7 5/31/89	APPROVED	DATE
----------------	----------------	----------------	----------	------

RESPONSE TO WORK AUTHORIZATION REQUEST
FROM: S. H. CHESTNUT
TO: W. C. RAMSEY

APPROVED AS REQUESTED
 APPROVED WITH FOLLOWING CHANGES

CHANGE APPROVED @ _____ NEW TOTAL AUTHORIZED @ _____

ADDITIONAL JUSTIFICATION REQUIRED
 DISAPPROVED

SUBJECT FOR THIS WORK SHOULD BE ALLOCATED FROM _____

COMMENTS	CC EEO J. D. HATHAWAY J. S. ALFORD/SHAWPE EOR FILE EEO FILE REA FILE DCR FILE OO-WORSE EEO D. P. SPERON S. K. BEARDY
----------	---

SUBMITTED _____ DATE _____	APPROVED _____ DATE _____
----------------------------	---------------------------

WRNATH:BMF

SCOPE SUMMARY

REFERENCE DOCUMENT (DGR/REA) VG-9010, ITEM 1(a) REV 0
REFERENCE RER (IF APPL) N/A
DATE INITIATED 5/24/89

SUMMARY DESCRIPTION THIS SCOPE SUMMARY APPLIES TO ITEM 1(a) OF THE SUBJECT RER. THIS ITEM INVOLVES ADDING PERMANENT SUPPORTS, TUBING, AND CONDUIT TO THE CONTAINMENT FOR USE WITH THE TEMPORARY LEVEL TRANSMITTERS CURRENTLY USED DURING MID-LOOP OPERATION. THIS ITEM ALSO INCLUDES PERFORMING AN UNCERTAINTY ANALYSIS FOR THESE TRANSMITTER LOOPS.
ATTACHMENTS:

- SCOPE DESCRIPTION
- SCHEDULE DESCRIPTION
- BUDGET SUMMARY

APPROVALS:

	<u>SIGNATURE</u>	<u>DATE</u>
LDEGS	<u>WR Nicholson</u>	<u>5/26/89</u>
NPS-V MGR	<u></u>	<u></u>

SCOPE DESCRIPTION SUMMARY

I. SCOPE TYPE:

- INITIAL SCOPE
 SCOPE REVISION

II. REFERENCE DOCUMENT (DCR/REA/RER):

REA VG-9010

III. DESCRIPTION: THIS SUMMARY DISCUSSES ITEM 1(a)
OF THE SUBJECT REA: ADD PERMANENT SUPPORTS, TUBING
AND CONDUIT FOR THE MID-LOOP TEMPORARY LEVEL TRANSMITTERS.
PERFORM AN UNCERTAINTY ANALYSIS FOR THESE
TRANSMITTER LOOPS.

IV. LIST OF DESIGN ACTIVITIES/WORK ITEMS:

- ATTACHED
 N/A

V. LIST OF MATERIALS:

- ATTACHED
 N/A

VI. SPECIAL ITEMS:

- ATTACHED
 N/A

LIST OF DESIGN ACTIVITIES

This item consists of providing two differential pressure transmitters located inside the Secondary Shield wall. These transmitters will require instrument supports. The instruments will not be installed during normal operation (due to radiation exposure) and therefore, the support design should allow for easy removal. The supports should be Seismic Category I, however the attachment of the instruments to the supports does not need to be Seismic Category I.

Permanent wiring will be provided between the location of the transmitters and the location of two of the accumulator level transmitters. A junction box will be provided for easy connection of the signals from the new transmitters to the loops for the accumulator level transmitters. None of the new wiring will penetrate Containment.

Permanent tubing will be installed between the RVLIS hot leg isolators (LX-1310 and LX-1320), the low pressure test port for instrument LT-459 and the 5-valve manifolds for the new transmitters. This tubing will be Project Class 424. The supports for this tubing must be Seismic Category I due to its location. The tubing design should incorporate adequate isolation of the Project Class 424 tubing from the Project Class 212 tubing connection points when not in mid-loop operation.

LIST OF MATERIALS

- 2 each Differential Pressure Transmitters, Project Class 62J.
- 140 L.F. 3/8 inch O.D. tubing, seamless, 0.065 inch min. wall thickness, ASTM A-213, Gr. 304L or 316L, Project Class 424.
- 1 lot Various tube fittings, 1500# compression and threaded, Project Class 424.
- 2 each Instrument manifold valve, 5-way, Mark No. 5M15S1K.
- 23 each Tubing supports.
- 2 each Instrument supports.
- 18 each Conduit supports.
- 100 L.F. 3/4 inch diameter, rigid steel conduit.
- 100 L.F. Cable, Type CL67.
- 2 each Pull boxes.
- 4 each Junction boxes.

BUDGET SUMMARY

INITIAL BUDGET

BUDGET REVISION

REFERENCE DOCUMENT (DCR/REA/RER) REA VG-9010, ITEM 1(a)
 REFERENCE CHANGE NOTICE NUMBER N/A

MANHOOR BUDGET CHANGES:

<u>DISCIPLINE</u>	<u>EXISTING</u>	<u>NEW ESTIMATE</u>	<u>CHANGE</u>
ELEC	<u>N/A</u>	<u>96 96</u>	<u>N/A</u>
MECH	<u> </u>	<u>432</u>	<u> </u>
I & C	<u> </u>	<u>176</u>	<u> </u>
P/D	<u> </u>	<u>274</u>	<u> </u>
NUC	<u> </u>	<u>N/A</u>	<u> </u>
EQ	<u> </u>	<u>N/A</u>	<u> </u>
MGT/ADM	<u> </u>	<u>4</u>	<u> </u>
TOTAL	<u>↓</u>	<u>982</u>	<u>↓</u>

EXPENSE RELATED CHANGES (TRAVEL, COMPUTER CHARGES, ETC.):

<u>EXPENSE TYPE</u>	<u>EXISTING</u>	<u>NEW ESTIMATE</u>	<u>CHANGE</u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>

IMPLEMENTATION BUDGET CHANGES:

CHANGE (\$)

EQUIPMENT & MATERIALS

INSTALLATION LABOR

PLANT SUPPORT

Completed by Project Cost Estimator Only

COST ESTIMATE SUMMARY

RELATED DOCUMENT (SER/REA) REA VG-9010 PLANT VOGTLE-UNIT NO. 142
RER/ACTION ITEM NUMBER N/A ITEM 1(a)

SCOPE DESCRIPTION: (ATTACHED)

TYPE OF ESTIMATE:

BUDGET CATEGORY:

- CONCEPTUAL ESTIMATE
- INITIAL COST ESTIMATE
- REVISED COST ESTIMATE

- CAPITAL
- O&M

IMPLEMENTATION SCHEDULE _____ DESIGN DURATION _____

APPROVAL _____ DATE _____
NPS-V MANAGER

.....

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>AMOUNT</u>
1.	EQUIPMENT & MATERIALS	\$ _____
2.	INSTALLATION LABOR	\$ _____
3.	PLANT SUPPORT (GPC-ON SITE)	\$ _____
4.	SUBTOTAL (Total of Lines 1-3)	\$ _____
5.	GPC IMPLEMENTATION CONTINGENCY @ _____ %	\$ _____
6.	NPS-V ENGINEERING (INCLUDES: DIRECTS \$ _____ INDIRECTS \$ _____)	\$ _____
7.	SUBTOTAL (Total of Lines 4-6)	\$ _____
8.	GPC OVERHEADS @ _____ % of line 7 (CAPITAL ONLY)	\$ _____
9.	TOTAL PROJECT ESTIMATE (Total of Lines 7 & 8)	\$ _____

NO.	PRIORITY	SCORE OF WORK PERMANENT DESIGN	LEGEND	DATE	RESP. ENG.	REASON OF CHANGE	GROUP	ISSUE	NAME	SIGNATURE	DATE	PLANT ROUTE	UNIT 1 & 2
1	WORK (DOR)		START										
2	RECEIVE ALL SHEETINGS FROM GPC W/REVISIONS		MECH SYSTEMS APPROVAL PAID										
3			CONTROL'S										
4			MECH SYSTEMS APPROVAL PAID										
5			MECH SYSTEMS APPROVAL PAID										
6			MECH SYSTEMS APPROVAL PAID										
7			MECH SYSTEMS APPROVAL PAID										
8			MECH SYSTEMS APPROVAL PAID										
9			MECH SYSTEMS APPROVAL PAID										
10			MECH SYSTEMS APPROVAL PAID										
11			MECH SYSTEMS APPROVAL PAID										
12			MECH SYSTEMS APPROVAL PAID										
13			MECH SYSTEMS APPROVAL PAID										
14			MECH SYSTEMS APPROVAL PAID										
15			MECH SYSTEMS APPROVAL PAID										
16			MECH SYSTEMS APPROVAL PAID										
17			MECH SYSTEMS APPROVAL PAID										
18			MECH SYSTEMS APPROVAL PAID										
19			MECH SYSTEMS APPROVAL PAID										
20			MECH SYSTEMS APPROVAL PAID										
21			MECH SYSTEMS APPROVAL PAID										
22			MECH SYSTEMS APPROVAL PAID										
23			MECH SYSTEMS APPROVAL PAID										
24			MECH SYSTEMS APPROVAL PAID										
25			MECH SYSTEMS APPROVAL PAID										
26			MECH SYSTEMS APPROVAL PAID										
27			MECH SYSTEMS APPROVAL PAID										
28			MECH SYSTEMS APPROVAL PAID										
29			MECH SYSTEMS APPROVAL PAID										
30			MECH SYSTEMS APPROVAL PAID										
31			MECH SYSTEMS APPROVAL PAID										
32			MECH SYSTEMS APPROVAL PAID										
33			MECH SYSTEMS APPROVAL PAID										
34			MECH SYSTEMS APPROVAL PAID										
35			MECH SYSTEMS APPROVAL PAID										
36			MECH SYSTEMS APPROVAL PAID										

SCORE OF WORK PERMANENT DESIGN
 FOR RCS LEVEL TRANSMITTERS
 FROM THE RVLS ISMATTERS TO
 THE LOW PRESSURE TEST POND
 FOR VA. LT. 459

LEGEND
 START
 CHANGE
 SITUATION

DATE RESP. ENG. REASON OF CHANGE

GROUP ISSUE NAME SIGNATURE DATE

PLANT ROUTE - UNIT 1 & 2
 ITEM 110: DIFFERENTIAL
 LEVEL TRANSMITTERS

PROJECT NO. M-9010
 REV/ISS. 3073-DU
 PAGE 1 OF 1

FORB HOOPS: 9182

CIVIL DESIGN, MECH DESIGN, MECH SYSTEMS APPROVAL PAID

MECH DESIGN ROUTE CONTROL

ELECTRICAL CHEMICAL

ELECTRICAL

MECH SYSTEMS APPROVAL PAID

MECH SYSTEMS APPROVAL PAID

MECH SYSTEMS APPROVAL PAID

MECH SYSTEMS APPROVAL PAID

MECH SYSTEMS APPROVAL PAID

MECH SYSTEMS APPROVAL PAID

MECH SYSTEMS APPROVAL PAID

MECH SYSTEMS APPROVAL PAID

WORK AUTHORIZATION REQUEST

NUCLEAR PLANT SUPPORT - YONKLE

DATE: 5/24/89

UNIT NO. 1

FILE: 178811 LOR _____

INITIAL REQUEST

FROM: K. C. RAMSEY, JR.

CHANGE REQUEST

TO : J. P. KANE

REQ/NO VG-9010	WAL/NO 3073-DU	DESCRIPTION NRC Generic Letter 88-17 Decay Heat Removal	
<input checked="" type="checkbox"/> WIP <input type="checkbox"/> OK \$ _____ \$ _____ \$ _____	DESCRIPTION OF WORK Determine cost and schedule for item 1(b) of the subject REA. This item is summarized below: Replace temporary tygon tubing with a permanent pipe/sight glass configuration to measure RCS level during mid-loop operation.		
		ESTIMATED WORKING HOURS NUMBER OF WORKERS WFL _____ 129 WEL _____ 4 WOP _____ 93 WED _____ 170 WAD _____ 4 WOT _____ 400	
WOP 5/25/89	REP 5/30/89	907 5-31-89	_____ _____

RESPONSE TO WORK AUTHORIZATION REQUEST

FROM: J. P. KANE
TO: K. C. RAMSEY, JR.

APPROVED AS REQUESTED
 APPROVED WITH FOLLOWING CHANGES:
 APPROVED WORKING HOURS: _____ EST. WORKING HOURS: _____
 APPROVED WITH MODIFICATIONS:
 UNAPPROVED

REMARKS FOR THE WORK SHOULD BE ALLOCATED PER: _____

APPROVED BY: _____ DATE: _____	APPROVED BY: _____ DATE: _____
-----------------------------------	-----------------------------------

SCOPE SUMMARY

REFERENCE DOCUMENT (DGR/REA) REA VG-9010, ITEM 1(b) REV 0

REFERENCE RER (IF APPL) N/A

DATE INITIATED 5/24/89

SUMMARY DESCRIPTION THIS SCOPE SUMMARY APPLIES TO ITEM 1(b) OF THE SUBJECT REA. THIS ITEM INVOLVES REPLACING THE TEMPORARY TYGON TUBING CURRENTLY USED IN DETERMINING PCS LEVEL DURING MID-LOOP OPERATION WITH A PERMANENTLY PIPED SLIGHT GLASS CONFIGURATION.

ATTACHMENTS:

- SCOPE DESCRIPTION
- SCHEDULE DESCRIPTION
- BUDGET SUMMARY

APPROVALS:

	<u>SIGNATURE</u>	<u>DATE</u>
LDEGS	<u>WR Nicholas</u>	<u>5/26/89</u>
NPS-V MGR	<u></u>	<u></u>

SCOPE DESCRIPTION SUMMARY

I. SCOPE TYPE:

- INITIAL SCOPE
 SCOPE REVISION

II. REFERENCE DOCUMENT (DCN/REA/RRR):

REA V6-9010

III. DESCRIPTION: THIS SUMMARY DISCUSSES ITEM 1 (b)
OF THE SUBJECT REA: REPLACE TEMPORARY TYGON
TUBING WITH PERMANENT PIPING AND A PERMANENT SIGHT
GLASS FOR USE DURING RCS MIDLOOP OPERATIONS.

IV. LIST OF DESIGN ACTIVITIES/WORK ITEMS:

- ATTACHED
 N/A

V. LIST OF MATERIALS:

- ATTACHED
 N/A

VI. SPECIAL ITEMS:

- ATTACHED
 N/A

LIST OF DESIGN ACTIVITIES

This option involves replacing the temporary tygon tubing level gage with permanent hard piping and a permanent level glass. The hard piping will run between the tygon tubing connections shown on P&ID's 1/2X4DB111 and 1/2X4DB112. The piping should be Project Class 424 and must allow for positive isolation from the 212 piping system. The piping and supports must meet Seismic Category II over I criteria. There is no electrical work required for this item.

LIST OF MATERIALS

- 1 each Level Glass, Project Class 424.
- 110 L.F. 1 inch diameter pipe, seamless, sch.40S, ASTM A-312, Gr. TP304L, Project Class 424.
- 1 lot Various pipe fittings, 3000#, Socket Weld, ASTM A-182, Gr. F304L, Project Class 424.
- 4 each Flanges with gaskets, bolts and nuts, 150# RFSW, ASTM A-182, Gr. F316L, Project Class 424.
- 13 each Miscellaneous pipe supports.

COST ESTIMATE SUMMARY

RELATED DOCUMENT (DGR/REA) REA VG-9010 PLANT VOGTLE-UNIT NO. 1E2
RER/ACTION ITEM NUMBER N/A ITEM 1(b)

SCOPE DESCRIPTION: (ATTACHED)

TYPE OF ESTIMATE:

- CONCEPTUAL ESTIMATE
- INITIAL COST ESTIMATE
- REVISED COST ESTIMATE

BUDGET CATEGORY:

- CAPITAL
- O&M

IMPLEMENTATION SCHEDULE _____ DESIGN DURATION _____

APPROVAL _____ DATE _____
NPS-V MANAGER

.....

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>AMOUNT</u>
1.	EQUIPMENT & MATERIALS	\$ _____
2.	INSTALLATION LABOR	\$ _____
3.	PLANT SUPPORT (GPC-ON SITE)	\$ _____
4.	SUBTOTAL (Total of Lines 1-3)	\$ _____
5.	GPC IMPLEMENTATION CONTINGENCY @ _____ %	\$ _____
6.	NPS-V ENGINEERING (INCLUDES: DIRECTS \$ _____ INDIRECTS \$ _____)	\$ _____
7.	SUBTOTAL (Total of Lines 4-6)	\$ _____
8.	GPC OVERHEADS @ _____ % of line 7 (CAPITAL ONLY)	\$ _____
9.	TOTAL PROJECT ESTIMATE (Total of Lines 7 & 8)	\$ _____

BUDGET SUMMARY

INITIAL BUDGET

BUDGET REVISION

REFERENCE DOCUMENT (DCR/REA/RER) REA V6-9010, ITEM 1(b)

REFERENCE CHANGE NOTICE NUMBER N/A

MANHOOR BUDGET CHANGES:

<u>DISCIPLINE</u>	<u>EXISTING</u>	<u>NEW ESTIMATE</u>	<u>CHANGE</u>
ELEC	<u>N/A</u>	<u>4</u>	<u>N/A</u>
MECH	<u>N/A</u>	<u>170</u>	<u>N/A</u>
I & C	<u>N/A</u>	<u>93</u>	<u>N/A</u>
P/D	<u>N/A</u>	<u>129</u>	<u>N/A</u>
NUC	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
EQ	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
MGT/ADM	<u>N/A</u>	<u>4</u>	<u>N/A</u>
TOTAL	<u>N/A</u>	<u>400</u>	<u>N/A</u>

EXPENSE RELATED CHANGES (TRAVEL, COMPUTER CHARGES, ETC.):

<u>EXPENSE TYPE</u>	<u>EXISTING</u>	<u>NEW ESTIMATE</u>	<u>CHANGE</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

IMPLEMENTATION BUDGET CHANGES:

- | | |
|--|--------------------|
| <input type="checkbox"/> EQUIPMENT & MATERIALS | <u>CHANGE (\$)</u> |
| <input type="checkbox"/> INSTALLATION LABOR | _____ |
| <input type="checkbox"/> PLANT SUPPORT | _____ |

Completed by Project Cost Estimator Only

LINE NO	DESCRIPTION	LEAD DISCIPLINE	RESPONSIBLE ENGINEER	EXTENSION	LOCATION
		CONTROLS	J.R. BULLHAM	3712	SITE
1	✓ SANITARY ANNOTATE WORK (DCR)				
2	② RECEIVE ALL SKETCHES FROM GPC IMPLEMENTATION GROUP				
3		MECHANICAL AND LEVEL GAUGE TO PFD	MECHANICAL ROUTE PIPING	CIVIL ANALYSE PIPING	CIVIL DESIGN PIPE SUPPORTS
4		4/2	8/4	10/20	50/10
5		MECH DESK DRAFT SUPPORTS	CONTROLS PREPARE PACKAGE	INTERDISCIPLINE REVIEW MECHANICAL SYSTEMS	MANAGEMENT REVIEW
6		6/15	38/9	4/2	4/2
7		CONTROLS DATA SHEET	CONTROLS ISSUE PROCEEDURE CHART	CONTROLS DRAFT FILE	
8		10/3	8/2	1/1	
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					

TOTAL HOURS: 400

MODE Scale	PRIORITY	SCOPE OF WORK PERMANENT DESIGN FOR A LEVEL GAUGE (SIGHT GUAGE) IN LIEU OF THE TYGON	LEGEND <input type="checkbox"/> MECHANICAL <input type="checkbox"/> ELECTRICAL <input type="checkbox"/> INSTRUMENTATION <input type="checkbox"/> CONSTRUCTION	DATE	RESP ENG	REASON OF CHANGE	GROUP	LEAD	NAME	SIGNATURE	DATE	PLANT YOGTE - UNIT 1 & 2
	YES						MECH/INSTR		J.R. BULLHAM		5/1/08	TITLE ITEM 1(b) PERMANENT SITE GAUGE

WORK AUTHORIZATION REQUEST

NUCLEAR PLANT SUPPORT - YOUTL

DATE: 5/24/89

UNIT NO. 1

FIELD: KYBELL

LDG: _____

INITIAL REQUEST

FROM: W. C. FARNEY, JR.

CHANGE REQUEST

TO: J. P. KANE

WORK ORDER NO. VG-9010	NRC/PLANT NO. 3073-DU	DESCRIPTION NRC Generic Letter 88-17 Decay Heat Removal	
UNIT NO. <input checked="" type="checkbox"/> 001 <input type="checkbox"/> 002	GENERAL APPROPRIATION \$ N/A	APPLICABLE CODE \$ A	WELL NUMBER APPROPRIATION \$ N/A
DESCRIPTION OF WORK Determine cost and schedule for item 1 of the subject REA. This item is summarized below: Add two thermal dispersion type level transmitters to measure RCS level during mid-loop operations.		QUANTITY REQUIRED NUMBER OF UNITS CYCLES <u>418</u> HOURS <u>98</u> DAYS <u>142</u> WEEKS <u>528</u> MONTHS <u>4</u> YEARS <u>1,190</u>	
WORK ORDER NO. 5/25/89	REP 5/30/89	DATE 5/31/89	APPROVED _____

RESPONSE TO WORK AUTHORIZATION REQUEST

FROM: J. P. KANE

TO: W. C. FARNEY, JR.

APPROVED AS REQUESTED

APPROVED WITH FOLLOWING CHANGES:

APPROVED DURING \$ _____

BY THIS APPROVATION \$ _____

ADDITIONAL APPROPRIATION REQUIRED

REAPPROVED

WORKER FOR THIS WORK SHOULD BE ALIGNED WITH: _____

COMMENTS

BY
 J. P. KANE
 J. L. SPENCER
 DATE
 BY
 S. H. HAYES
 S. L. HAYES
 PROJECT FILE

DATE

APPROVED

SCOPE SUMMARY

REFERENCE DOCUMENT (SER/REA) REA VG-9010, ITEM 1(c) REV 0
REFERENCE RER (IF APPL) N/A
DATE INITIATED 5/24/89

SUMMARY DESCRIPTION THIS SCOPE SUMMARY APPLIES TO ITEM 1(c) OF THE SUBJECT REA. THIS ITEM INVOLVES ADDING TWO THERMAL DISPERSION TYPE LEVEL TRANSMITTERS TO MEASURE RCS LEVEL DURING MID-LOOP OPERATIONS.

ATTACHMENTS:

- SCOPE DESCRIPTION
- SCHEDULE DESCRIPTION
- BUDGET SUMMARY

APPROVALS:

	<u>SIGNATURE</u>	<u>DATE</u>
LDEGS	<u>W. R. Richardson</u>	<u>3/25/89</u>
NPS-V MGR	<u></u>	<u></u>

SCOPE DESCRIPTION SUMMARY

I. SCOPE TYPE:

- INITIAL SCOPE
 SCOPE REVISION

II. REFERENCE DOCUMENT (DCR/REA/RER):

REA V6-9010

III. DESCRIPTION: THIS SUMMARY DISCUSSES ITEM (C) OF THE SUBJECT REA: ADD TWO THERMAL DISPERSION TYPE LEVEL TRANSMITTERS TO MEASURE RCS LEVEL DURING MID-LOOP OPERATIONS.

IV. LIST OF DESIGN ACTIVITIES/WORK ITEMS:

- ATTACHED
 N/A

V. LIST OF MATERIALS:

- ATTACHED
 N/A

VI. SPECIAL ITEMS:

VENDOR LITERATURE FOR THERMAL DISPERSION TYPE LEVEL TRANSMITTERS.

- ATTACHED
 N/A

LIST OF DESIGN ACTIVITIES

This option involves adding 3/4 inch O.D. tubing from two of the RCS drain lines to the pressurizer vent line. Installed in these lines will be Fluid Components Inc. CL-86 model thermal dispersion level transmitters. Cable and conduit will be provided to router the signal from these two devices to the accumulator level transmitters. The tubing should be Project Class 424 with adequate isolation from the Project Class 212 mainline piping. The piping and support system must meet Seismic Category II over I criteria. The level transmitters will be installed in 2 inch piping as shown on the e attached vendor information sheets.

LIST OF MATERIALS

- 2 each CL-86 Continuous Level Monitoring System, Project Class 424/62J.
- 2 each Sight glass for calibration of CL-86.
- 280 L.F. 3/4 inch O.D. tubing, seamless, 0.065 inch wall thickness min., ASTM A-213, Gr. 304L or 316L, Project Class 424.
- 6 L.F. 2 inch diameter pipe, seamless, sch.40S, ASTM A-312, Gr. TP304L, Project Class 424.
- 1 lot Various tube fittings, 1500#, compression or threaded, Project Class 424.
- 2 each Flanges with gaskets, bolts and nuts, 600# RFSW, ASTM A-182, Gr. F316L, Project Class 424.
- 40 each Miscellaneous pipe supports.

0081-1

LIST OF MATERIALS (cont.)

18 each Conduit supports.

2 each Junction boxes.

100 L.F. 3/4 inch diameter rigid steel conduit.

100 L.F. Cable, Type CL67.



FCI

Nuclear Generator

October 1988

Nuclear Power Industry Newsletter

Issue IX

The FCI CL86 Thermal Dispersion Continuous Level Sensor for RCS Mid-Loop Operation

In response to Generic Letter 87-12 and NRC Guidance on RCS Mid-Loop Operation while using Residual Heat Removal or Decay Heat Removal Systems, FCI is offering the CL86 Continuous Level Sensor in two installation configurations to satisfy RCS Mid-Loop Level Gauging requirements. Both configurations will provide independent indication of Hot Leg level in the control room. Redundant installations of either CL86 configuration or one of each type will satisfy NRC Guidance.

The CL86 Sensor Assembly

The model CL86 Continuous Level Sensor utilizes FCI's field-proven, proprietary Thermal Dispersion Operating Principle and No-Moving-Parts Design.

All sensing and heating elements on the CL86 are contained within mineral insulated stainless steel sheathed cable. The

cable can be as small as 0.03 inch (0.76 mm) but typically has an 0.06 to 0.093 inch (1.5 to 2.4 mm) outside diameter. The cable is drawn in lengths up to several hundred feet but is ordinarily purchased in 100-foot lengths. A heater wire and a platinum resistance temperature detector (RTD) wire are encased in the stainless steel sheath and electrically insulated from the sheath and from each other with magnesium or aluminum oxide.

Two such mineral insulated cables are mounted within a nominal 2-inch diameter supporting stilling well assembly, though both cables - 0.06 inch (1.5 mm) or less in diameter - can be mounted inside a 0.25 inch (6.35 mm) diameter tube if desired (See Figure 1).

In one of the cables, constant electrical power is applied to the heater so that in air, the heated RTD is nominally 100°F (38.7°C) hotter than the unheated cable. The electronic power supply also employs detector circuits to measure and compare the electrical resistance of the heated and reference RTDs. In addition, the electronic assembly employs signal conditioning devices to convert the differential resistance signals to 4 to 20 mA or other customary output signals.

Thermal Dispersion Continuous Level Sensing

As noted above, the heated RTD is approximately 100°F (38.7°C) hotter than the reference RTD when in air or gas. If part of the sensing array is immersed in liquid, the liquid rapidly disperses the heat from the heater so that the two RTDs are at the same temperature (and resistance) over the immersed lengths. The change in resistance as a function of the immersed length is calibrated at the factory so the output signal shows a linear relationship with the amount of immersion. The simplified version described above is suitable for most applications. However, if temperature and pressure of the vapor/gases and liquid media change, special compensators can be added as necessary to correct for these process variations.





Figure 1. Cross sectional view, CL86 Sensor Assembly.

FCI FLUID COMPONENTS INC.

1755 La Costa Meadows Dr., San Marcos, CA 92069 USA • (800)854-1993 • (619)744-6950 • TLX 695092 • FAX (619)744-6950



Ordinarily, the reference RTD applies sufficient compensation for the variable physical conditions of the process and added special compensators are not required.

In-Core Guide Tube Installation

FCI's Continuous Level Sensor is designed for installation in a spare guide tube which has the thimble removed and a vent path added to the pressurizer and/or reactor vessel head. This allows the media level in the reactor vessel to equalize with the media level in the guide tube. The level in the reactor vessel and guide tube is closely approximated to the level in the hot legs.

With this design, the level in the reactor vessel can be monitored during draindown operation from the seal table elevation to the lowest hot leg elevation. During this critical draining process, the control room operators will have continuous level indication displayed per plant design. The active length of the continuous level sensor is designed per customer specifications.

The connections on the FCI Continuous Level Sensor are designed to interface with existing seal table pressure connections. The vent isolation valves are closed during normal operation to isolate the vent lines. Calibration of the continuous level probe prior to draindown can be accomplished in place using a positive pressure to change the water level in the guide tube.

Advantages of In-Core Guide Tube Installations


- Wide range of level indication during draindown
- Ease of installation
- "Smart" performance
- Reduced radiation exposure (ALARA) on installation and operation
- Ease of calibration

- Accurate indication of level
- Reliable service-proven design
- IE Safety-Related Qualification

Hot Leg Standpipe Installation

The FCI Continuous Level Sensor is designed to be installed in a standpipe configuration to provide level indication in the hot leg portion of the RCS. This design allows continuous level in the control room as well as local indication on the standpipe gauge glass. Functional and calibration testing on the sensor assembly and electronics can be performed using the gauge glass and drain and fill connections prior to draindown.

Vent lines to the pressurizer/reactor head are unnecessary with this installation configuration as the level in the standpipe will equalize with the hot leg level regardless of RCS pressure. During all operation modes other than draindown, the standpipe and gauge glass will be disconnected from the RCS loop.



Advantages of Hot Leg Standpipe Installations

- Reliable local and remote indication
- Ease of calibration
- Accurate media level indication
- Bubbles and gas pocket errors eliminated
- "Smart" performance
- Reliable service-proven design
- IE Safety-Related Qualification

Call FCI today at (800)854-1993 or (619)744-6950 for more information on the FCI CL86 Continuous Level Sensor for Mid-Loop Level Gauging requirements.

BUDGET SUMMARY

INITIAL BUDGET

BUDGET REVISION

REFERENCE DOCUMENT (DCR/REA/RER) REA V6-9010, ITEM 1(C)
 REFERENCE CHANGE NOTICE NUMBER N/A

MANHOOR BUDGET CHANGES:

<u>DISCIPLINE</u>	<u>EXISTING</u>	<u>NEW ESTIMATE</u>	<u>CHANGE</u>
ELEC	<u>N/A</u>	<u>98</u>	<u>N/A</u>
MECH	<u>T</u>	<u>528</u>	<u>T</u>
I & C	<u>T</u>	<u>142</u>	<u>T</u>
P/D	<u>T</u>	<u>418</u>	<u>T</u>
NUC	<u>T</u>	<u>N/A</u>	<u>T</u>
EQ	<u>T</u>	<u>N/A</u>	<u>T</u>
MGT/ADM	<u>T</u>	<u>4</u>	<u>T</u>
TOTAL	<u>↓</u>	<u>690</u>	<u>↓</u>

EXPENSE RELATED CHANGES (TRAVEL, COMPUTER CHARGES, ETC.):

<u>EXPENSE TYPE</u>	<u>EXISTING</u>	<u>NEW ESTIMATE</u>	<u>CHANGE</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

IMPLEMENTATION BUDGET CHANGES:

- | | |
|--|--------------------|
| <input type="checkbox"/> EQUIPMENT & MATERIALS | <u>CHANGE (\$)</u> |
| <input type="checkbox"/> INSTALLATION LABOR | _____ |
| <input type="checkbox"/> PLANT SUPPORT | _____ |

Completed by Project Cost Estimator Only

COST ESTIMATE SUMMARY

RELATED DOCUMENT (DCR/REA) REA VG-9010
RER/ACTION ITEM NUMBER N/A ITEM (C)

PLANT VOGTLE-UNIT NO. 42

SCOPE DESCRIPTION: (ATTACHED)

TYPE OF ESTIMATE:

- CONCEPTUAL ESTIMATE
- INITIAL COST ESTIMATE
- REVISED COST ESTIMATE

BUDGET CATEGORY:

- CAPITAL
- O&M

IMPLEMENTATION SCHEDULE _____ DESIGN DURATION _____

APPROVAL _____ DATE _____
NPS-V MANAGER

.....

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>AMOUNT</u>
1.	EQUIPMENT & MATERIALS	\$ _____
2.	INSTALLATION LABOR	\$ _____
3.	PLANT SUPPORT (GPC-ON SITE)	\$ _____
4.	SUBTOTAL (Total of Lines 1-3)	\$ _____
5.	GPC IMPLEMENTATION CONTINGENCY @ _____ %	\$ _____
6.	NPS-V ENGINEERING (INCLUDES: DIRECTS \$ _____ INDIRECTS \$ _____)	\$ _____
7.	SUBTOTAL (Total of Lines 4-6)	\$ _____
8.	GPC OVERHEADS @ _____ % of line 7 (CAPITAL ONLY)	\$ _____
9.	TOTAL PROJECT ESTIMATE (Total of Lines 7 & 8)	\$ _____

NO	DESCRIPTION	LEAD DISCIPLINE	RESPONSIBLE ENGINEER	EXTENSION	LOCATION
1	SOFT COPY APPROVAL WORK ORDER	CONTROLS	Jim Bannerman	3-7-92	SITE
2	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
3	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
4	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
5	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
6	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
7	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
8	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
9	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
10	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
11	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
12	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
13	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
14	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
15	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
16	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
17	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
18	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
19	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
20	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
21	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
22	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
23	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
24	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
25	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
26	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
27	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
28	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
29	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
30	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
31	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
32	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
33	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
34	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
35	REVIEW ALL SHEETS FROM SFC	MECHANICAL			
36	REVIEW ALL SHEETS FROM SFC	MECHANICAL			

SCORE OF WORK PROVIDE A THROUGH DISPERSION LEVEL MEASUREMENT SYSTEM

LEGEND

- MECHANICAL
- ELECTRICAL
- PLUMBING
- MECHANICAL

DATE

RE:SP. ENG.

REASON OF CHANGE

GROUP

LEAD

NAME

SIGNATURE

DATE

PLANT WASTE - UNIT 1 & 2

ITEM 1 (C) - THERMAL DISPERSION CONTINUOUS LEVEL

REVISION

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

WORK AUTHORIZATION REQUEST

VOOTLE UNIT 1
1988 OFF-SITE ENGINEERING
FILE X78811

DATE: 5/24/89

FROM: W. C. RAMSEY
TO: S. H. CHESTNUT

INITIAL
 CHANGE

CC: SPO & S. HODGSON
& S. ALPHEUS
SPO S. P. BROWN
S. K. BERRY

DOC/REA VG-9010	REQ/SLIP 3073-DU	DESCRIPTION NRC Generic Letter 88-17 Decay Heat Removal	
WORK BY <input checked="" type="checkbox"/> SPO <input type="checkbox"/> SPO	CURRENT AUTHORIZATION \$	REQUESTED CHANGE \$	TOTAL REQUESTED AUTHORIZATION \$
DESCRIPTION OF WORK Determine cost and schedule for item 1 (d) of the subject REA. This item is summarized below: Add Ultrasonic Level Transmitters to the RCS Hot Legs.		REQUESTED CHANGE MATERIALS CPL 118 ELECT 221 MET 175 MECH 182 OTHER 4 TOTAL 700	
WORK SIGNED	REP 5/20/89	DATE 9/27 5-24-89	APPROVED DATE

RESPONSE TO WORK AUTHORIZATION REQUEST

FROM: S. H. CHESTNUT
TO: W. C. RAMSEY

- APPROVED AS REQUESTED
 APPROVED WITH FOLLOWING CHANGE:

CHANGE APPROVED \$ _____ NEW TOTAL AUTHORIZATIONS \$ _____

- ADDITIONAL JUSTIFICATION REQUIRED
 DENIED

BUDGET FOR THIS WORK SHOULD BE ALLOCATED FROM _____

COMMENTS:

CC:
SPO
& S. HODGSON
& S. ALPHEUS
SPO FILE
SPO FILE
SPO FILE
SPO FILE
SPO-NOFILE
SPO
S. P. BROWN
S. K. BERRY

REMITTED DATE	APPROVED DATE
------------------	------------------

WORKSHEET

SCOPE SUMMARY

REFERENCE DOCUMENT (RFR/REA) REA VG-9010, ITEM 1(d) REV 0
REFERENCE RFR (IF APPL) N/A
DATE INITIATED 5/24/89

SUMMARY DESCRIPTION THIS SCOPE SUMMARY APPLIES TO ITEM 1(d) OF THE SUBJECT REA. THIS ITEM INVOLVES ADDING ULTRASONIC LEVEL TRANSMITTERS ON THE RCS HOT LEGS.

ATTACHMENTS:

- SCOPE DESCRIPTION
- SCHEDULE DESCRIPTION
- BUDGET SUMMARY

APPROVALS:

	<u>SIGNATURE</u>	<u>DATE</u>
LDEGS	<u>WR. Dickson</u>	<u>5/26/89</u>
NPS-V MGR	<u></u>	<u></u>

SCOPE DESCRIPTION SUMMARY

I. SCOPE TYPE:

- INITIAL SCOPE
 SCOPE REVISION

II. REFERENCE DOCUMENT (DCR/REA/RER):

REA VG-9010

III. DESCRIPTION: THIS SUMMARY DISCUSSES ITEM (d)
OF THE SUBJECT REA: ADD ULTRASONIC LEVEL
TRANSMITTERS TO THE RCS HOT LEGS.

IV. LIST OF DESIGN ACTIVITIES/WORK ITEMS:

- ATTACHED
 N/A

V. LIST OF MATERIALS:

- ATTACHED
 N/A

VI. SPECIAL ITEMS:

VENDOR LITERATURE

- ATTACHED
 N/A

LIST OF DESIGN ACTIVITIES

This would add strap-on ultrasonic level transducers to the bottom of two of the RCS hot legs. The transducers are fed by a triaxial cable from a pre-amplifier assembly and a signal conditioner. The output of the signal conditioner (4 - 20 milliamps) will be routed to the accumulator level transmitters where it will be connected during mid-loop operation. The pre-amplifiers and signal conditioners will require Seismic Category I supports for Seismic Category II over I considerations. Due to radiation degradation, the pre-amplifiers and signal conditioners should either be mounted in a low radiation field or designed for easy removal prior to power operation of the NSSS.

LIST OF MATERIALS

- 2 each Westinghouse Ultrasonic Level Measurement System, Project Class 61J.
- 150 L.F. 3/4 inch diameter rigid steel conduit.
- 100 L.F. Cable, Type CL67.
- 100 L.F. Cable, Tri-axial.
- 2 each Junction boxes.
- 2 each Pull boxes.
- 18 each Conduit supports.
- 4 each Instrument supports.

R	C	ERP	PROIEUS	SIGNAL DESCRIPTION	ORIGINATING	SIGNAL	SIGNAL	CLASS	VAR	CLASS	VIA	SYSTEM	S
V	Y	SYMBOL	SYMBOL		DEVICE	CLASS	CLASS						P
		A7501		CONTAINMENT LEVEL 2 MOISTURE XDUCEH: 4-20MA SCALE: 0 > 100 PERCENT	MTSM-2564	B	FLD	NNS	--	--	MULTI	1501	
		A7502		CONTAINMENT LEVEL B-AREA C MOISTURE XDUCEH: 4-20MA SCALE: 0 > 100 PERCENT	MTSM-2614	B	FLD	NNS	--	--	MULTI	1501	
		A7503		CONTAINMENT LEVEL B-AREA D MOISTURE XDUCEH: 4-20MA SCALE: 0 > 100 PERCENT	MTSM-2615	B	FLD	NNS	--	--	MULTI	1501	
		89872	--	RCS BORON SAMPLE STATUS (1V=OFF, 2V=ON) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		89873	--	RCS LIQUID PH SAMPLE STATUS (1V=OFF, 2V=ON) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		89874	--	RCS DU2 SAMPLE STATUS (1V=OFF, 2V=ON) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		89875	--	RCS DU2 SAMPLE STATUS (1V=OFF, 2V=ON) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		89876	--	RCS DU2 SAMPLE SIGNAL RANGE XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		89877	--	RCS CHLORIDE SAMPLE STATUS (1V=OFF, 2V=ON) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		89878	--	RCS CHLORIDE SAMPLE STATUS (1V=CALIB, 2V=SAMPLE) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		89879	--	RCS CHLORIDE ANAL STATUS (1V=STANDBY, 2V=START) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	LATER	B	PASS	NNS	--	--	MUX	2702	
		C7581	--	CONTAINMENT HYDROGEN CONCENTRATION-TRAIN A XDUCEH: 4-20MA SCALE: 0 > 10 PERCENT	AIT-12979	B	QPCP	I	5.2.86-0	01	RPU A2	1513	X

R	ERP	PROTEUS					ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION				DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM
	C7982	--	CONTAINMENT HYDROGEN CONCENTRATION-TRAIN B				AIT-12988	B	GPCP	II	5.2.06-D	B1 RPU B2 1513	X
			XDUCER: 4-20MA	SCALE: 0 > 10	PERCENT		1143						
	C9257	--	RCS SAMPLING BUNON CONTENT				LATER	B	PASS	NNS	5.2.01-C	C3 MUX	2782
			XDUCER: 4-20MA	SCALE: 0 > 6000	PPM		1148						
*	C9258	--	RCS SAMPLING CHLORIDE CONTENT				LATER	B	PASS	NNS	5.2.01-C	C3 MUX	2782
			XDUCER: 0-1V	SCALE: 0 > 20	PPM		1149						
	C9259	--	RCS SAMPLING DISSOLVED HYDROGEN (DH2)				LATER	B	PASS	NNS	5.2.01-C	C3 MUX	2782
			XDUCER: 4-20MA	SCALE: 0 > 2000	CC/KG		1150						
	C9260	--	RCS SAMPLING DISSOLVED OXYGEN (DO2)				LATER	B	PASS	NNS	5.2.01-C	C3 MUX	2782
			XDUCER: 4-20MA	SCALE: 0 > 2.00E04	PPB		1151						
	C9880	--	CTB AIR HYDROGEN CONCENTRATION				LATER	B	PASS	NNS	--	- MUX	2782
			XDUCER: 4-20MA	SCALE: 0 > 10	PCT VOL		1431						
*	C9881	--	CTB AIR OXYGEN CONCENTRATION				LATER	B	PASS	NNS	--	- MUX	2782
			XDUCER: 4-20MA	SCALE: 0 > 30	PCT VOL		1432						
*	F5106	--	PLANT VENT SAMPLE FLOW				FI-12835	B	PERMS	NNS	5.2.04	E2 MUX	1689
			XDUCER: 4-20MA	SCALE: 3.20E03 > 1.60E05	SCFM		1441						
	F8125	F8125	RCP 4 SEAL INJECTION WATER FLOW				FI-8142	N	PCS	NNS	7.2.03-D	D2 MULT	1288
			XDUCER: 0-10V	SCALE: 0 > 20	GPM		1160						
	F8127	F8127	RCP 3 SEAL INJECTION WATER FLOW				FI-8143	N	PCS	NNS	7.2.03-D	D2 MULT	1288
			XDUCER: 0-10V	SCALE: 0 > 20	GPM		1165						
	F8128	F8128	MAKEUP (CVC8) FLOW				FI-8121	N	PCS	NNS	7.2.03-A	D2 MULT	1288 X
			XDUCER: 0-10V	SCALE: 0 > 200	GPM		1157						
	F8129	F8129	RCP 2 SEAL INJECTION WATER FLOW				FI-8144	N	PCS	NNS	7.2.03-D	D2 MULT	1288
			XDUCER: 0-10V	SCALE: 0 > 20	GPM		1164						

R	ERF	PROTEUS	SIGNAL DESCRIPTION				ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	
Y	SYMBOL	SYMBOL					DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM
*	F0131	F0131	RCP 1 SEAL INJECTION WATER FLOW										
			XDUCE1: 0-10V	SCALE1	0 >	20 GPM	FT-0145	n	PCS	NNS	7.2.03-D	D2 MULT 1200	
								1163					
	F0134	F0134	LETDOWN HEAT EXCH OUTLET FLOW										
			XDUCE1: 0-10V	SCALE1	0 >	200 GPM	FT-0132	n	PCS	NNS	7.2.03-B	D2 MULT 1200 X	
								1159					
	F0400	F0400	PRIMARY COOLANT LOOP 1 FLOW (CH 1)										
			XDUCE1: 0-10V	SCALE1	0 >	120 PERCENT	FT-0414	n	PCS	NNS	--	- MULT 1201	
								1251					
	F0403	F0403	SG1 Fw FLOW										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0510	n	PCS	NNS	7.2.04-G	D2 MULT 1305 X	
								1179					
	F0404	F0404	SG1 Fw FLOW										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0511	n	PCS	NNS	7.2.04-G	D2 MULT 1305 X	
								1175					
	F0405	F0405	SG1 STEAM LINE FLOW 1										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0512	n	PCS	NNS	7.2.04-C	D2 MULT 1301 X	
								1167					
	F0406	F0406	SG1 STEAM LINE FLOW 2										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0513	n	PCS	NNS	7.2.04-C	D2 MULT 1301 X	
								1171					
	F0421	F0421	PRIMARY COOLANT LOOP 2 FLOW (CH 2)										
			XDUCE1: 0-10V	SCALE1	0 >	120 PERCENT	FT-0425	n	PCS	NNS	--	- MULT 1201	
								1252					
	F0423	F0423	SG2 Fw FLOW										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0520	n	PCS	NNS	7.2.04-G	D2 MULT 1305 X	
								1180					
	F0424	F0424	SG2 Fw FLOW										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0521	n	PCS	NNS	7.2.04-G	D2 MULT 1305 X	
								1176					
	F0425	F0425	SG2 STEAM LINE FLOW 1										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0522	n	PCS	NNS	7.2.04-C	D2 MULT 1301 X	
								1172					
	F0426	F0426	SG2 STEAM LINE FLOW 2										
			XDUCE1: 0-10V	SCALE1	0 >	4000 KBH	FT-0523	n	PCS	NNS	7.2.04-C	D2 MULT 1301 X	
								1168					

R	E	EHF	PROTEUS				ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT		S
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION				DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	B
	F0442	F0442	PRIMARY COOLANT LOOP 3 FLOW (CH 3) XDUCEH: 0-10V SCALE: 0 > 120 PERCENT				FT-0436	N	PCS	NNS	--	-	MULT	1201
	F0443	F0443	SG3 Fw FLOW XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0530	N	PCS	NNS	7.2.04-C	D2	MULT	1305 X
	F0444	F0444	SG3 Fw FLOW XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0531	N	PCS	NNS	7.2.04-C	D2	MULT	1305 X
	F0445	F0445	SG3 STEAM LINE FLOW 1 XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0532	N	PCS	NNS	7.2.04-C	D2	MULT	1301 X
	F0446	F0446	SG3 STEAM LINE FLOW 2 XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0533	N	PCS	NNS	7.2.04-C	D2	MULT	1301 X
	F0460	F0460	PRIMARY COOLANT LOOP 4 FLOW (CH 4) XDUCEH: 0-10V SCALE: 0 > 120 PERCENT				FT-0444	N	PCS	NNS	--	-	MULT	1201
	F0463	F0463	SG4 Fw FLOW XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0540	N	PCS	NNS	7.2.04-C	D2	MULT	1305 X
	F0464	F0464	SG4 Fw FLOW XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0541	N	PCS	NNS	7.2.04-C	D2	MULT	1305 X
	F0465	F0465	SG4 STEAM LINE FLOW 1 XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0542	N	PCS	NNS	7.2.04-C	D2	MULT	1301 X
	F0466	F0466	SG4 STEAM LINE FLOW 2 XDUCEH: 0-10V SCALE: 0 > 4000 KBH				FT-0543	N	PCS	NNS	7.2.04-C	D2	MULT	1301 X
	F0626	F0626	RHR TRAIN A COOLANT FLOW XDUCEH: 0-10V SCALE: 0 > 5000 GPM				FT-0618	N	PCS	NNS	7.2.10-C	D2	MULT	1205 X
	F0627	F0627	RHR TRAIN B COOLANT FLOW XDUCEH: 0-10V SCALE: 0 > 5000 GPM				FT-0619	N	PCS	NNS	7.2.10-C	D2	MULT	1205 X

REF SYMBOL	PHUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
F5918	F0918	SAFETY INJECTION PUMP TRAIN A FLOW XDUCEH: 0-10V SCALE: 0 > 500 GPM	FT-0918	n 1183	PCS	III	7.2.05-C D2 RPU A3 1204			
F5920	F0920	CHARGING PUMPS FLOW TO B1 TANK XDUCEH: 0-10V SCALE: 0 > 1000 GPM	FT-0917	n 1185	PCS	IV	7.2.03-A D2 HPU B3 1204			
F5922	F0922	SAFETY INJECTION PUMP TRAIN B FLOW XDUCEH: 0-10V SCALE: 0 > 500 GPM	FT-0922	n 1184	PCS	II	7.2.05-C D2 RPU B2 1204			
* F6418	--	FT-0018 WASTE LIQUID EFFLUENT FLOW XDUCEH: RS-232C SCALE: 0 > 2.25E02	FT-0018	n 1382	PERMS	-	-- - PERMS 1009 (PERMS DOC. SHOWS ORG. DEVICE OF FE-,NOT FT-)			
F6411	--	FT-0021 STEAM GEN BLOWDOWN LIQUID FLOW XDUCEH: RS-232C SCALE: 1.25E02 > 1.25E03	FT-0021	n 1383	PERMS	-	-- - PERMS 1009 (PERMS DOC. SHOWS ORG. DEVICE OF FE-,NOT FT-)			
* F6416	--	AFT-0014 WGPS GAS DISCHARGE FLOW XDUCEH: RS-232C SCALE: 2.00E-01 > 2.00E00	AFT-0014	n 1306	PERMS	-	-- - PERMS 1902 (UNIT 1 INPUT ONLY;PERMS DOC. SHOWS FE-,NOT FT-)			
F6417	--	FT-12442 PLANT VENT EFFLUENT LOW RANGE FLOW XDUCEH: RS-232C SCALE: 0 > 3.00E05	FT-12442	n 1229	PERMS	-	8.2.04 E2 PERMS 1009 (PERMS DOC. SHOWS ORG. DEVICE OF FE-,NOT FT-)			
F6419	--	AFT-026 WASTE SOLIDIFICATION BLDG EFFLUENT FLOW XDUCEH: RS-232C SCALE: 0 > 4.00E04	AFT-026	n 1230	PERMS	-	-- - PERMS 1009 (UNIT 1 INPUT ONLY;PERMS DOC. SHOWS FE-,NOT FT-)			
F6420	--	FT-2565 CONTAINMENT VENT EFFLUENT FLOW XDUCEH: RS-232C SCALE: 0 > 2.07E04	FT-2565	n 1387	PERMS	-	-- - PERMS 1009 (PERMS DOC. SHOWS ORG. DEVICE OF FE-,NOT FT-)			
F6421	--	FT-12639 COND SR AIR EJECTR-SIM PKG EFFLUENT FLOW XDUCEH: RS-232C SCALE: 0 > 5.67E03	FT-12639	n 1231	PERMS	-	-- - PERMS 1009 (PERMS DOC. SHOWS ORG. DEVICE OF FE-,NOT FT-)			
F7326	F2326	SG1 AUX FW FLOW XDUCEH: 0-10V SCALE: 0 > 500 GPM	FT-5152	n 1062	PCS-BOP	I	4.2.12 A1 RPU A2 1302 X			
F7327	F2327	SG2 AUX FW FLOW XDUCEH: 0-10V SCALE: 0 > 500 GPM	FT-5151	n 1063	PCS-BOP	II	4.2.12 A1 RPU B2 1302 X			

VOLUME 1 REG GUIDE 1 7/ERF INPUT LIST

R	E	ERF	PROTEUS	SIGNAL DESCRIPTION			ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S
V	SYMBOL	SYMBOL				DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	S
	F7328	F2328	3G3 AUX FM FLOW	SCALE:	0 > 500 GPM	FI-5153	W	PCS-80P	II	4.2.12	A1 RPU B2	1302	X
			XDUCER: 0-10V				1864						
	F7329	F2329	3G4 AUX FM FLOW	SCALE:	0 > 500 GPM	FI-5150	W	PCS-80P	I	4.2.12	A1 RPU A2	1302	X
			XDUCER: 0-10V				1865						
	F7391	F2391	FM PUMP A SUCTION FLOW	SCALE:	0 > 2.00E04	FI-5200	W	PCS-80P	NNS	--	-	MULT	1305
			XDUCER: 0-10V			GPM	1376						
	F7411	F2411	FM PUMP B SUCTION FLOW	SCALE:	0 > 2.00E04	FI-5201	W	PCS-80P	NNS	--	-	MULT	1305
			XDUCER: 0-10V			GPM	1377						
	F7475	F2475	CONDENSATE PUMPS FLOW	SCALE:	0 > 2.50E04	FI-4486	W	PCS-80P	NNS	--	-	MULT	1305
			XDUCER: 0-10V			GPM	1373						
	F7601	F2601	N3CW TRAIN A SUPPLY HEADER FLOW	SCALE:	0 > 2.50E04	FI-1640B	W	PCS-80P	NNS	7.2.09-A	D2 RPU N1	1202	
			XDUCER: 0-10V			GPM	1195						
	F7602	F2602	N3CW TRAIN B SUPPLY HEADER FLOW	SCALE:	0 > 2.50E04	FI-1641B	W	PCS-80P	NNS	7.2.09-A	D2 RPU N1	1202	
			XDUCER: 0-10V			GPM	1196						
	F7603	F2603	N3CW TRAIN A RETURN HEADER FLOW	SCALE:	0 > 2.50E04	FI-1640A	W	PCS-80P	NNS	--	-	RPU N1	1202
			XDUCER: 0-10V			GPM	1349						
	F7604	F2604	N3CW TRAIN B RETURN HEADER FLOW	SCALE:	0 > 2.50E04	FI-1641A	W	PCS-80P	NNS	--	-	RPU N1	1202
			XDUCER: 0-10V			GPM	1350						
	F7671	F2671	CCW FLOW TRAIN A	SCALE:	0 > 1.50E04	FI-1876	W	PCS-80P	NNS	7.2.08-D	D2 RPU N1	1203	
			XDUCER: 0-10V			GPM	1193						
	F7672	F2672	CCW FLOW TRAIN B	SCALE:	0 > 1.50E04	FI-1877	W	PCS-80P	NNS	7.2.08-D	D2 RPU N1	1203	
			XDUCER: 0-10V			GPM	1194						
	F771W	--	ACCW FLOW	SCALE:	0 > 1.00E04	FI-1976	B	FLO	NNS	--	-	MUX	1217
			XDUCER: 4-20MA			GPM	1358						

REF	PHUTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	HG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
* F9268	--	CHARGING PUMP A FLOW XDUCE: 0-10V SCALE: 0 > 150 GPM	FT-0138	n	PCS	NNS	7.2.03-A D2	MULT	1208	
F9269	--	REACTOR HEAD VENT LETDOWN LINE FLOW XDUCE: 0-10V SCALE: 0 > 80 GPM	FT-0406	n	PCS	NNS	7.2.03-B D2	MULT	1208	
F9270	--	REACTOR HEAD VENT LETDOWN LINE FLOW XDUCE: 0-10V SCALE: 0 > 80 GPM	FT-0407	n	PCS	NNS	7.2.03-B D2	MULT	1208	
F9489	--	SPRAY ADDITIVE TANK OUTLET FLOW XDUCE: 0-5V SCALE: 0 > 300 GPM	FT-0930	n	PCS	NNS	7.2.07-A D2	RPU N1	1206	
F9627	--	SG1 AUX FM FLOW XDUCE: 4-20MA SCALE: 0 > 600 GPM	FT-15152	B	FLD	II	4.2.12	A1 RPU B2	1302	X
F9628	--	SG2 AUX FM FLOW XDUCE: 4-20MA SCALE: 0 > 600 GPM	FT-15151	B	FLD	I	4.2.12	A1 RPU A2	1302	X
F9629	--	SG3 AUX FM FLOW XDUCE: 4-20MA SCALE: 0 > 600 GPM	FT-15153	B	FLD	I	4.2.12	A1 RPU A2	1302	X
F9630	--	SG4 AUX FM FLOW XDUCE: 4-20MA SCALE: 0 > 600 GPM	FT-15150	B	FLD	II	4.2.12	A1 RPU B2	1302	X
F9641	--	AFT-2532 FUEL HANDLING BLDG VENT EFFLUENT FLOW XDUCE: RS-232C SCALE: 0 > 1,34E04	AFT-2532	n	PERMS	-	-	-	PERMS 1000	
			CFM	1308						(UNIT 1 INPUT ONLY; PERMS DOC. SHOWS FE-, NOT FT-)
F9642	--	AFT-2533 FUEL HANDLING BLDG VENT EFFLUENT FLOW XDUCE: RS-232C SCALE: 0 > 1,34E04	AFT-2533	n	PERMS	-	-	-	PERMS 1000	
			CFM	1309						(UNIT 1 INPUT ONLY; PERMS DOC. SHOWS FE-, NOT FT-)
H5190	H0190	CHARGING PUMP TRAIN A THROTTLE VALVE XDUCE: 0-10V SCALE: 0 > 100 PERCENT	HV-0190A	n	PCS	NNS	7.2.03-E D2	MUX	1208	
				1133						(SEPERATE INPUT SIGNAL TO PROTEUS)
H5191	H0191	CHARGING PUMP TRAIN B THROTTLE VALVE XDUCE: 0-10V SCALE: 0 > 100 PERCENT	HV-0190B	n	PCS	NNS	7.2.03-E D2	MUX	1208	
				1134						(SEPERATE INPUT SIGNAL TO PROTEUS)

Y	ERF SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
	H5442	H0442	LETDOWN TO PRT TRN A THROTTLE VLV XDUCER: 0-10V SCALE: 0 > 100 PERCENT	HV-0442A	0	PCS	NNS	7.2.05-E D2 MUX	1200	(SEPERATE INPUT SIGNAL TO PRUTEUS)	
*	H5443	H0443	LETDOWN TO PRT TRN B THROTTLE VLV XDUCER: 0-10V SCALE: 0 > 100 PERCENT	HV-0442B	0	ASI	NNS	7.2.05-E D2 MUX	1200	(SEPERATE INPUT SIGNAL TO PRUTEUS)	
	H5943	H0943	S1 ACCUM TANK N2 HDR VENT VLV TRN A XDUCER: 0-10V SCALE: 0 > 100 PERCENT	HV-0943A	0	PCS	NNS	7.2.05-E D2 MUX	1204	(SEPERATE INPUT SIGNAL TO PRUTEUS)	
	H5944	H0944	S1 ACCUM TANK N2 HDR VENT VLV TRN B XDUCER: 0-10V SCALE: 0 > 100 PERCENT	HV-0943B	0	ASI	NNS	7.2.05-E D2 MUX	1204	(SEPERATE INPUT SIGNAL TO PRUTEUS)	
	J7835	--	PRESSURIZER HEATER NB0105 CURRENT XDUCER: 0-1MA SCALE: 0 > 800 AMPS	XDCR-A	0	SMGR	NNS	7.2.02-C D2 MUX	1201		
	J7836	--	PRESSURIZER HEATER NB1005 CURRENT XDUCER: 0-1MA SCALE: 0 > 800 AMPS	XDCR-A	0	SMGR	NNS	7.2.02-C D2 MUX	1201		
	J8501	--	RCP 1 AMPS XDUCER: 0-1MA SCALE: 0 > 400 AMPS	XDRA	0	SMGR	NNS	-- - MUX	1020	E/D1-80-001A	
	J8502	--	RCP 2 AMPS XDUCER: 0-1MA SCALE: 0 > 400 AMPS	XDRA	0	SMGR	NNS	-- - MUX	1025	E/D1-80-001B	
	J8503	--	RCP 3 AMPS XDUCER: 0-1MA SCALE: 0 > 400 AMPS	XDRA	0	SMGR	NNS	-- - MUX	1025	E/D1-80-001C	
*	J8504	--	RCP 4 AMPS XDUCER: 0-1MA SCALE: 0 > 400 AMPS	XDRA	0	SMGR	NNS	-- - MUX	1025	E/D1-80-001D	
	J9613	--	4KV 1E BUS 1AA02 OFFSITE NORM LINE CURRENT XDUCER: 0-1MA SCALE: 0 > 2000 AMPS	XCDR-A	0	WEAB	I	7.2.12 D2 RPU A2	1004	E/D1-8A-002B	
	J9614	--	4KV 1E BUS 1AA02 OFFSITE EMERGENCY LINE CURRENT XDUCER: 0-1MA SCALE: 0 > 2000 AMPS	XCDN-A	0	WEAB	I	7.2.12 D2 RPU A2	1004	E/D1-8A-002C	

R	E	PROTEUS	SIGNAL DESCRIPTION		ORIGINATING	Y	SIGNAL	SIGNAL	RG 1.97	INPUT	S
V	SYMBOL	SYMBOL			DEVICE		SOURCE	CLASS	VAR CLASS	VIA	SYSTEM
	J9610	--	4KV 1E BUS 18A03 OFFSITE NORM LINE CURRENT	XCDR-A	B	WEAB	II	7.2.12	D2 RPU B2 1804		
			XDUCER: 0-1MA SCALE: 0 > 2000 AMPS		1283	E/D1-BA-083B					
	J9617	--	4KV 1E BUS 18A03 OFFSITE EMERGENCY LINE CURRENT	XCDR-A	B	WEAB	II	7.2.12	D2 RPU B2 1804		
			XDUCER: 0-1MA SCALE: 0 > 2000 AMPS		1284	E/D1-BA-083C					
*	J9619	--	CLASS 1E 125VDC BATTERY 1A01B CURRENT	XCDR-A	B	SWGR	I	7.2.12	D2 RPU A2 1806		
			XDUCER: 4-20MA SCALE: -800 > 2000 AMPS		1286	E/D1-BA-H01A					
*	J9620	--	CLASS 1E 125VDC BATTERY 1B01B CURRENT	XCDR-A	B	SWGR	II	7.2.12	D2 RPU B2 1806		
			XDUCER: 4-20MA SCALE: -800 > 2000 AMPS		1287	E/D1-BA-H02A					
*	J9621	--	CLASS 1E 125VDC BATTERY 1C01B CURRENT	XCDR-A	B	SWGR	III	7.2.12	D2 RPU A3 1806		
			XDUCER: 4-20MA SCALE: -600 > 600 AMPS		1288	E/D1-BA-H03A					
*	J9622	--	CLASS 1E 125VDC BATTERY 1D01B CURRENT	XCDR-A	B	SWGR	IV	7.2.12	D2 RPU B3 1806		
			XDUCER: 4-20MA SCALE: -400 > 400 AMPS		1289	E/D1-BA-H04A					
	L5112	L0112	VCT LEVEL CH 1	LT-0512	N	PCS	NB	--	- MUL: 1200		
			XDUCER: 0-10V SCALE: 0 > 100 PERCENT		1344						
	L5400	L0400	SG1 LEVEL NARROW RANGE CH 4	LT-0517	N	PCS	IV	4.2.05	A1 RPU B3 1301 X		
			XDUCER: 0-10V SCALE: 0 > 100 PERCENT		1012						
	L5401	L0401	SG1 LEVEL NARROW RANGE CH 3	LT-0518	N	PCS	III	4.2.05	A1 RPU A3 1301 X		
			XDUCER: 0-10V SCALE: 0 > 100 PERCENT		1013						
	L5402	L0402	SG1 LEVEL NARROW RANGE CH 2	LT-0519	N	PCS	II	4.2.05	A1 RPU B2 1301 X		
			XDUCER: 0-10V SCALE: 0 > 100 PERCENT		1014						
	L5403	L0403	SG1 LEVEL NARROW RANGE CH 1	LT-0501	N	PCS	I	4.2.05	A1 RPU A2 1301 X		
			XDUCER: 0-10V SCALE: 0 > 100 PERCENT		1045						
	L5404	L0404	SG1 LEVEL WIDE RANGE CH 1	LT-0501	N	PCS	I	4.2.04	A1 RPU A2 1301 X		
			XDUCER: 0-10V SCALE: 0 > 100 PERCENT		1008						

R	ERP	PROTEUS				ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT		B
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION			DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	B
L5420	L0420	3G2 LEVEL NARROW RANGE CH 4	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0527	W	1015	PCS	IV	4.2.05	A1 RPU B3 1301	X	
L5421	L0421	3G2 LEVEL NARROW RANGE CH 3	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0528	W	1016	PCS	III	4.2.05	A1 RPU A3 1301	X	
L5422	L0422	3G2 LEVEL NARROW RANGE CH 1	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0529	W	1017	PCS	I	4.2.05	A1 RPU A2 1301	X	
L5423	L0423	3G2 LEVEL NARROW RANGE CH 2	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0552	W	1046	PCS	II	4.2.05	A1 RPU B2 1301	X	
L5424	L0424	3G2 LEVEL WIDE RANGE CH 2	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0502	W	1009	PCS	II	4.2.04	A1 RPU B2 1301	X	
L5440	L0440	3G3 LEVEL NARROW RANGE CH 4	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0537	W	1010	PCS	IV	4.2.05	A1 RPU B3 1301	X	
L5441	L0441	3G3 LEVEL NARROW RANGE CH 3	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0538	W	1019	PCS	III	4.2.05	A1 RPU A3 1301	X	
L5442	L0442	3G3 LEVEL NARROW RANGE CH 1	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0539	W	1020	PCS	I	4.2.05	A1 RPU A2 1301	X	
L5443	L0443	3G3 LEVEL NARROW RANGE CH 2	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0563	W	1129	PCS	II	4.2.05	A1 RPU B2 1301	X	
L5444	L0444	3G3 LEVEL WIDE RANGE CH 3	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0503	W	1010	PCS	III	4.2.04	A1 RPU B2 1301	X	
L5460	L0460	3G4 LEVEL NARROW RANGE CH 4	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0547	W	1021	PCS	IV	4.2.05	A1 RPU B3 1301	X	
L5461	L0461	3G4 LEVEL NARROW RANGE CH 3	XDUCER: 0-10V SCALE: 0 > 100 PERCENT		LT-0548	W	1022	PCS	III	4.2.05	A1 RPU A3 1301	X	

R	E	REF	PROTEUS	SIGNAL DESCRIPTION			ORIGINATING	B	SIGNAL	SIGNAL	WG 1.97	INPUT		B
V		SYMBOL	SYMBOL				DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	S
		L5462	L0462	SG4 LEVEL NARROW RANGE CH 2			LT-8849	W	PCS	II	4.2.05	A1 RPU 02 1301	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1023						
		L5463	L0463	SG4 LEVEL NARROW RANGE CH 1			LT-8854	W	PCS	I	4.2.05	A1 RPU A2 1301	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1130						
		L5464	L0464	SG4 LEVEL WIDE RANGE CH 4			LT-8584	W	PCS	IV	4.2.04	A1 RPU A3 1301	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1011						
		L5480	L0480	PRESSURIZER LEVEL (CH 1)			LT-8459	W	PCS	I	4.2.00	A1 RPU A2 1201	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1024						
		L5481	L0481	PRESSURIZER LEVEL (CH 2)			LT-8460	W	PCS	II	4.2.00	A1 RPU B2 1201	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1025						
		L5482	L0482	PRESSURIZER LEVEL (CH 3)			LT-8461	W	PCS	III	4.2.00	A1 RPU A3 1201	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1026						
		L5485	L0485	PRESSURIZER RELIEF TANK LEVEL			LT-8470	W	PCS	NNS	--	- MULT 1201		
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1259						
*		L6130	--	RWST LEVEL CHANNEL 1			LT-8990	W	PCS	I	4.2.09	A1 RPU A2 1204	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1043						
*		L6131	--	RWST LEVEL CHANNEL 2			LT-8991	W	PCS	II	4.2.09	A1 RPU 02 1204	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1044						
*		L6132	--	RWST LEVEL CHANNEL 3			LT-8992	W	PCS	III	4.2.09	A1 RPU A3 1204	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1047						
*		L6133	--	RWST LEVEL CHANNEL 4			LT-8993	W	PCS	IV	4.2.09	A1 RPU B3 1204	X	
				XDUCEH: 0-10V	SCALE:	0 > 100 PERCENT		1048						
		L8175	--	PRIMARY MET TOWER PRECIPITATION			NR TWR	B	MET TOWER NNS	NNS	8.2.00	E3 MUX 2001		
				XDUCEH: 0-5V	SCALE:	0 > 1 INCHES		1237				(UNIT 1 INPUT ONLY)		

GEORGIA POWER COMPANY-ENGINEERING & CONSTRUCTION SERVICES REVISION W7.05 12/11/88 #AGB 0121
 VOGTLE 1 REG GUIDE 7/ERF INPUT LIST

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM B	S P D
L6300	--	VCT LEVEL CH 4 XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LT-8185	n	F.3	NNS	7.2.03-C D2	MULT	1288	
L6320	--	BORIC ACID STORAGE TANK LEVEL CH 4 XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LT-8184	n	PCS	IV	--	- RPU B3	1288	
L6321	--	BORIC ACID STORAGE TANK LEVEL CH 1 XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LT-8182	n	PCS	I	--	- RPU A2	1288	
* L7409	L2489	CONDENSATE STORAGE TANK 1 LEVEL XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LT-5111	n	PCS-BOP	I	4.2.11	A1 RPU A2	1382	x
* L7490	L2490	CONDENSATE STORAGE TANK 2 LEVEL XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LT-5116	n	PCS-BOP	I	4.2.11	A1 RPU A2	1382	x
* L7501	--	REACTION CAVITY SUMP LEVEL XDUCE: 4-20MA SCALE: 0 > 48 INCHES	LT-7778	B	FLO	I	--	- RPU A3	1214	x
* L7502	--	CONTAINMENT SOUTH SUMP LEVEL XDUCE: 4-20MA SCALE: 0 > 48 INCHES	LT-7777	B	FLO	I	4.2.10	A1 RPU A2	1214	
* L7503	--	CONTAINMENT NORTH SUMP LEVEL XDUCE: 4-20MA SCALE: 0 > 48 INCHES	LT-7789	B	FLO	II	4.2.10	A1 RPU B2	1214	
L7601	L2601	NSCW BASIN LEVEL TOWER A XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LT-1686	n	PCS-BOP	NNS	--	- MULT	1282	
L7602	L2602	NSCW BASIN LEVEL TOWER B XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LT-1687	n	PCS-BOP	NNS	--	- MULT	1282	
L7671	L2671	CCW SUDGE TANK LEVEL TRAIN A XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LIT-1846	n	PCS-BOP	NNS	7.2.00-C D2	RPU N1	1283	
L7672	L2672	CCW SUDGE TANK LEVEL TRAIN B XDUCE: 0-10V SCALE: 0 > 100 PERCENT	LIT-1847	n	PCS-BOP	NNS	7.2.00-C D2	RPU N1	1283	

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.07 VAR CLASS	INPUT VIA	SYSTEM	S
L7700	L2700	ACC# SURGE TANK LEVEL XDUCE# 0-10V SCALE# 0 > 100 PERCENT	LIT-11953	W	PCB-BOP	NNS	--	- MULT	1217	
* L9003	--	CONTAINMENT EMERG FLOOR DRAINS LEVEL-TRAIN A XDUCE# 0-10V SCALE# 0 > 120 INCHES	LT-0764	W	PCB-BOP	I	4.2.10	A1 RPU A2	1205	X
* L9004	--	CONTAINMENT EMERG FLOOR DRAINS LEVEL-TRAIN B XDUCE# 0-10V SCALE# 0 > 120 INCHES	LT-0765	W	PCB-BOP	II	4.2.10	A1 RPU B2	1205	X
* L9005	--	CONDENSATE STORAGE TANK 1 LEVEL XDUCE# 0-10V SCALE# 0 > 100 PERCENT	LT-5101	W	PCB-BOP	II	4.2.11	A1 RPU B2	1302	X
* L9006	--	CONDENSATE STORAGE TANK 2 LEVEL XDUCE# 0-10V SCALE# 0 > 100 PERCENT	LT-5104	W	PCB-BOP	II	4.2.11	A1 RPU B2	1302	X
* L9659	--	RVLIS UPPER RANGE DP TRAIN A XDUCE# 4-20MA SCALE# -7 > -1 IN WATER	LT-1310	W	FLO	III	5.2.03-B B1	RPU A3	1201	(RANGE=-7.986>-1.361)
* L9660	--	RVLIS FULL RANGE DP TRAIN A XDUCE# 4-20MA SCALE# -19 > -1 IN WATER	LT-1311	W	FLO	III	5.2.03-B B1	RPU A3	1201	(RANGE=-19.224>-1.361)
* L9661	--	RVLIS DYNAMIC HEAD DP TRAIN A XDUCE# 4-20MA SCALE# -19 > 39 IN WATER	LT-1312	W	FLO	III	5.2.03-B B1	RPU A3	1201	(RANGE=-19.224>39.773)
* L9662	--	RVLIS UPPER RANGE DP TRAIN B XDUCE# 4-20MA SCALE# -7 > -1 IN WATER	LT-1320	W	FLO	IV	5.2.03-B B1	RPU B3	1201	(RANGE=-7.986>-1.361)
* L9663	--	RVLIS FULL RANGE DP TRAIN B XDUCE# 4-20MA SCALE# -19 > -1 IN WATER	LT-1321	W	FLO	IV	5.2.03-B B1	RPU B3	1201	(RANGE=-19.224>-1.361)
* L9664	--	RVLIS DYNAMIC HEAD DP TRAIN B XDUCE# 4-20MA SCALE# -19 > 39 IN WATER	LT-1322	W	FLO	IV	5.2.03-B B1	RPU B3	1201	(RANGE=-19.224>39.773)
L9661	--	RVLIS STATIC HEAD UPPER RANGE TRAIN A XDUCE# RS-422 SCALE# 0 > 120 % LEVEL	CALC-DPUA	W	-	-	5.2.01-B C2	DPUA	1201	X

R	E	Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
			L9862	--	RVLIS STATIC HEAD FULL RANGE TRAIN A XDUCEH: RS-422 SCALE: 0 > 120 X LEVEL	CALC-DPUA	W 1256	-	-	6.2.01-B C2 DPUA	1281	X	
			L9863	--	RVLIS DYNAMIC HEAD TRAIN A XDUCEH: RS-422 SCALE: 0 > 120 X LIQUID	CALC-DPUA	W 1258	-	-	6.2.01-B C2 DPUA	1281	X	
			L9864	--	RVLIS STATIC HEAD UPPER RANGE TRAIN B XDUCEH: RS-422 SCALE: 60 > 120 X LEVEL	CALC-DPUB	W 1255	-	-	6.2.01-B C2 DPUB	1281	X	
			L9865	--	RVLIS STATIC HEAD FULL RANGE TRAIN B XDUCEH: RS-422 SCALE: 0 > 120 X LEVEL	CALC-DPUB	W 1257	-	-	6.2.01-B C2 DPUB	1281	X	
			L9866	--	RVLIS DYNAMIC HEAD TRAIN B XDUCEH: RS-422 SCALE: 0 > 120 X LIQUID	CALC-DPUB	W 1331	-	-	6.2.01-B C2 DPUB	1281	X	
*			N5031	N0031	NEUTRON FLUX SOURCE RANGE 1 COUNT RATE XDUCEH: 0-5V SCALE: 1.00E00 > 1.00E06	NM-031F CPS	W 1245	NIS	NNS	-- - MULT	1602	X	
*			N5032	N0032	NEUTRON FLUX SOURCE RANGE 2 COUNT RATE XDUCEH: 0-5V SCALE: 1.00E00 > 1.00E06	NM-032F CPS	W 1246	NIS	NNS	-- - MULT	1602	X	
*			N5035	N0035	NEUTRON FLUX INTERMEDIATE RANGE 1 COUNT RATE XDUCEH: 0-5V SCALE: 1.00E-11 > 1.00E-03	NM-35B AMPS	W 1243	NIS	NNS	-- - MULT	1602	X	
*			N5036	N0036	NEUTRON FLUX INTERMEDIATE RANGE 2 COUNT RATE XDUCEH: 0-5V SCALE: 1.00E-11 > 1.00E-03	NM-36B AMPS	W 1244	NIS	NNS	-- - MULT	1602	X	
			N5049	N0049	NEUTRON FLUX POWER RANGE (CH 1) XDUCEH: 0-5V SCALE: 0 > 120 PERCENT	NM-41F	W 1242	NIS	NNS	-- - MULT	1602	X	
			N5050	N0050	NEUTRON FLUX POWER RANGE (CH 2) XDUCEH: 0-5V SCALE: 0 > 120 PERCENT	NM-42F	W 1407	NIS	NNS	-- - MULT	1602	X	
			N5051	N0051	NEUTRON FLUX POWER RANGE (CH 3) XDUCEH: 0-5V SCALE: 0 > 120 PERCENT	NM-43F	W 1408	NIS	NNS	-- - MULT	1602	X	

VOLUME 1 REG GUIDE 7/ERF INPUT LIST

R	E	V	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S
*			N5052	N0052	NEUTRON FLUX POWER RANGE (LH 4) XDUCE: 0-5V SCALE: 0 > 120 PERCENT	NM-44F	W 1489	NIS	NNS	--	- MULT	1602	X
*			N9643	--	NEUTRON FLUX HIGH RANGE-TRN A XDUCE: 0-10V SCALE: 1.00E-03 > 2.00E02	RE-13135A2 PERCENT	W 1136	NIS	I	5.2.01-A	01 RPU A2	1602	X
*			N9653	--	NEUTRON FLUX LOW RANGE-TRN A XDUCE: 0-10V SCALE: 1.00E-01 > 1.00E00	RE-13135A1 CPS	W 1131	NIS	I	5.2.01-A	01 RPU A2	1602	X
*			N9658	--	NEUTRON FLUX HIGH RANGE-TRN B XDUCE: 0-10V SCALE: 1.00E-03 > 2.00E02	RE-13135B2 PERCENT	W 1137	NIS	II	5.2.01-A	01 RPU 02	1602	X
*			N9668	--	NEUTRON FLUX LOW RANGE-TRN B XDUCE: 0-10V SCALE: 1.00E-01 > 1.00E00	RE-13135B1 CPS	W 1132	NIS	II	5.2.01-A	01 RPU 02	1602	X
			N9867	--	NEUT FLUX STARTUP RATE LOW RANGE-TRAIN A XDUCE: 0-10V SCALE: -1.00E00 > 5.00E00	RE-13135A3 DKCM	W 1335	NIS	I	--	- RPU A2	1602	
			N9868	--	NEUT FLUX STARTUP RATE HIGH RANGE-TRAIN A XDUCE: 0-10V SCALE: -1.00E00 > 5.00E00	RE-13135A4 DKCM	W 1337	NIS	I	--	- RPU A2	1602	
			N9869	--	NEUT FLUX STARTUP RATE LOW RANGE-TRAIN B XDUCE: 0-10V SCALE: -1.00E00 > 5.00E00	RE-13135B3 DKCM	W 1339	NIS	II	--	- RPU 02	1602	
			N9870	--	NEUT FLUX STARTUP RATE HIGH RANGE-TRAIN B XDUCE: 0-10V SCALE: -1.00E00 > 5.00E00	RE-13135B4 DKCM	W 1340	NIS	II	--	- RPU 02	1602	
			P0130	P0130	LETDOWN HEAT EXCH OUTLET PRESS XDUCE: 0-10V SCALE: 0 > 800 PSIG	PT-0131	W 1363	PCS	NNS	--	- MULT	1200	
			P0142	P0142	CHARGING PUMPS DISCHARGE PRESSURE XDUCE: 0-10V SCALE: 0 > 3500 PSIG	PT-0120	W 1343	PCS	NNS	--	- MULT	1200	
*			P0398	P0398	MAIN TURBINE FIRST STAGE PRESSURE XDUCE: 0-10V SCALE: 0 > 120 PCT POWER	PT-0505	W 1221	PCS	I	7.2.14	02 RPU A2	1301	

R	E	Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	S P D SYSTEM B
*			P5399	P0399	MAIN TURBINE FIRST STAGE PRESSURE XDUCE: 0-10V SCALE: 0 > 120 PCT POWER	PT-0506	W 1222	PCS	II	7.2.14	02 RPU 02 1301	
			P5400	P0400	SG1 PRESSURE OUT (CH 1) XDUCE: 0-10V SCALE: 0 > 1300 PSIG	PT-0514	W 1031	PCS	I	4.2.08	A1 RPU A2 1301	X
			P5401	P0401	SG1 PRESSURE OUT (CH 2) XDUCE: 0-10V SCALE: 0 > 1300 PSIG	PT-0515	W 1032	PCS	II	4.2.08	A1 RPU 02 1301	X
			P5402	P0402	SG1 PRESSURE OUT (CH 4) XDUCE: 0-10V SCALE: 0 > 1300 PSIG	PT-0516	W 1033	PCS	IV	4.2.08	A1 RPU 03 1301	X
			P5408	P0408	RCS PRESS WIDE RANGE CH 3 XDUCE: 0-10V SCALE: 0 > 3000 PSIG	PT-0408	W 1051	PCS	III	4.2.01	A1 RPU A3 1201	X
			P5410	P0410	RCS PRESS WIDE RANGE CH 4 XDUCE: 0-10V SCALE: 0 > 3000 PSIG	PT-0410	W 1052	PCS	IV	4.2.01	A1 RPU 03 1201	X
			P5420	P0420	SG2 PRESSURE OUT (CH 1) XDUCE: 0-10V SCALE: 0 > 1300 PSIG	PT-0524	W 1034	PCS	I	4.2.08	A1 RPU A2 1301	X
			P5421	P0421	SG2 PRESSURE OUT (CH 2) XDUCE: 0-10V SCALE: 0 > 1300 PSIG	PT-0525	W 1035	PCS	II	4.2.08	A1 RPU 02 1301	X
			P5422	P0422	SG2 PRESSURE OUT (CH 3) XDUCE: 0-10V SCALE: 0 > 1300 PSIG	PT-0526	W 1036	PCS	III	4.2.08	A1 RPU A3 1301	X
			P5428	P0428	RCS PRESS WIDE RANGE CH 2 XDUCE: 0-10V SCALE: 0 > 3000 PSIG	PT-0428	W 1050	PCS	II	4.2.01	A1 RPU 02 1201	X
			P5436	P0436	RCS PRESS WIDE RANGE CH 1 XDUCE: 0-10V SCALE: 0 > 3000 PSIG	PT-0436	W 1049	PCS	I	4.2.01	A1 RPU A2 1201	X
			P5440	P0440	SG3 PRESSURE OUT (CH 1) XDUCE: 0-10V SCALE: 0 > 1300 PSIG	PT-0534	W 1037	PCS	I	4.2.08	A1 RPU A2 1301	X

REF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S
P5441	P0441	SG3 PRESSURE OUT (CH 2) XDUCEr: 0-10V SCALE: 0 > 1300 PSIG	PT-0535	n	PCS	II	4.2.08	A1 RPU 02 1301	X	P
P5442	P0442	SG3 PRESSURE OUT (CH 3) XDUCEr: 0-10V SCALE: 0 > 1300 PSIG	PT-0536	n	PCS	III	4.2.08	A1 RPU A3 1301	X	D
P5460	P0460	SG4 PRESSURE OUT (CH 1) XDUCEr: 0-10V SCALE: 0 > 1300 PSIG	PT-0544	n	PCS	I	4.2.08	A1 RPU A2 1301	X	S
P5461	P0461	SG4 PRESSURE OUT (CH 2) XDUCEr: 0-10V SCALE: 0 > 1300 PSIG	PT-0545	n	PCS	II	4.2.08	A1 RPU 02 1301	X	
P5462	P0462	SG4 PRESSURE OUT (CH 4) XDUCEr: 0-10V SCALE: 0 > 1300 PSIG	PT-0546	n	PCS	IV	4.2.08	A1 RPU 03 1301	X	
P5480	P0480	PRESSURIZER PRESSURE (CH 1) XDUCEr: 0-10V SCALE: 1700 > 2500 PSIG	PT-0455	n	PCS	NNS	7.2.02-F 02	MULT 1201	X	
P5481	P0481	PRESSURIZER PRESSURE (CH 2) XDUCEr: 0-10V SCALE: 1700 > 2500 PSIG	PT-0456	n	PCS	NNS	7.2.02-F 02	MULT 1201	X	
P5482	P0482	PRESSURIZER PRESSURE (CH 3) XDUCEr: 0-10V SCALE: 1700 > 2500 PSIG	PT-0457	n	PCS	NNS	7.2.02-F 02	MULT 1201	X	
P5483	P0483	PRESSURIZER PRESSURE (CH 4) XDUCEr: 0-10V SCALE: 1700 > 2500 PSIG	PT-0458	n	PCS	NNS	7.2.02-F 02	MULT 1201	X	
P5485	P0485	PRESSURIZER RELIEF TANK PRESSURE XDUCEr: 0-10V SCALE: 0 > 100 PSIG	PT-0489	n	PCS	NNS	--	- MULT 1201		
P6000	PI000	CONTAINMENT PRESSURE CH 2 XDUCEr: 0-10V SCALE: 0 > 75 PSIG	PT-0936	n	PCS	II	4.2.07	A1 RPU 02 1206	X	
P6001	PI001	CONTAINMENT PRESSURE CH 3 XDUCEr: 0-10V SCALE: 0 > 75 PSIG	PT-0935	n	PCS	III	4.2.07	A1 RPU A3 1206	X	

REF SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE	SIGNAL CLASS	SIGNAL AG	VAR CLASS	INPUT VIA	SYSTEM
P6882	P1882	CONTAINMENT PRESSURE CH 4 XDUCE: 0-10V SCALE: 0 > 75 PSIG	PT-8934	PCS	IV	4.2.67	A1 RPU 03	1286	X
P6893	--	CONTAINMENT PRESSURE CH 1 XDUCE: 0-10V SCALE: 0 > 75 PSIG	PT-8937	PCS	I	4.2.87	A1 RPU A2	1286	X
P6194	--	MAIN STEAM LINE PRESSURE XDUCE: 0-10V SCALE: 0 > 1500 PSIG	PT-8587	PCS	MNS	--	-	MULT	1361
P6270	--	SAFETY INJECTION PUMP TRAIN A PRESSURE XDUCE: 1-5V SCALE: 0 > 2800 PSIG	PT-8919	PCS	MNS	--	-	MULT	1284
P6271	--	SAFETY INJECTION PUMP TRAIN B PRESSURE XDUCE: 1-5V SCALE: 0 > 2800 PSIG	PT-8923	PCS	MNS	--	-	MULT	1284
P6273	--	SIS ACCUMULATOR PRESSURE (LOOP 1) XDUCE: 0-10V SCALE: 0 > 700 PSIG	PT-8968	PCS	MNS	7.2.85-F	D3	MULT	1284
P6275	--	SIS ACCUMULATOR PRESSURE (LOOP 2) XDUCE: 0-10V SCALE: 0 > 700 PSIG	PT-8967	PCS	MNS	7.2.85-F	D3	MULT	1284
P6277	--	SIS ACCUMULATOR PRESSURE (LOOP 3) XDUCE: 0-10V SCALE: 0 > 700 PSIG	PT-8964	PCS	MNS	7.2.85-F	D3	MULT	1284
P6279	--	SIS ACCUMULATOR PRESSURE (LOOP 4) XDUCE: 0-10V SCALE: 0 > 700 PSIG	PT-8966	PCS	MNS	7.2.85-F	D3	MULT	1284
P6310	--	RHR PUMP A DISCH PRESS XDUCE: 0-10V SCALE: 0 > 800 PSIG	PT-8614	PCS	MNS	--	-	MULT	1285
P6311	--	RHR PUMP B DISCH PRESS XDUCE: 0-10V SCALE: 0 > 800 PSIG	PT-8615	PCS	MNS	--	-	MULT	1285
P7011	P2011	MAIN STEAM PRESSURE XDUCE: 0-10V SCALE: 0 > 1200 PSIG	PT-6193	PCS-SUP	MNS	--	-	MULT	1361

R
E
V

S
P
D
S

ERP SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	SCALE	ORIGINATING DEVICE	SIGNAL SOURCE	SIGNAL CLASS	RC 1.97 VAR CLASS	INPUT VIA SYSTEM	S
P7825	P2825	EMC FLUID PRESSURE XDUCE: 0-10V	0 > 2000 PSIG	PT-6336 1365	PCS-80P	MNS	--	MULT	1615
P7895	P2895	LP TURBINE A EXHAUST HOOD PRESSURE XDUCE: 0-10V	0 > 30 IN HG VAC	PT-6292 1367	PCS-80P	MNS	--	MULT	1381
P7897	P2897	LP TURBINE B EXHAUST HOOD PRESSURE XDUCE: 0-10V	0 > 30 IN HG VAC	PT-6293 1368	PCS-80P	MNS	--	MULT	1381
P7899	P2899	LP TURBINE C EXHAUST HOOD PRESSURE XDUCE: 0-10V	0 > 30 IN HG VAC	PT-6294 1369	PCS-80P	MNS	--	MULT	1381
P7327	P2327	TURBINE DRIVEN AUX FW PUMP DISCH PRESS XDUCE: 0-10V	0 > 2000 PSIG	PT-5187 1386	PCS-80P	MNS	--	RPU NI	1382 X
P7329	P2329	MOTOR DRIVEN AUX FW PUMP A DISCH PRESS XDUCE: 0-10V	0 > 2000 PSIG	PT-5141 1382	PCS-80P	MNS	--	RPU NI	1382 X
P7338	P2338	MOTOR DRIVEN AUX FW PUMP B DISCH PRESS XDUCE: 0-10V	0 > 2000 PSIG	PT-5148 1381	PCS-80P	MNS	--	RPU NI	1382 X
P7348	P2348	CIRCULATING WATER PRESSURE XDUCE: 0-10V	0 > 100 PSIG	PT-7176 1488	PCS-80P	MNS	--	MULT	1481
P7392	P2392	MFW PUMP A DISCHARGE PRESSURE XDUCE: 0-10V	0 > 2000 PSIG	PT-5234 1374	PCS-80P	MNS	--	MULT	1385
P7412	P2412	MFW PUMP B DISCHARGE PRESSURE XDUCE: 0-10V	0 > 2000 PSIG	PT-6235 1375	PCS-80P	MNS	--	MULT	1385
P7471	P2471	CONDENSATE PUMPS DISCHARGE HEADER PRESSURE XDUCE: 0-10V	0 > 75R PSIG	PT-4482 1372	PCS-80P	MNS	--	MULT	1385
P7671	P2671	CCW PUMPS TRAIN A DISCH PRESSURE XDUCE: 0-10V	0 > 200 PSIG	PT-1874 1187	PCS-80P	MNS	7.2.00-A D2 RPU NI		1283

R E V	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
	P7672	P2572	CCW PUMPS TRAIN B DISCH PRESSURE XDUCEH: 0-10V SCALE: 0 > 200 PSIG	PT-1075	N 1188	PCS-BOP	NNS	7.2.08-A	D2 RPU N1	1203	
	P7742	P2742	INSTHUMENT AIR HEADER PRESSURE XDUCEH: 0-10V SCALE: 0 > 150 PSIG	PT-9361	N 1397	PCS-BOP	NNS	--	MULT	2420	
	P7931	--	FIRE MAIN PRESSURE XDUCEH: 4-20MA SCALE: 0 > 200 PSIG	PT-7918	B 1262	FLD	NNS	--	MUX	2301	(UNIT 1 INPUT ONLY)
	P9253	--	CONTAINMENT PRESS EXTENDED RANGE CH 1 XDUCEH: 0-10V SCALE: -5 > 160 PSIG	PT-10942	B 1144	PCS-BOP	I	6.2.03-A	C1 RPU A2	1206	X
	P9254	--	CONTAINMENT PRESS EXTENDED RANGE CH 2 XDUCEH: 0-10V SCALE: -5 > 160 PSIG	PT-10943	B 1145	PCS-BOP	II	6.2.03-A	C1 RPU B2	1206	X
*	P9071	--	CONTAINMENT PRESSURE NARROW RANGE XDUCEH: 4-20MA SCALE: -1.50E00 > 3.00E00	PT-10944 PSIG	B 1341	FLD	NNS	--	MUX	1206	X
	P07021	P02021	ENC LOW ETS PRESSURE TURBINE TRIP ALM ON CONTACT: CLSD ALM/NML: TRIPPED / RESET	TM2-15	B 2266	WEAC	NNS	--	MULT	1615	
	07791	02791	DIESEL GENERATOR A KW XDUCEH: 0-10V SCALE: 0 > 1.05E04	XDCR-W-2A KW	N 1216	PCS-BOP	NNS	7.2.12	D2 MULT	1004	
	07792	02792	DIESEL GENERATOR B KW XDUCEH: 0-10V SCALE: 0 > 1.05E04	XDCR-W-2B KW	N 1217	PCS-BOP	NNS	7.2.12	D2 MULT	1004	
*	07030	02030	GENERATOR OUTPUT NET POWER XDUCEH: 0-1MA SCALE: 0 > 1450 MW	XDCR-W-10	B 1371	QPRP E/D1-AA-804E	NNS	--	MULT	1002	
*	07031	02031	GENERATOR OUTPUT GROSS POWER XDUCEH: 0-1MA SCALE: 0 > 1450 MW	XDCR-W1	B 1370	QPRP E/D1-AA-804E	NNS	--	MULT	1002	
	09802	--	MET TMR INSTR POWER (WV#ON, 5V#OFF) XDUCEH: 0-5V SCALE: 0 > 5 VOLTS	MW TMR	B 1146	MET TOWER	NNS	--	MUX	2001	(UNIT 1 INPUT ONLY)

R	EXP	PROTEUS	SIGNAL DESCRIPTION	UNIT	INATING	Y	SIGNAL	SIGNAL	RG 1.97	INPUT	SYSTEM	S
V	SYMBOL	SYMBOL		DEVICE			SOURCE	CLASS	VAR CLASS	VIA		P
*	R6200	--	RE-001 CONTROL ROOM AREA RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E03	RE-001 MR/H	n	1223	PERMS	-	0.2.07	E3 PERMS	1609	X
*	R6201	--	RE-002 CNMT BLDG OPER LEV RAD-LOW RANGE (TS) XDUCE1: RS-232C SCALE: 0 > 5.40E03	RE-002 MR/H	n	1070	RPAMS	-	--	- PERMS	1609	X
*	R6202	--	RE-003 CNMT BLDG OPER LEV RAD-LOW RANGE (TS) XDUCE1: RS-232C SCALE: 0 > 5.40E03	RE-003 MR/H	n	1071	RPAMS	-	--	- PERMS	1609	X
*	R6203	--	RE-005 CNMT BLDG OPER LEV RAD-HIGH RANGE (TS) XDUCE1: RS-232C SCALE: 0 > 1.00E11	RE-005 MR/H	n	1072	RPAMS	-	4.2.13	A1 PERMS	1609	X
*	R6204	--	RE-006 CNMT BLDG OPER LEV RAD-HIGH RANGE (TS) XDUCE1: RS-232C SCALE: 0 > 1.00E11	RE-006 MR/H	n	1073	RPAMS	-	4.2.13	A1 PERMS	1609	X
*	R6205	--	RE-004 CNMT BLDG ACCESS HATCH AREA RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E04	RE-004 MR/H	n	1266	PERMS	-	--	- PERMS	1609	X
*	R6206	--	RE-011 CNMT BLDG INCONE INSTR ROOM RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E04	RE-011 MR/H	n	1267	PERMS	-	--	- PERMS	1609	X
*	R6207	--	ARE-007A RADIOCHEMISTRY LAB AREA RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E04	ARE-007A MR/H	n	1268	PERMS	-	0.2.07	E3 PERMS	1609	X
										(UNIT 1 INPUT ONLY)		
*	R6208	--	ARE-007B SAMPLING ROOM AREA RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E04	ARE-007B MR/H	n	1269	PERMS	-	0.2.07	E3 PERMS	1609	X
										(UNIT 1 INPUT ONLY)		
*	R6209	--	RE-008 FUEL HANDLING BLDG AREA RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E04	RE-008 MR/H	n	1224	PERMS	-	0.2.07	E3 PERMS	1609	X
*	R6210	--	ARE-009A LARGE PARTS DECON STA AREA RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E04	ARE-009A MR/H	n	1270	PERMS	-	0.2.07	E3 PERMS	1609	X
										(UNIT 1 INPUT ONLY)		
*	R6211	--	ARE-009b SMALL PARTS DECON STA AREA RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E04	ARE-009b MR/H	n	1271	PERMS	-	0.2.07	E3 PERMS	1609	X
										(UNIT 1 INPUT ONLY)		

R	ERF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT		S
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	D
*	R6212	--	ARE-009C HOT INSTR DEC IN STA AREA RAD (NTS) XDUCE: RS-232C SCALE: 0 > 1.00E-04	ARE-009C MR/H	N	PERMS	-	8.2.07	E3 PERMS	1609 X	
											(UNIT 1 INPUT ONLY)
*	R6215	--	RE-2562A CNMT ATMOS PROCESS AIR PART (TS) XDUCE: RS-232C SCALE: 0 > 2.30E-07	RE-2562A UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
*	R6216	--	RE-2562C CNMT ATMOS PROCESS RADIOGAS (TS) XDUCE: RS-232C SCALE: 0 > 5.00E-02	RE-2562C UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
*	R6217	--	RE-12442A PLANT VENT EFFL PART-LOW RANGE (TS) XDUCE: RS-232C SCALE: 0 > 2.30E-07	RE-12442A UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
*	R6218	--	RE-12442B PLANT VENT EFFL IODINE-LOW RANGE (TS) XDUCE: RS-232C SCALE: 0 > 2.30E-05	RE-12442B UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
*	R6219	--	RE-12442C PLANT VENT EFFL RAD-LOW RANGE (TS) XDUCE: RS-232C SCALE: 0 > 5.00E-02	RE-12442C UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
*	R6220	--	ARE-13133A VRS ROOM AIR PARTICULATE (NTS) XDUCE: RS-232C SCALE: 0 > 1.00E-06	ARE-13133A UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
											(UNIT 1 INPUT ONLY)
*	R6221	--	ARE-13133B VRS ROOM IODINE (NTS) XDUCE: RS-232C SCALE: 0 > 1.00E-06	ARE-13133B UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
											(UNIT 1 INPUT ONLY)
*	R6222	--	ARE-13133C VRS ROOM RADIOGAS (NTS) XDUCE: RS-232C SCALE: 0 > 1.00E-03	ARE-13133C UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
											(UNIT 1 INPUT ONLY)
*	R6223	--	RE-2565A CNMT VENT EFFLUENT AIR PART (TS) XDUCE: RS-232C SCALE: 0 > 2.30E-07	RE-2565A UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
*	R6224	--	RE-2565B CNMT VENT EFFL IODINE (TS) XDUCE: RS-232C SCALE: 0 > 2.30E-05	RE-2565B UCI/CC	N	PERMS	-	--	-	PERMS	1609 X
*	R6225	--	RE-2565C CNMT VENT EFFL RADIOGAS (TS) XDUCE: RS-232C SCALE: 0 > 1.00E-01	RE-2565C UCI/CC	N	PERMS	-	--	-	PERMS	1609 X

VOLUME 1 REG GUIDE /ENF INPUT LIST

R E V	ENF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	S Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
*	R6227	--	RE-W24A SELECTIVE CUBICLE AIR PART (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E-05	RE-W24A UCI/CC	N 1226	PERMS	-	--	-	PERMS 1689	X
*	R6228	--	RE-W24B SELECTIVE CUBICLE AIR RADIOGAS (NTS) XDUCE1: RS-232C SCALE: 0 > 5.00E-02	RE-W24B UCI/CC	N 1227	PERMS	-	--	-	PERMS 1689	X
*	R6229	--	ARE-W26A WASTE SOLID BLDG EFFL AIR PART (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E-06	ARE-W26A UCI/CC	N 1239	PERMS	-	--	-	PERMS 1689 (UNIT 1 INPUT ONLY)	X
*	R6230	--	ARE-W26B WASTE SOLID BLDG EFFL IODINE (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E-06	ARE-W26B UCI/CC	N 1228	PERMS	-	--	-	PERMS 1689 (UNIT 1 INPUT ONLY)	X
*	R6231	--	ARE-W26C WASTE SOLID BLDG EFFL RADIOGAS (NTS) XDUCE1: RS-232C SCALE: 0 > 1.00E-03	ARE-W26C UCI/CC	N 1225	PERMS	-	--	-	PERMS 1689 (UNIT 1 INPUT ONLY)	X
*	R6232	--	ARE-W16 BORON RECYCLE LIQ PROCESS RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 4.00E-02	ARE-W16 UCI/CC	N 1284	PERMS	-	--	-	PERMS 1689 (UNIT 1 INPUT ONLY)	X
*	R6233	--	RE-W17A CCW PROCESS RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 4.00E-02	RE-W17A UCI/CC	N 1285	PERMS	-	--	-	PERMS 1689	X
*	R6234	--	RE-W17B CCW PROCESS RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 4.00E-02	RE-W17B UCI/CC	N 1286	PERMS	-	--	-	PERMS 1689	X
*	R6235	--	RE-W18 WASTE LIQUID EFFLUENT RAD (TS) XDUCE1: RS-232C SCALE: 0 > 1.00E-01	RE-W18 UCI/CC	N 1287	PERMS	-	--	-	PERMS 1689	X
*	R6236	--	RE-W19 STM GEN SAMPLE LIQ PROCESS RAD (NTS) XDUCE1: RS-232C SCALE: 0 > 4.00E-02	RE-W19 UCI/CC	N 1288	PERMS	-	--	-	PERMS 1689	X
*	R6237	--	RE-W20A NSCW PROCESS RAD (TS) XDUCE1: RS-232C SCALE: 0 > 4.00E-02	RE-W20A UCI/CC	N 1289	PERMS	-	--	-	PERMS 1689	X
*	R6238	--	RE-W20B NSCW PROCESS RAD (IS) XDUCE1: RS-232C SCALE: 0 > 4.00E-02	RE-W20B UCI/CC	N 1290	PERMS	-	--	-	PERMS 1689	X

R E V	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
*	R6239	--	RE-021 STM GEN BLOWDOWN LIQ PROC RAD (TS) XDUCE: RS-232C SCALE: @ > 4.00E-02	RE-021 UCI/CC	N 1291	PERMS	-	--	- PERMS	1689	X
*	R6240	--	RE-0848 TURB BLDG DRAIN LIQ EFFL RAD (TS) XDUCE: RS-232C SCALE: @ > 4.00E-02	RE-0848 UCI/CC	N 1292	PERMS	-	--	- PERMS	1689	X
*	R6241	--	ARE-025 ELECT BLR COND RIN PROCESS RAD (NTS) XDUCE: RS-232C SCALE: @ > 4.00E-02	ARE-025 UCI/CC	N 1293	PERMS	-	--	- PERMS (UNIT 1 INPUT ONLY)	1689	X
*	R6242	--	RE-1950 ACCM PROCESS RAD (NTS) XDUCE: RS-232C SCALE: @ > 4.00E-02	RE-1950 UCI/CC	N 1294	PERMS	-	--	- PERMS	1689	X
*	R6244	--	RE-12116 CR AIR INTAKE PROC RADIOGAS (TS) XDUCE: RS-232C SCALE: @ > 1.00E-01	RE-12116 UCI/CC	N 1296	PERMS	-	--	- PERMS	1689	X
*	R6245	--	RE-12117 CR AIR INTAKE PROC RADIOGAS (TS) XDUCE: RS-232C SCALE: @ > 1.00E-01	RE-12117 UCI/CC	N 1297	PERMS	-	--	- PERMS	1689	X
*	R6246	--	RE-039A WASTE BAS DECAY TANK EFFL RAD (NTS) XDUCE: RS-232C SCALE: @ > 1.00E-01	RE-039A UCI/CC	N 1298	PERMS	-	--	- PERMS	1689	X
*	R6247	--	RE-039B WASTE GAS CMPSH VENT EFFL RAD (NTS) XDUCE: RS-232C SCALE: @ > 1.00E-01	RE-039B UCI/CC	N 1299	PERMS	-	--	- PERMS	1689	X
*	R6248	--	ARE-2532A FUEL HAND BLDG EFFL RADIOGAS (TS) XDUCE: RS-232C SCALE: @ > 1.00E-01	ARE-2532A UCI/CC	N 1310	PERMS	-	--	- PERMS (UNIT 1 INPUT ONLY)	1689	X
*	R6249	--	ARE-2532B FUEL HAND BLDG EFFL RADIOGAS (TS) XDUCE: RS-232C SCALE: @ > 1.00E-01	ARE-2532B UCI/CC	N 1311	PERMS	-	--	- PERMS (UNIT 1 INPUT ONLY)	1689	X
*	R6250	--	ARE-2533A FUEL HAND BLDG EFFL RADIOGAS (TS) XDUCE: RS-232C SCALE: @ > 1.00E-01	ARE-2533A UCI/CC	N 1312	PERMS	-	--	- PERMS (UNIT 1 INPUT ONLY)	1689	X
*	R6251	--	ARE-2533B FUEL HANDLING BLDG EFFL RADIOGAS (TS) XDUCE: RS-232C SCALE: @ > 1.00E-01	ARE-2533B UCI/CC	N 1313	PERMS	-	--	- PERMS (UNIT 1 INPUT ONLY)	1689	X

R	ERF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT		B
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	D
*	R6252	--	RE-013 WASTE GAS PROC SYS PROC RADIOGAS (NTS) XDUCEH: RS-232C SCALE: 0 > 2.00E03	RE-013 UCI/CC	N	PERMS	-	--	-	PERMS 1609	X
*	R6253	--	RE-014 WASTE GAS PROC SYS EFFL RADIOGAS (TS) XDUCEH: RS-232C SCALE: 0 > 1.00E04	RE-014 UCI/CC	N	PERMS	-	--	-	PERMS 1609 (UNIT 1 INPUT ONLY)	X
*	R6374	--	RE-48000 CVC8 LETDOWN RAD (NTS) XDUCEH: RS-232C SCALE: 0 > 4.00E01	RE-48000 UCI/CC	N	PERMS	-	--	-	PERMS 1609	X
*	R6377	--	RE-12444C PLANT VENT RADIOGAS-LOW RANGE (TS) XDUCEH: RS-232C SCALE: 0 > 3.40E-03	RE-12444C UCI/CC	N	PERMS	-	6.2.03-C	C2 PERMS	1609	X
*	R6378	--	RE-12444D PLANT VENT RADIOGAS-MID RANGE (TS) XDUCEH: RS-232C SCALE: 0 > 4.00E01	RE-12444D UCI/CC	N	PERMS	-	6.2.03-C	C2 PERMS	1609	X
*	R6379	--	RE-12444E PLANT VENT RADIOGAS-HI RANGE (TS) XDUCEH: RS-232C SCALE: 0 > 5.00E04	RE-12444E UCI/CC	N	PERMS	-	6.2.03-C	C2 PERMS	1609	X
*	R6381	--	RE-12839E CNDSR AIR EJCTR/STM RAD-HI RANGE (TS) XDUCEH: RS-232C SCALE: 0 > 5.00E05	RE-12839E UCI/CC	N	PERMS	-	8.2.05	E3 PERMS	1609	X
*	R6382	--	RE-12839D CNDSR AIR EJCTR/STM RAD-MID RNGE (TS) XDUCEH: RS-232C SCALE: 0 > 4.00E01	RE-12839D UCI/CC	N	PERMS	-	8.2.05	E3 PERMS	1609	X
*	R6383	--	RE-12839C CNDSR AIR EJCTR/STM RAD-LOW RNGE (TS) XDUCEH: RS-232C SCALE: 0 > 3.40E-03	RE-12839C UCI/CC	N	RPAMS	-	8.2.05	E3 PERMS	1609	X
*	R6385	--	RE-13119 STM GEN 4 MAIN STM LINE MONITOR (TS) XDUCEH: RS-232C SCALE: 0 > 1.00E03	RE-13119 UCI/CC	N	RPAMS	-	4.2.14	A1 PERMS	1609	X
*	R6386	--	RE-13120 STM GEN 1 MAIN STM LINE MONITOR (TS) XDUCEH: RS-232C SCALE: 0 > 1.00E03	RE-13120 UCI/CC	N	RPAMS	-	4.2.14	A1 PERMS	1609	X
*	R6387	--	RE-13121 STM GEN 2 MAIN STM LINE MONITOR (TS) XDUCEH: RS-232C SCALE: 0 > 1.00E03	RE-13121 UCI/CC	N	RPAMS	-	4.2.14	A1 PERMS	1609	X

REF	ERP SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S
*	R6388	--	RE-13122 STM GEN 3 MAIN STM LINE MONITOR (TS) XDUCE: RS-232C SCALE: 0 > 1.00E03	RE-13122 UCI/CC	W	RPAMS	-	4.2.14 A1 PERMS	1689	X	
*	R9631	--	ARE-50002A TSC CK? DISP ROOM AREA RAD (NTS) XDUCE: RS-232C SCALE: 0 > 1.00E03	ARE-50002A MR/H	W	PERMS	-	-- - PERMS	1689	X	(UNIT 1 INPUT ONLY)
*	R9632	--	ARE-50002B TSC WORK AREA-AREA RAD (NTS) XDUCE: RS-232C SCALE: 0 > 1.00E03	ARE-50002B MR/H	W	PERMS	-	-- - PERMS	1689	X	(UNIT 1 INPUT ONLY)
*	R9633	--	ARE-50003 TSC VENT EFFL RADIOGAS (NTS) XDUCE: RS-232C SCALE: 0 > 1.00E-01	ARE-50003 UCI/CC	W	PERMS	-	-- - PERMS	1689	X	(UNIT 1 INPUT ONLY)
	36170	--	PRIMARY MET TOWER 10 METER WIND SPEED XDUCE: 0-5V SCALE: 0 > 100 MPH	MR TWR	B	MET TOWER NNS		0.2.08 E3 MUX	2001		(UNIT 1 INPUT ONLY)
	36438	--	PRIMARY MET TOWER 60 METER WIND SPEED XDUCE: 0-5V SCALE: 0 > 100 MPH	MR TWR	B	MET TOWER NNS		0.2.08 E3 MUX	2001		(UNIT 1 INPUT ONLY)
	36436	--	SECONDARY MET TOWER 10 METER WIND SPEED XDUCE: 0-5V SCALE: 0 > 100 MPH	MR TWR	B	MET TOWER NNS		0.2.08 E3 MUX	2001		(UNIT 1 INPUT ONLY)
*	37011	32011	MAIN TURBINE SPEED XDUCE: 2-10V SCALE: 0 > 2500 RPM	SS-6299	B	ATSI	NNS	-- - MULT	1301		
*	T5001	T0001	INCORE THERMOCOUPLE A06 TEMP, TRAIN A, QUAD 4 XDUCE: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10001	W	T/C (FLD)	III	4.2.15 A1 RPU A3	1612	X	
*	T5002	T0002	INCORE THERMOCOUPLE A10 TEMP, TRAIN B, QUAD 3 XDUCE: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10002	W	T/C (FLD)	IV	4.2.15 A1 RPU B3	1612	X	
	T5003	T0003	INCORE THERMOCOUPLE C04 TEMP, TRAIN B, QUAD 4 XDUCE: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10003	W	T/C (FLD)	IV	4.2.15 A1 RPU B3	1612	X	
	T5004	T0004	INCORE THERMOCOUPLE C08 TEMP, TRAIN A, QUAD 3&4 XDUCE: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10004	W	T/C (FLD)	III	4.2.15 A1 RPU A3	1612	X	

Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
T5005	T0005		INCORE THERMOCOUPLE C12 TEMP, TRAIN A, QUAD 3 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10005	N	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X	
T5006	T0006		INCORE THERMOCOUPLE E#2 TEMP, TRAIN B, QUAD 4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10006	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5007	T0007		INCORE THERMOCOUPLE E#6 TEMP, TRAIN A, QUAD 4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10007	N	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X	
T5008	T0008		INCORE THERMOCOUPLE E10 TEMP, TRAIN B, QUAD 3 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10008	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5009	T0009		INCORE THERMOCOUPLE E14 TEMP, TRAIN B, QUAD 3 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10009	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5010	T0010		INCORE THERMOCOUPLE G#4 TEMP, TRAIN B, QUAD 4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10010	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5011	T0011		INCORE THERMOCOUPLE G#8 TEMP, TRAIN B, QUAD 3&4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10011	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5012	T0012		INCORE THERMOCOUPLE G12 TEMP, TRAIN B, QUAD 3 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10012	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5013	T0013		INCORE THERMOCOUPLE H#1 TEMP, TRAIN A, QUAD 1&4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10013	N	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X	
T5014	T0014		INCORE THERMOCOUPLE J#2 TEMP, TRAIN B, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10014	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5015	T0015		INCORE THERMOCOUPLE J#6 TEMP, TRAIN B, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10015	N	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X	
T5016	T0016		INCORE THERMOCOUPLE J10 TEMP, TRAIN B, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10016	N	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	

R E Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D B
T5017	T0017	INCORE	THERMOCOUPLE J14 TEMP, TRAIN B, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10017	W 1095	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5018	T0018	INCORE	THERMOCOUPLE L04 TEMP, TRAIN B, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10018	W 1096	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5019	T0019	INCORE	THERMOCOUPLE L00 TEMP, TRAIN B, QUAD 1&2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10019	W 1097	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5020	T0020	INCORE	THERMOCOUPLE L12 TEMP, TRAIN A, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10020	W 1098	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X	
T5021	T0021	INCORE	THERMOCOUPLE N02 TEMP, TRAIN B, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10021	W 1099	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5022	T0022	INCORE	THERMOCOUPLE N00 TEMP, TRAIN B, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10022	W 1100	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5023	T0023	INCORE	THERMOCOUPLE N10 TEMP, TRAIN B, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10023	W 1101	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5024	T0024	INCORE	THERMOCOUPLE N14 TEMP, TRAIN B, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10024	W 1102	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5025	T0025	INCORE	THERMOCOUPLE N08 TEMP, TRAIN B, QUAD 1&2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10025	W 1103	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5026	T0026	INCORE	THERMOCOUPLE A00 TEMP, TRAIN B, QUAD 3&4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10026	W 1104	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	
T5027	T0027	INCORE	THERMOCOUPLE C02 TEMP, TRAIN A, QUAD 4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10027	W 1105	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X	
T5028	T0028	INCORE	THERMOCOUPLE C06 TEMP, TRAIN B, QUAD 4 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10028	W 1106	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X	

R	E	ERF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION		DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM B
T5029	T0029	INCORE THERMOCOUPLE C10 TEMP, TRAIN A, QUAD 3 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10029	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1107		
T5030	T0030	INCORE THERMOCOUPLE C14 TEMP, TRAIN A, QUAD 3 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10030	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1108		
T5031	T0031	INCORE THERMOCOUPLE E04 TEMP, TRAIN A, QUAD 4 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10031	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1109		
T5032	T0032	INCORE THERMOCOUPLE E08 TEMP, TRAIN A, QUAD 3&4 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10032	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1110		
T5033	T0033	INCORE THERMOCOUPLE E12 TEMP, TRAIN A, QUAD 3 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10033	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1111		
T5034	T0034	INCORE THERMOCOUPLE G02 TEMP, TRAIN B, QUAD 4 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10034	W	T/C (FLD) IV	4.2.15	A1 RPU B3 1612	X	1112		
T5035	T0035	INCORE THERMOCOUPLE G06 TEMP, TRAIN A, QUAD 4 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10035	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1113		
T5036	T0036	INCORE THERMOCOUPLE G10 TEMP, TRAIN B, QUAD 3 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10036	W	T/C (FLD) IV	4.2.15	A1 RPU B3 1612	X	1114		
T5037	T0037	INCORE THERMOCOUPLE G14 TEMP, TRAIN B, QUAD 3 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10037	W	T/C (FLD) IV	4.2.15	A1 RPU B3 1612	X	1115		
T5038	T0038	INCORE THERMOCOUPLE H15 TEMP, TRAIN A, QUAD 2&3 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10038	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1116		
T5039	T0039	INCORE THERMOCOUPLE J04 TEMP, TRAIN A, QUAD 1 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10039	W	T/C (FLD) III	4.2.15	A1 RPU A3 1612	X	1117		
T5040	T0040	INCORE THERMOCOUPLE J08 TEMP, TRAIN B, QUAD 1&2 XDUCE1: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10040	W	T/C (FLD) IV	4.2.15	A1 RPU B3 1612	X	1118		

R	E	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S
V	SYMBOL	SYMBOL			DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM
	T5041	T0041		INCORE THERMOCOUPLE J12 TEMP, TRAIN A, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10041	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5042	T0042		INCORE THERMOCOUPLE L02 TEMP, TRAIN A, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10042	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5043	T0043		INCORE THERMOCOUPLE L06 TEMP, TRAIN A, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10043	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5044	T0044		INCORE THERMOCOUPLE L10 TEMP, TRAIN A, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10044	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5045	T0045		INCORE THERMOCOUPLE L14 TEMP, TRAIN A, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10045	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5046	T0046		INCORE THERMOCOUPLE N04 TEMP, TRAIN A, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10046	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5047	T0047		INCORE THERMOCOUPLE N08 TEMP, TRAIN A, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10047	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5048	T0048		INCORE THERMOCOUPLE N12 TEMP, TRAIN A, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10048	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5049	T0049		INCORE THERMOCOUPLE R06 TEMP, TRAIN A, QUAD 1 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10049	W	T/C (FLD)	III	4.2.15	A1 RPU A3 1612	X
	T5050	T0050		INCORE THERMOCOUPLE R10 TEMP, TRAIN B, QUAD 2 XDUCEH: TYPE K TC SCALE: 0 > 2300 DEG F	TE-10050	W	T/C (FLD)	IV	4.2.15	A1 RPU B3 1612	X
	T5122	T0122		EXCESS LETDOWN HEAT EXCH OUTLET TEMP XDUCEH: 0-10V SCALE: 50 > 250 DEG F	TE-0122	W	PCS	NNS	--	- MULT 1200	
	T5145	T0145		LETDOWN HEAT EXCH OUTLET TEMP XDUCEH: 0-10V SCALE: 50 > 200 DEG F	TE-0130	W	PCS	NNS	--	- MULT 1200	

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	RC 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
* T5406	T0406	LOOP 1 WIDE RANGE T-COLD XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0413B	N 1004	PCS	II	4.2.03 A1 RPU 02 1201		X	
T5419	T0419	LOOP 1 WIDE RANGE T-HOT XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0413A	N 1008	PCS	I	4.2.02 A1 RPU A2 1201		X	
* T5426	T0426	LOOP 2 WIDE RANGE T-COLD XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0423B	N 1005	PCS	II	4.2.03 A1 RPU 02 1201		X	
T5439	T0439	LOOP 2 WIDE RANGE T-HOT XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0423A	N 1001	PCS	I	4.2.02 A1 RPU A2 1201		X	
* T5446	T0446	LOOP 3 WIDE RANGE T-COLD XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0433B	N 1006	PCS	II	4.2.03 A1 RPU 02 1201		X	
T5459	T0459	LOOP 3 WIDE RANGE T-HOT XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0433A	N 1002	PCS	I	4.2.02 A1 RPU A2 1201		X	
* T5466	T0466	LOOP 4 WIDE RANGE T-COLD XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0443B	N 1007	PCS	II	4.2.03 A1 RPU 02 1201		X	
T5479	T0479	LOOP 4 WIDE RANGE T-HOT XDUCE: 0-10V SCALE: 0 > 700 DEG F	TE-0443A	N 1003	PCS	I	4.2.02 A1 RPU A2 1201		X	
T5480	T0480	PRESSURIZER TEMPERATURE (WATER) XDUCE: 0-10V SCALE: 100 > 700 DEG F	TE-0453	N 1323	PCS	NNS	-- - MULT 1201			
T5481	T0481	PRESSURIZER TEMPERATURE (STEAM) XDUCE: 0-10V SCALE: 100 > 700 DEG F	TE-0454	N 1324	PCS	NNS	-- - MULT 1201			
T5485	T0485	PRESSURIZER RELIEF TANK TEMPERATURE XDUCE: 0-10V SCALE: 50 > 350 DEG F	TE-0468	N 1261	PCS	NNS	-- - MULT 1201			
T5627	T0627	RHR HEAT EXCH TRAIN A OUTLET TEMP XDUCE: 0-10V SCALE: 50 > 400 DEG F	TE-0604	N 1214	PCS	NNS	7.2.10-A 02 MULT 1205			

R E V
 E M F P
 Y S Y M B O L S Y M B O L S
 P R O T E U S
 S I G N A L D E S C R I P T I O N
 O R I G I N A T I N G D E V I C E
 S I G N A L S I G N A L
 S O U R C E C L A S S V A R C L A S S V I A S Y S T E M S

SYMBOL	DESCRIPTION	SCALE	UNIT	PCS	NMS	MUX	INPUT
T6628	RHR HEAT EXCH TRAIN B OUTLET TEMP	50 > 400 DEG F	TE-0605	M	NMS	7.2.10-A D2	MULT 1200
T6630	RHM HEAT EXCH TRAIN A INLET TEMP	50 > 400 DEG F	TE-0612	M	NMS	--	MULT 1200
T6631	RHR HEAT EXCH TRAIN B INLET TEMP	50 > 400 DEG F	TE-0613	M	NMS	--	MULT 1200
T6172	PRIMARY MET TOWER 10 METER AMBIENT TEMPERATURE	-10 > 120 DEG F	MN TMR	B	MET TOWER NMS	6.2.08	E3 MUX 2001 (UNIT 1 INPUT ONLY)
T6173	PRIMARY MET TOWER 10 METER DEW POINT TEMP	-10 > 120 DEG F	MN TMR	B	MET TOWER NMS	6.2.08	E3 MUX 2001 (UNIT 1 INPUT ONLY)
T6174	PRIMARY MET TOWER 00-10 METER DELTA TEMP	-5 > 10 DEG F	MN TMR	B	MET TOWER NMS	6.2.07	E3 MUX 2001 (UNIT 1 INPUT ONLY)
T6202	PRESSURIZER PURV PV0450A OUTLET TEMP	50 > 400 DEG F	TE-0463	M	PCS	NMS	--
T6203	PRESSURIZER SAFETY VALVE PSV-0010A OUTLET TEMP	50 > 400 DEG F	TE-0466	M	PCS	NMS	--
T6204	PRESSURIZER SAFETY VALVE PSV-0010B OUTLET TEMP	50 > 400 DEG F	TE-0465	M	PCS	NMS	--
T6205	PRESSURIZER SAFETY VALVE PSV-0010C OUTLET TEMP	50 > 400 DEG F	TE-0464	M	PCS	NMS	--
T6430	SECONDARY MET TOWER 10 METER AMBIENT TEMP	-10 > 120 DEG F	MN TMR	B	MET TOWER NMS	6.2.08	E3 MUX 2001 (UNIT 1 INPUT ONLY)
T7317	FEEDWATER HEATER 6A OUTLET TEMPERATURE	0 > 600 DEG F	TE-5222	M	PCS-80P	NMS	--

R	ERP	PROTEUS				ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT		B
Y	SYMBOL	SYMBOL	SIGNAL DESCRIPTION			DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	S
	T7322	T2322	FEEDWATER HEATLX 0B OUILET TEMPERATURE XDUCE: TYPE T TC SCALE: 0 > 600 DEG F			TE-5223	B	PCS-80P	NNS	--	-	MULT	1305
	T7501	T2501	CONTAINMENT LEVEL 2 TEMPERATURE XDUCE: TYPE T TC SCALE: 0 > 500 DEG F			TE-2563	B	T/C (FLD)	NNS	--	-	MULT	1501 X
	T7502	T2502	CONTAINMENT LEVEL C TEMPERATURE XDUCE: TYPE T TC SCALE: 0 > 500 DEG F			TE-2612	B	T/C (FLD)	NNS	--	-	MULT	1501 X
	T7503	T2503	CONTAINMENT LEVEL B TEMPERATURE XDUCE: TYPE T TC SCALE: 0 > 500 DEG F			TE-2613	B	T/C (FLD)	NNS	--	-	MULT	1501 X
	T7506	T2506	REACTOR CAVITY AREA B CONCRETE TEMPERATURE XDUCE: 0-10V SCALE: 32 > 200 DEG F			TE-12266	B	T/T (FLD)	NNS	--	-	MULT	1511
	T7507	T2507	REACTOR CAVITY AREA D CONCRETE TEMPERATURE XDUCE: 0-10V SCALE: 32 > 200 DEG F			TE-12268	B	T/T (FLD)	NNS	--	-	MULT	1511
	T7508	T2508	REACTOR CAVITY AREA A CONCRETE TEMPERATURE XDUCE: 0-10V SCALE: 32 > 200 DEG F			TE-12269	B	T/T (FLD)	NNS	--	-	MULT	1511
*	T7509	T2509	REACTOR CAVITY AREA C CONCRETE TEMPERATURE XDUCE: 0-10V SCALE: 32 > 200 DEG F			TE-12261	B	T/T (FLD)	NNS	--	-	MULT	1511
	T7511	T2511	REACTOR CAVITY UPPER NORTH AIR TEMP XDUCE: TYPE T TC SCALE: 0 > 500 DEG F			TE-2664	B	T/C (FLD)	NNS	--	-	MULT	1512
	T7512	T2512	REACTOR CAVITY UPPER EAST AIR TEMP XDUCE: TYPE T TC SCALE: 0 > 500 DEG F			TE-2667	B	T/C (FLD)	NNS	--	-	MULT	1512
	T7513	T2513	REACTOR CAVITY UPPER SOUTH AIR TEMP XDUCE: TYPE T TC SCALE: 0 > 500 DEG F			TE-2665	B	T/C (FLD)	NNS	--	-	MULT	1512
	T7514	T2514	REACTOR CAVITY UPPER WEST AIR TEMP XDUCE: TYPE T TC SCALE: 0 > 500 DEG F			TE-2666	B	T/C (FLD)	NNS	--	-	MULT	1512

REF	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	8
	T7515	T2515	REACTION CAVITY LOWER A AIR TEMP XDUCE: TYPE T TC SCALE: 0 > 500 DEG F	TE-2668	B	T/C (FLD)	NNS	--	-	MULT	1511
	T7516	T2516	REACTOR CAVITY LOWER B AIR TEMP XDUCE: TYPE T TC SCALE: 0 > 500 DEG F	TE-2669	B	T/C (FLD)	NNS	--	-	MULT	1511
*	T7601	T2601	NSCM SUPPLY HEADER TEMP TRAIN A XDUCE: TYPE T TC SCALE: 0 > 300 DEG F	TE-1642	B	T/C (FLD)	NNS	--	-	MULT	1202
*	T7602	T2602	NSCM SUPPLY HEADER TEMP TRAIN B XDUCE: TYPE T TC SCALE: 0 > 300 DEG F	TE-1643	B	T/C (FLD)	NNS	--	-	MULT	1202
	T7603	T2603	NSCM RETURN HEADER TEMP TRAIN A XDUCE: TYPE T TC SCALE: 0 > 200 DEG F	TE-1676	B	PCS-BOP	NNS	--	-	MULT	1202
	T7604	T2604	NSCM RETURN HEADER TEMP TRAIN B XDUCE: TYPE T TC SCALE: 0 > 200 DEG F	TE-1677	B	PCS-BOP	NNS	--	-	MULT	1202
	T7671	T2671	CCM HEAT EXCH OUTLET TEMP TRAIN A XDUCE: TYPE T TC SCALE: 0 > 300 DEG F	TE-1866	B	T/C (FLD)	NNS	7.2.08-B	D2 RPU N1		1203
	T7672	T2672	CCM HEAT EXCH OUTLET TEMP TRAIN B XDUCE: TYPE T TC SCALE: 0 > 300 DEG F	TE-1867	B	T/C (FLD)	NNS	7.2.08-B	D2 RPU N1		1203
	T7701	T2701	ACCM HEAT EXCH 1 OUTLET TEMP XDUCE: TYPE T TC SCALE: 0 > 300 DEG F	TE-1967	B	T/C (FLD)	NNS	--	-	MULT	1217
	T7702	T2702	ACCM HEAT EXCH 2 OUTLET TEMP XDUCE: TYPE T TC SCALE: 0 > 300 DEG F	TE-1978	B	T/C (FLD)	NNS	--	-	MULT	1217
	T9644	--	RCS SUBCOOLING-TRAIN A XDUCE: RS-422 SCALE: -600 > 350 DEG F	CALC-OPUA	B	-	-	4.2.16	A1 OPUA		1201 X
	T9645	--	RCS SUBCOOLING-TRAIN B XDUCE: RS-422 SCALE: -600 > 350 DEG F	CALC-OPUB	B	-	-	4.2.16	A1 OPUB		1201 X

REF SYMBOL	PRTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	8 Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM 3
T9847	--	RVLIS HEAD TEMP COMP AT HV TRAIN A XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1313	N	T/C (FLD)	III	5.2.03-B 81 RPU A3	1201	1342
T9848	--	RVLIS HEAD TEMP COMP AT ISOL TRAIN A XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1314	N	T/C (FLD)	III	5.2.03-B 81 RPU A3	1201	1386
T9849	--	RVLIS HOT LEG TEMP COMP AT RV TRAIN A XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1315	N	T/C (FLD)	III	5.2.03-B 81 RPU A3	1201	1401
T9850	--	RVLIS HOT LEG TEMP COMP AT ISOL TRAIN A XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1316	N	T/C (FLD)	III	5.2.03-B 81 RPU A3	1201	1402
T9851	--	RVLIS SEAL TBL TEMP COMP AT RV TRAIN A XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1317	N	T/C (FLD)	III	5.2.03-B 81 RPU A3	1201	1403
T9852	--	RVLIS SEAL TBL TEMP COMP AT SEAL TBL TRAIN A XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1318	N	T/C (FLD)	III	5.2.03-B 81 RPU A3	1201	1404
T9853	--	RVLIS SEAL TBL TEMP COMP AT ISOL TRAIN A XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1319	N	T/C (FLD)	III	5.2.03-B 81 RPU A3	1201	1405
T9854	--	RVLIS HEAD TEMP COMP AT RV TRAIN B XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1323	N	T/C (FLD)	IV	5.2.03-B 81 RPU B3	1201	1406
T9855	--	RVLIS HEAD TEMP COMP AT ISOL TRAIN B XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1324	N	T/C (FLD)	IV	5.2.03-B 81 RPU B3	1201	1410
T9856	--	RVLIS HOT LEG TEMP COMP AT RV TRAIN B XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1325	N	T/C (FLD)	IV	5.2.03-B 81 RPU B3	1201	1410
T9857	--	RVLIS HOT LEG TEMP COMP AT ISOL TRAIN B XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1326	N	T/C (FLD)	IV	5.2.03-B 81 RPU B3	1201	1419
T9858	--	RVLIS SEAL TBL TEMP COMP AT RV TRAIN B XDUCE: 100 OHM SCALE: 50 > 420 DEG F	TE-1327	N	T/C (FLD)	IV	5.2.03-B 81 RPU B3	1201	1420

R E V	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S
											P
	T9859	--	RVL13 SEAL TBL TEMP COMP AT SEAL TBL TRAIN B XDUCE1: 100 OHM SCALE: 50 > 420 DEG F	TE-1328	#	T/C (FLD)	IV	5.2.03-B 01	RPU 03	1201	3
	T9860	--	RVL13 SEAL TBL TEMP COMP AT ISOL TRAIN B XDUCE1: 100 OHM SCALE: 30 > 420 DEG F	TE-1329	#	T/C (FLD)	IV	5.2.03-B 01	RPU 03	1201	3
	T9882	--	MET 1WR EQUIP BLDG TEMP (BYNORM, 5VWHI-LO) XDUCE1: 0-5V SCALE: 0 > 5 VOLTS	MN 1WR	B	MET TOXER	NNS	--	- MUX	2001	0
									(UNIT 1 INPUT ONLY)		3
	T9883	--	STEAM GEN 1 BLOWDOWN TEMP XDUCE1: TYPE T TC SCALE: 0 > 600 DEG F	TE-5734	B	T/C (FLD)	NNS	--	- MULT	1301	0
	T9884	--	STEAM GEN 2 BLOWDOWN TEMP XDUCE1: TYPE T TC SCALE: 0 > 600 DEG F	TE-5735	B	T/C (FLD)	NNS	--	- MULT	1301	0
	T9885	--	STEAM GEN 3 BLOWDOWN TEMP XDUCE1: TYPE T TC SCALE: 0 > 600 DEG F	TE-5736	B	T/C (FLD)	NNS	--	- MULT	1301	0
	T9886	--	STEAM GEN 4 BLOWDOWN TEMP XDUCE1: TYPE T TC SCALE: 0 > 600 DEG F	TE-5737	B	T/C (FLD)	NNS	--	- MULT	1301	0
	T9887	--	TURBINE DRIVEN AUX F> PUMP 1 TRAIN C DISCH TEMP XDUCE1: TYPE T TC SCALE: 0 > 300 DEG F	TE-5106	B	T/C (FLD)	NNS	--	- MULT	1302	0
	T9888	--	MOTOR DRIVEN AUX FM PUMP 3 TRAIN A DISCH TEMP XDUCE1: TYPE T TC SCALE: 0 > 300 DEG F	TE-5210	B	T/C (FLD)	NNS	--	- MULT	1302	0
	T9889	--	MOTOR DRIVEN AUX FM PUMP 2 TRAIN B DISCH TEMP XDUCE1: TYPE T TC SCALE: 0 > 300 DEG F	TE-5211	B	T/C (FLD)	NNS	--	- MULT	1302	0
	T09520	--	RHR PUMP ROOM TRAIN A TEMP ALM ON CONTACT: CLSD ALM/NML: HIGH / NORMAL	TISH-12200	B	MCC	I	7.2.11-B 02	RPU A2	1555	0
						E/01-BG-0056					3
	T09528	--	RHR PUMP ROOM TRAIN B TEMP ALM ON CONTACT: CLSD ALM/NML: HIGH / NORMAL	TISH-12212	B	MCC	II	7.2.11-B 02	RPU B2	1555	0
						E/01-BG-005H					3

R	E	ERF	PHOTEUS		ORIGINATING	B	SIGNAL	SIGNAL	WG 1.97	INPUT		B
Y	SYMBOL	SYMBOL	SIGNAL DESCRIPTION		DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	B
	T09530	--	CNMT SPRAY PUMP ROOM TRAIN A TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12207	B	MCC	I	7.2.11-8 02	RPU A2	1555	
						2015	E/D1-8G-005J					
	T09532	--	CNMT SPRAY PUMP ROOM TRAIN K TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		" 13	B	MCC	II	7.2.11-8 02	RPU B2	1555	
						2009	E/D1-8G-005K					
	T09534	--	CCW PUMP ROOM TRAIN A TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12208	B	MCC	I	7.2.11-8 02	RPU A2	1555	
						2007	E/D1-8G-005E					
	T09536	--	CCW PUMP ROOM TRAIN B TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12214	B	MCC	II	7.7.11-8 02	RPU B2	1555	
						2384	E/D1-8G-005F					
	T09538	--	CHARGING PUMP ROOM TRAIN A TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12209	B	MCC	I	7.2.11-8 02	RPU A2	1555	
						2382	E/D1-8G-005N					
	T09540	--	CHARGING PUMP ROOM TRAIN B TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12215	B	MCC	II	7.2.11-8 02	RPU B2	1555	
						2002	E/D1-8G-005P					
	T09542	--	ELEC SWGR & MCC RM LEVEL D TRAIN A TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12240	B	MCC	I	7.2.11-8 02	RPU A2	1555	
						2509	E/D1-8G-005A					
	T09544	--	ELEC SWGR & MCC RM LEVEL 2 TRAIN B TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12201	B	MCC	II	7.2.11-8 02	RPU B2	1555	
						2379	E/D1-8G-005B					
	T09546	--	ELEC SWGR & MCC RM LEVEL C TRAIN A TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12202	B	MCC	I	7.2.11-8 02	RPU A2	1555	
						2000	E/D1-8G-005C					
	T09548	--	ELEC SWGR & MCC RM LEVEL B TRAIN B TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12203	B	MCC	II	7.2.11-8 02	RPU B2	1555	
						2076	E/D1-8G-005D					
	T09550	--	ELEC SWGR & MCC RM LEVEL 1 TRAIN A TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12204	B	MCC	I	7.2.11-8 02	RPU A2	1555	
						2506	E/D1-8G-005E					
	T09552	--	ELEC SWGR & MCC RM LEVEL 1 TRAIN B TEMP ALM ON CONTACTS CLSD ALM/NML: HIGH / NORMAL		TISH-12205	B	MCC	II	7.2.11-8 02	RPU B2	1555	
						2415	E/D1-8G-005F					

R ERF PROTEUS
 E SYMBOL Y SIGNAL DESCRIPTION
 Y SOURCE CLASS VAR CLASS VIA SYSTEM S
 P
 D

ALM ON CONTACTS	SIGNAL DESCRIPTION	ALM/NMLE HIGH	CLSD ALM/NMLE HIGH	TRAIN A TEMP	TRAIN B TEMP	TRAIN C TEMP	TRAIN A TEMP	TRAIN B TEMP	TRAIN C TEMP	ORIGINATING DEVICE	SIGNAL SIGNAL	SOURCE CLASS	VAR CLASS	VIA SYSTEM
TD9554	--- SIS PUMP ROOM TRAIN A TEMP									TISH-12218	MCC I	E/01-86-005R	7.2.11-B 02 RPU A2	1565
TD9556	--- SIS PUMP ROOM TRAIN B TEMP									TISH-12218	MCC II	E/01-86-085Q	7.2.11-B 02 RPU B2	1565
TD9558	--- BFP HEAT EXCH & PUMP RM TRAIN A TEMP									TISH-12211	MCC I	E/01-86-083U	7.2.11-B 02 RPU A2	1555
TD9558	--- BFP HEAT EXCH & PUMP RM TRAIN B TEMP									TISH-12217	MCC II	E/01-86-085V	7.2.11-B 02 RPU B2	1555
TD9572	--- AUX Fw PUMP HOUSE TRAIN A TEMP									TIS-12086	FLD I	E/01-86-083A	7.2.11-B 02 RPU A2	1593
TD9576	--- AUX Fw PUMP HOUSE TRAIN B TEMP									TIS-12086	FLD II	E/01-86-083B	7.2.11-B 02 RPU B2	1593
TD9665	--- DIESEL GEN BUILDING TRAIN B									TISHL-12057A	FLD NMS	7.2.11-B 02 SOE	1566	
TD9666	--- DIESEL GEN BUILDING TRAIN A									TISHL-12056A	FLD NMS	7.2.11-B 02 SOE	1566	
TD9667	--- AUX Fw PUMP HOUSE TRAIN C TEMP									TIS-12084	FLD NMS	--	RPU NI	1593
UC9257	--- LATEST PASS BORON SAMPLE SCALE1	B > 6000	PT/A							CALC VALUE	GPC	--	6.2.01-C C3 CALC	2782
UC9258	--- LATEST PASS CHLORIDE SAMPLE SCALE1	B > 20	PPM							CALC VALUE	GPC	--	6.2.01-C C3 CALC	2782
UC9259	--- LATEST PASS DISSOLVED HYDROGEN SAMPLE SCALE1	B > 2000	CC/RS							CALC VALUE	GPC	--	6.2.01-C C3 CALC	2782

Y	ERF SYMBOL	PHOTEUB SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	WG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D
	UC9268	--	LATEST PASS DISSOLVED OXYGEN SAMPLE SCALES B > 2.00E+4	CALC VALUE PPB	GPC 8182	-	-	6.2.01-C	C3 CALC	2702	
	UD5006	--	REACTOR	CALC VALUE	GPC 8317	-	-	7.2.14	D2 CALC	1800	X
	UD5198	--	CHARGING PMP TRN A THROTTLE VLV (SEE H5198)	CALC VALUE	GPC 8325	-	-	7.2.03-E	D2 CALC	1200	
	UD5191	--	CHARGING PMP TRN B THROTTLE VLV (SEE H5191)	CALC VALUE	GPC 8326	-	-	7.2.03-E	D2 CALC	1200	
	UD5442	--	LETDOWN TO PRT TRN A THROTTLE VLV (SEE H5442)	CALC VALUE	GPC 8321	-	-	7.2.05-E	D2 CALC	1200	
	UD5443	--	LETDOWN TO PRT TRN B THROTTLE VLV (SEE H5443)	CALC VALUE	GPC 8322	-	-	7.2.05-E	D2 CALC	1200	
	UD5943	--	B1 ACCUM TANK N2 HDR VENT VLV TRN A (SEE H5943)	CALC VALUE	GPC 8323	-	-	7.2.05-E	D2 CALC	1204	
	UD5944	--	B1 ACCUM TANK N2 HDR VENT VLV TRN B (SEE H5944)	CALC VALUE	GPC 8324	-	-	7.2.05-E	D2 CALC	1204	
*	UD5626	--	RHW TROUBLE	CALC VALUE	GPC 8329	-	-	--	- CALC	1205	X
*	UD6001	--	ADVERSE CONTAINMENT CONDITIONS	CALC VALUE	GPC 8328	-	-	--	- CALC	1206	X
	UD6158	--	SAFETY INJECTION SIGNAL	CALC VALUE	GPC 8314	-	-	7.2.14	D2 CALC	1204	X
	UD6160	--	CONTAINMENT ISOLATION SIGNAL	CALC VALUE	GPC 8316	-	-	7.2.14	D2 CALC	2415	X

R ERF PROTEUS
 V SYMBOL SIGNAL DESCRIPTION SIGNAL SOURCE CLASS VAR CLASS IN-IT SYSTEM 3
 P

UD	SYMBOL	SIGNAL	DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE	CLASS	VAR CLASS	IN-IT	SYSTEM
UD06101	--	CONTAINMENT ISOLATED	GPC 0313	7.2.14	02	CALC	2415	X	
UD07001	--	TURBINE	GPC 0315	7.2.14	02	CALC	1701	X	
UD07002	--	MAIN TURB STOP VALVE SV1	XY-0001 GPC 0307	7.2.14	02	CALC	1701	X	
UD07004	--	MAIN TURB STOP VALVE SV2	XY-0002 GPC 0309	7.2.14	02	CALC	1701	X	
UD07006	--	MAIN TURB STOP VALVE SV3	XY-0003 GPC 0301	7.2.14	02	CALC	1701	X	
UD07008	--	MAIN TURB STOP VALVE SV4	XY-0004 GPC 0303	7.2.14	02	CALC	1701	X	
UD07010	--	MAIN TURB CONTROL VALVE CV1	XY-0005 GPC 0420	--	--	CALC	1301		
UD07012	--	MAIN TURB CONTROL VALVE CV2	XY-0006 GPC 0430	--	--	CALC	1301		
UD07014	--	MAIN TURB CONTROL VALVE CV3	XY-0007 GPC 0432	--	--	CALC	1301		
UD07016	--	MAIN TURB CONTROL VALVE CV4	XY-0008 GPC 0411	--	--	CALC	1301		
UD07042	--	MAIN TURB INTERMEDIATE STOP VLV ISV1	CALC VALUE GPC 0413	--	--	CALC	1301		
UD07044	--	MAIN TURB INTERMEDIATE STOP VLV ISV2	CALC VALUE GPC 0415	--	--	CALC	1301		

Y	ERP SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	B
	UD7040	--	MAIN TURB INTERMEDIATE STOP VLV ISV3	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0417						
	UD7040	--	MAIN TURB INTERMEDIATE STOP VLV ISV4	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0419						
	UD7050	--	MAIN TURB INTERMEDIATE STOP VLV ISV5	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0421						
	UD7052	--	MAIN TURB INTERMEDIATE STOP VLV ISV6	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0439						
	UD7054	--	MAIN TURBINE INTERCEPT VALVE IV1	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0441						
	UD7056	--	MAIN TURBINE INTERCEPT VALVE IV2	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0443						
	UD7058	--	MAIN TURBINE INTERCEPT VALVE IV3	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0445						
	UD7060	--	MAIN TURBINE INTERCEPT VALVE IV4	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0447						
	UD7062	--	MAIN TURBINE INTERCEPT VALVE IV5	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0449						
	UD7064	--	MAIN TURBINE INTERCEPT VALVE IV6	CALC VALUE	GPC	-	-	--	-	CALC	1301
					0451						
	UD7101	--	S01 MAIN STM ISOL VLV UPSTREAM TRAIN A	HV-3006A	GPC	-	-	S,2,05-F 02		CALC	1301
					0404						
	UD7103	--	S02 MAIN STM ISOL VLV UPSTREAM TRAIN A	HV-3016A	GPC	-	-	S,2,05-F 02		CALC	1301
					0401						

R E ERF PROTEUS
 Y SYMBOL SYMBOL SIGNAL DESCRIPTION SIGNAL SOURCE B ORIGINATING B SIGNAL SIGNAL HG 1.97 INPUT
 DEVICE Y SOURCE CLASS VAR CLASS VIA SYSTEM S

UD7185	--	SG3 MAIN STM ISOL VLV UPSTREAM TRAIN A	GP	GP	5.2.05-F	B2 CALC	1301
UD7187	--	SG4 MAIN STM ISOL VLV UPSTREAM TRAIN A	GP	GP	5.2.05-F	B2 CALC	1301
UD7111	--	SG1 MAIN STM ISOL VLV DNSTHM TRAIN B	GP	GP	5.2.05-F	B2 CALC	1301
UD7113	--	SG2 MAIN STM ISOL VLV DNSTHM TRAIN B	GP	GP	5.2.05-F	B2 CALC	1301
UD7115	--	SG3 MAIN STM ISOL VLV DNSTHM TRAIN B	GP	GP	5.2.05-F	B2 CALC	1301
UD7117	--	SG4 MAIN STM ISOL VLV DNSTHM TRAIN B	GP	GP	5.2.05-F	B2 CALC	1301
UD7131	--	SG1 OUILET VALVE TO TDAFM TRAIN B	GP	GP	7.2.06-C	O2 CALC	1301
UD7133	--	SG2 OUILET VALVE TO TDAFM TRAIN C	GP	GP	7.2.06-C	O2 CALC	1301
UD7146	--	STM DUMP TV-580A TO CONDENSER A	GP	GP	--	-- CALC	1301
UD7148	--	STM DUMP TV-580B TO CONDENSER B	GP	GP	--	-- CALC	1301
UD7150	--	STM DUMP TV-580C TO CONDENSER C	GP	GP	--	-- CALC	1301
UD7152	--	STM DUMP TV-580D TO CONDENSER A	GP	GP	--	-- CALC	1301

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D B
UD7154	--	STM DUMP -500E TO CONDENSER	TV-0500E	GPC 0499	-	-	--	- CALC	1301	
UD7156	--	STM DUMP TV-500F TO CONDENSER C	TV-0500F	GPC 0498	-	-	--	- CALC	1301	
UD7158	--	STM DUMP TV-500G TO CONDENSER A	TV-0500G	GPC 0497	-	-	--	- CALC	1301	
UD7160	--	STM DUMP TV-500H TO CONDENSER B	TV-0500H	GPC 0496	-	-	--	- CALC	1301	
UD7162	--	STM DUMP TV-500J TO CONDENSER C	TV-0500J	GPC 0495	-	-	--	- CALC	1301	
UD7164	--	STM DUMP PV-507A TO CONDENSER A	PV-0507A	GPC 0464	-	-	--	- CALC	1301	
UD7166	--	STM DUMP PV-507B TO CONDENSER B	PV-0507B	GPC 0463	-	-	--	- CALC	1301	
UD7168	--	STM DUMP PV-507C TO CONDENSER C	PV-0507C	GPC 0462	-	-	--	- CALC	1301	
UD7331	--	TDAFW DISCH VLV TO 8G4	HV-5120	GPC 0522	-	-	7.2.06-C 02	CALC	1302	
UD7333	--	TDAFW DISCH VLV TO 8G1	HV-5122	GPC 0521	-	-	7.2.06-C 02	CALC	1302	
UD7335	--	TDAFW DISCH VLV TO 8G2	HV-5125	GPC 0520	-	-	7.2.06-C 02	CALC	1302	
UD7337	--	TDAFW DISCH VLV TO 8G3	HV-5127	GPC 0519	-	-	7.2.06-C 02	CALC	1302	

R E Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	HG 1.97 VAL CLASS	INPUT VIA	SYSTEM	B P D B
	UD7338	--	MD AFW-B DISCH VLV TO 362	HV-5132	GPC 8518	-	-	7.2.86-C	D2 CALC	1382	
	UD7341	--	MD AFW-B DISCH VLV TO 363	HV-5134	GPC 8517	-	-	7.2.86-C	D2 CALC	1382	
	UD7343	--	MD AFW-A DISCH VLV TO 364	HV-5137	GPC 8516	-	-	7.2.86-C	D2 CALC	1382	
	UD7345	--	MD AFW-A DISCH VLV TO 361	HV-5139	GPC 8515	-	-	7.2.86-C	D2 CALC	1382	
	UD7351	--	MD AFW-A INLET VALVE	HV-5119	GPC 8414	-	-	7.2.86-C	D2 CALC	1382	
	UD7353	--	MD AFW-B INLET VALVE	HV-5118	GPC 8412	-	-	7.2.86-C	D2 CALC	1382	
	UD7355	--	TDAFW INLET VALVE	HV-5113	GPC 8418	-	-	7.2.86-C	D2 CALC	1382	
	UD7357	--	TDAFW STEAM INLET VALVE	HV-5186	GPC 8489	-	-	7.2.86-C	D2 CALC	1382	
	UD7396	--	TDAFW PUMP TRAIN C	CALC VALUE	GPC 8327	-	-	7.2.14	D2 CALC	1382	
	UD7527	--	36 LOUP 1 FW ISOLATION - MFIV	HV-5227	GPC 8418	-	-	7.2.84-F	D2 CALC	1385	
	UD7528	--	36 LOUP 2 FW ISOLATION - MFIV	HV-5228	GPC 8428	-	-	7.2.84-F	D2 CALC	1385	
	UD7531	--	36 LOUP 3 FW ISOLATION - MFIV	HV-5229	GPC 8422	-	-	7.2.84-F	D2 CALC	1385	

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	RC 1.97 VAR CLASS	INPUT VIA	SYSTEM	8 P D 8
UD7533	--	36 LOOP 4 FW ISOLATION - MFIV	HV-5238	GPC #423	-	-	7.2.04-F D2 CALC	1305		
UD7537	--	361 BLUDDOWN ISOLATION	HV-7603A	GPC #513	-	-	7.2.04-K D2 CALC	1301		
UD7539	--	362 BLUDDOWN ISOLATION	HV-7603B	GPC #512	-	-	7.2.04-K D2 CALC	1301		
UD7541	--	363 BLUDDOWN ISOLATION	HV-7603C	GPC #511	-	-	7.2.04-K D2 CALC	1301		
UD7543	--	364 BLUDDOWN ISOLATION	HV-7603D	GPC #510	-	-	7.2.04-K D2 CALC	1301		
UD7603	--	N3CW COOLING TOWER WTN VALVE TRAIN A	HV-1668A	GPC #490	-	-	7.2.09-B D2 CALC	1202		
UD7604	--	N3CW COOLING TOWER BYPASS VLV TRAIN A	HV-1668B	GPC #397	-	-	7.2.09-B D2 CALC	1202		
UD7605	--	N3CW COOLING TOWER RTN VALVE TRAIN B	HV-1669A	GPC #489	-	-	7.2.09-B D2 CALC	1202		
UD7606	--	N3CW COOLING TOWER BYPASS VLV TRAIN B	HV-1669B	GPC #395	-	-	7.2.09-B D2 CALC	1202		
* UD7701	--	ACCW RETURN TRAIN A	HV-1975	GPC #487	-	-	-- - CALC	1217		
* UD7703	--	ACCW RETURN TRAIN B	HV-1974	GPC #488	-	-	-- - CALC	1217		
* UD7705	--	ACCW SUPPLY TRAIN A	HV-1979	GPC #485	-	-	-- - CALC	1217		

R	ERF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RC	1.97	INPUT		S
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR	CLASS	VIA	SYSTEM	D
*	UD7707	--	ACCM SUPPLY TRAIN 8	HV-1978	GPC	-	-	--	-	CALC	1217	
				#486								
	UD8418	--	CNMT BLDG AIR COOLING UNIT 1	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#359							
	UD8420	--	CNMT BLDG AIR COOLING UNIT 2	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#368							
	UD8422	--	CNMT BLDG AIR COOLING UNIT 5	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#363							
	UD8424	--	CNMT BLDG AIR COOLING UNIT 6	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#364							
	UD8458	--	CNMT BLDG AIR COOLING UNIT 3	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#361							
	UD8460	--	CNMT BLDG AIR COOLING UNIT 4	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#362							
	UD8462	--	CNMT BLDG AIR COOLING UNIT 7	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#365							
	UD8464	--	CNMT BLDG AIR COOLING UNIT 8	CALC VALUE	GPC	-	-	7.2.07-E	D2	CALC	1501	
					#366							
	UD8511	--	ACCUM ISOLATION LOOP 1 HV-8888A	HV-8888A	GPC	-	-	7.2.05-E	D2	CALC	1204	
					#536							
	UD8513	--	ACCUM ISOLATION LOOP 2 HV-8888B	HV-8888B	GPC	-	-	7.2.05-E	D2	CALC	1204	
					#535							
	UD8515	--	ACCUM ISOLATION LOOP 3 HV-8888C	HV-8888C	GPC	-	-	7.2.05-E	D2	CALC	1204	
					#534							

R ERF PROTEUS SIGNAL DESCRIPTION ORIGINATING DEVICE SIGNAL SOURCE CLASS VAR CLASS VIA SYSTEM S
 V SYMBOL SYMBOL SIGNAL DESCRIPTION ORIGINATING DEVICE SIGNAL SOURCE CLASS VAR CLASS VIA SYSTEM S

U08517	--	ACCUM ISOLATION LOOP 4	MV-8888D	GPC 0533	-	-	7.2.05-E 02 CALC	1200
U08541	--	PORV-455A BLOCK VLV	MV-8888A	GPC 0509	-	-	7.2.02-A P2 CALC	1201
U08543	--	PORV-456B BLOCK VLV	MV-8888B	GPC 0508	-	-	7.2.02-A 02 CALC	1201
U08545	--	PRESSURIZER PORV-456A TRAIN B	PV-8456A	GPC 0465	-	-	7.2.02-A 02 CALC	1201
U08547	--	PRESSURIZER PORV-455A TRAIN A	PV-8455A	GPC 0466	-	-	7.2.02-A 02 CALC	1201
U08561	--	S1 PUMPS INLET VALVE	MV-8888	GPC 0537	-	-	7.2.05-E 02 CALC	1204
U08630	--	CHARGING PATH VLV TO REGEN HX TRAIN B	MV-8105	GPC 0544	-	-	7.2.03-E 02 CALC	1200
U08638	--	CHARGING PATH VLV TO REGEN HX TRAIN A	MV-8106	GPC 0543	-	-	7.2.03-E 02 CALC	1200
U08641	--	CHARGING PATH VALVE TO RCS TRAIN A	MV-8146	GPC 0542	-	-	7.2.03-E 02 CALC	1200
U08643	--	CHARGING PATH VALVE TO RCS TRAIN B	MV-8147	GPC 0454	-	-	7.2.03-E 02 CALC	1200
U08646	--	RHR PUMP A TO CVCS PUMP SUCTION VALVE	MV-8894A	GPC 0371	-	-	7.2.10-B 02 CALC	1200
U08648	--	RHR PUMP B TO SIS PUMP SUCTION VALVE	MV-8894B	GPC 0378	-	-	7.2.10-B 02 CALC	1200

R	ERF	PHOTEUS		ORIGINATING	B	SIGNAL	SIGNAL	HG 1.97	INPUT		B
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAL CLASS	VIA	SYSTEM	B
	UD8651	--	CHARGING PUMP (TRAIN A) DISCH VALVE	HV-8116	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#455						
	UD8653	--	CHARGING PUMP (TRAIN A) DISCH VALVE	HV-8485A	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#539						
	UD8655	--	CHARGING PUMP (TRAIN B) DISCH VALVE	HV-8485B	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#538						
	UD8666	--	CHARGING PUMP (TRAIN A) SUCTION VALVE	HV-8471A	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#541						
	UD8668	--	CHARGING PUMP (TRAIN B) SUCTION VALVE	HV-8471B	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#540						
	UD8671	--	RWST TO CHARGING PUMPS TRAIN A VALVE	LV-8112D	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#475						
	UD8673	--	RWST TO CHARGING PUMPS TRAIN B VALVE	LV-8112E	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#474						
	UD8676	--	VCT TO CHARGING PUMPS TRAIN A VALVE	LV-8112B	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#532						
	UD8678	--	VCT TO CHARGING PUMPS TRAIN B VALVE	LV-8112C	GPC	-	-	7.2.03-E	D2 CALC	1200	
					#531						
	UD8681	--	RHR PUMP TRAIN A SUCTION VALVE 8701A	HV-8701A	GPC	-	-	7.2.10-B	D2 CALC	1200	X
					#375						
	UD8683	--	RHR PUMP TRAIN A SUCTION VALVE 8701B	HV-8701B	GPC	-	-	7.2.10-B	D2 CALC	1200	X
					#377						
	UD8685	--	RHR PUMP TRAIN B SUCTION VALVE 8702A	HV-8702A	GPC	-	-	7.2.10-B	D2 CALC	1200	X
					#379						

R	E	ERF	PROTEUS	SIGNAL DESCRIPTION	UNIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT		B	
V		SYMBOL	SYMBOL		DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	P	
												D	
		UD8687	--	RHR PUMP TRAIN B SUCTION VALVE 87028	HV-87028	GPC	-	-	7.2.10-B	D2	CALC	1205	X
		UD8691	--	RHR PUMP TRAIN A RECIRC VALVE	FV-8618	GPC	-	-	7.2.10-B	D2	CALC	1205	
		UD8693	--	RHR PUMP TRAIN B RECIRC VALVE	FV-8611	GPC	-	-	7.2.10-B	D2	CALC	1205	
		UD8696	--	RHR HEAT EXCH TRAIN A BYPASS VALVE	FV-8618	GPC	-	-	--	-	CALC	1205	
		UD8698	--	RHR HEAT EXCH TRAIN B BYPASS VALVE	FV-8619	GPC	-	-	--	-	CALC	1205	
		UD8701	--	RHR HEAT EXCH TRAIN A DISCH VALVE	HV-8606	GPC	-	-	--	-	CALC	1205	
		UD8703	--	RHR HEAT EXCH TRAIN B DISCH VALVE	HV-8607	GPC	-	-	--	-	CALC	1205	
		UD8706	--	RHR PUMP A SUCTION VALVE (RWST)	HV-8812A	GPC	-	-	7.2.10-B	D2	CALC	1205	
		UD8708	--	RHR PUMP B SUCTION VALVE (RWST)	HV-8812B	GPC	-	-	7.2.10-B	D2	CALC	1205	
		UD8711	--	RHR VALVE TO COLD LEGS 1 & 2 TRAIN A	HV-8809A	GPC	-	-	7.2.10-B	D2	CALC	1204	X
		UD8713	--	RHR VALVE TO COLD LEGS 3 & 4 TRAIN B	HV-8809B	GPC	-	-	7.2.10-B	D2	CALC	1204	X
		UD8727	--	BORIC ACID VALVE TO CHARGING PUMPS	HV-8184	GPC	-	-	7.2.03-E	D2	CALC	1200	

R	E	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S
V	SYMBOL	SYMBOL			DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	9 STEM 8
*	UD8793	--		ELEC PEN RM FLTR TRN A OUT DAMPER	HV-12561	GPC	-	-	7.2.11-A D2 CALC	1562	
					8476				(UNIT 1 INPUT ONLY)		
*	UD8795	--		ELEC PEN RM FLTR TRN A VENT DAMPER	HV-12555	GPC	-	-	7.2.11-A D2 CALC	1562	
					8478				(UNIT 1 INPUT ONLY)		
*	UD8799	--		ELEC PEN RM FLTR TRN B OUT DAMPER	HV-12568	GPC	-	-	7.2.11-A D2 CALC	1562	
					8477				(UNIT 1 INPUT ONLY)		
*	UD8801	--		ELEC PEN RM FLTR TRN B VENT DAMPER	HV-12554	GPC	-	-	7.2.11-A D2 CALC	1562	
					8479				(UNIT 1 INPUT ONLY)		
	UD9875	--		SI PUMP B TO HOT LEGS 2&3	HV-88028	GPC	-	-	7.2.05-E D2 CALC	1204	
					8551						
	UD9879	--		BORON INJECTION TANK DISCH TRAIN A	HV-8801A	GPC	-	-	7.2.05-E D2 CALC	1204	
					8458						
	UD9881	--		BORON INJECTION TANK DISCH TRAIN B	HV-8801B	GPC	-	-	7.2.05-E D2 CALC	1204	
					8448						
	UD9885	--		SI PUMP A TO HOT LEGS 1&4	HV-8802A	GPC	-	-	7.2.05-E D2 CALC	1204	
					8552						
	UD9889	--		RHR PUMP A CMHT SUMP SUCTION ISOL VALVE	HV-8811A	GPC	-	-	7.2.10-B D2 CALC	1205	
					8482						
	UD9891	--		RHR PUMP B CMHT SUMP SUCTION ISOL VALVE	HV-8811B	GPC	-	-	7.2.10-B D2 CALC	1205	
					8484						
	UD9137	--		RHR PUMP DISCH TO HOT LEG LOOPS 1&4	HV-8848	GPC	-	-	7.2.10-B D2 CALC	1204	
					8558						
	UD9262	--		PRESSURIZER SAFETY VALVE A	PSV-8818A	GPC	-	-	7.2.02-B D2 CALC	1201	
					8318						

ERP SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	SIGNAL CLASS	7.2.82-B 02 CALC	7.2.83-E 02 CALC	1200
U09264	--	PRESSURIZER SAFETY VALVE B	PSV-8818B	GPC 8319	--	7.2.82-B 02 CALC		1200
U09266	--	PRESSURIZER SAFETY VALVE C	PSV-8818C	GPC 8320	--	7.2.82-B 02 CALC		1200
U09288	--	SEAL FLOW CONTROL-THROTTLES CMG FLOW	HV-8182	GPC 8487	--	--	--	1200
U09291	--	CCP A MINIFLOW VALVE TO VCT	HV-8111A	GPC 8431	--	7.2.83-E 02 CALC		1200
U09293	--	CCP B MINIFLOW VALVE TO VCT	HV-8111B	GPC 8456	--	7.2.83-E 02 CALC		1200
U09295	--	CCP COMMON MINIFLOW VALVE TO VCT	HV-8110	GPC 8429	--	7.2.83-E 02 CALC		1200
U09305	--	MCP 1 SEAL WATER INLET	HV-8103A	GPC 8587	--	7.2.83-E 02 CALC		1200
U09307	--	RCP 2 SEAL WATER INLET	HV-8103B	GPC 8586	--	7.2.83-E 02 CALC		1200
U09309	--	RCP 3 SEAL WATER INLET	HV-8103C	GPC 8585	--	7.2.83-E 02 CALC		1200
U09311	--	RCP 4 SEAL WATER INLET	HV-8103D	GPC 8545	--	7.2.83-E 02 CALC		1200
U09325	--	CHARGING PUMPS DISCHARGE XCONN	HV-8436	GPC 8453	--	7.2.83-E 02 CALC		1200
U09327	--	BORIC ACID TO CHARGING PUMP B	HV-8439	GPC 8452	--	7.2.83-E 02 CALC		1200

REV	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	UNIT	SIGNAL SOURCE	SIGNAL CLASS	RC 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
	UD9329	--	CHARGING PUMP SUCT HDR TO/FROM 3/8 PMP A	HY-8924	GPC 8369	-	-	7.2.85-E D2	CALC	1288	
	UD9335	--	3G1 MAIN FEED HEG VALVE - MFRV	FV-8518	GPC 8494	-	-	7.2.84-E D2	CALC	1385	
	UD9337	--	3G2 MAIN FEED HEG VALVE - MFRV	FV-8528	GPC 8493	-	-	7.2.84-E D2	CALC	1385	
	UD9339	--	3G3 MAIN FEED HEG VALVE - MFRV	FV-8538	GPC 8492	-	-	7.2.84-E D2	CALC	1385	
	UD9341	--	3G4 MAIN FEED HEG VALVE - MFRV	FV-8548	GPC 8491	-	-	7.2.84-E D2	CALC	1385	
	UD9343	--	3G1 BYPASS FEED HEG VALVE - BFRV	LV-5243	GPC 8472	-	-	7.2.84-E D2	CALC	1385	
	UD9345	--	3G2 BYPASS FEED HEG VALVE - BFRV	LV-5244	GPC 8471	-	-	7.2.84-E D2	CALC	1385	
	UD9347	--	3G3 BYPASS FEED HEG VALVE - BFRV	LV-5245	GPC 8478	-	-	7.2.84-E D2	CALC	1385	
	UD9349	--	3G4 BYPASS FEED HEG VALVE - BFRV	LV-5242	GPC 8473	-	-	7.2.84-E D2	CALC	1385	
	UD9351	--	3G1 ATMOSPHERIC RELIEF VALVE (CH 1)	PV-3888	GPC 8459	-	-	7.2.84-A D2	CALC	1381	
	UD9353	--	3G2 ATMOSPHERIC RELIEF VALVE (CH 2)	PV-3818	GPC 8458	-	-	7.2.84-A D2	CALC	1381	
	UD9355	--	3G3 ATMOSPHERIC RELIEF VALVE (CH 1)	PV-3828	GPC 8457	-	-	7.2.84-A D2	CALC	1381	

R E Y	ENF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	HG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S
											P
	UD9367	--	364 ATMOSPHERIC RELIEF VALVE (CH 2)	PV-3030	GPC 0504	-	-	7.2.04-A	02 CALC	1301	
	UD9371	--	81 PUMP A INLET VALVE	HV-0923A	GPC 0372	-	-	7.2.05-E	02 CALC	1204	
	UD9373	--	81 PUMP B INLET VALVE	HV-0923B	GPC 0370	-	-	7.2.05-E	02 CALC	1204	
	UD9375	--	81 PUMP A TO COLD LEGS 104	HV-0021A	GPC 0376	-	-	7.2.05-E	02 CALC	1204	
	UD9377	--	81 PUMP B TO COLD LEGS 243	HV-0021B	GPC 0374	-	-	7.2.05-E	02 CALC	1204	
	UD9379	--	81S COLD LEG LOOP INLET HEADER	HV-0035	GPC 0373	-	-	7.2.05-E	02 CALC	1204	
	UD9391	--	81 PUMP B MINIFLOW VALVE (TRAIN A ISOL)	HV-0920	GPC 0436	-	-	7.2.05-E	02 CALC	1204	
	UD9393	--	81 PUMPS MINIFLOW VALVE (TRAIN B ISOL)	HV-0013	GPC 0442	-	-	7.2.05-E	02 CALC	1204	
	UD9395	--	81 PUMP A MINIFLOW	HV-0014	GPC 0440	-	-	7.2.05-E	02 CALC	1204	
	UD9399	--	MAIN STEAM LINE DRAIN TO CONDENSER	HV-0179	GPC 0399	-	-	--	- CALC	1301	
	UD9401	--	AUX FEED TRB STM LINE DRAIN TO CONDENSER	HV-0178	GPC 0410	-	-	--	- CALC	1301	
	UD9405	--	MD AUX FEED PUMP B MINIFLOW VALVE	FV-0154	GPC 0382	-	-	7.2.06-C	02 CALC	1302	

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	HG 1.07 VAN CLASS	INPUT VIA	SYSTEM	S P D
UD9407	--	MD AUX FEED PUMP A MINIFLOW VALVE	FV-515B	GPC #384	-	-	7.2.06-C D2 CALC		1302	
UD9410	--	CNMT SPRAY PUMP A RNST SUCTION	HV-9817A	GPC #368	-	-	7.2.07-C D2 CALC		1206	
UD9412	--	CNMT SPRAY PUMP B RNST SUCTION	HV-9817B	GPC #367	-	-	7.2.07-C D2 CALC		1206	
UD9414	--	CNMT SPRAY PUMP A DISCHARGE TO SPRAY HDR	HV-9801A	GPC #435	-	-	7.2.07-C D2 CALC		1206	
UD9416	--	CNMT SPRAY PUMP B DISCHARGE TO SPRAY HDR	HV-9801B	GPC #434	-	-	7.2.07-C D2 CALC		1206	
UD9418	--	SPRAY ADDITIVE TANK OUTLET TRAIN A	HV-8994A	GPC #437	-	-	7.2.07-C D2 CALC		1206	
UD9420	--	SPRAY ADDITIVE TANK OUTLET TRAIN B	HV-8994B	GPC #436	-	-	7.2.07-C D2 CALC		1206	
UD9422	--	CS PUMP A CNMT SUMP SUCTION VALVE IRC	HV-9802A	GPC #549	-	-	7.2.07-C D2 CALC		1206	
UD9424	--	CS PUMP B CNMT SUMP SUCTION VALVE IRC	HV-9802B	GPC #548	-	-	7.2.07-C D2 CALC		1206	
UD9426	--	CS PUMP A CNMT SUMP SUCTION VALVE ORC	HV-9803A	GPC #547	-	-	7.2.07-C D2 CALC		1206	
UD9428	--	CS PUMP B CNMT SUMP SUCTION VALVE ORC	HV-9803B	GPC #546	-	-	7.2.07-C D2 CALC		1206	
UD9454	--	PIPING PEN RM HVAC TRN A TO LOADS	PV-2500A	GPC #538	-	-	7.2.11-A D2 CALC		1661	

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	SIGNAL	SOURCE CLASS	VAR CLASS	INPUT VIA SYSTEM
UD9456	--	PIPING PEN RM HVAC TRN B TO LOADS	PV-2551A	GPC 8529	7.2.11-A D2 CALC	1561
UD9458	--	PIPING PEN RM HVAC TRN A TO ATMOS	PV-2558B	GPC 8451	7.2.11-A D2 CALC	1561
UD9459	--	PIPING PEN RM HVAC TRN B TO ATMOS	PV-2551B	GPC 8488	7.2.11-A D2 CALC	1561
UD9465	--	CONTROL ROOM HVAC #5A INTAKE TRAIN A	HV-12114	GPC 8433	7.2.11-A D2 CALC	1531
UD9468	--	CONTROL ROOM HVAC #5A INTAKE TRAIN B	HV-12115	GPC 8484	7.2.11-A D2 CALC	1531
UD9594	--	MHW PUMP A TO HOT LEG ISOLATION VALVE	HV-8716A	GPC 8486	7.2.10-B D2 CALC	1285
UD9595	--	MHW PUMP B TO HOT LEG ISOLATION VALVE	HV-8716B	GPC 8488	7.2.10-B D2 CALC	1285
UD9604	--	ATMT SIGNAL	CALC VALUE	GPC 8338	-- CALC	1626 X
UD9801	--	CHARGING PUMP A MINIFLOW ISOL VLV	HV-8588A	GPC 8353	7.2.03-E D2 CALC	1288
UD9803	--	CHARGING PUMP B MINIFLOW ISOL VLV	HV-8588B	GPC 8354	7.2.03-E D2 CALC	1288
UD9805	--	CHARGING PUMP C MINIFLOW ISOL VLV	HV-8589A	GPC 8355	7.2.03-E D2 CALC	1288
UD9807	--	CHARGING PUMP A MINIFLOW ISOL VLV	HV-8589B	GPC 8356	7.2.03-E D2 CALC	1288

R E V

REF SYMBOL	PROIEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D
UD9809	--	SI/CHARGING PUMPS SUCTION IRN A TIE VLV	HV-8807A	GPC #357	-	-	7.2.05-E 02	CALC	1204	
UD9811	--	SI/CHARGING PUMPS SUCTION IRN B TIE VLV	HV-8807B	GPC #358	-	-	7.2.05-E 02	CALC	1204	
UD9817	--	SG1 MSIV UPSTREAM TRAIN A BYPASS	HV-13005A	GPC #345	-	-	5.2.05-F 02	CALC	1301	
UD9819	--	SG1 MSIV UPSTREAM TRAIN B BYPASS	HV-13005B	GPC #349	-	-	5.2.05-F 02	CALC	1301	
UD9821	--	SG4 MSIV UPSTREAM TRAIN A BYPASS	HV-13006A	GPC #346	-	-	5.2.05-F 02	CALC	1301	
UD9823	--	SG4 MSIV UPSTREAM TRAIN B BYPASS	HV-13006B	GPC #350	-	-	5.2.05-F 02	CALC	1301	
UD9825	--	SG2 MSIV UPSTREAM TRAIN A BYPASS	HV-13007A	GPC #347	-	-	5.2.05-F 02	CALC	1301	
UD9827	--	SG2 MSIV UPSTREAM TRAIN B BYPASS	HV-13007B	GPC #351	-	-	5.2.05-F 02	CALC	1301	
UD9829	--	SG3 MSIV UPSTREAM TRAIN A BYPASS	HV-13008A	GPC #348	-	-	5.2.05-F 02	CALC	1301	
UD9831	--	SG3 MSIV UPSTREAM TRAIN B BYPASS	HV-13008B	GPC #352	-	-	5.2.05-F 02	CALC	1301	
UP5403	--	TOTAL FEEDWATER FLOW (FW + AUX FW) SCALE: 0 > 4.30E04	CALC VALUE GPM	GPC #215	-	-	--	- CALC	1305	X
UP5404	--	SG1 TOTAL FW FLOW (FW + AUX FW) SCALE: 0 > 5300 KBH	CALC VALUE	GPC #207	-	-	--	- CALC	1305	X

R	E	Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
			UF5485	--	TOTAL STEAM GENERATOR STEAM LINE FLOW SCALE: @ > 1.92E04	CALC VALUE RBH	GPC #258	-	-	7.2.04-C 02	CALC	1301	
			UF5424	--	SG2 TOTAL FW FLOW (FW + AUX FW) SCALE: @ > 5300 KBH	CALC VALUE	GPC #208	-	-	--	-	CALC	1305 X
			UF5425	--	CALC LO LIMIT (MODES 1,2) FOR SG1-4 STEAM FLOW SCALE: @ > 5500 KBH	CALC VALUE	GPC #213	-	-	--	-	CALC	1301 X
			UF5426	--	CALC HI LIMIT (MODES 1,2) FOR SG1-4 STEAM FLOW SCALE: @ > 5500 KBH	CALC VALUE	GPC #214	-	-	--	-	CALC	1301 X
			UF5444	--	SG3 TOTAL FW FLOW (FW + AUX FW) SCALE: @ > 5300 KBH	CALC VALUE	GPC #209	-	-	--	-	CALC	1305 X
			UF5464	--	SG4 TOTAL FW FLOW (FW + AUX FW) SCALE: @ > 5300 KBH	CALC VALUE	GPC #210	-	-	--	-	CALC	1305 X
			UF7326	--	CALC LO LIMIT (MODES 1,2) FOR SG TOTAL FW FLOW SCALE: @ > 5500 KBH	CALC VALUE	GPC #211	-	-	--	-	CALC	1305 X
			UF7327	--	CALC HI LIMIT (MODES 1,2) FOR SG TOTAL FW FLOW SCALE: @ > 5500 KBH	CALC VALUE	GPC #212	-	-	--	-	CALC	1305 X
			UF7601	--	NSCW THAIN A SUPPLY/RETURN DIFFERENTIAL FLOW SCALE: @ > 2.50E04	CALC VALUE GPH	GPC #256	-	-	--	-	CALC	1202
			UF7602	--	NSCW THAIN B SUPPLY/RETURN DIFFERENTIAL FLOW SCALE: @ > 2.50E04	CALC VALUE GPH	GPC #255	-	-	--	-	CALC	1202
			UF9627	--	TOTAL AUXILIARY FEEDWATER FLOW SCALE: @ > 2400 GPM	CALC VALUE	GPC #201	-	-	--	-	CALC	1302 X
			UJR610	--	CLASS 1E 125VDC BATTERY 1AD10 CUMULATIVE DISCH SCALE: @ > 9999 AMP HOURS	CALC VALUE	GPC #184	-	-	--	-	CALC	1000

R	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING	B	SIGNAL	SIGNAL	HC 1.97	INPUT		S
Y	SYMBOL	SYMBOL		DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	D
	UJ9620	--	CLASS 1E 125VDC BATTERY 18018 CUMULATIVE DISCH SCALE: 0 > 9999 AMP HOURS	CALC VALUE	GPC	-	-	--	-	CALC	1806
	UJ9621	--	CLASS 1E 125VDC BATTERY 1C01C CUMULATIVE DISCH SCALE: 0 > 9999 AMP HOURS	CALC VALUE	GPC	-	-	--	-	CALC	1806
	UJ9622	--	CLASS 1E 125VDC BATTERY 1001D CUMULATIVE DISCH SCALE: 0 > 9999 AMP HOURS	CALC VALUE	GPC	-	-	--	-	CALC	1806
*	UL5480	--	CALC LO LIMIT (MODE 1-2) FOR PRESSURIZER LEVEL SCALE: 15 > 55 PERCENT	CALC VALUE	GPC	-	-	--	-	CALC	1201 X
	UL5481	--	CALC HI LIMIT (MODE 1-2) FOR PRESSURIZER LEVEL SCALE: 25 > 65 PERCENT	CALC VALUE	GPC	-	-	--	-	CALC	1201 X
*	UL6175	--	PRI MET TWR PRECIPITATION (15 MIN AVG) SCALE: 0 > 1 INCHES	CALC VALUE	GPC	-	-	0.2.00	E3	CALC	2001 (UNIT 1 INPUT ONLY)
*	UL9003	--	CONTAINMENT WATER LEVEL SCALE: 0 > 800 KGAL	CALC VALUE	GPC	-	-	4.2.10	A1	CALC	1205 X
*	UM5000	--	CPU ACTIVITY SCALE: 0 > 100 PERCENT	CALC VALUE	GPC	-	-	--	-	CALC	1010
	UM5001	--	PLANT OPERATING MODE SCALE: 0 > 6	CALC VALUE	GPC	-	-	--	-	CALC	1006 X
	UM5026	--	RHR LOOPS IN OPERATION SCALE: 0 > 2 LOOP(S)	CALC VALUE	GPC	-	-	--	-	CALC	1205 X
	UM5001	--	NUMBER OF RCPS RUNNING SCALE: 0 > 4	CALC VALUE	GPC	-	-	7.2.01-0	D2	CALC	1201 X
	UP5400	--	CALC LO LIMIT (MODE 1-4) FOR SG PRESSURE OUT SCALE: 0 > 3000 PSIG	CALC VALUE	GPC	-	-	--	-	CALC	1301 X

R E V	ERF SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RC 1,97 VAR CLASS	INPUT VIA	SYSTEM	S
	UP5400	--	CALC LU LIMIT (MODE 4)-RCS HR PRESS (PSAT+30) SCALE: 0 > 3200 PSIG	CALC VALUE	GPC	-	-	--	-	CALC	1201 X
	UP5409	--	CALC HI LIMIT (MODE 4)-RCS HR PRESS (PSAT+100) SCALE: 0 > 3200 PSIG	CALC VALUE	GPC	-	-	--	-	CALC	1201 X
	UP5420	--	CALC HI LIMIT (MODE 1-4) FOR SG PRESSURE OUT SCALE: 0 > 3000 PSIG	CALC VALUE	GPC	-	-	--	-	CALC	1301 X
	UR5031	--	SOURCE RANGE STARTUP RATE SCALE: -2.00E02 > 7.00E00	CALC VALUE DPM	GPC 8284	-	-	--	-	CALC	1602 X
	UR5035	--	INTERMEDIATE RANGE STARTUP RATE SCALE: -2.00E02 > 7.00E00	CALC VALUE DPM	GPC 8285	-	-	--	-	CALC	1602 X
*	UR5112	--	VCT 2 HOUR VOLUME CHANGE (GROSS LEAKAGE) SCALE: -1920 > 1920 GALLONS	CALC VALUE	GPC	-	-	--	-	CALC	1201
*	UR5419	--	RCS 2 HOUR VOLUME CORRECTION FOR TEMPERATURE SCALE: -2.00E04 > 2.00E04	CALC VALUE GALLONS	GPC 0175	-	-	--	-	CALC	1201
	UR5467	--	COOLDOWN RATE (1 MINUTE AVERAGE) SCALE: -9998 > 9998 DEG F/HR	CALC VALUE	GPC	-	-	--	-	CALC	1201 X
	UR5468	--	COOLDOWN RATE (10 MIN AVERAGE) SCALE: -9998 > 9998 DEG F/HR	CALC VALUE	GPC	-	-	--	-	CALC	1201
*	UR5480	--	PRZR 2 HOUR VOLUME CHANGE (GROSS LEAKAGE) SCALE: -7560 > 7560 GALLONS	CALC VALUE	GPC	-	-	--	-	CALC	1201
*	UR5481	--	TOTAL LEAK RATE DUE TO VCT, PZR, RCS TEMP SCALE: -319 > 319 GPM	CALC VALUE	GPC	-	-	--	-	CALC	1201
*	UR5482	--	PRELIMINARY UNIDENTIFIED LEAK RATE SCALE: -410 > 410 GPM	CALC VALUE	GPC	-	-	--	-	CALC	1201

Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
*	UR5485	--	PRI 2 HOUR INLEAKAGE RATE SCALE: -189 > 189 GPM	CALC VALUE	GPC	-	-	--	-	CALC	1201
*	UH6248	--	AUCTIONEERED FUEL HAND BLDG EFFL RADIOGAS (TS) SCALE: 0 > 1.00E-01	CALC VALUE UCI/CC	GPC	-	-	--	-	CALC	1609 X
*	US6174	--	PRI MET TWR 10 METER WIND SPEED (15 MIN AVG) SCALE: 0 > 100 MPH	CALC VALUE	GPC	-	-	8.2.00	E3	CALC	2001
					#186						(UNIT 1 INPUT ONLY)
*	US6438	--	PRI MET TWR 60 METER WIND SPEED (15 MIN AVG) SCALE: 0 > 100 MPH	CALC VALUE	GPC	-	-	8.2.00	E3	CALC	2001
					#191						(UNIT 1 INPUT ONLY)
*	US6436	--	SEC MET TWR 10 METER WIND SPEED (15 MIN AVG) SCALE: 0 > 100 MPH	CALC VALUE	GPC	-	-	8.2.00	E3	CALC	2001
					#190						(UNIT 1 INPUT ONLY)
	UT5001	--	MAXIMUM IN CORE THERMOCOUPLE TEMPERATURE SCALE: 0 > 2300 DEG F	CALC VALUE	GPC	-	-	4.2.15	A1	CALC	1612 X
					#257						
	UT5002	--	AVERAGE OF HIGHEST 5 IN CORE T/C TEMPERATURES SCALE: 0 > 2300 DEG F	CALC VALUE	GPC	-	-	4.2.15	A1	CALC	1612 X
					#246						
	UT5003	--	MINIMUM IN CORE THERMOCOUPLE TEMPERATURE SCALE: 0 > 2300 DEG F	CALC VALUE	GPC	-	-	4.2.15	A1	CALC	1612
					#233						
	UT5004	--	CALC LO LIMIT (MODE 0-6) FOR IN CORE T/C TEMPS SCALE: 0 > 2300 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1612 X
					#227						
	UT5005	--	CALC HI LIMIT (MODE 0-6) FOR IN CORE T/C TEMPS SCALE: 0 > 2300 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1612 X
					#228						
	UT5110	--	MAXIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 1 SCALE: 0 > 2300 DEG F	CALC VALUE	GPC	-	-	4.2.15	A1	CALC	1612
					#234						
	UT5111	--	AVERAGE IN CORE THERMOCOUPLE TEMP-QUADRANT 1 SCALE: 0 > 2300 DEG F	CALC VALUE	GPC	-	-	4.2.15	A1	CALC	1612
					#236						

R	E	EXP	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B	Y	SIGNAL SOURCE	SIGNAL CLASS	WG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S	P	D	B
		UT5112	--	MINIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 1 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1612				
		UT5220	--	MAXIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 2 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1612				
		UT5221	--	AVERAGE IN CORE THERMOCOUPLE TEMP-QUADRANT 2 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1512				
		UT5222	--	MINIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 2 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1612				
		UT5330	--	MAXIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 3 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1612				
		UT5331	--	AVERAGE IN CORE THERMOCOUPLE TEMP-QUADRANT 3 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1612				
		UT5332	--	MINIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 3 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1612				
*		UT5406	--	ACTIONEERED (LOW) WIDE RANGE T-COLD SCALE1 0 > 700 DEG F	CALC VALUE	GPC		-	-	4.2.03	A1 CALC	1201	X			
		UT5419	--	ACTIONEERED (HIGH) WIDE RANGE T-HOT SCALE1 0 > 700 DEG F	CALC VALUE	GPC		-	-	4.2.02	A1 CALC	1201	X			
*		UT5426	--	AVERAGE WIDE RANGE T-COLD SCALE1 0 > 700 DEG F	CALC VALUE	GPC		-	-	4.2.03	A1 CALC	1201				
		UT5439	--	CALC LU LIMIT (MODE 1-2) FOR HOT LEG TEMPS SCALE1 551 > 626 DEG F	CALC VALUE	GPC		-	-	--	- CALC	1201	X			
		UT5440	--	MAXIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 4 SCALE1 0 > 2300 DEG F	CALC VALUE	GPC		-	-	4.2.15	A1 CALC	1612				

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT V/A	SYSTEM	S P D B
UT5441	--	AVERAGE IN CORE THERMOCOUPLE TEMP-QUADRANT 4 SCALE: 0 > 2300 DEG F	CALC VALUE	GPC #241	-	-	4.2.15	21 CALC	1012	
UT5442	--	MINIMUM IN CORE THERMOCOUPLE TEMP-QUADRANT 4 SCALE: 0 > 2300 DEG F	CALC VALUE	GPC #245	-	-	4.2.15	A1 CALC	1012	
UT5459	--	CALC HI LIMIT (MODE 1-2) FOR MUT LEG TEMPS SCALE: 502 > 637 DEG F	CALC VALUE	GPC #226	-	-	--	- CALC	1201	X
UT5467	--	AUCTIONEERED HIGH WIDE RANGE DELTA T SCALE: -700 > 700 DEG F	CALC VALUE	GPC #185	-	-	--	- CALC	1201	
UT5468	--	AUCTIONEERED HIGH WIDE RANGE T-AVG SCALE: 0 > 700 DEG F	CALC VALUE	GPC #265	-	-	--	- CALC	1201	X
UT5511	--	LOOP 1 WIDE RANGE T-AVG SCALE: 0 > 700 DEG F	CALC VALUE	GPC #200	-	-	--	- CALC	1201	X
UT5512	--	LOOP 1 WIDE RANGE DELTA T SCALE: -700 > 700 DEG F	CALC VALUE	GPC #252	-	-	--	- CALC	1201	
UT5531	--	LOOP 2 WIDE RANGE T-AVG SCALE: 0 > 700 DEG F	CALC VALUE	GPC #261	-	-	--	- CALC	1201	X
UT5532	--	LOOP 2 WIDE RANGE DELTA T SCALE: -700 > 700 DEG F	CALC VALUE	GPC #251	-	-	--	- CALC	1201	
UT5551	--	LOOP 3 WIDE RANGE T-AVG SCALE: 0 > 700 DEG F	CALC VALUE	GPC #262	-	-	--	- CALC	1201	X
UT5552	--	LOOP 3 WIDE RANGE DELTA T SCALE: -700 > 700 DEG F	CALC VALUE	GPC #250	-	-	--	- CALC	1201	
UT5571	--	LOOP 4 WIDE RANGE T-AVG SCALE: 0 > 700 DEG F	CALC VALUE	GPC #263	-	-	--	- CALC	1201	X

Y	SYMBOU	SYMBUL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	B P D S
	UT5572	--	LOOP 4 WIDE RANGE DELTA T SCALE: -700 > 700 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1201
	UT5627	--	RHR HEAT EXCH THAIN A INL/OUT DIFF TEMP SCALE: 0 > 400 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1205
	UT5628	--	RHR HEAT EXCH THAIN B INL/OUT DIFF TEMP SCALE: 0 > 400 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1205
*	UT6172	--	PR1 MET TWR 10 METER AMBIENT TEMP (15 MIN AVG) SCALE: -10 > 120 DEG F	CALC VALUE	GPC	-	-	0.2.00	E3	CALC	2001 (UNIT 1 INPUT ONLY)
*	UT6173	--	PR1 MET TWR 10 METER DEN PHT TEMP (15 MIN AVG) SCALE: -10 > 120 DEG F	CALC VALUE	GPC	-	-	0.2.00	E3	CALC	2001 (UNIT 1 INPUT ONLY)
*	UT6174	--	PR1 MET TWR 60-10 METER DELTA TEMP (15 MIN AVG) SCALE: -5 > 10 DEG F	CALC VALUE	GPC	-	-	0.2.00	E3	CALC	2001 (UNIT 1 INPUT ONLY)
*	UT6438	--	SEC MET TWR 10 METER AMBIENT TEMP (15 MIN AVG) SCALE: -10 > 120 DEG F	CALC VALUE	GPC	-	-	0.2.00	E3	CALC	2001 (UNIT 1 INPUT ONLY)
	UT7317	--	FEEDWATER AVG TEMPERATURE SCALE: 0 > 600 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1305
	UT7501	--	AVERAGE CONTAINMENT TEMPERATURE SCALE: 0 > 600 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1501 X
	UT7601	--	NSCW THAIN A SUPPLY/RETURN DIFFERENTIAL TEMP SCALE: 0 > 300 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1202
	UT7602	--	NSCW THAIN B SUPPLY/RETURN DIFFERENTIAL TEMP SCALE: 0 > 300 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1202
*	UT9644	--	CALC HI LIMIT FOR RCS SUBCOOLING (MODES 3-6) SCALE: 320 > 400 DEG F	CALC VALUE	GPC	-	-	--	-	CALC	1201 X

R	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	B
*	UV5031	--	VALIDATED NEUTRON FLUX SOURCE RANGE SCALE: 1.00E+00 > 1.00E+00	CALC VALUE CP3	GPC 0309	-	-	--	-	CALC	1002 X
*	UV5035	--	VALIDATED NEUTRON FLUX INTERMEDIATE RANGE SCALE: 1.00E-11 > 1.00E-03	CALC VALUE AMPS	GPC 0283	-	-	--	-	CALC	1002 X
*	UV5049	--	VALIDATED NEUTRON FLUX POWER RANGE SCALE: 0 > 120 PERCENT	CALC VALUE	GPC 0307	-	-	--	-	CALC	1002 X
*	UV5112	--	VALIDATED VCT LEVEL SCALE: 0 > 100 PERCENT	CALC VALUE	GPC 0309	-	-	--	-	CALC	1200
*	UV5398	--	VALIDATED MAIN TURBINE FIRST STAGE PRESSURE SCALE: 0 > 120 PCT POWER	CALC VALUE	GPC 0271	-	-	7.2.14	D2	CALC	1301
*	UV5400	--	VALIDATED 061 PRESSURE OUT SCALE: 0 > 1300 PSIG	CALC VALUE	GPC 0301	-	-	4.2.08	A1	CALC	1301 X
*	UV5401	--	VALIDATED 061 NARROW RANGE LEVEL SCALE: 0 > 100 PERCENT	CALC VALUE	GPC 0297	-	-	4.2.05	A1	CALC	1301 X
*	UV5403	--	VALIDATED 003 FW FLOW SCALE: 0 > 4000 KBH	CALC VALUE	GPC 0293	-	-	7.2.04-G	D2	CALC	1305 X
*	UV5405	--	VALIDATED 061 STEAM LINE FLOW SCALE: 0 > 4000 KBH	CALC VALUE	GPC 0272	-	-	7.2.04-C	D2	CALC	1301 X
*	UV5408	--	VALIDATED R03 WIDE RANGE PRESSURE SCALE: 0 > 3000 PSIG	CALC VALUE	GPC 0306	-	-	4.2.01	A1	CALC	1201 X
*	UV5420	--	VALIDATED 062 PRESSURE OUT SCALE: 0 > 1300 PSIG	CALC VALUE	GPC 0300	-	-	4.2.00	A1	CALC	1301 X
*	UV5421	--	VALIDATED 062 NARROW RANGE LEVEL SCALE: 0 > 100 PERCENT	CALC VALUE	GPC 0296	-	-	4.2.05	A1	CALC	1301 X

Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	WG 1.97 VAR CLASS	INPUT VIA	SYSTEM	B P D S
*	UV5423	--	VALIDATED 362 F# FLOW SCALE1 0 > 4800 KBH	CALC VALUE	GPC 8292	-	-	7.2.04-C D2	CALC	1305	X
*	UV5425	--	VALIDATED 362 STEAM LINE FLOW SCALE1 0 > 4800 KBH	CALC VALUE	GPC 8273	-	-	7.2.04-C D2	CALC	1301	X
*	UV5440	--	VALIDATED 363 PRESSURE OUT SCALE1 0 > 1300 PSIG	CALC VALUE	GPC 8299	-	-	4.2.08 A1	CALC	1301	X
*	UV5441	--	VALIDATED 363 NARROW RANGE LEVEL SCALE1 0 > 100 PERCENT	CALC VALUE	GPC 8295	-	-	4.2.05 A1	CALC	1301	X
*	UV5443	--	VALIDATED 363 F# FLOW SCALE1 0 > 4800 KBH	CALC VALUE	GPC 8291	-	-	7.2.04-C D2	CALC	1305	X
*	UV5445	--	VALIDATED 363 STEAM LINE FLOW SCALE1 0 > 4800 KBH	CALC VALUE	GPC 8274	-	-	7.2.04-C D2	CALC	1301	X
*	UV5460	--	VALIDATED 364 PRESSURE OUT SCALE1 0 > 1300 PSIG	CALC VALUE	GPC 8298	-	-	4.2.08 A1	CALC	1301	X
*	UV5461	--	VALIDATED 364 NARROW RANGE LEVEL SCALE1 0 > 100 PERCENT	CALC VALUE	GPC 8294	-	-	4.2.05 A1	CALC	1301	X
*	UV5463	--	VALIDATED 364 F# FLOW SCALE1 0 > 4800 KBH	CALC VALUE	GPC 8290	-	-	7.2.04-C D2	CALC	1305	X
*	UV5465	--	VALIDATED 364 STEAM LINE FLOW SCALE1 0 > 4800 KBH	CALC VALUE	GPC 8275	-	-	7.2.04-C D2	CALC	1301	X
*	UV5480	--	VALIDATED PRESSURIZER LEVEL SCALE1 0 > 100 PERCENT	CALC VALUE	GPC 8305	-	-	4.2.06 A1	CALC	1201	X
*	UV5481	--	VALIDATED PRESSURIZER PRESSURE SCALE1 1700 > 2500 PSIG	CALC VALUE	GPC 8277	-	-	7.2.02-F D2	CALC	1291	X

R E V	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
*	UV6881	--	VALIDATED CONTAINMENT PRESSURE SCALE1 -5 > 160 PSIG	CALC VALUE	GPC #282	-	-	--	-	CALC 1286	X
*	UV6883	--	VALIDATED CONT PRESS (RG 1.97 A INPUTS ONLY) SCALE1 0 > 75 PSIG	CALC VALUE	GPC #384	-	-	4.2.07	A1	CALC 1286	X
*	UV6138	--	VALIDATED RWST LEVEL SCALE1 0 > 100 PERCENT	CALC VALUE	GPC #382	-	-	4.2.09	A1	CALC 1284	X
*	UV6328	--	VALIDATED BORIC ACID STORAGE TANK LEVEL SCALE1 0 > 100 PERCENT	CALC VALUE	GPC #287	-	-	--	-	CALC 1280	
*	UV7326	--	VALIDATED 8G1 AUX FW FLOW SCALE1 0 > 600 GPM	CALC VALUE	GPC #278	-	-	4.2.12	A1	CALC 1382	X
*	UV7327	--	VALIDATED 8G2 AUX FW FLOW SCALE1 0 > 600 GPM	CALC VALUE	GPC #279	-	-	4.2.12	A1	CALC 1382	X
*	UV7328	--	VALIDATED 8G3 AUX FW FLOW SCALE1 0 > 600 GPM	CALC VALUE	GPC #280	-	-	4.2.12	A1	CALC 1382	X
*	UV7329	--	VALIDATED 8G4 AUX FW FLOW SCALE1 0 > 600 GPM	CALC VALUE	GPC #281	-	-	4.2.12	A1	CALC 1382	X
*	UV7489	--	VALIDATED CONDENSATE STORAGE TANK 1 LEVEL SCALE1 0 > 100 PERCENT	CALC VALUE	GPC #276	-	-	4.2.11	A1	CALC 1382	X
*	UV7498	--	VALIDATED CONDENSATE STORAGE TANK 2 LEVEL SCALE1 0 > 100 PERCENT	CALC VALUE	GPC #269	-	-	4.2.11	A1	CALC 1382	X
*	UV7581	--	VALIDATED CONTAINMENT HYDROGEN CONCENTRATION SCALE1 0 > 1% PERCENT	CALC VALUE	GPC #383	-	-	5.2.06-D	B1	CALC 1513	X
*	UV9883	--	VALIDATED CONTAINMENT WATER LEVEL SCALE1 0 > 120 INCHES	CALC VALUE	GPC #259	-	-	4.2.10	A1	CALC 1285	X

GEORGIA POWER COMPANY-ENGINEERING & CONSTRUCTION SERVICES
 VOLUME 1 REG GUIDE 7/ERF INPUT LIST

REVISION 07.05 12/11/88 PAGE 11 MAX 1

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	UNIT	CLASS	SCALE	INPUT VIA	SYSTEM	STATUS
* UV9253	--	VALIDATED CONTAINMENT PRESS EXTENDED RANGE SCALE: -5 > 100 PSIG	CALC VALUE	GPC		83-A C1	CALC	1206	X
* UV9260	--	VALIDATED REACTOR HEAD VENT LETDOWN LINE FLOW SCALE: 0 > 80 GPM	CALC VALUE	GPC		2.03-B D2	CALC	1208	
* UV9644	--	VALIDATED RCS SUBCOOLING SCALE: -600 > 350 DEG F	CALC VALUE	GPC		4.2.10 B1	CALC	1201	X
* UV9659	--	VALIDATED RVLIS UPPER RANGE DP SCALE: -7 > -1 IN WATER	CALC VALUE	GPC		5.2.03-B B1	CALC	1201	
									(RANGE=-7.986>-1.361)
* UV9660	--	VALIDATED RVLIS FULL RANGE DP SCALE: -19 > -1 IN WATER	CALC VALUE	GPC		5.2.03-B B1	CALC	1201	
									(RANGE=-19.224>-1.361)
* UV9661	--	VALIDATED RVLIS DYNAMIC HEAD DP SCALE: -19 > 39 IN WATER	CALC VALUE	GPC		5.2.03-B B1	CALC	1201	
									(RANGE=-19.224>39.773)
* UV9861	--	VALIDATED RVLIS STATIC HEAD UPPER RANGE SCALE: 0 > 120 % LEVEL	CALC VALUE	GPC		6.2.01-B C2	CALC	1201	X
* UV9862	--	VALIDATED RVLIS STATIC HEAD FULL RANGE SCALE: 0 > 120 % LEVEL	CALC VALUE	GPC		6.2.01-B C2	CALC	1201	X
* UV9863	--	VALIDATED RVLIS DYNAMIC HEAD SCALE: 0 > 120 % LIQUID	CALC VALUE	GPC		6.2.01-B C2	CALC	1201	X
* UV6171	--	PRI MET TWR 10 METER WIND DIRECT (15 MIN AVG) SCALE: 0 > 340 DEGREES	CALC VALUE	GPC		8.2.00 E3	CALC	2001	
									(UNIT 1 INPUT ONLY)
* UV6431	--	PRI MET TWR 6M METER WIND DIRECT (15 MIN AVG) SCALE: 0 > 340 DEGREES	CALC VALUE	GPC		8.2.00 E3	CALC	2001	
									(UNIT 1 INPUT ONLY)
* UV6432	--	PRI MET TWR 10 METER SIGMA THETA (15 MIN AVG) SCALE: 0 > 100 DEGREES	CALC VALUE	GPC		8.2.00 E3	CALC	2001	
									(UNIT 1 INPUT ONLY)

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
* UY6433	--	SEC MET TWR 10 METER SIGMA THETA (15 MIN AVG) SCALE: 0 > 100 DEGREES	CALC VALUE	GPC	-	-	8.2.08 E3 CALC	2001	(UNIT 1 INPUT ONLY)	
* UY6435	--	SEC MET TWR 10 METER WIND DIRECT (15 MIN AVG) SCALE: 0 > 540 DEGREES	CALC VALUE	GPC	-	-	8.2.08 E3 CALC	2001	(UNIT 1 INPUT ONLY)	
UY9261	--	LATEST PASS PH SAMPLE SCALE: 0 > 14 PH	CALC VALUE	GPC	-	-	8.2.01-C C3 CALC	2702		
V9615	--	4.16KV 1E BUS 1A002 VOLTAGE XDUCE: 0-1MA SCALE: 0 > 5250 VOLTS	XCDR-V	B	SWGR	I	7.2.12 D2 RPU A2 1004		X	
V9618	--	4.16KV 1E BUS 1B003 VOLTAGE XDUCE: 0-1MA SCALE: 0 > 5250 VOLTS	XCDR-V	B	SWGR	II	7.2.12 D2 RPU B2 1004		X	
V9623	--	CLASS 1E 125VDC LOADCENTER 1AD1 BUS VOLTAGE XDUCE: 4-20MA SCALE: 0 > 150 VOLTS	XCDR-V	B	SWGR	I	7.2.12 D2 RPU A2 1005			
V9624	--	CLASS 1E 125VDC LOADCENTER 1BD1 BUS VOLTAGE XDUCE: 4-20MA SCALE: 0 > 150 VOLTS	XCDR-V	B	SWGR	II	7.2.12 D2 RPU B2 1006			
V9625	--	CLASS 1E 125VDC LOADCENTER 1CD1 BUS VOLTAGE XDUCE: 4-20MA SCALE: 0 > 150 VOLTS	XCDR-V	B	SWGR	III	7.2.12 D2 RPU A3 1006			
V9626	--	CLASS 1E 125VDC LOADCENTER 1DD1 BUS VOLTAGE XDUCE: 4-20MA SCALE: 0 > 150 VOLTS	XCDR-V	B	SWGR	IV	7.2.12 D2 RPU B3 1006			
V99604	--	DIESEL GENERATOR A VOLTAGE ALM ON CONTACT: CLSD ALM/NML: LOW / NOT LOW	127X	B	PAR68	I	7.2.12 D2 RPU A1 1004			
V99610	--	DIESEL GENERATOR B VOLTAGE ALM ON CONTACT: CLSD ALM/NML: LOW / NOT LOW	127X	B	PAR7C	II	7.2.12 D2 RPU B1 1004			
V6171	--	PRIMARY MET TOWER 10 METER WIND DIRECTION XDUCE: 0-5V SCALE: 0 > 540 DEGREES	HW TWR	B	MET TOWER NNS		8.2.08 E3 MUX	2001	(UNIT 1 INPUT ONLY)	

Y	ERF SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S
	Y6431	--	PRIMARY MET TOWER 60 METER WIND DIRECTION XDUCE1: 0-5V SCALE: 0 > 540 DEGREES	MM TWR	B	MET TOWER NNS		8.2.08 E3 MUX	2001		
					1317			(UNIT 1 INPUT ONLY)			
	* Y6432	--	PRIMARY MET TOWER 10 METER SIGMA THETA XDUCE1: 0-5V SCALE: 0 > 180 DEGREES	MM TWR	B	MET TOWER NNS		8.2.08 E3 MUX	2001		
					1412			(UNIT 1 INPUT ONLY)			
	* Y6433	--	SECONDARY MET TOWER 10 METER SIGMA THETA XDUCE1: 0-5V SCALE: 0 > 180 DEGREES	MM TWR	B	MET TOWER NNS		8.2.08 E3 MUX	2001		
					1413			(UNIT 1 INPUT ONLY)			
	Y6435	--	SECONDARY MET TOWER 10 METER WIND DIRECTION XDUCE1: 0-5V SCALE: 0 > 540 DEGREES	MM TWR	B	MET TOWER NNS		8.2.08 E3 MUX	2001		
					1414			(UNIT 1 INPUT ONLY)			
	Y9261	--	RCS SAMPLING PH XDUCE1: 4-20MA SCALE: 0 > 14 PH	LATER	B	PASS NNS		6.2.01-C C3 MUX	2782		
					1152						
	Y9882	--	MET TWR ASPIRATOR (0V=NOT FAILED, 5V=FAILED) XDUCE1: 0-5V SCALE: 0 > 5 VOLTS	MM TWR	B	MET TOWER NNS		-- - MUX	2001		
					1433			(UNIT 1 INPUT ONLY)			
	Y05006	Y00006	REACTION TRIP BRKR TRAIN A ALM ON CONTACT: OPEN ALM/NML: TRIP / NOT TRIPPED	X5A	N	RTSG NNS		7.2.14 D2 MULT	1000	X	
					2498	E/D1-CD-M01A					
	Y05007	Y00007	REACTION TRIP BRKR TRAIN B ALM ON CONTACT: OPEN ALM/NML: TRIP / NOT TRIPPED	X5B	N	RTSG NNS		7.2.14 D2 MULT	1000	X	
					2502	E/D1-CD-M01A					
	Y05026	Y00026	REACTION TRIP BY-PASS BRKR TRAIN A ALM ON CONTACT: CLSD ALM/NML: NOT TRIPPED / TRIPPED	X2A	N	RTSG NNS		7.2.14 D2 80E	1000	X	
					2499						
	Y05027	Y00027	REACTION TRIP BY-PASS BRKR TRAIN B ALM ON CONTACT: CLSD ALM/NML: NOT TRIPPED / TRIPPED	X2B	N	RTSG NNS		7.2.14 D2 80E	1000	X	
					2503						
	Y05100	Y00100	POSITIVE DISPLACMENT CHARGING PUMP 1 BRKR ALM ON CONTACT: CLSD ALM/NML: UPEN / CLOSED	528-N02100	B	80GR NNS		-- - MULT	1200		
					2542	E/D1-8U-C01C					
	Y05101	Y00101	CENTRIFIGAL CHARGING PUMP TRAIN A BRKR ALM ON CONTACT: CLSD ALM/NML: UPEN / CLOSED	528-A08213	B	100 PNL NNS		7.2.03 D2 MULT	1200		
					2262	E/D1-8U-C01A					

R	ENF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RW 1.97	INPUT		S
E	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	P
≡											D
	YD5102	YD0102	CENTRIFIGAL CHARGING PUMP TRAIN B BRKR ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	52B-BA0313	B	180 PNL	NMS	7.2.03	D2 MULT	1200	
					2263	E/D1-6D-C01B					
	YD5600	YD0600	NHR PUMP A BRKR ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	52B-AA0209	B	180 PNL	NMS	7.2.10	D2 MULT	1205	
					2021	E/D1-8D-E01A					
	YD5601	YD0601	NHR PUMP B BRKR ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	52B-BA0310	B	180 PNL	NMS	7.2.10	D2 MULT	1206	
					2018	E/D1-8D-E01B					
	YD9606	--	DIESEL GENERATOR A FREQUENCY ALM ON CONTACTS: OPEN ALM/NML: LOW / NOT LOW	334B	B	PDG2	I	7.2.12	D2 RPU A2	1004	
					2181	E/D1-BA-D02D					
	YD9612	--	DIESEL GENERATOR B FREQUENCY ALM ON CONTACTS: OPEN ALM/NML: LOW / NOT LOW	334B	B	PDG4	II	7.2.12	D2 RPU B2	1004	
					2183	E/D1-BA-D03D					
	YD9643	--	NFMS NEUT DET POWER TRAIN A ALM ON CONTACTS: CLSD ALM/NML: OFF NORMAL / NORMAL	NEUTRA	n	NFMS	I	--	- RPU A2	1002	
					2023						
	YD9650	--	NFMS NEUT DET POWER TRAIN B ALM ON CONTACTS: CLSD ALM/NML: OFF NORMAL / NORMAL	NEUTRB	n	NFMS	II	--	- RPU B2	1002	
					2025						
	ZD6150	--	SI ACTUATION TRAIN A ALM ON CONTACTS: CLSD ALM/NML: ACTUATED / NORMAL	K001A	n	33P3	I	7.2.14	D2 RPU A2	1204	X
					2053	E/D1-8D-K04L					
	ZD6151	--	SI ACTUATION TRAIN B ALM ON CONTACTS: CLSD ALM/NML: ACTUATED / NORMAL	K001B	n	33P3	II	7.2.14	D2 RPU B2	1204	X
					2051	E/D1-8D-K04Q					
	ZD6160	--	CONTAINMENT ISOL SIGNAL PHASE A TRAIN A ALM ON CONTACTS: CLSD ALM/NML: ISOLATED / NORMAL	K631A	n	33P3	I	7.2.14	D2 RPU A2	2415	X
					2091	E/D1-8D-C03L					
	ZD6161	--	CONTAINMENT ISOL SIGNAL PHASE A TRAIN B ALM ON CONTACTS: CLSD ALM/NML: ISOLATED / NORMAL	K631B	n	33P3	II	7.2.14	D2 RPU B2	2415	X
					2340	E/D1-8D-C03D					
*	ZD7002	ZD2002	MAIN TURB STOP VALVE SV1 ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	XV-6001	B	VALVE	NMS	7.2.14	D2 MULT	1301	X
					2016						

R	E	ERF	PHUTEUS	SIGNAL DESCRIPTION	ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S	
V	SYMBOL	SYMBOL			DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	B
	Z07003	Z02003	MAIN TURB STOP VALVE SV1	ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	XV-6001	B	VALVE	NNS	7.2.14	02 MULT	1301	X
						2842						
	Z07004	Z02004	MAIN TURB STOP VALVE SV2	ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	XV-6002	B	VALVE	NNS	7.2.14	02 MULT	1301	X
						2820						
	Z07005	Z02005	MAIN TURB STOP VALVE SV2	ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	XV-6002	B	VALVE	NNS	7.2.14	02 MULT	1301	X
						2844						
	Z07006	Z02006	MAIN TURB STOP VALVE SV3	ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	XV-6003	B	VALVE	NNS	7.2.14	02 MULT	1301	X
						2822						
	Z07007	Z02007	MAIN TURB STOP VALVE SV3	ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	XV-6003	B	VALVE	NNS	7.2.14	02 MULT	1301	X
						2846						
	Z07008	Z02008	MAIN TURB STOP VALVE SV4	ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	XV-6004	B	VALVE	NNS	7.2.14	02 MULT	1301	X
						2824						
	Z07009	Z02009	MAIN TURB STOP VALVE SV4	ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	XV-6004	B	VALVE	NNS	7.2.14	02 MULT	1301	X
						2840						
	Z07010	Z02010	MAIN TURB CONTROL VALVE CV1	ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	XV-6005	B	VALVE	NNS	--	- MULT	1301	
						2883						
	Z07011	Z02011	MAIN TURB CONTROL VALVE CV1	ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	XV-6005	B	VALVE	NNS	--	- MULT	1301	
						2907						
	Z07012	Z02012	MAIN TURB CONTROL VALVE CV2	ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	XV-6006	B	VALVE	NNS	--	- MULT	1301	
						2885						
	Z07013	Z02013	MAIN TURB CONTROL VALVE CV2	ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	XV-6006	B	VALVE	NNS	--	- MULT	1301	
						2909						
	Z07014	Z02014	MAIN TURB CONTROL VALVE CV3	ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	XV-6007	B	VALVE	NNS	--	- MULT	1301	
						2887						

R	ERF SYMBOL	PROIEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE	SIGNAL CLASS	H6 1.97 VAR CLASS	INPUT VIA SYSTEM	S P D
	Z07015	Z02015	MAIN TURB CONTROL VALVE CV3 ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	XV-6887	VALVE	NNS	--	MULT	1301
	Z07016	Z02016	MAIN TURB CONTROL VALVE CV4 ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	XV-6888	VALVE	NNS	--	MULT	1301
	Z07017	Z02017	MAIN TURB CONTROL VALVE CV4 ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	XV-6889	VALVE	NNS	--	MULT	1301
	Z07042	Z02042	MAIN TURB INTERMEDIATE STOP VLV ISV1 ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	XV-6889	VALVE	NNS	--	MULT	1301
	Z07043	Z02043	MAIN TURB INTERMEDIATE STOP VLV ISV1 ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	XV-6889	VALVE	NNS	--	MULT	1301
	Z07044	Z02044	MAIN TURB INTERMEDIATE STOP VLV ISV2 ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	XV-6810	VALVE	NNS	--	MULT	1301
	Z07045	Z02045	MAIN TURB INTERMEDIATE STOP VLV ISV2 ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	XV-6810	VALVE	NNS	--	MULT	1301
	Z07046	Z02046	MAIN TURB INTERMEDIATE STOP VLV ISV3 ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	XV-6811	VALVE	NNS	--	MULT	1301
	Z07047	Z02047	MAIN TURB INTERMEDIATE STOP VLV ISV3 ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	XV-6811	VALVE	NNS	--	MULT	1301
	Z07048	Z02048	MAIN TURB INTERMEDIATE STOP VLV ISV4 ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	XV-6812	VALVE	NNS	--	MULT	1301
	Z07049	Z02049	MAIN TURB INTERMEDIATE STOP VLV ISV4 ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	XV-6812	VALVE	NNS	--	MULT	1301
	Z07050	Z02050	MAIN TURB INTERMEDIATE STOP VLV ISV5 ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	XV-6813	VALVE	NNS	--	MULT	1301

R ERF PROIEUS
 Y SYMBOL SYMBOL SIGNAL DESCRIPTION
 S
 P
 D
 O
 B

REF SYMBOL	PROIEUS SYMBOL	SIGNAL DESCRIPTION	VALVE	ORIGINATING DEVICE	SIGNAL SOURCE	SIGNAL CLASS	RG	VAR	CLASS	INPUT	SYSTEM
Z07051	Z02051	MAIN TURB INTERMEDIATE STOP VALV ISV5 ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	VALVE	XV-0813	VALVE	NNS	--	--	MULT	1301	
Z07052	Z02052	MAIN TURB INTERMEDIATE STOP VALV ISV6 ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	VALVE	XV-0814	VALVE	NNS	--	--	MULT	1301	
Z07053	Z02053	MAIN TURB INTERMEDIATE STOP VALV ISV6 ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	VALVE	XV-0814	VALVE	NNS	--	--	MULT	1301	
Z07054	Z02054	MAIN TURBINE INTERCEPT VALVE IV1 ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	VALVE	XV-0809	VALVE	NNS	--	--	MULT	1301	
Z07050	Z02050	MAIN TURBINE INTERCEPT VALVE IV1 ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	VALVE	XV-0809	VALVE	NNS	--	--	MULT	1301	
Z07056	Z02056	MAIN TURBINE INTERCEPT VALVE IV2 ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	VALVE	XV-0810	VALVE	NNS	--	--	MULT	1301	
Z07057	Z02057	MAIN TURBINE INTERCEPT VALVE IV2 ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	VALVE	XV-0810	VALVE	NNS	--	--	MULT	1301	
Z07058	Z02058	MAIN TURBINE INTERCEPT VALVE IV3 ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	VALVE	XV-0811	VALVE	NNS	--	--	MULT	1301	
Z07059	Z02059	MAIN TURBINE INTERCEPT VALVE IV3 ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	VALVE	XV-0811	VALVE	NNS	--	--	MULT	1301	
Z07060	Z02060	MAIN TURBINE INTERCEPT VALVE IV4 ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	VALVE	XV-0812	VALVE	NNS	--	--	MULT	1301	
Z07061	Z02061	MAIN TURBINE INTERCEPT VALVE IV4 ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	VALVE	XV-0812	VALVE	NNS	--	--	MULT	1301	
Z07062	Z02062	MAIN TURBINE INTERCEPT VALVE IV5 ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	VALVE	XV-0813	VALVE	NNS	--	--	MULT	1301	

R ERF PROTEUS
 V SYMBOL SYMBOL SIGNAL DESCRIPTION

ORIGINATING DEVICE	SIGNAL SOURCE CLASS	SIGNAL CLASS	MG 1.97 INPUT	VAR CLASS	VIA SYSTEM
XV-0813	B	VALVE	NNS	--	MULT 1301
XV-0814	B	VALVE	NNS	--	MULT 1301
XV-0814	B	VALVE	NNS	--	MULT 1301
HV-3080A	B	VALVE	I	3.2.05-F	B2 RPU A1 1301
HV-3080A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3016A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3016A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3016A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3026A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3026A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3036A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3036A	B	VALVE	I	5.2.05-F	B2 RPU A1 1301
HV-3086B	B	VALVE	II	5.2.05-F	B2 RPU B1 1301

Z07063 Z02863 MAIN TURBINE INTERCEPT VALVE IV5
 ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED

Z07064 Z02864 MAIN TURBINE INTERCEPT VALVE IV6
 ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN

Z07065 Z02865 MAIN TURBINE INTERCEPT VALVE IV5
 ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED

Z07101 -- 861 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN

Z07102 -- 861 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: CLSD ALM/NML: CLSD / NOT CLSD

Z07103 -- 862 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN

Z07104 -- 862 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: CLSD ALM/NML: CLSD / NOT CLSD

Z07105 -- 863 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN

Z07106 -- 863 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: CLSD ALM/NML: CLSD / NOT CLSD

Z07107 -- 864 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN

Z07108 -- 864 MAIN STM ISOL VLV UPSTREAM TRAIN A
 ALM ON CONTACT: CLSD ALM/NML: CLSD / NOT CLSD

Z07111 -- 861 MAIN STM ISOL VLV DOWNSTREAM TRAIN B
 ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN

S
 P
 D

R
 E
 Y

PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	SIGNAL CLASS	MG 1.97 INPUT VAR CLASS	SYSTEM
Z07112	-- 3G1 MAIN STM ISOL VLV DMS1HM TRAIN B ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	3034	VALVE II	5.2.05-F	02 RPU 01	1301
Z07113	-- 3G2 MAIN STM ISOL VLV DMS1HM TRAIN B ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	3079	VALVE II	5.2.05-F	02 RPU 01	1301
Z07114	-- 3G2 MAIN STM ISOL VLV DMS1HM TRAIN B ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	3103	VALVE II	5.2.05-F	02 RPU 01	1301
Z07115	-- 3G3 MAIN STM ISOL VLV DMS1HM TRAIN B ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	3076	VALVE II	5.2.05-F	02 RPU 01	1301
Z07116	-- 3G3 MAIN STM ISOL VLV DMS1HM TRAIN B ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	3100	VALVE II	5.2.05-F	02 RPU 01	1301
Z07117	-- 3G4 MAIN STM ISOL VLV DMS1HM TRAIN B ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	3074	VALVE II	5.2.05-F	02 RPU 01	1301
Z07118	-- 3G4 MAIN STM ISOL VLV DMS1HM TRAIN B ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	3098	VALVE II	5.2.05-F	02 RPU 01	1301
Z07131	-- 3G1 OUTLET VALVE TO TDAFM TRAIN B ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	3089	VALVE II	7.2.06-C	02 RPU 01	1301
Z07132	-- 3G1 OUTLET VALVE TO TDAFM TRAIN B ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	3033	VALVE II	7.2.06-C	02 RPU 01	1301
Z07133	-- 3G2 OUTLET VALVE TO TDAFM TRAIN C ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	3078	VALVE I	7.2.06-C	02 RPU A1	1301
Z07134	-- 3G2 OUTLET VALVE TO TDAFM TRAIN C ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	3102	VALVE I	7.2.06-C	02 RPU A1	1301
Z07146	Z02146 STM DUMP TV-500A TO CONDENSER A ALM ON CONTACTS CLSD ALM/NML1 OPEN / NOT OPEN	3030	VALVE NNS	--	--	RPU N1 1301

9
 P
 D
 B

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAN CLASS	INPUT VIA SYSTEM
Z07147	Z02147	STM DUMP TV-580A TO CONDENSER A ALM ON CONTACT: OPEN / CLOSED / NOT OPEN	TV-0580A	N VALVE	NNS E/D1-8C-083A	--	RPU NI 1381
Z07148	Z02148	STM DUMP TV-580B TO CONDENSER B ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	TV-0580B	N VALVE	NNS E/D1-8C-083B	--	RPU NI 1381
Z07149	Z02149	STM DUMP TV-580C TO CONDENSER C ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	TV-0580C	N VALVE	NNS E/D1-8C-083C	--	RPU NI 1381
Z07150	Z02150	STM DUMP TV-580D TO CONDENSER A ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	TV-0580D	N VALVE	NNS E/D1-8C-083D	--	RPU NI 1381
Z07151	Z02151	STM DUMP TV-580E TO CONDENSER B ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	TV-0580E	N VALVE	NNS E/D1-8C-083E	--	RPU NI 1381
Z07152	Z02152	STM DUMP TV-580F TO CONDENSER C ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	TV-0580F	N VALVE	NNS E/D1-8C-083F	--	RPU NI 1381
Z07153	Z02153	STM DUMP TV-580G TO CONDENSER A ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	TV-0580G	N VALVE	NNS E/D1-8C-083G	--	RPU NI 1381
Z07154	Z02154	STM DUMP TV-580H TO CONDENSER B ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	TV-0580H	N VALVE	NNS E/D1-8C-083H	--	RPU NI 1381
Z07155	Z02155	STM DUMP TV-580I TO CONDENSER C ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	TV-0580I	N VALVE	NNS E/D1-8C-083I	--	RPU NI 1381
Z07156	Z02156	STM DUMP TV-580J TO CONDENSER A ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	TV-0580J	N VALVE	NNS E/D1-8C-083J	--	RPU NI 1381
Z07157	Z02157	STM DUMP TV-580K TO CONDENSER B ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	TV-0580K	N VALVE	NNS E/D1-8C-083K	--	RPU NI 1381
Z07158	Z02158	STM DUMP TV-580L TO CONDENSER C ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	TV-0580L	N VALVE	NNS E/D1-8C-083L	--	RPU NI 1381

M
 E
 V
 S
 P
 D
 S

R ERF PROTEUS SIGNAL DESCRIPTION
 Y SYMBOL SYMBOL ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED / CLOSED / NOT OPEN

Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	UNIGINATING DEVICE	B	SIGNAL SOURCE	H	SIGNAL CLASS	RS	1.97	INPUT	S
					Y						VIA	
											SYSTEM	
Z07169	Z02159	STM DUMP	TV-500G TO CONDENSER A	TV-0500G	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	OPEN ALM/NML: NOT CLOSED / CLOSED			3040	E/D1-8C-0030		--			
Z07168	Z02160	STM DUMP	TV-500H TO CONDENSER B	TV-0500H	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	CLSD ALM/NML: OPEN / NOT OPEN			3023	E/D1-8C-003H		--			
Z07161	Z02161	STM DUMP	TV-500H TO CONDENSER B	TV-0500H	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	OPEN ALM/NML: NOT CLOSED / CLOSED			3047	E/D1-8C-003H		--			
Z07162	Z02162	STM DUMP	TV-500J TO CONDENSER C	TV-0500J	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	CLSD ALM/NML: OPEN / NOT OPEN			3022	E/D1-8C-003J		--			
Z07163	Z02163	STM DUMP	TV-500J TO CONDENSER C	TV-0500J	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	OPEN ALM/NML: NOT CLOSED / CLOSED			3040	E/D1-8C-003J		--			
Z07164	Z02164	STM DUMP	PV-507A TO CONDENSER A	PV-0507A	N	VALVE	NNS				RPU NI	1301
		ALM UN CONTACT:	CLSD ALM/NML: OPEN / NOT OPEN			2967	E/D1-8C-003K		--			
Z07165	Z02165	STM DUMP	PV-507A TO CONDENSER A	PV-0507A	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	OPEN ALM/NML: NOT CLOSED / CLOSED			2991	E/D1-8C-003K		--			
Z07166	Z02166	STM DUMP	PV-507B TO CONDENSER B	PV-0507B	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	CLSD ALM/NML: OPEN / NOT OPEN			2966	E/D1-8C-003L		--			
Z07167	Z02167	STM DUMP	PV-507B TO CONDENSER B	PV-0507B	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	OPEN ALM/NML: NOT CLOSED / CLOSED			2990	E/D1-8C-003L		--			
Z07168	Z02168	STM DUMP	PV-507C TO CONDENSER C	PV-0507C	N	VALVE	NNS				RPU NI	1301
		ALM ON CONTACT:	CLSD ALM/NML: OPEN / NOT OPEN			2965	E/D1-8C-003M		--			
Z07169	Z02169	STM DUMP	PV-507C TO CONDENSER C	PV-0507C	N	VALVE	NNS				RPU NI	1301
		ALM UN CONTACT:	OPEN ALM/NML: NOT CLOSED / CLOSED			2989	E/D1-8C-003M		--			
Z07331	Z02331	TDAF# DISCH	VLV TU 9G4	HV-5120	B	180 PNL	NNS	7.2.86-C	D2	MULT		1302
		ALM ON CONTACT:	OPEN ALM/NML: NOT OPEN / OPEN			3073	E/D1-8C-F89A					

R	ERF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RL	1.97	INPUT	B
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR	CLASS	VIA	SYSTEM
	Z07332	Z02332	TOAFW DISCH VLV TO 9G4 ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5128	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3097	E/D1-BC-F09A				
	Z07333	Z02333	TOAFW DISCH VLV TO 9G1 ALM ON CONTACTS OPEN ALM/NML: NOT OPEN / OPEN	HV-5122	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3072	E/D1-BC-F09B				
	Z07334	Z02334	TOAFW DISCH VLV TO 9G1 ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5122	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3095	E/D1-BC-F09B				
	Z07335	Z02335	TOAFW DISCH VLV TO 9G2 ALM ON CONTACTS OPEN ALM/NML: NOT OPEN / OPEN	HV-5125	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3071	E/D1-BC-F09C				
	Z07336	Z02336	TOAFW DISCH VLV TO 9G2 ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5125	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3095	E/D1-BC-F09C				
	Z07337	Z02337	TOAFW DISCH VLV TO 9G3 ALM ON CONTACTS OPEN ALM/NML: NOT OPEN / OPEN	HV-5127	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3070	E/D1-BC-F09D				
	Z07338	Z02338	TOAFW DISCH VLV TO 9G3 ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5127	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3094	E/D1-BC-F09D				
	Z07339	Z02339	MD AFW-B DISCH VLV TO 9G2 ALM ON CONTACTS OPEN ALM/NML: NOT OPEN / OPEN	HV-5132	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3069	E/D1-BC-F09A				
	Z07340	Z02340	MD AFW-B DISCH VLV TO 9G2 ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5132	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3093	E/D1-BC-F09A				
	Z07341	Z02341	MD AFW-B DISCH VLV TO 9G3 ALM ON CONTACTS OPEN ALM/NML: NOT OPEN / OPEN	HV-5134	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3068	E/D1-BC-F09B				
	Z07342	Z02342	MD AFW-B DISCH VLV TO 9G3 ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5134	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3092	E/D1-BC-F09B				
	Z07343	Z02343	MD AFW-A DISCH VLV TO 9G4 ALM ON CONTACTS OPEN ALM/NML: NOT OPEN / OPEN	HV-5137	B	180 PNL	NNS	7.2.06-C	D2	MULT	1302
						3067	E/D1-BC-F09C				

REVISED PROJECT SIGNAL DESCRIPTION ORIGINATING DEVICE Y SIGNAL SIGNAL CLASS RC 1.97 INPUT VAR CLASS VIA SYSTEM S

REVISED	PROJECT	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL CLASS	RC 1.97	INPUT VAR CLASS	VIA SYSTEM	S
Z07344	Z02344 MD AFM-A DISCH VLV TO SG4 ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED		HV-5137	B	180 PNL NNS E/D1-BC-F88C	7.2.06-C	D2 MULT	1382	
Z07345	Z02345 MU AFM-A DISCH VLV TO SG1 ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN		HV-5139	B	180 PNL NNS E/D1-BC-F88D	7.2.06-C	D2 MULT	1382	
Z07346	Z02346 MD AFM-A DISCH VLV TO SG1 ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED		HV-5139	B	180 PNL NNS E/D1-BC-F88D	7.2.06-C	D2 MULT	1382	
Z07351	-- MD AFM-A INLET VALVE ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN		HV-5119	B	VALVE I E/D1-BC-F82D	7.2.06-C	D2 RPU A1	1382	
Z07352	-- MD AFM-A INLET VALVE ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED		HV-5119	B	VALVE I E/D1-BC-F82D	7.2.06-C	D2 RPU A1	1382	
Z07353	-- MD AFM-B INLET VALVE ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN		HV-5118	B	VALVE II E/D1-BC-F82C	7.2.06-C	D2 RPU B1	1382	
Z07354	-- MD AFM-B INLET VALVE ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED		HV-5118	B	VALVE II E/D1-BC-F82C	7.2.06-C	D2 RPU B1	1382	
Z07355	-- TDAFM INLET VALVE ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN		HV-5113	B	VALVE I E/D1-BC-F82B	7.2.06-C	D2 RPU A3	1382	
Z07356	-- TDAFM INLET VALVE ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED		HV-5113	B	VALVE I E/D1-BC-F82B	7.2.06-C	D2 RPU A3	1382	
Z07357	-- TDAFM STEAM INLET VALVE ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN		HV-5106	B	VALVE I E/D1-BC-F82A	7.2.06-C	D2 RPU A3	1382	
Z07358	-- TDAFM STEAM INLET VALVE ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED		HV-5106	B	VALVE I E/D1-BC-F82A	7.2.06-C	D2 RPU A3	1382	
Z07361	Z02361 CIRCULATING WATER PUMP 1 ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING		528-NA885	R	5MCR NNS E/D1-BC-B85A	--	MULT	1401	

GEORGIA POWER COMPANY-ENGINEERING & CONSTRUCTION SERVICES REVISION #7.05 12/11/80 #ASB 11/80
 YUGILE 1 REG GUIDE 7/ENF INPUT LIST

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D B
ZD7386	ZD2386	CIRCULATING WATER PUMP 2 ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-NAAW4	N	8NCR	NNS	--	-	MULT 1481	
ZD7381	ZD2381	MAIN FEED PUMP TURBINE A ALM ON CONTACT: CLSD ALM/NML: TRIP / RESET	PSL-5346X	N	FLD	NNS	--	-	MULT 1385	
ZD7396	ZD2396	TDAFW PUMP TRN C TRIP/THRUTTLE VLV ALM ON CONTACT: CLSD ALM/NML: TRIPPED / NOT TRIPPED	PV-16129	B	180 PNL	NNS	7.2.14	D2	MULT 1382	
ZD7397	ZD2397	MOTOR DRIVEN AUX FW PUMP B ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-BA0321	B	180 PNL	NNS	7.2.14	D2	MULT 1382	
ZD7398	ZD2398	MOTOR DRIVEN AUX FW PUMP A ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-AA0217	B	180 PNL	NNS	7.2.14	D2	MULT 1382	
ZD7401	ZD2401	MAIN FEED PUMP TURBINE B ALM ON CONTACT: CLSD ALM/NML: TRIP / RESET	PSL-5347X	N	FLD	NNS	--	-	MULT 1385	
ZD7451	ZD2451	CONDENSATE PUMP 1 ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-NAA85	N	8NCR	NNS	--	-	MULT 1385	
ZD7456	ZD2456	CONDENSATE PUMP 2 ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-NAA86	N	8NCR	NNS	--	-	MULT 1385	
ZD7461	ZD2461	CONDENSATE PUMP 3 ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-NA884	N	8NCR	NNS	--	-	MULT 1385	
ZD7501	ZD2501	CONTAINMENT SPRAY PUMP A ALM ON CONTACT: OPEN ALM/NML: RUNNING / STOPPED	52B-AA0214	B	180 PNL	NNS	7.2.07	D2	MULT 1286	
ZD7502	ZD2502	CONTAINMENT SPRAY PUMP B ALM ON CONTACT: OPEN ALM/NML: RUNNING / STOPPED	52B-BA0314	B	180 PNL	NNS	7.2.07	D2	MULT 1286	
ZD7527	ZD2527	BG LOOP 1 FW ISOLATION - MFIV ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-5227	B	VALVE	I	7.2.04-F	D2	RPU A2 1385	

R	ERF	PROTEUS									S	
V	SYMBOL	SYMBOL	SIGNAL	DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.07 VAR CLASS	INPUT VIA	SYSTEM	B
	ZD7528	ZD2528	SG LOOP 1	FW ISOLATION - MFIV ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5227	B	VALVE	I	7.2.04-F 02	RPU A2	1305	
	ZD7529	ZD2529	SG LOOP 2	FW ISOLATION - MFIV ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-5228	B	VALVE	I	7.2.04-F 02	RPU A2	1305	
	ZD7530	ZD2530	SG LOOP 2	FW ISOLATION - MFIV ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5228	B	VALVE	I	7.2.04-F 02	RPU A2	1305	
	ZD7531	ZD2531	SG LOOP 3	FW ISOLATION - MFIV ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-5229	B	VALVE	I	7.2.04-F 02	RPU A2	1305	
	ZD7532	ZD2532	SG LOOP 3	FW ISOLATION - MFIV ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5229	B	VALVE	I	7.2.04-F 02	RPU A2	1305	
	ZD7533	ZD2533	SG LOOP 4	FW ISOLATION - MFIV ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-5230	B	VALVE	I	7.2.04-F 02	RPU A2	1305	
	ZD7534	ZD2534	SG LOOP 4	FW ISOLATION - MFIV ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-5230	B	VALVE	I	7.2.04-F 02	RPU A2	1305	
	ZD7537	ZD2537	SG1	BLUDDOWN ISOLATION ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-7603A	B	PAR6	NNS	7.2.04-K 02	MULT	1301	
	ZD7538	ZD2538	SG1	BLUDDOWN ISOLATION ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-7603A	B	PAR6	NNS	7.2.04-K 02	MULT	1301	
	ZD7539	ZD2539	SG2	BLUDDOWN ISOLATION ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-7603B	B	PAR7D	NNS	7.2.04-K 02	MULT	1301	
	ZD7540	ZD2540	SG2	BLUDDOWN ISOLATION ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-7603B	B	PAR7D	NNS	7.2.04-K 02	MULT	1301	
	ZD7541	ZD2541	SG3	BLUDDOWN ISOLATION ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-7603C	B	PAR6	NNS	7.2.04-K 02	MULT	1301	

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM S
ZD7542	ZD2542	3G3 BLOWDOWN ISOLATION ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-7603C	B 3086	PAR6 E/D1-BC-Q01C	NN3	7.2.04-K 02	MULT	1301
ZD7543	ZD2543	3G4 BLOWDOWN ISOLATION ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-7603D	B 3061	PAR7D E/D1-BC-Q01D	NN3	7.2.04-K 02	MULT	1301
ZD7544	ZD2544	3G4 BLOWDOWN ISOLATION ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-7603D	B 3085	PAR7D E/D1-BC-Q01D	NN3	7.2.04-K 02	MULT	1301
ZD7571	ZD2571	NSCW PUMP 1 TRAIN A ALM ON CONTACT: CLSD ALM/NML: OFF / ON	520-AA0204	B 2582	IS0 PNL E/D1-80-K04A	NN3	7.2.14	02 MULT	1202
ZD7576	ZD2576	NSCW PUMP 2 TRAIN B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	520-BA0307	B 2585	IS0 PNL E/D1-80-K04B	NN3	7.2.14	02 MULT	1202
ZD7581	ZD2581	NSCW PUMP 3 TRAIN A ALM ON CONTACT: CLSD ALM/NML: OFF / ON	520-AA0208	B 2583	IS0 PNL E/D1-80-K04C	NN3	7.2.14	02 MULT	1202
ZD7586	ZD2586	NSCW PUMP 4 TRAIN B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	520-BA0311	B 2586	IS0 PNL E/D1-80-K04D	NN3	7.2.14	02 MULT	1202
ZD7591	ZD2591	NSCW PUMP 5 TRAIN A ALM ON CONTACT: CLSD ALM/NML: OFF / ON	520-AA0212	B 2584	IS0 PNL E/D1-80-K04E	NN3	7.2.14	02 MULT	1202
ZD7596	ZD2596	NSCW PUMP 6 TRAIN B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	520-BA0315	B 2587	IS0 PNL E/D1-80-K04F	NN3	7.2.14	02 MULT	1202
ZD7603	ZD2603	NSCW COOLING TOWER RTN VALVE TRAIN A ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-1668A	B 3017	IS0 PNL E/D1-80-K05U	NN3	7.2.09-B 02	MULT	1202
ZD7604	ZD2604	NSCW COOLING TOWER BYPASS VLV TRAIN A ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-1668B	B 2828	IS0 PNL E/D1-80-K05V	NN3	7.2.09-B 02	MULT	1202
ZD7605	ZD2605	NSCW COOLING TOWER RTN VALVE TRAIN B ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-1669A	B 3016	IS0 PNL E/D1-80-K05W	NN3	7.2.09-B 02	MULT	1202

R	ERF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S
Y	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM
	Z07606	Z02606	NSCW COOLING TOWER BYPASS VLV TRAIN B ALM ON CONTACTS: CLSD ALM/NML: OPEN / NOT OPEN	HV-1669B	B	180 PNL	NNS	7.2.09-B 02	MULT	1202
						2826	E/01-80-K05X			
	Z07607	Z02607	NSCW COOLING TOWER RTN VALVE TRAIN A ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-1668A	B	180 PNL	NNS	7.2.09-B 02	MULT	1202
						3041	E/01-80-K05U			
	Z07608	Z02608	NSCW COOLING TOWER BYPASS VLV TRAIN A ALM ON CONTACTS: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-1668B	B	180 PNL	NNS	7.2.09-B 02	MULT	1202
						2852	E/01-80-K05V			
	Z07609	Z02609	NSCW COOLING TOWER RTN VALVE TRAIN B ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-1669A	B	180 PNL	NNS	7.2.09-B 02	MULT	1202
						3840	E/01-80-K05W			
	Z07610	Z02610	NSCW COOLING TOWER BYPASS VLV TRAIN B ALM ON CONTACTS: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-1669B	B	180 PNL	NNS	7.2.09-B 02	MULT	1202
						2850	E/01-80-K05X			
	Z07611	Z02611	NSCW FAN 1 TRAIN A ALM ON CONTACTS: CLSD ALM/NML: OFF / ON	52B-AB1505	B	180 PNL	NNS	7.2.09-C 02	MULT	1202
						2588	E/01-80-K03A			
	Z07612	Z02612	NSCW FAN 2 TRAIN A ALM ON CONTACTS: CLSD ALM/NML: OFF / ON	52B-AB1506	B	180 PNL	NNS	7.2.09-C 02	MULT	1202
						2589	E/01-80-K03B			
	Z07613	Z02613	NSCW FAN 3 TRAIN A ALM ON CONTACTS: CLSD ALM/NML: OFF / ON	52B-AB1513	B	180 PNL	NNS	7.2.09-C 02	MULT	1202
						2590	E/01-80-K03C			
	Z07614	Z02614	NSCW FAN 4 TRAIN A ALM ON CONTACTS: CLSD ALM/NML: OFF / ON	52B-AB1508	B	180 PNL	NNS	7.2.09-C 02	MULT	1202
						2591	E/01-80-K03D			
	Z07616	Z02616	NSCW FAN 1 TRAIN B ALM ON CONTACTS: CLSD ALM/NML: OFF / ON	52B-881605	B	180 PNL	NNS	7.2.09-C 02	MULT	1202
						2592	E/01-80-K03E			
	Z07617	Z02617	NSCW FAN 2 TRAIN B ALM ON CONTACTS: CLSD ALM/NML: OFF / ON	52B-881606	B	180 PNL	NNS	7.2.09-C 02	MULT	1202
						2593	E/01-80-K03F			
	Z07618	Z02618	NSCW FAN 3 TRAIN B ALM ON CONTACTS: CLSD ALM/NML: OFF / ON	52B-881613	B	180 PNL	NNS	7.2.09-C 02	MULT	1202
						2594	E/01-80-K03G			

R	ENF	PRUTEUS		ORIGINATING	B	SIGNAL	SIGNAL	RG 1.97	INPUT	S
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	YAN CLASS	VIA	SYSTEM S
	Z07619	Z02619	N3CR FAN 4 TRAIN B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-8B1600	B	180 PNL	NNS	7.2.09-C	D2 MULT	1202
					2595	E/01-80-K03H				
	Z07631	Z02631	CCW PUMP 1 TRAIN A ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-AA0203	B	180 PNL	NNS	7.2.14	D2 MULT	1203
					2576	E/01-80-L01A				
	Z07636	Z02636	CCW PUMP 2 TRAIN B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-BA0300	B	180 PNL	NNS	7.2.14	D2 MULT	1203
					2579	E/01-80-L01B				
	Z07641	Z02641	CCW PUMP 3 TRAIN A ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-AA0207	B	180 PNL	NNS	7.2.14	D2 MULT	1203
					2577	E/01-80-L01C				
	Z07646	Z02646	CCW PUMP 4 TRAIN B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-BA0312	B	180 PNL	NNS	7.2.14	D2 MULT	1203
					2580	E/01-80-L01D				
	Z07651	Z02651	CCW PUMP 5 TRAIN A ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-AA0211	B	180 PNL	NNS	7.2.14	D2 MULT	1203
					2578	E/01-80-L01E				
	Z07656	Z02656	CCW PUMP 6 TRAIN B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-BA0316	B	180 PNL	NNS	7.2.14	D2 MULT	1203
					2581	E/01-80-L01F				
	Z07681	Z02681	ACCW PUMP 1 ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-AA0215	B	180 PNL	NNS	--	- MULT	1217
					2448	E/01-80-L03A				
	Z07691	Z02691	ACCW PUMP 2 (SPARE) ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-BA0320	B	180 PNL	NNS	--	- MULT	1217
					2446	E/01-80-L03B				
*	Z07701	Z02701	ACCW RETURN TRAIN A ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-1975	B	180 PNL	NNS	--	- MULT	1217
					3014	E/01-80-L03C				
*	Z07702	Z02702	ACCW RETURN TRAIN A ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-1975	B	180 PNL	NNS	--	- MULT	1217
					3038	E/01-80-L03C				
*	Z07703	Z02703	ACCW RETURN TRAIN B ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-1974	B	180 PNL	NNS	--	- MULT	1217
					3015	E/01-80-L03F				

Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
*	ZD7704	ZD2704	ACCM RETURN TRAIN B ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-1974	B 3039	ISO PNL E/D1-BD-L03F	NNS	-- -	MULT	1217	
*	ZD7705	ZD2705	ACCM SUPPLY TRAIN A ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-1979	B 3012	ISO PNL E/D1-BD-L03J	NNS	-- -	MULT	1217	
*	ZD7706	ZD2706	ACCM SUPPLY TRAIN A ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-1979	B 3036	ISO PNL E/D1-BD-L03J	NNS	-- -	MULT	1217	
*	ZD7707	ZD2707	ACCM SUPPLY TRAIN B ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-1978	B 3013	ISO PNL E/D1-BD-L03H	NNS	-- -	MULT	1217	
*	ZD7708	ZD2708	ACCM SUPPLY TRAIN B ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-1978	B 3037	ISO PNL E/D1-BD-L03H	NNS	-- -	MULT	1217	
	ZD7793	ZD2793	4.16KV BUS 1AA02 DG BRKR 19 ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	520-AA0219	B 2039	ISO PNL E/D1-BA-D02D	NNS	-- -	MULT	1004	
	ZD7794	ZD2794	4.16KV BUS 1BA03 DG BRKR 19 ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	520-BA0319	B 2041	ISO PNL E/D1-BA-D03D	NNS	-- -	MULT	1004	
	ZD7851	ZD2851	GENERATOR BREAKER 161710 ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	4520	N 2264	TERM10	NNS	-- -	MULT	1002	
	ZD7852	ZD2852	GENERATOR BREAKER 161810 ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	4520	N 2341	TERM10	NNS	-- -	MULT	1002	
	ZD7901	ZD2901	13.8KV BUS 1NAA NORMAL INCOMING BRKR 03 ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	520-NAA03	B 2445	SMGR E/D1-BA-C01B	NNS	-- -	MULT	1025	
	ZD7902	ZD2902	13.8KV BUS 1NAB NORMAL INCOMING BRKR 03 ALM ON CONTACTS: CLSD ALM/NML: OPEN / CLOSED	520-NAB03	B 2453	SMGR E/D1-BA-C02B	NNS	-- -	MULT	1025	
	ZD7903	ZD2903	13.8KV BUS 1NAA ALTERNATE INCOMING BRKR 01 ALM ON CONTACTS: OPEN ALM/NML: CLOSED / OPEN	520-NAA01	B 2443	SMGR E/D1-BA-C01C	NNS	-- -	MULT	1025	

R	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D
ZD7904	ZD2904	13.8KV BUS 1A01	ALTERNATE INCOMING BRKR #1 ALM ON CONTACT: OPEN ALM/NML: CLOSED / OPEN	52B-NA001	B 2277	SWGR E/D1-BA-C02C	NNS	-- -	MULT	1825	
ZD7905	ZD2905	4.16KV BUS 1A02	NORMAL INCOMING BRKR #5 ALM ON CONTACT: CLSD ALM/NML: OPEN / CLOSED	52B-AA0205	B 2285	ISU PNL E/D1-BA-D02B	NNS	-- -	MULT	1804	X
ZD7906	ZD2906	4.16KV BUS 1A05	NORMAL INCOMING BRKR #3 ALM ON CONTACT: CLSD ALM/NML: OPEN / CLOSED	52B-NA0503	B 2269	SWGR E/D1-BA-D05B	NNS	-- -	MULT	1804	
ZD7907	ZD2907	4.16KV BUS 1A01	NORMAL INCOMING BRKR #3 ALM ON CONTACT: CLSD ALM/NML: OPEN / CLOSED	52B-NA0103	B 2265	SWGR E/D1-BA-D01B	NNS	-- -	MULT	1804	
ZD7908	ZD2908	4.16KV BUS 1A04	NORMAL INCOMING BRKR #3 ALM ON CONTACT: CLSD ALM/NML: OPEN / CLOSED	52B-NA0403	B 2043	SWGR E/D1-BA-D04B	NNS	-- -	MULT	1804	
ZD7909	ZD2909	4.16KV BUS 1B03	NORMAL INCOMING BRKR #1 ALM ON CONTACT: CLSD ALM/NML: OPEN / CLOSED	52B-BA0301	B 2539	ISU PNL E/D1-BA-D03B	NNS	-- -	MULT	1804	X
ZD7910	ZD2910	4.16KV BUS 1A02	EMERGENCY INCOMING BRKR #1 ALM ON CONTACT: OPEN ALM/NML: CLOSED / OPEN	52B-AA0201	B 2283	ISU PNL E/D1-BA-D02C	NNS	-- -	MULT	1804	X
ZD7911	ZD2911	4.16KV BUS 1A05	ALTERNATE INCOMING BRKR #1 ALM ON CONTACT: OPEN ALM/NML: CLOSED / OPEN	52B-NA0501	B 2267	SWGR E/D1-BA-D05C	NNS	-- -	MULT	1804	
ZD7912	ZD2912	4.16KV BUS 1A01	ALTERNATE INCOMING BRKR #1 ALM ON CONTACT: OPEN ALM/NML: CLOSED / OPEN	52B-NA0101	B 2342	SWGR E/D1-BA-D01C	NNS	-- -	MULT	1804	
ZD7913	ZD2913	4.16KV BUS 1A04	ALTERNATE INCOMING BRKR #1 ALM ON CONTACT: OPEN ALM/NML: CLOSED / OPEN	52B-NA0401	B 2541	SWGR E/D1-BA-D04C	NNS	-- -	MULT	1804	
ZD7914	ZD2914	4.16KV BUS 1B03	EMERGENCY INCOMING BRKR #5 ALM ON CONTACT: OPEN ALM/NML: CLOSED / OPEN	52B-BA0305	B 2537	ISU PNL E/D1-BA-D03C	NNS	-- -	MULT	1804	X
ZD8417	ZD3417	CHMT BLDG AIR COOLING UNIT 1	ALM ON CONTACT: CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-AB0405	B 2766	ISU PNL E/D1-BG-B03F	NNS	7.2.07-E 02	MULT	1501	

R	E	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING	B	SIGNAL	SIGNAL	KG 1.97	INPUT	B
V	SYMBOL	SYMBOL			DEVICE	Y	SOURCE	CLASS	VAH CLASS	VIA	SYSTEM
	Z08418	Z03418	CNMT BLDG AIR COOLING UNIT 1	ALM ON CONTACT: CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-AB0404	B	180 PNL	NNS	7.2.07-E 02	MULT	1501
						2742	E/D1-BG-B01A				
	Z08419	Z03419	CNMT BLDG AIR COOLING UNIT 2	ALM ON CONTACT: CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-AB0409	B	180 PNL	NNS	7.2.07-E 02	MULT	1501
						2767	E/D1-BG-B03G				
	Z08420	Z03420	CNMT BLDG AIR COOLING UNIT 2	ALM ON CONTACT: CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-AB0408	B	180 PNL	NNS	7.2.07-E 02	MULT	1501
						2743	E/D1-BG-B01B				
	Z08421	Z03421	CNMT BLDG AIR COOLING UNIT 5	ALM ON CONTACT: CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-AB0413	B	180 PNL	NNS	7.2.07-E 02	MULT	1501
						2794	E/D1-BG-B03K				
	Z08422	Z03422	CNMT BLDG AIR COOLING UNIT 5	ALM ON CONTACT: CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-AB0412	B	180 PNL	NNS	7.2.07-E 02	MULT	1501
						2770	E/D1-BG-B01E				
	Z08423	Z03423	CNMT BLDG AIR COOLING UNIT 6	ALM ON CONTACT: CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-AB0417	B	180 PNL	NNS	7.2.07-E 02	MULT	1501
						2795	E/D1-BG-B03L				
	Z08424	Z03424	CNMT BLDG AIR COOLING UNIT 6	ALM ON CONTACT: CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-AB0416	B	180 PNL	NNS	7.2.07-E 02	MULT	1501
						2771	E/D1-BG-B01F				
	Z08438	Z03438	DG/ESF SUPPLY FAN 1 TRAIN A	ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-AB0512	B	180 PNL	NNS	7.2.11-B 02	MULT	1566
						2437	E/D1-BG-F01B				
	Z08439	Z03439	DG/ESF SUPPLY FAN 3 TRAIN A	ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-AB0513	B	180 PNL	NNS	7.2.11-B 02	MULT	1566
						2383	E/D1-BG-F01C				
	Z08441	--	CB ESF BATTERY ROOM EXH FAN 1 TRAIN A	ALM ON CONTACT: CLSD ALM/NML: OFF / ON	42B-ABC05	B	MCC	I	7.2.11-B 02	RPU A2	1532
						2444	E/D1-BG-C04N				
	Z08442	--	CB ESF BATTERY ROOM EXH FAN 2 TRAIN B	ALM ON CONTACT: CLSD ALM/NML: OFF / ON	42B-BBC05	B	MCC	II	7.2.11-B 02	RPU B2	1532
						2452	E/D1-BG-C04P				
	Z08443	--	CB ESF BATTERY ROOM EXH FAN 3 TRAIN A	ALM ON CONTACT: CLSD ALM/NML: OFF / ON	42B-ABC06	B	MCC	I	7.2.11-B 02	RPU A2	1532
						2442	E/D1-BG-C04Q				

R	E	Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D S
			Z08444	-- CB ESF BATTERY ROOM EXH FAN 4 TRAIN B	ALM ON CONTACTS CLSD ALM/NML: OFF / ON	42B-BBC06	B	MCC	II	7.2.11-B 02 RPU B2	1532		
			Z08446	-- CB ESF ELEC EQUIP ROOM COOLER UNIT 1	ALM ON CONTACTS CLSD ALM/NML: OFF / ON	42B-ABC29	B	MCC	I	7.2.11-B 02 RPU B2	1532		
			Z08447	-- CB ESF ELEC EQUIP ROOM COOLER UNIT 2	ALM ON CONTACTS CLSD ALM/NML: OFF / ON	42B-BBC29	B	MCC	II	7.2.11-B 02 RPU B2	1532		
			Z08448	-- CB ESF CHILLED WATER PUMP 1 TRAIN A	ALM ON CONTACTS CLSD ALM/NML: OFF / ON	42B-ABA15	B	MCC	I	-- - RPU A2	1532		
			Z08449	-- CB ESF CHILLED WATER PUMP 2 TRAIN B	ALM ON CONTACTS CLSD ALM/NML: OFF / ON	42B-BBA15	B	MCC	II	-- - RPU B2	1532		
			Z08457	Z03457 CNMT BLDG AIR COOLING UNIT 3	ALM ON CONTACTS CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-BB0605	B	ISO PNL	NNS	7.2.07-E 02 MULT	1501		
			Z08458	Z03458 CNMT BLDG AIR COOLING UNIT 3	ALM ON CONTACTS CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-BB0604	B	ISO PNL	NNS	7.2.07-E 02 MULT	1501		
			Z08459	Z03459 CNMT BLDG AIR COOLING UNIT 4	ALM ON CONTACTS CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-BB0609	B	ISO PNL	NNS	7.2.07-E 02 MULT	1501		
			Z08460	Z03460 CNMT BLDG AIR COOLING UNIT 4	ALM ON CONTACTS CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-BB0608	B	ISO PNL	NNS	7.2.07-E 02 MULT	1501		
			Z08461	Z03461 CNMT BLDG AIR COOLING UNIT 7	ALM ON CONTACTS CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-BB0613	B	ISO PNL	NNS	7.2.07-E 02 MULT	1501		
			Z08462	Z03462 CNMT BLDG AIR COOLING UNIT 7	ALM ON CONTACTS CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-BB0612	B	ISO PNL	NNS	7.2.07-E 02 MULT	1501		
			Z08463	Z03463 CNMT BLDG AIR COOLING UNIT 8	ALM ON CONTACTS CLSD ALM/NML: NOT LOW SPEED / LOW SPEED	52B-BB0617	B	ISO PNL	NNS	7.2.07-E 02 MULT	1501		

R	EMF	PRTEUS		ORIGINATING	B	SIGNAL	SIGNAL	HG 1.97	INPUT		B
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	B
Z08464	Z03464	CNMT BLDG AIR COOLING UNIT 8	ALM ON CONTACT: CLSD ALM/NML: NOT HIGH SPEED / HIGH SPEED	52B-880616	B	IS0 PNL	NNS	7.2.07-E	D2 MULT	1501	
					2773	E/D1-BG-B01H					
Z08479	Z03479	DC/ESF SUPPLY FAN 4 TRAIN 8	ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-880713	B	IS0 PNL	NNS	7.2.11-B	D2 MULT	1566	
					2337	E/D1-BG-F01F					
Z08490	Z03480	DC/ESF SUPPLY FAN 2 TRAIN 8	ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-880712	B	IS0 PNL	NNS	7.2.11-B	D2 MULT	1566	
					2221	E/D1-BG-F01E					
Z08501	Z03501	RCP 1	ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-MAA00	B	SWGR	NNS	7.2.01-B	D2 MULT	1201	X
					2247	E/D1-B0-B01A					
Z08502	Z03502	RCP 2	ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-NAB06	B	SWGR	NNS	7.2.01-B	D2 MULT	1201	X
					2245	E/D1-B0-B01B					
Z08503	Z03503	RCP 3	ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-NAAW7	B	SWGR	NNS	7.2.01-B	D2 MULT	1201	X
					2441	E/D1-B0-B01C					
Z08504	Z03504	RCP 4	ALM ON CONTACT: CLSD ALM/NML: STOPPED / RUNNING	52B-NAB07	B	SWGR	NNS	7.2.01-B	D2 MULT	1201	X
					2439	E/D1-B0-B01D					
Z08511	--	ACCUM ISOLATION LOOP 1 HV-8800A	ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-8800A	B	VALVE	NNS	7.2.05-E	D2 RPU N1	1204	
					3111	E/D1-B0-D02R		(NON 1E SWITCH)			
Z08512	--	ACCUM ISOLATION LOOP 1 HV-8800A	ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-8800A	B	VALVE	NNS	7.2.05-E	D2 RPU N1	1204	
					3135	E/D1-B0-D02R		(NON 1E SWITCH)			
Z08513	--	ACCUM ISOLATION LOOP 2 HV-8800B	ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-8800B	B	VALVE	NNS	7.2.05-E	D2 RPU N1	1204	
					3110	E/D1-B0-D02S		(NON 1E SWITCH)			
Z08514	--	ACCUM ISOLATION LOOP 2 HV-8800B	ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-8800B	B	VALVE	NNS	7.2.05-E	D2 RPU N1	1204	
					3134	E/D1-B0-D02S		(NON 1E SWITCH)			
Z08515	--	ACCUM ISOLATION LOOP 3 HV-8800C	ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-8800C	B	VALVE	NNS	7.2.05-E	D2 RPU N1	1204	
					3109	E/D1-B0-D02T		(NON 1E SWITCH)			

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ALM ON CONTACTS	ORIGINATING DEVICE	B	SIGNAL SOURCE	SIGNAL CLASS	HS	INPUT	SYSTEM
Z08510	--	ALM ON CONTACTS	ALM/NML1 CLOSED / NOT CLOSED	3133	B	VALVE	MNS	7.2.05-E	D2 RPU N1 1204	(NON IE SWITCH)
Z08517	--	ALM ON CONTACTS	ALM/NML1 NOT OPEN / OPEN	3108	B	VALVE	MNS	7.2.05-E	D2 RPU N1 1204	(NON IE SWITCH)
Z08518	--	ALM ON CONTACTS	ALM/NML1 CLOSED / NOT CLOSED	3132	B	VALVE	MNS	7.2.05-E	D2 RPU N1 1204	(NON IE SWITCH)
Z08521	ZUJ521	ALM ON CONTACTS	ALM/NML1 RUNNING / STOPPED	528-AA0216	B	130 PNL	MNS	7.2.14	D2 MULT	1204
Z08522	ZUJ522	ALM ON CONTACTS	ALM/NML1 RUNNING / STOPPED	528-BA0317	B	180 PNL	MNS	7.2.14	D2 MULT	1204
Z08541	--	ALM ON CONTACTS	ALM/NML1 NOT OPEN / OPEN	3006	B	VALVE	I	7.2.02-A	D2 RPU A1 1201	
Z08542	--	ALM ON CONTACTS	ALM/NML1 CLOSED / NOT CLOSED	3064	B	VALVE	I	7.2.02-A	D2 RPU A1 1201	
Z08543	--	ALM ON CONTACTS	ALM/NML1 NOT OPEN / OPEN	3059	B	VALVE	II	7.2.02-A	D2 RPU B1 1201	
Z08544	--	ALM ON CONTACTS	ALM/NML1 CLOSED / NOT CLOSED	3003	B	VALVE	II	7.2.02-A	D2 RPU B1 1201	
Z08545	--	ALM ON CONTACTS	ALM/NML1 OPEN / NOT OPEN	2968	B	VALVE	II	7.2.02-A	D2 RPU B1 1201	
Z08546	--	ALM ON CONTACTS	ALM/NML1 NOT CLOSED / CLOSED	2992	B	VALVE	II	7.2.02-A	D2 RPU B1 1201	
Z08547	--	ALM ON CONTACTS	ALM/NML1 OPEN / NOT OPEN	2969	B	VALVE	I	7.2.02-A	D2 RPU A1 1201	

R
E
V

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RC 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D
Z08548	--	PRESSURIZER PUV-455A TRAIN A ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	PV-0455A	B	2993	VALVE I E/D1-80-B03H	7.2.02-A 02	RPU A1	1201	
Z08551	--	PRESSURIZER HEATERS CONTROL GROUP C ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-N80012	B	2292	SMGR NNS E/D1-80-B01J	--	- 30E	1201	
Z08552	--	PRESSURIZER HEATERS BACKUP GROUP A ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-N80109	B	2258	SMGR NNS E/D1-80-B01K	7.2.02-C 02	30E	1201	
Z08553	--	PRESSURIZER HEATERS BACKUP GROUP B ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-N81005	B	2259	SMGR NNS E/D1-80-B01L	7.2.02-C 02	30E	1201	
Z08554	--	PRESSURIZER HEATERS BACKUP GROUP D ALM ON CONTACT: CLSD ALM/NML: OFF / ON	52B-N80912	B	2290	SMGR NNS E/D1-80-B01M	--	- 30E	1201	
Z08561	--	S1 PUMPS INLET VALVE ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-8006	B	3112	VALVE NNS E/D1-80-D02H	7.2.05-E 02	RPU N1	1204	
Z08562	--	S1 PUMPS INLET VALVE ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-8006	B	3136	VALVE NNS E/D1-80-D02H	7.2.05-E 02	RPU N1	1204	
Z08572	--	S1S ACCUM N2 VLV TRAIN A LOOP 1 ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8075A	B	2459	VALVE I E/D1-80-D04H	7.2.05-E 02	RPU A1	1204	
Z08574	--	S1S ACCUM N2 VLV TRAIN A LOOP 2 ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8075B	B	2461	VALVE I E/D1-80-D04H	7.2.05-E 02	RPU A1	1204	
Z08576	--	S1S ACCUM N2 VLV TRAIN A LOOP 3 ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8075C	B	2463	VALVE I E/D1-80-D04H	7.2.05-E 02	RPU A1	1204	
Z08578	--	S1S ACCUM N2 VLV TRAIN A LOOP 4 ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8075D	B	2465	VALVE I E/D1-80-D04H	7.2.05-E 02	RPU A1	1204	
Z08632	--	CVCS AUX SPRAY VALVE ALM ON CONTACT: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8145	B	2261	VALVE NNS E/D1-80-B03K	7.2.03-E 02	30E	1201	

EMF SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	SIGNAL	MG 1.97 INPUT	VAH CLASS	VIA SYSTEM
Z08636	-- ALM ON CONTACT	CHARGING PATH VLV TO NEGEN HX TRAIN B OPEN ALM/NML; NOT OPEN / OPEN	HV-8185	B	VALVE II E/O1-BD-CW36	7.2.83-E 02 RPU B1 1288		
Z08637	-- ALM ON CONTACT	CHARGING PATH VLV TO NEGEN HX TRAIN B CLSD ALM/NML; CLOSED / NOT CLOSED	HV-8185	B	VALVE II E/O1-BD-CW36	7.2.83-E 02 RPU B1 1288		
Z08638	-- ALM ON CONTACT	CHARGING PATH VLV TO NEGEN HX TRAIN A OPEN ALM/NML; NOT OPEN / OPEN	HV-8186	B	VALVE I E/O1-BD-CW3H	7.2.83-E 02 RPU A1 1288		
Z08639	-- ALM ON CONTACT	CHARGING PATH VLV TO NEGEN HX TRAIN A CLSD ALM/NML; CLOSED / NOT CLOSED	HV-8186	B	VALVE I E/O1-BD-CW3H	7.2.83-E 02 RPU A1 1288		
Z08641	-- ALM ON CONTACT	CHARGING PATH VALVE TO RCS TRAIN A OPEN ALM/NML; NOT OPEN / OPEN	HV-8146	B	VALVE I E/O1-BD-CW3T	7.2.83-E 02 RPU A1 1288		
Z08642	-- ALM ON CONTACT	CHARGING PATH VALVE TO RCS TRAIN A CLSD ALM/NML; CLOSED / NOT CLOSED	HV-8146	B	VALVE I E/O1-BD-CW3T	7.2.83-E 02 RPU A1 1288		
Z08643	-- ALM ON CONTACT	CHARGING PATH VALVE TO RCS TRAIN B OPEN ALM/NML; NOT OPEN / NOT OPEN	HV-8147	B	VALVE II E/O1-BD-CW3U	7.2.83-E 02 RPU B1 1288		
Z08644	-- ALM ON CONTACT	CHARGING PATH VALVE TO RCS TRAIN B OPEN ALM/NML; NOT CLOSED / CLOSED	HV-8147	B	VALVE II E/O1-BD-CW3U	7.2.83-E 02 RPU B1 1288		
Z08646	-- ALM ON CONTACT	RHR PUMP A TO CVCS PUMP SUCTION VALVE CLSD ALM/NML; OPEN / NOT OPEN	HV-8884	B	VALVE I E/O1-BD-DW2L	7.2.18-B 02 RPU A1 1285		
Z08647	-- ALM ON CONTACT	RHR PUMP A TO CVCS PUMP SUCTION VALVE CLSD ALM/NML; NOT CLOSED / CLOSED	HV-8884	B	VALVE I E/O1-BD-DW2L	7.2.18-B 02 RPU A1 1285		
Z08648	-- ALM ON CONTACT	RHR PUMP B TO SIS PUMP SUCTION VALVE CLSD ALM/NML; OPEN / NOT OPEN	HV-8884B	B	VALVE II E/O1-BD-DW2M	7.2.18-B 02 RPU B1 1285		
Z08649	-- ALM ON CONTACT	RHR PUMP B TO SIS PUMP SUCTION VALVE CLSD ALM/NML; NOT CLOSED / CLOSED	HV-8884B	B	VALVE II E/O1-BD-DW2M	7.2.18-B 02 RPU B1 1285		

R
C
V

S
P
D
S

MOBILE I REC GUIDE T/ERF INPUT LIST

R	E	V	SYM	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL	CLASS	VALVE	RPV	AL	1200
---	---	---	-----	---------	--------------------	--------------------	--------	-------	-------	-----	----	------

Z08651	--			CHARGING PUMP (TRAIN A) DISCH VALVE	HY-8116	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS CLSD ALM/NMLE OPEN / NOT OPEN		2934	E/01-80-C85E					

Z08652	--			CHARGING PUMP (TRAIN A) DISCH VALVE	HY-8116	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS OPEN ALM/NMLE NOT CLOSED / CLOSED		2958	E/01-80-C80E					

Z08653	--			CHARGING PUMP (TRAIN A) DISCH VALVE	HY-8485A	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS OPEN ALM/NMLE NOT OPEN / OPEN		3114	E/01-80-C85A					

Z08654	--			CHARGING PUMP (TRAIN A) DISCH VALVE	HY-8485A	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS CLSD ALM/NMLE CLOSED / NOT CLOSED		3138	E/01-80-C85A					

Z08655	--			CHARGING PUMP (TRAIN B) DISCH VALVE	HY-8485B	B	VALVE II		7.2.03-E	D2	RPV B1	1200
				ALM ON CONTACTS OPEN ALM/NMLE NOT OPEN / OPEN		3113	E/01-80-C85B					

Z08656	--			CHARGING PUMP (TRAIN B) DISCH VALVE	HY-8485B	B	VALVE II		7.2.03-E	D2	RPV B1	1200
				ALM ON CONTACTS OPEN ALM/NMLE CLOSED / NOT CLOSED		3137	E/01-80-C85B					

Z08660	--			CHARGING PUMP (TRAIN A) SUCTION VALVE	HY-8471A	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS OPEN ALM/NMLE NOT OPEN / OPEN		3116	E/01-80-C85C					

Z08667	--			CHARGING PUMP (TRAIN A) SUCTION VALVE	HY-8471A	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS CLSD ALM/NMLE CLOSED / NOT CLOSED		3148	E/01-80-C85C					

Z08668	--			CHARGING PUMP (TRAIN B) SUCTION VALVE	HY-8471B	B	VALVE II		7.2.03-E	D2	RPV B1	1200
				ALM ON CONTACTS OPEN ALM/NMLE NOT OPEN / OPEN		3115	E/01-80-C85D					

Z08669	--			CHARGING PUMP (TRAIN B) SUCTION VALVE	HY-8471B	B	VALVE II		7.2.03-E	D2	RPV B1	1200
				ALM ON CONTACTS OPEN ALM/NMLE CLOSED / NOT CLOSED		3139	E/01-80-C85D					

Z08671	--			WAST TO CHARGING PUMPS TRAIN A VALVE	LV-81120	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS CLSD ALM/NMLE OPEN / NOT OPEN		2978	E/01-80-C82M					

Z08672	--			WAST TO CHARGING PUMPS TRAIN A VALVE	LV-81120	B	VALVE I		7.2.03-E	D2	RPV A1	1200
				ALM ON CONTACTS OPEN ALM/NMLE NOT CLOSED / CLOSED		3082	E/01-80-C82M					

5050

R
E
V
S
YMBOL SYMBOL SIGNAL DESCRIPTION

SYMBOL	DESCRIPTION	ORIGINATING DEVICE	SIGNAL CLASS	SIGNAL SOURCE	REVISION	DATE	BY
Z08673	-- HRS1 TO CHARGING PUMPS TRAIN B VALVE ALM ON CONTACTS CLSD ALM/NML1 OPEN / NOT OPEN	LV-8112E	B	VALVE II	2977	7.2.83-E 02	RPU B1 1288
Z08674	-- HRS1 TO CHARGING PUMPS TRAIN B VALVE ALM ON CONTACTS OPEN ALM/NML1 NOT CLOSED / CLOSED	LV-8112E	B	VALVE II	3881	7.2.83-E 02	RPU B1 1288
Z08676	-- VCI TO CHARGING PUMPS TRAIN A VALVE ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	LV-8112B	B	VALVE I	3187	7.2.83-E 02	RPU A1 1288
Z08677	-- VCI TO CHARGING PUMPS TRAIN A VALVE ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	LV-8112B	B	VALVE I	3131	7.2.83-E 02	RPU A1 1288
Z08678	-- VCI TO CHARGING PUMPS TRAIN B VALVE ALM ON CONTACTS OPEN ALM/NML1 NOT OPEN / OPEN	LV-8112C	B	VALVE II	3186	7.2.83-E 02	RPU B1 1288
Z08679	-- VCI TO CHARGING PUMPS TRAIN B VALVE ALM ON CONTACTS CLSD ALM/NML1 CLOSED / NOT CLOSED	LV-8112C	B	VALVE II	3136	7.2.83-E 02	RPU B1 1288
Z08681	-- RHR PUMP TRAIN A SUCTION VALVE 8781A ALM ON CONTACTS CLSD ALM/NML1 OPEN / NOT OPEN	HV-8781A	B	VALVE I	2782	7.2.18-B 02	RPU A1 1285
Z08682	-- RHR PUMP TRAIN A SUCTION VALVE 8781A ALM ON CONTACTS CLSD ALM/NML1 NOT CLOSED / CLOSED	HV-8781A	B	VALVE I	2886	7.2.18-B 02	RPU A1 1285
Z08683	-- RHR PUMP TRAIN A SUCTION VALVE 8781B ALM ON CONTACTS CLSD ALM/NML1 OPEN / NOT OPEN	HV-8781B	B	VALVE III	2784	7.2.18-B 02	RPU A3 1285
Z08684	-- RHR PUMP TRAIN A SUCTION VALVE 8781B ALM ON CONTACTS OPEN ALM/NML1 NOT CLOSED / CLOSED	HV-8781B	B	VALVE III	2888	7.2.18-B 02	RPU A3 1285
Z08685	-- RHR PUMP TRAIN B SUCTION VALVE 8782A ALM ON CONTACTS CLSD ALM/NML1 OPEN / NOT OPEN	HV-8782A	B	VALVE IV	2786	7.2.18-B 02	RPU B3 1285
Z08686	-- RHR PUMP TRAIN B SUCTION VALVE 8782A ALM ON CONTACTS OPEN ALM/NML1 NOT CLOSED / CLOSED	HV-8782A	B	VALVE IV	2814	7.2.18-B 02	RPU B3 1285

B
P
D
SYSTEM B

EMF SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	SIGNAL CLASS	RC 1.97	INPUT VIA SYSTEM
Z08687	--	MHR PUMP TRAIN B SUCTION VALVE 87828 ALM ON CONTACTS: CLSD ALM/NML: OPEN / NOT OPEN	MV-87828	B	VALVE II	7.2.10-B 02 RPU 01 1285	X
Z08688	--	MHR PUMP TRAIN B SUCTION VALVE 87828 ALM ON CONTACTS: CLSD ALM/NML: NOT CLOSED / CLOSED	MV-87828	B	VALVE II	7.2.10-B 02 RPU 01 1285	X
Z08691	--	MHR PUMP TRAIN A RECIRC VALVE ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	FV-8619	B	VALVE I	7.2.10-B 02 RPU A1 1285	X
Z08692	--	MHR PUMP TRAIN A RECIRC VALVE ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	FV-8619	B	VALVE I	7.2.10-B 02 RPU A1 1285	X
Z08693	--	MHR PUMP TRAIN B RECIRC VALVE ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	FV-8611	B	VALVE II	7.2.10-B 02 RPU 01 1285	X
Z08694	--	MHR PUMP TRAIN B RECIRC VALVE ALM ON CONTACTS: CLSD ALM/NML: CLOSED / NOT CLOSED	FV-8611	B	VALVE II	7.2.10-B 02 RPU 01 1285	X
Z08696	--	MHR HEAT EXCH TRAIN A BYPASS VALVE ALM ON CONTACTS: CLSD ALM/NML: OPEN / NOT OPEN	FV-8618	B	VALVE NNS	-- -- 30E 1285	X
Z08697	--	MHR HEAT EXCH TRAIN A BYPASS VALVE ALM ON CONTACTS: CLSD ALM/NML: NOT CLOSED / CLOSED	FV-8618	B	VALVE NNS	-- -- 30E 1285	X
Z08698	--	MHR HEAT EXCH TRAIN B BYPASS VALVE ALM ON CONTACTS: CLSD ALM/NML: OPEN / NOT OPEN	FV-8619	B	VALVE NNS	-- -- 30E 1285	X
Z08699	--	MHR HEAT EXCH TRAIN B BYPASS VALVE ALM ON CONTACTS: CLSD ALM/NML: NOT CLOSED / CLOSED	FV-8619	B	VALVE NNS	-- -- 30E 1285	X
Z08701	--	MHR HEAT EXCH TRAIN A DISCH VALVE ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	MV-8686	B	VALVE NNS	-- -- 30E 1285	X
Z08702	--	MHR HEAT EXCH TRAIN A DISCH VALVE ALM ON CONTACTS: OPEN ALM/NML: CLOSED / NOT CLOSED	MV-8686	B	VALVE NNS	-- -- 30E 1285	X

REF SYMBOL	PROTUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	RG 1.97 VAR CLASS	INPUT VIA SYSTEM
Z08783	--	MHR HEAT EXCH TRIN B DISCH VALVE ALM ON CONTACTS OPEN / OPEN / OPEN	MV-8887	B VALVE NMS E/D1-80-EM2Q	--	- 80E 1285
Z08784	--	MHR HEAT EXCH TRIN B DISCH VALVE ALM ON CONTACTS OPEN / NOT CLOSED	MV-8887	B VALVE NMS E/D1-80-EM2Q	--	- 80E 1285
Z08786	--	MHR PUMP A SUCTION VALVE (MST) ALM ON CONTACTS OPEN / OPEN / OPEN	MV-8812A	B VALVE I E/D1-80-EM2E	7.2.18-B 02 RPU A1	1285
Z08787	--	MHR PUMP A SUCTION VALVE (MST) ALM ON CONTACTS OPEN / NOT CLOSED	MV-8812A	B VALVE I E/D1-80-EM2E	7.2.18-B 02 RPU A1	1285
Z08788	--	MHR PUMP B SUCTION VALVE (MST) ALM ON CONTACTS OPEN / OPEN	MV-8812B	B VALVE II E/D1-80-EM2F	7.2.18-B 02 RPU B1	1285
Z08789	--	MHR PUMP B SUCTION VALVE (MST) ALM ON CONTACTS OPEN / NOT CLOSED	MV-8812B	B VALVE II E/D1-80-EM2F	7.2.18-B 02 RPU B1	1285
Z08711	--	MHR VALVE TO COLD LEGS 1 & 2 TRIN A ALM ON CONTACTS OPEN / OPEN	MV-8889A	B VALVE I E/D1-80-082V	7.2.18-B 02 RPU A1	1284 X
Z08712	--	MHR VALVE TO COLD LEGS 1 & 2 TRIN A ALM ON CONTACTS OPEN / NOT CLOSED	MV-8889A	B VALVE I E/D1-80-082V	7.2.18-B 02 RPU A1	1284 X
Z08713	--	MHR VALVE TO COLD LEGS 3 & 4 TRIN B ALM ON CONTACTS OPEN / OPEN	MV-8889B	B VALVE II E/D1-80-082W	7.2.18-B 02 RPU B1	1284 X
Z08714	--	MHR VALVE TO COLD LEGS 3 & 4 TRIN B ALM ON CONTACTS OPEN / NOT CLOSED	MV-8889B	B VALVE II E/D1-80-082W	7.2.18-B 02 RPU B1	1284 X
Z08722	--	EXCESS LETDOWN ISOLATION VALVE ALM ON CONTACTS OPEN / CLOSED	MV-8153	B VALVE NMS E/D1-80-C83Z	--	- 80E 1286
Z08724	--	EXCESS LETDOWN ISOLATION VALVE ALM ON CONTACTS OPEN / CLOSED	MV-8154	B VALVE NMS E/D1-80-C818	--	- 80E 1288

M ERF PHUTEUS SIGNAL DESCRIPTION UNIGINATING B SIGNAL SIGNAL MG 1.97 INPUT P
 V SYMBOL SYMBOL DESCRIPTION DEVICE Y SOURCE CLASS VAR CLASS VIA SYSTEM B

Z08725	--	BURIC ACID TRANSFER PUMP IMHN A ALM ON CONTACTS	OPEN	ALM/NML	RUNNING / STOPPED	428-88047	B	MCC I	--	--	RPU A2	1288
Z08726	--	BURIC ACID TRANSFER PUMP IMHN B ALM ON CONTACTS	OPEN	ALM/NML	RUNNING / STOPPED	428-88047	B	MCC II	--	--	RPU B2	1288
Z08727	--	BURIC ACID VALVE TO CHARGING PUMPS ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	HV-8184	B	VALVE	NMS	7.2.03-E	D2 80E	1288
Z08728	--	BURIC ACID VALVE TO CHARGING PUMPS ALM ON CONTACTS	CLSD	ALM/NML	NOT CLOSED / CLOSED	HV-8184	B	VALVE	NMS	7.2.03-E	D2 80E	1288
Z08751	--	FMS PUST ACCIDENT FLTR IMN A INL DAMPER ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	AMV-12518	B	VALVE	I	7.2.11-A	D2 RPU A1	1542
Z08752	--	FMS PUST ACCIDENT FLTR IMN A OUT DAMPER ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	AMV-12512	B	VALVE	I	7.2.11-A	D2 RPU A1	1542
Z08753	--	FMS PUST ACCIDENT FLTR IMN B INL DAMPER ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	AMV-12511	B	VALVE	II	7.2.11-A	D2 RPU B1	1542
Z08754	--	FMS PUST ACCIDENT FLTR IMN B OUT DAMPER ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	AMV-12513	B	VALVE	II	7.2.11-A	D2 RPU B1	1542
Z08761	--	PIPING PEN RM FLTR-EXM IMN A INLET ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	HV-12614	B	VALVE	I	7.2.11-A	D2 RPU A1	1561
Z08765	--	PIPING PER RM FLTR-EXM IMN B INLET ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	HV-12616	B	VALVE	II	7.2.11-A	D2 RPU B1	1561
Z08771	--	CNTL BLDG CNTL RM FLTR IMN A INL DAMPER ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	HV-12118	B	VALVE	I	7.2.11-A	D2 RPU A1	1531
Z08773	--	CNTL BLDG CNTL RM FLTR IMN A OUT DAMPER ALM ON CONTACTS	CLSD	ALM/NML	UPEN / NOT UPEN	HV-12128	B	VALVE	I	7.2.11-A	D2 RPU A1	1531

H
 E
 Y
 PROTEUS
 SYMBOL
 SIGNAL DESCRIPTION
 ORIGINATING DEVICE
 SIGNAL SOURCE CLASS
 NO. 1-97 INPUT
 VHM CLASS VIA SYSTEM 3

PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	NO. 1-97 INPUT	VHM CLASS VIA SYSTEM 3
Z08775	-- CNIL BLDG CMTL RM FLTR INH B INL DAMPER ALM ON CONTACTS CLSD ALM/NML: UPEN / NOT UPEN	MY-12119	B VALVE II 2436 E/01-85-CW1Z	7.2.11-A 02 RPU B1 1531	
Z08777	-- CNIL BLDG CMTL RM FLTR INH B OUT DAMPER ALM ON CONTACTS CLSD ALM/NML: UPEN / NOT UPEN	MY-12129	B VALVE II 2434 E/01-85-CW1Z	7.2.11-A 02 RPU B1 1531	
Z08779	-- CNIL BLDG RTN AIR FAN INH A INL DAMPER ALM ON CONTACTS CLSD ALM/NML: UPEN / NOT UPEN	MY-12138	B VALVE I 2626 E/01-85-CW1X	7.2.11-A 02 RPU A1 1531	
Z08781	-- CNIL BLDG RTN AIR FAN INH B INL DAMPER ALM ON CONTACTS CLSD ALM/NML: UPEN / NOT UPEN	MY-12131	B VALVE II 2627 E/01-85-CW1Z	7.2.11-A 02 RPU B1 1531	
Z08784	-- ELEC PEN RM FLTR INH A INL ISOL DAMPER ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	MY-2636A	B VALVE I 2634 E/01-85-UM1P	7.2.11-A 02 RPU A1 1562 (UNIT 1 INPUT ONLY)	
Z08786	-- ELEC PEN RM FLTR INH A OUT ISOL DAMPER ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	MY-2636A	B VALVE I 2635 E/01-85-UM1P	7.2.11-A 02 RPU A1 1562 (UNIT 1 INPUT ONLY)	
Z08788	-- ELEC PEN RM FLTR INH B INL ISOL DAMPER ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	MY-2636B	B VALVE II 2636 E/01-85-UM1P	7.2.11-A 02 RPU B1 1562 (UNIT 1 INPUT ONLY)	
Z08790	-- ELEC PEN RM FLTR INH B OUT ISOL DAMPER ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	MY-2636B	B VALVE II 2637 E/01-85-UM1P	7.2.11-A 02 RPU B1 1562 (UNIT 1 INPUT ONLY)	
Z08791	-- ELEC PEN RM FLTR TRP A INL DAMPER ALM ON CONTACTS CLSD ALM/NML: UPEN / NOT UPEN	MY-12563	B VALVE I 2638 E/01-85-DM6A	7.2.11-A 02 RPU A1 1562 (UNIT 1 INPUT ONLY)	
Z08793	-- ELEC PEN RM FLTR INH A OUT DAMPER ALM ON CONTACTS CLSD ALM/NML: UPEN / NOT UPEN	MY-12561	B VALVE I 2979 E/01-85-DM6J	7.2.11-A 02 RPU A1 1562 (UNIT 1 INPUT ONLY)	
Z08794	-- ELEC PEN RM FLTR INH A OUT DAMPER ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	MY-12561	B VALVE I 3063 E/01-85-DM6J	7.2.11-A 02 RPU A1 1562 (UNIT 1 INPUT ONLY)	
Z08795	-- ELEC PEN RM FLTR INH A VENT DAMPER ALM ON CONTACTS CLSD ALM/NML: UPEN / NOT UPEN	MY-12565	B VALVE I 2981 E/01-85-DM6J	7.2.11-A 02 RPU A1 1562 (UNIT 1 INPUT ONLY)	

M ERF PROTEUS B SIGNAL SIGNAL RV 1.07 INPUT B
 V SYMBOL SYMBOL Y SOURCE CLASS VAR CLASS VIA SYSTEM D
 3

ALM ON CONTACTS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL CLASS	SIGNAL CLASS	VAR CLASS	VIA SYSTEM
008796	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	3885	E/01-85-086J	VALVE I	7.2.11-A D2 RPU A1 1562	(UNIT 1 INPUT ONLY)
008797	ALM ON CONTACTS CLOSED ALM/NML: OPEN / NOT OPEN	2641	E/01-85-086A	VALVE II	7.2.11-A D2 RPU B1 1562	(UNIT 1 INPUT ONLY)
008798	ALM ON CONTACTS CLOSED ALM/NML: OPEN / NOT OPEN	2988	E/01-85-086K	VALVE II	7.2.11-A D2 RPU B1 1562	(UNIT 1 INPUT ONLY)
008800	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	3884	E/01-85-086K	VALVE II	7.2.11-A D2 RPU B1 1562	(UNIT 1 INPUT ONLY)
008801	ALM ON CONTACTS CLOSED ALM/NML: OPEN / NOT OPEN	2982	E/01-85-086N	VALVE II	7.2.11-A D2 RPU B1 1562	(UNIT 1 INPUT ONLY)
008802	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	3886	E/01-85-086N	VALVE II	7.2.11-A D2 RPU B1 1562	(UNIT 1 INPUT ONLY)
008812	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	2824	E/01-8C-084A	VALVE MNS	--	30E 1411
008814	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	2826	E/01-8C-084A	VALVE MNS	--	30E 1411
008816	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	2828	E/01-8C-084A	VALVE MNS	--	30E 1411
008818	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	2838	E/01-8C-084A	VALVE MNS	--	30E 1411
008820	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	2832	E/01-8C-087E	VALVE II	7.2.04-L D2 RPU A1 1311	
008822	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	2834	E/01-8C-087E	VALVE II	7.2.04-L D2 RPU B1 1311	

Y	ERP SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	ORIGINATING DEVICE	B	SIGNAL SOURCE	VALVE	I	7.2.04-L	D2	RPU	01	1311	B	P
	Z09024	--	STEAM GEN 3 BLOWDOWN SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9453	B	VALVE	I	7.2.04-L	D2	RPU	01	1311			
	Z09026	--	STEAM GEN 4 BLOWDOWN SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9454	B	VALVE	I	7.2.04-L	D2	RPU	A1	1311			
	Z09028	--	STEAM GEN 1 SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9553A	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09030	--	STEAM GEN 1 BLOWDOWN LINE SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9553B	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09032	--	STEAM GEN 2 SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9554A	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09034	--	STEAM GEN 2 BLOWDOWN LINE SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9554B	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09036	--	STEAM GEN 3 SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9555A	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09038	--	STEAM GEN 3 BLOWDOWN LINE SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9555B	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09040	--	STEAM GEN 4 SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9556A	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09042	--	STEAM GEN 4 BLOWDOWN LINE SAMPLE	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-9556B	B	VALVE	NMS	--	--	--	--	80E	1311		
	Z09044	--	CONTAINMENT AIR RAD MONITOR INL TRN A	ALM UN CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-12970	B	VALVE	I	6.2.03-D	C2	RPU	A1	1609	X		
	Z09046	--	CONTAINMENT AIR RAD MONITOR INL TRN B	ALM ON CONTACTS	UPEN	ALM/NMLT	NOT CLOSED	MY-12976	B	VALVE	II	6.2.03-D	C2	RPU	B1	1609	X		

R E V
 ENF PROTEUS B
 SYMBOL SIGNAL DESCRIPTION ORIGINATING DEVICE Y SIGNAL CLASS VAR CLASS VIA SYSTEM B P D

Z09848	--	CONTAINMENT AIR RAD MONITOR OUT TRN B	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-12977	B	VALVE	II	6.2.03-D	C2	RPU	01	609	X
Z09850	--	CONTAINMENT AIR RAD MONITOR OUT TRN A	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-12978	B	VALVE	I	6.2.03-D	C2	RPU	A1	1089	X
Z09852	--	STM GEN 1 MET LAYUP CHEM ADDITION	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-5194	B	VALVE	NNS	--	--	--	80E	1305	
Z09854	--	STM GEN 2 MET LAYUP CHEM ADDITION	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-5195	B	VALVE	NNS	--	--	--	80E	1305	
Z09856	--	STM GEN 3 MET LAYUP CHEM ADDITION	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-5196	B	VALVE	NNS	--	--	--	80E	1305	
Z09858	--	STM GEN 4 MET LAYUP CHEM ADDITION	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-5197	B	VALVE	NNS	--	--	--	30E	1305	
Z09860	--	RCS HOT LEG SAMPLE LINE LOOP 1 TRN A	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-3992	B	VALVE	I	6.2.03-D	C2	RPU	A1	1212	X
Z09862	--	RCS HOT LEG SAMPLE LINE LOOP 3 TRN B	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-3549	B	VALVE	II	6.2.03-D	C2	RPU	01	1212	X
Z09874	--	SAFETY INJECTION PUMPS RECIRC TEST	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-8823	B	VALVE	II	6.2.03-D	C2	RPU	01	1284	X
Z09875	--	SI PUMP B TO HOT LEGS 2&3	ALM ON CONTACTS	OPEN	ALM/NMLI UPEN	/	NOT OPEN	HY-8828	B	VALVE	II	7.2.05-E	D2	RPU	01	1284	
Z09876	--	SI PUMP B TO HOT LEGS 2&3	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-8828	B	VALVE	II	7.2.05-E	D2	RPU	01	1284	
Z09878	--	SI RECIRC TEST TRIN B	ALM ON CONTACTS	OPEN	ALM/NMLI NOT CLOSED	/	CLOSED	HY-8824	B	VALVE	II	6.2.03-D	C2	RPU	01	1284	X

S
P

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	CLASS	VAR CLASS	INPUT SYSTEM
Z09879	--	BORON INJECTION TANK DISCH TRAIN A ALM ON CONTACTS CLSD ALM/NMLT UPEN / NOT OPEN	HY-8881A 2929	VALVE I E/01-80-0W2E	I	7.2.05-E 02 RPU A1	1284
Z09880	--	BORON INJECTION TANK DISCH TRAIN A ALM ON CONTACTS UPEN ALM/NMLT NOT CLOSED / CLOSED	HY-8881A 2953	VALVE I E/01-80-0W2E	I	7.2.05-E 02 RPU A1	1284
Z09881	--	BORON INJECTION TANK DISCH TRAIN B ALM ON CONTACTS CLSD ALM/NMLT UPEN / NOT OPEN	HY-8881B 2927	VALVE II E/01-80-0W2F	II	7.2.05-E 02 RPU B1	1284
Z09882	--	BORON INJECTION TANK DISCH TRAIN B ALM ON CONTACTS UPEN ALM/NMLT NOT CLOSED / CLOSED	HY-8881B 2951	VALVE II E/01-80-0W2F	II	7.2.05-E 02 RPU B1	1284
Z09884	--	S18 TEST LINE BYPASS ALM ON CONTACTS UPEN ALM/NMLT NOT CLOSED / CLOSED	HY-8882 2896	VALVE II E/01-80-0W4T	II	6.2.03-D 02 RPU B1	1284 X
Z09885	--	S1 PUMP A TO HOT LEGS 1&4 ALM ON CONTACTS UPEN ALM/NMLT UPEN / NOT OPEN	HY-8882A 3127	VALVE I E/01-80-0W2G	I	7.2.05-E 02 RPU A1	1284
Z09886	--	S1 PUMP A TO HOT LEGS 1&4 ALM ON CONTACTS UPEN ALM/NMLT NOT CLOSED / CLOSED	HY-8882A 3151	VALVE I E/01-80-0W2G	I	7.2.05-E 02 RPU A1	1284
Z09888	--	S1 PUMP ACCUM FILL ALM ON CONTACTS UPEN ALM/NMLT NOT CLOSED / CLOSED	HY-8881 2894	VALVE II E/01-80-0W4T	II	6.2.03-D 02 RPU B1	1284 X
Z09889	--	RMR PUMP A CNMT SUMP SUCTION ISOL VALVE ALM ON CONTACTS UPEN ALM/NMLT UPEN / NOT OPEN	HY-8811A 2833	VALVE I E/01-80-E03F	I	7.2.16-B 02 RPU A1	1286
Z09890	--	RMR PUMP A CNMT SUMP SUCTION ISOL VALVE ALM ON CONTACTS CLSD ALM/NMLT NOT CLSD / CLSD	HY-8811A 2857	VALVE I E/01-80-E03F	I	7.2.16-B 02 RPU A1	1286
Z09891	--	RMR PUMP B CNMT SUMP SUCTION ISOL VALVE ALM ON CONTACTS UPEN ALM/NMLT UPEN / NOT OPEN	HY-8811B 2835	VALVE II E/01-80-E03G	II	7.2.16-B 02 RPU B1	1286
Z09892	--	RMR PUMP B CNMT SUMP SUCTION ISOL VALVE ALM ON CONTACTS CLSD ALM/NMLT NOT CLSD / CLSD	HY-8811B 2859	VALVE II E/01-80-E03G	II	7.2.16-B 02 RPU B1	1286

M E V	SYMBO L	PHUT EJUS	SIGNAL DESCRIPTION	ORIGINA TING DEVICE	SIGNAL CLASS	SIGNAL SOURCE	CLASS	NO	VALVE	NO	CLASS	NO	VALVE	NO	CLASS	NO	VALVE	NO	CLASS
	Z09102	--	ALM ON CONTACTS	OPEN	ALM/NML	NOT CLOSED	/	CLOSED	2896	E/01-80-FW1M	0.2.03-D	C2	RPV	B1	1204	X			
	Z09104	--	ALM ON CONTACTS	OPEN	ALM/NML	NOT CLOSED	/	CLOSED	2898	E/01-80-063K	6.2.03-D	C2	RPV	B1	1204	X			
	Z09106	--	ALM ON CONTACTS	OPEN	ALM/NML	NOT CLOSED	/	CLOSED	2100	E/01-80-064G	6.2.03-D	C2	RPV	B1	1204	X			
	Z09108	--	ALM ON CONTACTS	OPEN	ALM/NML	NOT CLOSED	/	CLOSED	2102	E/01-80-064B	6.2.03-D	C2	RPV	B1	1204	X			
	Z09110	--	ALM ON CONTACTS	OPEN	ALM/NML	NOT CLOSED	/	CLOSED	2104	E/01-80-063J	6.2.03-D	C2	RPV	B1	1204	X			
	Z09112	--	ALM ON CONTACTS	CLSD	ALM/NML	CLOSED	/	NOT CLOSED	2106	E/01-80-K64L	7.2.09-B	D2	RPV	B1	1202				
	Z09114	--	ALM ON CONTACTS	CLSD	ALM/NML	CLOSED	/	NOT CLOSED	2226	E/01-80-K64G	7.2.09-B	D2	RPV	B1	1202				
	Z09116	--	ALM ON CONTACTS	CLSD	ALM/NML	CLSD	/	NOT CLSD	2108	E/01-80-K64M	7.2.09-B	D2	RPV	B1	1202				
	Z09118	--	ALM ON CONTACTS	CLSD	ALM/NML	CLSD	/	NOT CLSD	2110	E/01-80-K64N	7.2.09-B	D2	RPV	B1	1202				
	Z09137	--	ALM ON CONTACTS	OPEN	ALM/NML	OPEN	/	NOT OPEN	3125	E/01-80-063J	7.2.10-B	D2	RPV	B1	1204				
	Z09138	--	ALM ON CONTACTS	OPEN	ALM/NML	NOT CLOSED	/	CLOSED	3129	E/01-80-063J	7.2.10-B	D2	RPV	B1	1204				
	Z09140	--	ALM ON CONTACTS	OPEN	ALM/NML	NOT CLOSED	/	CLOSED	2235	E/01-80-064I	6.2.03-D	C2	RPV	B1	1204	X			

S
P
D
B

R	E	Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	HG 1.97 VARI CLASS	INPUT VIA	SYSTEM	B P U S
			Z09146	--	BIS RECIRC TEST COLD LEG LOOPS 1 & 2 ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8899A	B	VALVE	II	6.2.03-D C2 RPU 01 1204		X	
			Z09148	--	BIS RECIRC TEST COLD LEG LOOPS 3 & 4 ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8899B	B	VALVE	II	6.2.03-D C2 RPU 01 1204		X	
			Z09150	--	PRESSURIZER RELIEF TANK VENT TRAIN A ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8847	B	VALVE	I	6.2.03-D C2 RPU A1 1201		X	
			Z09152	--	PRESSURIZER RELIEF TANK VENT TRAIN B ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8833	B	VALVE	II	6.2.03-D C2 RPU 01 1201		X	
			Z09154	--	PRESSURIZER RELIEF TANK PHM WATER ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8828	B	VALVE	II	6.2.03-D C2 RPU 01 1201		X	
			Z09156	--	PRESSURIZER STEAM SPACE SAMPLE TRN A ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-3514	B	VALVE	I	6.2.03-D C2 RPU A1 1212		X	
			Z09158	--	PRESSURIZER STEAM SPACE SAMPLE TRN B ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-3513	B	VALVE	II	6.2.03-D C2 RPU 01 1212		X	
			Z09160	--	PRESSURIZER LIQUID SPACE SAMPLE TRN A ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-3508	B	VALVE	I	6.2.03-D C2 RPU A1 1212		X	
			Z09162	--	PRESSURIZER LIQUID SPACE SAMPLE TRN B ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-3507	B	VALVE	II	6.2.03-D C2 RPU 01 1212		X	
			Z09164	--	CNMT H2 TRAIN B MONITOR SUPPLY IRC ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2791A	B	VALVE	I	-- - RPU A1 1513			
			Z09166	--	CNMT H2 TRAIN A MONITOR SUPPLY IRC ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2792A	B	VALVE	I	-- - RPU A1 1513			
			Z09168	--	CNMT H2 TRAIN A MONITOR SUPPLY IRC ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2792B	B	VALVE	I	-- - RPU A1 1513			

R	E	ERF SYMBOL	PHOTIUS	SIGNAL DESCRIPTION	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	VALVE I	VALVE II	SIGNAL CLASS	HG 1.97 INPUT	YAH CLASS VIA SYSTEM	B	P
		Z09170	--	CNMT H2 TRAIN B MONITOR RETURN	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	136	E/01-85-003E					
		Z09172	--	CNMT H2 TRAIN B MONITOR SUPPLY	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	IRC	2138	E/01-85-0058					
		Z09174	--	CNMT H2 TRAIN B MONITOR SUPPLY	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	IRC	2148	E/01-85-0058					
		Z09176	--	CNMT H2 TRAIN A MONITOR SUPPLY	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	2142	E/01-85-0058					
		Z09178	--	CNMT H2 TRAIN A MONITOR RETURN	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	2144	E/01-85-0058					
		Z09180	--	ACCUMULATOR TANK 1 SAMPLE	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	2145	E/01-80-004M		6.2.03-D C2	RPU A1 1204		X
		Z09182	--	ACCUMULATOR TANK 2 SAMPLE	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	2148	E/01-80-004X		6.2.03-D C2	RPU B1 1204		X
		Z09184	--	ACCUMULATOR TANK 3 SAMPLE	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	2158	E/01-80-004M		6.2.03-D C2	RPU A1 1204		X
		Z09186	--	ACCUMULATOR TANK 4 SAMPLE	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	ORC	2152	E/01-80-004X		6.2.03-D C2	RPU B1 1204		X
		Z09188	--	RC DRAIN TANK ISOLATION VLV	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	TRN A	2154	E/01-80-002M		6.2.03-D C2	RPU A1 1001		X
		Z09190	--	RC DRAIN TANK PUMPS DISCH	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	TRN B	2156	E/01-80-002C		6.2.03-D C2	RPU B1 1001		X
		Z09192	--	MEACT CVTY/CNMT SUMP DRAIN	ALM ON CONTACT	OPEN	ALM/NML	NOT CLOSED	PMP HDN TRN A	2158	E/01-80-001E		6.2.03-D C2	RPU A1 1214		X

Y	ERF SYMBOL	PHUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAK CLASS	INPUT VIA	SYSTEM	B P D B
Z09194	--	HEACT CVTY/CNMT SUMP DRAIN PMP HDR TRN B	ALM ON CONTACTS OPEN ALM/NML: NOT CLSD / CLSD	HV-0781	B	VALVE	II	6.2.03-D C2 RPU B1	1214	X	
Z09196	--	MC DRAIN TANK VENT TRAIN A	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-7126	B	VALVE	I	6.2.03-D C2 RPU A1	1981	X	
Z09198	--	MC DRAIN TANK VENT TRAIN B	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-7158	B	VALVE	II	6.2.03-D C2 RPU B1	1981	X	
Z09200	--	CONTAINMENT SERVICE AIR	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-9385	B	VALVE	I	6.2.03-D C2 RPU A1	2481	X	
Z09202	--	CONTAINMENT INSTRUMENT AIR ISOLATION VLV	ALM ON CONTACTS OPEN ALM/NML: NOT CLSD / CLSD	HV-9378	B	VALVE	II	6.2.03-D C2 RPU b1	2420	X	
Z09204	--	CNMT PREACCESS PURGE SUPPLY TRN A	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2626A	B	VALVE	I	6.2.03-D C2 RPU A1	1505	X	
Z09206	--	CONTAINMENT MINI PURGE SUPPLY TRN A	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2626B	B	VALVE	I	6.2.03-D C2 RPU A1	1505	X	
Z09208	--	CNMT PREACCESS PURGE SUPPLY TRN B	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2627A	B	VALVE	II	6.2.03-D C2 RPU B1	1505	X	
Z09210	--	CONTAINMENT MINI PURGE SUPPLY TRN B	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2627B	B	VALVE	II	6.2.03-D C2 RPU B1	1505	X	
Z09212	--	CONTAINMENT PREACCESS PURGE EXH TRN A	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2628A	B	VALVE	I	6.2.03-D C2 RPU A1	1506	X	
Z09214	--	CONTAINMENT MINI PURGE EXH TRN A	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2628B	B	VALVE	I	6.2.03-D C2 RPU A1	1506	X	
Z09216	--	CONTAINMENT PREACCESS PURGE EXH TRN B	ALM ON CONTACTS OPEN ALM/NML: NOT CLOSED / CLOSED	HV-2629A	B	VALVE	II	6.2.03-D C2 RPU B1	1506	X	

R E V	PHUIEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE	SIGNAL CLASS	HW VAM	IMP. CLASS	VI. SYSTEM	S P D S
Z09244	-- ALM ON CONTACT	PASS GAS SAMPLE RETURN TRAIN B OPEN / CLOSED	RV-0211	VALVE E/01-8H-Y020	II	6.2.03-0	C2 RPU 01	2702	X
Z09245	-- ALM ON CONTACT	PASS CONTAINMENT SAMPLE PUMPS TRAIN A OPEN / CLOSED	RV-0906A	VALVE E/01-8U-102L	I	--	- RPU A1	2702	X
Z09246	-- ALM UN CONTACT	PASS CONTAINMENT SAMPLE PUMPS TRAIN B OPEN / CLOSED	RV-0906B	VALVE E/01-8U-102M	II	--	- RPU 01	2702	X
Z09250	-- ALM ON CONTACT	PASS LIQUID SAMPLE RETURN TRAIN A OPEN / CLOSED	RV-0200	VALVE E/01-8H-Y02C	I	6.2.03-0	C2 RPU A1	2702	X
Z09252	-- ALM UN CONTACT	PASS LIQUID SAMPLE RETURN TRAIN B OPEN / CLOSED	RV-0200	VALVE E/01-8H-Y02D	II	6.2.03-0	C2 RPU 01	2702	X
Z09262	-- ALM ON CONTACT	PRESSURIZER SAFETY VALVE A TRAIN A CLOSED / NOT OPEN	PSV-0010A	VALVE E/01-8U-003J	I	7.2.02-0	02 RPU A1	1201	
Z09263	-- ALM ON CONTACT	PRESSURIZER SAFETY VALVE A TRAIN A OPEN / CLOSED	PSV-0010A	VALVE E/01-8U-003J	I	7.2.02-0	02 RPU A1	1201	
Z09264	-- ALM ON CONTACT	PRESSURIZER SAFETY VALVE B TRAIN A CLOSED / NOT OPEN	PSV-0010B	VALVE E/01-8U-003J	I	7.2.02-0	02 RPU A1	1201	
Z09265	-- ALM ON CONTACT	PRESSURIZER SAFETY VALVE B TRAIN A OPEN / CLOSED	PSV-0010B	VALVE E/01-8U-003J	I	7.2.02-0	02 RPU A1	1201	
Z09266	-- ALM ON CONTACT	PRESSURIZER SAFETY VALVE C TRAIN A CLOSED / NOT OPEN	PSV-0010C	VALVE E/01-8U-003J	I	7.2.02-0	02 RPU A1	1201	
Z09267	-- ALM ON CONTACT	PRESSURIZER SAFETY VALVE C TRAIN A OPEN / CLOSED	PSV-0010C	VALVE E/01-8U-003J	I	7.2.02-0	02 RPU A1	1201	
Z09272	-- ALM UN CONTACT	PRESSURIZER SAFETY VALVE A TRAIN B CLOSED / NOT OPEN	PSV-0010A	VALVE E/01-8U-003J	II	7.2.02-0	02 RPU 01	1201	

R ENF PROTEUS UNIGINATING B SIGNAL SIGNAL H6 1.97 INPUT B
 V SYMBOL SYMBOL SIGNAL DESCRIPTION DEVICE Y SOURCE CLASS PAR CLASS VIA SYSTEM B

Z09273	--	PRESSURIZER SAFETY VALVE A TRAIN B	PSV-0010A	B	VALVE II	7.2.02-B 02 RPU B1 1201	B
	ALM ON CONTACTS	OPEN ALM/NML; NOT CLOSED / CLOSED	2239	E/01-80-003J			P
Z09274	--	PRESSURIZER SAFETY VALVE B TRAIN B	PSV-0010B	B	VALVE II	7.2.02-B 02 RPU B1 1201	D
	ALM ON CONTACTS	CLOS ALM/NML; OPEN / NOT OPEN	2310	E/01-80-003J			B
Z09275	--	PRESSURIZER SAFETY VALVE C TRAIN B	PSV-0010C	B	VALVE II	7.2.02-B 02 RPU B1 1201	
	ALM ON CONTACTS	OPEN ALM/NML; NOT CLOSED / CLOSED	2311	E/01-80-003J			
Z09276	--	PRESSURIZER SAFETY VALVE C TRAIN B	PSV-0010C	B	VALVE II	7.2.02-B 02 RPU B1 1201	
	ALM ON CONTACTS	CLOS ALM/NML; OPEN / NOT OPEN	2430	E/01-80-003J			
Z09277	--	PRESSURIZER SAFETY VALVE C TRAIN B	PSV-0010C	B	VALVE II	7.2.02-B 02 RPU B1 1201	
	ALM ON CONTACTS	OPEN ALM/NML; NOT CLOSED / CLOSED	2431	E/01-80-003J			
Z09282	--	CYCS LETDOWN ISOLATION	MV-0100	B	VALVE I	6.2.03-D 02 RPU A1 1200	X
	ALM ON CONTACTS	OPEN ALM/NML; NOT CLOSED / CLOSED	2312	E/01-80-C04A			
Z09284	--	CYCS LETDOWN ISOLATION OUTSIDE CMPT	MV-0102	B	VALVE II	6.2.03-D 02 RPU B1 1200	X
	ALM ON CONTACTS	OPEN ALM/NML; NOT CLOSED / CLOSED	2314	E/01-80-C03J			
Z09289	--	SEAL FLOW CONTROL-THRUSTLES CHG FLOW	MV-0102	B	VALVE NNS	-- -- 30E 1200	
	ALM ON CONTACTS	OPEN ALM/NML; NOT OPEN / OPEN	2030				
Z09290	--	SEAL FLOW CONTROL-THRUSTLES CHG FLOW	MV-0102	B	VALVE NNS	-- -- 30E 1200	
	ALM ON CONTACTS	OPEN ALM/NML; CLOSED / NOT CLOSED	2062				
Z09291	--	CCP A MINIFLOW VALVE TO VCI	MV-0111A	B	VALVE II	7.2.03-E 02 RPU B1 1200	
	ALM ON CONTACTS	OPEN ALM/NML; NOT OPEN / OPEN	2006	E/01-80-C03K			
Z09292	--	CCP A MINIFLOW VALVE TO VCI	MV-0111A	B	VALVE II	7.2.03-E 02 RPU B1 1200	
	ALM ON CONTACTS	OPEN ALM/NML; CLOSED / NOT CLOSED	2910	E/01-80-C03K			
Z09293	--	CCP B MINIFLOW VALVE TO VCI	MV-0111B	B	VALVE II	7.2.03-E 02 RPU B1 1200	
	ALM ON CONTACTS	OPEN ALM/NML; NOT OPEN / OPEN	2935	E/01-80-C05L			

R LRF PROTEUS
 C SYMBOL SIGNAL DESCRIPTION
 V SYMBOL

PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	SIGNAL	MG 1.07 INPUT	VAR CLASS	VIA SYSTEM
Z09294	-- CCP B MINIFLOW VALVE TO VCI ALM ON CONTACTS OPEN ALM/NMLI CLOSED / NOT CLOSED	HY-8111B	B	VALVE II E/01-80-C85L	7.2.03-E 02 RPU 01 1200		B
Z09295	-- CCP COMMON MINIFLOW VALVE TO VCI ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	HY-8111B	B	VALVE I E/01-80-C83J	7.2.03-E 02 RPU A1 1200		P
Z09296	-- CCP COMMON MINIFLOW VALVE TO VCI ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	HY-8111B	B	VALVE I E/01-80-C83J	7.2.03-E 02 RPU A1 1200		D
Z09298	-- REACTOR HEAD VENT LINE TRAIN A ALM ON CONTACTS OPEN ALM/NMLI NOT CLOSED / CLOSED	HY-8095A	B	VALVE I E/01-80-C856	7.2.05-E 02 RPU A1 1200		B
Z09300	-- REACTOR HEAD VENT LINE TRAIN B ALM ON CONTACTS OPEN ALM/NMLI NOT CLOSED / CLOSED	HY-8095B	B	VALVE II E/01-80-C85F	7.2.05-E 02 RPU -- 1200		P
Z09302	-- REACTOR HEAD VENT LINE TRAIN A ALM ON CONTACTS OPEN ALM/NMLI NOT CLOSED / CLOSED	HY-8096A	B	VALVE I E/01-80-C856	7.2.05-E 02 RPU A1 1200		D
Z09304	-- REACTOR HEAD VENT LINE TRAIN B ALM ON CONTACTS OPEN ALM/NMLI NOT CLOSED / CLOSED	HY-8096B	B	VALVE II E/01-80-C85F	7.2.05-E 02 RPU 01 1200		B
Z09305	-- RCP 1 SEAL WATER INLET ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	HY-8103A	B	VALVE II E/01-80-C84L	7.2.03-E 02 RPU 01 1200		P
Z09306	-- RCP 1 SEAL WATER INLET ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	HY-8103A	B	VALVE II E/01-80-C84L	7.2.03-E 02 RPU 01 1200		D
Z09307	-- RCP 2 SEAL WATER INLET ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	HY-8103B	B	VALVE II E/01-80-C84M	7.2.03-E 02 RPU 01 1200		B
Z09308	-- RCP 2 SEAL WATER INLET ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	HY-8103B	B	VALVE II E/01-80-C84M	7.2.03-E 02 RPU 01 1200		P
Z09309	-- RCP 3 SEAL WATER INLET ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	HY-8103C	B	VALVE II E/01-80-C84J	7.2.03-E 02 RPU 01 1200		D

R	EMP SYMBOL	PHOTOLUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SIGNAL SOURCE CLASS	HW 1.97 INPUT VAR CLASS	SYSTEM
	Z09310	-- MCP 3 SEAL WATER INLET ALM ON CONTACTS CLSD	ALM/NML: CLOSED / NOT CLOSED	HY-8183C 3088	VALVE II E/01-80-C042	7.2.03-E 02 RPU 01 1200	B
	Z09311	-- MCP 4 SEAL WATER INLET ALM ON CONTACTS OPEN	ALM/NML: NOT OPEN / OPEN	HY-8183D 3120	VALVE II E/01-80-C040	7.2.03-E 02 RPU 01 1200	B
	Z09312	-- RCP 4 SEAL WATER INLET ALM ON CONTACTS CLSD	ALM/NML: CLOSED / NOT CLOSED	HY-8183D 3144	VALVE II E/01-80-C040	7.2.03-E 02 RPU 01 1200	B
	Z09314	-- MCP 1 SEAL LEAK ISOLATION ALM ON CONTACTS CLSD	ALM/NML: CLOSED / NOT CLOSED	HY-8141A 2344	VALVE NMS E/01-80-C03M	-- - 50E 1200	B
	Z09316	-- MCP 2 SEAL LEAK ISOLATION ALM ON CONTACTS CLSD	ALM/NML: CLOSED / NOT CLOSED	HY-8141B 2346	VALVE NMS E/01-80-C03M	-- - 50E 1200	B
	Z09318	-- MCP 3 SEAL LEAK ISOLATION ALM ON CONTACTS CLSD	ALM/NML: CLOSED / NOT CLOSED	HY-8141C 2348	VALVE NMS E/01-80-C03M	-- - 50E 1200	B
	Z09320	-- MCP 4 SEAL LEAK ISOLATION ALM ON CONTACTS CLSD	ALM/NML: CLOSED / NOT CLOSED	HY-8141D 2350	VALVE NMS E/01-80-C03M	-- - 50E 1200	B
	Z09322	-- MCP SEAL WATER ISOLATION THAIN A ALM ON CONTACTS OPEN	ALM/NML: NOT CLOSED / CLOSED	HY-8112 2352	VALVE I E/01-80-C03L	6.2.03-0 C2 RPU A1 1200 X	X
	Z09324	-- RCP SEAL WATER ISOLATION THAIN B ALM ON CONTACTS OPEN	ALM/NML: CLOSED / CLOSED	HY-8108 2354	VALVE II E/01-80-C03D	6.2.03-0 C2 RPU 01 1200 X	X
	Z09325	-- CHARGING PUMPS DISCHARGE XCONN ALM ON CONTACTS OPEN	ALM/NML: NOT OPEN / OPEN	HY-8438 2932	VALVE II E/01-80-C05P	7.2.03-E 02 RPU 01 1200	B
	Z09326	-- CHARGING PUMPS DISCHARGE XCONN ALM ON CONTACTS OPEN	ALM/NML: CLOSED / NOT CLOSED	HY-8438 2956	VALVE II E/01-80-C05P	7.2.03-E 02 RPU 01 1200	B
	Z09327	-- MURIC ACID TO CHARGING PUMP B ALM ON CONTACTS CLSD	ALM/NML: OPEN / NOT OPEN	HY-8439 2931	VALVE II E/01-80-C050	7.2.03-E 02 RPU 01 1200	B

H
E
V

EMF SYMBOL	PHOTUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL CLASS	SIGNAL	REG	INPUT
Z09326	--	MIC ACID TO CHARGING PUMP B ALM ON CONTACTS OPEN ALM/NML NOT CLOSED / CLOSED	MV-8839	2955	VALVE II E/D1-80-CW59	7.2.83-E	D2 RPU 01 1288
Z09329	--	CHARGING PUMP SUCTI HDR TU/FRUM SIS PMP A ALM ON CONTACTS OPEN ALM/NML NOT OPEN / OPEN	MV-8924	2776	VALVE I E/D1-80-CW4V	7.2.85-E	D2 RPU A1 1288
Z09338	--	CHARGING PUMP SUCTI HDR TU/FRUM SIS PMP A ALM ON CONTACTS OPEN ALM/NML CLSD / NOT CLSD	MV-8924	2898	VALVE I E/D1-80-CW4V	7.2.85-E	D2 RPU A1 1288
Z09335	--	SG1 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS CLSD ALM/NML OPEN / NOT OPEN	FV-8518	3821	VALVE NNS E/D1-8C-CW4H	7.2.84-E	D2 SOE 1385
Z09336	--	SG1 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS OPEN ALM/NML NOT CLOSED / CLOSED	FV-8518	3845	VALVE NNS E/D1-8C-CW4H	7.2.84-E	D2 SOE 1385
Z09337	--	SG2 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS CLSD ALM/NML OPEN / NOT OPEN	FV-8528	3828	VALVE NNS E/D1-8C-CW4E	7.2.84-E	D2 SOE 1385
Z09339	--	SG2 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS OPEN ALM/NML NOT CLOSED / CLOSED	FV-8528	3844	VALVE NNS E/D1-8C-CW4E	7.2.84-E	D2 SOE 1385
Z09339	--	SG3 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS CLSD ALM/NML OPEN / NOT OPEN	FV-8538	3819	VALVE NNS E/D1-8C-CW4F	7.2.84-E	D2 SOE 1385
Z09340	--	SG3 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS OPEN ALM/NML NOT CLOSED / CLOSED	FV-8538	3843	VALVE NNS E/D1-8C-CW4F	7.2.84-E	D2 SOE 1385
Z09341	--	SG4 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS CLSD ALM/NML OPEN / NOT OPEN	FV-8548	3818	VALVE NNS E/D1-8C-CW4G	7.2.84-E	D2 SOE 1385
Z09342	--	SG4 MAIN FEED REG VALVE - MFRV ALM ON CONTACTS OPEN ALM/NML NOT CLOSED / CLOSED	FV-8548	3842	VALVE NNS E/D1-8C-CW4G	7.2.84-E	D2 SOE 1385
Z09343	--	SG1 BYPASS FEED REG VALVE - BFRV ALM ON CONTACTS CLSD ALM/NML OPEN / NOT OPEN	LV-5243	2975	VALVE NNS E/D1-8C-CW4K	7.2.84-E	D2 SOE 1385

B
P
D
VAN CLASS VIA SYSTEM 9

R E V	SYMBOL	PHUTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B	SIGNAL SOURCE	SIGNAL CLASS	RG	DATE	INPUT	SYSTEM
Z09344	--	3G1 BYPASS FEED NEG VALVE - BFRV	ALM ON CONTACTS OPEN / CLOSED	LV-5243	B	VALVE	NMS	7.2.84-E	02	SOE	1385
Z09345	--	3G2 BYPASS FEED REG VALVE - BFRV	ALM ON CONTACTS CLSD / NOT OPEN	LV-5244	B	VALVE	NMS	7.2.84-E	02	SOE	1385
Z09346	--	3G2 BYPASS FEED REG VALVE - BFRV	ALM ON CONTACTS OPEN / CLOSED	LV-5244	B	VALVE	NMS	7.2.84-E	02	SOE	1385
Z09347	--	3G3 BYPASS FEED REG VALVE - BFRV	ALM ON CONTACTS CLSD / NOT OPEN	LV-5245	B	VALVE	NMS	7.2.84-E	02	SOE	1385
Z09348	--	3G3 BYPASS FEED REG VALVE - BFRV	ALM ON CONTACTS OPEN / CLOSED	LV-5245	B	VALVE	NMS	7.2.84-E	02	SOE	1385
Z09349	--	3G4 BYPASS FEED NEG VALVE - BFRV	ALM ON CONTACTS CLSD / NOT OPEN	LV-5242	B	VALVE	NMS	7.2.84-E	02	SOE	1385
Z09350	--	3G4 BYPASS FEED NEG VALVE - BFRV	ALM ON CONTACTS OPEN / CLOSED	LV-5242	B	VALVE	NMS	7.2.84-E	02	SOE	1385
Z09351	--	3G1 ATMOSPHERIC RELIEF VALVE (CM 1)	ALM ON CONTACTS CLSD / NOT OPEN	PV-3009	B	VALVE	NMS	7.2.84-A	02	RPU NI	1381
Z09352	--	3G1 ATMOSPHERIC RELIEF VALVE (CM 1)	ALM ON CONTACTS OPEN / CLOSED	PV-3008	B	VALVE	NMS	7.2.84-A	02	RPU NI	1381
Z09353	--	3G2 ATMOSPHERIC RELIEF VALVE (CM 2)	ALM ON CONTACTS CLSD / NOT OPEN	PV-3010	B	VALVE	NMS	7.2.84-A	02	RPU NI	1381
Z09354	--	3G2 ATMOSPHERIC RELIEF VALVE (CM 2)	ALM ON CONTACTS OPEN / CLOSED	PV-3010	B	VALVE	NMS	7.2.84-A	02	RPU NI	1381
Z09355	--	3G3 ATMOSPHERIC RELIEF VALVE (CM 1)	ALM ON CONTACTS CLSD / NOT OPEN	PV-3020	B	VALVE	NMS	7.2.84-A	02	RPU NI	1381

K
 E ERF PHOTIUS
 V SYMBOL SIGNAL DESCRIPTION
 S
 P
 D
 B
 YAN CLASS VIA SYSTEM S

Z09356	--	863 ATMOSPHERIC RELIEF VALVE (CM 1)	ALM ON CONTACTS OPEN	ALM/NML1 NOT CLOSED / CLOSED	PV-3828	B	VALVE NMS	7.2.04-A 02 RPU N1 1281	E/01-8C-083P
Z09357	--	864 ATMOSPHERIC RELIEF VALVE (CM 2)	ALM ON CONTACTS CLSD	ALM/NML1 UPEN / NOT OPEN	PV-3836	B	VALVE NMS	7.2.04-A 02 RPU N1 1281	E/01-8C-083P
Z09358	--	864 ATMOSPHERIC RELIEF VALVE (CM 2)	ALM ON CONTACTS UPEN	ALM/NML1 NOT CLOSED / CLOSED	PV-3836	B	VALVE NMS	7.2.04-A 02 RPU N1 1281	E/01-8C-083P
Z09371	--	SI PUMP A INLET VALVE	ALM ON CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-8923A	B	VALVE I	7.2.05-E 02 RPU A1 1284	E/01-80-083F
Z09372	--	SI PUMP A INLET VALVE	ALM ON CONTACTS OPEN	ALM/NML1 CLOSED / NOT CLOSED	HY-8923A	B	VALVE I	7.2.05-E 02 RPU A1 1284	E/01-80-083F
Z09373	--	SI PUMP B INLET VALVE	ALM ON CONTACTS UPEN	ALM/NML1 NOT OPEN / OPEN	HY-8923B	B	VALVE II	7.2.05-E 02 RPU B1 1284	E/01-80-083G
Z09374	--	SI PUMP B INLET VALVE	ALM ON CONTACTS UPEN	ALM/NML1 CLOSED / NOT CLOSED	HY-8923B	B	VALVE II	7.2.05-E 02 RPU B1 1284	E/01-80-083G
Z09375	--	SI PUMP A TO COLD LEGS 184	ALM ON CONTACTS UPEN	ALM/NML1 NOT OPEN / OPEN	HY-8921A	B	VALVE I	7.2.05-E 02 RPU A1 1284	E/01-80-083D
Z09376	--	SI PUMP A TO COLD LEGS 184	ALM ON CONTACTS UPEN	ALM/NML1 CLOSED / NOT CLOSED	HY-8921A	B	VALVE I	7.2.05-E 02 RPU A1 1284	E/01-80-083D
Z09377	--	SI PUMP B TO COLD LEGS 243	ALM ON CONTACTS UPEN	ALM/NML1 NOT OPEN / OPEN	HY-8921B	B	VALVE II	7.2.05-E 02 RPU B1 1284	E/01-80-083E
Z09378	--	SI PUMP B TO COLD LEGS 243	ALM ON CONTACTS UPEN	ALM/NML1 CLOSED / NOT CLOSED	HY-8921B	B	VALVE II	7.2.05-E 02 RPU B1 1284	E/01-80-083E
Z09379	--	SI3 COLD LEG LOOP INLET HEADER	ALM ON CONTACTS UPEN	ALM/NML1 NOT OPEN / OPEN	HY-8935	B	VALVE I	7.2.05-E 02 RPU A1 1284	E/01-80-083H

R	E	V	ERF SYMBOL	PROIEUS	SIGNAL DESCRIPTION	UNIGINATIP/ DEVICE	B	Y	SIGNAL SOURCE CLASS	RG 1.97	INPUT	VAR CLASS	VIA SYSTEM
			Z09388	--	S13 COLD LEG LOOP INLET HEADER ALM ON CONTACTS OPEN / NOT CLOSED	HY-8835	B		VALVE I E/01-80-083H	7.2.05-E	02	RPV	A1 1284
			Z09384	--	S13 ACCUM N2 VLV TRAIN B LOOP 1 ALM ON CONTACTS OPEN / CLOSED	HY-8875E	B		VALVE II E/01-80-085H	7.2.05-E	02	RPV	B1 1284
			Z09386	--	S13 ACCUM N2 VLV TRAIN B LOOP 2 ALM ON CONTACTS OPEN / CLOSED	HY-8878F	B		VALVE II E/01-80-085H	7.2.05-E	02	RPV	B1 1284
			Z09388	--	S13 ACCUM N2 VLV TRAIN B LOOP 3 ALM ON CONTACTS OPEN / CLOSED	HY-8875G	B		VALVE II E/01-80-085H	7.2.05-E	02	RPV	B1 1284
			Z09390	--	S13 ACCUM N2 VLV TRAIN B LOOP 4 ALM ON CONTACTS OPEN / CLOSED	HY-8875H	B		VALVE II E/01-80-085H	7.2.05-E	02	RPV	B1 1284
			Z09391	--	S1 PUMP B MINIFLOW VALVE (TRAIN A ISOL) ALM ON CONTACTS OPEN / OPEN	HY-8928	B		VALVE I E/01-80-082B	7.2.05-E	02	RPV	A1 1284
			Z09392	--	S1 PUMP B MINIFLOW VALVE (TRAIN A ISOL) ALM ON CONTACTS CLSD / NOT CLSD	HY-8928	B		VALVE I E/01-80-082B	7.2.05-E	02	RPV	A1 1284
*			Z09393	--	S1 PUMPS MINIFLOW VALVE (TRAIN B ISOL) ALM ON CONTACTS OPEN / OPEN	HY-8813	B		VALVE II E/01-80-083B	7.2.05-E	02	RPV	B1 1284
*			Z09394	--	S1 PUMPS MINIFLOW VALVE (TRAIN B ISOL) ALM ON CONTACTS CLSD / NOT CLSD	HY-8813	B		VALVE II E/01-80-083B	7.2.05-E	02	RPV	B1 1284
			Z09395	--	S1 PUMP A MINIFLOW ALM ON CONTACTS OPEN / OPEN	HY-8814	B		VALVE I E/01-80-083C	7.2.05-E	02	RPV	A1 1284
			Z09396	--	S1 PUMP A MINIFLOW ALM ON CONTACTS CLSD / NOT CLSD	HY-8814	B		VALVE I E/01-80-083C	7.2.05-E	02	RPV	A1 1284
			Z09399	--	MAIN STEAM LINE DRAIN TO CONDENSER ALM ON CONTACTS CLSD / NOT OPEN	HY-5179	B		VALVE MNS E/01-8C-F82H	--	--	RPV	A1 1381

1101

R
E
V
SYMBOL PRUTEUS
SIGNAL DESCRIPTION
ORIGINATING DEVICE
SIGNAL SOURCE CLASS
HG 1.97 INPUT
VAR CLASS VIA SYSTEM 3

Z09400	--	MAIN STEAM LINE DRAIN TO CONDENSER	ALM ON CONTACTS	UPEN	ALM/NML: NOT CLOSED / CLOSED	MV-5179	B	VALVE NNS	--	RPU N1 1301
Z09401	--	AUX FM TRB STM LINE DRAIN TO CONDENSER	ALM ON CONTACTS	CLS	ALM/NML: UPEN / NOT UPEN	MV-5178	B	VALVE NNS	--	RPU N1 1301
Z09402	--	AUX FM TRB STM LINE DRAIN TO CONDENSER	ALM ON CONTACTS	UPEN	ALM/NML: NOT CLSD / CLSD	MV-5178	B	VALVE NNS	--	RPU N1 1301
Z09403	--	MD AUX FEED PUMP B MINIFLUM VALVE	ALM ON CONTACTS	UPEN	ALM/NML: NOT UPEN / OPEN	FV-5154	B	VALVE II	7.2.00-C 02	RPU B1 1302
Z09404	--	MD AUX FEED PUMP B MINIFLUM VALVE	ALM ON CONTACTS	CLS	ALM/NML: CLOSED / NOT CLOSED	FV-5154	B	VALVE II	7.2.00-C 02	RPU B1 1302
Z09405	--	MD AUX FEED PUMP A MINIFLUM VALVE	ALM ON CONTACTS	UPEN	ALM/NML: NOT UPEN / OPEN	FV-5155	B	VALVE I	7.2.00-C 02	RPU A1 1302
Z09406	--	MD AUX FEED PUMP A MINIFLUM VALVE	ALM ON CONTACTS	CLS	ALM/NML: CLOSED / NOT CLOSED	FV-5155	B	VALVE I	7.2.00-C 02	RPU A1 1302
Z09410	--	CNMT SPRAY PUMP A RWST SUCTION	ALM ON CONTACTS	UPEN	ALM/NML: NOT UPEN / OPEN	MV-9017A	B	VALVE I	7.2.07-C 02	RPU A1 1200
Z09411	--	CNMT SPRAY PUMP A RWST SUCTION	ALM ON CONTACTS	UPEN	ALM/NML: CLOSED / NOT CLOSED	MV-9017A	B	VALVE I	7.2.07-C 02	RPU A1 1200
Z09412	--	CNMT SPRAY PUMP B RWST SUCTION	ALM ON CONTACTS	UPEN	ALM/NML: NOT UPEN / OPEN	MV-9017B	B	VALVE II	7.2.07-C 02	RPU B1 1200
Z09413	--	CNMT SPRAY PUMP B RWST SUCTION	ALM ON CONTACTS	UPEN	ALM/NML: CLOSED / NOT CLOSED	MV-9017B	B	VALVE II	7.2.07-C 02	RPU B1 1200
Z09414	--	CNMT SPRAY PUMP A DISCHARGE TO SPRAY HDR	ALM ON CONTACTS	CLS	ALM/NML: UPEN / NOT UPEN	MV-9017A	B	VALVE I	7.2.07-C 02	RPU A1 1200

3
P
0

FILE 1 REG GUIDE /ERF INPUT LIST

PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	SIGNAL SOURCE CLASS	SIGNAL CLASS	VALVE	RPV	SYSTEM
Z09415	-- CNMT SPRAY PUMP A DISCHARGE TO SPRAY HDR ALM ON CONTACTS OPEN ALM/NML1 NOT CLSD / CLSD	MV-9881A	B	VALVE I	7.2.87-C 02	RPV A1	1286
Z09416	-- CNMT SPRAY PUMP B DISCHARGE TO SPRAY HDR ALM ON CONTACTS CLSD ALM/NML2 UPEN / NOT UPEN	MV-9881B	B	VALVE II	7.2.87-C 02	RPV B1	1286
Z09417	-- CNMT SPRAY PUMP B DISCHARGE TO SPRAY HDR ALM ON CONTACTS OPEN ALM/NML1 NOT CLSD / CLSD	MV-9881B	B	VALVE II	7.2.87-C 02	RPV B1	1286
Z09418	-- SPRAY ADDITIVE TANK OUTLET TRAIN A ALM ON CONTACTS CLSD ALM/NML1 UPEN / NOT UPEN	MV-9894A	B	VALVE I	7.2.87-C 02	RPV A1	1286
Z09419	-- SPRAY ADDITIVE TANK OUTLET TRAIN A ALM ON CONTACTS OPEN ALM/NML1 NOT CLOSED / CLOSED	MV-9894A	B	VALVE I	7.2.87-C 02	RPV A1	1286
Z09420	-- SPRAY ADDITIVE TANK OUTLET TRAIN B ALM ON CONTACTS CLSD ALM/NML1 UPEN / NOT UPEN	MV-9894B	B	VALVE II	7.2.87-C 02	RPV B1	1286
Z09421	-- SPRAY ADDITIVE TANK OUTLET TRAIN B ALM ON CONTACTS OPEN ALM/NML1 NOT CLOSED / CLOSED	MV-9894B	B	VALVE II	7.2.87-C 02	RPV B1	1286
Z09422	-- CS PUMP A CNMT SUMP SUCTION VALVE IRC ALM ON CONTACTS OPEN ALM/NML1 UPEN / NOT UPEN	MV-9882A	B	VALVE I	7.2.87-C 02	RPV A1	1286
Z09423	-- CS PUMP A CNMT SUMP SUCTION VALVE IRC ALM ON CONTACTS OPEN ALM/NML1 NOT CLOSED / CLOSED	MV-9882A	B	VALVE I	7.2.87-C 02	RPV A1	1286
Z09424	-- CS PUMP B CNMT SUMP SUCTION VALVE IRC ALM ON CONTACTS OPEN ALM/NML1 UPEN / NOT UPEN	MV-9882B	B	VALVE II	7.2.87-C 02	RPV B1	1286
Z09425	-- CS PUMP B CNMT SUMP SUCTION VALVE IRC ALM ON CONTACTS OPEN ALM/NML1 NOT CLOSED / CLOSED	MV-9882B	B	VALVE II	7.2.87-C 02	RPV B1	1286
Z09426	-- CS PUMP A CNMT SUMP SUCTION VALVE IRC ALM ON CONTACTS OPEN ALM/NML1 UPEN / NOT UPEN	MV-9883A	B	VALVE I	7.2.87-C 02	RPV A1	1286

S
P

R
 E
 Y
 SYMBOL
 PHOTOUS
 SIGNAL DESCRIPTION
 ORIGINATING DEVICE
 SIGNAL SOURCE CLASS
 SIGNAL CLASS
 VAR CLASS
 INPUT
 VIA SYSTEM
 S
 P
 D
 S

Z09427	-- CS PUMP A CMHT SUMP SUCTION VALVE ORC ALM ON CONTACTS OPEN	ALM/NML1 NOT CLOSED / CLOSED	HY-9883A	B	VALVE I E/D1-80-J82J	7.2.87-C 02 RPU A1 1286
Z09428	-- CS PUMP B CMHT SUMP SUCTION VALVE ORC ALM UN CONTACTS OPEN	ALM/NML1 UPEN / NOT OPEN	HY-9883B	B	VALVE II E/D1-80-J82K	7.2.87-C 02 RPU B1 1286
Z09429	-- CS PUMP B CMHT SUMP SUCTION VALVE ORC ALM UN CONTACTS OPEN	ALM/NML1 NOT CLOSED / CLOSED	HY-9883B	B	VALVE II E/D1-80-J82K	7.2.87-C 02 RPU B1 1286
Z09430	-- CTB COOLING UNIT 1 OUTLET DAMPER ALM ON CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2582A	B	VALVE I E/D1-86-883V	7.2.87-0 02 RPU A1 1581
Z09431	-- CTB COOLING UNIT 2 OUTLET DAMPER ALM ON CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2582B	B	VALVE I E/D1-86-883V	7.2.87-0 02 RPU A1 1581
Z09432	-- CTB COOLING UNIT 3 OUTLET DAMPER ALM ON CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2583A	B	VALVE II E/D1-86-883W	7.2.87-0 02 RPU B1 1581
Z09433	-- CTB COOLING UNIT 4 OUTLET DAMPER ALM UN CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2583B	B	VALVE II E/D1-86-883W	7.2.87-0 02 RPU B1 1581
Z09438	-- CTB COOLING UNIT 5 OUTLET DAMPER ALM ON CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2584A	B	VALVE I E/D1-86-883X	7.2.87-0 02 RPU A1 1581
Z09440	-- CTB COOLING UNIT 6 OUTLET DAMPER ALM UN CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2584B	B	VALVE I E/D1-86-883X	7.2.87-0 02 RPU A1 1581
Z09442	-- CTB COOLING UNIT 7 OUTLET DAMPER ALM ON CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2585A	B	VALVE II E/D1-86-883Y	7.2.87-0 02 RPU B1 1581
Z09444	-- CTB COOLING UNIT 8 OUTLET DAMPER ALM ON CONTACTS OPEN	ALM/NML1 NOT OPEN / OPEN	HY-2585B	B	VALVE II E/D1-86-883Y	7.2.87-0 02 RPU B1 1581
Z09449	-- N3CW TOWER A BLURDORN ALM ON CONTACTS CLSD	ALM/NML1 CLUSED / NOT CLOSED	CV-9446	B	VALVE I E/D1-80-A84J	7.2.89-B 02 RPU A1 1282

M E V	EMF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE CLASS	II CLASS	WG VIA	1.67 CLASS	INPUT SYSTEM	D S
	Z09451	--	NSCW TURNER B BLOWDOWN ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	CV-9447	B	VALVE E/01-80-K08K	II	7.2.09-B	02	RPU 01	1282
	Z09454	--	PIPING PEN RM HVAC TRN A TO LOADS ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	PV-2558A	B	VALVE E/01-86-081L	I	7.2.11-A	02	RPU A1	1561
	Z09455	--	PIPING PEN RM HVAC TRN A TO LOADS ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	PV-2558A	B	VALVE E/01-86-081L	I	7.2.11-A	02	RPU A1	1561
	Z09456	--	PIPING PEN RM HVAC TRN B TO LOADS ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	PV-2551A	B	VALVE E/01-86-081M	II	7.2.11-A	02	RPU 01	1561
	Z09457	--	PIPING PEN RM HVAC TRN B TO LOADS ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	PV-2551A	B	VALVE E/01-86-081M	II	7.2.11-A	02	RPU 01	1561
	Z09458	--	PIPING PEN RM HVAC TRN A TO ATMOS ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	PV-2558B	B	VALVE E/01-86-081J	I	7.2.11-A	02	RPU A1	1561
	Z09459	--	PIPING PEN RM HVAC TRN A TO ATMOS ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	PV-2558B	B	VALVE E/01-86-081J	I	7.2.11-A	02	RPU A1	1561
	Z09460	--	PIPING PEN RM HVAC TRN B TO ATMOS ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	PV-2551B	B	VALVE E/01-86-081K	II	7.2.11-A	02	RPU 01	1561
	Z09461	--	PIPING PEN RM HVAC TRN B TO ATMOS ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	PV-2551B	B	VALVE E/01-86-081K	II	7.2.11-A	02	RPU 01	1561
	Z09463	--	CONTROL ROOM NORMAL HVAC INTAKE TRN A ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	AMV-12153	B	VALVE E/01-86-C81L	I	7.2.11-A	02	RPU A1	1531 (UNIT 1 INPUT ONLY)
	Z09465	--	CONTROL ROOM NORMAL HVAC INTAKE TRN B ALM ON CONTACTS CLSD ALM/NMLI CLOSED / NOT CLOSED	AMV-12152	B	VALVE E/01-86-C81M	II	7.2.11-A	02	RPU 01	1531 (UNIT 1 INPUT ONLY)
	Z09466	--	CONTROL ROOM HVAC #5A INTAKE TRN A ALM ON CONTACTS OPEN ALM/NMLI NOT OPEN / OPEN	MV-12114	B	VALVE E/01-86-C81G	I	7.2.11-A	02	RPU A1	1531

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	YAH CLASS	47 INPUT VIA	SYSTEM	S P D S
Z09467	--	CONTROL ROOM HVAC #5A INTAKE TRAIN A ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12114	B	2936	VALVE I E/D1-BG-C016	7.2.11-A 02 RPU A1	1531		
Z09468	--	CONTROL ROOM HVAC #5A INTAKE TRAIN B ALM ON CONTACTS OPEN ALM/NML: NOT OPEN / OPEN	HV-12115	B	2983	VALVE II E/D1-BG-C01N	7.2.11-A 02 RPU B1	1531		
Z09469	--	CONTROL ROOM HVAC #5A INTAKE TRAIN B ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12115	B	3007	VALVE II E/D1-BG-C01N	7.2.11-A 02 RPU B1	1531		
Z09471	--	CR KIT,TOIL,CONF RM EXH FAN INL TRN A ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	AHV-12162	B	2607	VALVE I E/D1-BG-C010	7.2.11-A 02 RPU A1	1531 (UNIT 1 INPUT ONLY)		
Z09473	--	CR KIT,TOIL,CONF RM EXH FAN INL TRN B ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	AHV-12163	B	2609	VALVE II E/D1-BG-C01R	7.2.11-A 02 RPU B1	1531 (UNIT 1 INPUT ONLY)		
Z09475	--	CR NORMAL COOLER UNITS SUPPLY TRAIN A ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12146	B	2671	VALVE I E/D1-BG-C07B	7.2.11-A 02 RPU A1	1531		
Z09477	--	CR NORMAL COOLER UNITS SUPPLY TRAIN B ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12147	B	2483	VALVE II E/D1-BG-C07C	7.2.11-A 02 RPU B1	1531		
Z09479	--	CR NORMAL COOLER UNITS RETURN TRAIN A ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12149	B	2395	VALVE I E/D1-BG-C07B	7.2.11-A 02 RPU A1	1531		
Z09481	--	CR NORMAL COOLER UNITS RETURN TRAIN B ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12148	B	2307	VALVE II E/D1-BG-C07C	7.2.11-A 02 RPU B1	1531		
Z09482	--	SAFETY FEATURE BAT RM EXH FAN 1 TO ATMOS ALM ON CONTACTS CLSD ALM/NML: OPEN / NOT OPEN	HV-12742	B	2377	VALVE I E/D1-BG-C04B	7.2.11-A 02 RPU A1	1532		
Z09484	--	SAFETY FEATURE BAT RM EXH FAN 2 TO ATMOS ALM ON CONTACTS CLSD ALM/NML: OPEN / NOT OPEN	HV-12727	B	2388	VALVE II E/D1-BG-C04T	7.2.11-A 02 RPU B1	1532		
Z09486	--	SAFETY FEATURE BAT RM EXH FAN 3 TO ATMOS ALM ON CONTACTS CLSD ALM/NML: OPEN / NOT OPEN	HV-12748	B	2588	VALVE I E/D1-BG-C04U	7.2.11-A 02 RPU A1	1532		

R	ERP	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	WG 1.97	INPUT		B
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM	B
	Z09488	--	SAFETY FEATURE BAT RM EXH FAN 4 TO ATMOS ALM ON CONTACTS CLSD ALM/NML: OPEN / NOT OPEN	HV-12749	B	VALVE	II	7.2.11-A 02 RPU 02	1532		
	Z09511	--	FHB HVAC NORMAL EXHAUST TRAIN A ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	AHV-12479	B	VALVE	I	7.2.11-A 02 RPU A1	1541		
	Z09513	--	FHB HVAC NORMAL EXHAUST TRAIN B ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	AHV-12480	B	VALVE	II	7.2.11-A 02 RPU B1	1541		
	Z09515	--	FHB NML COOLER UNIT OUT (AHV-2529) TRN A ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	AHV-2529	B	VALVE	I	7.2.11-A 02 RPU A1	1541		
	Z09517	--	FHB NML COOLER UNIT OUT (AHV-2528) TRN B ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	AHV-2528	B	VALVE	II	7.2.11-A 02 RPU B1	1541		
*	Z09519	--	FHB NML COOLER UNIT OUT (AHV-2535) TRN A ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	AHV-2535	B	VALVE	I	7.2.11-A 02 RPU A1	1541		
	Z09521	--	FHB NML COOLER UNIT OUT (AHV-2534) TRN B ALM ON CONTACTS CLSD ALM/NML: CLSD / NOT CLSD	AHV-2534	B	VALVE	II	7.2.11-A 02 RPU B1	1541		
	Z09523	--	FHB NORMAL EXH UNITS OUTLET TRAIN A ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	AHV-12481	B	VALVE	I	7.2.11-A 02 RPU A1	1541		
	Z09525	--	FHB NORMAL EXH UNITS OUTLET TRAIN B ALM ON CONTACTS CLSD ALM/NML: CLOSED / NOT CLOSED	AHV-12482	B	VALVE	II	7.2.11-A 02 RPU B1	1541		
	Z09527	--	RHM PUMP ROOM TRAIN A COOLER UNIT ALM ON CONTACTS CLSD ALM/NML: ON / OFF	428-88053	B	MCC	I	7.2.11-B 02 RPU A2	1555		
	Z09529	--	RHM PUMP ROOM TRAIN B COOLER UNIT ALM ON CONTACTS CLSD ALM/NML: ON / OFF	428-88053	B	MCC	II	7.2.11-B 02 RPU B2	1555		
	Z09531	--	CNMT SPRAY PUMP ROOM TRAIN A COOLER UNIT ALM ON CONTACTS CLSD ALM/NML: ON / OFF	428-88052	B	MCC	I	7.2.11-B 02 RPU A2	1555		

W	ERF	PROTEUS		ORIGINATING	B	SIGNAL	SIGNAL	WG 1.97	INPUT	S
V	SYMBOL	SYMBOL	SIGNAL DESCRIPTION	DEVICE	Y	SOURCE	CLASS	VAR CLASS	VIA	SYSTEM
Z09533	--	CNMT SPRAY PUMP ROOM TRAIN B COOLER UNIT	ALM ON CONTACTS CLSD ALM/NML: UN / OFF	42B-88052	B	MCC	II	7.2.11-B 02 RPU B2 1555		
					2888	E/D1-8G-D85R				
Z09535	--	CCM PUMP ROOM TRAIN A COOLER UNIT	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88028	B	MCC	I	7.2.11-B 02 RPU A2 1555		
					2885	E/D1-8G-D85E				
Z09537	--	CCM PUMP ROOM TRAIN B COOLER UNIT	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88028	B	MCC	II	7.2.11-B 02 RPU B2 1555		
					2883	E/D1-8G-D85F				
Z09539	--	CHARGING PUMP ROOM TRAIN A COOLER UNIT	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88022	B	MCC	I	7.2.11-B 02 RPU A2 1555		
					2518	E/D1-8G-D85N				
Z09541	--	CHARGING PUMP ROOM TRAIN B COOLER UNIT	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88022	B	MCC	II	7.2.11-B 02 RPU B2 1555		
					2381	E/D1-8G-D85P				
Z09543	--	ELEC SWGR & MCC HM LEVEL 0 TRAIN A COOLER	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88049	B	MCC	I	7.2.11-B 02 RPU A2 1555		
					2881	E/D1-8G-D85A				
Z09545	--	ELEC SWGR & MCC HM LEVEL 2 TRAIN B COOLER	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88049	B	MCC	II	7.2.11-B 02 RPU B2 1555		
					2882	E/D1-8G-D85B				
Z09547	--	ELEC SWGR & MCC HM LEVEL 0 TRAIN A COOLER	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88058	B	MCC	I	7.2.11-B 02 RPU A2 1555		
					2878	E/D1-8G-D85C				
Z09549	--	ELEC SWGR & MCC HM LEVEL B TRAIN B COOLER	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88058	B	MCC	II	7.2.11-B 02 RPU B2 1555		
					2598	E/D1-8G-D85D				
Z09551	--	ELEC SWGR & MCC HM LEVEL 1 TRAIN A COOLER	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88023	B	MCC	I	7.2.11-B 02 RPU A2 1555		
					2417	E/D1-8G-D85E				
Z09553	--	ELEC SWGR & MCC HM LEVEL 1 TRAIN B COOLER	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88023	B	MCC	II	7.2.11-B 02 RPU B2 1555		
					2413	E/D1-8G-D85F				
Z09555	--	SIS PUMP ROOM TRAIN A COOLER UNIT	ALM ON CONTACTS OPEN ALM/NML: UN / OFF	42B-88023	B	MCC	I	7.2.11-B 02 RPU A2 1555		
					2407	E/D1-8G-D85R				

R	E	Y	ERF SYMBOL	PRUTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	HG 1.97 VAR CLASS	INPUT VIA	S P D SYSTEM
			Z09557	--	SIS PUMP ROOM TRAIN B COOLER UNIT ALM ON CONTACT: OPEN ALM/NML: ON / OFF	42B-88023	B	MCC	II	7.2.11-B 02 RPU B2 1555		
			Z09559	--	SFP HEAT EXCH & PUMP RM TRAIN A COOLER UNIT ALM ON CONTACT: CLSD ALM/NML: ON / OFF	42B-88828	B	MCC	I	7.2.11-B 02 RPU A2 1555		
			Z09561	--	SFP HEAT EXCH & PUMP RM TRAIN B COOLER UNIT ALM ON CONTACT: CLSD ALM/NML: ON / OFF	42B-88829	B	MCC	II	7.2.11-B 02 RPU B2 1555		
			Z09562	--	DG SUPPLY FAN 1 TRAIN A DAMPER ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-12050	B	VALVE	I	7.2.11-A 02 RPU A1 1566		
			Z09564	--	DG SUPPLY FAN 3 TRAIN A DAMPER ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-12051	B	VALVE	I	7.2.11-A 02 RPU A1 1566		
			Z09566	--	DG SUPPLY FAN 2 TRAIN B DAMPER ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-12053	B	VALVE	II	7.2.11-A 02 RPU B2 1566		
			Z09568	--	DG SUPPLY FAN 4 TRAIN B DAMPER ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-12054	B	VALVE	II	7.2.11-A 02 RPU B2 1566		
			Z09573	--	AUX FW PUMP HOUSE TRAIN A SUPPLY FAN ALM ON CONTACT: OPEN ALM/NML: OFF / ON	42B-88789	B	MCC	I	7.2.11-B 02 RPU A2 1593		
			Z09577	--	AUX FW PUMP HOUSE TRAIN B SUPPLY FAN ALM ON CONTACT: OPEN ALM/NML: OFF / ON	42B-88789	B	MCC	II	7.2.11-B 02 RPU B2 1593		
			Z09583	--	AUX BLDG VENT SYSTEM TRN A SUPPLY ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12604	B	VALVE	I	7.2.11-A 02 RPU A1 1561		
			Z09585	--	AUX BLDG VENT SYSTEM TRN B SUPPLY ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12607	B	VALVE	II	7.2.11-A 02 RPU B2 1561		
			Z09587	--	AUX BLDG VENT SYSTEM TRN A RETURN ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12605	B	VALVE	I	7.2.11-A 02 RPU A1 1561		

VOLUME 1 REG GUIDE 7/ERF INPUT LIST

W	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	RG 1.97 VAM CLASS	INPUT VIA	SYSTEM	S P D
	Z09589	--	AUX BLDG VERT SYSTEM TRN B RETURN ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-12606	B 2389	VALVE E/D1-B6-UM4B	II	7.2.11-A 02 RPU B2	1961		
	Z09594	--	KHR PUMP A TO HOT LEG ISOLATION VALVE ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-8716A	B 2837	VALVE E/D1-B0-EW2N	I	7.2.10-B 02 RPU A1	1285		
	Z09595	--	KHR PUMP A TO HOT LEG ISOLATION VALVE ALM ON CONTACT: CLSD ALM/NML: NOT CLOSED / CLOSED	HV-8716A	B 2861	VALVE E/D1-B0-EW2N	I	7.2.10-B 02 RPU A1	1285		
	Z09596	--	KHR PUMP B TO HOT LEG ISOLATION VALVE ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-8716B	B 2839	VALVE E/D1-B0-EW2P	II	7.2.10-B 02 RPU B2	1285		
	Z09597	--	KHR PUMP B TO HOT LEG ISOLATION VALVE ALM ON CONTACT: CLSD ALM/NML: NOT CLOSED / CLOSED	HV-8716B	B 2863	VALVE E/D1-B0-EW2P	II	7.2.10-B 02 RPU B2	1285		
*	Z09600	--	AMSAC LOW FR FLOW SG1 ALM ON CONTACT: CLSD ALM/NML: ACTUATED / NORMAL	FB-510C	B 2250	AMSAC	NNS	--	- SOE	1626	X
*	Z09601	--	AMSAC LOW FR FLOW SG2 ALM ON CONTACT: CLSD ALM/NML: ACTUATED / NORMAL	FB-520C	B 2251	AMSAC	NNS	--	- SOE	1626	X
*	Z09602	--	AMSAC LOW FR FLOW SG3 ALM ON CONTACT: CLSD ALM/NML: ACTUATED / NORMAL	FB-530C	B 2252	AMSAC	NNS	--	- SOE	1626	X
*	Z09603	--	AMSAC LL3 FR FLOW SG4 ALM ON CONTACT: CLSD ALM/NML: ACTUATED / NORMAL	FB-540C	B 2253	AMSAC	NNS	--	- SOE	1626	X
*	Z09604	--	AMSAC ACTUATION ALM ON CONTACT: CLSD ALM/NML: ACTUATED / NORMAL	AMSAC	B 2254	AMSAC	NNS	--	- SOE	1626	X
*	Z09605	--	AMSAC 1ST STG TRB IMP CHBK PRES CHAN 1 LU ALM ON CONTACT: CLSD ALM/NML: ACTUATED / NML	PB-505D	B 2255	AMSAC	NNS	--	- SOE	1626	X
*	Z09606	--	AMSAC 1ST STG TRB IMP CHBK PRES CHAN 2 LU ALM ON CONTACT: CLSD ALM/NML: ACTUATED / NML	PB-506D	B 2256	AMSAC	NNS	--	- SOE	1626	X

Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	MG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S P D B
*	Z09667	--	AMSAC GENERAL WARNING ALM ON CONTACTS: CLSD ALM/NML: ACTUATED / NORMAL	AMSAC	B	AMSAC	NNS	--	- SOE	1626	X
	Z09670	--	301 FR BYP BLOC VALVE - BFIV ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-15196	B	VALVE	NNS	7.2.04-F	D2 SOE	1302	
	Z09672	--	302 FR BYP BLOC VALVE - BFIV ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-15197	B	VALVE	NNS	7.2.04-F	D2 SOE	1302	
	Z09674	--	303 FR BYP BLOC VALVE - BFIV ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-15198	B	VALVE	NNS	7.2.04-F	D2 SOE	1302	
	Z09676	--	304 FR BYP BLOC VALVE - BFIV ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-15199	B	VALVE	NNS	7.2.04-F	D2 SOE	1302	
	Z09678	--	RCS HOT LEG SAMPLE ALM ON CONTACTS: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8220	B	VALVE	I	6.2.03-D	C2 RPU A2	1212	X
	Z09680	--	CONTAINMENT ATMOSPHERE SAMPLE ALM ON CONTACTS: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8221	B	VALVE	NNS	--	- RPU N1	1513	
	Z09801	--	CHARGING PUMP A MINIFLOW ISOL VLV ALM ON CONTACTS: CLSD ALM/NML: OPEN / NOT OPEN	HV-8508A	B	ISO PNL	NNS	7.2.03-E	D2 SOE	1200	
	Z09802	--	CHARGING PUMP A MINIFLOW ISOL VLV ALM ON CONTACTS: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8508A	P	ISO PNL	NNS	7.2.03-E	D2 SOE	1200	
	Z09803	--	CHARGING PUMP B MINIFLOW ISOL VLV ALM ON CONTACTS: CLSD ALM/NML: OPEN / NOT OPEN	HV-8508B	B	ISO PNL	NNS	7.2.03-E	D2 SOE	1200	
	Z09804	--	CHARGING PUMP B MINIFLOW ISOL VLV ALM ON CONTACTS: OPEN ALM/NML: NOT CLOSED / CLOSED	HV-8508B	B	ISO PNL	NNS	7.2.03-E	D2 SOE	1200	
	Z09805	--	CHARGING PUMP B MINIFLOW ISOL VLV ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-8509A	B	ISO PNL	NNS	7.2.03-E	D2 SOE	1200	

R	E	Y	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL SOURCE	SIGNAL CLASS	KG 1.97 YAH CLASS	INPUT VIA	SYSTEM	S	P	D	S
			Z09886	--	CHARGING PUMP B MINIFLOW ISOL VLV ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-8589A	B 2762	ISD PNL	NNS	7.2.03-E 02	SOE	1208				
			Z09887	--	CHARGING PUMP A MINIFLOW ISOL VLV ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-8589B	B 2759	ISD PNL	NNS	7.2.03-E 02	SOE	1208				
			Z09888	--	CHARGING PUMP A MINIFLOW ISOL VLV ALM ON CONTACT: CLSD ALM/NML: CLOSED / NOT CLOSED	HV-8589B	B 2763	ISD PNL	NNS	7.2.03-E 02	SOE	1208				
			Z09889	--	S1/CHARGING PUMPS SUCTION INH A TIE VLV ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-8887A	B 2748	ISD PNL	NNS	7.2.05-E 02	SOE	1204				
			Z09810	--	S1/CHARGING PUMPS SUCTION INH A TIE VLV ALM ON CONTACT: OPEN ALM/NML: NOT CLSD / CLSD	HV-8887A	B 2764	ISD PNL	NNS	7.2.05-E 02	SOE	1204				
			Z09811	--	S1/CHARGING PUMPS SUCTION INH B TIE VLV ALM ON CONTACT: CLSD ALM/NML: OPEN / NOT OPEN	HV-8887B	B 2741	ISD PNL	NNS	7.2.05-E 02	SOE	1204				
			Z09812	--	S1/CHARGING PUMPS SUCTION INH B TIE VLV ALM ON CONTACT: OPEN ALM/NML: NOT CLSD / CLSD	HV-8887B	B 2765	ISD PNL	NNS	7.2.05-E 02	SOE	1204				
			Z09813	--	POST LUCA RX CAVITY PURGE UNIT 87001 ALM ON CONTACT: OPEN ALM/NML: ON / OFF	42B-88E29	B 2165	ISD PNL	NNS	7.2.11-B 02	SOE	1516				
			Z09814	--	POST LUCA RX CAVITY PURGE UNIT 87002 ALM ON CONTACT: OPEN ALM/NML: ON / OFF	42B-88E29	B 2167	ISD PNL	NNS	7.2.11-B 02	SOE	1516				
			Z09815	--	CB AUX RELAY ROOM ESF COOLER UNIT A7001 ALM ON CONTACT: CLSD ALM/NML: ON / OFF	42B-88C22	B 2169	ISD PNL	NNS	7.2.11-B 02	SOE	1539				
			Z09816	--	CB AUX RELAY ROOM ESF COOLER UNIT A7002 ALM ON CONTACT: CLSD ALM/NML: ON / OFF	42B-88A17	B 2171	ISD PNL	NNS	7.2.11-B 02	SOE	1539				
			Z09817	--	S61 MSIV UPSTREAM TRAIN A BYPASS ALM ON CONTACT: OPEN ALM/NML: NOT OPEN / OPEN	HV-13005A	B 2728	VALVE	I	8.2.05-F 02	RPU A1	1301				


M ERF PROTEUS SIGNAL DESCRIPTION ORIGINATING DEVICE Y SIGNAL CLASS VALVE CLASS VALVE I 5.2.05-F 02 RPU A1 1301 S
 Y SYMBOL SYMBOL ALM ON CONTACTS CLSD ALM/NMLT LUSED / NOT CLOSED / NOT CLOSED ALM ON CONTACTS UPEN ALM/NMLT NOT OPEN / UPEN / UPEN

REF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	Y	SIGNAL CLASS	VALVE CLASS	VALVE I
Z09818	--	SG1 MSIV UPSTREAM TRAIN A BYPASS	HV-13805A	B	2/52	E/01-BC-002H	5.2.05-F 02 RPU A1 1301
	ALM ON CONTACTS	CLSD ALM/NMLT LUSED / NOT CLOSED					
Z09819	--	SG1 MSIV UPSTREAM TRAIN B BYPASS	HV-13806	B	2/32	E/01-BC-002J	5.2.05-F 02 RPU B1 1301
	ALM ON CONTACTS	UPEN ALM/NMLT NOT OPEN / UPEN					
Z09820	--	SG1 MSIV UPSTREAM TRAIN C BYPASS	HV-13808	B	2/56	E/01-BC-002J	5.2.05-F 02 RPU B1 1301
	ALM ON CONTACTS	CLSD ALM/NMLT LUSED / NOT CLOSED					
Z09821	--	SG4 MSIV UPSTREAM TRAIN A BYPASS	HV-13806A	B	2/29	E/01-BC-002H	5.2.05-F 02 RPU A1 1301
	ALM ON CONTACTS	UPEN ALM/NMLT NOT OPEN / UPEN					
Z09822	--	SG4 MSIV UPSTREAM TRAIN A BYPASS	HV-13806A	B	2/53	E/01-BC-002H	5.2.05-F 02 RPU A1 1301
	ALM ON CONTACTS	CLSD ALM/NMLT LUSED / NOT CLOSED					
Z09823	--	SG4 MSIV UPSTREAM TRAIN B BYPASS	HV-13808	B	2/33	E/01-BC-002J	5.2.05-F 02 RPU B1 1301
	ALM ON CONTACTS	UPEN ALM/NMLT NOT OPEN / UPEN					
Z09824	--	SG4 MSIV UPSTREAM TRAIN C BYPASS	HV-13808	B	2/57	E/01-BC-002J	5.2.05-F 02 RPU B1 1301
	ALM ON CONTACTS	CLSD ALM/NMLT LUSED / NOT CLOSED					
Z09825	--	SG2 MSIV UPSTREAM TRAIN A BYPASS	HV-13807A	B	2/36	E/01-BC-002H	5.2.05-F 02 RPU A1 1301
	ALM ON CONTACTS	UPEN ALM/NMLT NOT OPEN / UPEN					
Z09826	--	SG2 MSIV UPSTREAM TRAIN A BYPASS	HV-13807A	B	2/54	E/01-BC-002H	5.2.05-F 02 RPU A1 1301
	ALM ON CONTACTS	CLSD ALM/NMLT LUSED / NOT CLOSED					
Z09827	--	SG2 MSIV UPSTREAM TRAIN B BYPASS	HV-13807B	B	2/34	E/01-BC-002J	5.2.05-F 02 RPU B1 1301
	ALM ON CONTACTS	UPEN ALM/NMLT NOT OPEN / UPEN					
Z09828	--	SG2 MSIV UPSTREAM TRAIN C BYPASS	HV-13807B	B	2/58	E/01-BC-002J	5.2.05-F 02 RPU B1 1301
	ALM ON CONTACTS	CLSD ALM/NMLT LUSED / NOT CLOSED					
Z09829	--	SG3 MSIV UPSTREAM TRAIN A BYPASS	HV-13808A	B	2/31	E/01-BC-002H	5.2.05-F 02 RPU A1 1301
	ALM ON CONTACTS	UPEN ALM/NMLT NOT OPEN / UPEN					

R E V	ERF SYMBOL	PROTEUS SYMBOL	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B Y	SIGNAL SOURCE	SIGNAL CLASS	HW 1.97 VIA CLASS	INPUT VIA	SYSTEM	B P D S
	Z09830	--	863 MSIV UPSTREAM TRAIN A BYPASS ALM ON CONTACTS: CLSD ALM/NML: CLUSED / NOT CLOSED	HV-13008A	B	VALVE	I	5.2.05-F B2 RPU A1 1301			
	Z09831	--	863 MSIV UPSTREAM TRAIN B BYPASS ALM ON CONTACTS: OPEN ALM/NML: NOT OPEN / OPEN	HV-13008B	B	VALVE	II	5.2.05-F B2 RPU B1 1301			
	Z09832	--	863 MSIV UPSTREAM TRAIN B BYPASS ALM ON CONTACTS: CLSD ALM/NML: CLUSED / NOT CLOSED	HV-13008C	B	VALVE	II	5.2.05-F B2 RPU B1 1301			
	Z09841	--	HVLIS HV HOT LEG ISOLATOR TRAIN A ALM ON CONTACTS: OPEN ALM/NML: OPEN / NOT OPEN	Z18-1310	N	FLD	NNS	-- - RPU N1 1201 (WESTINGHOUSE ORG DEVICE SHOWS LIS, NOT Z18)			
	Z09842	--	HVLIS HV HEAD ISOLATION TRAIN A ALM ON CONTACTS: OPEN ALM/NML: OPEN / NOT OPEN	Z18-1311	N	FLD	NNS	-- - RPU N1 1201 (WESTINGHOUSE ORG DEVICE SHOWS LIS, NOT Z18)			
	Z09843	--	HVLIS SEAL TABLE ISOLATION TRAIN A ALM ON CONTACTS: OPEN ALM/NML: OPEN / NOT OPEN	Z18-1312	N	FLD	NNS	-- - RPU N1 1201 (WESTINGHOUSE ORG DEVICE SHOWS LIS, NOT Z18)			
	Z09844	--	HVLIS HV HOT LEG ISOLATION TRAIN B ALM ON CONTACTS: OPEN ALM/NML: OPEN / NOT OPEN	Z18-1320	N	FLD	NNS	-- - RPU N1 1201 (WESTINGHOUSE ORG DEVICE SHOWS LIS, NOT Z18)			
	Z09845	--	HVLIS HV HEAD ISOLATOR TRAIN B ALM ON CONTACTS: OPEN ALM/NML: OPEN / NOT OPEN	Z18-1321	N	FLD	NNS	-- - RPU N1 1201 (WESTINGHOUSE ORG DEVICE SHOWS LIS, NOT Z18)			
	Z09846	--	HVLIS HV SEAL TABLE ISOLATOR TRAIN B ALM ON CONTACTS: OPEN ALM/NML: OPEN / NOT OPEN	Z18-1322	N	FLD	NNS	-- - RPU N1 1201 (WESTINGHOUSE ORG DEVICE SHOWS LIS, NOT Z18)			
*	Z09994	--	80E CARD 1 FLIP-FLUP POINT ALM ON CONTACTS: OPEN ALM/NML: OPEN / CLOSED	TEST POINT	GPC	-	-	-- - 80E 1618			
*	Z09995	--	80E CARD 2 FLIP-FLUP POINT ALM ON CONTACTS: OPEN ALM/NML: OPEN / CLOSED	TEST POINT	GPC	-	-	-- - 80E 1618			
*	Z09996	--	80E CARD 3 FLIP-FLUP POINT ALM ON CONTACTS: OPEN ALM/NML: OPEN / CLOSED	TEST POINT	GPC	-	-	-- - 80E 1618			

W	ERF	PROTEUS	SIGNAL DESCRIPTION	ORIGINATING DEVICE	B	SIGNAL SOURCE	SIGNAL CLASS	KG 1.97 VAR CLASS	INPUT VIA	SYSTEM	S
Y	SYMBOL	SYMBOL			Y						D
Z09997	--	SOE CARD 1 TEST POINT	ALM ON CONTACTS OPEN ALM/NML: OPEN / CLOSED	TEST POINT	GPC	-	-	--	-	SOE	1010
					2043						
Z09998	--	SOE CARD 2 TEST POINT	ALM ON CONTACTS OPEN ALM/NML: OPEN / CLOSED	TEST POINT	GPC	-	-	--	-	SOE	1010
					2045						
Z09999	--	SOE CARD 3 TEST POINT	ALM ON CONTACTS OPEN ALM/NML: OPEN / CLOSED	TEST POINT	GPC	-	-	--	-	SOE	1010
					2047						



Approval <i>W F Kitchens</i>	Vogtle Electric Generating Plant NUCLEAR OPERATIONS	 Georgia Power	Procedure No. 14406-1
Date 2/6/89	Unit <u>1</u>		Revision No. 3
			Page No. 1 of 5

05-54-90

MANUAL SET
NO. 7

BORON INJECTION FLOW PATH VERIFICATION - SHUTDOWN

- 1.0 PURPOSE
- 1.1 The purpose of this procedure is to verify that the valves in one operable boron injection flow path described in Technical Specification 3.1.2.1 are in the required position.
- 1.2 This surveillance satisfies Technical Specification 4.1.2.1b.
- 1.3 The frequency of this surveillance is at least once every 31 days.
- 2.0 APPLICABILITY
- This surveillance is required for Modes 5 and 6.
- 3.0 PRECAUTIONS AND LIMITATIONS
- NONE
- 4.0 PREREQUISITES OR INITIAL CONDITIONS
- The Unit Shift Supervisor (USS) shall ensure this surveillance test does not affect other tests presently in progress or jeopardize plant operation prior to granting approval to perform this surveillance test.

INITIALS

USS APPROVAL

**INFORMATION
ONLY**

42 02190524 588

INITIALS

5.0 INSTRUCTIONS

TEST STARTED

DATE TIME MODE

NOTES

- a. Power operated valves (motor, air or solenoid) will be considered in the proper position if valves have power available and are capable of being repositioned to establish flow.
 - b. Valves or breakers should not be repositioned unless directed to do so by USS.
- 5.1 SELECT the operable borated water source(s) and circle same below.
- BORIC ACID STORAGE TK REFUELING WATER STORAGE TK
- 5.2 For the selected boric acid source(s) VERIFY that 14225-1 "Operations Weekly Surveillance Logs" are active. INITIAL Figure 1.
- 5.3 If the Refueling Water Storage Tank (RWST) is the operable source, CHECK 14000-1 "Operations Shift & Daily Surveillance Logs" to verify RWST temperature is within limits. INITIAL Figure 1.
- 5.4 If the Positive Displacement Pump is utilized, VERIFY 14705-1, "Boron Injection Flow Rate Verification" is active, for the Positive Displacement Pump. INITIAL Figure 1.
- 5.5 If the Boric Acid Transfer Pump(s) are utilized VERIFY 14811-1, "Boric Acid Transfer Pumps and Discharge Check Valves Inservice Test" is active. INITIAL Figure 1.
- 5.6 If the Centrifugal Charging Pump(s) is utilized, VERIFY 14808-1, "Centrifugal Charging Pump And Check Valve Inservice Test" is active. INITIAL Figure 1.
- 5.7 COMPLETE Figure 1 by placing initials in the appropriate blocks for the boron injection flow path. Power operated valves must be operable and local manual valves must be open.
- 5.8 Using Figure 1, ENSURE a complete flow path from borated water source through operable pump to RCS exists.

6.0 ACCEPTANCE CRITERIA

The valves in the boron injection flow path shown on Figure 1 were found to be in the required status to provide at least one flow path of borated water to the RCS. All required surveillances are active.

7.0 EVALUATION AND REVIEW

7.1 TEST PURPOSE

- Surveillance
- Maintenance Retest
- Other (explain) _____

7.2 Results obtained through performance of this procedure meet ACCEPTANCE CRITERIA of Section 6.0.

- YES NO

7.2.1 If NO was checked, NOTIFY the USS and REFER to Technical Specification 3.1.2.1.

7.2.2 Comments (include any abnormal conditions and corrective actions taken): _____

USS notified of Test Completion and Results


	_____/_____/_____ Initials Date Time
Test Completed By:	_____/_____/_____ Signature Date Time
Supervisory Review:	_____/_____/_____ Signature Date Time

8.0 REFERENCES

8.1 P&ID's

- 8.1.1 1X4DB114 Chemical and Volume Control System
- 8.1.2 1X4DB116-1 Chemical and Volume Control System
- 8.1.3 1X4DB116-2 Chemical and Volume Control System
- 8.1.4 1X4DB118 Chemical and Volume Control System
- 8.1.5 1X4DB119 Safety Injection System
- 8.1.6 1X4DB121 Safety Injection System
- 8.2 VEGP Technical Specifications

END OF PROCEDURE TEXT



NOTE: Initial in appropriate box to indicate correct status. (OPERABLE for power operated valves OPEN for manual valves)

Completed by _____
Date _____

FIGURE 1

Date Issued:

3-1-90

Standing Order
VOGTLE ELECTRIC GENERATING PLANT



Georgia Power

Order No.:

1-90-05

Procedure Ref.:

Unit 1

Title: EMERGENCY BORATION FLOWPATH

05-55-90

Approved:

[Signature]
Operations Supervisor

[Signature]
Operations Superintendent

During the outage extensive work and clearances on CVCS will require special attention to our required Emergency Boration Flow Path.

In Mode 5 and 6 keep a laminated figure from 14406-1 at the RO desk. Mark-up each time you change the flowpath you are maintaining and copy the figure to the SSS.

INFORMATION ONLY

FOR INFORMATION ONLY

PROCEDURE NO. VEGP	27563-C	REVISION 2	PAGE NO. 2 of 75
-----------------------	---------	---------------	---------------------

1.0 PURPOSE

The purpose of this procedure is to verify the control system functions. This procedure is not intended to verify the calibration of the devices within the panel.

2.0 PRECAUTIONS AND LIMITATIONS

2.1 If only portions of the procedure are required:

2.1.1 Contact the Maintenance Foreman.

2.1.2 Use only the steps that apply.

2.1.3 Document the steps used in the comments section of the "Completion" or "Data" sheet.

2.1.4 N/A the steps that were not used.

2.2 Steps in this Procedure may be performed out of sequence only:

2.2.1 With prior approval of the Maintenance Foreman.

2.2.2 If they do not violate the intent of the Procedure.

2.2.3 Are documented in the "Comments" section of the "Completion" Sheet.

2.3 Maintenance area cleanliness in accordance with Procedure 21427-C, "Maintenance Cleanliness And Housekeeping Control".

3.0 PREREQUISITES AND INITIAL CONDITIONS

3.1 Prior to beginning work, notify QC if:

3.1.1 Hold points are indicated on the "Completion" AND/OR "Data Sheet".

3.1.2 The MWO/Work Package has a QC hold point.

3.2 Starting air pressure must be available to the control panel.

3.3 AC and DC power to the panel must be available.

3.4 Fuel supply to the engine is isolated and tagged out.

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	3 of 75

- 3.5 DG breaker is racked out to prevent inadvertent closure.
- 3.6 Local/Remote switch is in the remote position.
- 3.7 Both starting air receiver are above the low alarm set point.
- 4.0 TEST SET-UP MAINTENANCE MODE AND ENGINE ROLL CHECKOUT
- 4.1 TEST SET-UP
- 4.1.1 */* Verify all prerequisites and Initial conditions have been met.
- 4.1.2 */* Notify Shift supervisor of work to be performed.
- 4.1.3 */* Verify all applicable equipment is fully isolated and tagged in accordance with procedure 00304-C, "Equipment clearance and tagging".
- 4.1.4 */* Disconnect and lift instrument, control and power leads from the equipment as required.
- a. Ensure each wire is marked so that it can be uniquely identified with its termination point.
 - b. Record their removal by wire number and termination point in the "Power and Signal Removal/Replacement Data" Sheet.
 - c. To install jumpers or lift wires, other than those directly associated with the equipment tag number(s) or scheme number(s) listed on the Work Order.
 - (1) Notify Shift Supervisor.
 - (2) Comply with his instructions.

NOTE

The following procedural steps are intended to prepare the engine control system for actual functional tests. All numbers shown in () are wire numbers.

- 4.1.5 Trip - "Low Pressure Lube Oil":
- 4.1.5.1 */* Disconnect incoming tubing at bulkhead fitting E10-A in panel and cap bulkhead fitting.
- 4.1.5.2 */* Disconnect incoming tubing at bulkhead fitting E-10B in panel and cap bulkhead fitting.
- 4.1.5.3 */* Disconnect incoming tubing at bulkhead fitting E-10C in panel and cap bulkhead fitting.
- 4.1.6 Trip - "Low Pressure Turbocharger Lube oil":
- 4.1.6.1 */* Disconnect incoming tubing at bulkhead fitting E-92 in panel and cap bulkhead fitting.
- 4.1.7 Trip - "Low Pressure Jacket Water":
- 4.1.7.1 */* Disconnect incoming tubing at bulkhead fitting E-14 in panel and cap bulkhead fitting.
- 4.1.8 Open the following sliding link terminals:
- 4.1.8.1 */* A-Bank Starting Air Valve.
Terminals E5 (4) and E4 (2).
- 4.1.8.2 */* B-Bank Starting Air Valve.
Terminals L5 (105) and L4 (102).
- 4.1.8.3 Field Flash, Exciter Reg Enable.
Terminals E19 (53), E22 (56), E17 (51), and E21 (55).
- 4.1.8.4 */* Preset V.R. and Gov.:
Terminals E23 (57), E18 (52), and E24 (59).
- 4.1.8.5 */* Ready to Load, DG Brkr.:
Terminals F5 (77) and F6 (78).
- 4.1.8.6 */* Ready to Load, HVAC Sys.:
Terminals E57 (46) and E58 (47).
- 4.1.8.7 */* Ready to Load, Spare.
Terminals E59 (48) and E60 (49).
- 4.1.8.8 */* Start, Spare.
Terminals F1 (73) and F2 (74).

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	5 of 75

- 4.1.8.9 Stop, Spare.
/ Terminals F3 (75) and F4 (76).
- 4.1.8.10 Pre-position Gov and V.R.
/ Terminals L30 (170) and L31 (171).
- 4.1.8.11 186C Trip Delay
Terminals L32 (172) and L33 (173).
- 4.1.8.12 Field Flash, Exciter Reg Enable.
/ Terminals L23 (153), L20 (141), L21 (144), and L24 (155).
- 4.1.8.13 Trip 52G.
/ Terminals L51 (159) and L52 (160).
- 4.1.8.14 Emergency Stop.
/ Terminals L53 (164) and L54 (165).
- 4.1.8.15 Running, Spare.
/ Terminals L55 (166) and L56 (167).
- 4.1.8.16 Running, Spare.
/ Terminals L57 (168) and L58 (169).
- 4.1.8.17 Overspeed, Spare.
/ Terminals L59 (179) and L60 (180).
- 4.1.8.18 Running W/Delay.
/ Terminals L35 (175) and L36 (176).
- 4.1.8.19 Ready to Load - HVAC System.
/ Terminals L9 (137) and L10 (138).
- 4.1.8.20 Ready to Load - Spare.
/ Terminals L11 (139) and L12 (140).
- 4.1.8.21 Emergency Stop.
/ Terminals L14 (336) and L15 (337).
- 4.1.8.22 ERF Computer.
/ Terminals L49 (S4B1) and L50 (S4B2).
- 4.1.8.23 Emergency Stop Annunciation.
/ Terminals L25 (79-180) and L26 (90-180).
- 4.1.8.24 CC Fan #1.
/ Terminals C3 (244) and C9 (245).

PROCEDURE NO.	REVISION	PAGE NO.
VEGP	27563-C	2 6 of 75
4.1.8.25 <u>**</u>	CC Fan #2. Terminals C5 (246) and C11 (247).	
4.1.8.26 <u>**</u>	Generator Space Heater Control. Terminals C7 (239) and C8 (240).	
4.1.8.27 <u>**</u>	Running Contacts. Terminals G3 (253), G4 (254), G5 (255), G6 (256), G7 (257), G8 (258), G9 (259), G10 (260), G11 (161), and G12 (162).	
4.1.8.28 <u>**</u>	Running W/Delay Contacts. Terminals G13 (263), G14 (264), G15 (265), G16 (266), G17 (267), G18 (268), G19 (269), G20 (270), G21 (271), G22 (272), G23 (273) and G24 (274).	
4.1.8.29 <u>**</u>	Loss of DC Annunciation. Terminals H1 (275) and H2 (276).	
4.1.8.30 <u>**</u>	Mechanical Trouble Alarm. Terminals H19 (298) and H20 (299).	
4.1.8.31 <u>**</u>	Lockout Alarm. Terminals H3 (277) and H4 (278).	
4.1.8.32 <u>**</u>	Failed to Start. Terminals H7 (281) and H8 (282).	
4.1.8.33 <u>**</u>	Unit Available Local Control. Terminals H9 (283) and H10 (284).	
4.1.8.34 <u>**</u>	Unit Available. Terminals H11 (285), H12 (286), H13 (287), H14 (288), H15 (289), and H16 (290).	
4.1.8.35 <u>**</u>	Alarm. Terminals H17 (296) and H18 (297).	
4.1.8.36 <u>**</u>	Loss of DC Power. Terminals A35 (612) and A36 (613).	
4.1.8.37 <u>**</u>	DG Brkr Inop. Terminals F7 (79) and F8 (80).	
4.1.9 <u>**</u>	Open toggle switches to de-energize hourmeter.	

PROCEDURE NO. VEGP	REVISION 27563-C	PAGE NO. 2 7 of 75
4.1.10	A-Bank Starting Air Valve:	-
<u>4.1.10.1</u> */*	At on-engine "EJBA" Junction Box, disconnect engine wire number 4 and tape wire end.	
4.1.11	B-Bank Starting Air Valve:	
<u>4.1.11.1</u> */*	At on-engine "EJBB" Junction Box, disconnect engine wire number 105 and tape wire end.	
<u>4.1.12</u> */*	Verify that all circuit breakers are closed.	
<u>4.1.13</u> */*	Verify 50 psi at control air pressure gauge.	
<u>4.1.14</u> */*	Verify 125 vdc across circuit breakers CB-1 and CB-2, CB-3 and CB-4.	
4.1.15	Manual Permissive Start - "A" Side:	
4.1.15.1	Jumper terminals E49 (3) and E50 (11).	
4.1.16	Manual Permissive Start - "B" Side:	
4.1.16.1	Jumper terminals L37 (106) and L42 (110).	
4.2	MAINTENANCE MODE AND ENGINE ROLL CHECKOUT	
<u>4.2.1</u> */*	Jumper terminals L45 (101) and L48 (129), Control Room permissive for maintenance mode.	
4.2.2	Lockout Alarm & Unit Available.	
<u>4.2.2.1</u> */*	Disconnect jumper across terminals H4 (278) and H12 (286) and verify:	
<u>4.2.2.2</u> */*	Open contact across terminals H3 (277) and H4 (278).	
<u>4.2.2.3</u> */*	Open contact across terminals H9 (283) and H10 (284).	
<u>4.2.2.4</u> */*	Open contact across terminals H11 (285) and H12 (286).	
<u>4.2.2.5</u> */*	Contact closure across terminals H13 (287) and H14 (288).	
<u>4.2.2.6</u> */*	Contact closure across terminals H15 (289) and H16 (290).	

PROCEDURE NO.	REVISION	PAGE NO
VEGP 27563-C	2	8 of 75
4.2.3	Depress maintenance mode pushbutton and verify:	
<u>4.2.3.1</u> */*	Engine shutdown cylinder is extended.	
<u>4.2.3.2</u> */*	Maintenance lockout alarm is energized.	
<u>4.2.3.3</u> */*	Unit available emergency status light is deenergized.	
<u>4.2.3.4</u> */*	Group I pressure gauge indicates 0 psi.	
<u>4.2.3.5</u> */*	The engine barring device lockout pin can be removed.	
4.2.3.6	The stopping light is energized.	
<u>4.2.3.7</u> */*	Contact closure across terminals B21 (565) and B22 (566).	
<u>4.2.3.8</u> */*	Contact closure across terminals H3 (277) and H4 (278).	
<u>4.2.3.9</u> */*	Contact closure across terminals H9 (283) and H10 (284).	
<u>4.2.3.10</u> */*	Contact closure across terminals H11 (285) and H12 (286).	
<u>4.2.3.11</u> */*	Open contact across terminals H13 (287) and H14 (288).	
<u>4.2.3.12</u> */*	Open contact across terminals H15 (289) and H16 (290).	
<u>4.2.4</u> */*	Reconnect jumper across H4 (278) and H12 (286).	
4.2.5	Push engine roll pushbutton and verify:	
<u>4.2.5.1</u> */*	125 vdc across terminal E4 (2) and E5 (4), "A" side starting valve.	
4.2.6	Push normal start pushbutton and verify:	
<u>4.2.6.1</u> */*	No voltage across terminals E4 (2) and E5 (4), "A" side starting air valve.	

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	9 of 75
<u>4.2.6.2</u> <u>*/*</u>	No voltage across terminals L4 (102) and L5 (105), "B" side starting air valve.	
<u>4.2.7</u> <u>*/*</u>	Disconnect wire 564 (tape wire) at PS-46N and verify:	
<u>4.2.7.1</u> <u>*/*</u>	Relay R35 is de-energized.	
<u>4.2.7.2</u> <u>*/*</u>	Open contact across terminals B21 (565) and B22 (566).	
<u>4.2.7.3</u> <u>*/*</u>	Maintenance lockout alarm is de-energized.	
4.2.8	Release engine barring device and verify:	
<u>4.2.8.1</u> <u>*/*</u>	Barring device engaged alarm energized.	
<u>4.2.8.2</u> <u>*/*</u>	Contact closure across terminals B27 (590) and B28 (591).	
<u>4.2.8.3</u> <u>*/*</u>	Relay R35 is energized.	
4.2.9	Push return to operational pushbutton:	
4.2.9.1	Push engine roll pushbutton and verify:	
<u>4.2.9.1.1</u> <u>*/*</u>	125 vdc across terminals E4 (2) and E5 (4), "A" side starting valve.	
4.2.9.2	Push normal start pushbutton and verify:	
<u>4.2.9.2.1</u> <u>*/*</u>	No voltage across terminals E4 (2) and E5 (4), "A" side starting air valve.	
<u>4.2.9.2.2</u> <u>*/*</u>	No voltage across terminals L4 (102) and L5 (105), "B" side starting air valve.	
4.2.10	Lockout engine barring device and verify:	
<u>4.2.10.1</u> <u>*/*</u>	Barring device engaged alarm is de-energized.	
<u>4.2.10.2</u> <u>*/*</u>	Open contact across terminals B27 (590) and B28 (591).	

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	10 of 75
<u>4.2.10.3</u> <u>*/*</u>	Relay R35 is de-energized.	
<u>4.2.11</u> <u>*/*</u>	Reconnect wire 564 at pressure switch PS-46N, Maintenance lockout alarm and verify:	
<u>4.2.11.1</u> <u>*/*</u>	Relay R35 is energized.	
<u>4.2.11.2</u> <u>*/*</u>	Maintenance Lockout alarm is energized.	
4.2.12	Push return to operational pushbutton and verify:	
<u>4.2.12.1</u> <u>*/*</u>	Engine shutdown cylinder is retracted.	
<u>4.2.12.2</u> <u>*/*</u>	Group I pressure gauge indicates 60 psi.	
<u>4.2.12.3</u> <u>*/*</u>	Maintenance lockout alarm is de-energized.	
<u>4.2.12.4</u> <u>*/*</u>	Unit available emergency status light is energized.	
<u>4.2.12.5</u> <u>*/*</u>	The engine barring device lockout pin is in the locked position.	
<u>4.2.12.6</u> <u>*/*</u>	The stopping light is de-energized.	
<u>4.2.12.7</u> <u>*/*</u>	Ensure barring device is retracted.	
<u>4.2.12.8</u> <u>*/*</u>	Locking pin is installed.	
4.2.13	Push engine roll pushbutton and verify:	
<u>4.2.13.1</u> <u>*/*</u>	No voltage across terminals E4 (2) and E5 (4), "A" side starting air valve.	
4.2.14	Open circuit breakers CB-1 and CB-2 and verify:	
<u>4.2.14.1</u> <u>*/*</u>	No voltage across solenoid valve Sol 202-6A ("A" circuit DC Power Solenoid), wires 1 and 2.	
<u>4.2.14.2</u> <u>*/*</u>	"A" power available light is de-energized.	

PROCEDURE NO. VEGP	REVISION 27563-C	PAGE NO. 2 11 of 75
<u>4.2.14.3</u> */*	Engine control panel "A" failure (pos 8-2) alarm is energized.	
<u>4.2.14.4</u> */*	Contact closure across terminals A17 (466) and A18 (467).	
<u>4.2.15</u> */*	Remove timer TD-1B from relay socket, field flash timer.	
4.2.16	Push normal start push button and verify:	
<u>4.2.16.1</u> */*	125 vdc across terminals L4 (102) and L5 (105), starting air valve for 5 seconds.	
<u>4.2.16.2</u> */*	Failure to start alarm is energized after 5 seconds.	
<u>4.2.16.3</u> */*	Relay R1 is de-energized.	
<u>4.2.16.4</u> */*	Contact closure across terminals H7 (281) and H8 (282).	
<u>4.2.16.5</u> */*	Contact closure across terminals K33 (581) and K34 (582).	
<u>4.2.16.6</u> */*	Relay R35 is energized.	
<u>4.2.16.7</u> */*	Horn is energized.	
4.2.17	Push the annunciator silent, acknowledge and reset pushbutton and verify:	
<u>4.2.17.1</u> */*	Horn is de-energized.	
<u>4.2.17.2</u> */*	Open contact across terminals H7 (281) and H8 (282).	
<u>4.2.17.3</u> */*	Relay R35 is de-energized.	
<u>4.2.17.4</u> */*	Failed to start alarm is de-energized.	
4.2.18	Connect frequency generator to terminals L7 (118) and L8 (119). Push normal start pushbutton again and within 5 seconds turn on generator to 490 Hz (450 RPM) and verify:	

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	12 of 75

- 4.2.18.1 */* Contact closure across terminals L35 (175) and L36 (176) after approx. 60 sec delay.
- 4.2.18.2 */* Contact closure across terminals L32 (172) and L33 (173) after approx. 60 sec delay.
- 4.2.18.3 */* No voltage across terminal L4 (102) and L5 (105), starting air valve.
- 4.2.18.4 */* Contact closure across terminals L55 (166) and L56 (167).
- 4.2.18.5 */* Open contact across terminals L57 (168) and L58 (169).
- 4.2.18.6 */* Unit running light is energized.
- 4.2.18.7 */* Failed to start alarm remains de-energized.
- 4.2.18.8 */* Closure across terminals L23 (153) and L21 (144), field flash pressure switch.
- 4.2.18.9 */* Open circuit across terminal L24 (155) and L23 (153), exciter reg enable.
- 4.2.18.10 */* Contact closure across terminals L49 (S4B1) and L50 (S4B2), ERF computer.
- 4.2.18.11 */* Relays R1, R1AUX1, R2, R2AUX2 and R8 are energized.
- 4.2.18.12 */* Contact closure across terminals C3 (244) and C9 (245), CC Fan #1.
- 4.2.18.13 */* Contact closure across terminals C5 (246) and C11 (247), CC Fan #2.
- 4.2.18.14 */* Contact closure across terminals G3 (253) and G4 (254).
- 4.2.18.15 */* Contact closure across terminals G5 (255) and G6 (256).
- 4.2.18.16 */* Open contact across terminals G7 (257) and G8 (258).
- 4.2.18.17 */* Open contact across terminals G9 (259) and G10 (260).

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	13 of 75
<u>4.2.18.18</u> */*	Open contact across terminals G11 (261) and G12 (262).	
<u>4.2.18.19</u> */*	Contact closure across terminals G13 (263) and G14 (264).	
<u>4.2.18.20</u> */*	Contact closure across terminals G15 (265) and G16 (266).	
<u>4.2.18.21</u> */*	Contact closure across terminals G17 (267) and G18 (268).	
<u>4.2.18.22</u> */*	Open contact across terminal G19 (269) and G20 (270).	
<u>4.2.18.23</u> */*	Open contact across terminals G21 (271) and G22 (272).	
<u>4.2.18.24</u> */*	Open contact across terminals G23 (273) and G24 (274).	
<u>4.2.19</u> */*	Push Maintenance Pushbutton and verify:	
<u>4.2.19.1</u> */*	Maintenance mode alarm remains de-energized.	
<u>4.2.20</u> */*	Push local stop push button and turn off frequency generator and verify:	
<u>4.2.20.1</u> */*	Open circuit across terminals L23 (153) and L21 (144), field flash pressure switch.	
<u>4.2.20.2</u> */*	Engine shutdown cylinder is extended and verify that there is no air leakage at the pneumatic cylinder.	
<u>4.2.20.3</u> */*	After approx. 120 sec, verify engine shutdown cylinder is retracted and vented.	
<u>4.2.20.4</u> */*	Open contact across terminals L55 (166) and L56 (167).	
<u>4.2.20.5</u> */*	Contact closure across terminals L57 (168) and L58 (169).	
<u>4.2.20.6</u> */*	Unit running light is de-energized.	
<u>4.2.20.7</u> */*	Open contact across terminals L35 (175) and L36 (176).	

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	14 of 75

- 4.2.20.8
/ Open contact across terminals L32 (172) and L33 (173).
- 4.2.20.9
/ Open contact across terminals L49 (S4B1) and L50 (S4B2), ERF computer.
- 4.2.21 Push maintenance pushbutton and verify:
- 4.2.21.1
/ Maintenance mode alarm is energized.
- 4.2.22 Push return to operational pushbutton and verify:
- 4.2.22.1
/ Maintenance mode alarm is de-energized.
- 4.2.23 Install timer TD-1B into Relay Socket, field flash timer.
- 4.2.24 Momentarily jumper terminals L37 (106) and L43 (104), remote emergency start and verify:
- 4.2.24.1
/ 125 VDC across terminals L4 (102) and L5 (105), starting air solenoid.
- 4.2.24.2 Push maintenance mode pushbutton and verify:
- 4.2.24.2.1
/ Maintenance mode alarm indication remains de-energized.
- 4.2.24.3
/ Contact closure across terminals L23 (153) and L21 (144), field flash.
- 4.2.24.4
/ Turn on frequency generator (setting should be at 490 Hz). Check that relays R1, R1A and R2 are energized, if not, manually set relays.
- 4.2.24.5
/ Closure across Terminals L23 (153) and L21 (144), field flash pressure switch.
- 4.2.24.6
/ Safety injection signal light is energized.
- 4.2.24.7
/ Shutdown system active light de-energized.
- 4.2.24.8
/ No voltage across terminal L4 (102) and L5 (105), starting air solenoid.

- 4.2.24.9
*/
*/ Verify jumper across terminals L37 (106) and L43 (104) is removed.
- 4.2.24.10
*/
*/ Emergency start alarm is energized.
- 4.2.24.11
*/
*/ Contact closure across terminals B33 (601) and B34 (602), emergency start remote annunciator.
- 4.2.24.12
*/
*/ Contact closure across terminals L22 (151) and L24 (155), exciter reg enable.
- 4.2.25 Push normal stop push button and verify:
- 4.2.25.1
*/
*/ The stopping light remains de-energized.
- 4.2.26 Disconnect incoming tubing at bulkhead fitting E-18, high temp lube oil shutdown, after 60 seconds from completing step 24 above and verify:
- 4.2.26.1
*/
*/ Group I pressure gauge reads below 25 psi.
- 4.2.26.2
*/
*/ Engine shutdown cylinder is not extended.
- 4.2.26.3
*/
*/ Trip high temp lube oil alarm is energized.
- 4.2.26.4
*/
*/ The stopping light is not energized.
- 4.2.26.5
*/
*/ Contact closure across terminals J9 (426) and J10 (427), trip high temp lube oil remote annunciator.
- 4.2.26.6
*/
*/ Contact closure across terminals 6 and 7 at annunciator pos 5-1, trip high temp lube oil, spare contact.
- 4.2.27
*/
*/ Re-connect incoming tubing at bulkhead fitting E-18, high temp lube oil shutdown and verify:
- 4.2.27.1
*/
*/ Group I pressure gauge reads 60 PSI.
- 4.2.27.2
*/
*/ Trip high temp lube oil alarm is de-energized.
- 4.2.27.3
*/
*/ Open contact across terminals J9 (426) and J10 (427), trip high temp lube oil remote annunciator.

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	16 of 75

- 4.2.27.4
/ Open contact across terminals 6 and 7 at annunciator pos 5-1.
- 4.2.28 Push reset from local pushbutton. Remove plug from bulkhead fitting E-92, trip low pressure turbo oil and turn off frequency generator and verify:
- 4.2.28.1
/ The stopping light is energized.
- 4.2.28.2
/ Trip low Pressure turbo oil alarm is energized.
- 4.2.28.3
/ Contact closure across terminals J21 (457) and J22 (458). Trip low press turbo oil remote annunciator.
- 4.2.28.4
/ Contact closure across terminals 10 and 11 at annunciator pos 5-2, trip low press turbo oil spare contact.
- 4.2.28.5
/ Engine shutdown cylinder is extended.
- 4.2.29 Manually transfer R10B relay contacts at the same time, push maintenance pushbutton and verify:
- 4.2.29.1
/ Maintenance mode alarm indication remains de-energized.
- 4.2.30
/ Reinstall plug on bulkhead fitting E-92. Trip low pressure turbo oil and jumper contact SS3B wires 101 and 123, ready to load, at "B: side speed transmitter and jumper wires 123 and 124 at relay UVR1B, under voltage relay and verify:
- 4.2.30.1
/ Relay R-11B is energized.
- 4.2.30.1.1
/ Contact closure across terminals L9 (137) and L10 (138), running-HVAC system.
- 4.2.30.1.2
/ Contact closure across terminals L11 (139) and L12 (140), running-spare.
- 4.2.30.1.3
/ Contact closure across terminals F5 (77) and F6 (78), ready to load - DG breaker.

VEGP

27563-C

2

17 of 75

- 4.2.30.1.4 Ready to load light is energized.
/
- 4.2.30.2 Remove jumper at SS3B contact, wires 101 and 123,
/ ready to load at "B: side speed transmitter and
remove jumper across wires 123 and 124 and verify:
- 4.2.30.2.1 Open contact across terminals L9 (137) and L10
/ (138), running-HVAC system.
- 4.2.30.2.2 Open contact across terminals L11 (139) and L12
/ (140), running-spare.
- 4.2.30.2.3 Open contact across terminals F5 (77) and F6 (78),
/ ready to load-DG breaker.
- 4.2.30.2.4 Ready to load light is de-energized.
/
- 4.2.31 Release Emergency Start Button and turn on
frequency generator and verify:
- 4.2.31.1 No voltage across terminal L4 (102) and L5 (105),
/ starting air solenoid.
- 4.2.31.2 Relay R5B is energized.
/
- 4.2.32 Trip overspeed trip valves on engine and then turn
off frequency generator and verify:
- 4.2.32.1 Relay R23B is energized.
/
- 4.2.32.2 Contact closure across terminals L51 (159) and L52
/ (160), trip 52G.
- 4.2.32.3 Contact closure across terminals L53 (164) and L54
/ (165), emergency stop.
- 4.2.32.4 Contact closure across terminals L59 (179) and L60
/ (180), overspeed-spare.
- 4.2.32.5 Contact closure across terminals L14 (336) and L15
/ (337), emergency stop.
- 4.2.32.6 Emergency stop light energized.
/

VEGP

27563-C

2

18 of 75

- 4.2.32.7 The stopping light energized. -
/
- 4.2.32.8 Pressure at cylinder port of solenoid 3B.
/
- 4.2.32.9 Unit available emergency status light is
/ de-energized.
- 4.2.32.9.1 Momentarily jumper pressure switch PS-23N, wires
/ 225 and 226 and note no change in light status.
- 4.2.32.10 Overspeed trip alarm is energized.
/
- 4.2.32.11 Contact closure across terminal A9 (442) and A10
/ (443), overspeed remote annunciator.
- 4.2.32.12 Relay R35 is energized, locked out alarm.
/
- 4.2.32.12.1 Momentarily open sliding link F11 (79)
 and reset annunciator and verify:
- 4.3.32.12.1.1 Relay R35 remains energized, locked out alarm.
/
- 4.2.32.12.1.2 Disabled non-reset of emergency trip alarm is
/ de-energized.
- 4.2.32.13 Push normal start pushbutton and verify:
- 4.2.32.13.1 No voltage across terminals E5 (4) and E4 (2),
/ A-Bank starting air valve.
- 4.2.32.13.2 No voltage across terminals L5 (105) and L4 (102),
/ B-Bank starting air valve.
- 4.2.33 Verify that break glass cover is reinstalled on
/ emergency start pushbutton.
- 4.2.34 Depress reset from LOCA pushbutton.
- 4.2.35 Reset overspeed trip valves located on engine and
 verify:
- 4.2.35.1 Open contact across terminals L59 (179) and L60
/ (180), overspeed-spare.

- 4.2.35.2
*/
*/ Overspeed Trip alarm is de-energized.
- 4.2.35.3
*/
*/ Open contact across terminals A9 (442) and A10 (443).
- 4.2.36 Push emergency stop reset pushbutton and verify:
- 4.2.36.1
*/
*/ Relay R23B is de-energized.
- 4.2.36.2
*/
*/ Open contact across terminals L51 (159) and L52 (160), trip 52G.
- 4.2.36.3
*/
*/ Open contact across terminals L53 (164) and L54 (165), emergency stop.
- 4.2.36.4
*/
*/ Open contact across terminals L14 (336) and L15 (337), emergency stop.
- 4.2.36.5
*/
*/ Emergency stop light light de-energized.
- 4.2.36.6 The stopping light de-energized.
- 4.2.36.7
*/
*/ Relay R35 is de-energized, locked out alarm.
- 4.2.37 Jumper across terminals L39 (101) and L38 (113), loss of offsite power and verify:
- 4.2.37.1
*/
*/ 125 VDC across terminals L4 (102) and L5 (105), starting air solenoid.
- 4.2.37.2
*/
*/ DG auto start signal light is energized.
- 4.2.38 Remove jumper across terminals L39 (101) and L38 (113), loss of offsite power and verify:
- 4.2.38.1
*/
*/ No voltage across terminals L4 (102) and L5 (105), starting air solenoid.
- 4.2.38.2
*/
*/ DG auto start signal light is de-energized.
- 4.2.39 Manually transfer R6B relay contacts and at the same time push emergency stop reset button and verify:

- 4.2.39.1
*/
*/
Contact closure across terminals L51 (159) and L52 (160).
- 4.2.39.2
*/
*/
Release emergency stop reset button and then R6B relay contacts and verify:
- 4.2.39.2.1
*/
*/
Relay R23B is energized.
- 4.2.39.2.2
*/
*/
Contact closure across terminals L51 (159) and L52 (160).
- 4.2.39.2.3
*/
*/
Contact closure across terminals L53 (164) and L54 (165).
- 4.2.40
Push emergency stop reset button to reset relay R23B.
- 4.2.41
Push emergency stop pushbutton and verify:
- 4.2.41.1
*/
*/
Disabled non-reset of emergency trip alarm is energized.
- 4.2.41.2
*/
*/
Contact closure across terminals A33 (503) and A34 (504), emergency trip-remote annunciator.
- 4.2.41.3
*/
*/
Relay R35 is energized, locked out alarm.
- 4.2.42
Push emergency stop reset pushbutton and verify:
- 4.2.42.1
*/
*/
Disabled non-reset of emergency trip alarm is de-energized.
- 4.2.42.2
*/
*/
Open contact across terminals A33 (503) and A34 (504), emergency trip-remote annunciator.
- 4.2.42.3
*/
*/
Relay R35 is de-energized, locked out alarm.
- 4.2.43
Disconnect frequency generator from terminals L7 (118) and L8 (119).
- 4.2.44
*/
*/
Disconnect jumper across terminals L45 (101) and L48 (129), control room permissive for maintenance mode:
- 4.2.45
Close Circuit Breakers CB-1 and CB-2, and verify:

VEGP

27563-C

2

21 of 75

- 4.2.45.1
/ 125 vdc across solenoid valve Sol 202-6A, "A" circuit DC power, wires 1 and 2.
- 4.2.45.2
/ "A" power available light is energized.
- 4.2.45.3
/ Reset annunciator and verify at engine control power A failure (pos 8-2) alarm is de-energized.
- 4.2.45.4
/ Open contact across terminals A17 (466) and A18 (467).
- 4.2.46 Open circuit breakers CB-3 and CB-4 and verify:
- 4.2.46.1
/ No voltage across solenoid valve Sol 202-6B, "B" circuit DC power, wires 101 and 102.
- 4.2.46.2
/ "B" power available light is de-energized.
- 4.2.46.3
/ Engine control power B Failure (pos 9-2) alarm is energized.
- 4.2.46.4
/ Contact closure across terminals A19 (469) and A20 (470).
- 4.2.47 Remove timer TD-1A from socket, field flash timer:
- 4.2.48 Push normal start pushbutton and verify:
- 4.2.48.1
/ 125 vdc across terminal E4 (2) and E5 (4), solenoid for 5 seconds.
- 4.2.48.2
/ Failure to start alarm is energized after 5 seconds.
- 4.2.49 Connect frequency generator to terminals E7 (20) and E8 (21). Push normal start pushbutton again and within 5 sec turn on generator to 490 Hz (450 RPM) and verify:
- 4.2.49.1
/ No voltage across terminal E4 (2) and E5 (4), starting air solenoid.
- 4.2.49.2
/ Closure across panel terminals E19 (53) and E17 (51), field flash pressure switch.
- 4.2.49.3
/ Open circuit across terminals E21 (55) and E19 (53), exciter reg enable.

VEGP

27563-C

2

22 of 75

- 4.2.49.4
*/
*/ Contact closure across terminals F1 (73) and F2 (74), start signal for customer's use.
- 4.2.49.5
*/
*/ Starting light is energized, for 5 seconds.
- 4.2.49.6
*/
*/ Relay R1 is energized, run/stop relay.
- 4.2.49.7
*/
*/ The running light is energized.
- 4.2.50
Disconnect incoming tubing line E-19, high temperature main bearing shutdown, to allow the system to shutdown, then turn off frequency generator and verify:
- 4.2.50.1
*/
*/ Engine shutdown cylinder is extended for approximately 2 minutes.
- 4.2.50.2
*/
*/ Closure across terminals E21 (55) and E19 (53), exciter reg enable after approx 2 minutes.
- 4.2.50.3
*/
*/ Trip high temperature engine main bearing alarm is energized.
- 4.2.50.4
*/
*/ Open circuit across terminals E19 (53) and E17 (51), field flash pressure switch.
- 4.2.50.5
*/
*/ Relays R1, R1 aux, and R2 are reset.
- 4.2.50.6
*/
*/ Contact closure across terminals L30 (170) and L31 (171) for approximately 2 minutes, pre-position gov and V.R.
- 4.2.50.7
*/
*/ Contact closure across terminals F3 (75) and F4 (76) for approximately 2 minutes, stop signal.
- 4.2.50.8
*/
*/ Unit running light is de-energized.
- 4.2.50.9
*/
*/ Unit stopping light is energized for approximately 2 minutes.
- 4.2.50.10
*/
*/ Contact closure across terminals A3 (432) and A4 (433), main bearing trip-remote annunciator.
- 4.2.50.11
*/
*/ Contact closure across terminals 6 and 7 at annunciator pos. 7-1, main bearing Trip.

VEGP

27563-C

2

23 of 75

- 4.2.51 After reconnecting line E-19, main bearing trip, verify:
- 4.2.51.1 Trip high temp engine bearings alarm is de-energized.
/
- 4.2.51.2 Contact is open across terminals A3 (432) and A4 (433), main bearing trip-remote annunciator.
/
- 4.2.51.3 Contact is open across terminals 6 and 7 at annunciator pos 7-1, main bearing trip.
/
- 4.2.52 Install timer TD-1A into relay socket, field flash timer.
- 4.2.53 Momentarily jumper terminals E49 (3) and E51 (7) for remote emergency start and verify:
- 4.2.53.1 125 vdc across terminals E4 (2) and E5 (4), starting air solenoid.
/
- 4.2.53.2 Closure across terminals E19 (53) and E17 (51), field flash pressure switch.
/
- 4.2.53.3 Turn on frequency generator (setting should still be at 490 Hz). Check that relays R1, R1A, and R2 are energized, if not, manually set relay.
/
- 4.2.53.4 Shutdown system active light is de-energized.
/
- 4.2.53.5 No voltage across terminals E4 (2) and E5 (4), starting air solenoid.
/
- 4.2.53.6 Verify jumper across terminals E49 (3) and E51 (7) is removed.
/
- 4.2.53.7 Contact closure across terminals E23 (57) and E18 (52), preset V.R. and gov.
/
- 4.2.54 Disconnect incoming tubing line E68, trip high pressure crankcase and verify:
- 4.2.54.1 Trip high pressure crankcase alarm is energized.
/
- 4.2.54.2 The engine shutdown cylinder is not extended.
/

VEGP

27563-C

2

24 of 75

- 4.2.54.3
*/
*/ Contact closure across terminals A5 (435) and A6 (436), high pressure crankcase remote annunciator.
- 4.2.54.4
*/
*/ Contact closure across terminals 6 and 7 at annunciator pos 8-1, high pressure crankcase spare contact.
- 4.2.55
*/
*/ Reconnect incoming tubing line E-68, trip high pressure crankcase shutdown and verify:
- 4.2.55.1
*/
*/ Trip high pressure crankcase alarm is de-energized.
- 4.2.55.2
*/
*/ Open contact across terminals A5 (435) and A6 (436) high pressure crankcase remove annunciator.
- 4.2.55.3
*/
*/ Open contact across terminals 6 and 7 at annunciator pos 8-1, high pressure crankcase spare contact.
- 4.2.55.4
*/
*/ Engine shutdown cylinder is not extended.
- 4.2.56 Push reset from loca pushbutton and disconnect incoming tubing line E-23H, high engine vibration shutdown. Turn off frequency generator and verify:
- 4.2.56.1
*/
*/ No voltage across terminals E4 (2) and E5 (4), starting air solenoid.
- 4.2.56.2
*/
*/ Closure across terminals E21 (55) and E19 (53), exciter reg. enable, after approximately 2 minutes.
- 4.2.56.3
*/
*/ Engine shutdown cylinder is extended for approx 2 minutes.
- 4.2.56.4
*/
*/ Trip vibration alarm is energized.
- 4.2.56.5
*/
*/ Contact closure across terminals A7 (439) and A8 (440), trip vibration remote annunciator.
- 4.2.56.6
*/
*/ Contact closure across terminals 6 and 7 and annunciator pos 9-1, trip vibration spare contact.
- 4.2.56.7
*/
*/ Open contact across terminals E23 (57) and E18 (52), preset V.R. and gov.

- 4.2.57
*/
*/ Reconnect incoming tubing line E-23-H, trip engine vibration and verify
- 4.2.57.1
*/
*/ Trip vibration alarm is de-energized.
- 4.2.57.2
*/
*/ Open contact across terminals A7 (439) and A8 (440), trip vibration remote annunciator.
- 4.2.57.3
*/
*/ Open contact across terminals 6 and 7 at annunciator pos 9-1, trip vibration spare contact.
- 4.2.58
Release emergency start pushbutton and turn on frequency generator. After 60 seconds, depress and install glass in the emergency start pushbutton. Push reset from loca pushbutton and disconnect plugged tubing line E-14, low pressure jacket water shutdown, and verify:
- 4.2.58.1
*/
*/ Trip low pressure jacket water alarm is energized.
- 4.2.58.2
*/
*/ Engine shutdown cylinder is extended for approximately 2 minutes.
- 4.2.58.3
*/
*/ Contact closure across terminals A27 (494) and A28 (495), trip low pressure jacket water remote annunciator.
- 4.2.58.4
*/
*/ Contact closure across terminals 6 and 7 at annunciator pos 17-1, low pressure jacket water spare contact.
- 4.2.58.5
*/
*/ Contact closure across terminals L51 (159) and L52 (160), for approximately 2 minutes.
- 4.2.58.6
*/
*/ Contact closure across terminals L23 (153) and L20 (141), exciter reg lockout, for approximately 2 minutes.
- 4.2.58.7
*/
*/ Contact closure across terminals E19 (53) and E22 (56), exciter reg lockout, for approximately 2 minutes.
- 4.2.59
*/
*/ Reconnect plug to panel tubing line E14, trip low pressure jacket water. Turn off frequency generator and verify:

- 4.2.59.1
/ Trip low pressure jacket water alarm is de-energized.
- 4.2.59.2
/ Open contact across terminals A27 (494) and A28 (495), trip low pressure jacket water remote annunciator.
- 4.2.59.3
/ Open contact across terminals 6 and 7 at annunciator pos 17-1, low pressure jacket water spare contact
- 4.2.60 Jumper contact SS3A, wires 1 and 27, ready to load, at "A" side speed transmitter, jumper wires 27 and 28 at relay UVR1A, under voltage relay and verify:
- 4.2.60.1
/ Relay R-11A is energized and remove jumper after verification of R-11A and completion of steps 60.2, 3 and 4.
- 4.2.60.2
/ Contact closure across terminals E57 (46) and E58 (47), ready to load, HVAC system.
- 4.2.60.3
/ Contact closure across terminals E59 (48) and E60 (49), ready to load-spare.
- 4.2.60.4
/ Ready to load lights energized.
- 4.2.60.5
/ Open contact across terminals E57 (46) and E58 (47) ready to load - HVAC system.
- 4.2.60.6
/ Open contact across terminal E59 (48) and E60 (49) ready to load - HVAC system.
- 4.2.60.7
/ Ready to load light is de-energized.
- 4.2.60.8
/ Remove Jumper contact SS-3A, wires 1 and 27, ready to load, at "A" side speed transmitter and jumper at wires 27 and 28 at relay UVR1A, under voltage relay.
- 4.2.61 Jumper across terminals E54 (1) and E52 (15), loss of Off-site power.
- 4.2.61.1
/ 125 VDC Across terminals E4 (2) and E5 (4), starting air solenoid.
- 4.2.61.2
/ Contact closure across terminals E23 (57) and E18 (52), preset V.R. and gov.

- 4.2.61.3 DG auto start signal light is energized.
/
- 4.2.62 Remove jumper across terminals E54 (1) and E52
/ (15), loss of Off-site power and verify:
- 4.2.62.1 No voltage across terminals E4 (2) and E5 (4),
/ starting air solenoid.
- 4.2.62.2 Open contact across terminals E23 (57) and E18
/ (52), preset V.R. and gov.
- 4.2.62.3 DG auto start signal light is de-energized.
/
- 4.2.63 Open circuit breakers CB-1 and CB-2 and verify:
- 4.2.63.1 Unit available emergency status light is
/ de-energized.
- 4.2.63.2 Disabled D.C. start power failure alarm energized,
/ energized, pos 24-2.
- 4.2.63.3 Contact closure across terminals K31 (578) and K32
/ (579), disabled D.C. start power failure-remote
annunciation.
- 4.2.64 Close circuit breakers CB-1, 2, 3, and 4 and
verify:
- 4.2.64.1 Unit available emergency status light is
/ energized.
- 4.2.64.2 Disabled D.C. start power failure alarm
/ de-energized, pos. 24-2.
- 4.2.64.3 Open contact across terminals K31 (578) and
/ K32(79), disabled DC start power failure-remote
annunciation.
- 4.2.65 Release emergency start pushbutton and turn on
frequency generator. After approx 60 seconds,
disconnect plug at tubing line E-10A and verify:
- 4.2.65.1 Low oil pressure sensor malfunction alarm
/ energized.
- 4.2.65.2 Contact closure across terminals A15 (463) and A16
/ (464), low oil pressure sensor malfunction, remote
annunciator.

PROCEDURE NO	REVISION	PAGE NO
VEGP 27563-C	2	28 of 75
<u>4.2.65.3</u> */*	Disconnect plug at tubing line E-10B.	
<u>4.2.65.4</u> */*	Trip low pressure lube oil alarm is energized.	
<u>4.2.65.5</u> */*	Low oil pressure sensor malfunction alarm de-energized.	
<u>4.2.65.6</u> */*	Contact closure across terminals J15 (448) and J16 (449), low pressure lube oil trip-remote annunciator.	
<u>4.2.65.7</u> */*	Contact closure across terminals 10 and 11 at annunciator pos 2-2, pressure lube oil trip spare contact.	
<u>4.2.65.8</u> */*	Open contact across terminals A15 (463) and A16 (464), low oil pressure sensor malfunction remote annunciator.	
<u>4.2.65.9</u> */*	Relay R23B is energized - emergency stop.	
4.2.66	Depress emergency start pushbutton and install glass, push reset from loca, turn off frequency generator and reconnect plugs to tubing line E-10A and B, trip low pressure lube oil, depress emergency stop reset and verify:	
<u>4.2.66.1</u> */*	Emergency stop relay R-23B is de-energized.	
<u>4.2.66.2</u> */*	Open contact across terminals J15 (448) and J16 (449), low press lube oil trip - remote annunciator.	
<u>4.2.66.3</u> */*	Open contact across terminals 10 and 11 at annunciator pos 2-2, pressure lube oil trip - spare contact.	
4.2.67	Push normal start pushbutton and turn on frequency generator. After approx 60 seconds, disconnect plug from tubing line E10-B and verify:	
<u>4.2.67.1</u> */*	Low oil pressure sensor malfunction alarm energized.	
<u>4.2.67.2</u> */*	Disconnect plug from tubing line E10-C and verify.	

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	29 of 75
<u>4.2.67.2.1</u> */*	Low oil pressure sensor malfunction alarm de-energized.	
<u>4.2.67.2.2</u> */*	Trip low pressure lube oil shutdown alarm energized.	
<u>4.2.67.2.3</u> */*	Contact closure across terminals L51 (159) and L52 (160), trip 52G, for approximately 2 minutes.	
4.2.68	Turn off frequency generator and reconnect plugs to tubing lines E-10B and C.	
4.2.69	Push normal start pushbutton and turn on frequency generator. After approx 60 seconds, disconnect plug from tubing line E10-C and verify:	
<u>4.2.69.1</u> */*	Low oil pressure sensor malfunction alarm energized.	
<u>4.2.69.2</u> */*	Disconnect plug from tubing line E10-A and verify.	
<u>4.2.69.2.1</u> */*	Low oil pressure lube oil shutdown alarm energized.	
<u>4.2.70</u> */*	Turn off frequency generator and reconnect plugs to tubing lines E10-A and C.	
4.2.71	Push normal start pushbutton and turn on frequency generator. After approx 60 seconds, disconnect tubing line E16-A and verify:	
<u>4.2.71.1</u> */*	High jacket water temp sensor malfunction alarm light is energized.	
<u>4.2.71.2</u> */*	Contact closure across terminals A31 (500) and A32 (501), high jacket water temp sensor malfunction remote annunciator.	
<u>4.2.71.3</u> */*	Disconnect tubing line E16-B, high temp jacket water and verify:	
<u>4.2.71.3.1</u> */*	High jacket water temp sensor malfunction alarm de-energized.	
<u>4.2.71.3.2</u> */*	High jacket water temp shutdown alarm energized.	
<u>4.2.71.3.3</u> */*	Contact closure across terminals J33 (488) and J34 (489), high temp jacket water remote annunciator.	

VEGP

27563-C

2

30 of 75

- 4.2.71.3.4
*/
*/ Contact closure across terminals 6 and 7 at annunciator pos 15-1, high temp jacket water - spare contact.
- 4.2.72
*/
*/ Turn off frequency generator and reconnect tubing lines E16-A and B and verify:
- 4.2.73
*/
*/ Push normal start pushbutton and turn on frequency generator. After approx 60 seconds, disconnect tubing line E16-B and verify:
- 4.2.73.1
*/
*/ Trip high temp jacket water alarm is de-energized.
- 4.2.73.2
*/
*/ Open contact across terminals J33 (488) and J34 (489), trip high temp jacket water - remote annunciator.
- 4.2.73.3
*/
*/ Open contact across terminals 6 and 7 at annunciator pos 15-1, high temp jacket water - spare contact.
- 4.2.73.4
*/
*/ High jacket water temp sensor malfunction alarm.
- 4.2.73.5
*/
*/ Disconnect tubing line E16-C and verify:
- 4.2.73.5.1
*/
*/ High temp jacket water shutdown alarm energized.
- 4.2.74
*/
*/ Turn off frequency generator and reconnect tubing lines E16-B and C.
- 4.2.75
*/
*/ Push normal start pushbutton and turn on frequency generator. After approximately 60 seconds, disconnect tubing line E16-C and verify.
- 4.2.75.1
*/
*/ High jacketwater temp sensor malfunction alarm.
- 4.2.75.2
*/
*/ Disconnect tubing line E16-A and verify.
- 4.2.75.2.1
*/
*/ High jacketwater temp shutdown alarm.
- 4.2.76
*/
*/ Turn off frequency generator and reconnect tubing line E16-A and C.

PROCEDURE NO.	REVISION	PAGE NO
VEGP 27563-C	2	31 of 75
4.2.77	Test bypass. Release emergency start pushbutton after 60 seconds, and then push the test bypass pushbutton to verify.	
<u>4.2.77.1</u> */*	Group I pressure gauge is less than 25 PSI.	
<u>4.2.77.2</u> */*	Bypass test failure light is de-energized.	
4.2.77.3	After Group I pressure gauge pressure returns to 60 PSI, depress emergency start pushbutton and install glass, push reset from loca and then push the test bypass pushbutton and verify.	
<u>4.2.77.3.1</u> */*	Bypass test failure light is energized.	
4.2.78	Lube oil sump tank level. Push lube oil sump tank level pushbutton and verify:	
<u>4.2.78.1</u> */*	Sump tank level indicator is reading correctly by comparing it with the sump tank dip stick. Acceptance criteria: Indicator reading plus or minus 1/8 of full scale.	
4.2.79	Day tank level. Push day tank level pushbutton and verify:	
<u>4.2.79.1</u> */*	Day tank level indicator is reading correctly by comparing it with the day tank dip stick. Acceptance criteria: indicator reading plus or minus 1/8 of full scale.	
4.2.80	Annunciator. Push annunciator test button and verify:	
<u>4.2.80.1</u> */*	All alarm indicators are energized.	
<u>4.2.80.2</u> */*	Disconnect horn by disconnecting wire No. 402 at relay R-15 and tape wire end.	
4.2.81	Push silence, back and Reset to reset annunciator.	

- 4.2.82 Latch R2 relay, Group II Lockout, manually. Observe the annunciator board and determine if conditions displayed are valid. If conditions, either alarmed or cleared, are in the opposite state from what they should be, advise foreman for document and disposition. Then energize each individual alarm as listed below by momentarily either jumpering the sensor, pressure switch, relay or terminal, or disconnect the wire. Remove relays R16, R17, R18 and R20, also lift wire 437 at PS 22N and tape wire end.
- 4.2.82.1 Lube oil filter differential high, PS-4N, pos 6-2.
/
- 4.2.82.1.1 Contact closure across terminals A13 (460) and A14 (461) when alarm is energized and contact open when alarm is de-energized.
/
- 4.2.82.1.2 Relay R38, mechanical trouble alarm is energized at the same time as alarm.
/
- 4.2.82.1.3 Contact closure across terminals H19 (298) and H20 (299), mechanical trouble alarm at the same time as alarm is energized.
/
- 4.2.82.2 Turbo oil pressure low, right, PS 43N, pos 3-2.
- 4.2.82.2.1 Contact closure across terminals J17 (451) and J18 (452) when alarm is energized and contact open when alarm is de-energized.
/
- 4.2.82.2.2 Relay R38, mechanical trouble alarm is energized at the same time as alarm.
/
- 4.2.82.3 Turbo oil pressure low, left, PS 20N, pos 4-2.
- 4.2.82.3.1 Contact closure across terminals J19 (454) and J20 (455), when alarm is energized and contact open when alarm is de-energized.
/
- 4.2.82.3.2 Relay R38, mechanical trouble alarm is energized at the same time as alarm.
/
- 4.2.82.4 Lube oil pressure low, PS-25N, pos 1-2.
- 4.2.82.4.1 Contact closure across terminals J13 (445) and J14 (466) when alarm is energized and contact open when alarm is de-energized.
/

VEGP

27563-C

2

33 of 75

- 4.2.82.4.2
*/
*/ Relay R38, mechanical trouble alarm is energized at the same time as alarm.
- 4.2.82.5 Loss of generator DC control power, terminals F11 (79) and F10 (89).
- 4.2.82.5.1
*/
*/ Contact closure across terminals A21 (472) and A22 (473) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.6 High F.O. leak tank alarm, terminals C29 (411) and C30 (512) pos 13-2.
- 4.2.82.6.1
*/
*/ Contact closure across terminals K5 (513) and K6 (514) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.7 Lube oil tank level low, terminal C25 (411) and C26 (428) pos 6-1.
- 4.2.82.7.1
*/
*/ Contact closure across terminals A1 (429) and A2 (430) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.8 High level main tank, terminal C31 (411) and C32 (515) pos 14-2.
- 4.2.82.8.1
*/
*/ Contact closure across terminals K7 (516) and K8 (517) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.9 Lube oil inlet temperature low, R16, pins 10 (411) and 9 (412) pos 1-1.
- 4.2.82.9.1
*/
*/ Contact closure across terminals J1 (414) and J2 (415) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.9.2
*/
*/ Relay R38, mechanical trouble alarm is energized at the same time as alarm.
- 4.2.82.10 Lube oil outlet temperature low, R17, pins 10 (411) and 9 (416) pos 2-1.
- 4.2.82.10.1
*/
*/ Contact closure across terminals J3 (417) and J4 (418) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.10.2
*/
*/ Relay R38, mechanical trouble alarm is energized at the same time as alarm.

PROCEDURE NO	REVISION	PAGE NO.
VEGP 27563-C	2	34 of 75
4.2.82.11	Lube oil outlet temperature low, R16, pins 6 (419) and 7 (437) pos 3-1.	
<u>4.2.82.11.1</u> */*	Contact closure across terminals J5 (420) and J6 (421) when alarm is energized and contact open when alarm is de-energized.	
<u>4.2.82.11.2</u> */*	Relay R38, mechanical trouble alarm is energized at the same time as alarm.	
4.2.82.12	Lube oil outlet temperature high, R17, pins 6 (422) and 7 (437) pos 4-1.	
<u>4.2.82.12.1</u> */*	Contact closure across terminals J7 (423) and J8 (424) when alarm is energized and contact open when alarm is de-energized.	
<u>4.2.82.12.2</u> */*	Relay R38, mechanical trouble alarm is energized at the same time as alarm.	
4.2.82.13	Low level main tank, terminals D13 (411) and D14 (518) pos 15-2.	
<u>4.2.82.13.1</u> */*	Contact closure across terminals K9 (519) and K10 (520) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.14	Generator under frequency, terminals F7 (79) and F9 (81) pos 16-2.	
<u>4.2.82.14.1</u> */*	Contact closure across terminals B1 (522) and B2 (523) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.15	Spare alarm, terminals D19 (411) and D20 (527) pos 18-2.	
<u>4.2.82.15.1</u> */*	Contact closure across terminals B5 (528) and B6 (529) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.16	Spare alarm, terminals D21 (411) and D22 (530) pos 19-2.	
<u>4.2.82.16.1</u> */*	Contact closure across terminals B7 (531) and B8 (532) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.17	Disabled D.G. circuit breaker inoperable, terminals F7 (79) and F8 (80) pos 20-2.	

- 4.2.82.17.1
*/
*/ Contact closure across terminals B9 (534) and B10 (535) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.17.2
*/
*/ Relay R35, locked out alarm is energized at the same time as alarm is energized.
- 4.2.82.18 Fuel oil day tank level high/low, terminals D17 (411) and D18 (524) pos 17-2.
- 4.2.82.18.1
*/
*/ Contact closure across terminals B3 (525) and B4 (526) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.19 Generator trouble, terminals E28 (79) and E29 (82) pos 21-1.
- 4.2.82.19.1
*/
*/ Contact closure across terminals K13 (538) and K14 (539) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.20 Fuel filter differential pressure high, PS-5N, pos 12-1.
- 4.2.82.20.1
*/
*/ Contact closure across terminals K3 (510) and K4 (511) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.20.2
*/
*/ Relay R38, mechanical trouble alarm is energized at the same time as alarm.
- 4.2.82.21 Low voltage, terminals E28 (79) and E30 (83) pos 22-1.
- 4.2.82.21.1
*/
*/ Contact closure across terminals K15 (541) and K16 (542) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.22 Fuel oil pressure low, PS-28N, pos 11-2.
- 4.2.82.22.1
*/
*/ Contact closure across terminals K1 (507) and K2 (508) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.22.2
*/
*/ Relay R38, mechanical trouble alarm is energized at the same time as alarm.
- 4.2.82.23 Jacket water pressure low, PS-22N, pos 16-1.

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	36 of 75
4.2.82.23.1 <u>*/*</u>	Contact closure across terminals A25 (491) and A26 (492) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.23.2 <u>*/*</u>	Relay R38, mechanical trouble alarm is energized at the same time as alarm.	
4.2.82.24	High temperature gen control panel, terminals E28 (79) and E31 (84) pos 23-1.	
4.2.82.24.1 <u>*/*</u>	Contact closure across terminals K17 (544) and K18 (545) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.25	Jacket water level low, terminals C27 (411) and C28 (496) pos 18-1.	
4.2.82.25.1 <u>*/*</u>	Contact closure across terminals A29 (497) and A30 (498) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.26	Jacket water in temperature low, R18, pins 10 (411) and 9 (474) pos 11-1.	
4.2.82.26.1 <u>*/*</u>	Contact closure across terminals J25 (476) and J26 (477) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.26.2 <u>*/*</u>	Relay R38, mechanical trouble alarm is energized at the same time as alarm.	
4.2.82.27	Jacket water out temperature low, R21, pins 10 (411) and 9 (478) pos 12-1.	
4.2.82.27.1 <u>*/*</u>	Contact closure across terminals J27 (479) and J28 (480) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.27.2 <u>*/*</u>	Relay R38, mechanical trouble alarm is energized at the same time as alarm.	
4.2.82.28	Jacket water in temperature high, R18, pins 6 (481) and 7 (437) pos 13-1.	
4.2.82.28.1 <u>*/*</u>	Contact closure across terminals J29 (482) and J30 (483) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.28.2 <u>*/*</u>	Relay R38, mechanical trouble alarm is energized at the same time as alarm.	

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	37 of 75
4.2.82.29	Jacket water out temperature low, R21, pins 6 (484) and 7 (437) pos 14-1.	
<u>4.2.82.29.1</u> <u>*/*</u>	Contact closure across terminals J31 (485) and J32 (486) when alarm is energized and contact open when alarm is de-energized.	
<u>4.2.82.29.2</u> <u>*/*</u>	Relay R38, mechanical trouble alarm is energized at the same time as alarm.	
4.2.82.30	Low excitation, terminals E28 (79) and E32 (85) pos 24-1.	
<u>4.2.82.30.1</u> <u>*/*</u>	Contact closure across terminals K19 (547) and K20 (548) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.31	Engine control in local, terminals E28 (79) and E33 (86) pos 25-1.	
<u>4.2.82.31.1</u> <u>*/*</u>	Contact closure across terminals K21 (550) and K22 (551) when alarm is energized and contact open when alarm is de-energized.	
<u>4.2.82.31.2</u> <u>*/*</u>	With R-20 relay energized, verify contact closure across terminals H9 (283) and H10 (284) as long as alarm is energized.	
4.2.82.32	Control air pressure low, PS-39N. Pos 21-2.	
<u>4.2.82.32.1</u> <u>*/*</u>	Contact closure across terminals K25 (568) and K26 (569) when alarm is energized and contact open when alarm is de-energized.	
4.2.82.33	Diesel start air pressure low, PS-3N1, and PS-4N1, pos 22-2.	
<u>4.2.82.33.1</u> <u>*/*</u>	Contact closure across terminals K27 (572) and K28 (573) when alarm is energized and contact open when alarm is de-energized.	
<u>4.2.82.33.2</u> <u>*/*</u>	Unit available emergency status light de-energized as long as alarm is energized.	
4.2.82.34	Diesel start air pressure high, PS-3N2, and PS-4N2, pos 22-2.	
<u>4.2.82.34.1</u> <u>*/*</u>	Contact closure across terminals K29 (575) and K30 (576) when alarm is energized and contact open when alarm is de-energized.	

- 4.2.82.35 Generator fault, terminals E28 (79) and E34 (87) pos 26-1.
- 4.2.82.35.1 */* Contact closure across terminals B13 (553) and B14 (554) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.35.2 */* Contact closure across terminals 6 and 7 at annunciator pos 26-1 as long as alarm is energized.
- 4.2.82.36 Trip generator diff, terminals E28 (79) and E35 (88) pos 27-1.
- 4.2.82.36.1 */* Contact closure across terminals B15 (556) and B16 (557) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.36.2 */* Contact closure across terminals 6 and 7 at annunciator pos 27-1 as long as alarm is energized.
- 4.2.82.37 High generator bearing temp, terminals D31 (411) and D32 (558) pos 28-1.
- 4.2.82.37.1 */* Contact closure across terminals B17 (559) and B18 (560) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.38 Spare alarm, terminals D33 (411) and D34 (561) pos 29-1.
- 4.2.82.38.1 */* Contact closure across terminals B19 (562) and B20 (563) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.39 Switch not in auto, terminals D11 (411) and D12 (586) also E55 (79) and E56 (91) pos 26-2.
- 4.2.82.39.1 */* Contact closure across terminals B25 (587) and B26 (588) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.40 Panel intrusion, pos 28-2.
- 4.2.82.40.1 */* Contact closure across terminals B29 (595) and B30 (596) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.41 High temp engine control panel, pos 29-2.

VEGP

27563-C

2

39 of 75

- 4.2.82.41.1
*/
*/ Contact closure across terminals B31 (598) and B32 (599) when alarm is energized and contact open when alarm is de-energized.
- 4.2.82.42
*/
*/ Install relays R16, R17, R18 and R20. Also reconnect lifted wire 437 to PS22N.
- 4.2.83
*/
*/ Reset R2 relay, Group II lockout, manually.
- 4.2.84 Close shutoff valve tubing connection E31L and vent pressure, starting air pressure L.B. and verify: Trip low pressure lube oil -
- 4.2.84.1
*/
*/ No pressure at starting air pressure L.B. gauge.
- 4.2.84.2 Momentarily jumper terminals L37 (106) and L43 (104), remote emergency start and verify.
- 4.2.84.2.1
*/
*/ 120 volt D.C. across terminal L4 (102) and L5 (105), starting air solenoid.
- 4.2.84.3 Momentarily jumper terminals E49 (3) and E51 (7), remote emergency start and verify.
- 4.2.84.3.1
*/
*/ 120 volt A.C. across terminal E5 (4) and E4 (2) starting air solenoid.
- 4.2.85 Close shutoff valve tubing connection E31R and vent Pressure Below 150 PSIG starting air pressure R.B. and verify:
- 4.2.85.1
*/
*/ Pressure Below 150 PSIG at starting air pressure R.B. gauge.
- 4.2.85.2
*/
*/ No pressure at starting air pressure L.B. gauge.
- 4.2.85.3 Momentarily jumper terminals L37 (106) and L43 (104), remote emergency start and verify:
- 4.2.85.3.1
*/
*/ No voltage across terminals L4 (102) and L5 (105), starting air solenoid.
- 4.2.85.4 Momentarily jumper terminals E49 (3) and E51 (7) remote emergency start and verify:
- 4.2.85.4.1
*/
*/ No voltage across terminals E5 (4) and E4 (2), starting air solenoid.

- 4.2.86 Open shutoff valve E31R and E31L and verify jumpers are removed across terminals L37 (106) and L43 (104) and L4 (102) and L5 (105).
- 4.2.87 Open circuit breaker CB-9 and CB-10 and verify:
- 4.2.87.1 */* Contact closure across terminals H1 (275) and H2 (276).
- 4.2.87.2 */* Contact closure across terminals A35 (612) and A36 (613).
- 4.2.88 Close circuit breaker CB-9 and CB-10 and verify:
- 4.2.88.1 */* Open contact closure across terminals H1 (275) and H2 (276).
- 4.2.88.2 */* Open contact closure across terminals A35 (612) and A36 (613).
- 4.2.89 Trip low pressure lube oil.
- 4.2.89.1 */* Trip low pressure lube oil - remove plug at bulkhead fitting E-10A and connect incoming tubing line.
- 4.2.89.2 */* Trip low pressure lube oil - remove plug at bulkhead fitting E-10B and connect incoming tubing line.
- 4.2.89.3 */* Trip low pressure lube oil - remove plug at bulkhead fitting E-10C and connect incoming tubing line.
- 4.2.90 */* Trip - low pressure turbo oil. Remove plug at bulkhead fitting E92 and connect incoming tubing line.
- 4.2.91 */* Trip - low pressure jacket water. Remove plug at bulkhead fitting E-14 and connect incoming tubing line.
- 4.2.92 Close the following sliding link terminals:
- 4.2.92.1 */* A-Bank starting air valve. Terminals E5 (4) and E4 (2).
- 4.2.92.2 */* B-Bank starting air valve. Terminals L5 (105) and L4 (102).

PROCEDURE NO.	REVISION	PAGE NO.
VEGP	27563-C	2 41 of 75
<u>4.2.92.3</u> */*	Field flash, exciter reg enable. Terminals E19 (53), E22 (56), E17 (51), and E21 (55).	
<u>4.2.92.4</u> *	Preset V.R. and Gov. Terminals E23 (57), E18 (52), and E24 (59).	
<u>4.2.92.5</u> */*	Ready to load, DG brkr. Terminals F5 (77) and F6 (78).	
<u>4.2.92.6</u> */*	Ready to load, HVAC sys. Terminals E57 (46) and E58 (47).	
<u>4.2.92.7</u> */*	Ready to load, spare. Terminals E59 (48) and E60 (49).	
<u>4.2.92.8</u> */*	Start, spare. Terminals F1 (73) and F2 (74).	
4.2.92.9	Stop, spare. Terminals F3 (75) and F4 (76).	
<u>4.2.92.10</u> */*	Pre-position Gov and V.R. Terminals L30 (172) and L32 (171).	
<u>4.2.92.11</u> */*	186C Trip delay. Terminals L32 (172) and L33 (173).	
<u>4.2.92.12</u> */*	Field flash, exciter reg enable. Terminals L23 (153), L20 (141), L21 (144), and L24 (155).	
<u>4.2.92.13</u> */*	Trip 52G. Terminals L51 (159) and L52 (160).	
<u>4.2.92.14</u> */*	Emergency stop. Terminals L53 (164) and L54 (165).	
<u>4.2.92.15</u> */*	Running, spare. Terminals L55 (166) and L56 (167).	
<u>4.2.92.16</u> */*	Running, spare. Terminals L57 (168) and L58 (169).	
<u>4.2.92.17</u> */*	Overspeed, spare. Terminals L59 (179) and L60 (180).	
<u>4.2.92.18</u> */*	Running W/Delay. Terminals L35 (175) and L36 (176).	

VEGP

27563-C

2

42 of 75

- 4.2.92.19 Ready to load - HVAC system. Terminals L9 (137) and L10 (138).
/
- 4.2.92.20 Ready to load - spares. Terminals L11 (139) and L12 (140).
/
- 4.2.92.21 Emergency stop Terminals L14 (336) and L15 (337).
/
- 4.2.92.22 ERF computer. Terminals L49 (S4B1) and L50 (S4B2).
/
- 4.2.92.23 Emergency stop annunciation. Terminals L25 (no wire number) and L26 (no wire number).
/
- 4.2.92.24 CC Fan #1. Terminals C3 (244) and C9 (245).
/
- 4.2.92.25 CC Fan #2. Terminals C5 (246) and C11 (242).
/
- 4.2.92.26 Generator space heater control. Terminals C7 (239) and C8 (240).
/
- 4.2.92.27 Running contacts. Terminals G3 (253), G4 (254), G5 (255), G6 (256), G7 (257), G8 (258), G9 (259), G10 (260), G11 (161), and G12 (162).
/
- 4.2.92.28 Running W/Delay contacts. Terminals G13 (263), G14 (264), G15 (265), G16 (266), G17 (267), G18 (268), G19 (269), G20 (270), G21 (271), G22 (272), G23 (273), and G24 (274).
/
- 4.2.92.29 Loss of DC annunciation. Terminals H1 (275) and H2 (276).
/
- 4.2.92.30 Mechanical trouble alarm. Terminals H19 (298) and H20 (299).
/
- 4.2.92.31 Lockout alarm. Terminals H3 (277) and H4 (278).
/
- 4.2.92.32 Failed to start. Terminals H7 (281) and H8 (282).
/
- 4.2.92.33 Unit available local control. Terminals H9 (283) and H10 (284).
/

PROCEDURE NO.		REVISION	PAGE NO.
VEGP	27563-C	2	43 of 75

- 4.2.92.31
*/
*/ Unit available. Terminals H11 (285), H12 (286), H13 (287), H14 (288), H15 (289), and H16 (290).
- 4.2.92.35
*/
*/ Alarm. Terminals H17 (296) and H18 (297).
- 4.2.92.36
*/
*/ Loss of DC power. Terminals A35 (612) and A36 (613).
- 4.2.92.37
*/
*/ DG Brkr inop. Terminals F7 (75) and F8 (80).
- 4.2.93
*/
*/ Open toggle switches to allow hourmeter to be energized.
- 4.2.94
*/
*/ A-Bank starting air valve. Reconnect engine wire number 4 at engine "EJBA" junction box.
- 4.2.95
*/
*/ B-Bank starting air valve. Reconnect engine wire number 105 at engine "EJBB" junction box.
- 4.2.96
*/
*/ Reconnect the horn by reconnecting wire No. 402 at relay R-15, connection is across from wire No. 401A.
- 4.2.97
*/
*/ Manual permissive start "A" side, remove jumper across terminals E49 (3) and E50 (11).
- 4.2.98
*/
*/ Manual permissive start "B" side, remove jumper across terminals L37 (106) and L42 (110).
- 4.2.99
*/
*/ Disconnect frequency generator from terminals E7 (20) and E8 (21).
- 4.2.100
*/
*/ Panel check. Check for disconnected/plugged tubing or fittings. Check for any jumper/disconnected wires. Check for any open terminal links. Control panel should now be operational for engine start.
- 4.2.101
*/
*/ Notify Shift Supervisor that required maintenance is complete.
- 5.0 ACCEPTANCE CRITERIA
- 5.1 Maintenance performed using this procedure is acceptable when:
- 5.1 1 The "Completion" Sheet is properly filled out.

PROCEDURE NO.	REVISION	PAGE NO.
VEGP 27563-C	2	44 of 75

- 5.1.2 Deviations from the Procedure data and recommended settings have been reviewed on a case-by-case basis with the Maintenance Foreman.
- 5.1.3 Divations have been identified in the "Comments" section of the "Completion" Sheet.
- 5.1.4 The "Completion" Sheet has been approved.
- 5.1.5 Maintenance Work Orders have been written and submitted for conditions evaluated as needing attention.
- 6.0 REFERENCES
- 6.1 00304-C, "Equipment Clearance And Tagging"
- 6.1.1 20407-C, "Maintenance Cleanliness And Housekeeping Control"
- 6.2 AX4AK01-509 "Transamerica Delevel Instruction Manual"

COMPLETION SHEET

PROCEDURE 27563-C	REVISION 2	SHEET 1 OF 30
TAG NO.	DESCRIPTION	
SERIAL NO.	MANUFACTURER	MODEL
TEST EQUIPMENT USED	M&TE #	<input type="checkbox"/> Safety Related/QC Hold Point <input type="checkbox"/> Non-Safety Related

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.1.1	Prerequisites met	/		/
4.1.2	Shift Supervisor notified	/		/
4.1.5.1	Tubing E-10A disconnected	/		/
4.1.5.2	Tubing E-10B disconnected	/		/
4.1.5.3	Tubing E-10C disconnected	/		/
4.1.6.1	Tubing E-92 disconnected	/		/
4.1.7.1	Tubing E-14 disconnected	/		/
4.1.8.1	A-Bank Starting Air Valve. Terminals E5 (4) and E4 (2).	/		/
4.1.8.2	B-Bank Starting Air Valve. Terminals L5 (105) and L4 (102).	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>OC INIT/DATE</u>
4.1.8.3	Field Flash, Exciter Reg Enable. Terminals E19 (53), E22 (56), E17 (51), and E21 (55).	/		/
4.1.8.4	Preset V.R. and Gov.: Terminals E23 (57), E18 (52), and E24 (59).	/		/
4.1.8.5	Ready to Load, DG Brkr.: Terminals F5 (77) and F6 (78).	/		/
4.1.8.6	Ready to Load, HVAC Sys.: Terminals E57 (46) and E58 (47).	/		/
4.1.8.7	Ready to Load, Spare. Terminals E59 (48) and E60 (49).	/		/
4.1.8.8	Start, Spare. Terminals F1 (73) and F2 (74).	/		/
4.1.8.9	Stop, Spare. Terminals F3 (75) and F4 (76).	/		/
4.1.8.10	Pre-position Gov and V.R. Terminals L30 (170) and L31 (171).	/		/
4.1.8.11	186C Trip Delay Terminals L32 (172) and L33 (173).	/		/
4.1.8.12	Field Flash, Exciter Reg Enable. Terminals L23 (153), L20 (141), L21 (144), and L24 (155).	/		/
4.1.8.13	Trip 52G. Terminals L51 (159) and L52 (160).	/		/
4.1.8.14	Emergency Stop. Terminals L53 (164) and L54 (165).	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.1.8.15	Running, Spare. Terminals L55 (166) and L56 (167).	/		/
4.1.8.16	Running, Spare. Terminals L57 (168) and L58 (169).	/		/
4.1.8.17	Overspeed, Spare. Terminals L59 (179) and L60 (180).	/		/
4.1.8.18	Running W/Delay. Terminals L35 (175) and L36 (176).	/		/
4.1.8.19	Ready to Load - HVAC System. Terminals L9 (137) and L10 (138).	/		/
4.1.8.20	Ready to Load - Spare. Terminals L11 (139) and L12 (140).	/		/
4.1.8.21	Emergency Stop. Terminals L14 (336) and L15 (337).	/		/
4.1.8.22	ERF Computer. Terminals L49 (S4B1) and L50 (S4B2).	/		/
4.1.8.23	Emergency Stop Annunciation. Terminals L25 (79-180) and L26 (90-180).	/		/
4.1.8.24	CC Fan #1. Terminals C3 (244) and C9 (245).	/		/
4.1.8.25	CC Fan #2. Terminals C5 (246) and C11 (247).	/		/
4.1.8.26	Generator Space Heater Control. Terminals C7 (239) and C8 (240).	/		/
4.1.8.27	Running Contacts. Terminals G3 (253), G4 (254), G5 (255), G6 (256), G7 (257), G8 (258), G9 (259), G10 (260), G11 (161), and G12 (162).	/		/

PROCEDURE NO.		REVISION	PAGE NO.	
VEGP	27563-C	2	49 of 75	
Sheet 4 of 30				
<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.1.8.28	Running W/Delay Contacts. Terminals G13 (263), G14 (264), G15 (265), G16 (266), G17 (267), G18 (268), G19 (269), G20 (270), G21 (271), G22 (272), G23 (273) and G24 (274).	/		/
4.1.8.29	Loss of DC Annunciation. Terminals H1 (275) and H2 (276).	/		/
4.1.8.30	Mechanical Trouble Alarm. Terminals H19 (298) and H20 (299).	/		/
4.1.8.31	Lockout Alarm. Terminals H3 (277) and H4 (278).	/		/
4.1.8.32	Failed to Start. Terminals H7 (281) and H8 (282).	/		/
4.1.8.33	Unit Available Local Control. Terminals H9 (283) and H10 (284).	/		/
4.1.8.34	Unit Available. Terminals H11 (285), H12 (286), H13 (287), H14 (288), H15 (289), and H16 (290).	/		/
4.1.8.35	Alarm. Terminals H17 (296) and H18 (297).	/		/
4.1.8.36	Loss of DC Power. Terminals A35 (612) and A36 (613).	/		/
4.1.8.37	DG Brkr Inop. Terminals F7 (79) and F8 (80).	/		/
4.1.9	Toggle switches to hourmeter open.	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.1.10.1	At on-engine "EJBA" Junction Box, disconnect engine wire number 4 and tape wire end.	/	---	/
4.1.11.1	At on-engine "EJBb" Junction Box, disconnect engine wire number 105 and tape wire end.	/	---	/
4.1.12	Verify that all circuit breakers are closed.	/	---	/
4.1.13	Verify 60 psi at control air pressure gauge.	/	---	/
4.1.14	Verifv 125 vdc across circuit breakers CB-1 and CB-2, CB-3 and CB-4.	/	---	/
4.2.1	Jumper terminals L45 (101) and L48 (129), Control Room permissive for maintenance mode.	/	---	/
4.2.2.1	Disconnect jumper across terminals H4 (278) and H12 (286) and verify:	/	---	/
4.2.2.2	Open contact across terminals H3 (277) and H4 (278).	/	---	/
4.2.2.3	Contact OPEN	/	---	/
4.2.2.4	Contact OPEN	/	---	/
4.2.2.5	Contact CLOSED	/	---	/
4.2.2.6	Contact CLOSED	/	---	/
4.2.3.1	Shutdown Cylinder EXTENDED	/	---	/
4.2.3.2	Lockout alarm ENERGIZED	/	---	/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.3.3	Light DeEnergized	/		/
4.2.3.4	Gauge indicates 0 PSI	/		/
4.2.3.5	Lockout Pin REMOVED	/		/
4.2.3.6	STOPPING light ENERGIZED	/		/
4.2.3.7	Contact CLOSED	/		/
4.2.3.8	Contact CLOSED	/		/
4.2.3.9	Contact CLOSED	/		/
4.2.3.10	Contact CLOSED	/		/
4.2.3.11	Contact OPEN	/		/
4.2.3.12	Contact OPEN	/		/
4.2.4	Jumper Removed	/		/
4.2.5.1	125VDC present	/		/
4.2.6.1	No voltage present	/		/
4.2.6.2	No voltage present	/		/
4.2.7	Wire disconnected	/		/
4.2.7.1	Relay R-35 De-energized	/		/
4.2.7.2	Contact OPEN	/		/
4.2.7.3	Lockout alarm de-energized	/		/
4.2.8.1	Barring device engaged alarm ENERGIZED	/		/

PROCEDURE NO.		REVISION	PAGE NO.	
VEGP	27563-C	2	52 of 75	
Sheet 7 of 30				
<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.8.2	Contact CLOSED	/		/
4.2.8.3	Relay R-35 ENERGIZED	/		/
4.2.9.1.1	125VDC Present	/		/
4.2.9.2.1	No voltage present	/		/
4.2.9.2.2	No voltage present	/		/
4.2.10.1	Barring device engaged alarm ENERGIZED	/		/
4.2.10.2	Contact OPEN	/		/
4.2.10.3	Relay R-35 DE-ENERGIZED	/		/
4.2.11	Wire Reconnected	/		/
4.2.11.1	Relay R-35 DE-ENERGIZED	/		/
4.2.11.2	Lockout alarm ENERGIZED	/		/
4.2.12.1	Shutdown cylinder RETRACTED	/		/
4.2.12.2	Pressure Gauge reads 60PSI	/		/
4.2.12.3	Lockout alarm DE-ENERGIZED	/		/
4.2.12.4	Emergency status light ENERGIZED	/		/
4.2.12.5	Lockout pin in LOCKED position	/		/
4.2.12.6	STOPPING light DE-ENERGIZED	/		/

PROCEDURE NO.		REVISION	PAGE NO.	
VEGP	27563-C	2	53 of 75	
Sheet 8 of 30				
<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.12.7	BARRING device RETRACTED	/		/
4.2.12.8	Locking pin INSTALLED	/		/
4.2.13.1	No voltage PRESENT	/		/
4.2.14.1	No voltage PRESENT	/		/
4.2.14.2	"A" power light DE-ENERGIZED	/		/
4.2.14.3	Panel "A" failure alarm ENERGIZED	/		/
4.2.14.4	Contact CLOSED	/		/
4.2.15	Timer REMOVED	/		/
4.2.16.1	125VDC PRESENT	/		/
4.2.16.2	Alarm ENERGIZED	/		/
4.2.16.3	Relay DE-ENERGIZED	/		/
4.2.16.4	Contact CLOSED	/		/
4.2.16.5	Contact CLOSED	/		/
4.2.16.6	Relay R-35 ENERGIZED	/		/
4.2.16.7	Horn ENERGIZED	/		/
4.2.17.1	Horn DE-ENERGIZED	/		/
4.2.17.2	Contact OPEN	/		/
4.2.17.3	Relay R-35 DE-ENERGIZED	/		/

VEGP

27563-C

2

54 of 75

Sheet 9 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.17.4	Failed to start alarm DE-ENERGIZED	/		/
4.2.18.1	Contact CLOSED	/		/
4.2.18.2	Contact CLOSED	/		/
4.2.18.3	No voltage PRESENT	/		/
4.2.18.4	Contact CLOSED	/		/
4.2.18.5	Contact CLOSED	/		/
4.2.18.6	Running light ENERGIZED	/		/
4.2.18.7	Failed to start alarm DE-ENERGIZED	/		/
4.2.18.8	Contact CLOSED	/		/
4.2.18.9	Contact OPEN	/		/
4.2.18.10	Contact CLOSED	/		/
4.2.18.11	Relay R 1 ENERGIZED	/		/
4.2.18.12	Contact CLOSED	/		/
4.2.18.13	Contact CLOSED	/		/
4.2.18.14	Contact CLOSED	/		/
4.2.18.15	Contact CLOSED	/		/
4.2.18.16	Contact OPEN	/		/
4.2.18.17	Contact OPEN	/		/
4.2.18.18	Contact OPEN	/		/
4.2.18.19	Contact CLOSED	/		/
4.2.18.20	Contact CLOSED	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.18.21	Contact CLOSED	/		/
4.2.18.22	Contact OPEN	/		/
4.2.18.23	Contact OPEN	/		/
4.2.18.24	Contact OPEN	/		/
4.2.19	Maintenance Button Pushed	/		/
4.2.19.1	Maintenance mode alarm DE-ENERGIZED	/		/
4.2.20.1	Contact OPEN	/		/
4.2.20.2	Shutdown cylinder EXTENDED	/		/
4.2.20.3	Cylinder retracted and VENTED	/		/
4.2.20.4	Contact OPEN	/		/
4.2.20.5	Contact CLOSED	/		/
4.2.20.6	Unit running light DE-ENERGIZED	/		/
4.2.20.7	Contact OPEN	/		/
4.2.20.8	Contact OPEN	/		/
4.2.20.9	Contact OPEN	/		/
4.2.21.1	Maintenance mode alarm ENERGIZED	/		/
4.2.22.1	Maintenance mode alarm DE-ENERGIZED	/		/
4.2.24.1	125VDC PRESENT	/		/
4.2.24.2.1	Maintenance mode alarm DE-ENERGIZED	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.24.3	Contact CLOSED	/		/
4.2.24.4	Relays ENERGIZED	/		/
4.2.24.5	Contact CLOSED	/		/
4.2.24.6	Safety injection signal light ENERGIZED	/		/
4.2.24.7	Shutdown light DE-ENERGIZED	/		/
4.2.24.8	No voltage on solenoid	/		/
4.2.24.9	Jumper REMOVED	/		/
4.2.24.10	EMERGENCY start alarm ENERGIZED	/		/
4.2.24.11	Contact CLOSED	/		/
4.2.24.12	Contact CLOSED	/		/
4.2.25.1	Stopping light DE-ENERGIZED	/		/
4.2.26.1	Pressure gauge below 25 PSI	/		/
4.2.26.2	Shutdown cylinder NOT EXTENDED	/		/
4.2.26.3	Hi temp lube oil alarm ENERGIZED	/		/
4.2.26.4	Stopping light NOT ENERGIZED	/		/
4.2.26.5	Contact CLOSED	/		/
4.2.26.6	Contact CLOSED annunciator "ON"	/		/
4.2.27	Tubing E-18 RECONNECTED	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>OC INIT/DATE</u>
4.2.27.1	Group 1 pressure gauge 60 PSI	/		/
4.2.27.2	Hi temp alarm DE-ENERGIZED	/		/
4.2.27.3	Contact OPEN	/		/
4.2.27.4	Contact OPEN	/		/
4.2.28.1	Stopping light ENERGIZED	/		/
4.2.28.2	Lo pressure alarm ENERGIZED	/		/
4.2.28.3	Contact CLOSED	/		/
4.2.28.4	Contact CLOSED	/		/
4.2.28.5	Engine shutdown Cylinder EXTENDED	/		/
4.2.29.1	Maintenance mode alarm DE-ENERGIZED	/		/
4.2.30	Plug installed on E-92	/		/
4.2.30.1	Relay R11B ENERGIZED	/		/
4.2.30.1.1	Contact CLOSED	/		/
4.2.30.1.2	Contact CLOSED	/		/
4.2.30.1.3	Contact CLOSED	/		/
4.2.30.1.4	Ready to load light ENERGIZED	/		/
4.2.30.2	Jumper Removed	/		/
4.2.30.2.1	Contact OPEN	/		/
4.2.30.2.2	Contact OPEN	/		/

Sheet 13 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.30.2.3	Contact OPEN	/		/
4.2.30.2.4	Ready to load light ENERGIZED	/		/
4.2.31.1	No voltage PRESENT	/		/
4.2.31.2	Relay R-5B ENERGIZED	/		/
4.2.32.1	Relay R-23B ENERGIZED	/		/
4.2.32.2	Contact CLOSED	/		/
4.2.32.3	Contact CLOSED	/		/
4.2.32.4	Contact CLOSED	/		/
4.2.32.5	Contact CLOSED	/		/
4.2.32.6	Emergency Stop ENERGIZED	/		/
4.2.32.7	Stopping light ENERGIZED	/		/
4.2.32.8	Pressure at Solenoid 3B	/		/
4.2.32.9	Unit available light DE-ENERGIZED	/		/
4.2.32.9.1	No change in status light	/		/
4.2.32.10	Overspeed alarm ENERGIZED	/		/
4.2.32.11	Contact CLOSED	/		/
4.2.32.12	Relay R-35 ENERGIZED	/		/
4.2.32.12.1.1	Relay R-35 ENERGIZED	/		/
4.2.32.12.1.2	Emergency trip DE-ENERGIZED	/		/

Sheet 14 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.32.13.1	No voltage present	/		/
4.2.32.13.2	No voltage present	/		/
4.2.33	Cover INSTALLED	/		/
4.2.35.1	Contact OPEN	/		/
4.2.35.2	Overspeed trip DE-ENERGIZED	/		/
4.2.35.3	Contact OPEN	/		/
4.2.36.1	Relay R23B DE-ENERGIZED	/		/
4.2.36.2	Contact OPEN	/		/
4.2.36.3	Contact OPEN	/		/
4.2.36.4	Contact OPEN	/		/
4.2.36.5	Emergency stop light DE-ENERGIZED	/		/
4.2.36.6	Stopping light DE-ENERGIZED	/		/
4.2.36.7	Relay R-35 DE-ENERGIZED	/		/
4.2.37.1	125VDC present	/		/
4.2.37.2	DG Auto start signal ENERGIZED	/		/
4.2.38.1	No voltage present	/		/
4.2.38.2	DG Auto start signal DE-ENERGIZED	/		/
4.2.39.1	Contact CLOSED	/		/
4.2.39.2.1	Relay R23B ENERGIZED	/		/
4.2.39.2.2	Contact CLOSED	/		/

PROCEDURE NO		REVISION	PAGE NO.	
VEGP	27563-C	2	60 of 75	
Sheet 15 of 30				
<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>OC INIT/DATE</u>
4.2.39.2.3	Contact CLOSED	/		/
4.2.41.1	Emergency trip alarm is ENERGIZED	/		/
4.2.41.2	Contact CLOSED	/		/
4.2.41.3	Relay R-35 ENERGIZED	/		/
4.2.42.1	Emergency trip alarm DE-ENERGIZED	/		/
4.2.42.2	Contact OPEN	/		/
4.2.42.3	Relay R-35 DE-ENERGIZED	/		/
4.2.44	Jumper Disconnected	/		/
4.2.45.1	125VDC across solenoid 202-6A	/		/
4.2.45.2	Power available light ENERGIZED	/		/
4.2.45.3	Annunciator DE-ENERGIZED	/		/
4.2.45.4	Contact OPEN	/		/
4.2.46.1	No voltage across solenoid 202-6B	/		/
4.2.46.2	Power available light DE-ENERGIZED	/		/
4.2.46.3	Power "B" failure ALARM ENERGIZED	/		/
4.2.46.4	CONTACT CLOSED	/		/
4.2.48.1	125VDC PRESENT	/		/
4.2.48.2	FAILURE TO START ALARM ENERGIZED	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.49.1	No voltage present	/	---	/
4.2.49.2	CONTACT CLOSED	/	---	/
4.2.49.3	OPEN CIRCUIT	/	---	/
4.2.49.4	CONTACT CLOSED	/	---	/
4.2.49.5	STARTING LIGHT ENERGIZED	/	---	/
4.2.49.6	Relay R1 ENERGIZED	/	---	/
4.2.49.7	RUNNING LIGHT ENERGIZED	/	---	/
4.2.50.1	SHUTDOWN CYLINDER EXTENDED	/	---	/
4.2.50.2	Contact Closure	/	---	/
4.2.50.3	High Temperature trip ENERGIZED	/	---	/
4.2.50.4	OPEN CIRCUIT	/	---	/
4.2.50.5	Relay R1, R1AUX, and R2 are reset	/	---	/
4.2.50.6	Contact Closed	/	---	/
4.2.50.7	Contact closed	/	---	/
4.2.50.8	Unit running light DF-ENERGIZED	/	---	/
4.2.50.9	Stopping light ENERGIZED	/	---	/
4.2.50.10	Contact CLOSED	/	---	/
4.2.50.11	CONTACT CLOSED	/	---	/
4.2.51.1	Hi bearing temp ALARM DE-ENERGIZED	/	---	/

Sheet 17 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.51.2	CONTACT OPEN	/		/
4.2.51.3	CONTACT OPEN	/		/
4.2.53.1	125V DC PRESENT	/		/
4.2.53.2	CONTACT CLOSED	/		/
4.2.53.3	RELAYS R1, R1A R2, ENERGIZED	/		/
4.2.53.4	SHUTDOWN SYSTEM ACTIVE Light DE-ENERGIZED	/		/
4.2.53.5	NO VOLTAGE PRESENT	/		/
4.2.53.6	Jumper Removed	/		/
4.2.53.7	Contact CLOSED	/		/
4.2.54.1	Hi Pressure Alarm ENERGIZED	/		/
4.2.54.2	ENGINE SHUTDOWN CYLINDER NOT EXTENDED	/		/
4.2.54.3	CONTACT CLOSED	/		/
4.2.54.4	CONTACT CLOSED	/		/
4.2.55	TUBING E-68 RECONNECTED	/		/
4.2.55.1	Hi Pressure Alarm DE-ENERGIZED	/		/
4.2.55.2	CONTACT OPEN	/		/
4.2.55.3	CONTACT OPEN	/		/
4.2.55.4	SHUTDOWN CYLINDER NOT EXTENDED	/		/
4.2.56.1	No voltage present	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.56.2	CONTACT CLOSED	/		/
4.2.56.3	SHUTDOWN CYLINDER EXTENDED	/		/
4.2.56.4	VIBRATION ALARM ENERGIZED	/		/
4.2.56.5	CONTACT CLOSED	/		/
4.2.56.6	CONTACT CLOSED	/		/
4.2.56.7	CONTACT OPEN	/		/
4.2.57	TUBING E-23-H RECONNECTED	/		/
4.2.57.1	VIBRATION ALARM DE-ENERGIZED	/		/
4.2.57.2	CONTACT OPEN	/		/
4.2.57.3	CONTACT OPEN	/		/
4.2.58.1	Jacket Water Lo PRESSURE ENERGIZED	/		/
4.2.58.2	ENGINE SHUTDOWN CYLINDER EXTENDED	/		/
4.2.58.3	CONTACT CLOSED	/		/
4.2.58.4	CONTACT CLOSED	/		/
4.2.58.5	CONTACT CLOSED	/		/
4.2.58.6	CONTACT CLOSED	/		/
4.2.58.7	CONTACT CLOSED	/		/
4.2.59	TUBING E-14 RECONNECTED	/		/
4.2.59.1	JACKET WATER ALARM DE-ENERGIZED	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>OC INIT/DATE</u>
4.2.59.2	CONTACT OPEN	/		/
4.2.59.3	CONTACT OPEN	/		/
4.2.60.1	RELAY R-11A ENERGIZED	/		/
4.2.60.2	CONTACT CLOSED	/		/
4.2.60.3	CONTACT CLOSED	/		/
4.2.60.4	READY TO LOAD LIGHT ENERGIZED	/		/
4.2.60.5	CONTACT OPEN	/		/
4.2.60.6	CONTACT OPEN	/		/
4.2.60.7	READY TO LOAD LIGHT DE-ENERGIZED	/		/
4.2.60.8	JUMPER REMOVED	/		/
4.2.61.1	125VDC PRESENT	/		/
4.2.61.2	CONTACT CLOSED	/		/
4.2.61.3	AUTO START LIGHT ENERGIZED	/		/
4.2.62	REMOVE JUMPER	/		/
4.2.62.1	NO VOLTAGE PRESENT	/		/
4.2.62.2	CONTACT OPEN	/		/
4.2.62.3	AUTO START	/		/
4.2.63.1	UNIT AVAILABLE LIGHT DE-ENERGIZED	/		/
4.2.63.2	POWER FAILURE ALARM ENERGIZED	/		/
4.2.63.3	CONTACT CLOSED	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.64.1	UNIT AVAILABLE STATUS LIGHT ENERGIZED	/	---	/
4.2.64.2	START POWER FAILURE ALARM DE-ENERGIZED	/	---	/
4.2.64.3	CONTACT OPEN	/	---	/
4.2.65.1	PRESSURE SENSOR MALFUNCTION ALARM ENERGIZED	/	---	/
4.2.65.2	CONTACT CLOSED	/	---	/
4.2.65.3	TUBING E-10B DISCONNECTED	/	---	/
4.2.65.4	LUBE OIL ALARM ENERGIZED	/	---	/
4.2.65.5	PRESSURE SENSOR MALFUNCTION ALARM DE-ENERGIZED	/	---	/
4.2.65.6	CONTACT CLOSED	/	---	/
4.2.65.7	CONTACT CLOSED	/	---	/
4.2.65.8	CONTACT OPEN	/	---	/
4.2.65.9	RELAY R23D DEENERGIZED	/	---	/
4.2.66.1	RELAY R23D DEENERGIZED	/	---	/
4.2.66.2	CONTACT OPEN	/	---	/
4.2.66.3	CONTACT OPEN	/	---	/
4.2.67.1	MALFUNCTION ALARM ENERGIZED	/	---	/
4.2.67.2.	PLUG REMOVED FROM TUBING E-10C	/	---	/

Sheet 21 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.67.2.1	LO OIL PRESSURE ALARM DE-ENERGIZED	/		/
4.2.67.2.2	LUBE OIL SHUTDOWN ALARM ENERGIZED	/		/
4.2.67.2.3	CONTACT CLOSED	/		/
4.2.69.1	MALFUNCTION ALARM ENERGIZED	/		/
4.2.69.2	PLUG E-10A DISCONNECTED	/		/
4.2.69.2.1	LUBE OIL SHUTDOWN ALARM ENERGIZED	/		/
4.2.70	PLUGS RECONNECTED TO TUBING E10A and E10C	/		/
4.2.71.1	JACKET WATER TEMP SENSOR MALFUNCTION ALARM ENERGIZED	/		/
4.2.71.2	CONTACT CLOSED	/		/
4.2.71.3	Disconnect Tubing E-16B	/		/
4.2.71.3.1	TEMP SENSOR MALFUNCTION ALARM DE-ENERGIZED	/		/
4.2.71.3.2	JACKET WATER TEMP SHUTDOWN ALARM ENERGIZED	/		/
4.2.71.3.3	CONTACT CLOSED	/		/
4.2.71.3.4	CONTACT OPEN	/		/
4.2.72	TUBING E-16 and RECONNECTED	/		/
4.2.73	E16-B Disconnected	/		/

Sheet 22 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.73.1	Hi Temp. JACKET WATER ALARM DE-ENERGIZED	/		/
4.2.73.2	CONTACT OPEN	/		/
4.2.73.3	CONTACT OPEN	/		/
4.2.73.4	TEMP. SENSOR MALFUNCTION ALARM	/		/
4.2.73.5	TUBING E16-C Disconnected	/		/
4.2.73.5.1	Jacket Water Shutdown ALARM ENERGIZED	/		/
4.2.74	TUBING LINES E16-B AND C RECONNECTED	/		/
4.2.75	Disconnect Tubing E16-C	/		/
4.2.75.1	SENSOR MALFUNCTION ALARM	/		/
4.2.75.2	TUBING E16-A Disconnected	/		/
4.2.75.2.1	JACKETWATERS SHUTDOWN ALARM	/		/
4.2.76	TUBING E16-A and C RECONNECTED	/		/
4.2.77.1	PRESSURE GAUGE READING LESS THAN 25PSI	/		/
4.2.77.2	BYPASS TEST FAILURE LIGHT DE-ENERGIZED	/		/
4.2.77.3.1	BYPASS TEST FAILURE LIGHT ENERGIZED	/		/
4.2.78.1	SUMP TANK READING O.K.	/		/

Sheet 23 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.79.1	DAY TANK READING O.K.	/		/
4.2.80.1	ALARMS ENERGIZED	/		/
4.2.80.2	Horn Disconnected	/		/
4.2.82.1	LUBE OIL FILTER DIFFERENTIAL HIGH FUNCTIONS	/		/
4.2.82.1.1	ALARM FUNCTIONS Correctly	/		/
4.2.82.1.2	RELAY R38 ENERGIZED	/		/
4.2.82.1.3	CONTACT CLOSED	/		/
4.2.82.2.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.2.2	RELAY R38 ENERGIZED	/		/
4.2.82.3.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.3.2	RELAY R38 ENERGIZED	/		/
4.2.82.4.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.4.2	RELAY R38 ENERGIZED	/		/
4.2.82.5.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.6.1	ALARM FUNCTION CORRECTLY	/		/
4.2.82.7.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.8.1	ALARM FUNCTIONS CORRECTLY	/		/

Sheet 24 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.82.9.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.9.2	RELAY R38 ENERGIZED	/		/
4.2.82.10.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.10.2	RELAY R38 ENERGIZED	/		/
4.2.82.11.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.11.2	RELAY R38 ENERGIZED	/		/
4.2.82.12.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.12.2	RELAY R38 ENERGIZED	/		/
4.2.82.13.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.14.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.15.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.16.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.17.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.17.2	RELAY R35 ENERGIZED	/		/
4.2.82.18.1	ALARM FUNCTIONS CORRECTLY	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.82.19.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.20.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.20.2	RELAY R38 ENERGIZED	/		/
4.2.82.21.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.22.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.22.2	RELAY R38 ENERGIZED	/		/
4.2.82.23.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.23.2	RELAY R38 ENERGIZED	/		/
4.2.82.24.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.25.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.26.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.26.2	RELAY R38 ENERGIZED	/		/
4.2.82.27.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.27.2	RELAY R38 ENERGIZED	/		/
4.2.82.28.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.28.2	RELAY R38 ENERGIZED	/		/

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.82.29.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.29.2	RELAY R38 ENERGIZED	/		/
4.2.82.30.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.31.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.31.2	RELAY R20 ENERGIZED CONTACT CLOSED	/		/
4.2.82.32.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.33.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.33.2	EMERGENCY STATUS LIGHT DE-ENERGIZED	/		/
4.2.82.34.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.35.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.35.2	CONTACT CLOSED	/		/
4.2.82.36.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.36.2	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.37.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.38.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.39.1	ALARM FUNCTIONS CORRECTLY	/		/

Sheet 27 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.82.40.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.41.1	ALARM FUNCTIONS CORRECTLY	/		/
4.2.82.42	RELAYS INSTALLED	/		/
4.2.83	RELAY RESET	/		/
4.2.84.1	NO PRESSURE AT L.B. GAUGE	/		/
4.2.84.2.1	120 VDC PRESENT	/		/
4.2.84.3.1	120 VDC PRESENT	/		/
4.2.85.1	PRESSURE AT R.B.GAUGE	/		/
4.2.85.2	NO PRESSURE AT LB GAUGE	/		/
4.2.85.3.1	NO VOLTAGE PRESENT	/		/
4.2.85.4.1	NO VOLTAGE PRESENT	/		/
4.2.87.1	CONTACT CLOSED	/		/
4.2.87.2	CONTACT CLOSED	/		/
4.2.88.1	CONTACT OPEN	/		/
4.2.88.2	CONTACT OPEN	/		/
4.2.89.1	TUBING RECONNECTED	/		/
4.2.89.2	TUBING RECONNECTED	/		/
4.2.89.3	TUBING RECONNECTED	/		/
4.2.90	TUBING RECONNECTED	/		/
4.2.91	TUBING RECONNECTED	/		/

Sheet 28 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.92.1	LINKS CLOSED	/		/
4.2.92.2	LINKS CLOSED	/		/
4.2.92.3	LINKS CLOSED	/		/
4.2.92.4	LINKS CLOSED	/		/
4.2.92.5	LINKS CLOSED	/		/
4.2.92.6	LINKS CLOSED	/		/
4.2.92.7	LINKS CLOSED	/		/
4.2.92.8	LINKS CLOSED	/		/
4.2.92.9	LINKS CLOSED	/		/
4.2.92.10	LINKS CLOSED	/		/
4.2.92.11	LINKS CLOSED	/		/
4.2.92.12	LINKS CLOSED	/		/
4.2.92.13	LINKS CLOSED	/		/
4.2.92.14	LINKS CLOSED	/		/
4.2.92.15	LINKS CLOSED	/		/
4.2.92.16	LINKS CLOSED	/		/
4.2.92.17	LINKS CLOSED	/		/
4.2.92.18	LINKS CLOSED	/		/
4.2.92.19	LINKS CLOSED	/		/
4.2.92.20	LINKS CLOSED	/		/
4.2.92.21	LINKS CLOSED	/		/
4.2.92.22	LINKS CLOSED	/		/

Sheet 29 of 30

<u>PROCEDURE STEP</u>	<u>DESCRIPTION</u>	<u>MAINT. INIT/DATE</u>	<u>HOLD POINT (Yes/No)</u>	<u>QC INIT/DATE</u>
4.2.92.23	LINKS CLOSED	/		/
4.2.92.24	LINKS CLOSED	/		/
4.2.92.25	LINKS CLOSED	/		/
4.2.92.26	LINKS CLOSED	/		/
4.2.92.27	LINKS CLOSED	/		/
4.2.92.28	LINKS CLOSED	/		/
4.2.92.29	LINKS CLOSED	/		/
4.2.92.30	LINKS CLOSED	/		/
4.2.92.31	LINKS CLOSED	/		/
4.2.92.32	LINKS CLOSED	/		/
4.2.92.33	LINKS CLOSED	/		/
4.2.92.34	LINKS CLOSED	/		/
4.2.92.35	LINKS CLOSED	/		/
4.2.92.36	LINKS CLOSED	/		/
4.2.92.37	LINKS CLOSED	/		/
4.2.93	TOGGLE SWITCHES OPEN	/		/
4.2.94	ENGINE WIRE RECONNECTED	/		/
4.2.95	ENGINE WIRE RECONNECTED	/		/
4.2.96	WIRE 402 RECONNECTED	/		/
4.2.97	JUMPER REMOVE	/		/

722-1000 Test 2104 NOUE 2/23/90^{ED}MSC (3)

PROCEDURE NO VEGP	91102-C	REVISION	6	PAGE NO	12 of 18
----------------------	---------	----------	---	---------	----------

Sheet 2 of 8

EMERGENCY DIRECTOR CHECKLIST

SUBSEQUENT ACTIONS

Transfer of Responsibilities

1. Review with the ED:
 - a. Summary of events
 - b. Plant status
 - c. Equipment status
 - d. Emergency classification
 - e. Status of notifications of offsite authorities
 - f. Protective and corrective actions
 - g. Completed checklist items
 - h. Status of facilities activation
 - i. Any noted deficiencies
 - j. Status of assembly and accountability, if initiated
 - k. Outstanding orders
 - l. Recovery plan of action, if known

INFO

CAUTION

Assure that initial actions in Procedure 91001-C, "Emergency Classification And Implementing Instructions", have been completed as necessary prior to proceeding with this checklist.

2. Review facility readiness with facility managers.
3. Assure that logkeeper maintains a log of ED actions and records any transfer of responsibility.
4. Formally assume from the OSOS the position of ED, using the following message format:

AT 1822 ON 2/23/90 I AM ASSUMING THE EMERGENCY
 (Central Time) (Date)
 DIRECTOR POSITION AND HEREBY RELIEVE YOU OF ALL EMERGENCY
 DIRECTOR RESPONSIBILITIES.

CHECKLIST 1

EMERGENCY DIRECTOR NOTIFICATION CHECKLIST

RESPONSIBILITIES

NOTE

Ensure NOUE, Alert, or Site Area/General Emergency Classification check list in Procedure 91001-C has been initiated.

1. This checklist must be completed by the Emergency Director (1) upon the declaration of any emergency condition (NOUE... ALERT, SITE AREA EMERGENCY, or GENERAL EMERGENCY), (2) the change in the level of classification of the emergency condition declared, or (3) a change in protective action recommendations.
2. The Emergency Director will complete Checklist 2 and sign the completed form.
3. The Emergency Director will supervise completion of notification and insure completion within the time limits.
4. When the notification responsibilities have been transferred to the EOF or TSC, the EOF Support Coordinator or the TSCC Support Coordinator will supervise the preparation and transmission of Notification Messages.
5. The assigned Communicator will perform the notification.

IMMEDIATE ACTIONS

1. Direct the ENN Communicator (Shift Clerk in the Control Room) to establish communications and complete roll call in accordance with Step B of Checklist 2.
2. Complete the Notification Form Checklist 2, from Initial Notification.
3. Direct the designated ENN Communicator to make the notification in accordance with Checklist 2 within 15 minutes of the declaration.

CHECKLIST 1

EMERGENCY DIRECTOR NOTIFICATION CHECKLIST

1. ✓ Supervise completion of the notifications to state and local agencies insuring that notification is made within 15 minutes of the emergency declaration.
2. ✓ Complete the Event Notification Worksheet, Checklist 3, and direct a plant knowledgeable individual to notify the NRC.
3. ✓ Direct a Communicator to perform the Georgia Power Company Notification per Checklist 4.
4. ✓ Direct VEGP Security to notify the Visitor Center, Training Center, Recreation Park, GPC Vogtle Control Warehouse, Corporate Garage, Administrative Support Building, and Projects and Facility Services.
5. ✓ After normal working hours, for an ALERT or higher classification, direct Security to recall Emergency Response Personnel per EPIP 91704-C, "Actions For Security During A Radiological Emergency". On Shift Supervisory personnel in the maintenance, operations and security departments shall recall additional personnel as needed since these departments are not included in the plant recall system.

FOLLOW-UP ACTIONS

1. ✓ For Alert and higher classifications maintain communications with offsite agencies (Georgia, South Carolina, Savannah River Site, Burke County, Allendale County, Barnwell County, and Aiken County). Shift to alternate state and county notification locations, as requested.
2. ✓ Provide emergency follow-up status messages every 30-minutes incorporating new information as available. All follow-up messages are made utilizing Checklist 1. Follow-up status is not required for a NOUE.
3. ✓ Complete and transmit an Emergency Notification Message whenever the emergency classification or the protective action recommendation is changed utilizing Checklist 2.
4. ✓ Keep the NRC updated with all changes. Inform the NRC immediately of any further degradation in the plant conditions, any change from one emergency class to another, or of the termination of an emergency utilizing the Event Notification Worksheet (Checklist 3). Upon activation of the TSC, the TSC Manager assumes the responsibility of communicating with the NRC.

CHECKLIST 1EMERGENCY DIRECTOR NOTIFICATION CHECKLISTTERMINATION ACTIONS

1. At Alert or higher classification, reduce a classification or terminate an emergency after coordination with offsite authorities followed by a written summary within 8 hours of termination or class reduction.
2. For a NOUE close out with verbal summary to offsite authorities; followed by written summary within 24 hours.
3. Complete and transmit termination messages in accordance with Checklist 2 for Georgia and South Carolina, and Checklist 3 of this procedure for the NRC.

NOTIFICATION OF UNUSUAL EVENT CHECKLIST

1. Maintain a log of the incident (this may be delegated to other personnel, as available).
2. Make an announcement over the public address system for all areas as follows:

NOTE

Wording in [] may not be applicable in all situations.

"ATTENTION ALL PERSONNEL - THIS IS NOT A DRILL - A NOTIFICATION OF UNUSUAL EVENT HAS BEEN DECLARED [FOR UNIT 1]."

(Include brief description of the event)

~~Shutdown requested by Tech Specs due to 303 entry on both lines of 10 control room scope on 4/2/11~~

(Repeat Announcement)

3. Implement notifications in accordance with Checklist 1, Emergency Director Notification Checklist, in Procedure 91002-C, Emergency Notifications".
4. If a radiological release is involved, request offsite dose projections be performed (see Procedure 91304-C, "Computerized And Manual Back-Up Methods For Release Rate And Dose Calculations").
5. As necessary, make protective action recommendations per Procedure 91305-C, "Protective Action Guidelines".
6. Continue with subsequent actions per the Emergency Director Checklist in Procedure 91102-C, "Duties Of The Emergency Director".

Signature [Signature]
Emergency Director

Date/Central Time 4/22/11 1655

DATA SHEET 1

CLASSIFICATION DETERMINATION

1. Evaluate status of fission product barriers:

Breached/Challenged

- | | | | | | |
|----|--|-----|-----|----|---|
| a. | Fuel Cladding Integrity
(See Figure 1) | YES | ___ | NO | ___ <input checked="" type="checkbox"/> |
| b. | Reactor Coolant System
Integrity (See Figure 2) | YES | ___ | NO | ___ <input checked="" type="checkbox"/> |
| c. | Containment Integrity
(See Figure 3) | YES | ___ | NO | ___ <input checked="" type="checkbox"/> |

2. Determine the highest emergency classification level for present plant conditions (See Figure 4).

Check One:

- Notification of Unusual Event
- Alert
- Site Area Emergency
- General Emergency

Comments: Shut down required by Tech Spec → Entered 20.5 hrs to both trains if 18 switches error

3. Assume the position of Emergency Director.

Signature [Signature]
Emergency Director

Date 2/23/90

Central Time 1655

4. Proceed to Notification of Unusual Event, Alert, Site Area Emergency/General Emergency Checklist of this procedure.

CHECKLIST 2

EMERGENCY NOTIFICATION MESSAGE FOR
STATE AND LOCAL RESPONSE AGENCIES

A. INSTRUCTIONS:

1. Complete as much of the information on this form as possible.
2. Have the Emergency Director sign the form to authorize release.
3. These notifications MUST be made within 15 minutes of event classification.
4. Use communication circuits in the following order of priority:
 - a. ENN (broadcast to all stations simultaneously)
 - b. SC Backup ENN (Two digit phone numbers found in VEGP Emergency Response Telephone Directory)
 - c. Commercial telephones (Phone numbers in VEGP Emergency Response Telephone Directory)
 - d. Radios:
 1. Use SRS radio in TSC (Freq. 1, ask SRS to notify other South Carolina agencies).
 2. Use Burke County radio in TSC (ask Burke County to notify the Georgia Emergency Management Agency).

B. INITIAL ROLL CALL: State the following:

THIS ~~X~~/IS NOT A DRILL! (Cross out one)
HELLO, THIS IS (Name) FRISA JONES AT THE VOGTLE
ELECTRIC GENERATING PLANT. PLEASE OBTAIN A COPY OF THE
EMERGENCY NOTIFICATION FORM. STANDBY TO RECEIVE A MESSAGE. (Proceed with
roll call in the following order, check box for responding agencies)

- | | |
|---|--|
| <input checked="" type="checkbox"/> Savannah River Site | <input checked="" type="checkbox"/> Aiken County |
| <input checked="" type="checkbox"/> State of South Carolina | <input checked="" type="checkbox"/> Allendale County <i>Notified by Commercial Phone</i> |
| <input checked="" type="checkbox"/> Georgia Emergency Management Agency | <input checked="" type="checkbox"/> Barnwell County |
| <input checked="" type="checkbox"/> Burke County | |

C. NOTIFICATION MESSAGE TRANSMISSION: Transmit complete notification form, obtain roll call and record acknowledgements.

NOTE

The Emergency Notification Message for State and Local Response Agencies (Sheet 2 and 3 of 3) Checklist 2, of this procedure is a reproduction of the actual form. The actual form should be used, although reproduction of the form in this procedure is authorized.

CHECKLIST 3
NRC NOTIFICATION CHECKLIST

Initiate contact on the ENS line. When contact is made, the caller shall state:

"HELLO, THIS IS (NAME): ~~XXXXX~~ AT THE VOGTLE ELECTRIC GENERATING PLANT. PLEASE OBTAIN A COPY OF THE EVENT NOTIFICATION WORKSHEET AND STAND BY TO RECEIVE A MESSAGE".

NOTES

- a. If no response on the ENS is obtained, use a commercial line and one of the following numbers:

(301) 951-0550	(301) 427-4259
(301) 492-8893	(301) 427-4056

- b. The Event Notification Worksheet (NRC Form 361) in this procedure is a reproduction of the actual NRC form. The actual NRC Form 361 should be used, although reproduction of the form in this procedure is authorized.

EVENT NOTIFICATION WORKSHEET

NOTIFICATION TIME 1601 EST	FACILITY OR ORGANIZATION PLANT VIOLETTA	UNIT 1	CALLER'S NAME JAMES WILLIAMS	CALL BACK # ENS 01 (414) 826-3005
--------------------------------------	---	------------------	--	---

EVENT TIME & DATE 1655 C - 0 23 90	EVENT DATE 0 23 90	1 Hr Non-Emergency 10 CFR 50.72(b)(1)		(i) Lost Offsite Comms AESS
POWER MODE BEFORE 24 / 1	POWER MODE AFTER FC / 1	(i)(A) TS Require S/D ASHU	(ii) Fire AFIR	(ii) Toxic Gas ACHE
EVENT CLASSIFICATIONS		(i)(B) TS Deviation ADEV	(iv) Rad Release ARAD	(iv) Oth. Hampering Safe Op. AHIN
		(i) Degraded Condition ADEG	4 Hr Non-Emergency 10 CFR 50.72(b)(2)	
GENERAL EMERGENCY GEN/AAEC		(ii)(A) Unanalyzed Condition AUNA	(i) Degrade While S/D ADAS	(ii) RPS Actuation (scram) ARPS
		(ii)(B) Outside Design Basis AOUT	(ii) ESF Actuation AESF	(ii)(A) Safe S/D Capability AINA
SITE AREA EMERGENCY SIT/AAEC		(ii)(C) Not Covered by OPs, EPs ACNC	(ii) Earthquake ANEA	(ii)(B) RHR Capability AINE
ALERT ALE/AAEC		(ii) Flood ANFL	(ii) Hurricane ANHU	(ii)(C) Control of Rad Release AINC
UNUSUAL EVENT UNL/AAEC		(ii) Ice/Hail ANIC	(ii) Lightning ANLI	(ii)(D) Accident Mitigation AIND
50.72 NON-EMERGENCY (see next columns)		(ii) Torn. do ANTO	(ii) Oth. Natural Phenomenon ANOT	(ii)(A) Air Release > 2X App B AAIR
PHYSICAL SECURITY (73.71) D???		(iv) ECCS Discharge to RCS ACCS	(iv) Lost ENS AENS	(ii)(B) Liq Release > 2X App B ALIQ
TRANSPORTATION NTRA		(v) Lost Emerg. Assessment AARC	(iv) Offsite Medical AMED	(iv) Offsite Notification APRE
20.403 MATERIAL EXPOSURE B???				
OTHER NDAM, NLCO, NBNL, NINF, NLTR, NONR CDEF, FLOM, EIRR, GCON				

DESCRIPTION

DECLARED NRE @ 1655 CST DUE TO INITIATING A PLANT SHUTDOWN DUE TO PLANT TECH SPECS. DEENERGIZED SWGR CABINET WHICH RENDERED A CNMT PEN. INOPERABLE. PLANT EXCEEDED THE 4 HRS AVAILABLE TO REENERGIZE CABOT. COMMENCED A PLANT S/D. (SHUTDOWN CONCURRED WITH S/D - SCHEDULED MAINTENANCE).

- 1608 STANSKY (OPS CENTER, NRC)
- 1707 STATE/LOCAL NOTS CONF. CONTACT ALLENDALE
- 1711 ALLENDALE NOTIFIED
- 1710 REN PERILLO NOTIFIED

Include: Systems affected, actuations & their initiating signals, causes, effect of event on plant, actions taken or planned, etc.

IFICATIONS	YES	NO	WILL BE	ANYTHING UNUSUAL OR NOT UNDERSTOOD?	YES (Explain above)	NO
NRC RESIDENT	<input checked="" type="checkbox"/>	<input type="checkbox"/>				<input checked="" type="checkbox"/>
STATENI	<input checked="" type="checkbox"/>	<input type="checkbox"/>		DID ALL SYSTEMS FUNCTION AS REQUIRED?	<input checked="" type="checkbox"/> YES	NO (Explain above)
LOCAL	<input checked="" type="checkbox"/>	<input type="checkbox"/>		MODE OF OPERATION		
OTHER GOV AGENCIES	<input checked="" type="checkbox"/>	<input type="checkbox"/>	2/23/90	UNTIL CORRECTED	1	ESTIMATE FOR RESTART DATE
MEDIA/PRESS RELEASE	<input checked="" type="checkbox"/>	<input type="checkbox"/>				NA
						ADDITIONAL INFO ON BACK?

CHECKLIST 4

GEORGIA POWER COMPANY NOTIFICATION CHECKLIST

NOTE

This checklist to be completed by a Control Room Communicator following completion of initial notifications to State and Local authorities.

IMMEDIATE ACTION

1. Obtain the latest approved version of Checklist 2.
2. If any individual cannot be reached, proceed to the next person and repeat notification steps later.
3. Make the notifications below and inform the Emergency Director of any problems encountered.
 - (1) Notify each individual below when any emergency class is declared or changed. Inform each of the:
 - (a) time of classification
 - (b) the emergency classification
 - (c) the description of the event

Utilize the information in the latest version of Checklist 2.

	<u>Primary Number</u>	<u>Alternate Number</u>	<u>Beeper</u>	<u>Central Time/Initials</u>
Security (PESB)	3737	4111	312	17061 JFW
VEGP General Manager	3118	3119	001	17051 MC
Plant Wilson Manager	8-526-3140	8-526-3129		1

NOTE

Request Vogtle Duty Manager to notify the On Call Project Manager

Vogtle
Duty Manager

[see PLAN OF THE DAY]

17081 MC

CHECKLIST 4

GEORGIA POWER COMPANY NOTIFICATION CHECKLIST

	<u>Primary Number</u>	<u>Alternate Number</u>	<u>Beeper</u>	<u>Central Time/Initials</u>
NRC Resident Inspector(s) VEGP	4116	4249	293 009 303	<u>17101 / E</u>
Assistant General Manager Plant Operations	3140	404/592-2867	002	<u>17101 / [initials]</u>
Manager Operations	3618		044	<u>17191 / [initials]</u>
Assistant General Manager Plant Support	3143		200	<u>17251 / [initials]</u>
Manager Training and Emergency Preparedness	3901	3903	303	<u>17251 / EMT</u>

2354 2304

EMERGENCY NOTIFICATION

Number CC 2

1. THIS IS A DRILL THIS IS AN ACTUAL EMERGENCY

2. AUTHENTICATION: 92 SAICOR
(Number) (Codeword)

3. TIME/DATE: 2354 / 2 / 23 / 90 REPORTED BY: Mary Maria
(Eastern) mm dd yy (Name)

4. SITE: VOGTLE UNIT: 1 CONFIRMATION PHONE NUMBER: 1-404-554-6762

5. EMERGENCY CLASSIFICATION:

NOTIFICATION OF UNUSUAL EVENT ALERT SITE AREA EMERGENCY GENERAL EMERGENCY

6. EMERGENCY DECLARATION AT: TIME/DATE: _____ / _____ / _____ / _____
(Eastern) mm dd yy

EMERGENCY TERMINATION AT: TIME/DATE: 2353 / 2 / 23 / 90 (If B, go to item 16.)
(Eastern) mm dd yy

7. EMERGENCY DESCRIPTION: _____

8. PLANT CONDITION: IMPROVING STABLE DEGRADING UNDETERMINED

9. EMERGENCY INVOLVES:

NO RELEASE (If A, go to item 14.) A RELEASE IS OCCURRING: Started _____ Expected Duration _____

POTENTIAL RELEASE A RELEASE HAS OCCURRED: Started _____ Stopped _____

10. TYPE OF RELEASE: ELEVATED GROUND LEVEL

RADIOACTIVE GASES RADIOACTIVE PARTICULATES

RADIOACTIVE LIQUIDS OTHER _____

11. RELEASE: CURIES PER SEC. CURIES

NOBLE GASES _____ IODINES _____

IODINE/NOBLE GAS RATIO (If available) _____ OTHER _____

12. REACTOR STATUS: SHUTDOWN: TIME/DATE: _____ / _____ / _____ / _____ _____ % POWER
(Eastern) mm dd yy

13. ESTIMATE OF PROJECTED OFFSITE DOSE: NEW UNCHANGED DURATION: _____ HRS.

Distance	Wholebody DOSE RATE (mrem/hr)	Child Thyroid DOSE RATE (mrem/hr)	Wholebody (mrem)	Child Thyroid (mrem)
SITE BOUNDARY	_____	_____	_____	_____
2 MILES	_____	_____	_____	_____
5 MILES	_____	_____	_____	_____
10 MILES	_____	_____	_____	_____

14. METEOROLOGICAL DATA: NOT AVAILABLE

WIND DIRECTION (from) _____ ° STABILITY CLASS _____

WIND SPEED (mph) _____ PRECIPITATION (type) _____

15. RECOMMENDED PROTECTIVE ACTIONS:

NO RECOMMENDED PROTECTIVE ACTIONS

SHELTER _____

EVACUATE _____

OTHER _____

16. APPROVED BY: Bludwig Costa EMERGENCY DIRECTOR TIME/DATE: 2353 / 2 / 23 / 90
(Name) (Title) (Eastern) mm dd yy

EVENT NOTIFICATION WORKSHEET

Gould

NOTIFICATION TIME 2310 EST	FACILITY OR ORGANIZATION VEGP	UNIT 1	CALLER'S NAME B.D. Carter	CALL BACK # - ENS or (404) 524-6762
--------------------------------------	---	------------------	-------------------------------------	---

EVENT TIME & ZONE 1755 EST	EVENT DATE 2/23/90	1-Hr Non-Emergency 10 CFR 50.72(b)(1)	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><td>(vi) Lost Offsite Comms</td><td>AESG</td></tr> <tr><td>(vii) Fire</td><td>AFIR</td></tr> <tr><td>(viii) Toxic Gas</td><td>ACHE</td></tr> <tr><td>(ix) Rad Release</td><td>ARAD</td></tr> <tr><td>(x) Oth Hampering Safe Op</td><td>AHIN</td></tr> </table>	(vi) Lost Offsite Comms	AESG	(vii) Fire	AFIR	(viii) Toxic Gas	ACHE	(ix) Rad Release	ARAD	(x) Oth Hampering Safe Op	AHIN
(vi) Lost Offsite Comms	AESG												
(vii) Fire	AFIR												
(viii) Toxic Gas	ACHE												
(ix) Rad Release	ARAD												
(x) Oth Hampering Safe Op	AHIN												
POWER/MODE BEFORE 84% 42%	POWER/MODE AFTER C 7c Mode 3	(i)(A) TS Required S/D ASHU	(vi) Degraded Condition ADEV										
		(i)(B) TS Deviation ADEV	(vii) Rad Release ARAD										
		(ii) Degraded Condition ADEV	(viii) Oth Hampering Safe Op AHIN										
		(iii)(A) Unanalyzed Condition AUNA	4-Hr Non-Emergency 10 CFR 50.72(b)(2)										
		(iii)(B) Outside Design Basis AOUT											
		(iii)(C) Not Covered by OPs/EPs ACNC											
		(iii)(D) Earthquake ANEA											
EVENT CLASSIFICATIONS		(iii)(E) Flood ANFL	(i) Degrade While S/D ADAS										
		(iii)(F) Hurricane ANHU	(ii) RPS Actuation (scram) ARPS										
GENERAL EMERGENCY GEN/AAEC		(iii)(G) Ice/Hail ANIC	(iii) ESF Actuation AESF										
SITE AREA EMERGENCY SIT/AAEC		(iii)(H) Lightning ANLI	(iii)(A) Safe S/D Capability AINA										
ALERT ALE/AAEC		(iii)(I) Tornado ANTO	(iii)(B) RHR Capability AINB										
UNUSUAL EVENT UNU/AAEC		(iii)(J) Oth Natural Phenomenon ANOT	(iii)(C) Control of Rad Release A/NC										
50.72 NON-EMERGENCY <i>(see next columns)</i>		(iv) ECCS Discharge to RCS ACCS	(iii)(D) Accident Mitigation A/ND										
PHYSICAL SECURITY (73.71) D???		(v) Lost ENS AENS	(iv)(A) Air Release > 2X App B AAIR										
TRANSPORTATION NTRA		(v) Lost Emerg. Assessment AARC	(iv)(B) Lic Release > 2X App B ALIC										
20.403 MATERIAL EXPOSURE B???			(v) Offsite Medical AMED										
OTHER NDAM, NLCD, NBNL, NINF, NLTR, NONR CDEF, FLOM, EIRR, GCON			(vi) Offsite Notification APRE										

DESCRIPTION

Termination of the Notification of Unusual Event. ^{2/23/90} ~~15~~
 Shutdown no longer required by Tech. Specs. Seismic
 holddown bolts installed in IAB04 and IAB05, and all
 safety related electrical distribution reenergized.

Include: Systems affected, actuations & their initiating signals, causes, effect of event on plant, actions taken or planned, etc.

NOTIFICATIONS	YES	NO	WILL BE	ANYTHING UNUSUAL OR NOT UNDERSTOOD?	YES <i>(Explain above)</i>	NO
NRC RESIDENT			<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>
STATE(s)	<input checked="" type="checkbox"/>			DID ALL SYSTEMS FUNCTION AS REQUIRED?	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO <i>(Explain above)</i>
LOCAL	<input checked="" type="checkbox"/>			MODE OF OPERATION		ADDITIONAL INFO ON BACK?
OTHER GOV AGENCIES	<input checked="" type="checkbox"/>			UNTIL CORRECTED	ESTIMATE FOR RESTART DATE	
MEDIA/PRESS RELEASE		<input checked="" type="checkbox"/>				

TABLE 1

GUIDELINES FOR RECOMMENDED PROTECTIVE ACTIONS FOR
GASEOUS PLUME EXPOSURE

CONDITION	RECOMMENDED ACTION*
NON-ESSENTIAL STATION PERSONNEL AND GENERAL POPULATION	
1. A General Emergency has been declared.	Recommend a 2-mile precautionary evacuation in all sectors and out to 5 miles in potentially affected sectors. Shelter the remainder of the plume EPZ.
2. A General Emergency has been declared and large amounts of fission products are in the reactor coolant but not in containment atmosphere.	Recommend a 2-mile precautionary evacuation in all sectors and out to 5-miles in potentially affected sectors. Shelter the remainder of the plume EPZ.
3a. A General Emergency has been declared and large amounts of fission products in addition to noble gases are in the containment atmosphere.	Recommend a precautionary evacuation to 5 miles in all sectors and a downwind evacuation to 10 miles in potentially affected sectors. Shelter the remainder of the plume EPZ.
3b. A General Emergency has been declared and substantial core damage has occurred or is likely and containment <u>failure is judged imminent</u> or has occurred.	Recommend precautionary evacuation to 5 miles in all sectors and evacuation to 10 miles in potentially affected sectors. Shelter the remainder of the plume EPZ.

NOTE: References for this table are a combination of Table 5.1, page 5.31, Rev. 6/79 - Manual of Protective Actions for Nuclear Incidents and NUREG-0654, dated 1/80. Affected sectors include, as a minimum, the downwind sector(s) and adjacent sectors.

*Use enclosed EPZ Map (Figure 1) to identify potentially affected sectors for Georgia and zones for South Carolina.

TABLE 1 (Cont'd.)

GUIDELINES FOR RECOMMENDED PROTECTIVE ACTIONS FOR
GASEOUS PLUME EXPOSURE

CONDITION	RECOMMENDED ACTION*
NON-ESSENTIAL STATION PERSONNEL AND GENERAL POPULATION	
4. An actual release has occurred or is imminent and the projected dose to individuals in the population is calculated to be:	
a. Whole Body: 0.2 rem to 1 rem	No planned protective action necessary. Consider sheltering as precautionary measure for all affected sectors.
b. Thyroid: 1 rem to 5 rem	
c. Whole Body: 0.005 rem to 0.2 rem	Continue field monitoring.
d. Thyroid: 0.025 rem to 1 rem	
e. Whole Body: Less than 0.005 rem	Increase frequency of environmental monitoring.
f. Thyroid: Less than 0.025 rem	
5. An actual release has occurred or is imminent and the projected dose to individuals in the population is calculated to be:	
a. Whole Body: Greater than 1 rem	Recommend evacuation to 5 miles in all sectors and evacuation to 10 miles in potentially affected sectors. Shelter the remainder of the plume EPZ.
b. Thyroid: Greater than 5 rem	

*Use enclosed EPZ (Figure 1) Map to identify potentially affected sectors for Georgia and zones for South Carolina.

TABLE 1 (Cont'd.)

GUIDELINES FOR RECOMMENDED PROTECTIVE ACTIONS FOR GASEOUS PLUME EXPOSURE

CONDITION	RECOMMENDED ACTION*
-----------	---------------------

EMERGENCY TEAM PERSONNEL

<p>6. An actual release has occurred or is imminent and the projected dose to Emergency Team workers is calculated to be:</p> <p>a. Whole Body: 5 rem to 25 rem b. Thyroid: 25 rem to 125 rem</p>	<p>Control exposure of Emergency Team members to ensure doses will be less than 25 rem whole body and 125 rem thyroid except for lifesaving missions. (Appropriate controls for Emergency Team workers include time limitations and respiratory protection and potassium iodide.)</p>
<p>7. An actual release has occurred or is imminent and the projected dose to Emergency Team workers performing lifesaving missions is calculated to be:</p> <p>a. Whole Body: 25 rem to 75 rem b. Thyroid: greater than 125 rem</p>	<p>Control exposures of Emergency Team members performing lifesaving missions to ensure whole body dose is less than 75 rem. (Control of time of exposure will be most effective.) Although respiratory protection and potassium iodide should be used where effective to control dose to Emergency Team workers, thyroid dose may not be a limiting factor for lifesaving missions.</p>

*Use enclosed EPZ (Figure 1) Map to identify potentially affected sectors for Georgia and zones for South Carolina.





FIGURE 1

DEFICIENCY CARD

CARD #	1-90-0025	UNIT 1 (X)	UNIT 2 ()	COMBACH ()
1: DESCRIPTION OF DEFICIENCY	(ADDITIONAL SHEETS ATTACHED? YES NO)			
SWGRs 1AB04X, 1AB05X, 1BB06X, and 1BB07X are missing steel hold down wedges which provide seismic support for the transformer cores.				
LOCATION OF THE DEFICIENCY? Central Bldg, Level R				
WHAT IS AFFECTED BY THE DEFICIENCY? Switchgear Seismic Integrity				
HOW WAS THE DEFICIENCY DISCOVERED? During inspection of transformers due to PC 1-90-0034				
EVENT TIME	Unknown	DATE	Unknown	DISCOVERY TIME
DISCOVERED BY	Row Burris	WORK #	3176	DEPT. Eng. Support
2 SHIFT SUPERVISOR REVIEW				
NAME OF SS REPORTED TO?	E.M. Thornton Jr.	TIME	1310	DATE
PLANT MODE/CONDITION:	Mode 1	87%		
IS IMMEDIATE NOTIFICATION REQUIRED?	<input checked="" type="radio"/> YES <input type="radio"/> NO			
IF YES, 1 HOUR, 2 HOUR, OR 24 HOUR	1/24/90	REPORTED: DATE	TIME	
TECH SPEC REQUIRED ACTION TAKEN?	YES NO NA			
LIST APPLICABLE TECH. SPEC. SECTION(S)	3.0.3 EMT: 123/90 3.0.3.1			
SUMMARIZE COMPENSATORY ACTION TAKEN	Engineering to evaluate. SEE attached letters LCO generated previously.			
LCO INITIATED:	NO <input checked="" type="radio"/> YES # 1-90-22	TYPE: INFO	<input checked="" type="radio"/> LCO	FIRE
WRT INITIATED:	NO <input checked="" type="radio"/> YES # 3818			

COMPLETED BY INITIATOR

COMPLETED BY SS WITHIN 2 HOURS



MAY 11, 1990.

" EMERGENCY ORGANIZATION STRUCTURE "

TO: MR. AL CHAFFEE (301) 492-8802

FROM: HERB BEACHER (404) 826-3769 BEEPER 138

I) TECHNICAL SUPPORT CENTER (TSC)

TSC Manager	W.F. Kitchens
OPERATIONS Supervisor	J.F. CASH
Engineering Supervisor	J. Aufdenkampe
Health Physics Supervisor	G. Brenenberg
Chemistry Supervisor	D.F. Hallman
Support Coordinator	B. Quick
Maintenance Supervisor	M. Hobbs
Security Coordinator	G. Grimes
ENR Communicators	E.L. Pickett J.B. Stanchy

II.) OPERATION SUPPORT CENTER (OSC)

OSC MANAGER	H. Handfinger
Assistant OSC Mgr.	D. Gustafson

Support Personnel from:

Maintenance (Electrical, Mechanical, + I+C)
 Telecommunication
 Health Physics + Dosimetry
 Chemistry
 Operations
 Rad Waste
 Document Control
 Engineering

III EMERGENCY OPERATION FACILITY (EOF) (NOT ACTIVATED - IN STANDBY)

EOF Manager	M.B. Luckey
NRC Liaison	K.R. Holmes
Dose Assessment Mgr.	Indira Kochery
Security Coordinator	Tom McQuillen
Support Coordinator	V. Agro
Public Information Mgr.	R. Harris

IF YOU HAVE ANY QUESTIONS PLEASE CONTACT JIM ROBERTS
 EXT. 3416 OR HERB BEACHER EXT. 3769.

SECURITY EMERGENCY RESPONSE ORGANIZATION PERSONNEL

The following personnel were involved in the Emergency Operations Facility activities during the VEGP emergency of 3/20/90.

ERO SECURITY QUALS

03/21/90

GE-001 = Badge Training
 RE-110 = Recall & Notification
 RE-080 = Mgt. of Rad Emergencies

DATES LISTED ARE DROP DEAD DATES
 * RENEW QUAL 3 MO. PRIOR TO EXPIR.

CAS/SAS OPERATOR / SUPERVISOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-110</u>
- BECKER, H.L.	5/5/91	4/24/'90*
BELL, D.L.	8/1/90	5/6/'90 *
BLACKMON, B.L.	11/28/90	11/29/'90
BRADY, R.	11/14/90	5/6/'90 *
- BRONSTEIN, S.G.	11/25/90	5/13/'90*
CHESTNUT, P.	6/21/90*	11/29/'90
CROOMS, H.R.	9/16/90	11/16/'90
DUNCAN, B.A.	8/15/90	6/13/'90*
DUNCAN, J.L.	7/7/90	5/6/'90 *
- DYE, P.B.	8/30/90	11/14/'90
FERGUSON, H.H.	5/12/91	5/13/'90*
GLOTH, B.	9/5/90	12/13/'90
GRAHAM, J.F.	5/12/91	5/6/'90 *
- GRIMES, H.G.	11/28/90	11/29/'90
- GRUBBS, R.J.	11/14/90	4/24/'90*
GUNN, R.L.	3/1/91	6/13/'90*
- HILLIARD, C.V.	6/3/90 *	4/24/'90*
- JOHNSON, W.J.	6/27/90	4/24/'90*
JUKES, W.A.	9/30/90	5/6/'90 *
KENT, D.P.	8/1/90	6/13/'90*
LARISCY, T.H.	5/26/91	11/14/'90
LENDRUM, T.L.	11/7/90	5/6/'90 *
LEWIS, S.F.	6/31/90	5/13/'90*
LOVETT, T.	10/31/90	5/13/'90*
MCCAFFERTY, T.D.	10/31/90	5/13/'90*
MC GEE, R.L.	8/15/90	6/13/'90*
MCVAY, J.E.	9/16/90	11/16/'90
OGDEN, W.F.	8/26/90	5/13/'90*
- ONEIL, P.M.	11/28/90	11/29/'90
PELL, D.W.	10/10/90	5/6/'90 *
PIPER, D.E.	8/30/90	4/24/'90*
RIDGDILL, J.M.	6/27/90	6/13/'90*
SMITH, A. Jr	9/16/90	11/16/'90
- STEWART, W.A.	10/10/90	5/13/'90*
TAYLOR, B.K.	6/31/90	5/13/'90*
TAYLOR, W.K.	5/13/90*	4/24/'90*
- THOMPSON, T.D.	5/26/91	4/24/'90*
VAKOC, V.J.	10/17/90	12/13/'90
VON PLINSKY, J.A.	8/15/90	6/13/'90*
- WILLIAMS, S.M.	5/12/91	4/24/'90*
WILLIFORD, R.A.	9/16/90	11/16/'90
- WILLIFORD, W.S.	9/16/90	11/16/'90
WILLIS, D.S.	7/5/90	11/29/'90
WINTER, L.V.	8/15/90	6/13/'90*
WRIGHT, K.	5/26/91	11/14/'90

ERO SECURITY QUALS

SECURITY OFFICER

<u>NAME</u>	<u>GE-001</u>
- ADCOX, J.W.	8/30/90
AGEE, R.L.	7/28/90
ALLEN, R.	8/30/90
ALLSUP, D.S.	11/7/90
- ATKINS, J.W.	7/24/90
BAILEY, J.M.	7/24/90
BARBOUR, S.L.	10/10/90
BARGERON, C.	9/30/90
BARRETT, C.A.	<u>EXP'D</u>
- BATES, C.B.	8/30/90
- BECKER, H.L.	5/5/91
- BERRY, R.O.	9/16/90
BLACKMON, B.L.	11/28/90
BOWEN, P.W.	9/5/90
BRADDY, R.	11/14/90
BURKE, L.	5/8/90 *
BUSSEY, P.W.	9/16/90
- BYRD, C.E.	8/30/90
- CARPENTER, W.	9/16/90
CASON, D.	9/16/90
CHANCE, T.W.	6/7/91
CHESTNUT, P.	6/21/90*
CLARKE, L.M.	11/14/90
COOPER, M.E.	1/30/91
- CROOMS, H.R.	9/16/90
DAVIS, B.Y.	6/1/90 *
- DINKINS, E.D.	9/16/90
- DIXON, R.M.	7/24/90
DIXON, R.W.	6/5/91
- DUKES, D.R.	8/30/90
DYCHES, P.H.	1/3/91
- DYE, P.B.	8/30/90
ELLOITT, J.L.	7/24/90
ENGLETT, J.P.	10/17/90
FERGUSON, H.H.	5/12/91
- FIELDING, D.L.	9/5/90
FIELDING, L.	5/26/91
FLOURNEY, B.	5/22/90*
FOSTER, J.A.	11/7/90
- FRANCIS, D.A.	9/16/90
- GIESBER, H.G.	9/16/90
- GILLIS, W.J.	9/5/90
GLOTH, B.J.	9/5/90
GODBEE, J.M.	10/26/90

UNQUALIFIED

ERO SECURITY QUALS

PAGE 3
03/21/90

GRAHAM, H.E.	8/1/90
GRAHAM, J.F.	5/12/91
GREENE, A.R.	7/24/90
GREENE, D.F.	11/9/90
- HARRIS, J.A.	9/5/90
HERRINGTON, L.W.	9/26/90
- HILLIARD, C.V.	6/3/90 *
- HILLIS, M.M.	11/28/90
HOLLEY, T.S.	11/25/90
- HOWELL, C.	10/17/90
IVEY, W.D.	6/1/90 *
- JACKSON, C.	5/13/90*
JENKINS, G.G.	6/27/90
- JENKINS, J.C.	9/5/90
JOHNSON, N.R.	6/12/91
JONES, C.L.	5/5/91
- KELLY, J.L.	8/30/90
KITCHENS, D.P.	9/5/90
LEWIS, E.E.	6/31/90
LEWIS, R.	5/26/91
LEWIS, S.F.	6/31/90
MCGEE, R.L.	8/15/90
MCKINNEY, F.	5/27/90*
MILLER, H.	7/28/90
MILLER, J.P.	6/1/90 *
MILLS, F.L.	8/5/90
MORRIS, B.K.	7/28/90
NEAL, T.W.	6/13/90*
NEWSOME, M.	9/30/90
OGDEN, W.F.	8/26/90
OLIVER, J.W.	5/5/91
OWENS, D.E.	9/21/90
PFEIFER, C.E.	8/1/90
POWELL, D.G.	5/12/91
PREVATT, W.R.	10/17/90
RHODES, R.L.	12/25/90
ROBERTS, G.A.	8/26/90
ROBERTSON, T.L.	5/15/90*
RUIZ, L.M.	9/30/90
RUSSELL, J.P.	8/5/90
SEWELL, J.M.	5/26/91
SHAFFER, H.J.	4/31/91
SHIPES, W.O.	11/25/90
SMITH, A. Jr	9/16/90
SMITH, D.A.	<u>EXP'D</u>
SMITH, E.A.	12/22/90
STEPHENS, L.E.	6/1/90 *
STEWART, W.A.	10/10/90
STOKES, R.	5/5/91
STROBRIDGE, G.E.	5/21/91

UNQUALIFIED

ERO SECURITY QUALS

TAPLEY, B.F.	110/17/90
TAYLOR, B.K.	6/31/90
TEBEAU, B.L.	111/25/90
- THOMPSON, T.D.	5/26/91
TITUS, J.A.	111/25/90
TODD, W.	5/12/91
- TOKARSKA, J.P.	110/7/90
TURNER, V.D.	5/13/90*
VAKOC, V.J.	110/17/90
WATERS, L.F.	111/7/90
WESTERMAN, A.P.	9/16/90
- WHITE, A.L.	5/27/90*
WHITFIELD, M.	9/16/90
- WILLIAMS, D.E.	5/26/91
- WILLIAMS, S.M.	5/12/91
- WILLIFORD, W.S.	9/16/90
WILLIFORD, R.A.	9/16/90
WILLIS, D.S.	7/5/90
WOODS, D.M.	9/16/90
WRIGHT, D.P.	3/11/91
WRIGHT, K.	5/26/91
- YOUMANS, J.	111/25/90

The following personnel were available for support in the Security
Emergency Response Organization.

SECURITY EMERGENCY RESPONSE ORGANIZATION

GUTHRIE W
HUYCK D
KITCHENS C
WALKER S

TECHNICAL SUPPORT CENTER PERSONNEL

The following personnel were involved in the Emergency Operations Facility activities during the VEGP emergency of 3/20/90.

TSEC POSITION QUALS

03/21/90

- GE-001 = Badge Training
- RE-020 = Off-site Dose Assessment
- RE-030 = Rad Emerg Team/ In-plant
- RE-040 = Field Monitoring Team
- RE-060 = Repair and Corrective Action
- RE-070 = Commun. and Records
- RE-080 = Mgt. of Rad Emergencies
- RE-090 = Core Damage Assessment
- RE-008 = Medical Support of Rad Emerg
- RE-057 or CH-413 = Post Acc. Sampling

DATES LISTED ARE DROP DEAD DATES
 * RENEW QUAL 3 MO. PRIOR TO EXPIR.

- GE-099 = SCBA Training
- RE-200 = Physical Exam
- RE-201 = Resp. Fit Test
- RE-111 = Security Coord. Train

TSC MANAGER

NAME	GE--001	RE-080	GE-099	RE-200	RE-201	
BOCKHOLD, G.	11/28/90	10/26/90	1/16/91	12/31/90	12/31/90	
BURMEISTER, W.	5/7/91	7/21/90	5/5/91	03/31/91	02/28/91	
RITCHENS, W.F.	4/11/91	10/26/90	4/29/91	03/31/91	09/30/90	
MOSBAUGH, W.L.	2/20/91	7/21/90	8/11/90	NO REC.	NO REC.	
SWARTZWELDER,	4/24/91	10/6/90	4/24/91	03/31/91	02/28/91	UNQUA

OPERATIONS SUPERVISOR

NAME	GE--001	RE-080	GE-099	RE-200	RE-201	
BRINKLEY, R.K.	5/14/91	7/21/90	5/14/91	03/31/91	08/31/90	
BURMEISTER, W.	5/7/91	7/21/90	5/5/91	03/31/91	02/28/91	
CARTER, B.D.	5/7/91	7/12/90	5/5/91	03/31/91	08/31/90	
CASH, J.P.	5/14/91	7/21/90	5/14/91	03/31/91	EXP'D	UNQUA
DUNN, W.R.	5/7/91	7/6/90	5/5/91	03/31/91	11/30/90	
GASSER, J.T.	5/14/91	10/26/90	5/14/91	03/31/90*	08/31/90	
HARGIS, T.S.	5/7/91	7/21/90	5/5/91	03/31/91	03/31/91	
HOPKINS, J.D.	4/24/91	6/29/90	4/24/91	03/31/91	09/30/90	
KOZINSKY, E.J.	4/11/91	6/29/90	4/29/91	03/31/91	10/31/90	
SWARTZWELDER,	4/24/91	10/6/90	4/24/91	03/31/91	02/28/91	
WILLIAMS, C.H.	4/11/91	7/24/90	4/29/91	04/30/90*	10/31/90	
WILLIAMS, J.D.	4/17/91	10/26/90	4/17/91	03/31/90*	09/30/90	

SUPPORT COORDINATOR

NAME	GE-001	RE-070
DRAWDY, P.H.		9/6/90
HUBER, V.J.		4/8/91
QUICK, B.W.		9/30/90
		8/1/90
		6/8/90 *
		8/11/90

TSC POSITION QUALS

PAGE 2
03/21/90

ENGINEERING SUPERVISOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-090</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>
✓ <u>AUFDENKAMP, J</u>	8/26/90	7/28/90	8/26/90	03/31/91	12/31/90
✓ <u>HORTON, W.W.</u>	12/22/90	6/16/90*	5/12/91	03/31/91	01/31/91
✓ <u>MANSFIELD, R.L.</u>	10/31/90	4/18/91	4/25/91	03/31/91	02/28/91
✓ <u>WILLIAMS, J.G.</u>	6/31/90	4/18/91	6/31/90	01/31/91	01/31/91

ELECTRICAL ENGINEER

<u>NAME</u>	<u>GE-001</u>
✓ <u>BURNS, J.W.</u>	8/26/90
✓ <u>CHANCE, W.E.</u>	12/29/90
✓ <u>RAILICK, R.D.</u>	1/3/91

MECHANICAL ENGINEER

<u>NAME</u>	<u>GE-001</u>
✓ <u>BURWINKEL, P.H.</u>	12/22/90
✓ <u>COVER, W.J.</u>	12/27/90
✓ <u>STEELE, T.D.</u>	1/30/91

REACTOR ENGINEER

<u>NAME</u>	<u>GE-001</u>	<u>RE-090</u>
✓ <u>BRADLEY, S.A.</u>	5/7/91	4/18/91
✓ <u>CHRISTIANSEN,</u>	2/27/91	9/30/90
✓ <u>WENDT, T.L.</u>	7/28/90	9/30/90

MAINTENANCE SUPERVISOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-060</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>	
✓ <u>ADAMS, D.E. JR</u>	8/15/90	8/15/90	8/15/90	03/31/90*	05/31/90*	
✓ <u>BARNETT, D.P.</u>	12/29/90	12/29/90	12/29/90	03/31/91	11/30/90	
✓ <u>COURSEY, C.L.</u>	9/16/90	9/16/90	9/16/90	03/31/91	EXP'D	UNQUA
✓ <u>HOBBS, M.L.</u>	6/27/90	6/27/90	6/27/90	03/31/91	NO REC.	UNQUA
✓ <u>HUDSON, P.R.</u>	10/31/90	10/31/90	10/31/90	03/31/91	11/30/90	
✓ <u>KELLUM, E.L.</u>	7/24/90	7/24/90	7/24/90	03/31/90*	05/31/90*	
✓ <u>LAVENDER, J.E.</u>	10/31/90	10/31/90	10/31/90	03/31/90*	08/31/90	

TSC POSITION QUALS

NORWOOD, L.	9/2/90	9/2/90	9/2/90	03/31/91	06/30/90	
PHILLIPS, S.A.	11/28/90	EXP'D	1/3/91	03/31/90*	10/31/90	UNQUA
* SEYMOUR, M.E.	11/25/90	11/25/90	11/25/90	03/31/90*	11/30/90	
WOLFE, R.I.	2/3/91	2/3/91	2/3/91	03/31/91	12/31/90	

HP SUPERVISOR

NAME	GE-001	RE-020	RE-030	RE-008
		GE-099	RE-200	RE-201
ARNOLD, H.F.	4/15/91	4/17/91	4/16/91	4/16/91
BRENENSONG, G.A.	5/12/91	4/15/91	03/31/90*	01/31/91
BRETT, H.M.	5/12/91	5/14/91	5/13/91	5/13/91
BROWN, K.M.	5/12/91	5/12/91	03/31/90*	02/28/91
BURRIS, F.R.	5/5/91	5/14/91	5/13/91	5/13/91
BUSH, T.E.	4/29/91	5/12/91	03/31/90*	04/30/90*
CARSWELL, J.A.	4/15/91	5/14/91	5/13/91	5/13/91
DIXON, J.R.	5/5/91	5/12/91	05/31/90*	08/31/90
KHERA, S.S.	4/8/91	5/7/91	5/6/91	5/6/91
LUCOT, J.F.	4/8/91	5/5/91	03/31/90*	02/28/91
MATTLAGE, G.G.	5/12/91	4/31/91	4/30/91	4/30/91
PETERS, C.E.	5/12/91	4/29/91	03/31/91	01/31/91
PETROSKY, K.T.	4/22/91	4/17/91	4/16/91	4/16/91
TURPIN, B.	11/14/90	4/15/91	03/31/90*	01/31/91
		4/31/91	4/30/91	4/30/91
		5/5/91	03/31/90*	07/31/90
		4/10/91	4/9/91	4/9/91
		4/8/91	03/31/91	01/31/91
		4/10/91	4/9/91	4/9/91
		4/8/91	05/31/90*	01/31/91
		5/14/91	5/13/91	5/13/91
		5/12/91	03/31/91	10/31/90
		5/14/91	5/13/91	5/13/91
		5/12/91	03/31/90*	03/31/90*
		4/24/91	4/23/91	4/23/91
		4/22/91	03/31/91	01/31/91
		5/7/91	EXP'D	EXP'D
		11/14/90	03/31/91	07/31/90

UNQUALIFIED

CHEMISTRY SUPERVISOR

NAME	GE-001	RE-090	RE-057	CH-413
		GE-099	RE-200	RE-201
✓ HALLMAN, D.F.	7/24/90	10/18/90	2/8/91	
✓ HAND, R.C.*	6/12/91	7/24/90	03/31/91	06/30/90
		8/3/90	EXP'D	NO REC.
		6/12/91	03/31/91	06/30/90

UNQUALIFIED

* available at OSC

TSC POSITION QUALS

LEE, D.R.	4/8/91	4/18/91	4/18/91	
SILLS, J.F.B.	4/29/91	4/8/91	03/31/90*	07/31/90
		7/28/90	6/2/91	
		4/29/91	03/31/90*	06/30/90

SUPPORT STAFF

<u>NAME</u>	<u>GE-001</u>
CLARKE, P.P.C.	5/21/91
DIXON, E.L.R.	4/29/91
DRAKE, B.T.T.	9/28/90
HUBER, V.M.B.	4/8/91
JOHNSON, M.T.B.	4/8/91
JOHNSON, V.V.S.	5/13/90*
JOHNSON, M.T.B.	5/5/91
JOHNSON, M.T.B.	3/29/91
MOORE, T.L.D.	12/25/90
PEARCE, M.T.A.	9/6/90
ROBERTS, E.R.	7/26/90

STATUS LOOP COMMUNICATOR

<u>NAME</u>	<u>GE-001</u>
BISHOP, H.L.K.	4/17/91
BLALOCK, A.A.L.	5/14/91
BUCHANAN, W.A.	4/17/91
COVINGTON, J.W.	4/31/91
DRAWDY, K.L.E.	4/17/91
DURRENCE, G.J.	4/17/91
DYER, S.N.	5/14/91
GENTRY, M.L.A.	4/24/91
GUNN, G.W.	4/17/91
HIGHTOWER, M.L.	5/7/91
HOWARD, F.W. J.	4/17/91
HUMPHREY, P.A.	4/24/91
JENKINS, C.D.R.	4/31/91
JOHNS, K.A.A.	4/17/91
KIRBY, J.E.E.	4/31/91
LEWIS, M.L.L.	4/17/91
MATHESON, B.B.	4/31/91
OUELLETTE, G.A.	4/24/91
PREWITT, S.S.E.	4/17/91
SALTER, C.L.D.	4/24/91
SMITH, A.K.R.	4/31/91
SMITH, R.P.P.	4/24/91
THOMPSON, T.N.	4/17/91

TSC POSITION QUALS

TUCKER, P.L.	4/17/91
VANNIER, L.P.	4/24/91
WAINWRIGHT, G.	4/31/91
WHITLEY, G.L.	5/10/90*
WHITTEMORE, B.	4/31/91

ENN COMMUNICATOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-070</u>
DAUGHNEY, D.	1/30/91	2/16/91
HINES, D.W.	2/6/91	7/13/90
TICKETT, S.L.	8/1/90	10/19/90
STANLEY, G.B.	3/11/91	2/16/91

SECURITY COORDINATOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-111</u>
GRIMES, H.G.	11/28/90	4/26/90*
GUNN, R.L.	3/1/91	<u>EXP'D</u>
HUYCK, D.G.	8/30/90	7/24/90
JOHNSON, W.J.	6/27/90	5/21/90*
JUKES, W.A.	9/30/90	5/21/90*
KENT, D.P.	8/1/90	8/15/90
LARISCY, T.H.	5/26/91	8/15/90
LOVETT, T.	10/31/90	5/24/90*
MCCAFFERTY, T.	10/31/90	9/30/90
MCVAY, J.E.	9/16/90	7/24/90
MOORE, J.W.	8/30/90	4/26/90*
O'NEIL, F.M.	11/28/90	4/26/90*
PIPER, D.E.	8/30/90	5/21/90*
RIDGDILL, J.M.	6/27/90	6/3/90 *
TAYLOR, W.K.	5/13/90*	5/21/90*

UNQUALIFIED

The following personnel were available for support in the

TECHNICAL SUPPORT CENTER

GIESBER, HG
JAQUES JH
LONG JA
ODOM M
ROBERSON AM
SAMMONS R
WALKER GW

2-68

CONTROL ROOM PERSONNEL

The following personnel were involved in the Emergency Operations Facility activities during the VEGP emergency of 3/20/90.

03/21/90

ERO CONTROL ROOM QUALS

GE-001 = Badge Training
 RE-070 = Commun. and Records
 RE-080 = Mgt. of Rad Emergencies
 GE-099 = SCBA Training
 RE-200 = Physical Exam
 RE-201 = Resp. Fit Test

DATES LISTED ARE DROP DEAD DATES
 * RENEW QUAL 3 MO. PRIOR TO EXPIR.

OSOS

<u>NAME</u>	<u>GE-001</u>	<u>RE-080</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>	
✓BRINKLEY, R.K.	5/14/91	7/21/90	5/14/91	03/31/91	08/31/90	
✓BURMEISTER, W.	5/7/91	7/21/90	5/5/91	03/31/91	02/28/91	
CARTER, B.D.	5/7/91	7/12/90	5/5/91	03/31/91	08/31/90	
CASH, J.P.	5/14/91	7/21/90	5/14/91	03/31/91	<u>EXP'D</u>	UNQUA
✓DUNN, W.R.	5/7/91	7/6/90	5/5/91	03/31/91	11/30/90	
✓GASSER, J.T.	5/14/91	10/26/90	5/14/91	03/31/90*	08/31/90	
HARGIS, T.S.	5/7/91	7/21/90	5/5/91	03/31/91	03/31/91	
✓HOPKINS, J.D.	4/24/91	6/29/90	4/24/91	03/31/91	09/30/90	
KOZINSKY, E.J.	4/31/91	6/29/90	4/29/91	03/31/91	10/31/90	
WILLIAMS, C.H.	4/31/91	7/24/90	4/29/91	04/30/90*	10/31/90	
WILLIAMS, J.D.	4/17/91	10/26/90	4/17/91	03/31/90*	09/30/90	

SHIFT SUPERVISOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-080</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>	
BARGERON, W.L.	4/24/91	10/11/90	4/24/91	03/31/91	01/31/91	
BOWLES, J.E.	4/31/91	7/6/90	4/29/91	03/31/90*	01/31/91	
✓CHRISTIANSEN,	4/24/91	7/21/90	4/24/91	03/31/91	01/31/91	
DIEHL, W.B.	5/7/91	7/21/90	5/5/91	03/31/91	02/28/91	
✓DOUGLAS, S.M.	5/14/91	<u>EXP'D</u>	5/14/91	03/31/91	<u>EXP'D</u>	UNQUA
HALE, F.E.	5/14/91	7/24/90	5/14/91	03/31/91	05/31/90*	
HART, S.C. JR	4/17/91	10/11/90	4/17/91	03/31/91	10/31/90	
LADD, C.R.	5/7/91	7/24/90	5/5/91	03/31/91	<u>EXP'D</u>	UNQUA
✓MOORE, G.A.	4/24/91	7/12/90	4/24/91	03/31/91	01/31/91	
POLITO, T.A.	5/14/91	7/21/90	5/14/91	03/31/91	<u>EXP'D</u>	UNQUA
ROBINSON, J.C.	5/7/91	7/21/90	5/5/91	03/31/91	<u>EXP'D</u>	UNQUA
RYAN, W.T.	4/27/90*	7/21/90	4/24/90*	03/31/90*	<u>EXP'D</u>	UNQUA
✓SNIDER, R.B.	5/7/91	8/9/90	5/5/91	03/31/91	02/28/91	
STEPHENS, W.P.	4/17/91	7/24/90	4/17/91	03/31/91	01/31/91	
THORNTON, E.M.	4/17/91	7/6/90	4/17/91	03/31/90*	01/31/91	
✓VINEYARD, D.R.	4/17/91	7/6/90	4/17/91	03/31/91	01/31/91	
WHITTEMORE, B.	4/31/91	7/21/90	4/29/91	03/31/91	<u>EXP'D</u>	UNQUA
WOODFIN, D.T.	4/31/91	7/12/90	4/29/91	04/30/90*	01/31/91	

REACTOR OPERATOR

<u>NAME</u>	<u>GE-001</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>
✓BISHOP, H.K.	4/17/91	4/17/91	03/31/90*	03/31/90*

ERO CONTROL ROOM QUALS

BLALOCK, A.L.	5/14/91	5/14/91	03/31/91	<u>EXP'D</u>	UNQUALIFIED
BROWN, E.H.	5/7/91	5/5/91	03/31/91	09/30/90	
COVINGTON, J.W.	4/31/91	4/29/91	03/31/90*	09/30/90	
✓DRAWDY, K.E.	4/17/91	4/17/91	03/31/90*	01/31/91	
DURRENCF, G.J.	4/17/91	4/17/91	03/31/91	01/31/91	
✓DYER, S.N.	5/14/91	5/14/91	03/31/91	<u>EXP'D</u>	UNQUALIFIED
GENTRY, M.A.	4/24/91	4/24/91	03/31/91	01/31/91	
HARRIS, T.L.	5/5/91	5/5/91	03/31/91	02/28/91	
HIGHTOWER, M.L.	5/7/91	5/5/91	03/31/90*	03/31/91	
✓HOWARD, F.W. J	4/17/91	4/17/91	03/31/91	10/31/90	
✓HUMPHREY, P.A.	4/24/91	4/24/91	03/31/90*	02/28/91	
JENKINS, D.R.	4/31/91	4/29/91	03/31/91	03/31/90*	
✓JOHNS, K.A.	4/17/91	4/17/91	03/31/90*	01/31/91	
KIRBY, J.E.	4/31/91	4/29/91	03/31/90*	09/30/90	
LEWIS, M.L.	4/17/91	4/17/91	03/31/91	03/31/91	
MANEY, W.D.	5/14/91	5/14/91	03/31/91	10/31/90	
MATHESON, B.B.	4/31/91	4/29/91	03/31/90*	10/31/90	
✓OUELLETTE, G.A.	4/24/91	4/24/91	03/31/91	01/31/91	
OVERBY, L.M.	5/7/91	5/5/91	03/31/90*	10/31/90	
ROWLAND, R.R.	5/7/91	5/5/91	03/31/91	09/30/90	
SALTER, C.D.	4/24/91	4/24/91	03/31/90*	10/31/90	
✓SHUMAN, W.H.	5/14/91	5/14/91	03/31/91	10/31/90	
SMITH, A.K.	4/31/91	4/29/91	03/31/91	01/31/91	
✓SMITH, R.P.	4/24/91	4/24/91	03/31/90*	01/31/91	
✓SWEAT, A.Q.	5/14/91	5/14/91	03/31/91	11/30/90	
✓VANNIER, L.P.	4/24/91	4/24/91	03/31/91	01/31/91	
WAINWRIGHT, G.	4/31/91	4/29/91	03/31/90*	08/31/90	

ENN COMMUNICATOR

NAME	GE-001	RE-070	GE-099	RE-200	RE-201	
ALLEN, R.	8/30/90	5/20/90*	<u>EXP'D</u>	03/31/90*	<u>NO REC.</u>	UNQUA
ALLSUP, D.S.	11/7/90	3/15/91	3/14/91	<u>NO REC.</u>	<u>NO REC.</u>	UNQUA
✓ANDERSON, A.J.	1/6/91	11/21/90	1/6/91	03/31/91	10/31/90	
ATKINS, J.W.	7/24/90	7/13/90	7/24/90	<u>NO REC.</u>	12/31/90	UNQUA
BLACKBURN, H.N	12/8/90	7/13/90	12/8/90	03/31/91	09/30/90	
BYRD, C.E.	8/30/90	5/20/90*	11/4/90	12/31/90	01/31/91	
DAVIS, B.Y.	6/1/90 *	8/11/90	<u>EXP'D</u>	12/31/90	<u>NO REC.</u>	UNQUA
✓DEWBRE, N.N.	5/12/91	7/11/90	5/12/91	03/31/91	02/28/91	
DINKINS, E.D.	9/16/90	5/2/90 *	9/16/90	<u>EXP'D</u>	12/31/90	UNQUA
DIXON, R.M.	7/24/90	7/13/90	7/24/90	<u>NO REC.</u>	12/31/90	UNQUA
DYCHES, P.H.	1/3/91	6/9/91	<u>EXP'D</u>	<u>NO REC.</u>	<u>NO REC.</u>	UNQUA
ENGLETT, J.P.	10/17/90	10/19/90	10/13/90	01/31/91	<u>NO REC.</u>	UNQUA
GLOTH, B.J.	9/5/90	5/14/90*	10/31/90	<u>EXP'D</u>	<u>NO REC.</u>	UNQUA
GRAHAM, H.E.	8/1/90	10/19/90	10/13/90	01/31/91	01/31/91	
GREENE, A.R.	7/24/90	5/20/90*	11/4/90	12/31/90	<u>NO REC.</u>	UNQUA
HARRIS, J.A.	9/5/90	10/19/90	11/4/90	<u>EXP'D</u>	<u>NO REC.</u>	UNQUA
HOLLEY, T.S.	11/25/90	6/8/90 *	10/13/90	01/31/91	<u>NO REC.</u>	UNQUA

ERO CONTROL ROOM QUALS

	<u>EXP'G</u>			<u>NO REC.</u>	<u>NO REC.</u>	
HULL, S.D.		7/11/90	4/26/90*			UNQUA
✓JENKINS, P.W.	9/5/90	7/11/90	9/16/90	03/31/90*	05/31/90*	
✓JONES, T.B.	2/6/91	7/13/90	2/6/91	03/31/91	05/31/90*	
LANE, L.P.	1/11/91	7/13/90	1/6/91	03/31/91	<u>EXP'D</u>	UNQUA
MCKINNEY, F.	5/27/90*	5/2/90 *	7/10/90	12/31/90	01/31/91	
MILES, D.	11/28/90	7/11/90	5/6/90 *	04/30/90*	05/31/90*	
MILLER, H.	7/28/90	10/19/90	10/13/90	01/31/91	01/31/91	
MILLS, F.L.	8/5/90	3/10/91	3/14/91	12/31/90	02/28/91	
MORRIS, B.K.	7/28/90	4/26/90*	7/10/90	01/31/91	01/31/91	
MORRIS, M.J.L.	5/1/90 *	7/13/90	5/2/90 *	<u>NO REC.</u>	<u>NO REC.</u>	UNQUA
PFEIFER, C.E.	8/1/90	6/8/90 *	10/13/90	01/31/91	01/31/91	
RHODES, R.L.	12/25/90	5/14/90*	7/24/90	<u>NO REC.</u>	12/31/90	UNQUA
ROBERTSON, T.L	5/15/90*	8/11/90	3/1/91	<u>EXP'D</u>	<u>NO REC.</u>	UNQUA
STEPHENS, L.E.	6/1/90 *	5/20/90*	10/31/90	02/28/91	02/28/91	
TOKARSKA, J.P.	10/7/90	5/2/90 *	7/10/90	01/31/91	01/31/91	
WESTERMAN, A.P	9/16/90	4/26/90*	9/16/90	01/31/91	01/31/91	
WILLIAMS, D.E.	5/26/91	5/14/90*	2/6/91	12/31/90	<u>NO REC.</u>	UNQUA

PLANT EQUIPMENT OPERATOR

<u>NAME</u>	<u>GE-001</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>
ADAMS, L.A.	4/29/91	4/29/91	07/31/90	06/30/90
ANDERSON, J.R.	5/5/91	5/5/91	03/31/91	02/28/91
BAREFIELD, M.C	5/5/91	5/5/91	03/31/91	02/28/91
BEARD, J.C.	5/5/91	5/5/91	03/31/91	02/28/91
✓BOUCHARD, R.	10/10/90	10/10/90	05/31/90*	08/31/90
BRACK, W.E.	1/6/91	1/6/91	03/31/91	03/31/90*
BRANTLEY, D.M.	4/13/91	4/22/91	03/31/91	03/31/91
BROWN, S.R.	4/29/91	4/29/91	03/31/91	01/31/91
CHANCE, R.D.	5/5/91	5/5/91	03/31/91	02/28/91
CLIFTON, J.C.	5/12/91	5/12/91	03/31/91	10/31/90
✓COBB, J.H. JR	6/27/90	6/27/90	03/31/91	04/30/90*
COLLINS, C.M.	5/12/91	5/12/91	03/31/91	09/30/90
CRABE, R.E.	5/5/91	5/5/91	03/31/91	02/28/91
DAVIS, T.	5/12/91	5/12/91	04/30/90*	05/31/90*
DELOACH, D.A.	5/5/91	5/5/91	03/31/90*	02/28/91
DUNN, L.B.	4/13/91	4/22/91	03/31/91	05/31/90*
EAVES, E.P.	6/27/90	6/27/90	03/31/91	05/31/90*
FORTNEY, L.A.	4/29/91	4/29/91	03/31/91	07/31/90
✓GANDY, D.L.	4/13/91	4/22/91	03/31/91	03/31/91
GATLIFF, J.A.	4/15/91	4/15/91	03/31/91	03/31/90*
✓GOODRUM, J.L.	4/13/91	4/22/91	03/31/91	03/31/91
GRAHAM, N.F.	4/29/91	4/29/91	03/31/91	01/31/91
✓GRANT, W.C.	4/13/91	4/22/91	03/31/91	05/31/90*
HAWES, D.H.	4/15/91	4/15/91	03/31/91	06/30/90
HENRY, M.C.	4/29/91	4/29/91	03/31/91	12/31/90
HUNT, P.M.	4/15/91	4/15/91	03/31/91	05/31/90*
✓HUTTON, C.E.	5/12/91	5/12/91	03/31/91	12/31/90

ERO CONTROL ROOM QUALS

JACKSON, J.C.	4/13/91	4/22/91	03/31/91	04/30/90*	
✓ JACKSON, M.T.	5/12/91	5/12/91	03/31/90*	02/28/91	
JENKINS, A.C.	4/29/91	4/30/90*	03/31/91	04/30/90*	
JOSEY, J.W.	1/30/91	1/30/91	03/31/91	03/31/90*	
JUNTUNEN, J.A.	3/11/91	<u>EXP'D</u>	03/31/91	03/31/91	UNQUALIFIED
KAISER, S.	5/26/91	5/30/91	03/31/90*	02/28/91	
KEADLE, R.V.	4/13/91	4/22/91	03/31/90*	02/28/91	
KESLER, S.B.	5/5/91	5/5/91	03/31/90*	02/28/91	
LEWIS, W.H.	4/15/91	4/15/91	03/31/91	04/30/90*	
✓ MANLEY, E.V.	6/5/91	6/5/91	03/31/90*	05/31/90*	
✓ MANLEY, L.W.	1/30/91	1/30/91	03/31/90*	10/31/90	
MARTINEZ, B.A.	3/11/91	<u>EXP'D</u>	03/31/91	03/31/91	UNQUALIFIED
MASON, F.L.	5/28/91	7/28/90	05/31/90*	06/30/90	
MCBRIDE, T.T.	5/5/91	5/5/91	04/30/90*	02/28/91	
MCDANIEL, E.S.	4/13/91	4/22/91	03/31/91	03/31/91	
MIMS, E.L.	4/29/91	4/29/91	03/31/91	01/31/91	
MITCHELL, W.R.	4/13/91	4/22/91	03/31/91	03/31/90*	
MOORE, R.S.	4/13/91	4/22/91	03/31/91	01/31/91	
✓ MORRIS, T.L.	4/13/91	4/22/91	03/31/91	03/31/91	
MORTON, R.R.	5/5/91	5/5/91	03/31/91	02/28/91	
MOXLEY, G.G.	5/26/91	6/5/91	03/31/90*	05/31/90*	
MULLING, S.C.	5/12/91	5/12/91	03/31/90*	03/31/90*	
MYLER, J.K.	5/5/91	5/5/91	03/31/91	02/28/91	
NEWSOME, J.M.	4/29/91	4/27/90*	03/31/90*	06/30/90	
NIX, H.A.	4/15/91	4/15/91	03/31/90*	05/31/90*	
POST, R.L.	4/15/91	4/15/91	03/31/91	04/30/90*	
POWERS, C.F.	4/15/91	4/15/91	03/31/90*	01/31/91	
PROCTOR, S.D.	5/5/91	5/5/91	03/31/91	02/28/91	
FRUITT, P.S.	4/29/91	4/29/91	03/31/91	09/30/90	
PURVIS, D.A.	4/29/91	4/29/91	03/31/90*	10/31/90	
✓ QUICK, D.K.	6/27/90	6/27/90	05/31/90*	05/31/90*	
SAXON, G.R.	5/5/91	5/5/91	03/31/91	02/28/91	
SHARKEY, J.P.	5/5/91	5/5/91	04/30/90*	02/28/91	
✓ SHEFFIELD, G.A.	4/15/91	4/15/91	03/31/91	04/30/90*	
✓ SMITH, R. III	4/15/91	4/15/91	03/31/91	07/31/90	
SONNEDECKER, G	5/12/91	5/12/91	03/31/91	08/31/90	
SOWELL, D.F.	4/29/91	4/29/91	03/31/90*	08/31/90	
THOMPSON, R.L.	4/13/91	5/12/91	03/31/91	02/28/91	
TOLBERT, T.S.	5/12/91	5/12/91	03/31/91	06/30/90	
✓ WALDEN, W.T.	2/27/91	2/27/91	03/31/91	12/31/90	
WALKER, M.W.	4/29/91	4/29/91	03/31/91	11/30/90	
WATERS, L.F.	5/26/91	6/5/91	03/31/90*	09/30/90	
✓ WEAVER, S.H.	5/12/91	5/12/91	03/31/91	03/31/90*	
WHITE, I.B.	4/29/91	4/29/91	03/31/90*	01/31/91	
WHITMAN, S.L.	4/13/91	4/22/91	03/31/90*	04/30/90*	
WILLIAMS, R.E.	5/12/91	5/12/91	03/31/91	07/31/90	
✓ WOOD, G.F.	4/15/91	4/15/91	03/31/91	05/31/90*	
WOOD, L.L.	4/29/91	4/29/91	03/31/91	01/31/91	

ERO CONTROL ROOM QUALS

PAGE 5
03/21/90

SHIFT TECHNICAL ADVISOR

<u>NAME</u>	<u>GE-001</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>	
BARGERON, W.L.	4/24/91	4/24/91	03/31/91	01/31/91	
BOWLES, J.E.	4/31/91	4/29/91	03/31/90*	01/31/91	
BURMEISTER, W.	5/7/91	5/5/91	03/31/91	02/28/91	
CARTER, B.D.	5/7/91	5/5/91	03/31/91	08/31/90	
CASH, J.P.	5/14/91	5/14/91	03/31/91	<u>EXP'D</u>	UNQUALIFIED
✓CHRISTIANSEN,	4/24/91	4/24/91	03/31/91	01/31/91	
DIEHL, W.B.	5/7/91	5/5/91	03/31/91	02/28/91	
✓DOUGLAS, S.M.	5/14/91	5/14/91	03/31/91	<u>EXP'D</u>	UNQUALIFIED
✓GASSER, J.T.	5/14/91	5/14/91	03/31/90*	08/31/90	
HARGIS, T.S.	5/7/91	5/5/91	03/31/91	03/31/91	
HART, S.C. JR	4/17/91	4/17/91	03/31/91	10/31/90	
KOZINSKY, E.J.	4/31/91	4/29/91	03/31/91	10/31/90	
LADD, C.R.	5/7/91	5/5/91	03/31/91	<u>EXP'D</u>	UNQUALIFIED
✓LOFTIN, R.A.	4/31/91	4/30/91	03/31/90*	01/31/91	
POLITO, T.A.	5/14/91	5/14/91	03/31/91	<u>EXP'D</u>	UNQUALIFIED
RYAN, W.T.	4/27/90*	4/24/90*	03/31/90*	<u>EXP'D</u>	UNQUALIFIED
SLIVKA, M.A.	10/17/90	1/27/91	03/31/91	10/31/90	
✓SNIDER, R.B.	5/7/91	5/5/91	03/31/91	02/25/91	
THORNTON, E.M.	4/17/91	4/17/91	03/31/90*	01/31/91	
WHITTEMORE, B.	4/31/91	4/29/91	03/31/91	<u>EXP'D</u>	UNQUALIFIED
WILLIAMS, J.L.	4/17/91	4/17/91	03/31/90*	09/30/90	
WOODFIN, D.T.	4/31/91	4/29/91	04/30/90*	01/31/91	

The following personnel were available for support in the control room.

CONTROL ROOM

BOCKHOLD G
CHESNUT SH
DIGBY JW
ECKERT, CC
MANSFIELD RL
PETTITT SD
POPE RK
RHULAND JE
SWARTZWELDER JE
WILLIAMS HG
WHITENER H

2-69

OPERATIONS SUPPORT CENTER PERSONNEL

The following personnel were involved in the Emergency Operations Facility activities during the VEGP emergency of 3/20/90.

OSC POSITION QUALS

03/21/90

GE-001 = Emerg Plan Overview
 RE-030 = Rad Emerg Team /In-plant
 RE-040 = Field Monitor Team
 RE-060 = Repair & Corr. Action
 RE-080 = Management of Rad Emerg
 RE-056 or CH-413 = Post Acc Sampling
 RE-008 = Medical Support of Rad Emerg
 GE-005 = First Aid Training or
 GE-155 = First Responder Course

DATES LISTED ARE DROP DEAD DATES
 * RENEW QUAL 3 MO. PRIOR TO EXPIR.

GE-099 = SCBA Training
 RE-200 = Physical Exam
 RE-201 = Resp. Fit Test

OSC MANAGER

<u>NAME</u>	<u>GE-001</u>	<u>RE-060</u>	<u>RE-080</u>
✓ COURSEY, C.L.	9/16/90	9/16/90	5/14/91
GRIFFIS, M.A.	12/8/90	1/23/91	7/5/90
GUSTAFSON D.E.	1/27/91	3/15/91	3/4/91
✓ HANDFINGER, H.	12/29/90	8/17/90	10/26/90
HOBBS, M.L.	6/27/90	6/27/90	4/10/91
PHILLIPS, S.A.	11/28/90	EXP'D	4/10/91
SUTPHIN, J.	5/3/90 *	5/20/91	10/26/90

UNQUA

ELECTRICAL FOREMAN

<u>NAME</u>	<u>GE-001</u>	<u>RE-060</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>
✓ ANSLEY, H.B.	8/1/90	8/1/90	8/1/90	03/31/90*	05/31/90*
BEASLEY, J.E.	5/12/91	5/12/91	5/12/91	03/31/91	02/28/91
BENNETT, M.O.	7/28/90	7/28/90	7/28/90	03/31/90*	05/31/90*
FIELDS, F.B.	5/13/90*	5/20/91	5/19/91	03/31/91	02/28/91
✓ FRY, J.L.	6/27/90	5/20/91	5/19/91	03/31/90*	02/28/91
HODNETT, W.K.	11/4/90	11/4/90	11/4/90	03/31/91	09/30/90
HUNT, T.L.	5/5/91	5/5/91	5/5/91	03/31/91	03/31/90*
JONES, A.A.	11/28/90	11/28/90	11/28/90	03/31/91	11/30/90
JUSTICE, C.W.	9/30/90	11/28/90	11/28/90	03/31/91	03/31/90*
LANE, G.F.	9/26/90	9/26/90	9/26/90	03/31/91	09/30/90
✓ LASSITER, D.L.	9/26/90	9/26/90	9/26/90	03/31/91	11/30/90
LEWIS, C.J.	11/7/90	11/7/90	11/7/90	03/31/91	06/30/90
PARRAM, E.W. J	8/1/90	8/1/90	8/1/90	03/31/90*	05/31/90*
✓ SHEPHERD, R.G.	9/2/90	9/2/90	9/2/90	03/31/91	06/30/90
✓ SILVA, M.P.	6/27/90	5/20/91	5/19/91	03/31/91	02/28/91
THOMPSON, G.H.	9/5/90	9/5/90	9/5/90	03/31/90*	05/31/90*
WILKES, I.D.	4/29/91	5/20/91	5/19/91	03/31/90*	02/28/91

MECHANICAL FOREMAN

<u>NAME</u>	<u>GE-001</u>	<u>RE-060</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>
ADAMS, M.C.	6/29/90	6/27/90	6/27/90	03/31/91	EXP'D
✓ BURCHETT, M.G.	5/5/91	5/5/91	5/5/91	03/31/91	06/30/90
EIDSON, M.S.	5/12/91	5/12/91	5/12/91	03/31/91	02/28/91

UNQUA

OSC POSITION QUALS

✓GARRISON, J.M.	5/12/91	5/12/91	5/12/91	03/31/91	02/28/91
GODFREY, M.W.	5/27/90*	5/20/91	5/19/91	03/31/91	09/30/90
HOWARD, R.C.	4/29/91	5/13/90*	4/29/91	03/31/91	03/31/90*
MULLINAX, R.A.	11/14/90	11/14/90	11/14/90	02/28/91	05/31/90*
RICHARDSON, L.	5/12/91	5/12/91	5/12/91	03/31/91	07/31/90
✓SECKINGER, D.A.	7/10/90	7/10/90	7/10/90	03/31/91	04/30/90*
WHEELER, H.M.	4/29/91	4/29/91	4/29/91	03/31/91	06/30/90
WHITFIELD, W.D.	7/26/90	7/28/90	7/28/90	03/31/90*	05/31/90*

INST & CONTROLS FOREMAN

NAME	GE-001	RE-060	GE-099	RE-200	RE-201	
BOUTWELL, A.S.	6/27/90	6/27/90	6/27/90	03/31/91	12/31/90	
✓BRINEY, M.S.	6/13/90*	6/13/90*	6/13/90*	03/31/91	08/31/90	
COOK, T.W.	6/27/90	6/27/90	6/27/90	03/31/91	07/31/90	
CORLEY, C.W.	11/28/90	11/28/90	EXP'D	03/31/91	03/31/90*	UNQUA
DENT, M.L.	4/29/91	4/29/91	4/29/91	03/31/91	08/31/90	
✓DUNCAN, M.D.	1/30/91	1/30/91	1/30/91	03/31/91	02/28/91	
FAULKNER, J.W.	3/29/91	3/29/91	3/29/91	03/31/91	12/31/90	
FORTSON, G.B.	5/26/91	5/6/90 *	5/6/90 *	03/31/90*	EXP'D	UNQUA
HAMMOND, R.S.	7/10/90	7/10/90	7/10/90	03/31/91	08/31/90	
✓LAMB, T.G.	5/12/91	5/12/91	5/12/91	03/31/90*	EXP'D	UNQUA
✓NOBLETT, L.P.	4/29/91	4/29/91	4/29/91	03/31/91	02/28/91	
RUCKMAN, T.A.	6/12/91	6/12/91	6/12/91	EXP'D	NO REC.	UNQUA
✓WILLIS, T.L.	11/28/90	11/28/90	11/28/90	03/31/91	07/31/90	
✓WIMBURN, J.M.	11/25/90	12/1/90	11/25/90	03/31/91	08/31/90	

ELECTRICIANS

NAME	GE-001	RE-060	GE-099	RE-200	RE-201	
ALFORD, G.R.	10/17/90	10/17/90	10/17/90	03/31/91	10/31/90	
BAKER, C.R.	5/5/91	5/5/91	5/5/91	03/31/91	11/30/90	
BAKER, R.E.	5/12/91	5/6/90 *	5/12/91	03/31/91	10/31/90	
BATES, C.W.	1/30/91	1/30/91	1/30/91	03/31/91	10/31/90	
BLAIR, R.P.	9/6/90	9/5/90	9/5/90	03/31/90*	11/30/90	
BOYKIN, D.L.	9/6/90	9/5/90	9/5/90	03/31/91	11/30/90	
✓BROOKS, J.W.	8/3/90	8/1/90	8/1/90	03/31/91	05/31/90*	
✓BROWN, D.S.	4/29/91	4/29/91	4/29/91	03/31/91	01/31/91	
✓BROWN, R.	11/9/90	11/7/90	11/7/90	03/31/91	06/30/90	
✓BROWNEE, J.W.	9/28/90	9/26/90	9/26/90	03/31/91	11/30/90	
BULLINS, K.W.	10/17/90	10/17/90	10/17/90	03/31/90*	09/30/90	
CHALKER, L.M.	11/28/90	11/28/90	11/28/90	03/31/91	10/31/90	
✓COOPER, C.D.	4/5/91	4/5/91	4/5/91	03/31/91	01/31/91	
DAVIS, III R.H.	12/25/90	12/25/90	12/25/90	03/31/91	07/31/90	
DEISLEY, D.A.	12/29/90	12/29/90	12/29/90	03/31/91	EXP'D	UNQUA
DIXON, R.C.	11/7/90	11/7/90	11/7/90	03/31/91	11/30/90	

GSC POSITION QUALS

EASON, W.F.	7/12/90	7/10/90	7/10/90	03/31/91	04/30/90*	
ELROD, D.B.	10/12/90	10/10/90	10/10/90	03/31/90*	09/30/90	
✓FAIRES, J.E.	11/7/90	11/7/90	11/7/90	03/31/91	08/31/90	
FIEST, R.B.	8/26/90	8/26/90	8/26/90	03/31/91	07/31/90	
✓FRAZIER, M.A.	5/3/90 *	5/20/91	5/19/91	03/31/91	03/31/90*	
GRIGGS, J.L.	10/31/90	10/31/90	10/31/90	03/31/91	11/30/90	
HALE, R.D.	11/28/90	11/28/90	11/28/90	03/31/91	03/31/90*	
✓HARRELL, J.V.	5/15/90*	5/20/91	5/19/91	03/31/91	<u>EXP'D</u>	UNQUA
✓HEATH, A.N. JR	8/3/90	8/1/90	8/1/90	03/31/90*	11/30/90	
✓HEATH, J.W.	3/29/91	3/29/91	3/29/91	03/31/91	12/31/90	
HJCKS, K.R.	4/29/91	4/29/91	4/29/91	03/31/91	01/31/91	
HOLIDAY, D.	11/28/90	11/28/90	11/28/90	03/31/91	09/30/90	
HOLLIDAY, R.M.	8/1/90	8/1/90	8/1/90	03/31/91	06/30/90	
HOOKS, W.H.	2/20/91	2/20/91	2/20/91	03/31/91	11/30/90	
✓HUTCHINS, D.E.	5/12/91	5/12/91	5/12/91	03/31/91	03/31/90*	
✓KITCHENS, J.M.	7/12/90	7/10/90	7/10/90	03/31/91	<u>NO REC.</u>	UNQUA
LING, R.W.	11/28/90	<u>EXP'D</u>	11/28/90	03/31/91	10/31/90	UNQUA
✓MACHAK, T.M.	5/12/91	5/12/91	5/12/91	03/31/91	02/28/91	
✓PARKER, S.R.	8/3/90	8/1/90	8/1/90	03/31/90*	<u>EXP'D</u>	UNQUA
✓RAYBURN, M.T.	5/12/91	5/12/91	5/12/91	03/31/91	05/31/90*	
RHODES, J.E.	7/10/90	7/10/90	7/10/90	03/31/91	05/31/90*	
✓ROBERSON, L.	4/8/91	4/8/91	4/27/90*	03/31/91	07/31/90	
✓ROGERS, F.K.	5/5/91	5/5/91	5/5/91	03/31/90*	06/30/90	
SANKEY, J.L.	3/11/91	<u>EXP'D</u>	<u>EXP'D</u>	03/31/91	12/31/90	UNQUA
SAUNDERS, R.B.	10/31/90	10/17/90	10/17/90	03/31/91	07/31/90	
SEAMONDS, M.E.	11/28/90	11/28/90	11/28/90	03/31/91	09/30/90	
SHUMAN, S.C.	3/11/91	<u>EXP'D</u>	<u>EXP'D</u>	03/31/91	11/30/90	UNQUA
✓SIENKIEWICZ, L	3/29/91	3/29/91	3/29/91	03/31/91	12/31/90	
TOWNSEND, D.W.	6/8/90 *	5/20/91	5/19/91	02/28/91	03/31/90*	
WALDRUP, W.A.	5/5/91	5/5/91	5/5/91	<u>EXP'D</u>	02/28/91	UNQUA
WEATHERSBEE, R	4/29/91	4/29/91	4/29/91	03/31/90*	11/30/90	
✓WILLIAMS, J.F.	12/22/90	12/22/90	12/22/90	03/31/90*	06/30/90	
WOLFE, D.W.	3/29/91	3/29/91	3/29/91	03/31/91	02/28/91	
✓WRIGHT, T.H.	5/5/91	5/5/91	5/5/91	03/31/91	02/28/91	

MECHANICS

<u>NAME</u>	<u>GE-001</u>	<u>RE-060</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>
✓ALLEN, A.A.	4/10/91	4/5/91	4/5/91	03/31/91	01/31/91
ARCHER, R.L.	11/7/90	11/7/90	11/7/90	03/31/91	08/31/90
✓ATCHLEY, J.L.	8/3/90	8/1/90	8/1/90	03/31/91	11/30/90
AVRET, J.W.	7/12/90	7/10/90	7/10/90	03/31/91	11/30/90
✓BAREFIELD, R.I	4/8/91	4/8/91	4/8/91	03/31/91	05/31/90*
✓BARWICK, G.L.	7/5/90	5/20/91	5/19/91	03/31/90*	05/31/90*
BRAGG, R.M.	11/14/90	11/14/90	11/14/90	03/31/91	06/30/90
✓COLE, J.I. JR	5/5/91	5/5/91	5/5/91	03/31/91	03/31/90*
✓CONNER, L.L.	4/5/91	4/5/91	4/5/91	03/31/91	05/31/90*
✓COOK, L.T.	5/5/91	5/5/91	5/5/91	03/31/91	02/28/91

OSC POSITION QUALS

✓ COSKREY, G.J.	11/14/90	11/14/90	11/14/90	03/31/91	05/31/90*
CUCCI, T.B.	11/7/90	11/7/90	11/7/90	03/31/91	05/31/90*
DAVIS, H.	4/5/91	4/5/91	4/5/91	03/31/91	01/31/91
EDWARDS, G.L.	10/17/90	10/17/90	10/17/90	03/31/91	09/30/90
✓ EDWARDS, P.M.	4/29/91	4/29/91	4/29/91	03/31/91	05/31/90*
ENGLE, F.H.	4/29/91	5/5/91	4/29/91	03/31/91	03/31/90*
EUBANKS, W.M.	8/17/90	8/15/90	8/15/90	03/31/91	11/30/90
FLANDEFS, J.M.	4/29/91	4/29/91	4/29/91	03/31/91	01/31/91
FOREHAND, K.R.	5/5/91	5/5/91	5/5/91	03/31/91	04/30/90*
FOREHAND, R.G.	9/28/90	9/26/90	9/26/90	03/31/91	07/31/90
GALLAGHER, D.E	10/17/90	10/17/90	10/17/90	03/31/91	03/31/90*
GILES, D.M.	5/5/91	5/5/91	5/5/91	03/31/91	03/31/91
GLOVER, C.E.	4/29/91	4/29/91	4/29/91	03/31/91	11/30/90
HARLON, T.B.	3/1/91	3/1/91	3/1/91	03/31/90*	11/30/90
HAWKINS, D.V.	3/1/91	3/1/91	3/1/91	03/31/91	05/31/90*
✓ HEATH, R.G.	1/11/91	2/10/91	1/12/91	03/31/91	EXP'D
HILL, R.E.	3/11/91	6/6/90 *	6/6/90 *	03/31/91	05/31/90*
HODGES, B.	10/31/90	10/31/90	10/31/90	03/31/91	08/31/90
✓ HOLCOMB, W.B.	4/8/91	4/8/91	4/8/91	03/31/91	02/28/91
JANOW, D.L.	4/8/91	4/8/91	4/27/90*	03/31/91	NO REC.
KEEN, J.R.	5/12/91	5/13/90*	5/12/91	03/31/91	03/31/90*
KING, F.L.	3/29/91	3/29/91	3/29/91	03/31/91	05/31/90*
LEONARD, D.W.	9/28/90	9/26/90	9/26/90	03/31/91	10/31/90
LOLLAR, D.H.	4/8/91	4/8/91	4/8/91	03/31/91	01/31/91
✓ MARTIN, T.L.	9/6/90	9/5/90	9/5/90	03/31/91	07/31/90
MCBRIDE, J.A.	4/5/91	4/5/91	4/5/91	03/31/91	02/28/91
MEGGS, S.G.	3/11/91	5/24/90*	5/24/90*	03/31/91	06/30/90
MOORE, J.V. II	11/28/90	11/28/90	11/28/90	03/31/91	08/31/90
MORRIS, R.F.	5/12/91	5/12/91	5/12/91	03/31/90*	03/31/90*
MURRAY, T.P.	11/28/90	11/28/90	11/28/90	03/31/90*	09/30/90
✓ PARKER, J.E.	12/1/90	12/1/90	12/1/90	03/31/90*	10/31/90
✓ PATTON, W.C.	5/12/91	6/27/90	5/12/91	03/31/91	02/28/91
PENDERGROFT, R	12/25/90	12/25/90	12/25/90	03/31/91	10/31/90
PHILLIPS, R.D.	5/15/90*	5/20/91	5/19/91	03/31/91	11/30/90
POPE, L.W. SR	11/7/90	11/7/90	11/7/90	03/31/91	08/31/90
RAYBURN, T.D.	9/26/90	9/26/90	9/26/90	03/31/91	07/31/90
REMINGTON, R.A	11/14/90	11/14/90	11/14/90	03/31/91	11/30/90
✓ SAYLORS, S.E.	11/4/90	11/4/90	11/4/90	03/31/91	08/31/90
SHEW, J.C.	9/6/90	9/5/90	9/5/90	03/31/90*	09/30/90
SHIELDS, J.D.	9/28/90	9/26/90	9/26/90	03/31/91	09/30/90
SLOOP, J.B.	11/4/90	11/4/90	11/4/90	03/31/91	08/31/90
SPICER, M.W.	11/28/90	11/28/90	11/28/90	03/31/91	07/31/90
STONE, J.B.	2/20/91	2/20/91	2/20/91	03/31/91	12/31/90
STUTZ, T.L.	4/29/91	5/5/91	4/29/91	03/31/91	02/28/91
THOMPSON, J.E.	6/29/90	6/27/90	6/27/90	03/31/91	08/31/90
✓ THOMPSON, R.D.	3/29/91	3/29/91	3/29/91	03/31/91	06/30/90
✓ TUGGLE, J.C.	5/12/91	5/12/91	5/12/91	03/31/91	03/31/90*
✓ WALKER, D.C.	11/7/90	11/7/90	11/7/90	03/31/91	06/30/90
WEAVER, B.O.	11/7/90	11/7/90	11/7/90	03/31/91	08/31/90
✓ WEAVER, R.E.	6/29/90	6/27/90	6/27/90	03/31/91	12/31/90

UNQDA

UNQDA

OSC POSITION QUALS

WEBB, W.L.	7/26/90	7/24/90	7/24/90	03/31/91	12/31/90
✓WHITE, B.K.	4/5/91	2/6/91	4/5/91	03/31/91	06/30/90
WITHROW, J.L.	5/5/91	5/5/91	5/5/91	03/31/91	03/31/90*
WOOTEN, W.M.	10/31/90	10/31/90	10/31/90	03/31/91	10/31/90

INSTR & CONTROLS TECHNICIANS

NAME	GE-001	RE-060	GE-099	RE-200	RE-201	
AQUINDE, D.N.	11/4/90	11/4/90	11/4/90	03/31/91	07/31/90	
BERRY, T.A.	5/5/91	5/20/91	5/5/91	03/31/91	02/28/91	
BIANCHI-ROSSI, *	5/6/90	5/20/91	5/19/91	03/31/91	02/28/91	
BOERNER, A.M.	2/3/91	2/3/91	2/3/91	03/31/91	11/30/90	
BOYER, W.E.	9/16/90	9/16/90	9/16/90	03/31/91	07/31/90	
BURROUGHS, J.J	11/7/90	11/7/90	11/7/90	03/31/91	03/31/90*	
CLAYBURN, N.	5/5/91	5/5/91	5/5/91	03/31/91	EXP'D	
✓CONTI, R.S.	6/5/91	6/5/91	6/5/91	03/31/91	03/31/90*	UNQUA
CULLUM, J.C.	11/25/90	11/25/90	11/25/90	03/31/91	06/30/90	
CULPEPPER, R.E	6/12/90*	EXP'D	11/25/90	03/31/91	03/31/90*	UNQUA
DALIS, M.J.	4/15/91	4/15/91	4/15/91	03/31/91	03/31/90*	
✓DAVIS, J.D.	4/29/91	4/29/91	4/29/91	03/31/91	03/31/90*	
DOMINGUEZ, P.A	2/17/91	2/27/91	2/27/91	03/31/91	01/31/91	
ERKENS, E.C.	4/5/91	4/5/91	4/5/91	03/31/91	07/31/90	
FERRARO, D.G.	2/3/91	2/3/91	2/3/91	03/31/91	04/30/90*	
✓FOWLER, A.V.	6/15/90*	6/13/90*	6/13/90*	03/31/91	07/31/90	
FULLER, D.	5/12/91	5/12/91	5/12/91	03/31/91	05/31/90*	
GILCHRIST, K.E	6/27/90	3/15/91	6/27/90	03/31/91	02/28/91	
✓GODBEE, J.J.	5/26/91	5/26/91	5/26/91	03/31/91	05/31/90*	
GOODWIN, G.B.	6/27/90	6/27/90	6/27/90	03/31/91	02/28/91	
✓GRANDY, J.M.	5/12/91	5/12/91	5/12/91	03/31/91	03/31/90*	
GUIDRY, M.J.	7/24/90	7/24/90	7/24/90	03/31/91	02/28/91	
HARGROVE, R.A.	5/5/91	5/5/91	5/5/91	03/31/91	05/31/90*	
HEATH, J.H. JR	5/12/91	5/12/91	5/12/91	03/31/90*	03/31/90*	
HELWIG, W.J.	5/5/91	5/5/91	5/5/91	03/31/91	02/28/91	
HOWLAND, B.G.	4/29/91	4/29/91	4/29/91	03/31/91	EXP'D	UNQUA
KIRCHNER, III	5/24/90*	5/20/91	5/19/91	03/31/91	03/31/91	
KNOX, P.J.	11/28/90	11/28/90	11/28/90	03/31/91	08/31/90	
MCCANN, V.E.	4/29/91	4/29/91	4/29/91	03/31/91	05/31/90*	
✓MCGRATH, M.E.	6/27/90	6/27/90	6/27/90	03/31/91	02/28/91	
MILLER, C.W.	4/29/91	5/5/91	4/29/91	03/31/91	12/31/90	
MORRIS, D.L.	12/29/90	12/29/90	12/29/90	03/31/91	02/28/91	
✓MORRIS, S.M.	7/10/90	7/10/90	7/10/90	03/31/91	08/31/90	
NEAL, III T.	7/10/90	7/10/90	7/10/90	03/31/90*	03/31/90*	
PALMER, D.L.	5/12/91	5/12/91	5/12/91	03/31/91	01/31/91	
REEVES, G.G.	2/17/91	12/15/90	5/12/91	03/31/90*	EXP'D	UNQUA
REYNOLDS, R.E.	6/15/90*	6/13/90*	2/20/91	03/31/91	11/30/90	
SEVIGNY, W.E.	11/7/90	11/7/90	6/13/90*	03/31/91	07/31/90	
SHERROD, D.T.	1/30/91	1/30/91	11/7/90	03/31/91	03/31/90*	
SKELLY, E.R.	7/10/90	7/10/90	1/30/91	03/31/91	11/30/90	
			7/10/90	03/31/91	04/30/90*	

OSC POSITION QUALS

SNEEDER, W.R.	6/27/90	6/27/90	6/27/90	03/31/91	04/30/90*
/STROUSE, J.L.	5/12/91	5/12/91	5/12/91	03/31/91	11/30/90
THAMES, D.B.	4/15/91	4/15/91	4/15/91	03/31/91	02/28/91
✓WALLACE, D.E.	6/27/90	6/27/90	6/27/90	03/31/91	08/31/90
WATERS, K.T.	6/13/90*	6/13/90*	6/13/90*	03/31/91	02/28/91
✓WHITTON, D.E.	4/15/91	4/15/91	4/15/91	03/31/91	<u>EXP'D</u>
✓WILDER, L. JR	9/6/90	9/5/90	9/5/90	03/31/90*	03/31/90*
WILKINS, M.C.	5/5/91	5/5/91	5/5/91	03/31/91	06/30/90
WOODS, C.A.	5/12/91	5/20/91	5/12/91	03/31/91	02/28/91

UNQUA

IN-PLANT SAMPLING

NAME	<u>GE-001</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>	
BELL, B.C.	2/27/91	2/27/91	03/31/90*	07/31/90	
✓COFFEY, J.M.	7/19/90	7/20/90	03/31/91	07/31/90	
COLLINS, R.V.	10/17/90	10/17/90	03/31/91	07/31/90	
DOSSETT, J.	11/14/90	11/14/90	03/31/90*	08/31/90	
✓EDWARDS, S.M.	9/30/90	9/30/90	03/31/91	07/31/90	
EVANS, D.H.	2/3/91	2/3/91	08/31/90	08/31/90	
FLETCHER, E.B.	6/12/91	6/12/91	03/31/91	07/31/90	
GOODWIN, D.G.	5/5/91	5/5/91	03/31/90*	07/31/90	
HAMILTON, R.R.	2/27/91	2/27/91	03/31/90*	11/30/90	
HARRIS, G.W.	7/10/90	7/10/90	03/31/91	07/31/90	
HENDRIX, N.W.	2/20/91	2/20/91	03/31/91	11/30/90	
HICKS, A.B.	2/20/91	2/20/91	03/31/91	03/31/91	
HOLLINGSWORTH,	10/31/90	10/31/90	03/31/91	09/30/90	
✓JACOBS, M.K.	10/7/90	10/27/90	03/31/91	07/31/90	
KHERA, H.S.	12/1/90	12/29/90	03/31/91	07/31/90	
MALLARI, J.R.	2/8/91	2/9/91	03/31/91	11/30/90	
MOORE, P.E.	11/28/90	11/28/90	03/31/91	09/30/90	
ODOM, M.R.	1/27/91	1/27/91	03/31/90*	06/30/90	
PALMER, R.O.	8/26/90	8/26/90	03/31/91	07/31/90	
PORTER, A.M. J	7/10/90	7/10/90	03/31/91	<u>EXP'D</u>	UNQUAL'D
REBSTOCK, D.E.	1/30/91	1/30/91	03/31/91	<u>EXP'D</u>	UNQUAL'D
ROBERSON, A.M.	6/12/91	6/27/90	03/31/91	07/31/90	
RODRIGUEZ, E.	6/6/90 *	6/6/90 *	03/31/91	<u>EXP'D</u>	UNQUAL'D
SAMPATHKUMAR,	2/20/91	2/20/91	03/31/91	11/30/90	
SMITH, R.E.	9/5/90	9/5/90	03/31/91	09/30/90	
THOMPSON, R.L.	1/31/91	1/27/91	03/31/91	07/31/90	
✓TRIPPE, K.H.	9/30/90	<u>EXP'D</u>	03/31/91	07/31/90	
WHITTEMORE, B.	3/29/91	3/29/91	03/31/91	12/31/90	UNQUA
WIDNER, D.G.	4/5/91	4/5/91	03/31/90*	01/31/91	
WILDER, R.A.	2/3/91	2/3/91	03/31/90*	06/30/90	
WOLFE, F.	2/27/91	2/27/91	03/31/90*	07/31/90	
WOOLEY, E.J.	10/17/90	10/17/90	03/31/90*	07/31/90	
WRIGHT, M.J.	9/2/90	9/2/90	03/31/91	07/31/90	

OSC POSITION QUALS

DOSIMETRY TEAM

<u>NAME</u>	<u>GE-001</u>
CLARK, B.A.	6/27/90
MILLER, R.H.	10/7/90
NEWTON, C.M.	11/25/90
✓ TRESSLER, G.J.	11/28/90
UTLEY, M.G.	7/10/90

STATUS LOOP COMMUNICATOR

<u>NAME</u>	<u>GE-001</u>
✓ BAKER, B.T.	11/28/90
DAVIS, H.H.	12/22/90
✓ DAVIS, J.A.	1/27/91
HOLT, D.A.	12/22/90
✓ JONES, R.E.	12/22/90
VAUGHT, H.R. J	7/24/90
WYRE, R.H.	12/1/90

SUPPORT STAFF

<u>NAME</u>	<u>GE-001</u>	
ATKINS, W.H.	9/16/90	
✓ BROXTON, E.R.	6/27/90	
BRYSON, R.S.	8/15/90	
✓ CIPOLLONE, J.B.	7/10/90	
HALCOMB, J.B.	5/15/90*	
HAMMOCK, P.	6/15/90*	
HEATH, G.K.	5/12/91	
✓ HERREN, R.T.	12/29/90	
✓ HOPKINS, S.P.	12/29/90	
JANOW, D.L.	4/8/91	
MCBRIDE, J.J.	12/27/90	
MCCLELLAN, R.W.	10/17/90	
MINOR, M.C.	<u>EXP'D</u>	
POLLOCK, J.E.	1/27/91	UNQUAL'D
✓ PROUDFOOT, D.S.	8/15/90	
PULLIAM, H.W.	<u>EXP'D</u>	
ROWELL, R.M.	6/8/90 *	UNQUAL'D
SHARKEY, F.P.	5/26/91	
SISTARE, J.H.	1/31/91	
TOY, D.M.	10/12/90	

OSC POSITION QUALS

VAUGHN, R.I	12/29/90
WILLIAMS, W.H.	6/12/91
ZACKERY, L.S.	9/1/90

POST ACCIDENT SAMPLING TEAM

<u>NAME</u>	<u>GE-001</u>	<u>RE-056</u>	<u>CH-413</u>	
		<u>GE-099</u>	<u>RE-200</u>	
BELL, B.C.		2/27/91	6/30/90	
		2/27/91	03/31/90*	07/31/90
COFFEY, J.M.		7/19/90	<u>NO REC.</u>	<u>NO REC.</u>
		7/20/90	03/31/91	07/31/90
COLLINS, R.V.		10/17/90	6/30/90	UNQUA
		10/17/90	03/31/91	07/31/90
DOSSETT, J.		11/14/90	<u>NO REC.</u>	<u>NO REC.</u>
		11/14/90	03/31/90*	08/31/90
DUVAL, R.A.		7/24/90	<u>NO REC.</u>	<u>EYP'D</u>
		10/17/90	03/31/91	07/31/90
✓ EDWARDS, S.M.		9/30/90	<u>NO REC.</u>	<u>EYP'D</u>
		9/30/90	03/31/91	07/31/90
FLETCHER, E.B.		6/12/91	<u>EXP'D</u>	<u>NO REC.</u>
		6/12/91	03/31/91	07/31/90
GOODWIN, D.G.		5/5/91	<u>EXP'D</u>	<u>NO REC.</u>
		5/5/91	03/31/90*	07/31/90
HAMILTON, R.R.		2/27/91	<u>NO REC.</u>	<u>NO REC.</u>
		2/27/91	03/31/90*	11/30/90
HARRIS, G.W.		7/10/90	<u>NO REC.</u>	<u>NO REC.</u>
		7/10/90	03/31/91	07/31/90
HENDRIX, N.W.		2/20/91	<u>NO REC.</u>	<u>NO REC.</u>
		2/20/91	03/31/91	11/30/90
HICKS, A.B.		2/20/91	6/30/90	UNQUA
		2/20/91	03/31/91	03/31/91
HOLLINGSWORTH,		10/31/90	<u>NO REC.</u>	<u>NO REC.</u>
		10/31/90	03/31/91	09/30/90
JACOBS, M.K.		10/7/90	<u>NO REC.</u>	<u>NO REC.</u>
		10/27/90	03/31/91	07/31/90
JAQUES, J.H.		7/24/90	<u>NO REC.</u>	<u>EYP'D</u>
		8/1/90	03/31/90*	04/30/90*
KHERA, H.S.		12/1/90	6/30/90	UNQUA
		12/29/90	03/31/91	07/31/90
MALLARD, J.R.		2/8/91	<u>NO REC.</u>	<u>NO REC.</u>
		2/9/91	03/31/91	11/30/90
MOORE, P.E.		11/28/90	6/30/90	UNQUA
		11/28/90	03/31/91	09/30/90
ODOM, M.R. <i>Went directly to TSC</i>		1/27/91	6/30/90	
		1/27/91	03/31/90*	06/30/90
PALMER, R.O.		8/26/90	<u>NO REC.</u>	<u>NO REC.</u>
		8/26/90	03/31/91	07/31/90

OSC POSITION QUALS

PORTER, A.M. J	7/10/90	<u>NO REC.</u>	<u>NO REC.</u>	
	7/10/90	03/31/91	<u>EXP'D</u>	UNQUAL'D
REBSTOCK, D.E.	1/30/91	<u>NO REC.</u>	<u>NO REC.</u>	
	1/30/91	03/31/91	<u>EXP'D</u>	UNQUAL'D
ROBERSON, A.M.	6/12/91	<u>NO REC.</u>	<u>EXP'D</u>	
	6/27/90	03/31/91	07/31/90	UNQUA
RODRIGUEZ, E.	6/6/90 *	<u>NO REC.</u>	<u>NO REC.</u>	
	6/6/90 *	03/31/91	<u>EXP'D</u>	UNQUAL'D
SAMPATHKUMAR,	2/20/91	<u>NO REC.</u>	<u>NO REC.</u>	
	2/20/91	03/31/91	11/30/90	UNQUA
SMITH, R.E.	9/5/90	<u>NO REC.</u>	<u>NO REC.</u>	
	9/5/90	03/31/91	09/30/90	UNQUA
THOMPSON, R.L.	1/31/91	<u>NO REC.</u>	<u>NO REC.</u>	
	1/27/91	03/31/91	07/31/90	UNQUA
✓TRIPPE, K.H.	9/30/90	6/30/90		UNQUA
	<u>EXP'D</u>	03/31/91	07/31/90	UNQUA
WHITTEMORE, B.	3/29/91	<u>NO REC.</u>	<u>NO REC.</u>	
	3/29/91	03/31/91	12/31/90	UNQUA
WIDNER, D.G.	4/5/91	<u>NO REC.</u>	<u>NO REC.</u>	
	4/5/91	03/31/90*	01/31/91	UNQUA
WILDER, R.A.	2/3/91	<u>NO REC.</u>	<u>NO REC.</u>	
	2/3/91	03/31/90*	06/30/90	UNQUA
WOLFE, F.	2/27/91	<u>NO REC.</u>	<u>NO REC.</u>	
	2/27/91	03/31/90*	07/31/90	UNQUA
WOOLEY, E.J.	10/17/90	<u>NO REC.</u>	<u>EXP'D</u>	
	10/17/90	03/31/90*	07/31/90	UNQUA
WRIGHT, M.J.	9/2/90	6/30/90		
	9/2/90	03/31/91	07/31/90	UNQUA

FIRST AID (SAFETY)

<u>NAME</u>	<u>GE-001</u>	<u>RE-008</u>	<u>GE-005</u>	<u>GE-155</u>
✓GREINER, T.B.	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>	
	6/27/90	6/10/90*	02/05/93	
JILES, J.D.	6/27/90	03/31/90*	<u>NO REC.</u>	UNQUAL'D
	7/5/90	10/19/90	02/05/93	
	<u>EXP'D</u>	03/31/90*	<u>NO REC.</u>	UNQUAL'D
JOHNSON, P.L.	12/25/90	6/10/90*	02/05/93	
	12/25/90	09/30/90	<u>EXP'D</u>	UNQUAL'D

FIELD MONITORING TECHNICIAN

<u>NAME</u>	<u>GE-001</u>	<u>RE-040</u>
ADAMS, C.M.	3/11/91	2/15/91
ALLEN, B.P. JR	3/11/91	6/15/90*
ASKEW, M.D.	3/29/91	5/15/90*

OSC POSITION QUALS

BELL, B.C.	2/27/91	4/27/90*	
CANCER, A.G.	7/24/90	12/19/90	
CARSWELL, C.A.	6/27/90	5/22/90*	
✓CARTER, W.R. J	4/29/91	4/13/90*	
CLARK, L.L.	4/29/91	4/11/90*	
COFFEY, J.M.	7/19/90	12/19/90	
COLLINS, R.V.	10/17/90	5/2/90 *	
DOSSETT, J.	11/14/90	6/17/90*	
DUVAL, R.A.	7/24/90	4/20/90*	
✓EDWARDS, S.M.	9/30/90	12/19/90	
EVANS, D.H.	2/3/91	2/15/91	
FLETCHER, E.B.	6/12/91	5/2/90 *	
FREEMAN, T.E.	11/28/90	3/21/90*	
GARDNER, A.J.	2/27/91	5/8/90 *	
GOODWIN, D.G.	5/5/91	4/11/90*	
GOODWIN, D.P.	4/9/90 *	<u>NO REC.</u>	UNQUAL'D
HAMILTON, R.R.	2/27/91	6/17/90*	
✓HARPER, W.H.	4/13/91	5/1/90 *	
HARRELL, R.E.	6/27/90	11/22/90	
✓HARRIS, G.W.	7/10/90	5/10/90*	
✓HENDRIX, N.W.	2/20/91	6/17/90*	
HICKS, A.B.	2/20/91	4/11/90*	
✓HLAVIN, W.E.	11/25/90	5/15/90*	
HOLLINGSWORTH,	10/31/90	<u>NO REC.</u>	UNQUAL'D
✓HUTCHESON, W.J	11/28/90	9/6/90	
JACOBS, M.K.	10/7/90	6/23/90	
JAQUES, J.H.	7/24/90	4/27/90*	
KAY, M.L.	4/29/91	4/18/90*	
KHERA, E.S.	12/1/90	4/27/90*	
✓KLUTZ, P.D.	5/12/91	4/25/90*	
LEFTWICH, B.C.	4/10/91	<u>NO REC.</u>	UNQUAL'D
MALLARD, J.R.	2/8/91	<u>NO REC.</u>	UNQUAL'D
MIDDLETON, E.L	5/5/91	9/6/90	
✓MOORE, P.E.	11/28/90	12/19/90	
ODOM, M.R.	1/27/91	5/22/90*	
PALMER, R.O.	8/26/90	<u>NO REC.</u>	UNQUAL'D
PARKER, W.K.	4/13/91	5/1/90 *	
✓PORTER, A.M. J	7/10/90	5/10/90*	
REBSTOCK, D.E.	1/30/91	4/27/90*	
REECE, R.E.	5/26/91	4/25/90*	
ROBERSON, A.M.	6/12/91	4/20/90*	
✓ROBINSON, H.L.	6/31/90	9/16/90	
RODRIGUEZ, E.	6/6/90 *	<u>EXP'D</u>	UNQUAL'D
SAMPATHKUMAR,	2/20/91	6/17/90*	
SAXON, T.W.	4/13/91	5/15/90*	
SMITH, R.E.	9/5/90	<u>NO REC.</u>	UNQUAL'D
✓THIGPEN, M.D.	5/12/91	5/8/90 *	
THOMPSON, R.L.	1/31/91	4/13/90*	
THORNTON, R.G.	1/6/91	9/6/90	
✓TRIPPE, K.H.	9/30/90	2/15/91	

OSC POSITION QUALS

✓ WEBB, G.D.	4/13/91	5/1/90 *
✓ WHITTEMORE, B.	3/29/91	6/23/90
✓ WIDNER, D.G.	4/5/91	5/10/90*
WILCOX, R.C.	5/5/91	4/25/90*
WILDER, R.A.	2/3/91	6/17/90*
WILLIAMS, H.M.	11/28/90	3/21/90*
WOLFE, F.	2/27/91	6/17/90*
WOOLEY, E.J.	10/17/90	11/22/90
WRIGHT, M.J.	9/2/90	5/2/90 *

HP TECHNICIAN

<u>NAME</u>	<u>RE-008</u>	<u>GE-001</u>	<u>GE-005</u>	<u>GE-155</u>	
	<u>RE-030</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE-201</u>	
✓ ARNOLD, H.F.	4/15/91	4/15/91	03/06/92		
✓ BAILEY, C.L. J	4/16/91	4/15/91	03/31/90*	01/31/91	
	<u>NO REC.</u>	1/27/91	<u>NO REC.</u>	<u>NO REC.</u>	
✓ BELGE, A.L.	<u>EXP'D</u>	1/27/91	05/31/90*	10/31/90	UNQUA
	4/23/91	4/22/91	03/21/92		
	4/23/91	4/22/91	03/31/91	01/31/91	
BOAZMAN, D.J.	5/6/91	4/29/91	03/21/92		
	5/6/91	4/29/91	03/31/91	04/30/90*	
BRETT, H.M.	5/13/91	5/12/91	02/20/92		
	5/13/91	5/12/91	03/31/90*	04/30/90*	
BROWN, K.M.	5/13/91	5/12/91	03/14/92		
	5/13/91	5/12/91	05/31/90*	08/31/90	
BURRIS, S.R.	5/6/91	5/5/91	03/21/92		
	5/6/91	5/5/91	03/31/90*	02/28/91	
CARSWELL, J.A.	4/16/91	4/15/91	03/06/92		
	4/16/91	4/15/91	03/31/90*	01/31/91	
COLEMAN, B. II	5/13/91	5/12/91	02/28/92		
	5/13/91	5/12/91	03/31/90*	03/31/90*	
COLEMAN, N.K.	4/23/91	4/22/91	03/21/92		
	4/23/91	4/22/91	03/31/91	01/31/91	
DIXON, J.R.	4/30/91	5/5/91	03/06/92		
	4/30/91	5/5/91	03/31/90*	07/31/90	
DUNLAP, M.M.	5/13/91	5/12/91	03/06/92		
	5/13/91	5/12/91	03/31/91	02/28/91	
DUNMIRE, R.L.	4/23/91	4/22/91	03/14/92		
	4/23/91	4/22/91	03/31/91	01/31/91	
ETHEREDGE, J.W	4/3/91	4/2/91	03/14/92		
	4/3/91	4/2/91	03/31/90*	07/31/90	
GILLIARD, M.A.	4/3/91	4/2/91	04/04/92		
	4/3/91	4/2/91	03/31/90*	01/31/91	
GRIMSLEY, F.O.	4/16/91	4/15/91	10/03/92		
	4/16/91	4/15/91	02/28/91	01/31/91	
HALL, R.W.	4/9/91	4/8/91	03/21/92		
	4/9/91	4/8/91	03/31/91	01/31/91	

OSC POSITION QUALS

✓ HARTFIELD, C.S	4/30/91	4/29/91	02/28/92		
HERRING, J.H.	4/30/91	4/29/91	03/31/91	03/31/90*	
	5/13/91	5/12/91	10/03/92		
✓ HILL, F.	5/13/91	5/12/91	03/31/91	06/30/90	
	4/16/91	4/15/91	03/14/92		
✓ HOWE, T.D.	4/16/91	4/15/91	05/31/90*	01/31/91	
	4/16/91	4/15/91	03/14/92		
JOHNSON, M.L.	4/16/91	4/15/91	03/31/90*	01/31/91	
	4/23/91	4/22/91	02/28/92		
KHERA, S.S.	4/23/91	4/22/91	03/31/91	01/31/91	
	4/9/91	4/8/91	02/20/92		
✓ LUCOT, J.F.	4/9/91	4/8/91	03/31/91	01/31/91	
	4/9/91	4/8/91	03/21/92		
✓ LYDA, L.H.	4/9/91	4/8/91	05/31/90*	01/31/91	
	4/16/91	4/15/91	10/03/92		
✓ MATTIAGE, G.G.	4/16/91	4/15/91	03/31/90*	01/31/91	
	5/13/91	5/12/91	03/21/92		
MCCORKLE, G.L.	5/13/91	5/12/91	03/31/91	10/31/90	
	4/9/91	4/8/91	03/21/92		
✓ MORGAN, V.R.	4/9/91	4/8/91	03/31/91	01/31/91	
	4/16/91	4/15/91	03/21/92		
OGDEN, M.L.	4/16/91	6/20/90*	03/31/91	01/31/91	
	4/9/91	4/8/91	02/28/92		
PETERS, C.E.	4/9/91	4/8/91	03/31/91	01/31/91	
	5/13/91	5/12/91	03/14/92		
PETROSKY, K.T.	5/13/91	5/12/91	03/31/90*	03/31/90*	
	4/23/91	4/22/91	02/28/92		
PITTMAN, B.W.	4/23/91	4/22/91	03/31/91	01/31/91	
	6/20/90*	5/5/91	03/21/92		
PRESTON, M.B.	6/21/90*	5/5/91	EXP'D	02/28/91	UNQUA
	4/9/91	4/8/91	03/14/92		
RAYBURN, N.S.	4/9/91	4/8/91	EXP'D	01/31/91	UNQUA
	5/13/91	5/12/91	03/14/92		
REES, W.S.	5/13/91	5/12/91	03/31/91	10/31/90	
	5/6/91	5/5/91	02/20/92		
✓ REEVES, T. III	5/6/91	5/5/91	03/31/90*	04/30/90*	
	4/30/91	4/29/91	02/28/92		
RILEY, R.L.	4/30/91	4/29/91	03/31/91	03/31/90*	
	4/3/91	4/2/91	03/21/92		
✓ SCOGGINS, F.S.	4/3/91	4/2/91	EXP'D	01/31/91	UNQUA
	5/6/91	5/5/91	02/28/92		
STANFORD, J.D.	5/6/91	5/5/91	03/31/90*	03/31/90*	
	4/16/91	4/22/91	10/03/92		
✓ STOKES, L.W.	4/16/91	4/22/91	EXP'D	01/31/91	UNQUA
	4/23/91	4/22/91	04/04/92		
✓ WEBB, T.D.	4/23/91	4/22/91	03/31/91	01/31/91	
	4/23/91	4/22/91	03/06/92		
✓ WIGGINS, S.M.	4/23/91	4/22/91	03/31/91	01/31/91	
	4/23/91	4/22/91	03/14/92		
	4/23/91	4/22/91	03/31/91	01/31/91	

OSC POSITION QUALS

VEGP AMBULANCE CREW

<u>NAME</u>	<u>GE-001</u>	<u>RE--008</u>	
BENNETT, M.O.	7/28/90	10/19/90	
BRUCE, A.R.	<u>EXP'D</u>	10/19/90	UNQUA
CAIL, P.L.	4/31/91	10/19/90	
DUFFIELD, B.M.	10/17/90	<u>NC REC.</u>	UNQUAL'D
GLENN, S.M.	3/11/91	<u>EXP'D</u>	UNQUAL'D
GREINER, T.B.	6/27/90	6/10/90*	
HUTTON, C.E.	5/12/91	10/31/90	
JOHNSON, F.L.	12/25/90	6/10/90*	
KWOLEK, J.	10/10/90	<u>EXP'D</u>	UNQUAL'D
MORRIS, B.K.	7/28/90	10/31/90	
PERKINS, M.E.	7/24/90	10/31/90	
WALKER, B.J.	11/28/90	<u>EXP'D</u>	UNQUAL'D
WILLIAMS, H.G.	3/11/91	<u>EXP'D</u>	UNQUAL'D
WIMBURN, J.M.	11/25/90	10/10/90	

The following personnel were available for support in the Operations Support Center.

OPERATIONS SUPPORT CENTER

ABSHER J
ACKER W
AILLOTT JD
ALLRED JJ
BARLOW R
BAYNES RL
BELLAIR E
BENTON T
BRADY CW
BURGESS J
CAMPBELL ML
CARPENTER A
CRIDER J
CROUCH D
DAVIS T
DEEN L
FEARRINGTON R
HALL PL
HANYOK, JA
HILL E
HUMPHRIES EJ
HUTCHERSON GA
JEFFERS HE
KICKLIGHTER WG
KINSEY A
KYLE C
MCKINNEY CD
MCLEOD SH
MERKEL R
PRICE J
SCHREIBER DW
SEYMOUR ME
TAYLOR J
WALLACE DE
WARD CE
WILSON J
YARNOLL R

03/21/90

EOF POSITION QUALS

GE-001 = Badge Training
 RE-020 = Off-site Dose Assessment
 RE-040 = Field Monitoring Team
 RE-070 = Commun. and Records
 RE-080 = Mgt. of Rad Emergencies
 RE-111 = Security Coord. Training
 GE-099 = SCBA Training

DATES LISTED ARE DROP DEAD DATES
 * RENEW QUAL 3 MO. PRIOR TO EXPIR.

RE-200 = Physical Exam
 RE-201 = Resp. Fit Test

EMERGENCY DIRECTOR (CORPORATE)

<u>NAME</u>	<u>GE-001</u>	<u>RE-080</u>
MCCOY, C.K.	6/7/91	10/6/90

EMERGENCY DIRECTOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-080</u>	<u>GE-099</u>	<u>RE-200</u>	<u>RE--201</u>	
BOCKHOLD, G.	11/28/90	10/26/90	1/16/91	12/31/90	12/31/90	
KITCHENS, W.F.	4/31/91	10/26/90	4/29/91	03/31/91	09/30/90	
MOSBAUGH, A.L.	2/20/91	7/21/90	8/11/90	NO REC.	NO REC.	UNQUA

EOF MANAGER

<u>NAME</u>	<u>GE-001</u>	<u>RE-080</u>
HOLMES, K.R.	4/31/91	7/12/90
LACKEY, M.B.	5/14/91	10/26/90
LEGRAND, R.L.	5/7/91	1/26/91

DOSE ASSESSMENT MANAGER

<u>NAME</u>	<u>GE-001</u>	<u>RE 020</u>	
CURE, P.A.	7/28/90	8/25/90	
KOCHERY, I.A.	8/30/90	12/28/90	
LEGRAND, R.L.	5/7/91	NO REC.	UNQUALIFIED

DOSE ANALYST

<u>NAME</u>	<u>GE-001</u>	<u>RE-020</u>	
BOURNE, R.C.	3/29/91	6/6/91	
CLARKE, J.R. II	3/1/91	EXP'D	UNQUALIFIED
CONNOR, S.J.	4/8/91	8/25/90	
CORDELL, A.	12/22/90	EXP'D	UNQUALIFIED
CURE, P.A.	7/28/90	8/25/90	
DUQUETTE, K.W.	11/7/90	12/20/90	
HOUGHTALING, H.	6/27/90	EXP'D	UNQUALIFIED

EOF POSITION QUALS

KURTZMAN, M.J.	4/15/91	5/7/91
ROUSE, L.A.	1/31/91	4/4/91
SEEPE, M.C.	8/15/90	8/25/90

FIELD MONITORING TEAM COMMUNICATOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-040</u>
ADAMS, C.M.	3/11/91	2/15/91
ALLEN, B.P.	3/11/91	6/15/90*
CANCER, A.G.	7/24/90	12/19/90
CARTER, W.R.	4/29/91	4/13/90*
DUVAL, R.A.	7/24/90	4/20/90*
GOODWIN, D.G. J	5/5/91	4/11/90*
JACKSON, S.M.	6/27/90	6/29/90
JAQUES, J.H.	7/24/90	4/27/90*
LEE, D.R.	4/8/91	2/15/91
WRIGHT, M.J.	9/2/90	5/2/90 *

SECURITY COORDINATOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-111</u>
HUYCK, D.G.	8/30/90	7/24/90
KITCHENS, C.J.	5/12/91	4/26/90*
MCQUILLEN T.	1/6/91	6/3/90 *
MIDDLETON, A.L.	10/26/90	4/26/90*
WALKER, S.P.	4/29/91	2/20/91

SUPPORT COORDINATOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-070</u>
AGRO, V.J.	2/3/91	5/1/91
AKIN, D.A.	6/27/90	6/8/90 *
HUGHES, J.R.	2/27/91	5/1/91

SUPPORT STAFF

<u>NAME</u>	<u>GE-001</u>
AKIN, D.A.	6/27/90
BELL, R.W.	6/27/90
BLACK, R.P.	6/27/90
CHANDLER, B.B.	8/24/90
CHANDLER, J.W.	9/14/90

EOF POSITION QUALS

DAVIS, B.B.	9/21/90
GRIFFIN, C.A.	11/14/90
HACKER, B.R.	2/27/91
JACKSON, E.G.	4/8/91
JOHNSON, V.S.	1/11/91
KICKLIGHTER, M.	11/14/90
MCDANIEL, M.C.	3/11/91
REEVES, J.	7/26/90
SMITH, H.M.	1/6/91
WALKER, G.W.	6/13/90*
WIMBERLY, M.K.	10/17/90
WOODS, C.B.	5/22/90*

ERF COMPUTER OPERATOR

<u>NAME</u>	<u>GE-001</u>
ALLISON, S.M.	4/31/91
BELL, H.R.	4/31/91
HALE, R.E.	5/14/91
RAY, L.F.	5/7/91
STUHANN, C.E.	5/14/91

NRC LIAISON

<u>NAME</u>	<u>GE-001</u>
HOLMES, K.R.	4/31/91
KURTZMAN, M.J.	4/15/91
ROBERTS, J.N.	9/26/90

ENN COMMUNICATOR

<u>NAME</u>	<u>GE-001</u>	<u>RE-070</u>
ADAMS, T.N.	12/22/90	10/19/90
BARRETT, W.R.	7/10/90	7/13/90
BOWLES, D.R.	8/15/90	7/13/90
CUPP, P.L.	3/11/91	7/13/90
MINYARD, D.L.	8/26/90	7/13/90
STANCIL, R.F.	11/4/90	7/13/90

EOF POSITION QUALS

PAGE 4
03/21/90

HABITABILITY MONITOR

<u>NAME</u>	<u>GE-001</u>
BOURNE, R.C.	3/29/91
GREEN, L.E.	2/6/91
ROUSE, L.A.	1/31/91

STATUS LOOP COMMUNICATOR

<u>NAME</u>	<u>GE-001</u>
ALLISON, S.M.	4/31/91
BELL, H.R.	4/31/91
HALE, R.E.	5/14/91
RAY, L.F.	5/7/91
STUHANN, C.E.	5/14/91

TECHNICAL ASSISTANT TO THE EMERGENCY DIRECTOR

<u>NAME</u>	<u>GE-001</u>
KOZINSKY, E.J.	4/31/91
LEGRAND, R.L.	5/7/91
TYNAN, C.L.	11/28/90

The following personnel were available for support in the Emergency Operations Facility.

EMERGENCY OPERATIONS FACILITY

AJLUNI MJ
BRIGDON RD
CANADA J
DORMAN RE
DRAKE BT
HARRIS, GW
HILL, DS
JOHNSON P
JORDAN E
JORDAN EH
KLUTTZ PD
MAYC LE
PORTER AM
RUCKER S
SCUKANEC D
STINESPRING CP
THIGPEN MD
TURPIN B
VICKERY DO
WHITTEMORE BD

OVERSIZE DOCUMENT PAGE PULLED

SEE APERTURE CARDS

NUMBER OF OVERSIZE PAGES FILMED ON APERTURE CARDS 9

APERTURE CARD/HARD COPY AVAILABLE FROM
RECORDS AND REPORTS MANAGEMENT BRANCH

9202200	310
"	312
"	316
"	320
"	320-01
"	322
"	325
"	326
"	329

OVERSIZE DOCUMENT PAGE PULLED

SEE APERTURE CARDS

NUMBER OF OVERSIZE PAGES FILMED ON APERTURE CARDS 6

**APERTURE CARD/HARD COPY AVAILABLE FROM
RECORDS AND REPORTS MANAGEMENT BRANCH**

9202200359
" 362
" 365
" 365-01
" 366-
" 366-01