

RELATED CORRESPONDENCE

LILCO, August 14, 1984

DOCKETED  
USNRC

UNITED STATES OF AMERICA  
NUCLEAR REGULATORY COMMISSION

'84 AGO 15 A9:56

OFFICE OF SECRETARY  
DOCKETING & SERVICE  
BRANCH

Before the Atomic Safety and Licensing Board

In the Matter of	)	
	)	
LONG ISLAND LIGHTING COMPANY	)	Docket No. 50-322 (OL)
	)	
(Shoreham Nuclear Power Station,	)	
Unit 1)	)	

TESTIMONY OF DAVID O. HARRIS, DUANE P. JOHNSON,  
 ROGER L. MCCARTHY, FRANZ F. PISCHINGER,  
 CRAIG K. SEAMAN, LEE A. SWANGER AND  
 EDWARD J. YOUNGLING ON BEHALF OF LONG ISLAND LIGHTING  
 COMPANY OF SUFFOLK COUNTY CONTENTION REGARDING  
AE PISTON SKIRTS ON DIESEL GENERATORS AT SHOREHAM

Testimony and Attachments

Volume 1 of 2

TABLE OF CONTENTS

	<u>Page</u>
I. Introduction of Witnesses.....	1
II. Background.....	7
III. FaAA's Crack Initiation and Growth Analyses Show Cracks In The AE Piston Skirts Might Initiate, But Will Not Grow.....	13
A. General Approach And Assumptions.....	13
B. Experimental Procedures.....	22
C. Numerical Procedures.....	25
1. Isothermal Analysis.....	28
2. Crown/Skirt Interaction Model.....	32
D. Fatigue Crack Initiation Analysis.....	39
E. Fatigue Crack Growth Analysis.....	44
IV. Operating Experience.....	50
V. Side Thrust Load Is Not A Design Or Operation Problem With The AE Pistons At Shoreham.....	58
A. Shoreham AE Piston Skirt.....	58
B. FaAA Analysis.....	64
VI. Tin Plating On The AE Pistons At Shoreham Will Not Lead To Failure.....	66
VII. Conclusion.....	72

LILCO, August 14, 1984

UNITED STATES OF AMERICA  
NUCLEAR REGULATORY COMMISSION

Before the Atomic Safety and Licensing Board

DOCKETED  
USNRC

'84 AGO 15 A9:56

OFFICE OF SECRETARY  
DOCKETING & SERVICE  
BRANCH

In the Matter of	)	
	)	
LONG ISLAND LIGHTING COMPANY	)	Docket No. 50-322 (OL)
	)	
(Shoreham Nuclear Power Station,	)	
Unit 1)	)	

TESTIMONY OF DAVID O. HARRIS, DUANE P. JOHNSON,  
ROGER L. McCARTHY, FRANZ F. FISCHINGER,  
CRAIG K. SEAMAN, LEE A. SWANGER AND  
EDWARD J. YOUNGLING ON BEHALF OF LONG ISLAND LIGHTING  
COMPANY ON SUFFOLK COUNTY CONTENTION REGARDING  
AE PISTON SKIRTS ON DIESEL GENERATORS AT SHOREHAM

I. Introduction of Witnesses

1. Please state your names, employers and business addresses.

A. (Harris) My name is Dr. David O. Harris. I am employed by Failure Analysis Associates (FaAA), 2225 East Bayshore Road, Palo Alto, California 94303.

(Johnson) My name is Dr. Duane P. Johnson. I am also employed by FaAA, 2225 East Bayshore Road, Palo Alto, California 94303

(McCarthy) My name is Dr. Roger L. McCarthy. I am President of FaAA, 2225 East Bayshore Road, Palo Alto, California 94303.

(Pischinger) My name is Dr. Franz F. Pischinger. I am President of FEV (Research Society for Energy, Technology and Internal Combustion Engines) and full professor at the University of Aachen, Institute of Applied Thermodynamics. My address is Erckfeld 4, Aachen, West Germany.

(Seaman) My name is Craig K. Seaman. I am employed by Long Island Lighting Company (LILCO), North Country Road, Wading River, New York 11792.

(Swanger) My name is Dr. Lee A. Swanger. I am also employed by FaAA, 2225 East Bayshore Road, Palo Alto, California 94303.

(Youngling) My name is Edward J. Youngling. I am also employed by LILCO, North Country Road, Wading River, New York 11792.

2. Please state your responsibilities in your current employment relevant to the AE pistons at Shoreham and your educational and professional backgrounds.

A. (Harris) I am a Managing Engineer and manager of the fracture mechanics section of FaAA. I am responsible for the stress analysis and fracture mechanics analysis of various mechanical components. I am the principal investigator in a number of fracture mechanics contracts in which FaAA is involved, including one analysis of cracking in nuclear reactor piping that is being funded by the Nuclear Regulatory Commission. FaAA has also recently begun work on development of a computer

code for NASA that will predict crack growth under a very wide variety of conditions. I have been involved in fracture mechanics analysis of crack growth for many years and, as can be seen from my resume (Attachment 1), have numerous technical publications in this area. I am the task leader for pistons for the TDI Owners Group. I am responsible for the stress and fracture mechanics of TDI pistons. My educational and professional backgrounds are detailed in my resume, Attachment 1 to this testimony.

(Johnson) I am nondestructive testing manager for FaAA responsible for all of its nondestructive testing. I am a qualified Level III inspector in eddy current and ultrasonic test methods. I supervised the eddy-current inspections of the AE pistons at TDI before shipment to LILCO and the inspections of the AE piston skirts after operation. My educational and professional backgrounds are detailed in my resume, Attachment 2 to this testimony.

(McCarthy) I am a registered professional engineer specializing in mechanical design. I am principal design engineer at FaAA. I have five degrees, culminating in a Ph.D. in Mechanical Engineering from MIT. My specialization and Ph.D. thesis was in mechanical and thermal design. My role in the piston program was to personally inspect various piston types at FaAA. I had executive oversight responsibility for FaAA's performance and performed final technical review of all the

reports. I have ultimate management responsibility for the quality and caliber of FaAA's technical product. My educational and professional backgrounds are detailed in my resume, Attachment 3 to this testimony.

(Pischinger) I am familiar with the design, function and operation of pistons as a result of 26 years of experience in diesel engine design and testing. Specifically, FEV reviewed the pistons, cylinder liners and piston rings in the EDGs at Shoreham as a part of Phase II of the TDI Owners Group Design Review Quality Revalidation (DRQR) program. My educational and professional backgrounds are detailed in my resume, Attachment 4 to this testimony.

(Seaman) I am the Project Engineer with the Shoreham Nuclear Power Station. As Program Manager for the TDI Owners Group Program my responsibilities for the AE pistons included: review and approval of the quality revalidation task descriptions and Phase I and Phase II reports; review of component (AE piston) reports both for Phase I and Phase II reports; chairing the Component Selection Committee charged with the responsibility for selecting the pistons for inclusion into the DRQR Program and establishing minimum review requirements; and managing the overall program which included the design review and inspections on the AE pistons. My educational and professional backgrounds are detailed in my resume, Attachment 5 to this testimony.

(Swanger) I am a Managing Engineer for FaAA specializing in materials science. My responsibilities in reviewing the AE piston skirts included, to some extent, evaluation of metallurgical aspects, evaluation of manufacturing techniques, assessment of interaction with other components, specifically piston rings, cylinder liners, piston pin and piston pin bushing and the influence of diesel engine operation on the pistons. My educational and professional backgrounds are detailed in my resume, Attachment 6 to this testimony.

(Youngling) I am Manager of the Nuclear Engineering Department for LILCO. Since May 1984, I have held the position of Manager of the Nuclear Engineering Department reporting to the Vice President, Nuclear Operations. In this capacity, I am responsible for engineering support of the Shoreham station, including the three TDI Emergency Diesel Generators. From 1981 through 1984 as Startup Manager, I was responsible for implementing the preoperational test program for the Shoreham station. In particular, I was responsible for implementing initial operation and check out and subsequent preoperational testing of the TDI diesel generators. After the failure of the EDG 102 crankshaft, I was designated as the Recovery Manager for the repair and requalification of the diesel generators. My educational and professional backgrounds are detailed in my resume, Attachment 7 to this testimony.

3. What issues have you been asked to address in your testimony?

A. (Harris, Johnson, McCarthy, Pischinger, Seaman, Swanger, Youngling) We have been asked to address the specific contentions admitted by the Board's July 17, 1984 Memorandum and Order regarding the AE piston skirts on the emergency diesel generators (EDGs) at Shoreham Nuclear Power Station (Shoreham):

All AF piston skirts in the EDGs were replaced with TDI model AE piston skirts. The replacement AE pistons are of inadequate design and manufacturing quality to satisfactorily withstand operating conditions, because:

(a) the FaAA report conclusion that cracks may occur but will not propagate improperly depends on a fracture mechanics analysis of an ideal situation which is not valid for the actual conditions which may be experienced by the Shoreham diesels,

(b) excessive side thrust load, which could lead to catastrophic failure, has not been considered adequately, and

(c) the analysis does not adequately consider that the tin-plated design of the pistons could lead to scoring causing excessive gas blow-by, and thereby causing a failure of proper operation.

Our testimony, in summary, is that:

- (1) The FaAA conclusion that cracks may or may not initiate in the AE piston skirts, but if initiated, will not grow, is based on crack initiation and growth analyses considering the important loads and displacements reflected in the actual operating conditions to be experienced by the Shoreham EDGs.



- (2) Actual operating experience shows no relevant indications in AE piston skirts.
- (3) The side thrust load on the AE piston skirts is not excessive. Side thrust load is not a design or operation problem with the AE piston skirt.
- (4) The tin-plated design of the AE piston skirt is intended to act as a protective covering for the piston skirt and is not the source of any excessive scuffing that could lead to failure. No known failures of pistons have been caused by tin plating.

4. Are you familiar with the testimony filed by the County on July 31, 1984 in support of its contentions regarding the pistons in this proceeding?

A. (Harris, Johnson, McCarthy, Pischinger, Seaman, Swanger, Youngling) Yes.

## II. Background

5. Before proceeding to the specific points to be discussed in your testimony, please describe the AE piston skirts.

A. (Harris, Swanger, Youngling) Exhibit P-1 is a photograph of an AE piston skirt. The skirt is a cylindrical casting manufactured of 100-70-03 grade ASTM A536 ductile iron. The piston skirt fits within the cylinder and transmits the loads resulting from the combustion cycle of the EDG to the wrist pin and connecting rod, thereby exerting loads that produce torque to drive the crankshaft. The mechanical link between the crankshaft and the piston are the connecting rod and the wrist pin (connected to the piston skirt).

The complete piston consists of the piston skirt and a piston crown. Exhibit P-2 shows the top of the skirt and crown with studs that extend through the skirt to attach the crown to the skirt. Exhibit P-3 shows the crown to skirt mounting. At room temperature when no pressure is applied, the crown contacts the skirt only over an inner ring located just inside the stud bolt circle. To compensate partially for normal thermal distortion of the crown due to temperature differential, the crown is manufactured so that there is a cold clearance or gap between 0.007 and 0.011 inch between the outer contact rings on the crown and the skirt. The gap at the outer ring will close under certain pressure and temperature conditions thereby transmitting a portion of the load from the piston crown to the piston skirt through the outer contact ring. This provides a corresponding reduction in the load on the inner contact ring. In turn, this results in a reduction in the stresses in the stud boss region of the skirt where the stresses are the highest.

6. Were the gap sizes between the outer contact ring on the crown and skirt in the AE pistons at Shoreham measured?

A. (Seaman, Youngling) Yes. The gap size is measured as a standard practice pursuant to piston reassembly guidelines. For instance, gap sizes were measured when the AE piston skirts were installed in November 1983. More recently, the gaps in the ten pistons inspected during the DRQR program

were measured during reassembly and were determined to be within the 0.007 and 0.011 inch range. Documentation of those measurements is included in Exhibit P-4.

7. Please describe the critical stresses on the piston skirts.

A. (Harris, McCarthy, Swanger) The pistons experience 1.35 million cycles of stress every 100 hours of engine operation. Therefore, cyclic stress levels that may produce crack initiation under high cycle fatigue conditions are of primary concern in evaluating a piston's ability to withstand operating stresses. The fatigue failure of metals, which involves the initiation of cracks, has been experimentally observed to occur as the result of repeated cycling between different stress levels. Therefore, the maximum and minimum stresses during a stress cycle are of primary interest in a fatigue analysis.

8. Please describe the factors that determine the minimum and maximum stresses in the Shoreham piston skirts.

A. (Harris, McCarthy, Swanger) Stresses in pistons are produced by various loads. The loading on the piston consists of pressure in the combustion chamber, friction and inertia. The largest loads that the piston sees occur at the top and bottom dead center. At top dead center and bottom dead center there is no relative motion between the piston and cylinder

liner. Frictional forces are very small at these positions, and frictional loads are, therefore, not considered in analyzing minimum and maximum stresses. The minimum stress (largest negative or compressive stress) in the skirt is caused by the firing pressure, which occurs close to top dead center of the power stroke. The maximum stress (largest positive or tensile stress) occurs due to inertia at top dead center of the exhaust stroke. The stresses due to inertia at top dead center of the exhaust stroke are insignificant in the analysis of crack initiation, but do serve to define the opposite end of the stress cycle, i.e., the maximum stresses. Other factors such as thermal distortion, gap size and inertia loading also influence the minimum stress. The most influential factor, however, is the peak firing pressure. Gap size, thermal distortion, stud pre-load and the influence of these parameters on the possibility of momentary lift-off of the crown from the skirt are also other factors influencing the maximum stress, but the most influential factor is the inertia loading.

9. How did FaAA determine that peak firing pressure occurred at top dead center of the power stroke?

A. (Harris, Swanger) FaAA developed a pressure/crank angle diagram that shows the firing pressure for various crank angles. The largest firing pressure occurs close to top dead center of the power stroke, which corresponds to zero degree of crank angle. Exhibit P-5 is a copy of the pressure/crank angle diagram.

10. How was it determined that the maximum inertia loading on the piston occurs at the top dead center position?

A. (Harris) A kinematic analysis of the piston, connecting rod, and crankshaft assembly revealed that the maximum piston acceleration occurs at the top dead center position. The top dead center position at exhaust is of primary interest only because this is one of the loadings that influences the cyclic stresses.

11. Why did LILCO replace the AF design piston skirts with AE design piston skirts?

A. (Seaman, Youngling) In November 1983, LILCO replaced the AF skirts with the AE skirts. At that time, the Owners Group analysis of the AF piston skirt to determine the possible extent of crack propagation which could result from continued operation had not been performed. Although cracking had been observed in the AF skirts, no failures had been experienced in the Shoreham type AF skirts in nuclear operation. LILCO, however, in consideration of its engine rebuild schedule and the time required to complete the AF analysis, decided to replace the AF skirts with the improved AE design. The analysis (which was completed later) verified through optical metallography, scanning electron microscopy and fracture mechanics analysis that the cracks in the AF skirt had arrested.

12. What are the major differences in the design between the AE piston skirt now in the EDGs at Shoreham and the AF design originally in place at Shoreham?

A. (Harris, Seaman, Swanger) The major differences between the AF and AE designs are in the boss regions through which studs extend to attach the crown to the skirt. The stud attachment bosses are considerably enlarged in the AE design. The thickness of the material around the stud hole for the AE design was increased by 82% over the AF design. The extent of the thickened area around the stud hole was also increased. In addition to the modifications to enlarge the stud attachment bosses, the following changes were made:

- (1) Thickening of the walls of a cavity that extends from the top of the wrist pin boss to the top of the skirt.
- (2) Thickening and filling in the material around the wrist pin hole.
- (3) Thickening and tapering of the circumferential rib that runs between the wrist pin bosses.

The major differences between the AF and AE designs are shown on Exhibit P-6.

13. Did the Owners Group review both the AE and AF piston skirts?

A. (Harris, McCarthy, Seaman) Yes. Even though the AE skirts had not demonstrated design or operational problems, the Owners Group decided to verify that the AE skirt design was, in fact, an improvement over the AF skirt design. The analyses showed that cracks in the AE skirt might not even initiate, but if they did, they would not propagate.

III. FaAA's Crack Initiation And  
Growth Analyses Show Cracks In The AE  
Piston Skirts Might Initiate, But Will Not Grow

A. General Approach And Assumptions

14. Please describe the FaAA analyses of crack initiation and growth in the AE piston skirt.

A. (Harris, McCarthy) The analyses included basically three steps. First, the minimum and maximum stresses in the stud boss region of the AE piston skirts were evaluated by both experimental procedures (strain gage measurements) and numerical procedures (finite element analysis). The stresses were determined for peak firing pressure and inertia at top dead center of the power stroke and for inertia loading at top dead center of the exhaust stroke. These two loading conditions provide the maximum and minimum stresses in the stud boss region and, therefore, serve fully to define the cyclic stress levels. The second step was to input these two sets of stresses into the fatigue analysis using a "modified Goodman diagram." The use of the experimental stresses, in combination with the modified Goodman diagram, predicted that cracks would not initiate in the piston skirt. Similar procedures using the numerical stresses, however, predicted that cracks could possibly initiate in the stud boss region. Therefore, a third step was necessary, i.e., a fracture mechanics analysis, to determine the growth behavior of the hypothesized initiated

cracks. Fracture mechanics analysis would also determine growth behavior from any possible initial imperfections in the skirt. The growth behavior of the hypothesized cracks was evaluated from information on stresses in the uncracked piston skirt in combination with fracture mechanics procedures. The analysis showed that any cracks that could possibly initiate in the stud boss region would not grow.

15. Why were both experimental and numerical procedures used to evaluate the stresses in the stud boss region?

A. (Harris, McCarthy) The experimental observations provided checks on the accuracy of the idealizations of the finite element analyses and verified that they provided conservative results. The use of the two approaches provided cross-checks and, therefore, provided results in which we have more confidence. Furthermore, a combination of experimental and numerical procedures was believed to be necessary to provide a complete understanding of the stresses in the critical regions of the skirt and to provide information on the combined behavior of the crown/skirt assembly.

16. Please describe why stresses in the stud boss region were considered as opposed to other areas of the piston skirt.

A. (Harris, McCarthy, Swanger) The numerical analysis did consider stresses in the entire piston skirt, but the analysis was concentrated in the stud boss region. The stresses derived from the experimental procedures also considered



several regions of the skirt, but also concentrated on the stud boss region. The stud boss region was emphasized for two reasons. First, inspection of all of the AF piston skirts originally installed in the Shoreham EDGs disclosed linear indications in one or more of the skirt-to-crown stud attachment bosses in each of these skirts. Second, a stress coat test performed on the AE skirt identified precisely this region as the most highly stressed area of the AE skirt.

17. Please describe the stress coat test.

A. (Harris, Swanger) The stress coat test consisted of applying a brittle lacquer on the inside of the piston skirt, stressing the skirt with hydraulic pressure and looking for cracks in the lacquer. The lacquer used is commercially available and is specifically intended for experimental determination of the location of maximum stresses. The regions where the lacquer first cracks as pressure is applied are the regions of highest stress. The piston was subjected to hydraulic pressures as high as 2,000 psig, well above any reported for the Shoreham EDGs. Only the lacquer in the stud boss region cracked, thereby indicating this region to be the most highly stressed.

18. What is wrong with the County's five criticisms of the assumptions it alleged FaAA made in its fracture mechanics analysis?

A. (Harris, McCarthy, Swanger) The County criticized FaAA's fracture mechanics analysis because it assumed (1) "complete adherence to TDI drawing dimensions;" (2) AE piston material free from imperfections; (3) "a non-corrosive operating environment free of gasses, water or vapor;" (4) "maximum peak firing pressure of 1,670 psi; and (5) a uniform skirt temperature. First, FaAA did not make the assumptions alleged by the County in (1) and (2). Second, the assumptions in (3) through (5) are reasonable.

19. Why is the County's allegation wrong that the FaAA analysis assumed "complete adherence to TDI drawing dimensions?"

A. (Harris, McCarthy, Swanger) FaAA made measurements from an actual AE piston skirt in addition to reviewing dimensions on TDI drawings. Furthermore, FaAA verified some of the dimensions used in its analysis with actual field measurements of AE piston skirts made during the engine rebuild program and the DRQR program. Representative measurements taken by these programs are included in Exhibit P-7.

20. Why is the County's allegation incorrect that FaAA assumed the AE piston material was free from any small imperfections?

A. (Harris, Johnson, McCarthy, Seaman, Swanger) Fracture mechanics analysis will actually show what level of imperfection can be tolerated in the material. The FaAA fracture mechanics analysis of the AE piston skirt, which will be

discussed in detail below, showed that a crack up to 1/2 inch deep would not propagate. This also means that cracks would not grow from any possible initial imperfection under 1/2 inch in size. In addition, to preclude any significant imperfections, all AE piston skirts were inspected by liquid dye penetrant and eddy-current at the TDI factory in Oakland prior to shipment to LILCO. TDI performed the liquid dye penetrant inspections which were witnessed by LILCO and Stone & Webster. FaAA performed the eddy-current testing. Piston skirts were rejected, prior to shipment to Shoreham, for any linear indications for which the liquid dye penetrant exceeded 1/32 inch in length. Exhibit P-8 includes documentation regarding the liquid dye penetrant testing, the certificates of compliance and the receipt inspections for the AE piston skirts at Shoreham.

21. Did FaAA consider the effect of corrosion in the operating environment in its fracture mechanics analysis?

A. (Harris, McCarthy, Swanger) Yes, and FaAA concluded that the environmental conditions inside the crankcase are not expected to have an influence on the crack growth characteristics of the piston skirt material. The vapors present in the crankcase are not the type that are commonly observed to accelerate crack growth. Furthermore, environmental enhancement of crack growth is not expected at the higher frequency (225 cycles per minute) experienced by the Shoreham EDGs.

22. Does LILCO have procedures to control the environmental conditions in the crankcase that might lead to corrosion?

A. (Youngling) Yes. LILCO takes routine oil samples from the Shoreham EDGs to check for any acidity and moisture.

23. Did the AF piston skirts in the Shoreham EDGs show any signs of corrosion?

A. (Youngling) No. After 600-800 hours of operation, the AF piston skirts in the EDGs at Shoreham showed no signs of corrosion.

24. Is 1,670 psig a reasonable representation of the peak firing pressures actually experienced by the Shoreham EDG's?

A. (Harris, Youngling) Yes. The 1,670 psig peak firing pressure is reasonable based on independent FaAA and Stone & Webster measurements, TDI factory tests and the preoperational qualification test procedures.

25. Please describe the FaAA and Stone & Webster measurements of the peak firing pressures.

A. (Swanger) FaAA and Stone & Webster conducted a joint test to measure the pressure versus crank angle relationship which included measuring the peak firing pressure. A piezo-electric transducer was used directly to measure the pressure inside the combustion chamber. The angle of the crankshaft was recorded simultaneously on a separate channel of the instrumentation recording the firing pressures. The position at top dead center was recorded for every revolution.

Measurements were also taken simultaneously at the pressure cocks on the side of the cylinder using a Kiene gage to measure the cylinder firing pressure. Exhibit P-5 is the pressure/crank angle diagram developed by FaAA.

26. What peak firing pressures did TDI measure in their factory tests as reported to LILCO in the TDI instruction manual?

A. (Seaman, Youngling) The County's Exhibit 46, Document No. 6 (DSR-48, Engine No. 74011) details these measurements. During actual operation of an engine, peak firing pressure was measured at 25%, 50%, 75%, 100%, and 110% of rated power. These measurements were made for each cylinder and provided to LILCO as a part of the TDI instruction manuals supplied with the engines. The maximum pressure shown on Document No. 6 for 100% is 1,650 psig. The County incorrectly characterized some TDI measurements as high as 1,750 for 100%. As shown on the County's Exhibit 46, Document No. 6, the 1,750 psig value was actually taken at 110%. The County used this erroneous interpretation of the TDI measurements to help support its conclusion that the Shoreham EDG peak firing pressure was as high as 1,750 to 1,800 psig.

27. Please describe the measurement of peak firing pressure in the preoperational qualification test procedures.

A. (Youngling) During the preoperational qualification test, the engine was run at 3,500 kW, and a full set of firing

pressures was taken at each of the eight cylinders using a Kiene gage. Exhibit P-9 includes the peak firing pressures measured before and after the crankshaft replacement. Exhibit P-9 also includes an example of the preoperational test procedures. These recorded data indicate a range of average firing pressures between 1,522.5 psig and 1,671 psig.

28. Did the FaAA analysis consider peak firing pressure under overload conditions?

A. (Harris, Swanger) The static experimental procedures considered pressures as high as 2,000 psig, which is well in excess of reported peak firing pressure. Contrary to the County's understanding, strain gage measurements were not limited to a maximum of 1,600 psig and strains corresponding up to 2,000 psig were reported on Figures 3-5 through 3-8 of the FaAA Piston Report. These figures are included in Exhibit P-10. In its numerical procedures, FaAA did not consider peak firing pressure at overload because the engine operates a relatively small amount of time under overload conditions and, therefore, would have little effect on the initiation and growth of cracks.

Subsequent analyses, using the crown/skirt interaction model described below, were performed on the cracking behavior of AE piston skirts subjected to higher hypothesized firing pressures. It was found that pressures above 2,200 psig are required before possible initiated cracks could grow.

Therefore, the conclusion drawn in the initial analysis that employed a peak firing pressure of 1,670 psig is valid for pressures up to 2,200 psig, which is well above any reported peak firing pressures in TDI R-4 engines, even under overload conditions.

29. Why is it reasonable to assume a uniform skirt temperature?

A. (Harris, McCarthy, Swanger) Temperatures measured by TDI, and independently verified by FaAA as being reasonable, indicate temperatures on the bottom of the crown are nearly constant and equal to about 200° F. This suggests the piston skirt is nearly isothermal under steady-state operating conditions where the surrounding cooling water and oil range in temperature between 190° F and 160° F.

30. How were the temperatures measured by TDI independently verified by FaAA?

A. (Harris, Swanger) TDI measured peak temperatures in the crown and furnished those temperatures to FaAA in the form shown on Exhibit P-11. FaAA made independent calculations using transient radiative and convective heat transfer analysis to verify these measurements. The analysis utilized reasonable values for coolant temperatures, convective heat transfer coefficients and combustion gas temperatures derived from the pressure/crank angle diagram (Exhibit P-5). Key features of the calculated temperature field, including peak temperature and

temperature gradient through the central portion of the crown, were in agreement with TDI measurements of temperature.

31. Did the FaAA analyses consider the operating conditions experienced by the EDGs at Shoreham?

A. (Harris, McCarthy, Swanger) Yes. FaAA determined the critical loads and areas to be studied and applied the analyses and procedures to predict and evaluate the stresses in these areas. The FaAA analyses contain assumptions that closely approximate the key factors concerned with the operating conditions at Shoreham relevant to a determination of cyclic stress levels and cracking behavior. As the procedures and analyses are described below, it will become clear that the factors considered produced a realistic evaluation of the stresses experienced under operating conditions.

B. Experimental Procedures

32. Please describe the experimental procedures used to evaluate the maximum and minimum stresses in the stud boss region of the AE piston skirts.

A. (Harris, Swanger) Foil resistance strain gage rosettes were mounted on the piston skirts in several areas including those of highest stress reflected by the stress coat test described above. Exhibit P-12 shows the location of the strain gages. The gages were connected to data acquisition and recording equipment. An actual cylinder liner was used in the test with two opposing pistons placed crown-to-crown within the



liner. The region between the crowns was pressurized with a hydraulic pump to as high a pressure as 2,000 psig. The pressure load on the instrumented skirt was reacted through the wrist pin and a short piece of connecting rod to a support plate. The connecting rod was in a vertical position, thereby simulating the top dead center position of the piston.

Two separate test series were conducted using this procedure. One series was conducted with a conventional crown, and one series was conducted with a crown that was modified to widen the gap at the outer ring between the crown and the skirt so that it would not close under the applied maximum pressure of 2,000 psig.

33. What conclusions did you draw from a comparison of the experimental results from the conventional and modified crown?

A. (Harris) A comparison of the strains observed at one of the stud bosses in the piston shown in Exhibit P-9 indicates that the crown-skirt gap closes at approximately 1,000 psig and distributes about 12% of the load at peak firing pressure on the outer ring. Strain gage measurements at numerous locations on the AE skirt also shows that the gap closed nearly simultaneously around the circumference of the piston, because the inflection point in the strain-pressure results always occurred at about 1,000 psig. This measured information showed gap closure at pressures below the 1,670 psig peak firing pressure

measured for Shoreham and showed simultaneous closure around the ring. These experimentally observed results provided guidance in the construction of the crown/skirt interaction model discussed below. Exhibit P-13 summarizes the experimental observations related to the closure of the gap due to pressure and stress reduction due to gap closure in the AE piston skirt.

34. Under what temperature conditions were the experimental procedures performed?

A. (Harris) The experimental procedures were conducted at room temperature or, in other words, under isothermal conditions.

35. Why was this a reasonable condition when the pistons do not operate at room temperature?

A. (Harris, McCarthy) Apart from contributing to the closure of the gap and consequent redistribution of the gas firing pressure load, temperature gradients play a relatively minor role in the analysis because they do not contribute to the cyclic stress range. At operating temperatures, the top of the crown is hotter than the underside of the crown, thereby producing thermal distortion that will tend to close the gap. This results in more load being transmitted through the outer ring as is seen by the comparison of the modified and normal crown experimental results. Since the stress on the stud attachment boss is governed by the load applied to the inner contact ring, thermal distortion reduces the peak stresses due to

firing pressure at the critical point (the stud boss region). A numerical analysis of thermal distortion of the crown discussed below confirmed that thermal distortion decreases the portion of the firing load carried on the inner ring and, therefore, reduces the cyclic stresses in the stud boss region.

36. What were the results of the experimental testing?

A. (Harris, Swanger) Exhibit P-14 summarizes the strain readings and calculated stresses for the complete stud boss gage rosettes. The principal strains and stresses were calculated from the rosette strain readings using the conventional equations for rectangular rosettes specified in Experimental Stress Analysis and Motion Measurement by R. C. Dove and P. H. Adams. Exhibit P-14 describes the significant stress value, the sigma III or the third (algebraic minimum) principal stress. The fracture initiation analysis showed that the experimentally derived stress would not cause cracks to initiate.

#### C. Numerical Procedure

37. Please describe the numerical procedure used to determine the maximum and minimum stresses in the stud boss region.

A. (Harris, McCarthy) The numerical analysis consisted of three-dimensional finite element calculations. The finite element method is an approximate technique to apply the theory of elasticity to determine how a body will perform in response

to specific loads or displacements applied to it. Those loads or displacements are termed "boundary conditions" and they define what factors come into play on the boundary of the piston skirt.

38. Please give some examples of the use of finite element analysis.

A. (Harris, McCarthy) Finite element analysis has been used in the design of a very wide range of structures such as the New York World Trade Center, the space shuttle, various commercial aircraft and nuclear reactor pressure vessels and piping.

39. Please describe the finite element analyses of the AE piston skirts.

A. (Harris) The finite element analyses of the piston skirt were composed of the following two parts:

Part 1. Isothermal Analysis: An isothermal analysis of a piston skirt with a crown mounted on it was performed. Closure of the gap at the outer contact ring and thermal distortion were not considered. This part of the analysis provided base line stresses for a skirt with a pressurized crown. These stresses were adjusted for gap closure and thermal distortion by use of a crown/skirt interaction model described in Part 2.

Part 2. Crown/Skirt Interaction Model: The second part of the finite element analysis provided a means of accounting for thermal distortion, gap closure and possible momentary lift-off of the crown from the skirt. This part of the analysis consisted of the following steps:

a. Construction of a crown/skirt interaction model to provide a means of calculating cyclic stresses in the stud boss region from information on the crown and skirt stiffnesses. This model considered the crown and skirt as coupled elastic springs, whose stiffnesses were evaluated by the finite element analyses described in b. below.

b. Evaluation of the stiffnesses used as inputs to the crown/skirt interaction model. This process involved

i. Evaluation of the relevant stiffnesses of the skirt.

ii. Evaluation of the stiffnesses and thermal distortion of the crown when subjected to steady-state operation temperature.

c. Evaluation of the peak stress when momentary lift-off of the crown from the skirt occurs.

The crown/skirt interaction model of Part 2 used the stress information from Part 1 to provide cyclic stresses under steady-state operating conditions.

40. What is the major value of the crown/skirt interaction model?

A. (Harris, McCarthy) The major value of the crown/skirt interaction model is its ability to predict cyclic stresses in a piston skirt at operating temperatures.

1. Isothermal Analysis

41. What boundary conditions were involved in the FaAA isothermal finite element calculations?

A. (Harris) The following boundary conditions were assumed:

- (1) a rigid wrist pin;
- (2) displacement on the inner contact ring between the skirt and the crown varying linearly with the radial position at any value of angular coordinates;
- (3) frictionless interface between the top of the skirt and the crown; and
- (4) frictionless interface between the piston assembly and cylinder wall.

42. Please discuss why the boundary condition of a rigid wrist pin is reasonable.

A. (Harris, Swanger) A rigid wrist pin exhibits no deformation. The wrist pin in actual operation is elastic and, therefore, exhibits some deformation thereby redistributing stresses in the stud boss area. A rigid wrist pin is actually conservative in the present case, because it assumes that the deformation will occur in the piston and not in the wrist pin.

Furthermore, the wrist pin in reality is actually thicker than the piston and, therefore, more resistant to deformation than the piston.

Modeling an elastic wrist pin in finite element analysis results in a more complicated model. Therefore, FaAA made the conservative rigid wrist pin assumption initially based on constructing a tractable, but reasonable finite element model. A subsequent analysis assuming a soft wrist pin confirmed that this assumption is conservative. The soft wrist pin analysis showed that peak stresses in the stud boss of the piston skirt assuming a soft wrist pin are decreased in comparison to the stresses assuming a rigid wrist pin.

43. Please describe the comparative analysis performed using the assumed types of wrist pins.

A. (Harris) In the original analysis with a rigid wrist pin, the boundary condition in the area of contact between the wrist pin and the piston skirt was a uniform displacement (i.e., a rigid wrist pin). In order to estimate the influence of elasticity of the wrist pin, another analysis was performed in which the boundary condition in the area of contact between the wrist pin and the piston skirt was a uniform pressure. This is the opposite extreme from a rigid wrist pin and represents a soft wrist pin. The calculated peak stud boss stresses in the AE piston skirt were reduced by 39% when a soft wrist pin was used. This demonstrates the conservative nature of the assumption of a rigid wrist pin.

44. Please describe the reasonableness of the assumption that the displacement on the inner contact ring between the crown and the skirt varies linearly with the radial position at any value of the angular coordinate.

A. (Harris) This assumption provides a simplification of the boundary conditions that is accurate because the approximate 1 inch width of the support ring is small relative to the 17 inch piston diameter. The assumption of linearity provides a good approximation over such a small distance.

45. Please discuss why the assumption of a frictionless interface between the piston skirt and crown and the piston assembly and cylinder wall is reasonable.

A. (Harris) The inner contact ring between the crown and skirt is clean upon assembly of the piston, and the region is well lubricated during operation of the engine. Therefore, the assumption of no friction at the crown-skirt interface is reasonable. Assuming no friction between the piston and cylinder wall is also reasonable because the relative velocity between these two components is very low at the top dead center position of interest.

46. What other factors were considered in the finite element procedure?

A. (Harris) The magnitude of the pressure load (379,000 pounds) created by the peak firing pressure was considered. At top dead center of the power stroke, this pressure load is somewhat offset by the inertia load (9,727 pounds), which is exerted by the crown on the top of the skirt. The inertia



force, therefore, was subtracted from the magnitude of the gas pressure load to determine a maximum net force on the top of the skirt of 369,300 pounds, which corresponds to an effective pressure of 1,627 psig.

47. What were the major results of of the isothermal finite element analysis using the boundary conditions described above?

A. (Harris) The peak stress ( $\sigma_{III}$ ) in the stud boss region of the AE piston skirt at top dead center of the power stroke for a rigid wrist pin was calculated to be -68.1 ksi. The corresponding cyclic stress was evaluated by determining the stress at top dead center of the exhaust stroke and accounting for gap closure during the power stroke. The stress at top dead center of the exhaust stroke was determined by multiplying the top dead center power stroke stress value by the ratio of the inertia load to the pressure-minus-inertia load. Gap closure was accounted for by multiplying the finite element stress value by 88% (in accordance with Exhibit P-9).

48. How do the results from the numerical procedures compare with those from the experimental procedures?

A. (Harris) The cyclic stress levels under isothermal conditions in the AE piston skirt that were estimated from the experimental and numerical results are presented in Exhibit P-15. As you can see, the numerical values are higher than the experimental values and, therefore, more conservative.

49. Can you explain why there is a difference, albeit on the conservative side, between the numerical and experimental results?

A. (Harris) The assumption of a rigid wrist pin is the main reason for the variance. As was described above, this assumption is conservative because an elastic or soft wrist pin would result in decreasing the stresses in the stud boss region. In fact, as shown in Exhibit P-16, the assumption of a soft wrist pin results in numerical stresses smaller than those experimentally measured.

## 2. Crown/Skirt Interaction Model

50. Please describe the crown/skirt interaction model.

A. (Harris) The numerical procedures that were described above analyzed stress levels under isothermal conditions. Load transfer between the skirt and the crown is influenced by thermal distortion of the crown and the initial size of the gap between the crown and the skirt. FaAA directly measured the effect of the gap on piston stresses in its experimental work, and used the experimental results on gap closure to adjust the numerical results to reflect gap closure. These were considered reasonable assumptions to evaluate the stresses, erring, if at all, to overestimate the stresses.

As time permitted, the crown/skirt analysis was conducted to consider directly the influence of thermal distortion and initial gap on cyclic stress levels and the possibility of

momentary lift-off of the crown from the skirt. These factors were estimated by combining the results of the isothermal finite element stress analysis with a crown/skirt interaction model.

51. Please describe the crown/skirt interaction model used to determine the influence of thermal distortion on the load split between the loading rings and the possibility of momentary lift-off of the crown from the skirt during the exhaust stroke.

A. (Harris) The crown skirt interaction model is a simple engineering model that accounts for all the factors influencing the maximum and minimum stresses such as initial outer ring gap, thermal distortion of the crown, pressure loading, inertia loading, stud preloads and possible momentary lift-off of the crown from the skirt during the exhaust stroke. Finite element results alone do not directly provide this information. Thermal distortion was included as a thermally-induced displacement or boundary condition that was calculated by finite elements using a steady-state temperature field in the piston assembly based on experimental measurements. The interaction model treated the crown and the skirt as springs whose stiffness was estimated by finite element techniques based on the assumption that the loading rings on the crown and skirt remain parallel to one another. The stiffnesses and crown thermal distortion result from the finite element analyses provided the necessary inputs to the crown/skirt interaction model.

52. What were the basic conditions in the crown/skirt interaction model?

A. (Harris) Two basic conditions were considered in the interaction model:

- (1) top dead center of the compression stroke (or beginning of the power stroke) where the maximum compressive stresses in the piston skirt occur; and
- (2) top dead center of the exhaust stroke where momentary lift-off of the crown may occur.

Isothermal and steady-state operating temperatures were considered for both of these load cases.

53. Please describe the boundary conditions employed in the finite element steps in the crown/skirt interaction analysis of the skirt.

A. (Harris) This analysis of the skirt utilized the following three sets of boundary conditions:

- (1) Uniform vertical displacement on the inner crown/skirt contact ring of a magnitude to react the load corresponding to 1627 psig effective pressure on the crown;
- (2) Uniform vertical displacement on the outer crown/skirt contact ring of a magnitude to react the load corresponding to 1627 psig effective pressure on the crown; and
- (3) A stud load applied on the stud washer landing area and reacting on the outer loading ring which is constrained to have a uniform vertical displacement.

The results of the analyses using boundary conditions (1) and

(2) above provided estimates of the skirt spring constants or stiffnesses that were required for the crown/skirt interaction model. Boundary condition (3) provided the stress levels due to inertia at top dead center of the exhaust stroke appropriate for crown/skirt lift-off. In the isothermal analysis no lift-off between the crown and skirt was considered. Therefore, the peak stress due to inertia could be obtained from the peak stress due to firing pressure simply by multiplying by the ratio of the inertia force to the peak pressure-minus-inertia force (changing the sign to account for the different direction of the loads).

54. Why is the boundary condition regarding uniform vertical displacement reasonable?

A. (Harris) A uniform vertical displacement boundary condition is simply a convenience for calculating the stiffnesses of the skirt, and this assumption is not key to the FaAA evaluation of stresses. Comparison with finite element calculations where the displacement was not required to remain uniform provides similar results. In addition, the experimental results shown in Exhibit P-10 indicate that gap closure will occur uniformly around the circumference of the piston/skirt.

55. In addition to the three sets of boundary conditions, were any other factors considered in the expanded finite element analysis of the skirt?

A. (Harris) There were basically three other factors. First, a rigid wrist pin was assumed in the first and second sets of boundary conditions. No wrist pin was utilized for the third set, i.e., stress when momentary lift-off occurs. Second, all of the finite element runs on the skirt models were performed for uniform temperature, reflecting the true operating condition of the skirt. Third, a stud preload of 6,600 pounds was used based on strain gage measurements obtained by measuring the strain in a stud when a crown was mounted on a skirt in accordance with manufacturer's specifications. This measurement was made by FaAA using strain gages.

56. Please describe the finite element analysis of the crown performed as a portion of the development of the crown/skirt interaction model.

A. (Harris) Three parameters related to the crown were of interest in the crown/skirt interaction model. These were the stiffness of the crown when subjected to pressure on the combustion side, stiffness of the crown when subjected to a load on the outer contact ring and thermal distortion of the crown when subjected to steady-state operating temperature. The stiffnesses of the crown were evaluated by finite elements by subjecting the crown to the load of interest (pressure or load on the outer ring) and calculating the resulting movement of the outer contact ring relative to the inner contact ring. The stiffness (or spring constant) is then equal to the load divided by the corresponding displacement.

The thermal distortion (as measured by the thermally induced relative displacement of the two concentric load rings) was calculated to be 0.0106 inch. This value was obtained by using the experimentally determined crown surface temperature measurements as boundary conditions for a steady-state heat conduction analysis of the temperatures in the interior of the crown. These temperatures were then used in a finite element thermoelastic calculation of the thermally induced displacement in the crown.

57. What were the major results drawn from the crown/skirt interaction model?

A. (Harris) The major results drawn from the crown/skirt interaction model were the cyclic stress levels in a piston skirt at isothermal and steady-state operating temperatures considering the influences of the initial gap and the possibility of momentary lift-off of the crown from the skirt. Exhibit P-17 summarizes the isothermal and steady-state operating temperature cyclic stresses for an AE piston skirt with various initial gap sizes. Results are presented for several sets of estimated skirt stiffnesses.

58. How do the cyclic stresses under isothermal and steady-state operating temperatures compare?

A. (Harris) The results presented in Exhibit P-17 show that the cyclic stresses are less severe under steady-state operating conditions, because the minimum stresses are increased

(less compressive) without a corresponding increase in the maximum stress. Therefore, the cyclic stresses are actually largest under isothermal conditions.

59. How do the gap closure pressures and load splits evaluated for the crown/skirt interaction model compare to those observed experimentally as a result of the strain gage measurements?

A. (Harris) The gap closure pressure and load split between the rings were calculated from the crown/skirt interaction results by an equation that assumes the peak stress is governed by the load on the inner ring. Exhibit P-18 shows that this assumption is a good approximation because the stresses for a given load that are applied by a uniform displacement on the inner ring are much higher than the corresponding values for the loading on the outer ring. Exhibit P-19 summarizes the calculated gap closure pressure and load split at nominal, minimum and maximum values in comparison to the experimental observations. The nominal, minimum, and maximum values in the column of experimental results provide the range of values actually observed. The corresponding values in the column of calculated values were calculated using the nominal, minimum, and maximum values of the initial gap. The comparison between the experimental and numerical results can also be made by estimating skirt stiffness from experimentally observed load splits and gap closure pressures by using equations developed for the crown/skirt interaction model. Exhibit P-20



compares the results of the estimated skirt stiffness from experimentally observed results with the finite element stiffnesses. Experimental values of the outer skirt stiffness are generally lower than the numerical value. Overall, the agreement between the experimental and numerical sets of data are quite good, which verifies the validity of the crown/skirt interaction model.

60. How do the different sets of stiffnesses affect the important results drawn from the crown/skirt interaction model?

A. (Harris) The calculated cyclic stresses, which are the most important results of the crown/skirt interaction model, are not strongly dependent on the values of the skirt stiffnesses. This can be seen from Exhibit P-17 which presents calculated cyclic stresses in the stud boss region for various initial gap sizes and loading conditions that were calculated using different sets of skirt stiffnesses. For a given gap and loading condition, the cyclic stresses are nearly the same for each of the sets of stiffnesses.

D. Fatigue Crack Initiation Analysis

61. What was the next step in the evaluation of the integrity of the piston once the cyclic stresses had been defined?

A. (Harris, McCarthy) The next step was to determine if cracks can initiate when the material is subjected to these cyclic stresses.

62. Please describe the analysis you performed to determine whether cracks would initiate in the AE piston skirts.

A. (Harris, McCarthy) As noted, the pistons experienced 1.35 million stress cycles every 100 hours of operation. Therefore, crack initiation under high cycle fatigue conditions is the main consideration. The fatigue property called the endurance limit of the material is of primary interest. The Iron Castings Handbook, edited by C. F. Walton and T. J. Omyer, indicates that the endurance limit of ductile cast iron with the properties of the 100-70-03 material used in the AE piston skirt is conservatively 30 ksi. Comparison of this fatigue property of the skirt material with the cyclic stresses evaluated from experimental measurements and finite element calculations allowed us to predict whether cracks would or would not initiate.

63. Please explain the procedure you followed to predict crack initiation behavior.

A. (Harris, McCarthy) The endurance limit of a material is directly applicable to the case where the mean stress is zero and the stress system is uniaxial. In order to perform the analysis on the AE piston skirt, procedures to account for a non-zero mean stress were employed. Non-zero mean stress was treated in the standard manner using a modified Goodman diagram. The Goodman diagram is the means by which the allowable cyclic stress for infinite life (or no crack initiation) for a

given mean stress can be plotted. These conditions are summarized in Exhibit P-21. The results in Exhibit P-21 are for uniaxial stress, and are directly applicable to the current problem because the experimental results discussed above show that stresses are nearly uniaxial in the highly stressed region of the stud boss area. The crack initiation criterion was used in combination with the cyclic stresses shown on Exhibit P-17 to evaluate the possibility of crack initiation for various gap sizes. The mean stress and stress amplitude for a given condition were plotted on a figure such as the one shown in Exhibit P-21. If the plotted point falls inside the solid lines (stress envelope) then crack initiation will not occur. An endurance limit of 30 ksi was used, and a modified Goodman diagram was used to adapt this endurance limit for cases other than zero mean stress. This same procedure was utilized in evaluating crack initiation from the experimental measurements and finite element results from both the isothermal and crown/skirt interaction calculations.

64. Please describe the modified Goodman diagram?

A. (Harris, McCarthy) The modified Goodman diagram is a plot defining the relationship of mean stress and cyclic stress for an infinite life. It is primarily based on experimental observations of the failure of fatigue specimens that were subjected to a given cyclic and mean stress. A considerable

amount of experimental data has been generated over the last several decades that provides the basis for using the modified Goodman diagram for analysis of fatigue with non-zero mean stress. In developing the modified Goodman diagram, failure (or crack initiation) was considered to occur if the material permanently deforms (plastically deforms or yields) as opposed to actually breaking.

65. Please describe the results of the fatigue analysis using the stresses evaluated from the experimental measurements and the isothermal finite element calculations.

A. (Harris) Exhibit P-22 is a plot of the allowable stress envelope for infinite life with the stresses at various gap sizes indicated. The stresses for isothermal conditions are shown. Exhibit P-22 shows that cracks are predicted not to initiate in AE skirts under cyclic stresses corresponding to the experimental results for any gap size and that cracks may or may not initiate under cyclic stresses corresponding to the finite element results depending on the yield strengths and gap size. The modified Goodman diagram is drawn for the range of values of yield strength from 63.5 to 70.5 ksi that bound the results of measurements of the yield strength of material taken from an AE skirt drawn from the lot of skirts now in use at Shoreham.

66. Did the results of the fatigue analysis using the stresses evaluated from the crown/skirt interaction model confirm that isothermal conditions are more severe than steady-state operating conditions?

A. (Harris) Yes. Exhibit P-23 shows the results for 0.007 and 0.011 inch initial gaps for isothermal and steady-state temperature distribution conditions. The results on Exhibit P-23 show that conditions for crack initiation are more severe under isothermal conditions. Therefore, cracks are more likely to initiate under isothermal than steady-state conditions. Exhibit P-23 also shows that cracks might initiate in the AE skirts under certain conditions, such as under isothermal conditions with a 0.011 inch gap in a piston of relatively low yield strength. A smaller initial gap is beneficial in reducing the cyclic stress under isothermal conditions, but contributes to the possibility of momentary crown lift-off. Such lift-off is not detrimental, however, because it does not have an adverse influence on the operation of the AE piston skirt at Shoreham and does not increase the cyclic stress.

67. Do the results of the finite element analyses showing that isothermal conditions are more severe than steady-state operating conditions support a conclusion that the experimental results are applicable to operating temperature conditions?

A. (Harris) Yes. The overall conclusion based on the experimental measurements is that cracks will not initiate in the stud boss region of the AE piston skirt. The fact that the crown/skirt interaction model predicted lower cyclic stresses under steady-state temperatures supports a conclusion that the experimental results showing no cracks under isothermal conditions also applies to operating temperature conditions.

E. Fatigue Crack Growth Analysis

68. Does the initiation of a crack mean that the piston will eventually fail?

A. (Harris, McCarthy, Swanger) No. The initiated crack may or may not grow. Even if it does grow, it may do so only for awhile and then arrest before growing to the point where the piston would fail. Fracture mechanics analysis is commonly employed to make this determination. Fracture mechanics is the body of engineering knowledge that is applicable to the analysis of the growth and stability of cracks in solids.

69. What is the purpose of fracture mechanics analysis?

A. (Harris, McCarthy) Modern design analysis is able to insure the safe operation of such structures as aircraft, spacecraft, pipelines and turbines, etc. through the application of engineering fracture mechanics. It is now common to design and operate critical structural components in such a manner that the initial presence of crack-like defects is assumed, and the possible growth of the defects due to fatigue is calculated. For example, even the highly-stressed rotating parts of military aircraft gas turbine engines are designed assuming the presence of small cracks that grow in fatigue. In fact, the United States Air Force has a formal procedure that expressly requires the manufacturer to adopt this design approach. Many other structures, i.e., civil, mechanical and

marine, are designed with the same philosophy. This philosophy merely reflects the fact that all materials and structures contain crack-like defects on some scale and that the primary objective of design analysis is, therefore, not to prevent initiation but to assure that such cracks cannot grow to significant size. Fracture mechanics analysis provides this assurance.

70. Please describe the methodology FaAA employed to determine whether cracks would grow in AE piston skirts.

A. (Harris) Because the crack initiation analysis using the conservative numerical finite element results predicted that crack initiation could possibly occur, a fracture mechanics analysis of the growth (and possible arrest) behavior of the hypothesized initiated cracks was performed. Not all crack tips are unstable, contrary to the County's testimony, and fracture mechanics provides the means of analyzing the stability and possible growth of cracks in solids. In the case of the AE piston skirt, the solid was considered as an elastic body. Standard linear elastic fracture mechanics procedures were used to evaluate the stresses near the tip of the crack from information on stresses in the uncracked skirt. The stress intensity factor provided the measure of the stresses near the crack tip. Elastic-plastic behavior of the material in the highly stressed region of the stud boss was accounted for by appropriate procedures. The fracture mechanics properties of the AE

piston material were compared with the fracture mechanics parameters computed by the finite element analyses, stress and fracture mechanics evaluation.

71. What were the fracture mechanics properties required in this analysis?

A. (Harris, McCarthy) Two fracture mechanics properties were necessary for this analysis: the fracture toughness of the material and the fatigue growth crack characteristics of the material.

72. Please describe the fracture toughness property utilized in this analysis?

A. (Harris) Exhibit P-24 summarizes some relevant fracture toughness data from the literature. A fracture toughness of KIC of 40 ksi-in<sup>1/2</sup> was considered a reasonable, but conservative, value of fracture toughness. This value is conservative because it represents a temperature of 70°F. Fracture toughness of cast iron is influenced by temperature within a range (room temperature to approximately 300°F). As temperature increases, the fracture toughness increases. As noted above, actual measurements of temperature during operation indicated that the temperature of the piston skirt is a uniform 200°F. Therefore, the use of a value measured at 70°F is conservative.



73. Please describe the fatigue crack growth characteristics used in this analysis.

A. (Harris) For a given material operating in a given environment, the rate at which a fatigue crack will grow is dependent mainly on the cyclic value of the stress intensity factor ( $\Delta K = K_{max} - K_{min}$ ). Other factors, such as the mean value of the stress intensity factor (represented as  $R = K_{min}/K_{max}$ ) also influence, to a lesser degree, the rate at which a fatigue crack grows. The threshold cyclic stress intensity factor below which cracks will not propagate is expressed as  $\Delta K_{th}$ . The  $\Delta K_{th}$  of a particular material is a function of the R-value. The Foreman relation for crack growth (which is a widely used relationship in fracture mechanics analysis) was combined with the treatment of the influence of the R-value on  $\Delta K_{th}$  from Metallurgical Transactions by A. Yuen, S. J. Hopkins, G. R. Leverante and C. A. Rau, to determine the influence of R on  $\Delta K_{th}$ . Cracks are considered not to propagate for a given  $\Delta K$  and R if  $\Delta K$  is less than the  $\Delta K_{th}$  at the given R-value.

74. Please describe the procedures used to perform the fracture mechanics analysis.

A. (Harris) The fracture mechanics properties described above and the calculated stress intensity factors from the finite element stresses were used in this analysis. The finite element results represented elastically calculated stresses.

The plastically redistributed stresses corresponding both to the isothermal and steady-state operation were analyzed. Two sets of calculations were performed, one for nominal tensile properties and one for poorer case tensile properties bound from the measurements of tensile strengths of the AE skirt drawn from the lot of skirts now at Shoreham. The BIGIF fracture mechanics code was used to obtain the elastic-plastic redistributed stress fields that exist after yielding. Residual tensile stresses were predicted by the use of BIGIF in the localized region where the cracks could possibly initiate. The BIGIF calculations accounted for the variation in Delta Kth with the stress ratio, the R-value. BIGIF was also used to calculate the stress intensity factor range, Delta K.

75. What is the BIGIF fracture mechanics code?

A. (Harris, McCarthy) BIGIF is a general purpose fracture mechanics code that is used in the analysis of crack stability and fatigue crack growth. It is based on linear elastic fracture mechanics, but does contain capabilities for treating contained plastic deformation. BIGIF is used by many different organizations on a wide variety of problems. In addition to its use on pistons and crankshafts of the TDI engines, it has been applied to cracking problems in pressure vessels, pipes, steam turbine and generator rotors, spacecraft components and gear teeth. Its great versatility makes it applicable to a very wide range of problems.

76. Did the fracture mechanics calculations show that the cracks that could possibly initiate in the AE piston skirts would not grow?

A. (Harris) Yes. For the AE skirt, the fracture mechanics calculations revealed that the Delta K and R values for all crack depths do not exceed the threshold conditions. Therefore, the cracks in the AE skirt that were predicted possibly to initiate based on the conservative finite element results were shown not to grow under isothermal or steady-state conditions. Exhibit P-25 shows the representative values of R and Delta K for various hypothesized crack depths for an AE piston skirt with a 0.007 inch gap operating under steady-state temperature conditions. This is the most severe condition from a crack propagation standpoint. Exhibit P-25 also shows the corresponding threshold condition for crack growth. It is seen that the operating conditions are always below the threshold condition. Therefore, any cracks that may initiate will never grow, even if they were as deep as 1/2 inch. Furthermore, contrary to the County's erroneous hypothesis, any imperfections introduced during fabrication of the piston also would not grow, even if they were as deep as 1/2 inch.

77. Do you consider your analytical results to reflect the possibility of crack growth under actual operating conditions?

A. (Harris, McCarthy, Swanger) Yes. The stresses upon which the fracture mechanics analysis was based considered the major loads and displacements actually influencing the piston

skirts under operating conditions. Assumptions required in the analytical process were conservative and resulted in over-estimating the stresses. Those assumptions have been discussed above and include, for instance, the use of a rigid wrist pin. The conservative nature of the assumptions can be seen by comparing the experimental results with the finite element results. The finite element stresses were invariably higher. Even the use of these conservative stresses indicated that cracks will not grow in the AE piston skirt. FaAA also considered the operating environmental conditions inside of the crankcase of the Shoreham EDGs and concluded that they would not be expected to have an influence on the crack growth characteristics of the piston skirt material.

#### IV. Operating Experience

78. Are you aware of any failures of AE piston skirts in operation?

A. (Harris, Seaman, Swanger) No. The DRQR created a computerized component tracking system to gather nuclear and non-nuclear experience on TDI R-4 engines, as well as additional information on other EDGs in nuclear service. No AE piston failures were reported in the component tracking system.

79. Have inspections of AE piston skirts after operation been conducted?

A. (Johnson, Seaman, Swanger, Youngling) Yes.

Inspections using eddy-current and liquid dye penetrant were performed on a total of fourteen skirts including ten AE piston skirts from the Shoreham EDGs and four AE piston skirts at two non-nuclear installations.

80. What was the significance of these inspections?

A. (Harris, McCarthy) Each inspection added an additional piece of information that the AE piston skirts are successfully operating without developing cracks. These inspections are merely data points and are not used to prove, but do serve to confirm, the validity of the fatigue crack initiation or fracture mechanics analyses. Conclusions from these analyses stand on their own.

81. What is a liquid dye penetrant inspection?

A. (Johnson, Swanger) Liquid dye penetrant inspection is a method of nondestructive testing used to detect and indicate discontinuities that are open to the surface. It can be used for the inspection of most structural materials. Examination by liquid penetrant testing is accomplished in five basic steps:

1) Precleaning. Each item to be inspected must have contaminants, such as dirt and oil, removed from the surface to be inspected.

2) Applying the penetrant which is colored red for high visibility.

3) Removing the penetrant quickly after it is set. Penetrant will be left within the discontinuities for lack of time to escape.

4) Applying the developer. As the penetrant is pulled into the developer an indication appears.

5) Visual examination and interpretation. Qualified inspectors can tell whether an indication is from a crack, lamination, lack of fusion, porosity, etc.

This test method is sensitive to imperfections such as cracks, shrinkage cracks, surface porosity, cold shuts, grinding and heat-treat cracks, seams, forging laps and bursts, cold lap, lack of fusion, etc.

82. What is an eddy-current inspection?

A. (Johnson, Swanger) Eddy-current tests are high-resolution NDE procedures that were used on the AE piston to determine if a liquid dye penetrant indication corresponded to a significant size crack-like defect or not. FaAA used its Procedure NDE 11.5, Rev. 0 in its inspection of the EDG 102 pistons and NDE 11.5, Rev. 1 in its inspections of the EDG 101 and 103 pistons. Because of the purpose of eddy-current tests, its use was limited to portions of the skirt where liquid dye penetrant had revealed an indication that needed further

examination. In this case, a penetrant indication 1/32 inch or longer required eddy-current examination.

The eddy-current test itself involved scanning a coil over the test area and monitoring the electrical impedance of the coil. Material defects cause a change in the coil impedance which generates a signal. A signal generated from a crack or a simulated crack was used as the crack standard. When the material at issue was scanned, all eddy-current crack indications exceeding a specified fraction of the crack standard were recorded.

83. Why it is reasonable to apply the 1/32 inch length criteria to determine what indications shown from the liquid dye penetrant will be subjected to further analysis?

A. (Harris, Johnson, Swanger) The presence of small imperfections in any cast material is normal. Contrary to the County's assertion, indications smaller than 1/32 inch in length cannot contribute significantly to the possibility of crack initiation and propagation. This is supported by the results of the fracture mechanics analysis of crack growth, which predicted that cracks less than 1/2 inch deep would not grow. Cracks of 1/2 inch depth would be expected to be at least 1 inch in surface length.

84. Please describe why it is reasonable to record signals exceeding a certain fraction of the signal from the crack standard.

A. (Harris, Johnson) For instance, the crack standard

for piston skirt inspection per NDE 11.5, Rev. 1 is 1/16 inch in length by 1/32 inch in depth. At the rejection level of fifty percent of the signal from the standard specified in Rev. 1, subcritical defects (1/2 inch deep by 1 inch long) are easily detected. The Rev. 0 inspection was approximately a factor of two more sensitive than the Rev. 1 inspections.

85. Please describe the inspections of the ten AE piston skirts from Shoreham.

A. (Johnson, Seaman, Youngling) After 300 hours total operation, including 100 hours at 100% load, liquid dye penetrant and eddy-current inspections were conducted of the stud boss region of AE piston skirts from EDGs 101, 102 and 103. LILCO and Stone and Webster performed the liquid dye penetrant test at the stud boss attachment areas for all three engines utilizing approved LILCO procedures. The results of those inspections are included in Exhibit P-26. FaAA conducted the eddy-current inspections which were observed by representatives from LILCO. The results of these inspections for all three engines and the FaAA eddy-current procedures are included in Exhibit P-27. The inspections revealed no relevant indications.

86. Describe the characterization of a nonrelevant indication.

A. (Harris, Johnson, McCarthy) It is important to remember that some surface liquid dye penetrant indications are



common in all iron castings. They can result from superficial features such as tool marks, pits, inclusions and other irregularities in the surface of the casting. These indications do not have any effect on fatigue behavior of an AE piston at Shoreham due to their bluntness and/or small depth.

87. Why are inspection results after 100 hours at 100% load meaningful in assessing the reliability of the AE piston skirts?

A. (Harris, McCarthy, Swanger) Each AE piston skirt incorporates 8 individual highly-stressed fillets in the intersections of the four stud attachment bosses with the wrist pin bosses. There are, as in all cast articles, minor variations in material composition, dimensions and physical properties as well as minor differences in stresses that result from the expected variations in temperature and pressure in the cylinders, stud preload and machining tolerances. Thus the 192 highly-stressed areas (24 piston skirts x 8 boss fillets) in the 3 Shoreham EDGs represent a population of similar fatigue samples with a distribution of endurance limits, i.e., stress levels below which the samples exhibit infinite fatigue lifetime. Conventionally, the endurance limit is accepted to be the stress level corresponding to 10 million stress reversals. Information contained in the Iron Castings Handbook, by Walton and Olpar, 1981, (p. 341) (Exhibit P-29) shows that the cyclic stress for cracking in 10 million cycles is 93% of the cyclic

stress for cracking in 1.35 million cycles. Scatter of 7% on stress is commonly observed in fatigue data. Therefore, it is likely that cracking indications would be observed in the population of inspected stud bosses if they had been operated for 1.35 million cycles at stresses above the endurance limit.

88. Please describe the inspections performed on the AE pistons in non-nuclear operation.

A. (Johnson) FaAA inspected two AE skirts from a RV-16-4 engine at Kodiak Electric Association in Alaska. This engine had experienced over 6,000 hours of service at an average peak firing pressure reported by the utility to be approximately 1,200 psi. FaAA also inspected two AE piston skirts from the TDI R-5 prototype engine after approximately 622 hours of operation at 2,000 psi. Neither the Kodiak nor the R-5 prototype engine inspections revealed any relevant indications. These inspection reports are included in Exhibit P-29.

89. Are the AE pistons in the TDI R-5 engine significantly different from those in the EDG's at Shoreham?

A. (Harris, Johnson, Swanger) No. There are variations reflecting design evolution between the R-5 AE piston skirts and the Shoreham piston skirts. These variations involve an area that is irrelevant to the analysis of crack initiation in the stud boss region. The County specifically stressed the fact that the R-5 engine has an operating speed of 514 RPM while the operating speed of the Shoreham EDG's is 450 RPM.

The increased inertia associated with the increased RPM reduces the effective peak firing pressure. For the R-5 engine, the effective peak firing pressure at 450 RPM would be 1,957 psig as opposed to its actual value of 1,944 psig at 514 RPM. The effective peak firing pressure on the R-5 engine at 450 RPM is still approximately 20% higher than the Shoreham peak firing pressure. The County ignored the more important point, i.e., the fact that the R-5 has operated successfully for over 622 hours at 2,000 psig. The fact that an AE piston skirt in the R-5, which represents an earlier stage in the evolution of the design, withstood that operation without relevant indications is the more persuasive point about the integrity of the AE piston skirts at Shoreham.

90. Please describe why the Kodiak operating experience is meaningful in evaluating the suitability of the AE piston skirt for safe operation at Shoreham.

A. (Harris, McCarthy) As mentioned above, the Kodiak experience with AE piston skirts involved 6,000 hours at a reported average peak firing pressure of 1,200 psi. In spite of the lower peak firing pressure, this experience is relevant because it involves a large number of stress cycles (about 80 million). The fact that no indications of excessive wear or fatigue cracking were observed after so many cycles provides additional evidence of the integrity of the AE piston skirt.

V. Side Thrust Load  
Is Not A Design Or Operation  
Problem With The AE Pistons At Shoreham.

A. Shoreham AE Piston Skirt

91. Please describe side thrust load.

A. (Pischinger, Swanger) All piston engines generate a side thrust load between the piston and the cylinder as the result of the balance of forces between the piston, the connecting rod and the cylinder wall. During the power stroke, as the piston descends in the cylinder from the top dead center position, the motion of the connecting rod causes it to assume an increasing angle greater than zero degrees with respect to the axis of the cylinder. The longitudinal force in the connecting rod is resolved into axial and transverse components in the piston. The axial component is generated by the net pressure force acting on the piston. The transverse component is the geometric result and is manifested as a force between the piston and the cylinder wall. This latter force, which varies with cylinder gas pressure, speed of the engine and the crankshaft angle, is the piston side thrust.

92. Is side thrust load a significant consideration in the design of a diesel engine?

A. (Pischinger) No. In current diesel engine design, side thrust, much less the excessive side thrust alleged by the County, is simply not a consideration. Proper lubrication

incorporated in the piston design makes side thrust load a nonissue. With adequate lubrication, the consequences of side thrust load will never reach the level described by the County. Pistons, including the AE pistons, are designed to lubricate the skirt to reduce friction. Exhibit P-30 details the lubrication system on the Shoreham EDGs.

93. Will side thrust load dramatically increase the temperature on one side of the piston?

A. (Pischinger, Swanger) With an adequately lubricated piston, side thrust will not create a dramatic temperature differential. In order to create the temperature effect described by the County, the piston and skirt would have to come into unlubricated contact. Lubrication minimizes the piston skirt/cylinder contact and facilitates heat flow from the piston to the liner.

94. Has operational experience shown that side thrust load is not a problem with pistons in nuclear service?

A. (Harris, McCarthy, Seaman, Swanger) Yes. The component tracking system does not indicate adverse consequences from side thrust on any pistons in nuclear service. Furthermore, the component tracking system does not indicate any failure on R-4 engines in either nuclear or non-nuclear service. This R-4 experience is helpful because the factors influencing side thrust load, crank angle, reciprocating piston weight and connecting rods, are the same on all R-4 engines and are not affected by individual piston designs.

95. Why do you disagree with the County's dramatic conclusions regarding the effect of piston side thrust load?

A. (Pischinger, Swanger) As described above, current design experience has indicated that side thrust is not a problem. The County characterizes the side thrust as excessive based on an outdated standard. Most modern engines would exceed this outdated standard. It has no meaning to current engine design. The County's standard is drawn from Diesel Engine Design by T.D. Walshaw, 1949 (County's testimony, p. 48, footnote 60). The dated value of this 35 year old source is exemplified by various information drawn from the reference. For example, for a roughly 17 inch bore four stroke diesel, a peak firing pressure of 700 psig (p. 80) and BMEP of 70 psig (p. 71) are given. The County's reference also states that two stroke diesels are "used universally for the higher powers, say above 3000 BHP per unit" (p. 47). These statements are at odds with more modern design practices and show the dated nature of the 85 psi limit on unital side thrust loads. Similar problems are found in the County's other reference on side thrust, Internal Combustion Engine by V. L. Maleev, 1945 (County's testimony, p. 49, footnote 61) when the reported BMEPs (pp. 352, 353, 355) and peak firing pressure (pp. 206, 207, 355) are compared with modern practice. Improved materials in more modern engines allow higher operating pressures to be attained. For instance, Maleev describes cast iron piston material with a

tensile strength of 20ksi - 30ksi (p. 499), whereas the nodular iron in TDI engines is approaching 100 ksi in tensile strength. The textual references noted from both references are included in Exhibit P-31.

In summary, the 35-40 year old material from which the County obtained its values of recommended side thrust does not reflect modern design practices. As noted above, design and operating experience indicates that side thrust load is simply not a consideration.

96. Is there any evidence of excessive side thrust on the AE piston in the EDG's at Shoreham?

A. (Seaman, Swanger) No. The County cited several reports by the DRQR of scuffing on the AE piston skirts. These reports, however, include not only a report of scuffing, in some cases, but a conclusion that it was acceptable or normal wear. Copies of the reports cited by the County are attached to this testimony as Exhibit P-32. Furthermore, as the County pointed out, DRQR personnel visually inspected the AE skirts at Shoreham and did not observe excessive side load wear.

97. On what basis did the County challenge the conclusion of the DRQR inspections?

A. (Seaman, Swanger) The County stated that during its June 1984 inspection the County's consultants noticed a "heavy wear pattern" on one AE skirt. The County also indicated it noticed that the tinplated area showed indications of "abraded

surfaces and evidence of debris that had been previously imbedded in the plating, but since removed." As will be discussed below, the purpose of the tinplating is to capture and absorb minute particulate material from the combustion chamber so that it will not harm the cylinder liner.

98. Why is the County's belief wrong that there may have been side thrust markings in some of the cylinder liners?

A. (Seaman, Youngling) The only reason the County offered in support of its belief is that its consultants "surmised" that deglazing observed was necessitated by the side thrust markings. The County went on to describe deglazing as "a maintenance operation in which the cylinder liner surface is honed." The County's June 1984 inspection was of EDG 103 during the block replacement. The cylinder liners had just been rehoned at TDI as a part of that engine rebuild. This is normal practice in an engine rebuild and has no relationship to the piston skirt performance prior to the rebuild. The rehoning certainly does not support a conclusion that there have been adverse consequences of side thrust on the AE piston skirt at Shoreham.

99. Was there any evidence of excessive side thrust in the AE skirts in the DSRV-16-4 engine at Kodiak Electric Association in Alaska?

A. (Joinson, Swanger) FaAA observed no evidence of excessive side thrust during the inspections of the Kodiak skirts after more than 6,000 hours of operation.



100. Would you anticipate that adverse effects of side thrust would evidence themselves on the Kodiak engine even at 1,200 psi?

A. (Harris, Swanger) According to the County's standard for acceptable unital side thrust, the Kodiak engine should have experienced excessive side thrust even at 1,200 psi. Assuming the County's calculation of the side thrust load at Shoreham is correct, the side thrust for Kodiak can be derived by multiplying the County's side thrust result times the ratio of the Kodiak and Shoreham peak firing pressures. As noted, Kodiak had not evidenced any symptoms of excessive side thrust.

101. Did inspections of the modified AF piston skirts removed from Shoreham after 600 - 800 hours of operation reveal any indication of excessive side thrust?

A. (Harris, Johnson, Swanger, Youngling) No. Both visual and nondestructive examination revealed no signs of the County's alleged excessive side thrust. The nondestructive evaluation (liquid dye penetrant and eddy current testing) showed that the cracks in the modified AF skirts were randomly distributed on all sides of the skirt in the boss area. The liquid dye penetrant test results are included in Exhibit P-33. If there had been excessive side thrust, the cracks would have shown some side to side variation indicating adverse effects of side thrust load. The same side loads were experienced on the AF piston skirts as the AE pistons skirts because the factors affecting side loading, i.e., firing pressure and the geometry

of the crank connecting rod and piston, are the same in both skirts.

102. Is the side thrust load on the Shoreham piston acceptable?

A. (Pischinger) Yes. Based upon the dimensions of the piston skirt, crank radius and the connecting rod length, I conclude that the Shoreham piston is an extremely low side-load piston. Moreover, based on current design practice, side thrust should not even be an issue in this proceeding.

B. FaAA Analysis

103. Did FaAA consider side thrust load in its analysis of the stresses on the AE piston skirt?

A. (Harris, McCarthy) No. As discussed above, cyclic stresses were the key factor FaAA considered in analyzing crack initiation in the AE piston skirts. The cyclic stresses are the differences in the minimum and maximum stresses. Pressure and stress have a linear relationship. Side thrust load is produced when the connecting rod angle varies from zero degrees. In this case, a portion of the load due to pressure on the piston is reacted through the wrist pin at an angle as contrasted to directly through the connecting rod to the crankshaft as would occur at top dead center. The pressure/crank angle diagram that FaAA developed (Exhibit P-5) shows that peak firing pressure during the power stroke occurs near the

position when the connecting rod is vertical and parallel to the cylinder axis, a position corresponding to top dead center. The minimum load (inertia) is exerted when the piston is at top dead center of the exhaust stroke, which also corresponds to a zero degree angle between the connecting rod and crankshaft.

104. Would side thrust load change the cyclic stress amplitude?

A. (Harris, McCarthy, Swanger) No, not significantly. The pressure/crank angle diagram shows that the pressure drops off rapidly as the piston moves away from top dead center. Therefore, the forces on the piston decrease rapidly away from top dead center, and consequently the stresses in the stud boss region decrease. The side thrust load is zero at top dead center, which is close to where the peak pressure loading occurs. By the time the crank angle has increased to the point where the side component of the load is appreciable, the pressure has decreased to the point where the total pressure load has greatly decreased.

105. Would the FaAA conclusions that cracks in the AE piston skirts at Shoreham may initiate, but would not grow under operating conditions, be changed if side thrust load were considered a significant contributor to cyclic stresses?

A. (Harris) No. In the unlikely event that side thrust loads were determined to be a significant contributor to cyclic stresses in the stud boss region, such increases would not alter the FaAA conclusions. This is borne out by calculations

made by FaAA on cracking of the AE skirt when subjected to peak firing pressure as large as 2,400 psig. These calculations, performed using the methodology described above, revealed that crack growth would not occur even at pressures of 2,200 psig. The maximum and minimum stresses and fracture mechanics analysis results from these calculations are shown on Exhibit P-34.

The small increases in estimates of cyclic stresses that may possibly occur if side thrust loads were included in the analysis would certainly be insufficient to increase the cyclic stresses to levels corresponding to 2,200 psig. Therefore, explicit consideration of side thrust loads would not alter our conclusions regarding the possibility of crack initiation but no growth of cracks in the AE piston skirt.

VI. The Tin Plating On The AE  
Pistons At Shoreham Will Not Lead To Failure

106. Please describe the purpose of the tin plating on the AE piston skirts.

A. (Pischinger, Swanger) Tin is a soft, low-friction material electroplated on piston skirts to facilitate a smoother break-in period for an engine. During break-in, piston rings and skirt surfaces are required to adapt themselves to new and non-broken-in cylinder liner and bore surfaces. Soft tin plating provides a low friction run-in surface similar to that provided by the overlay on the connecting rod bearing shells or on main bearing shells. In other words, the tin

plating provides a running-in surface between the new skirt and the new liner. In addition, due to its soft quality, the tin plating captures minute particulates created by the running-in process and absorbs these materials. This process, therefore, protects the honed cylinder liner. In summary, the purpose of the tin plating is to provide a smooth break-in period and to protect the cylinder liner and the piston skirt. Contrary to the County's allegation, the purpose of the tin plating on the skirt is not to offset the assumed bad effects of alleged excessive piston side thrust. In fact, the County's own reference, Internal Combustion Engines (p. 498), states that "cast iron pistons produce less cylinder liner wear than aluminum ones, especially if they are tin plated."

107. Does the experience collected in the component tracking system indicate that tin plating of piston skirts is not an operational problem?

A. (Seaman, Swanger) The component tracking system contained no evidence of any failures or adverse operational problems resulting from tin plating of piston skirts in nuclear or non-nuclear service. Furthermore, the County did not document any actual failures or operational problems caused by tin plating. The County was merely theorizing based on incorrect assumptions as to the purpose of tin plating.

108. The County alleged that the scoring it observed can result in gas blow-by and, therefore, perhaps eventual piston seizure. Has excessive gas blow-by ever been experienced in the EDGs at Shoreham?

A. (Seaman, Youngling) No. LILCO monitors crank case pressure which would increase if gas blow-by were experienced. If excessive blow-by were to occur, the pressure sensor would alarm and then trip the unit. Shoreham has never tripped due to excessive gas blow-by.

109. The County was also concerned about alleged problems that might occur from the electroplating process. Why is the County's concern about electroplating ill-founded?

A. (Pischinger, Swanger) The County stated its concern about failure because of embrittlement caused by hydrogen escaping into the metal during the electroplating. The County stated that hydrogen embrittlement has been responsible "for many dramatic failures of ferrous metals" and is a problem in "all plated metal components." This is incorrect. Hydrogen embrittlement is not a concern in relatively mild nodular cast iron which had relatively low ultimate tensile strengths as compared to steel. It is a consideration only in high strength steel with ultimate tensile strength in excess of 150,000 psi. The tensile strength values of the AE piston skirt measured by FaAA were 85,360 psi to 90,210 psi. Furthermore, any cathodically charged hydrogen in the piston would diffuse out of the iron matrix in less than 100 hours at the operating temperature of the AE piston at Shoreham.

110. The County seemed concerned about tin plating because of scoring it observed in several cylinders during the County's trips to Shoreham in 1983 and 1984. Was this scoring due to the tin plating?

A. (Seaman, Youngling) No. The County hypothesized, based on its 1983 observations, that the scoring was caused by an accumulation of imbedded material in the tin plated surface of the skirt. The accumulation of material, however, was not caused by the tin plating. In 1983, the Shoreham EDGs had Koppers piston rings which were allowing an excessive amount of carbon build-up on the cylinder liners. As the result of a recommendation of the DRQR program, those rings have been replaced, however, with Muskegon piston rings. The Phase II DRQR of the piston rings concluded the Muskegon rings were appropriate for the intended use at Shoreham and that minor scuffing score marks on the cylinder liners were within an acceptable range indicating acceptable performance. In addition to replacing the Koppers piston rings with Muskegon piston rings to assure freedom from unacceptable scuffing, LILCO has adopted the following practices:

1. Inspection of the cylinder liners at each fuel outage to evaluate liner wear and coat deposits.
2. Use of a high detergent oil.
3. Use of 135° fuel injection tips.

111. Who performed the review of the Muskegon piston rings.

A. (Pischinger, Seaman) FEV performed the Phase II review which included an evaluation of the service conditions versus the ring design specification and an analysis of the actual performance of the rings, pistons and liners.

112. How was this review performed?

A. (Pischinger, Seaman) FEV considered the results of quality revalidation inspections and numerous task evaluation reports. Furthermore, FEV performed detailed engineering inspections at Shoreham, and more general inspections at Catawba, the TDI Manufacturing Plant in Oakland, California and the Muskegon Piston Ring (MPR) Manufacturing Plant in Muskegon, Michigan.

113. Please describe the inspections performed of the Shoreham pistons, rings and liners.

A. (Pischinger, Seaman, Youngling) The Shoreham rings, pistons and liners were inspected following a 24-hour test run and a 7-day test run and after about 100 hours at greater than or equal to full load. In addition, the components on EDG 102 were reinspected following a 100 start test.

114. What were the results of the FEV evaluation of the service conditions against the ring design specifications?

A. (Pischinger) FEV concluded that the design specifications for the MPR piston rings used on the Shoreham engines are typical of industry practice and conservatively rated for



turbocharged and aftercooled medium speed diesel engines and are, therefore, appropriate for the intended use at Shoreham.

115. What were the results of the FEV inspection of the Shoreham pistons, rings and liners?

A. (Pischinger) Buildup of coke in the upper area of the liner and piston down to the second compression ring was noted. The coke buildup resulted in wear on the ring and the liner, and minor scuffing score marks were observed on them. Linear wear was also present, as well as some mirror-like bright areas on a high percentage of the cylinder liners. The magnitude and types of wear observed on the rings and liners, however, are within acceptable ranges, indicating acceptable performance.

116. Based upon the FEV review, do you conclude that the MPR piston rings are adequate for their intended function at Shoreham?

A. (Pischinger) Yes.

117. Does the tin plating in any way reflect a design deficiency?

A. (Pischinger, Swanger) No. The tin plating is an accepted mechanism to facilitate engine break-in and to protect the piston and cylinder liner from scoring from minute particulates escaping from the combustion chamber. There is simply no support for the allegation that tin plating has ever led to scoring, much less that it has caused excessive blow-by affecting the operation of the piston.

## VII. Conclusion

118. In light of the County's piston contentions, is it your conclusion that the AE piston skirts are safe and reliable for their intended service?

A. (Harris, McCarthy, Swanger) Yes. The analysis of AE piston skirts using the higher, more conservative stresses predicted that fatigue cracks could possibly initiate. The analysis by engineering fracture mechanics predicted that these cracks cannot grow in the Shoreham EDGs. These same design analysis procedures have been successfully applied in other industries, including highly sophisticated aircraft gas turbine engines, as well as to other critical components of nuclear power plants.

119. Is it unusual to operate structural components where the presence of fatigue cracks is assumed?

A. (Harris, McCarthy) It is now common to design and operate critical structural components such that the initial presence of crack-like defects is assumed and the growth of these defects in fatigue is calculated. The possibility of fatigue crack initiation in the stud attachment bosses of piston skirts poses no new or unusual problems when compared to common design practice in other industries, such as aerospace. For example, even the highly-stressed rotating parts of military aircraft gas turbine engines are designed assuming the presence of small cracks that can grow in fatigue. As noted above, the

United States Air Force has a formal procedure that expressly requires~~the~~ manufacturer to adopt this design approach. Many other structures - civil, mechanical, marine - are designed with the same philosophy. This philosophy merely reflects the fact that all materials and structures contain crack-like defects on some scale and that the primary objective of design analysis is therefore not to prevent "initiation" but to ensure that such cracks cannot grow to a significant size. It is important to appreciate the fact that all critical structural components in our common experience, such as aircraft, bridges, pipelines, tanks--even elevator cables--contain such defects. Modern design analysis is able to ensure the safe operation of all these structures through the application of engineering fracture mechanics. Contrary to the County's contention, the fracture mechanics analysis of AE piston skirts showed that they are safe and reliable.

Attachment 1

# Failure Analysis Associates

DAVID O. HARRIS

## Specialized Professional Competence

Fracture mechanics analysis and testing, fatigue and stress corrosion cracking in nuclear reactor piping, probabilistic fracture mechanics, stress analysis, acoustic emission testing and applications.

## Background and Professional Honors

Ph.D. (Applied Mechanics), Stanford University  
M.S. (Mechanical Engineering), University of Washington  
B.S. (Mechanical Engineering), University of Washington

Managing Engineer, Fracture Mechanics Group,  
Failure Analysis Associates

Division Manager,  
Science Applications, Inc.

Director of Research,  
Dunegan/Endevco

Mechanical Engineer,  
Lawrence Radiation Laboratory

Member, American Society of Mechanical Engineers

Member, American Society for Testing and Materials

Member, Acoustic Emission Working Group

Member, Tau Beta Pi, National Engineering Honorary Society

Member, Sigma Xi, Scientific Research Honorary Society

## Selected Publications

"Characterization of Acoustic Emission from Crack Growth in Steam Turbine Rotor Steels," to appear as Electric Power Research Institute Report, Palo Alto, California (with D. D. Dedhia and T. C. Mamaros).

"Stress Intensity Factors for Surface Cracks in Pipes: A Computer Code for Evaluation by Use of Influence Functions," Electric Power Research Institute Report NP-2425, Palo Alto, California (June 1982) (with D. D. Dedhia).

"Stress Corrosion Crack Growth in the Presence of Residual Stresses," *Residual Stress and Stress Relaxation*, 28th Sagamore Army Materials Research Conference, Plenum Press (1982).

"Probabilistic Analysis of the Influence of Vibratory Stresses on Piping Reliability," *Reliability and Safety of Pressure Components*, pp. 17-34, PVP—Vol. 62, American Society of Mechanical Engineers, New York (1982) (with E. Y. Lim).

"Fracture Mechanics Models Developed for Piping Reliability Assessment in Light Water Reactors," Report NUREG/CR-2301, U.S. Nuclear Regulatory Commission, Washington D.C. (1982) (with E. Y. Lim and D. D. Dedhia).

"Application of a Fracture Mechanics Model of Structural Reliability to the Effects of Seismic Events on Reactor Piping," *Progress in Nuclear Energy*, Vol. 10, (1) pp. 125-159 (with E. Y. Lim).

"The Influence of Nondestructive Inspection on the Reliability of Pressurized Components," *Fracture Tolerance Evaluation, Proceedings of U.S.-Japan Joint Symposium on Fracture Tolerance Evaluation*, Honolulu, Hawaii (December 1981) pp. 257-265.

"Applications of a Probabilistic Fracture Mechanics Model to the Influence of In-Service Inspection on Structural Reliability," to appear in the *Proceedings of ASTM Symposium on Probabilistic Methods for Design and Maintenance of Structures* (with E. Y. Lim).

"Approximate Influence Functions for Part-Circumferential Interior Surface Cracks in Pipes," presented at 14th National Symposium on Fracture Mechanics, Los Angeles, California (June 1981) (with E. Y. Lim and D. D. Dedhia).

Attachment 2

# Failure Analysis Associates

**DUANE P. JOHNSON**

## **Specialized Professional Competence**

Nondestructive evaluation and structural monitoring methods; production line inspection system development, field inspection and monitoring services, inspection and monitoring reliability analysis, nondestructive inspection procedure development and review, inspection level and interval optimization, eddy current instrument development, advanced electromagnetic sensor development, advanced signal processing, R&D on advanced nondestructive inspection and monitoring methods.

## **Background and Professional Honors**

B.S. (Electrical Engineering), University of Minnesota, with High Distinction

M.S. (Physics), University of Washington

Ph.D. (Physics), University of Washington

Manager, Nondestructive Evaluation and Monitoring,  
Failure Analysis Associates

President and Co-Founder,

Reluxtrol, Inc.

Supervisor, Nondestructive Inspection,

Pratt & Whitney Aircraft

Associate Professor of Physics,

American University, Cairo, Egypt

Member, American Society for Nondestructive Testing

Member, American Physical Society

Member, Institute of Electrical and Electronics Engineers

## **Selected Publications**

"Review of State of the Art Inspections of Steam Turbine Blades," EPRI Steam Turbine Blade Reliability Workshop (1982) (with E. K. Kietzman).

"Electromagnetic Testing of Ceramic Materials," EPRI Report (1981) (with L. Y. L. Shen).

"Controlled Reluctance Eddy Current Inspection of Steam Turbine Components," EPRI Workshop on NDE of Steam Turbine and Electrical Generator Components (1980) (with S. Sarian and E. K. Kietzman).

"Assessment of Current NDI Techniques for Determining the Type, Location and Extent of Fossil-Fired Boiler Tube Damage," EPRI Report (1980) (with E. R. Reinhart and S. Sarian).

"Production Line Nondestructive Evaluation of Continuous Formed Metal Parts Using Controlled Reluctance Eddy Current Probes," ASNT Spring Conference (1979) (with S. Sarian).

"Reliability of Flaw Detection by Nondestructive Inspection," Metals Handbook, Vol. 11 (with several authors).

"Economics and Managerial Aspects of Nondestructive Testing Evaluation and Inspection in Aerospace Manufacture," Appendix C, National Academy of Science Publication NRAB-337 (with T. L. Toomay).

"Determination of Nondestructive Inspection Reliability Using Field or Production Data," Materials Evaluation, Vol. 36 (1978).

"Estimation of Defect Detection Probability Using ASME Section XI UT Tests on Thick Section Steel Weldments," ASM/ASTM/ASNT/ANS International Conference NDE in Nuclear Industry (1978) (with T. L. Toomay and C. S. Davis).

"A Workable Approach for Extending the Life of Turbine Rotors," Fatigue Life Technology, ASME Symposium (1977) (with P. M. Besuner).

"Optimizing NDI Sensitivity," Metals Progress, Vol. 112 (1977).

"Inspection Uncertainty: The Key Element in Nondestructive Inspection," Materials Evaluation, Vol. 39 (1976).

Attachment 3



# Failure Analysis Associates

ROGER L. McCARTHY

## Specialized Professional Competence

Mechanical, machine, and mechanism design. Dynamic mechanical system design, analysis modeling, control (including dedicated computer control), and failure analysis. Custom product design. Human factors engineering and testing; design analysis of man/machine interface. Design analysis research. Risk analysis; quantification of hazards posed by design and construction of mechanical components, products, or system failure in the industrial and transportation environments. Design analysis through large scale accident data analysis and evaluation, including vehicle design and collision performance. Evaluation of mechanical/electrical design-related explosion hazard; heat transfer design. Reinforced polymer composite design analysis, including tires. Patent analysis relating to mechanical design.

## Background and Professional Honors

A.B. (Philosophy), University of Michigan, with High Distinction  
B.S.E. (Mechanical Engineering), University of Michigan, summa cum laude  
S.M. (Mechanical Engineering), Massachusetts Institute of Technology  
Mech.E. (Mechanical Engineering), Massachusetts Institute of Technology  
Ph.D. (Mechanical Engineering), Massachusetts Institute of Technology

President,

Failure Analysis Associates

Principal Design Engineer

Failure Analysis Associates

Program Manager, Special Machinery Group,

Foster-Miller Associates, Inc.

Project Engineer, Machine Design and Development Engineering, Engineering Development Division,  
Proctor & Gamble Company, Inc.

Registered Professional Mechanical Engineer, California, #M20040

Registered Professional Mechanical Engineer, Arizona, #13684

Phi Beta Kappa, Sigma Xi, James B. Angell Scholar

National Science Foundation Fellow

Outstanding Undergraduate in Mechanical Engineering, University of Michigan

Member, American Society of Metals, American Society of Mechanical Engineers, Society of  
Automotive Engineers, American Welding Society, National Safety Council, American Society  
for Testing and Materials

Member, American Society of Safety Engineers

Member, Human Factors Society, System Safety Society, National Society of Professional Engineers

Member, American Society of Heating, Refrigeration, and Air-Conditioning Engineers

Member, National Fire Prevention Association

## Selected Publications

"School Bus Wheel Rim Safety — Multipiece vs. Single Piece," National School Bus Report, Springfield,  
Virginia (December 1982) (with G. E. McCarthy).

"Warnings on Consumer Products: Objective Criteria For Their Use," 26th Annual Meeting of the Human  
Factors Society, Seattle, Washington (October 25-29, 1982) (with J. N. Robinson, J. P. Finnegan  
and R. K. Taylor).

"Average Operator Inaction Characteristics with Lever Controls — Study of the Column Mounted  
Gear Selector Lever," 26th Annual Meeting of the Human Factors Society, Seattle, Washington  
(October 25-29, 1982) (with J. P. Finnegan, G. F. Fowler and S. B. Brown).

"Catastrophic Events: Actual Risk versus Societal Impact," 1982 Proceedings, Annual Reliability and  
Maintainability Symposium, Los Angeles, California (January 26-28, 1982) (with J. P. Finnegan  
and R. K. Taylor).

- "Product Recall Decision Making: Valid Product Safety Indicators," Proceedings of the Fourth International System Safety Conference, San Francisco, California (July 9-13, 1979). Published by Professional Engineer Magazine (March 1981).
- "Large Vehicle Wheel Servicing: Reduction of Risk Through Implementation of An OSHA Standard Governing Multipiece and Single Piece Rims: Phase IV," Published by the National Wheel and Rim Association (March 1981) (with J. P. Finnegan).
- "Program to Improve Down Hole Drilling Motors: Task 2, Lip Seal Design," Failure Analysis Associates Report FA-81-7-6 to Sandia National Laboratories (October 1980) (with V. Pedotto).
- "A Safety and Fracture Mechanics Analysis of the Pneumatic Tire: A Perspective on the Firestone 500 Radial Tire," Presented at the International Conference on Reliability, Stress Analysis and Failure Prevention, of the American Society of Mechanical Engineers, San Francisco, California (August 18-21, 1980) (with W. G. Knauss).
- "Multipiece and Single Piece Rims: The Risk Associated with Their Unique Design Characteristics: Phase III," Published by the National Wheel and Rim Association (June 1980) (with J. P. Finnegan).
- "An Engineering Safety Analysis of the Steel Belted Radial Tire," Society of Automotive Engineers Paper #800840 (June 9-13, 1980).
- "A Simple Technique to Improve the Allocation of Safety Inspection Resources," Proceedings of the Fourth International System Safety Conference, San Francisco, California (July 9-13, 1979) (with P. M. Besuner).
- "An Engineering Analysis of the Risk Associated with Multipiece Wheels," National Highway Traffic Safety Administration, ANPR Docket No. 71-19, Number 7 (June 1979) (with J. P. Finnegan).
- "Planar Thermic Elements for Thermal Control Systems," Journal of Dynamic Systems, Measurement and Control, Vol. 99, Series G, No. 1 (March 1977) (with B. S. Buckley).

Attachment 4

## CURRICULUM VITAE

Professor Dr. techn. Franz F. Pischinger

Date of Birth: 18.07.1930, Waidhofen/Thaya, Austria

1948 to 1952 studies and graduation in mechanical engineering at Graz Technical University. From 1953 to 1958 (1954 doctors degree) technical assistant at Graz Technical University. Then Head of Research Department of AVL (Institute for Internal Combustion Engines, Professor List, Graz). 1958 habilitation. 1962 to 1970 leading positions in research and development at Klöckner-Humboldt-Deutz AG, Köln (last position: Director of Research and Development Department). Since 1970 Director of the Institute for Applied Thermodynamics at Aachen Technical University. Supervising Research and Teaching in the field of internal combustion engines and thermodynamics of combustion. Also (1978) president of the FEV Forschungsgesellschaft für Energietechnik und Verbrennungsmotoren mbH, Anchen.

Attachment 5

CRAIG K. SEAMAN  
358 CLUBHOUSE CT.  
CORAM, N.Y. 11727  
(516) 929-6050 BUSINESS  
(516) 698-0503 HOME

## SUMMARY

An aggressive, results-oriented engineer with extensive background in engineering supervision, mechanical and structural engineering, and construction. Most recent assignment requires management of 150 engineering, professional and technical personnel assigned to resolve design and quality concerns with a nuclear standby diesel generator manufacturer.

LONG ISLAND LIGHTING COMPANY  
SHOREHAM NUCLEAR POWER STATION  
(1979 - PRESENT)

---

## AS PROGRAM MANAGER

- . Established a program to provide an in-depth design review and quality revalidation of Transamerica Delaval diesel generators to qualify these units for nuclear emergency standby power. This program was required as a result of numerous engine failures and negative NRC audits of the vendor.
- . Responsible for presentations to utility executives to enlist participation in the program - results: 11 of 11 utilities with operating licenses or active construction programs are contributing and participating.
- . Managed the program utilizing a team concept involving over 150 personnel including engineers, scientists, diesel consultants, quality control inspectors and clerical support.

## AS SENIOR PROJECT ENGINEER

- . Managed an on-time and budget Pre-Service Inspection Program including providing expert testimony for the Atomic Safety and Licensing Board.
- . Responsible for coordination of utility/architect engineer response to an Independent Design Review resulting in a clean bill of health for Shoreham.
- . Supervised an engineering section responsible for all mechanical engineering, power systems, structural engineering, piping (including ASME) and pipe supports engineering.

## AS ASSISTANT PROJECT ENGINEER

- . Responsible for plant betterment program - one example is a radwaste system modification to back flushable etched disc filters which resulted in an over \$200,000 savings.
- . Assisted in development of the first domestic Induction Heating Stress Improvement Program for mitigation of stress corrosion cracking in Reactor Recirc System piping including coordination with NRC, G.E. and international firms.
- . Engineering responsibilities included NSSS systems, radwaste systems, ASME piping and supports, and structural disciplines.

DANIEL INTERNATIONAL CORPORATION  
ENRICO FERMI UNIT II  
(1978 - 1979)

AS PROJECT ENGINEER

- . Assigned to the Walbridge Aldinger Company (WACo) to establish the firm's ability to perform piping and mechanical installations. As a direct result, the WACo contract was increased 100% to \$40,000,000.
- . Supervised an engineering office responsible for ANSI B31.1 piping, fire protection piping, the biological shield wall and temporary facilities.

AS CONSTRUCTION ENGINEER

- . Assigned to a task force established to review three quality assurance manuals and 40 construction procedures for effectiveness and efficiency - this effort resulted in a 20% increase in productivity in the field.
- . Responsible for drywell piping including planning, engineering, materials procurement, and management of offsite programs in Michigan and California.

LONG ISLAND LIGHTING COMPANY  
SHOREHAM NUCLEAR POWER STATION  
(1975 - 1978)

AS CONSTRUCTION SUPERVISOR

- . Responsible for the first on-time completion of a mechanical system at Shoreham - the Reactor Recirculation System in the Primary Containment.
- . Established a coordinated construction team for piping and mechanical equipment installation in the Primary Containment including - contractor supervision, labor, quality control, cost engineering and scheduling.
- . Assigned to a task force established to evaluate the construction program - the result was a major construction reorganization with significant improvements in progress, scheduling and cost control.

AS CONSTRUCTION COORDINATOR

- . Provided a recommendation to purchase previously rented heavy construction equipment which resulted in a savings of over \$500,000.
- . Monitored civil/structural construction and field engineering activities including detailed reporting to management.

EDUCATION

Cornell University	B.S. Engineering
Brooklyn Polytechnic	18 Credits toward M.S. in Nuclear Engineering

PERSONAL

Age - 31      Height - 5'9"      Weight - 160  
Married - 1 Child      Health - Excellent

Attachment 6



# Failure Analysis Associates

**LEE A. SWANGER**

## **Specialized Professional Competence**

Failure analysis of materials; metallurgical engineering, physical and mechanical metallurgy, and thermodynamics; foundry process development including ferrous and non-ferrous castings; powder metallurgy and powder rolling; electrochemistry, including electroplating and corrosion; materials testing, fatigue, and fracture; metal matrix and polymer matrix composites; tribology, friction, wear, and lubrication; internal combustion engine and compressor component design and testing; sleeve bearing design, manufacture, and failure analysis.

## **Background and Professional Honors**

Ph.D. (Materials Science and Engineering), Stanford University, with Distinction

M.B.A. (Marketing/Finance), Cleveland State University

M.S. (Materials Science and Engineering), Stanford University

B.S. (Metallurgy), Case Institute of Technology, with Highest Honors

Managing Engineer,

Failure Analysis Associates

Director, Research and Development,

Imperial Clevite Inc.

Associate Director, Product Development,

Gould Inc., Engine Parts Division

Manager, Tribology and Bearing Research,

Gould Laboratories, Materials Research

Associate Senior Research Metallurgist,

General Motors Research Laboratories

Lecturer, Metallurgical Engineering,

Cleveland State University

Visiting Research Associate, Metallurgical Engineering,

Ohio State University

Registered Professional Engineer, State of Ohio, #44024

Member, Tau Beta Pi, Engineering Honorary Fraternity

Member, Sigma Xi, Scientific Research Honorary Fraternity

Member, Beta Gamma Sigma, Graduate Business Honorary Fraternity

National Merit Foundation Scholarship

Xerox Corporation Fellowship

IBM Corporation Fellowship

Hertz Foundation Fellowship

Member, American Society for Metals

Member, Society of Automotive Engineers

Interviewer, Hertz Foundation Fellowship Project

## **Selected Publications**

U.S. Patent No. 4,333,215: "Bearing Material and Method of Making," issued June 8, 1982.

"Compacted Graphic Cast Iron Components for Improved Thermal Fatigue Resistance," Imperial Clevite Inc., Internal Report (January 1982).

"Marketing Strategies to Achieve Cash Flow Objectives," M.B.A. thesis, Cleveland State University (June 1982).

"Squeeze-Cast Pistons for Heavy-Duty Applications," Gould Inc., Internal Report (February 1981).

"Evaluation of Graphite-Epoxy and Graphite-Babbitt Composite Sleeve Bearings," Gould Laboratories, Phase Report (October 1977).

"Environmentally Induced Blistering of Aluminum P/M Components," Gould Laboratories, Project Completion Report (December 1976).

Attachment 7

Edward J. Youngling  
Manager, Nuclear Engineering Department

Assigned as Manager, Nuclear Engineering Department in May 1984. Report to the Vice President, Nuclear. Responsible for the overall operation of the Nuclear Engineering Department. The Nuclear Engineering Department is charged with providing the technical direction for engineering, fuel management, and radiation protection for the purpose of maintaining the design basis of the Shoreham Nuclear Power Station.

Responsible for the organizational development of the Nuclear Engineering Department and the definition of functions and responsibilities of the Nuclear Systems Engineering, Nuclear Fuel, Nuclear Project Engineering, Engineering Assurance and Radiation Protection Divisions.

Provide timely technical support to Shoreham plant operating staff for routine and abnormal operations in areas of nuclear engineering, core analysis, radiation protection, health physics, chemistry and radiochemistry. Administer programs and approve procedures to provide engineering and engineering management for plant modifications and engineering studies. Establish reliability and risk assessment capability aimed at improving plant safety and availability. Provide engineering support to Shoreham in the disciplines of thermal-hydraulics, heat transfer, stress analysis, systems engineering, instrumentation and controls, materials engineering, nuclear fuel design, core physics, safety and reliability analysis, risk assessment, radiation protection, shielding, health physics, radiation chemistry, non-destructive examination, corrosion analysis, and nuclear waste technology. Direct engineering work to the Office of Engineering on matters encompassing the disciplines of electrical, civil, power and environmental engineering for projects related to Shoreham. Direct activities related to nuclear fuel cycle management and establish nuclear material accountability. Establish core analysis systems to provide core follow support and advice on control rod withdrawal patterns. Provide technical direction for the Company's Radiological Environmental Monitoring Program. Provide radiation protection engineering and health physics technology assessments for incorporation in the Company's ALARA radiation dose reduction program. Responsible for the Company's ALARA radiation dose reduction program. Participate with Nuclear Operations Support and Plant Operating Staff in the development and implementation of the Corporate Licensing Policy.

Prepare and approve all budgets related to departmental activities necessary to comply with Corporate requirements. Prepare testimony and participate in appearances before federal, state and local hearing boards as required (PSC Prudency, PSC Rate Case, NRC Hearings, etc.). Administer R&D efforts within the Department in support of the Corporate R&D program.

Edward J. Youngling

Responsible for the finalization of the Shoreham Delaval Diesel Generator Design Review/Quality Revalidation Program.

Graduated from Lehigh University in 1966 with a Bachelor of Science Degree in Mechanical Engineering. From June 1966 to March 1968 attended Union College and achieved credits towards a Masters of Science Degree in Nuclear Engineering. Successfully completed the following training courses:

- "Introduction to Nuclear Power" by NUS Corp., July 1970
- "Boiler Control Fundamentals" by General Electric Co., January 1972
- "Fundamentals of BWR Operation" by General Electric Co. at the GE Dresden Simulator, August 1972
- "Process Computer Concepts and Practices" by General Electric Co., February 1973
- "Shoreham Research Reactor Training Program" at Brookhaven National Laboratory Medical Research Reactor (NRC SROC License candidate research reactor training requirement), May 1975
- "Planning for Nuclear Emergencies" by Harvard School of Public Health, May 1976
- "Interagency Course in Radiological Emergency Response Planning in Support of Fixed Nuclear Facilities" by Nuclear Regulatory Commission, September 1978
- "Customer Engineer Training Program in the Methods Used to conduct Maximum Turbine Capacity Tests and Analyze Results to Detect and Correct Cycle Losses" by the General Electric Co., Large Steam Turbine Division, September 1979
- "Shoreham Nuclear Power Station On-Site Training Program" (NRC SROC license candidate plant systems training requirement), January - April 1979
- "LILCO Advanced Supervisory Workshop", April 1979
- "Assertiveness Training Workshop", November 1980
- "LILCO Management Workshop", December 1980
- "Shoreham General Employee Training", 1983

Achieved a Senior Operator Certification from the General Electric Company on the Duane Arnold Energy Center Boiling Water Reactor.

March 1981 - May 1984

Assigned as Startup Manager in March 1981. Responsible for the Preoperational test activities for the Shoreham Nuclear Power Station. Report to the Vice President-Nuclear. Responsible for coordinating all Checkout and Initial Operations and Preoperational Testing. Set initial construction priorities by system/subsystem and monitor construction progress as it relates to the startup schedule. Had the authority to modify construction schedule as conditions demand. Chaired construction release meetings at which status of construction, as it relates to systems scheduled to be released, was discussed. Member of the Joint Test Group. Ensured that the established procedures of documentation control were followed. Responsible for the review, monitoring, supervision and approval

Edward J. Youngling

of Checkout and Initial Operations Tests, Preoperational Tests, and Acceptance Tests, review of all test results summaries and recommend acceptance, rejection or modification by the JTG according to results. Responsible for the production of all the software required for testing of Shoreham. Certified Level III per ANSI N45.2.6 - 1978.

In August 1983 named as Manager for the Shoreham Delaval Emergency Diesel Generator Crankshaft Failure Recovery Program. Responsible for coordinating the failure analysis, rebuilding, retesting and requalification of the three diesel generator units.

Prepared testimony, was deposed and testified before the Atomic Safety and Licensing Board regarding Shoreham contentions dealing with quality assurance, startup testing and emergency diesel generators. Prepared testimony and testified before the New York State Public Service Commission. Responsible for direct interface with NRC Resident, Regional and Staff personnel for matters related to the preoperational test program and emergency diesel generators recovery effort.

May 1979 - March 1981

Assigned as Nuclear Services Supervisor in May 1979, reporting to the Manager, Nuclear Operations Support Division. Responsible for the management and coordination of those support services required by LILCO Nuclear Power Stations. These support services included coordination of major station modifications, performance of operational design reviews, coordinating the resources of other LILCO Departments and outside consultants to achieve a desired result assigned to the Division, coordinating long-range planning activities associated with plant maintenance, fuel cycle strategy and budget and cost control, monitoring overall plant and individual equipment performance, maintaining a current knowledge of federal regulations, industry codes and standards, and changes thereto applicable to the facility.

Participated on the LILCO Corporate Task Forces assessing Shoreham design and operations, corporate communications, crisis management and overall company emergency preparedness following the Three Mile Island Unit 2 accident. Chairman of the Shoreham Review Task Group, responsible for developing action plans for implementing post TMI recommendations. Responsible for the Shoreham Control Room human factors design review.

Developed the corporate policy manual defining interdepartmental responsibilities for the LILCO Nuclear Program.

Edward J. Youngling

February 1975 - May 1979

Assigned as Chief Technical Engineer of the Shoreham Nuclear Power Station - Unit 1 in January 1975. Responsible for the activities of the Instrumentation and Control, Health Physics, Radiochemistry and Reactor Engineering Sections of the plant staff, including the development of administrative and technical programs and procedures to meet regulatory, company and industry requirements; and the training of professional personnel and technicians to satisfy qualification standards. Served on the plant Review of Operations Committee (ROC) and when designated acted as Chairman of the ROC in the Plant Manager's absence. Served as a member of the plant Licensed Source User's Committee as stipulated in NRC Nuclear Material License No. 31-17432-01, February 1977.

August 1974 - January 1975

Reassigned to the plant staff as the Instrumentation and Control Engineer, then Acting Chief Engineer-Technical. Responsible for manpower planning and the development of the technical training programs for subordinate personnel. Participated in generating portions of the Shoreham Safety Analysis Report, and in the review and approval of plant operating procedures, lesson plans and system descriptions.

July 1973 - July 1974

Named the Instrumentation and Control Engineer for Shoreham Nuclear Power Station and assigned to the General Electric Company Startup, Test and Operations (STO) organization at the Duane Arnold Energy Center in Cedar Rapids, Iowa. Participated in the preoperational test program in the areas of in-core nuclear process radiation and reactor vessel (pressure, level and temperature) instrumentation. Acted as G.E. shift engineer during fuel loading operations and as assistant to G.E. shift engineer during startup testing and power ascension program. Participated in the G.E. shift engineer training program and sat for the G.E. Certification Examination for DAEC.

August 1972 - June 1973

Reassigned to Shoreham Nuclear Power Station Project as the Assistant Project Engineer, then Project Engineer. Responsible for overall plant design control. Coordinated design effort between LILCO, Stone and Webster Engineering Corporation, General Electric Co. Nuclear Energy Division, various major equipment suppliers and regulatory agencies.

November 1971 - July 1972

Reassigned to the Northport Power Station to participate in the startup of Northport Unit No. 3. Directly responsible for the startup of the boiler for this 380MW unit including the fuel safety system, the combustion and

Edward J. Youngling

feedwater control systems and associated mechanical equipment. Assumed overall plant shift operations responsibility during the latter stages of startup. Was an instructor in the Unit No. 3 systems training program given to plant supervisors, operators, technicians, and mechanics.

November 1969 - October 1971

Assigned to the Shoreham Nuclear Power Station Project in the Nuclear Engineering Department. Participated in the engineering review of the Shoreham plant design in the following areas: plant equipment layout, equipment specifications, equipment selection, main control board design, plant operations logic, plant instrumentation, plant computers. Review included contacts with the A-E, Stone and Webster, NSSS supplier, General Electric Company, various vendors and visits to several nuclear stations.

April 1968 - October 1969

Employed by the Long Island Lighting Company and assigned to the Northport Power Station. During the period, assisted in the startup of Northport Unit 2, assisted in the station maintenance section supervising route and shutdown maintenance activities and acted as the station Results Engineer responsible for the repair and calibration of the station instrument and control systems and for monitoring station performance.

June 1966 - March 1968

Employed by the General Electric Company at the Knolls Atomic Power Laboratory. Stationed at the West Milton Site as a Mechanical Test Engineer on the S3G Prototype "USS Triton" submarine. While at the S3G plant my responsibilities were to prepare procedures for tests and operations which were not in accordance with normal plant operations; supervise the actual tests, analyze the results and issue reports to the AEC. The following specific activities were engaged in: completed selected sessions of the Engineering Officer of the Watch Training Course, participated in numerous plant tests including routing low power physics testing including directing reactor control rod movements through Navy reactor operators, maneuvering transients, main coolant pump tests, power runs, various engine room tests and ultrasonic testing to trend pipeline degradation. Participated in the Advanced Reactor Control Program as Lead Shift Test Engineer, including completion of required training program, and performing preoperational tests and integrated plant acceptance testing.

Member - American Nuclear Society. Held a Guest Associate Engineer appointment in the Reactor Division at Brookhaven National Laboratory. Member - Pi Tau Sigma. Hold an Engineer in Training Certificate - State of Pennsylvania (State Registration Board for Professional Engineers).

UNITED STATES OF AMERICA  
NUCLEAR REGULATORY COMMISSION

Before the Atomic Safety and Licensing Board

DOCKETED  
USNRC

'84 AUG 15 9:57

OFFICE OF SECRETARY  
DOCKETING & SERVICE  
BRANCH

In the Matter of	)	
	)	
LONG ISLAND LIGHTING COMPANY	)	Docket No. 50-322 (OL)
	)	
(Shoreham Nuclear Power Station,	)	
Unit 1)	)	

TESTIMONY OF DAVID O. HARRIS, DUANE P. JOHNSON,  
ROGER L. McCARTHY, FRANZ F. PISCHINGER,  
CRAIG K. SEAMAN, LEE A. SWANGER AND  
EDWARD J. YOUNGLING ON BEHALF OF LONG ISLAND LIGHTING  
COMPANY ON SUFFOLK COUNTY CONTENTION REGARDING  
AE PISTON SKIRTS ON DIESEL GENERATORS AT SHOREHAM

Exhibits 1 through 34

Volume 2 of 2



LILCO, August 14, 1984

UNITED STATES OF AMERICA  
NUCLEAR REGULATORY COMMISSION

Before the Atomic Safety and Licensing Board

SECRET  
USNRC

'84 AGO 15

In the Matter of )  
 )  
LONG ISLAND LIGHTING COMPANY )  
 )  
(Shoreham Nuclear Power )  
Station, Unit 1) )

Docket No. 50-322 (OL)


AE PISTON SKIRT EXHIBITS

TESTIMONY OF DAVID O. HARRIS, DUANE P. JOHNSON,  
ROGER L. McCARTHY, FRANZ F. PISCHINGER,  
CRAIG K. SEAMAN, LEE A. SWANGER AND  
EDWARD J. YOUNGLING ON BEHALF OF LONG ISLAND LIGHTING  
COMPANY ON SUFFOLK COUNTY CONTENTION REGARDING  
AE PISTON SKIRTS ON DIESEL GENERATORS AT SHOREHAM


- P-1 Photograph of piston skirt with mounted crown and rings
- P-2 Photograph of a piston from a Shoreham EDG showing skirt and crown
- P-3 Cross section of crown and skirt indicating the two areas of load transfer from the crown to the skirt
- P-4 Piston reassembly guidelines showing measurement of cold gap
- P-5 Gas pressure versus crank angle diagram
- P-6 Comparison of all AE and AF piston skirts in the region of the stud attachment bosses
- P-7 Representative dimension checks shown on Task Evaluation Reports Q-338, 310, 194, 203 and 182
- P-8 Trip report on nondestructive examination of AE piston skirt and a copy of AE piston skirt, inspection, requirements, certificates of compliance and receipt inspection documentation
- P-9 A sample preoperational test procedure and Appendix F showing peak firing pressures taken before the crankshaft failure and after the crankshaft replacement

- P-10 Strains and sigma III stress from strain gage rosette measurements
- P-11 Results of tempplug measurements of peak temperature as a function of position on crown
- P-12 Location of strain gage rosettes on instrumented AE skirt
- P-13 Summary of experimental observations related to crown/skirt interaction
- P-14 Strain readings and calculated stresses for AE piston skirt for the complete stud boss rosettes at 1600 psig with a conventional crown
- P-15 Comparison of experimental and numerical values of cyclic stresses for the AE piston skirt
- P-16 Comparison of experimental observations of peak stress at 1627 psig for AE piston skirt with corresponding finite element results using extremes of wrist pin behavior
- P-17 Cyclic stresses in AE piston skirts under isothermal and steady-state conditions
- P-18 Comparison of peak stress in stud boss region of AE piston skirt for loads applied on inner and outer contact rings
- P-19 Comparison of experimental and numerical gap closure and load split
- P-20 Comparison of skirt stiffnesses as evaluated from experimental observation and crown/skirt interaction model with corresponding finite element values
- P-21 Mean and cyclic stresses for infinite fatigue life
- P-22 Stress states for isothermal AE piston skirt for various gap sizes plotted on graph of allowable stress amplitude as a function of mean stress
- P-23 Stress states for AE piston skirt for various conditions plotted on a graph of allowable stress amplitude as a function of mean stress for various gap sizes and for isothermal and steady-state temperature conditions
- P-24 Summary of fracture toughness data from the literature for nodular cast iron with strength levels similar to 100-70-03
- P-25 Applied values of Delta K and R as a function of crack depth and corresponding values of Delta K<sub>th</sub>


- P-26 Liquid dye penetrant inspection results after 100 hours operation for EDGs 101, 102, 103
- P-27 Eddy current test results after 100 hours operation for EDGs 101, 102, 103; FaAA Procedure NDE 11.5, Rev. 0 and Rev. 1
- P-28 Iron Castings Handbook, page 34
- P-29 Results of inspection of AE pistons on the Kodiak Electric Association engine and the TDI R-5 prototype engine
- P-30 Volume I, TDI Owners Manual (sections discussing engine lubrication)
- P-31 Excerpts from Diesel Engine Design by T.D. Walshaw and Internal-Combustion Engines by V. L. Maleev
- P-32 Task evaluation reports and LILCO deficiency reports which discuss the DRQR's visual inspections of AE piston skirts
- P-33 Liquid dye penetrant test results for AF piston skirts
- P-34 Minimum and maximum stresses in AE piston skirt for various peak firing pressures for isothermal and steady state operating conditions; applied values of Delta K and R as a function of crack depth and corresponding values of Delta K<sub>th</sub> (2,200 psig)



Photograph of piston skirt with mounted crown and rings.



Photograph of a piston from the Shoreham Nuclear Power Station emergency diesel generator piston skirt (left) and crown (right).



Cross section of crown and skirt indicating the two areas of load transfer from the crown to the skirt.

EDG 101

T.E.

Shoreham Nuclear Station - Unit 1

REPAIR/REWORK REQUEST

1. Request: RB-1627 Initiated By: CC Fuller 2/16/84 System #: 1R73A  
Test Engineer/Date

RS 3-15-84

Work performed under jurisdiction of: ( ) Unico Construction (X) LILCO Startup

Work to be performed by: ( ) Unico Construction (X) LILCO Startup

Quality Assurance function to be performed by: (X) QA ( ) FQC ( ) Work Supervisor

System or Subsystem Description: EDG 101

QA Category: I Completion Date Required: \_\_\_\_\_

Perform the following work: Emergency Diesel Generator 101 outage Disassembly for Inspection Tasks

Reason for Work: Diesel Generator Quality Revalidation

2. Work to be performed in accordance with the following applicable construction or maintenance procedure: SHI-089, SUE #5 and attached Guidelines

3. Notify W. Cook 360 prior to performing work.  
Startup Engineer

4. Request Approved: mmphely 3/15/84 B. Lawrence 3/15/84  
Lead Startup Engineer / Date S&W Lead Advisory Eng./Date

5. This form must be signed and returned to the party requesting the work when the work is completed.

The above work has been completed. A work summary and necessary documentation is attached.

CC Fuller 4/8/84  
Supervisor/Date

W. Cook 4/26/84  
Field QC or Operational QA/Date

6. The following retest(s) are required and completed: EDG 101 Run-in (8.7 # 97)

W. Cook 4/26/84 W. Cook 4/9/84  
LILCO Operational QA Engineer/Date Startup Engineer/Date

DISTRIBUTION: Original to: Organization Performing Work: ( ) Unico Construction Superintendent (via Turnover Coordinator), or ( ) LILCO Startup.  
Copies To: Organization Not Performing Work: ( ) Unico Construction Superintendent (via Turnover Coordinator), or ( ) LILCO Startup  
Operational QA  
Field QC

NOTED APR 28 1984  
X08501



PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 5

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine.

A. DISASSEMBLY

- 1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.

B. REASSEMBLY

- 1. Verify the following inspections are complete and do not restrain reassembly.

Task description no. 03-341A

a. Release received

William R. Smith  
TE Date

Remarks TDI's 2266 & 2275

TDI's 2266 & 2275 - 4.12

b. Corrective action complete (N/A if not required).

William R. Smith  
TE Date

2. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X". (4 places only. See attached copy of portion of TDI dwg. 03-341-7319). Should be .007/.011. Remove crown.

.009  
Record Gap

FEDERAL GAP N/A  
M&TE # Cal. Due Date

William R. Smith  
TE Date

R. Benvenuto 3/25/84  
OQA Date

PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 7

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine.

A. DISASSEMBLY

- 1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.

B. REASSEMBLY

- 1. Verify the following inspections are complete and do not restrict reassembly.

Task description no. 03-341A

a. Release received

U.S. AT 1/25/84  
DATE

Remarks

LOR'S 2266 & 2275  
LOR'S 2266 & 2275 Accut 4/2 2/84

- b. Corrective action complete (N/A if not required).

U.S. AT 1/25/84  
DATE

- 2. Reassemble piston as follows.

- a. Place crown on skirt. Measure job. gap at print "X". Use gauge only. See attached copy of portion of DM fig. 4-24-3192. Should be .007/.011. Remove crown.

1200 - .010, 0300 - .011, 0600 - .010, 0900 - .009 1200 = ALIGNMENT  
Record Gap MIN

F-1200 GAUGE

MITE #

DATE

U.S. AT 1/25/84  
DATE

H. Bennett 1/25/84  
DATE

PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 8

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine.

A. DISASSEMBLY

1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.

B. REASSEMBLY

1. Verify the following inspections are complete and do not restrain reassembly.

Task description no. 03-341A

a. Release received

TE

Date

Remarks

LDI'S 2266 & 2275

LDI'S 2266 & 2275 Acc'd to 15

b. Corrective action complete (N/A if not required).

TE

Date

2. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X". (4 places only. See attached copy of portion of TDI dwg. 03-341-7319). Should be .007/.011. Remove crown.

1200 - .011, 0300 - .010, 0600 - .009, 0900 - .010

Record Gap

1200 = 14" minimum  
MIN

M&TE #

Cal. Due Date

FREELINE LABS

N/A

TE

Date

OQA


Date

R Bernard


3/25/84

.970  
 .968  
 A-REF.  
 EM #2)

14.965  
 14.963  
 DIA-REF.  
 (ITEM #1)



DO NOT SCALE DRAWING



Transamerica Delaval Inc  
 Engine and Compressor Division  
 Oakland, California 94621

NOV 9 1983

PISTON ASSEMBLY-TWO PC.  
 (R/RV-4 ENGINES)

AND HARDNESS  
 AT ABOVE

APP. & P. [unclear]	OWN
[unclear]	[unclear]

03-341-7319

EDG 102

SHOREHAM 1  
NUCLEAR POWER STATION  
STARTUP FORM 7.6

Shoreham Nuclear Station - Unit 1

REPAIR/REWORK REQUEST

1. Request: 1443-1433 Initiated By: C. Fuller 2/6/84 System #: R43B  
Test Engineer/Date

Work performed under jurisdiction of: ( ) Unico Construction  LILCO Startup

Work to be performed by: ( ) Unico Construction  LILCO Startup AT-2/6/84

Quality Assurance function to be performed by:  OQA ( ) FQC ( ) Work Supervisor

System or Subsystem Description: DIESEL GENERATOR 102

QA Category: I Completion Date Required: 2/17/84

Perform the following work: EMERGENCY DIESEL ENGINE 102 OUTAGE DISASSEMBLY  
GUIDELINES FOR INSPECTION TASKS

Reason for Work: DIESEL GENERATOR QUALITY REVALIATION

2. Work to be performed in accordance with the following applicable construction or maintenance procedure: SUIT #5 AND ATTACHED GUIDELINES, SHI-89, TDI MANUAL (R43-120)

3. Notify T. McCarthy cat 361 + OQA 83-304: prior to performing work.  
Startup Engineer

4. Request Approved: M. M. [Signature] 2/6/84 [Signature] 2/6/84  
Lead Startup Engineer / Date SGW Lead Advisory Eng./Date

5. This form must be signed and returned to the party requesting the work when the work is completed.

The above work has been completed. A work summary and necessary documentation is attached.

[Signature] 3/2/84 Supervisor/Date [Signature] 4/7/84 Field QC or Operational QA/Date

6. The following retest(s) are required and completed: EDG 102 RUN-IN  
complete 3/11/84 8.7 R43-89

[Signature] 4/7/84 LILCO Operational QA Engineer/Date [Signature] 4/7/84 Startup Engineer/Date

DISTRIBUTION: Original to: Organization Performing Work: ( ) Unico Construction Superintendent (via Turnover Coordinator), or  LILCO Startup.

Copies To: Organization Not Performing Work: ( ) Unico Construction Superintendent (via Turnover Coordinator), or  LILCO Startup  
Operational QA R. Purcell (x)  
Field QC ISEG (x) SHG, (1)-3  
OGARE (x)

NOTED APR 28 1984 R. Lawrence

PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 5

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine. Inspection requirements remain in steps VII, VIII and IX of the disassembly guidelines.

1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.
2. Perform piston, piston rings, and piston pins Inspection Task Guidelines. (Steps VII, VIII and IX).

N/A

DGQRG

Date

3. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X" (4 places only. See attached copy of portion of IDI dwg. 03-341-1319). Should be .007/.011. Remove crown.


SEE BELOW  
Record Gap

N/A 2-15-84  
MATE # Cal. Due Date  
MATE 1" MIKE 6-29-84  
2-53-129

FEELER GUNGE

Parti-Lecton 2/15/84  
TE Date

William J. ... 2/15/84  
OQA Date



PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 6

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine. Inspection requirements remain in steps VII, VIII and IX of the disassembly guidelines.

1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.
2. Perform piston, piston rings, and piston pins Inspection Task Guidelines. (Steps VII, VIII and IX).

GGRG

Date

3. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X" (4 places only. See attached copy of portion of TDI dwg. 03-341-7319). Should be .007/.011. Remove crown.

SEE BELOW

Record Gap

FEELER GUAGE

M&TE #

Cal. Due Date

1" MIKE

M&TE # 2-53-129


CAL DUE 6-29-84

TE

OQA

Rest. Section 2/11/84  
Date  
W. J. Quirk 2-16-84  
Date

FRONT OF ENG.





PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 7

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine. Inspection requirements remain in steps VII, VIII and IX of the disassembly guidelines.

1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.
2. Perform piston, piston rings, and piston pins Inspection Task Guidelines. (Steps VII, VIII and IX).

DGQRG

Date

3. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X" (4 places only. See attached copy of portion of TDI Eng. 03-341-7319). Should be .007/.011. Remove crown.

SEE BELOW  
Record Gap

FELLER CURVE

M&TE # \_\_\_\_\_ Cal. Due Date

1" MIKE

M&TE # 2-53-129

CAL. DUE 6-29-84

Ant. Patton 2-11-84  
TE. Date

Alv. Ruschko 2-16-84  
OOA Date


FRONT OF ENG.

A .008

D  
.008

B  
.008

C  
.008



PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 8

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine. Inspection requirements remain in steps VII, VIII and IX of the disassembly guidelines.

1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.
2. Perform piston, piston rings, and piston pins Inspection Task Guidelines. (Steps VII, VIII and IX).

DGQRC

Date

3. Reassemble piston as follows.


- a. Place crown on skirt. Measure cold gap at point "X" (4 places only. See attached copy of portion of TDI dwg. 03-341-7319). Should be .007/.011. Remove crown.

SEE BELOW  
Record Gap

FEELEE GURGE  
M&TE # Cal. Due Date


1" MIKE  
M&TE # 2-53-129  
CAL. DUE 6-29-84

Art Lutton 2/16/74  
TE Date  
Alip Buisheko 2-16-84  
OQA Date



370  
 968  
 REF.  
 M #2)

14.965  
 14.963  
 DIA.-REF.  
 (ITEM #1)



DO NOT SCALE DRAWING.

**Transamerica Delaval**

Transamerica Delaval Inc.  
 Engine and Compressor Division  
 Oakland, California 94621

NOV 9 1983

PISTON ASSEMBLY-TY10 PC.  
 (R/RV-4 ENGINES)

AND HARDNESS  
 M. A30VE

APP *J.P. [unclear]* DWN  
 SCALE: 1/2

03-341-7319

EDG 103

T.E.

UNCONTROLLED  
For Information Only

REPAIR/REWORK REQUEST

1. Request: 243-1562 Initiated By: M. TURNER 2/22/84 System #: 1R43C  
Test Engineer/Date

Work performed under jurisdiction of: ( ) Unico Construction  LILCO Startup

Work to be performed by: ( ) Unico Construction  LILCO Startup ( ) Catalytic

Quality Assurance function to be performed by:  JOQA ( ) FQC ( ) Work Supervisor

System or Subsystem Description: EDG 103 AT 3/3/84

QA Category: I Completion Date Required: \_\_\_\_\_

Perform the following work: EMERGENCY DIESEL GENERATOR 103 OUTAGE  
DISASSEMBLY FOR INSPECTION TESTS

Reason for Work: Diesel Generator Quality Rehabilitation

2. Work to be performed in accordance with the following applicable construction or maintenance procedure: SAI-089, SUB #5 AND ATTACHED GUIDELINES

3. Notify M. DeGroot 8/30 JOQA 83-304 prior to performing work.  
Startup Engineer

4. Request Approved: [Signature] 3/2/84 William W. [Signature] 3/2/84  
Lead Startup Engineer / Date ScW Lead Advisory Eng./Date

5. This form must be signed and returned to the party requesting the work when the work is completed.

The above work has been completed. A work summary and necessary documentation is attached.

CC Fuller 4/22/84 [Signature] 5-2-84  
Supervisor/Date Field QC or Operational QA/Date

6. The following retest(s) are required and completed: EDG 103 P10-10

@ 4/10

[Signature] 5/2/84 [Signature] 4/23/84  
LILCO Operational QA Engineer/Date Startup Engineer/Date

DISTRIBUTION: Original to: Organization Performing Work: ( ) Unico Construction Superintendent (via Turnover Coordinator), or ( ) LILCO Startup.

Copies To: Organization Not Performing Work: ( ) Unico Construction Superintendent (via Turnover Coordinator), or ( ) LILCO Startup  
Operational QA  
Field QC

NOTED MAY 4 1984 R. Lawrence  
A10934

REWORK SUPERVISOR WORK SUMMARY

BRIEF DESCRIPTION OF WORK: Took The Following Cold Gap Readings at 4 places on Pistons #5, #7, & #8 step 2B of piston Disassembly/Reassembly Guidelines:

Skirt placed on crown

Guide pin being 1200 looking into piston 300's area

	1200	300	600	900
Piston #5	.009	.009	.009	.009
#7	.009	.009	.008	.008
#8	.010	.009	.009	.009

COMPONENTS REPLACED (IF APPLICABLE):

CAF - P. Kaplan 3/17/84

Step 2.B crown and skirt pilot readings recording I.D. and O.D. respectively and documented

CALIBRATED TOOLS UTILIZED:

ADDITIONAL COMMENTS:

[Signature] 3/17/84  
Rework Supervisor Signature/Date

PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 5

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine.

A. DISASSEMBLY

- 1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.

B. REASSEMBLY

- 1. Verify the following inspections are complete and do not restrain reassembly.

Task description no. 03-341A

- a. Release received

Alfred W. Wacker 3/15/84  
TE Date

Remarks LOR 2198 outstanding - Dispositioned acceptable 25-15 3/17

- b. Corrective action complete (N/A if not required).

N/A  
TE Date

- 2. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X". (4 places only. See attached copy of portion of TDI dwg. 03-341-7319). Should be .007/.011. Remove crown.

see attached summary sheet  
Record Gap

1-Feeler Gage used  
M&TE # Cal. Due Date

Jy Cotton 3/17/84  
TE Date

Paul B. [Signature]  
OQA Date

PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 7

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine.

A. DISASSEMBLY

- 1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.

B. REASSEMBLY

- 1. Verify the following inspections are complete and do not restrain reassembly.

Task description no. 03-341A

- a. Release received

Alphar 3/15/84  
 TE Date

Remarks

LDR 2198 outlanding - disposition accepted  
as-is on 3/17/84

- b. Corrective action complete (N/A if not required).

N/A  
 TE Date

- 2. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X". (4 places only. See attached copy of portion of TDI dwg. 03-341-7319). Should be .007/.011. Remove crown.

see Attached work summary sheet  
 Record Gap

Freeler Gage used  
 M&TE # Cal. Due Date

Jeff Gibson 3/17/84  
 TE Date

Paul Gibson 3/20  
 OQA Date



PISTON DISASSEMBLY/REASSEMBLY GUIDELINES

Piston No. 8

NOTE: This guideline provides piston disassembly/reassembly instructions following removal of the piston assembly from the engine.

A. DISASSEMBLY

- 1. Remove the four (4) crown to skirt nuts. Record breakaway torque on attached sheet.

B. REASSEMBLY

- 1. Verify the following inspections are complete and do not restrain reassembly.

Task description no. 03-341A

a. Release received

Al Miller 3/15/84  
TE Date

Remarks EOR 2198 outstanding - disposition acceptable  
as-is on 2/12/84 @

b. Corrective action complete (N/A if not required).

N/A  
TE Date

2. Reassemble piston as follows.

- a. Place crown on skirt. Measure cold gap at point "X". (4 places only. See attached copy of portion of TDI dwg. 03-341-7319). Should be .007/.011. Remove crown.

See Attached Dissect summary sheet  
Record Gap

Ferber Eng used  
M&TE # Cal. Due Date

J. Carter 3/17/84  
TE Date

Paul Kaplan 3/1/84  
OQA Date

REWORK SUPERVISOR WORK SUMMARY

BRIEF DESCRIPTION OF WORK: Took the following Cold Gap Readings at 4 places on Pistons #5, #7, & #8 step 2A of piston Assembly/Reassembly Guidelines:

skirt placed on crown  
 Guide pin being used locking into piston boss


COMPONENTS REPLACED (IF APPLICABLE):

	200	300	600	700
Piston #5	.009	.009	.009	.009
#7	.009	.009	.008	.008
#8	.010	.009	.009	.009

Step 2B crown and skirt pilot readings measured I.D and O.D respectively and documented


CALIBRATED TOOLS UTILIZED:

ADDITIONAL COMMENTS:

 3/17/79  
 Rework Supervisor Signature/Date

370  
368  
-REF.  
A#2)

14.965  
14.963  
DIA.-REF.  
(ITEM #1)



DO NOT SCALE DRAWING.

**Transamerica  
Delaval**

Transamerica Delaval Inc  
Engine and Compressor Division  
Oakland, California 94621

NOV 9 1983

PISTON ASSEMBLY-TWO PC.  
(R/RV-4 ENGINES)

AND HARDNESS  
M. ABOVE


APP *L.R. F...*

DWN

SCALE: 1/2




CHK

03-341-7319



ANGLE (DEGREES)

Gas pressure versus crank angle (0° corresponds to top dead center).



Dimensions  
in inches

Comparison of AE and AF piston skirts in the region of the stud attachment bosses.

TER # Q-338

114

NOTED MAR 26 1984

COMPONENT TASK EVALUATION REPORT

ATT #4

STEM/COMPONENT NO. <u>03-341A</u>	TDI PART NO. <u>1A-6522</u> <u>03-341A</u>	INITIATOR <u>GD Gluka</u> SIGNATURE	DATE <u>3-20-84</u>	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
--------------------------------------	--	---	------------------------	---

CONDITION DETAILS: ATTACHED INSPECTION REPORT ( 2 PAGES) GENERATED BY BR Williams DATED 3/20/84 IS CONSIDERED INFORMATIONAL AS NO ACCEPTANCE CRITERIA WAS PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION.

COMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION AND ALSO TO SEO AND LSU FOR INFORMATION ONLY. Attached IR is informational only - see sheet 2 for recommended disposition

REQUIRED COMPLETION DATE:

ASSIGNMENT

FUNCTION ASSIGNED TO <input checked="" type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>Michael S Curry</u> SIGNATURE	DATE <u>3-20-84</u>
--	--	------------------------

DISPOSITION

DISPOSITION DETAILS: Follow Procedure outlined on page 2

DISPOSITION ASSIGNED TO <input checked="" type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY <input type="checkbox"/> NONE REQUIRED					
APPLIED BY <u>K Adon</u>	DATE <u>3-21-84</u>	REVIEWED BY <u>K Adon</u>	DATE <u>3-21-84</u>	APPROVED BY <u>C. Wells</u>	DATE <u>3-25-84</u>
RESP. CHAIRPERSON			PROGRAM MANAGER		

ACTION

ACTION ASSIGNED TO <u>C. Wells</u>	ACTION COMPLETED BY <u>K Adon for C Wells</u>	DATE <u>3-29-84</u>
---------------------------------------	--	------------------------

CKS/GWR/RJN/EFM  
TER LOG

134466

RECOMMENDED  
INFORMATION TER DISPOSITION

TER # Q-338  
PAGE 2 OF 4

Distribution for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-338", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.

A2 4/67

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3/20/84

SYSTEM(S) OR PART(S) NAME  03-341 A+B  PISTON  DIMENSION VERIFICATION	LOCATION(S)  ENGINE 101	REFERENCE DOCUMENT(S)  SH: 089  IP # 14 REV. 4 CHG. 0
---	-------------------------------	--

DWG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)																																																																																																								
	4	2	<div style="display: flex; justify-content: space-around;"> <div data-bbox="271 829 766 1340"> </div> <div data-bbox="798 851 1356 1234"> </div> </div> <p style="text-align: right;">MITE 2-54-18 DUE 8/7/84 MITE 2-51-03 5-6-84</p> <div style="display: flex; justify-content: space-around; margin-top: 10px;"> <div data-bbox="351 1340 750 1425"> <p>PISTON # 5</p> <table border="1" style="width: 100%; text-align: center;"> <thead> <tr> <th></th> <th>A</th> <th>B</th> <th>C</th> </tr> </thead> <tbody> <tr><td>* 1</td><td>2.272</td><td>.570</td><td>.255</td></tr> <tr><td>2</td><td>2.146</td><td>.570</td><td>.255</td></tr> <tr><td>3</td><td>2.148</td><td>.572</td><td>.255</td></tr> <tr><td>4</td><td>2.275</td><td>.570</td><td>.255</td></tr> <tr><td>5</td><td>2.144</td><td>.570</td><td>.255</td></tr> <tr><td>6</td><td>2.145</td><td>.569</td><td>.255</td></tr> <tr><td>7</td><td>2.271</td><td>.570</td><td>.255</td></tr> <tr><td>8</td><td>2.147</td><td>.568</td><td>.255</td></tr> <tr><td>9</td><td>2.144</td><td>.570</td><td>.255</td></tr> <tr><td>10</td><td>2.274</td><td>.572</td><td>.255</td></tr> <tr><td>11</td><td>2.145</td><td>.569</td><td>.255</td></tr> <tr><td>12</td><td>2.144</td><td>.570</td><td>.255</td></tr> </tbody> </table> </div> <div data-bbox="861 1340 1404 1425"> <p>PISTON # 7</p> <table border="1" style="width: 100%; text-align: center;"> <thead> <tr> <th></th> <th>A</th> <th>B</th> <th>C</th> </tr> </thead> <tbody> <tr><td>* 1</td><td>2.258</td><td>.568</td><td>.255</td></tr> <tr><td>2</td><td>2.143</td><td>.569</td><td>.256</td></tr> <tr><td>3</td><td>2.143</td><td>.569</td><td>.256</td></tr> <tr><td>4</td><td>2.260</td><td>.569</td><td>.255</td></tr> <tr><td>5</td><td>2.142</td><td>.568</td><td>.256</td></tr> <tr><td>6</td><td>2.142</td><td>.569</td><td>.255</td></tr> <tr><td>7</td><td>2.259</td><td>.569</td><td>.255</td></tr> <tr><td>8</td><td>2.139</td><td>.569</td><td>.255</td></tr> <tr><td>9</td><td>2.139</td><td>.569</td><td>.255</td></tr> <tr><td>10</td><td>2.260</td><td>.569</td><td>.255</td></tr> <tr><td>11</td><td>2.140</td><td>.569</td><td>.255</td></tr> <tr><td>12</td><td>2.140</td><td>.568</td><td>.255</td></tr> </tbody> </table> </div> </div> <p style="font-size: small; margin-top: 5px;">GOG 3/20/84 ADDED LETTER DESIGNATIONS</p>		A	B	C	* 1	2.272	.570	.255	2	2.146	.570	.255	3	2.148	.572	.255	4	2.275	.570	.255	5	2.144	.570	.255	6	2.145	.569	.255	7	2.271	.570	.255	8	2.147	.568	.255	9	2.144	.570	.255	10	2.274	.572	.255	11	2.145	.569	.255	12	2.144	.570	.255		A	B	C	* 1	2.258	.568	.255	2	2.143	.569	.256	3	2.143	.569	.256	4	2.260	.569	.255	5	2.142	.568	.256	6	2.142	.569	.255	7	2.259	.569	.255	8	2.139	.569	.255	9	2.139	.569	.255	10	2.260	.569	.255	11	2.140	.569	.255	12	2.140	.568	.255
	A	B	C																																																																																																								
* 1	2.272	.570	.255																																																																																																								
2	2.146	.570	.255																																																																																																								
3	2.148	.572	.255																																																																																																								
4	2.275	.570	.255																																																																																																								
5	2.144	.570	.255																																																																																																								
6	2.145	.569	.255																																																																																																								
7	2.271	.570	.255																																																																																																								
8	2.147	.568	.255																																																																																																								
9	2.144	.570	.255																																																																																																								
10	2.274	.572	.255																																																																																																								
11	2.145	.569	.255																																																																																																								
12	2.144	.570	.255																																																																																																								
	A	B	C																																																																																																								
* 1	2.258	.568	.255																																																																																																								
2	2.143	.569	.256																																																																																																								
3	2.143	.569	.256																																																																																																								
4	2.260	.569	.255																																																																																																								
5	2.142	.568	.256																																																																																																								
6	2.142	.569	.255																																																																																																								
7	2.259	.569	.255																																																																																																								
8	2.139	.569	.255																																																																																																								
9	2.139	.569	.255																																																																																																								
10	2.260	.569	.255																																																																																																								
11	2.140	.569	.255																																																																																																								
12	2.140	.568	.255																																																																																																								

\* LOCATION OF THE PISTON NOTCH REVIEWED: H.I. [Signature]



STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL  
INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3/20/84

SYSTEM(S) OR PART(S) NAME  
03-341 A+B  
PISTON  
DIMENSION VERIFICATION

LOCATION(S)  
ENGINE 101



REFERENCE DOCUMENT(S)

SHI 089  
IP #14 REV. 4  
CHG. 0

WG NO OR PO ITEM QTY

4 4

DESCRIPTION(S) AND INSPECTION REMARK(S)



MTG 2-54-18  
DUE 8/9/84  
MTG 2-51-03  
DUE 5-6-84

PISTON # 8

	A	B	C
* 1	2.264	.570	.255
2	2.145	.568	.255
3	2.146	.568	.255
4	2.264	.569	.255
5	2.148	.568	.255
6	2.147	.568	.255
7	2.264	.568	.255
8	2.146	.569	.255
9	2.147	.568	.255
10	2.264	.568	.255
11	2.148	.569	.255
12	2.146	.569	.255

PISTON # RING 1ST

	#5	#7	#8
* 1	.250	.250	.250
2	.250	.250	.250
3	.250	.250	.250
4	.250	.250	.250
5	.250	.250	.250
6	.250	.250	.250
7	.250	.250	.250
8	.250	.250	.250
9	.250	.250	.250
10	.250	.250	.250
11	.250	.250	.250
12	.250	.250	.250

A. J. J. J.

LOCATION OF THE PISTON IN THE ENGINE  
REV. 2-5-84  
REVISED BY S. Smith

QUALITY CONTROL INSP/ENG

BR Williams

DATE 3/20/84

PAGE 2 of 2

This inspection report is acceptable for design  
review.

Q-33B

03-341A

K. Adair for C. Wells  
3/29/84

114770

TER # Q-310  
1/4

**DATED** MAR 20 1984 **COMPONENT TASK EVALUATION REPORT**

STEM/COMPONENT NO.	TDI PART NO.	INITIATOR	DATE	ORGANIZATION
01 03-341A	03-341A	R. TomPKWS SIGNATURE	3-28-84	<input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY

CONDITION DETAILS: ATTACHED INSPECTION REPORT (2 PAGES) GENERATED BY D. SMITH DATED 3-28-84 IS CONSIDERED INFORMATIONAL AS NO ACCEPTANCE CRITERIA WAS PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION AND ALSO TO SEO AND LSU FOR INFORMATION ONLY.

*Attached IR is informational only.  
See Sheet 2 for recommended disposition.*

REQUIRED COMPLETION DATE: 3-28-84

**ASSIGNMENT**

FUNCTION ASSIGNED TO	RESPONSIBLE CHAIRPERSON	DATE
ENGINEERING <input type="checkbox"/> QUALITY	<u>R. Ersser</u> SIGNATURE	3-20-84

**DISPOSITION**

DISPOSITION DETAILS: FOLLOW PROCEDURE 1 OUTLINED ON PAGE 2

DISPOSITION ASSIGNED TO  ENGINEERING  QUALITY  NONE REQUIRED

APPLIED BY	DATE	REVIEWED BY	DATE	APPROVED BY	DATE
<u>K. Solan</u>	3-21-84	<u>K. Solan</u> RESP. CHAIRPERSON	3-21-84	<u>[Signature]</u> PROGRAM MANAGER	3/25/84

**ACTION**

ACTION ASSIGNED TO	ACTION COMPLETED BY	DATE
<u>C. Wells</u>	<u>K. Solan for C. Wells</u>	3-29-84

CKS/GWR/RJN/EFM  
TER LOG

*120172*

RECOMMENDED  
INFORMATION TER DISPOSITION

TER # Q-310  
PAGE 2 OF 4

Distribution for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-310", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.



110172

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL  
SECTION REPORT

JOB NUMBER 11600.37 DATE 3-20-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: <b>Pistons</b>  COMPONENT NO. <b>03-341A</b>	DC- <b>101</b>	I.P. NO. <b>14</b> REV. <b>4</b> CHG <b>0</b>  TER # <b>DR-239</b>  LILCO LP PROC. _____ REV. _____  DWG. NO. _____

DWG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	5	3	<p>PERFORMED DIMENSIONAL INSPECTION OF PISTON PIN BORE DIAMETER AT 45° INTERVALS AROUND THE CIRCUMFERENCE (IE; 4 MEASUREMENTS) AND PERFORMED THE INSPECTION AT THREE BORE DEPTHS ON BOTH SIDES OF THE PISTONS FOR CYLINDERS 5, 7, AND 8. (SEE BELOW AND ATTACHED)</p> <div style="display: flex; justify-content: space-around; align-items: flex-start;"> <div style="text-align: center;">  <p>A-A</p> </div> <div style="text-align: center;"> <p>FACING EXHAUST SIDE</p>  <p>CROWN</p> </div> </div> <p style="text-align: right; margin-right: 100px;">11.2.73</p>
NOTE NO. <b>2-52-11</b>			
DUE <b>12-22-84</b>			

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL  
SECTION REPORT

JOB NUMBER 11600.37 DATE 3-20-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: <b>Pistons</b>	DG- <u>101</u>	I.P. NO. <u>14</u> REV. <u>4</u> CHG <u>0</u>
COMPONENT NO. <u>03-341A</u>		TER # _____ LILCO LP PROC. _____ REV. _____ DWG. NO. _____

DWG. NO. OR P.O.	ITEM	QTY.	CYL # 5 DESCRIPTION(S) AND						INSPECTION REMARK(S) CYL # 7					
			1	2	3	4	5	6	1	2	3	4	5	6
	A		6.751	6.750	6.750	6.750	6.750	6.750	6.751	6.750	6.750	6.751	6.750	6.750
	B		6.751	6.750	6.750	6.750	6.750	6.750	6.750	6.750	6.750	6.751	6.751	6.750
	C		6.751	6.750	6.750	6.750	6.750	6.750	6.751	6.750	6.750	6.750	6.751	6.750
	D		6.750	6.750	6.750	6.750	6.750	6.750	6.750	6.750	6.750	6.750	6.751	6.750
			CYL # 8						<div style="font-size: 4em; opacity: 0.5;">X</div>					
	A		6.750	6.750	6.750	6.751	6.751	6.751						
	B		6.750	6.750	6.750	6.751	6.751	6.751						
	C		6.750	6.750	6.750	6.751	6.751	6.751						
	D		6.750	6.750	6.750	6.751	6.751	6.751						

M&T NO. \* 2-52-11  
DUE 12-22-84

This inspection report is acceptable for design review.

Q-310  
03-341A

K. A. Wells  
3/29/84

134475

COMPONENT TASK EVALUATION REPORT

STEM/COMPONENT NO. <u>03-341A</u> <u>D.G.103</u>	TDI PART NO. <u>1A-6522</u>	INITIATOR <u>New-M. Faly</u> SIGNATURE	DATE <u>3-13-84</u>	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
--	--------------------------------	--	------------------------	---

CONDITION DETAILS: ATTACHED INSPECTION REPORT ( 3 PAGES) GENERATED BY J. DeLan DATED 2-12-84 IS CONSIDERED INFORMATIONAL AS NO ACCEPTANCE CRITERIA WAS PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION AND ALSO TO SEO AND LSU FOR INFORMATION ONLY.

*ATTACHED IR IS INFORMATIONAL ONLY - See sheet 2 for recommended disposition.*

REQUIRED COMPLETION DATE:

ASSIGNMENT

DISPOSITION ASSIGNED TO <input checked="" type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>William C. Wells</u> SIGNATURE	DATE <u>3/1/84</u>
---	---	-----------------------

DISPOSITION

DISPOSITION DETAILS: *Follow procedure 1 outlined on page 2*

DISPOSITION ASSIGNED TO  ENGINEERING  QUALITY  NONE REQUIRED

APPLIED BY <u>K. Astin</u>	DATE <u>3-14-84</u>	REVIEWED BY <u>K. Astin</u>	DATE <u>3-14-84</u>	APPROVED BY <u>J. DeLan</u>	DATE <u>3/17/84</u>
RESP. CHAIRPERSON			PROGRAM MANAGER		

ACTION

ACTION ASSIGNED TO <u>C. Wells</u>	ACTION COMPLETED BY <u>K. Astin for C. Wells</u>	DATE <u>3-17-84</u>
---------------------------------------	---	------------------------

CKS/GWR/RJN/EFM  
TER LOG



RECOMMENDED  
INFORMATION TER DISPOSITION

TER #Q-194  
Page 2 of 5

Distribution for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-194", for each component affected.
- 2) SE' (J. Kammeier) - distribute for information.

A10585

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER

11600-37

DATE

3/12/84

SYSTEM(S) OR PART(S) NAME

LOCATION(S)

REFERENCE DOCUMENT(S)

03-341 ~~A~~ <sup>EH10 3/12/84</sup> ~~B~~  
 PISTON  
 DIMENSION VERIFICATION



ENGINE  
 DG 103

IP NO 14, REV. 3  
~~SH-039~~ 3/12/84  
 6/1/84

NO. PO

DESCRIPTION(S) AND INSPECTION REMARK(S)

4 1



~~PISTON # 8~~ <sup>EH10 3/12/84</sup>

	A	B	C
* 1	<del>2.309</del>	<del>0.567</del>	0.251
2	<del>2.185</del>	<del>0.571</del>	0.254
3	<del>2.185</del>	0.570	0.254
4		0.570	0.254
5			
6			
7			
8			
9			
10			
11			
12			

PISTON # 5

	A	B	C
* 1	2.245	.566	.255
2	2.125	.566	.254
3	2.125	.565	.254
4	2.243	.567	.254
5	2.125	.568	.254
6	2.125	.567	.254
7	2.242	.566	.253
8	2.125	.566	.254
9	2.125	.568	.255
10	2.245	.567	.253
11	2.125	.568	.253
12	2.124	.567	.253

\* LOCATION OF THE PISTON NOTCH

received by Phil... MTE NO 2-54-18

QUALITY CONTROL INSPECTOR  
 DATE 3/12/84

DATE 3/12/84  
 PAGE 1 of 3

QUALITY CONTROL  
INSPECTION REPORT

100 NUMBER  
11600.37

DATE  
3-12-84

SYSTEM(S) OR  
PART(S) NAME

LOCATION(S)

REFERENCE  
DOCUMENT(S)

03-341 <sup>ENVC 3/12/84</sup> ~~A~~ B  
PISTON  
DIMENSION VERIFICATION

ENGINE # <sup>REV 12-84</sup> ~~103~~ 103

IP NO. 14 REV. 3  
~~SH-089~~ ENVC 3/12/84

NO PO	ITEM QTY	DESCRIPTION(S) AND INSPECTION REMARK(S)																																																																																																								
4	2	<div style="display: flex; justify-content: space-around;"> <div style="text-align: center;"> <p>PISTON # 8</p> <table border="1"> <thead> <tr> <th></th> <th>A</th> <th>B</th> <th>C</th> </tr> </thead> <tbody> <tr><td>1</td><td>2.300</td><td>.570</td><td>0.255</td></tr> <tr><td>2</td><td>2.176</td><td>.569</td><td>0.255</td></tr> <tr><td>3</td><td>2.176</td><td>0.569</td><td>0.255</td></tr> <tr><td>4</td><td>2.298</td><td>0.570</td><td>0.255</td></tr> <tr><td>5</td><td>2.176</td><td>0.570</td><td>0.254</td></tr> <tr><td>6</td><td>2.176</td><td>0.569</td><td>0.255</td></tr> <tr><td>7</td><td>2.399</td><td>0.569</td><td>0.256</td></tr> <tr><td>8</td><td>2.175</td><td>0.571</td><td>0.255</td></tr> <tr><td>9</td><td>2.176</td><td>0.571</td><td>0.255</td></tr> <tr><td>10</td><td>2.292</td><td>0.570</td><td>0.256</td></tr> <tr><td>11</td><td>2.180</td><td>0.570</td><td>0.256</td></tr> <tr><td>12</td><td>2.177</td><td>0.570</td><td>0.255</td></tr> </tbody> </table> </div> <div style="text-align: center;"> <p>PISTON # 7</p> <table border="1"> <thead> <tr> <th></th> <th>A</th> <th>B</th> <th>C</th> </tr> </thead> <tbody> <tr><td>1</td><td>2.250</td><td>0.570</td><td>0.255</td></tr> <tr><td>2</td><td>2.123</td><td>0.569</td><td>0.255</td></tr> <tr><td>3</td><td>2.120</td><td>0.570</td><td>0.255</td></tr> <tr><td>4</td><td>2.250</td><td>0.570</td><td>0.255</td></tr> <tr><td>5</td><td>2.120</td><td>0.569</td><td>0.255</td></tr> <tr><td>6</td><td>2.125</td><td>0.570</td><td>0.255</td></tr> <tr><td>7</td><td>2.250</td><td>0.569</td><td>0.254</td></tr> <tr><td>8</td><td>2.125</td><td>0.569</td><td>0.254</td></tr> <tr><td>9</td><td>2.126</td><td>0.569</td><td>0.254</td></tr> <tr><td>10</td><td>2.250</td><td>0.569</td><td>0.255</td></tr> <tr><td>11</td><td>2.125</td><td>0.571</td><td>0.255</td></tr> <tr><td>12</td><td>2.125</td><td>0.571</td><td>0.255</td></tr> </tbody> </table> </div> </div>		A	B	C	1	2.300	.570	0.255	2	2.176	.569	0.255	3	2.176	0.569	0.255	4	2.298	0.570	0.255	5	2.176	0.570	0.254	6	2.176	0.569	0.255	7	2.399	0.569	0.256	8	2.175	0.571	0.255	9	2.176	0.571	0.255	10	2.292	0.570	0.256	11	2.180	0.570	0.256	12	2.177	0.570	0.255		A	B	C	1	2.250	0.570	0.255	2	2.123	0.569	0.255	3	2.120	0.570	0.255	4	2.250	0.570	0.255	5	2.120	0.569	0.255	6	2.125	0.570	0.255	7	2.250	0.569	0.254	8	2.125	0.569	0.254	9	2.126	0.569	0.254	10	2.250	0.569	0.255	11	2.125	0.571	0.255	12	2.125	0.571	0.255
	A	B	C																																																																																																							
1	2.300	.570	0.255																																																																																																							
2	2.176	.569	0.255																																																																																																							
3	2.176	0.569	0.255																																																																																																							
4	2.298	0.570	0.255																																																																																																							
5	2.176	0.570	0.254																																																																																																							
6	2.176	0.569	0.255																																																																																																							
7	2.399	0.569	0.256																																																																																																							
8	2.175	0.571	0.255																																																																																																							
9	2.176	0.571	0.255																																																																																																							
10	2.292	0.570	0.256																																																																																																							
11	2.180	0.570	0.256																																																																																																							
12	2.177	0.570	0.255																																																																																																							
	A	B	C																																																																																																							
1	2.250	0.570	0.255																																																																																																							
2	2.123	0.569	0.255																																																																																																							
3	2.120	0.570	0.255																																																																																																							
4	2.250	0.570	0.255																																																																																																							
5	2.120	0.569	0.255																																																																																																							
6	2.125	0.570	0.255																																																																																																							
7	2.250	0.569	0.254																																																																																																							
8	2.125	0.569	0.254																																																																																																							
9	2.126	0.569	0.254																																																																																																							
10	2.250	0.569	0.255																																																																																																							
11	2.125	0.571	0.255																																																																																																							
12	2.125	0.571	0.255																																																																																																							

24% Piston 7  
3/12/84

\* LOCATION OF THE PISTON NOTCH

MT# 107-54 7-0 5/1/84

QUALITY CONTROL INSPECTOR

*[Signature]*

DATE

APR 05 1984

PAGE


2 of 3

TER # 12-124  
Page 5 of 5

QUALITY CONTROL  
INSPECTION REPORT

JOB NUMBER 11600.37	DATE 3/12/84
REFERENCE DOCUMENT(S)	
I.P. NO. <u>14 REV. 3</u> CHG	
TER # _____	
LILCO LP PROC. _____ REV. _____	
DWG. NO. _____	

SYSTEM(S) OR PART(S) NAME	LOCATION(S)
COMPONENT NAME: <u>PISTON</u>	DG- <u>103</u>
COMPONENT NO. <u>03-341A</u>	

WG. NO. OR P.C.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)																																																				
	4	3	(2ND PART)																																																				
																																																							
			<table border="1"> <thead> <tr> <th></th> <th>B/L 5</th> <th>7</th> <th>8</th> </tr> </thead> <tbody> <tr><td>1</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>2</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>3</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>4</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>5</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>6</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>7</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>8</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>9</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>10</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>11</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>12</td><td>.246</td><td>.246</td><td>.249</td></tr> </tbody> </table>		B/L 5	7	8	1	.246	.246	.249	2	.246	.246	.249	3	.246	.246	.249	4	.246	.246	.249	5	.246	.246	.249	6	.246	.246	.249	7	.246	.246	.249	8	.246	.246	.249	9	.246	.246	.249	10	.246	.246	.249	11	.246	.246	.249	12	.246	.246	.249
	B/L 5	7	8																																																				
1	.246	.246	.249																																																				
2	.246	.246	.249																																																				
3	.246	.246	.249																																																				
4	.246	.246	.249																																																				
5	.246	.246	.249																																																				
6	.246	.246	.249																																																				
7	.246	.246	.249																																																				
8	.246	.246	.249																																																				
9	.246	.246	.249																																																				
10	.246	.246	.249																																																				
11	.246	.246	.249																																																				
12	.246	.246	.249																																																				
			<p>MATE NO. <u>2-53-115 (Dwg 2/1/84)</u></p>																																																				

85523

G-194  
03-341A

NO FURTHER INFORMATION IS REQUIRED FOR DESIGN  
REVIEW

K. Logan for C. Wells 2/9/84

A14599

STONE & WEBSTER ENGINEERING CORPORATION



QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3/12/84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
03-341 <del>A-B</del> <sup>ENR 3/12/84</sup> PISTON DIMENSION VERIFICATION	ENGINE DG 103	IP NO 14, REV. 3 <del>SH 089</del> ENR 3/12/84

DWG NO OR PO ITEM QTY DESCRIPTION(S) AND INSPECTION REMARK(S)

4 / 1



AP 600

~~PISTON # 8 ENR 3/12/84~~

	A	B	C
* 1	<del>2.307</del>	<del>0.567</del>	0.251
2	<del>2.185</del>	0.571	0.254
3	<del>2.186</del>	0.570	0.254
4		0.570	0.254
5			
6			
7			
8			
9			
10			
11			
12			

PISTON # 5

	A	B	C
* 1	2.245	.566	.255
2	2.125	.566	.254
3	2.125	.565	.254
4	2.243	.567	.254
5	2.125	.568	.254
6	2.125	.567	.254
7	2.248	.566	.253
8	2.125	.566	.254
9	2.125	.568	.255
10	2.245	.567	.253
11	2.125	.568	.253
12	2.124	.567	.253

\* LOCATION OF THE PISTON NOTCH

Reviewed by *[Signature]* MTE NO. 2-54-18

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3-12-84

SYSTEM(S) OR PART(S) NAME

LOCATION(S)

REFERENCE DOCUMENT(S)

03-341 (A) ~~B~~ ENH 3/12/84  
 PISTON  
 DIMENSION VERIFICATION

ENGINE # ~~103~~ <sup>BY 3/12/84</sup> 103



IP NO. 14 REV. 3  
~~SH-089~~ ENH 3/12/84

DWG NO OR PO

ITEM QTY

DESCRIPTION(S) AND INSPECTION REMARK(S)

4 2



B/C Piston 718  
 BRUNSON  
 3/12/84

PISTON # 8

A1601

PISTON # 7

	A	B	C
* 1	2.300	.570	0.255
2	2.176	.569	0.255
3	2.176	0.569	0.255
4	2.298	0.570	0.255
5	2.176	0.570	0.254
6	2.176	0.569	0.255
7	2.299	0.569	0.256
8	2.175	0.571	0.255
9	2.176	0.571	0.255
10	2.298	0.570	0.256
11	2.180	0.570	0.256
12	2.177	0.570	0.255

	A	B	C
* 1	2.250	0.570	0.255
2	2.123	0.569	0.255
3	2.120	0.570	0.255
4	2.250	0.570	0.255
5	2.120	0.569	0.255
6	2.125	0.570	0.255
7	2.250	0.569	0.254
8	2.125	0.569	0.254
9	2.126	0.569	0.254
10	2.252	0.569	0.255
11	2.125	0.571	0.255
12	2.126	0.571	0.255

ENH 3/12/84

\* LOCATION OF THE PISTON NOTCH

MTE NO 2-54-19 Due 8/9/84

QUALITY CONTROL INSPEC/ENG

DATE

PAGE

*J.P. Dale*


2 of 3

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3/12/84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: <i>PISTON</i>	DG- <u>103</u>	I.P. NO. <u>14</u> REV. <u>3</u> CHG
COMPONENT NO. <u>03-341A</u>		TER # _____ LILCO LP PROC. _____ REV. _____ DWG. NO. _____

DWG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)																																																				
	4	3	(2ND PART)																																																				
			 <table border="1" style="margin-left: auto; margin-right: auto;"> <thead> <tr> <th></th> <th>CYL 5</th> <th>7</th> <th>8</th> </tr> </thead> <tbody> <tr><td>1</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>2</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>3</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>4</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>5</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>6</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>7</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>8</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>9</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>10</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>11</td><td>.246</td><td>.246</td><td>.249</td></tr> <tr><td>12</td><td>.246</td><td>.246</td><td>.249</td></tr> </tbody> </table>		CYL 5	7	8	1	.246	.246	.249	2	.246	.246	.249	3	.246	.246	.249	4	.246	.246	.249	5	.246	.246	.249	6	.246	.246	.249	7	.246	.246	.249	8	.246	.246	.249	9	.246	.246	.249	10	.246	.246	.249	11	.246	.246	.249	12	.246	.246	.249
	CYL 5	7	8																																																				
1	.246	.246	.249																																																				
2	.246	.246	.249																																																				
3	.246	.246	.249																																																				
4	.246	.246	.249																																																				
5	.246	.246	.249																																																				
6	.246	.246	.249																																																				
7	.246	.246	.249																																																				
8	.246	.246	.249																																																				
9	.246	.246	.249																																																				
10	.246	.246	.249																																																				
11	.246	.246	.249																																																				
12	.246	.246	.249																																																				
			A74602																																																				
			M&TE NO. <u>2-53-116 (Dwg 8/1/84)</u>																																																				



ATT #5

TER # Q-203

1/6

EO6 103

## COMPONENT TASK EVALUATION REPORT

STEM/COMPONENT NO. 03-341A D. G. 103	TDI PART NO. 1A-6522	INITIATOR <u>Kevin M. Fahy</u> SIGNATURE	DATE 3-13-84	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
--	-------------------------	--	-----------------	---

CONDITION DETAILS: ATTACHED INSPECTION REPORT (3 PAGES) GENERATED BY B. Hayes  
DATED 3-13-84 IS CONSIDERED INFORMATIONAL AS NO ACCEPTANCE CRITERIA WAS  
PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION AND ALSO TO SEO AND LSU  
FOR INFORMATION ONLY.

REQUIRED COMPLETION DATE: 3-15-84  
*Attached IR is informational only.  
See Sheet 2 for recommended disposition.*

## ASSIGNMENT

FUNCTION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>R. Fraser</u> SIGNATURE	DATE 3-14-84
--	--	-----------------

## DISPOSITION

DISPOSITION DETAILS: *Follow Procedure 1 outlined on Page 2*

DISPOSITION ASSIGNED TO  ENGINEERING  QUALITY  NONE REQUIRED

APPLIED BY <u>K. Adm</u>	DATE 3-14-84	REVIEWED BY <u>K. Adm</u>	DATE 3-14-84	APPROVED BY <u>[Signature]</u>	DATE 3/15/84
		RESP. CHAIRPERSON	PROGRAM MANAGER		

## ACTION

ACTION ASSIGNED TO <u>C. Wells</u>	ACTION COMPLETED BY <u>K. Adm for C. Wells</u>	DATE 3-19-84
---------------------------------------	---	-----------------

CKS/GWR/RJN/EFM  
TER LOG

A10618

RECOMMENDED  
INFORMATION TER DISPOSITION

Q -  
2/6

Distribution for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-203", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.

A14619

QUALITY CONTROL  
INSPECTION REPORT

JOB NUMBER 111-00.37 DATE 3-13-84

SYSTEM(S) OR  
PART(S) NAME

LOCATION(S)

REFERENCE  
DOCUMENT(S)

COMPONENT NAME:

PISTONS  
CYL. 5

DG- 103

I.P. NO. 14 N.F.S. 11/2/84  
REV. 3 CHG 2

TER # 23-259



LILCO LP PROC. REV.

COMPONENT NO. 03341A

DWG. NO.

ING. NO. OR P.O. ITEM QTY DESCRIPTION(S) AND INSPECTION REMARK(S)

1/1 3



	①	②	③	④
A	6.50	6.70	6.70	6.75
B	6.70	6.75	6.75	6.75
C	6.70	6.70	6.75	6.70
D	6.75	6.75	6.70	6.70
E	6.75	6.75	6.70	6.75
F	6.75	6.70	6.70	6.75

A1 0520

NOTE NO. 2-52-11 DUE 12/27/84



Stone & Webster 5/13/84

QUALITY CONTROL  
INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3-13-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: PISTONS CYL. 7  COMPONENT NO. 03-3-114	DG- 103	I.P. NO. 7 REV. 3 CHG 0 TER # _____ LILCO LP PROC. _____ REV. _____ DWG. NO. _____

VG. NO. R P.O. ITEM QTY DESCRIPTION(S) AND INSPECTION REMARK(S)

VG. NO. R P.O.	ITEM	QTY	DESCRIPTION(S) AND INSPECTION REMARK(S)																																			
	4/6		<div style="display: flex; justify-content: space-around;"> <div style="text-align: center;">  </div> <div style="text-align: center;">  </div> </div> <table border="1" style="margin-left: auto; margin-right: auto;"> <thead> <tr> <th></th> <th>①</th> <th>②</th> <th>③</th> <th>④</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>6.750</td> <td>6.751</td> <td>6.751</td> <td>6.751</td> </tr> <tr> <td>B</td> <td>6.750</td> <td>6.750</td> <td>6.751</td> <td>6.751</td> </tr> <tr> <td>C</td> <td>6.750</td> <td>6.750</td> <td>6.751</td> <td>6.750</td> </tr> <tr> <td>D</td> <td>6.751</td> <td>6.750</td> <td>6.750</td> <td>6.751</td> </tr> <tr> <td>E</td> <td>6.751</td> <td>6.751</td> <td>6.750</td> <td>6.751</td> </tr> <tr> <td>F</td> <td>6.751</td> <td>6.751</td> <td>6.750</td> <td>6.751</td> </tr> </tbody> </table> <div style="text-align: right; margin-right: 100px;"> <p>AG 0322</p> </div>		①	②	③	④	A	6.750	6.751	6.751	6.751	B	6.750	6.750	6.751	6.751	C	6.750	6.750	6.751	6.750	D	6.751	6.750	6.750	6.751	E	6.751	6.751	6.750	6.751	F	6.751	6.751	6.750	6.751
	①	②	③	④																																		
A	6.750	6.751	6.751	6.751																																		
B	6.750	6.750	6.751	6.751																																		
C	6.750	6.750	6.751	6.750																																		
D	6.751	6.750	6.750	6.751																																		
E	6.751	6.751	6.750	6.751																																		
F	6.751	6.751	6.750	6.751																																		
			M&TE NO. 0250 11 DUE 12/22/84																																			

REVIEWED *[Signature]* 3/13/84

QUALITY CONTROL  
INSPECTION REPORT

JOB NUMBER  
11600.37

DATE  
3-13-84

SYSTEM(S) OR  
PART(S) NAME

LOCATION(S)

REFERENCE  
DOCUMENT(S)

COMPONENT NAME:

DC- 10.3

I.P. NO. 14 <sup>2/5/84</sup> <sub>3/13/84</sub> REV. 3 CHG 0



PISTONS  
CYL. 8

TER # 23 257

LILCO LP PROC. \_\_\_\_\_ REV. \_\_\_\_\_

COMPONENT NO. 03-341A

DWG. NO. \_\_\_\_\_

G. NO & P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)																																			
	<i>A/C</i>		<div style="display: flex; justify-content: space-around;">   </div> <table border="1" style="margin-left: auto; margin-right: auto;"> <thead> <tr> <th></th> <th>①</th> <th>②</th> <th>③</th> <th>④</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> </tr> <tr> <td>B</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> </tr> <tr> <td>C</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> </tr> <tr> <td>D</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> </tr> <tr> <td>E</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> </tr> <tr> <td>F</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> <td>6.750</td> </tr> </tbody> </table> <div style="text-align: right; margin-right: 50px;"> <p><i>MAG 313</i></p> </div>		①	②	③	④	A	6.750	6.750	6.750	6.750	B	6.750	6.750	6.750	6.750	C	6.750	6.750	6.750	6.750	D	6.750	6.750	6.750	6.750	E	6.750	6.750	6.750	6.750	F	6.750	6.750	6.750	6.750
	①	②	③	④																																		
A	6.750	6.750	6.750	6.750																																		
B	6.750	6.750	6.750	6.750																																		
C	6.750	6.750	6.750	6.750																																		
D	6.750	6.750	6.750	6.750																																		
E	6.750	6.750	6.750	6.750																																		
F	6.750	6.750	6.750	6.750																																		
			<p>NOTE NO. <u>23211</u> <u>Due 11/12/84</u></p>																																			

Reviewed *Xu* 3/13/84

QUALITY CONTROL INSPECTION ENG

DATE

PAGE

COMPONENT TASK EVALUATION REPORT

6/6

ITEM/COMPONENT NO. 03-341A	TDI PART NO. 03-341A	INITIATOR <i>[Signature]</i> SIGNATURE	DATE 3/12/84	ORGANIZATION <input checked="" type="checkbox"/> ENGINEER <input type="checkbox"/> QUALITY
-------------------------------	-------------------------	--	-----------------	--

CONDITION DETAILS: IP No 14 needs clarification on LP Test requirements for the Piston also, dimensional inspections of the piston pin <sup>bore</sup> area are needed. These requirements are for cylinders #5, 7 & 8.

COMMENDATIONS: Revise IP No 14 to delete the LP test of the piston pin boss area. The LP test of the piston skirt at the bosses for belt attachment of crown is required. In addition, the following dimensional inspection is to be added to IP No. 14: Perform Dimensional Inspection of the Piston Pin <sup>bore</sup> Diameter at 45° intervals around the circumference (i.e. 4 measurements) and perform this inspection at 3 bore depths and on both sides of the pistons. ~~SKIRT~~

REQUIRED COMPLETION DATE: 3/12/84

ASSIGNMENT

SITUATION ASSIGNED TO ENGINEERING <input checked="" type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <i>[Signature]</i> SIGNATURE	DATE 3/12/84
--	--	-----------------

DISPOSITION

DISPOSITION DETAILS: M. Curry - Revise T.O. accordingly  
EFM - Revise CTS  
B. Murray - Revise IP  
INSPECTIONS to proceed T.O. update if required

DISPOSITION ASSIGNED TO		<input type="checkbox"/> ENGINEERING	<input checked="" type="checkbox"/> QUALITY	<input type="checkbox"/> NONE REQUIRED
PREPARED BY <i>[Signature]</i>	DATE 3-12-84	REVIEWED BY <i>[Signature]</i> RESP. CHAIRPERSON	DATE 3-12-84	APPROVED BY <i>[Signature]</i> PROGRAM MANAGER
				DATE 3/12/84

ACTION

SITUATION ASSIGNED TO ASC, EFM, B Murray INFO: MHS S.B. [unclear]	ACTION COMPLETED BY	DATE

: CKS/GWR/RJN/EFM  
TER LOG

M 1023

Q-203  
C-341A

NO FURTHER INFORMATION IS REQUIRED FOR DESIGN  
REVIEW

K. Adlan for C. Wells 3/19/84

M 067A

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER  
11600.37

DATE  
3-13-84

SYSTEM(S) OR PART(S) NAME

LOCATION(S)

REFERENCE DOCUMENT(S)

COMPONENT NAME:

DG- 103

I.P. NO. 14 <sup>7.1.84</sup> <sub>3/13/84</sub> REV. 3 CHG 0

PISTONS  
CYL. 5

TER # DR-239

COMPONENT NO. 03-341A

LILCO LP PROC. \_\_\_\_\_ REV. \_\_\_\_\_

DWG. NO. \_\_\_\_\_



DWG. NO. OR P.O.

ITEM

QTY.

DESCRIPTION(S) AND INSPECTION REMARK(S)

N/A 3



	①	②	③	④
A	6.750	6.750	6.751	6.751
B	6.750	6.750	6.751	6.751
C	6.750	6.750	6.751	6.750
D	6.751	6.751	6.750	6.750
E	6.751	6.751	6.750	6.751
F	6.751	6.751	6.750	6.751

M 0025

M&T NO. 2-52-11

2UE 12/22/84

*[Handwritten signature]* 3/13/84

QUALITY CONTROL INSPEC/ENG  
*[Handwritten signature]*

DATE  
3-13-84

PAGE  
1 of 3



STONE & WEBSTER ENGINEERING CORPORATION



QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37	DATE 3-13-84
REFERENCE DOCUMENT(S)	
I.P. NO. <u>7</u> REV. <u>3</u> CHG <u>0</u>	
TER # <u>DR-239</u>	
LILCO LP PROC. _____ REV. _____	
DWG. NO. _____	

SYSTEM(S) OR PART(S) NAME	LOCATION(S)
COMPONENT NAME: <u>PISTONS</u> <u>CYL. 7</u>	DG- <u>103</u>
COMPONENT NO. <u>03-341A</u>	

DWG. NO OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
-----------------	------	------	---

N/A



	①	②	③	④
A	6.750	6.750	6.751	6.751
B	6.750	6.750	6.751	6.751
C	6.750	6.750	6.751	6.750
D	6.751	6.750	6.750	6.751
E	6.751	6.751	6.750	6.751
F	6.751	6.751	6.750	6.751

M. 0526

M&TE NO. 2-52-11 DUE 12/22/84

RECEIVED BY [Signature] DATE 3/13/84

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER  
11600.37

DATE  
3-13-84

SYSTEM(S) OR PART(S) NAME

LOCATION(S)

REFERENCE DOCUMENT(S)

COMPONENT NAME:

DG- 103

I.P. NO. 14 <sup>N.E.S.</sup> 2 <sup>3/13/84</sup> REV. 3 CHG 0

PISTONS  
CYL. 8

TER # DB 239

COMPONENT NO. 03-341A

LILCO LP PROC. \_\_\_\_\_ REV. \_\_\_\_\_



DWG. NO. \_\_\_\_\_

DWG. NO. OR P.O.

ITEM QTY.

DESCRIPTION(S) AND INSPECTION REMARK(S)

N/A



	①	②	③	④
A	6.750	6.750	6.750	6.750
B	6.750	6.750	6.750	6.750
C	6.750	6.750	6.750	6.750
D	6.750	6.750	6.750	6.750
E	6.750	6.750	6.750	6.750
F	6.750	6.750	6.750	6.750

MAGNET

M&TE NO. 052-11 , DIE 12/22/84 , \_\_\_\_\_ , \_\_\_\_\_

REVIEWED [Signature] 3/13/84

QUALITY CONTROL INSPEC/ENG  
BARKASO, D HALL

DATE  
3-13-84

PAGE  
3 - 3

COMPONENT TASK EVALUATION REPORT

NOTED FEB 20 1984

ATT #5

DR 182

M/COMPONENT NO. Piston 03-341-A	TDI PART NO. 1A-6522	INITIATOR <u>R Bernard</u> SIGNATURE	DATE 2/19/84	ORGANIZATION <input checked="" type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
---------------------------------------	-------------------------	--	-----------------	--

CONDITION DETAILS:

ADDITIONAL INSPECTION PER TERQ - 21 PISTONS AND 7

RECOMMENDATIONS:

SUBMITTED FOR FAA REVIEW & ACTION AND SEO - ~~INFO~~  
FOR ~~INFO~~ INFO.

REQUIRED COMPLETION DATE: 2/19/84

ASSIGNMENT

POSITION ASSIGNED TO <input checked="" type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>Nestor A. Saleta</u> SIGNATURE	DATE 2/19/84
--	---	-----------------

DISPOSITION

DISPOSITION DETAILS:

Send copy to C. Wells / FAA, and SEO for information only.

DISPOSITION ASSIGNED TO  ENGINEERING  QUALITY  NONE REQUIRED

SUPPLIED BY <u>Robert R. Scheibe</u>	DATE 2/19/84	REVIEWED BY <u>S. Suit for G.W. Rogers</u> RESP. CHAIRPERSON	DATE 2/19/84	APPROVED BY <u>C. A. James</u> PROGRAM MANAGER	DATE 2/20/84
---	-----------------	--	-----------------	--	-----------------

ACTION

ACTION ASSIGNED TO <u>C. Wells / FAA</u>	ACTION COMPLETED BY <u>C. Wells</u>	DATE 2/27/84
---	--	-----------------

CC: CKS/GWR/RJN/EFM  
TER LOG

ATT #5

130560

STONE & WEBSTER ENGINEERING CORPORATION


QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 2/17/84


SYSTEM(S) OR PART(S) NAME  03-341 A+B Rev 1 PISTON DIMENSION VERIFICATION	LOCATION(S)  ENGINE 102	REFERENCE DOCUMENT(S)  SHI 089 TER-Q-21  VITE USED: 2-54-06 DUE 9/10/84 2-51-03 DUE 8/6/84 2-54-18 DUE 8/9/84
---	-------------------------------	---

DWG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
------------------	------	------	---

5



PISTON 5 ——— DIAMETER 16.715  
 PISTON 7 ——— DIAMETER 16.900



PISTON # 5

PISTON # 7

	A	B	C
* 1	2.240	.570	.255
2	2.105	.570	.255
3	2.105	.570	.255
4	2.240	.570	.255
5	2.115	.570	.255
6	2.115	.570	.255
7	2.240	.570	.255
8	2.115	.570	.255
9	2.115	.570	.255
10	2.240	.570	.255
11	2.115	.570	.255
12	2.110	.570	.255

	A	B	C
* 1	2.280	.569	.255
2	2.150	.568	.255
3	2.130	.568	.255
4	2.280	.567	.255
5	2.150	.567	.255
6	2.150	.568	.255
7	2.280	.568	.255
8	2.150	.569	.255
9	2.150	.569	.255
10	2.280	.569	.255
11	2.150	.569	.255
12	2.150	.570	.255

A. J. D. S. E. A.

\* LOCATION OF THE PISTON NOTCH NOTED FEB 17 1984 A. GRANITE

DR-182

This inspection report is  
acceptable for design review

Carol Bobroff for Cliff Wells  
personal comm. 2/27/84

A3 0562


DATE: 2-18-84

TO: E. J. Youngling  
LSU Manager


FROM: C. K. Seaman  
DR/QR Program Manager

SUBJECT: RELEASE FOR REASSEMBLY FROM DR/QR PROGRAM  
COMPONENT NO. 03-341A  
COMPONENT TITLE PISTONS  
EMERGENCY DIESEL GENERATOR NO. 102

This is to advise you that the subject component no./title for the stated Emergency Diesel Generator Unit has been released by the Design Review/Quality Revalidation (DR/QR) Program for completion of its Quality Revalidation inspections, to LILCO Start-up (LSU) for reassembly. This release is acknowledged by the signatures shown below.

  
C. K. Seaman  
DR/QR Program Manager

  
G. W. Rogers  
Design Review Group Chairperson

 2/18/84  
J. C. Kammeyer  
Stone & Webster Engineering Corp. (SEO)

cc: W.J. Museler  
M.H. Milligan  
E.F. Montgomery  
M.H. Schuster  
R.J. Najuch  
R. Bernard  
E. ...

Note: This release is applicable only to the satisfactory completion of DR/QR Program component inspection requirements. Outstanding LDR's, E&DCR's, etc. and their satisfactory resolution are not covered under this release. Furthermore, completion of the Design Review portion of the DR/QR Program may result in additional component inspection requirements.

103563


November 14, 1983

03-341 A

TO: J. M. Kelly  
FROM: E. J. Nicholas  
Subject: Trip Report On Nondestructive Examination (PT) of Piston Skirt

On November 9, 1983 I was requested to visit Transamerica Delaval in Oakland, California to witness the Liquid Penetrant (PT) Nondestructive Examination performed on the piston skirt bolt holes. The extent of the examination is as identified in Engineering & Design Coordination Report (E&DCR) F-46324 Section II (Ref. Attach. I). Attachment II identifies the piston skirts which were examined and witnessed by myself and the results.

Surface defects were removed utilizing TDI's "Spring Boss, Two Pc. Piston Skirt Repair Procedure for Removing Surface Defects Observed after Penetrant Inspection (PT)" (Attachment III). Defect removal was verified by Liquid Penetrant Examination of the ground areas, in addition dimensional inspections of the Trust Collar area were performed. These inspections were performed by the S&W PQA inspector and witnessed by myself. The results of the Liquid Penetrant Examinations were photographed. These photographs will be turned over to OQA.

  
E. J. Nicholas  
Field QA Section Supervisor

EJN/rc

cc: A. R. Muller - UQA  
J. Kaumeyer - SEQ  
M. Schuster - UNICO  
R. Perra - S&W FQC OPS


→ FQA FILE

83-0638

REFERENCES: LDR-1811 R43 A/C

PROBLEM DESCRIPTION:

Inspections performed on piston skirts for Engine 101 revealed numerous indications in the machined area on Boss around bolt holes, reference LDR-1811.



TELECOPY DATES (REQUESTING PARTY)  
 Sent:  
 Rec'd:

Requested By: P. MARTIN Dept. or Div. 550 Tele. Ext. 550 Date 11/9/83 Needed By

PROBLEM SOLUTION:

To expedite the arrival of new piston skirts on site, should it be determined that new skirts are required, LSU will issue a purchase requisition for a complete set of piston skirts, part no. 03-341-04-AE, for each engine plus two spares (total-26). Purchase of new piston skirts is on a risk basis pending results of failure analysis by FAA, and submittal and evaluation of required documentation by TDI. Inspection and Documentation requirements per attached pages 2 to 4.

TELECOPY DATE (RESPONDING PARTY)  
 Sent:  
 Rec'd:

AFFECTS WORK UNDER SPECIFICATION SH-089

IMPLEMENTATION VERIFICATION  IS REQUIRED  IS NOT VERIFIED BY 11/9/83

Furnished By: [Signature] Date 11/9/83 Responsible Lead Engr: [Signature] Date 11/9/83

- INFORMATION ONLY
- DRAWING CHANGE MANUAL
- SPECIFICATION CHANGE
- PROCEDURE CHANGE
- ENG. SERV. SCOPE OF WORK CHANGE
- Change will  be incorporated in the following documents:  
 will not  following documents:

SH-089 R43-1 Vol II  
 Nuclear Safety Related (QA Cat I)  
 Not Nuclear Safety Related ( QA Cat II  QA Cat III)

Project Design Engr. [Signature] Date 11/9/83  
 Equipment Specialist [Signature] Date 11/9/83  
 Cost Est. or Eng. Accur. Dept. [Signature] Date 11/9/83  
 Materials Engr. [Signature] Date  
 Project Engineer Approval & Date [Signature] 11/9/83

ESAR CHANGE  Yes  No  
 CLIENT APPROVAL:  
 Required  Not Req.  
 Obtained Date: 11/9/83  
 Reference: CK [Signature]  
 CLIENT DISTRIBUTION-CLIENT HEADQUARTERS:  
 Engineering  
 Project Manager

HEADQUARTERS		FIELD DISTRIBUTION		CONST SUPERVISORS	
<input checked="" type="checkbox"/> Proj. Engr.	<input type="checkbox"/> Chief Engr.	<input type="checkbox"/> Originator	<input checked="" type="checkbox"/> E. Krummeyer	<input type="checkbox"/> Structural	<input checked="" type="checkbox"/> [Signature]
<input checked="" type="checkbox"/> Proj. Des. Engr.	<input type="checkbox"/> Chief Des. Engr.	<input type="checkbox"/> Client QA Mgr.	<input checked="" type="checkbox"/> [Signature]	<input type="checkbox"/> Mechanical	<input checked="" type="checkbox"/> [Signature]
<input checked="" type="checkbox"/> Boss Engr.	<input type="checkbox"/> Supl. Const. Serv.	<input type="checkbox"/> Client Const. Insp.	<input checked="" type="checkbox"/> [Signature]	<input type="checkbox"/> Electrical	<input checked="" type="checkbox"/> [Signature]
<input checked="" type="checkbox"/> Camp Spec.	<input type="checkbox"/> Engr.-EA Div.	<input type="checkbox"/> SEW FOC	<input checked="" type="checkbox"/> [Signature]	<input type="checkbox"/> Piping	<input type="checkbox"/> [Signature]
<input checked="" type="checkbox"/> Const. Engr.	<input checked="" type="checkbox"/> R. J. Smith	<input type="checkbox"/> SEW Res. Engr.	<input checked="" type="checkbox"/> [Signature]	<input checked="" type="checkbox"/> Welding	<input type="checkbox"/> [Signature]
<input checked="" type="checkbox"/> QA-Qual. Sys. D.	<input checked="" type="checkbox"/> L. [Signature]	<input type="checkbox"/> Fid. Des. Engr.	<input checked="" type="checkbox"/> [Signature]	<input type="checkbox"/> Instrument	<input type="checkbox"/> [Signature]
<input checked="" type="checkbox"/> QA-POC D.V.	<input checked="" type="checkbox"/> J. [Signature]	<input type="checkbox"/> Prod. Fid. Engr.	<input checked="" type="checkbox"/> [Signature]	<input type="checkbox"/> Planning	<input type="checkbox"/> [Signature]



ATTACHMENT TO E&DCR # F-46324  
PAGE 2 OF 4

Attachment to E&DCR F-46324

Page 1

I - Shop Inspections/Verifications:

Prior to shipment, the engineer's inspector shall perform the inspections and verifications as described below. A Certificate of Conformance to specification SH1-089 is required for all parts:

(A) General:

(1) NDE

Verify all NDE documented on Shop routing ledger has been performed and results acceptable. Verify and document that NDE procedures used are the same as those approved for use in accordance with SH1-089 original requirements. If any procedure deviates from those approved under original contract (either revision level or alternate procedure) the procedure actually used shall become part of the as shipped documentation package on a risk basis and shall be submitted to S&W for review. Inspector shall provide a list of applicable discrepancies (i.e. procedure used but not approved) to S&W Boston directly.

Verify that personnel certified to appropriate SMT-TC-IA levels have performed NDE as required.

(2) HEAT TREATMENT

Verify that any heat treatment as documented on the Shop routing ledger has been performed and accepted. Procedures used shall be reviewed for changes (revision level or alternate procedure) from those approved for use under SH1-089. If any procedure deviates from those approved under original contract, the procedure actually used shall become part of the as shipped documentation package on a risk basis and shall be submitted to S&W for review. Inspection shall provide a list of applicable discrepancies (i.e. procedure used but not approved) to S&W directly.

(3) SHOP ROUTING LEDGER SHEETS

Verify Shop Routing Ledger Sheet has been properly filled out and each applicable station task has been performed. Review in detail for any non-conformance or rework required during the manufacturing-testing process. Complete details of any such defect/resolution acceptance criteria and final acceptance shall be obtained and become part of the as shipped documentation package on a risk basis. Copies of all such documentation, as well as the shop routing ledger shall be provided to S&W Boston for review.

Page 2

(4) SHIP CLEANING SHIPPING/CRATING

The inspector shall review and verify the method of cleaning, shipping and crating is appropriate and acceptable in accordance with SHI-089.

(5) VISUAL INSPECTION

The inspector shall perform a complete visual inspection of all parts for obvious defects and/or deviation from the detail shop fabrication drawings. A dimensional check of a sufficient number of points shall be performed to verify the parts are in accordance with the shop drawings.

All items checked shall be documented. Any deviations should be brought to the immediate attention of the engineers.

Surface finish as specified on the shop drawing shall be verified.

(6) NDE TEST REPORTS

All NDE Test Reports shall be reviewed for completeness and accuracy and shall become part of the documentation package.

(7) CMTRS (if applicable)

Certified Material Test Reports shall be reviewed for completeness and shall become part of the documentation package.

II Shoreham Specific NDE Requirements

In addition to the Standard TDI piston skirt NDE, a color contrast penetrant test will be performed on each piston skirt by TDI personnel, in accordance with approved procedures. This may be supplemented by the use of LILCO NDE procedures/personnel.

The location to be inspected is the machined area on the boss around the four bolt holes inside the piston skirt, with particular emphasis on the vertical blended radii surfaces.

The penetrant test will be witnessed by SWEC POA & LILCO FOC. Acceptance criteria will be per TDI procedures or LILCO procedures as applicable, however linear indications will not be accepted without SWEC Engineering approval. All indications will be mapped by LILCO FOC personnel, clearly identifiable to the piston in question.

Page 3

### III DOCUMENTATION

(A) The following documentation will be included with the shipment:


1. C of C to specification SH1-089
2. CMTRs if applicable
3. Heat Treatment records
4. Shop routing sheets
5. Results of MPI

(B) Documentation to be supplied by TDI, following shipment:

1. Seismic qualification per SH1-089
2. IEEE-387 qualification; analysis or testing per Section 5.4.4.
3. Inst. Manual Inserts.
4. Nonconformance & disposition records
5. 341-AS piston service history. To include details of both shop testing and field history (number in field, operating hours, etc).
6. TDI to perform review and document the effects, if any, of piston skirt changeout on the ability of the unit to achieve rated load and speed in the required time, and on the "Torsional and Lateral Critical Speed Analysis".

ATTACHMENT II

<u>Serial No.</u>	<u>Heat No.</u>	<u>Accept/Reject</u>
1. C88X	827J	Accept
2. C89	811J	Accept
3. D42	937J	Accept
4. D49	937J	REJECT
5. E5	104K	REJECT
6. E8	104K	accept
7. F7	181K	Accept
8. F12	181K	Accept
9. F15	200K	Accept
10. F18	200K	Accept
11. F21	200K	Accept
12. F24	200K	Accept
13. F27	205K	REJECT
14. F29	205K	REJECT
15. F32	205K	REJECT
16. F35	205K	Accept
17. F53	256K	REJECT
18. F56	256K	Accept
19. F58	256K	Accept
20. F87	289K	Accept
21. F97	289K	Accept
22. F98	289K	Accept
23. G1	298K	Accept
24. G2	298K	Accept
25. G4	298K	Accept
26. G5	298K	Accept
27. G26	312K	Accept
28. G29	312K	Accept
29. G30	312K	Accept
30. G33	312K	Accept
31. G34	312K	Accept
32. G35	312K	Accept



SPRING BOSS, TWO PC., PISTON SKIRT  
REPAIR PROCEDURE FOR REMOVING SURFACE DEFECTS  
OBSERVED AFTER PENETRANT INSPECTION (PT)



- MINOR -

- 1) HAND GRIND EACH DEFECT WITHIN BOUNDARY LIMITS CAREFULLY REMOVING ALL SHARP EDGES WITH BLEND RADIUS.
- 2) FINISH POLISH ALL REPAIRS WITH "CRATEX #1350C" GRINDING WHEEL. -
- 3) DO NOT VIOLATE  $9/32$ " LIMITING DIMENSION SHOWN FOR THRUST COLLAR SEATING SURFACE.
- 4) DO NOT EXCEED  $5/8$ " LIMITS SHOWN FROM CAST SURFACES. -

- MAJOR -

- 1) MULTIPLE DEFECTS MAY BE COMPLETELY REMOVED BY HAND GRINDING ENTIRE LIP WITHIN BOUNDARY LIMITS.
- 2) USE THE SAME GRIND AND POLISH PROCEDURE AND OBSERVE ALL LIMITS SPECIFIED FOR SINGLE DEFECTS.

LILCO RD 310652  
SUGREYNDORLEA POWER STATION UNIT 1  
PART NO. 03-241-04 AE PISTON SKIRTS

D-4991

# LONG ISLAND LIGHTING COMPANY

PURCHASE ORDER NO. 310552-32  
 DATE: 11/10/83

*OPS*

<input type="checkbox"/> PROJECT NO.	<input type="checkbox"/> PROJECT CTR.	PROJECT NUMBER	QUANTITY OR SHIP NO	DATE	PURCHASE ORDER NO.
			F77679/T.Brown	11/10/83	310552-32

ORDERED TO <b>TRANSAMERICA DELAVAL, INC.</b> 550 85th Ave. P.O. Box 2161 Oakland Calif. 94621 (415) 577-7400	TERMS* <input type="checkbox"/> NET 30 DAYS <input type="checkbox"/> 2% 10 DAYS	FILE NO.
BUYER AF:gr	*ALL CASH DISCOUNTS ARE TAKEN STARTING WITH DATE OF INVOICE OR RECEIPT OF MERCHANDISE WHICHEVER IS LATER	

SHIP VIA <input type="checkbox"/> YOUR DELIVERY <b>Air Freight</b>	ACCEPTANCE OF THIS ORDER IS SUBJECT TO THE TERMS AND CONDITIONS PRINTED ON THE REVERSE SIDE HEREOF. THE TYPED MATERIAL CONTAINED HEREIN AND ANY FURTHER INSTRUCTIONS AND MATERIALS ATTACHED HERETO
VENDOR'S SHIPPING PROMISE Delivery - November 12, 1983 Balance - November 30, 1983	VENDOR'S QUOTE REFERENCE Telecon of November 10, 1983

IF YOU WANT TO SEND ACKNOWLEDGEMENT AND/OR SHIPPING INFORMATION  
 → LONG ISLAND LIGHTING COMPANY AT MARK: 310552-32

DESCRIPTION	M & S CODE	QUANTITY ORDERED	PRICE
<b>CONFIRMING: DO NOT DUPLICATE-START-UP</b>			
Modify our Purchase Order 310552 for Diesel Generator Sets (Spec. 1-089) for Shoreham Nuclear Power Station Unit No. 1 to incorporate the following additions:			
1.) Piston Skirt P/N D3-341-04-AE		26 ea.	\$6,323.00/ea.
2.) Thrust Collar P/N D3-341-04-AC		104 ea.	35.95/ea.
3.) Spring Guide P/N D3-341-04-AF		104 ea.	53.60/ea.
4.) Lock Tab P/N D3-341-04-ad		104 ea.	6.90/ea.
5.) Lock Pin P/N GC-023-000		104 ea.	1.00/ea.
6.) Cotter Pin GC-002-055		100 ea.	1.00/ea.
7.) Stud P/N D3-341-04-AB		104 ea.	86.55/ea.

*Handwritten notes:*  
 8 1/2 - CLR #447  
 11 1/3 - CLR #448  
 7 1/16 - CLR #448  
 L7 CR #445

Certificate of Compliance is required to state the material supplied is in accordance with Spec. SH1-089. PQA inspection is required only for item 1, Piston Skirt.

SHOREHAM NUCLEAR POWER STATION  
**APPROVED**

NOV 10 1983

MONTHLY REPORT FORM PREPARED <input checked="" type="checkbox"/> YES (FC-8574) DATE _____ <input type="checkbox"/> NOT REQUIRED	FIELD QUALITY CONTROL EXTRA COPIES OF P.O. TO CONTRACTED PROJECTS <i>D.J. Jersey</i> <input type="checkbox"/> INSURANCE DIV. <input type="checkbox"/> PROPERTY RECORDS <input type="checkbox"/> ADMINISTRATIVE SERV. <input type="checkbox"/> OFFICE SERVICES <input type="checkbox"/> ENGINEERING <input type="checkbox"/> TAX
BPO RECORD - CATEGORY _____ BPO EXPIRATION FOLLOW-UP DATE _____	PURCHASE ORDER NO. 310552-32 <i>PK 11/1/83 2</i>

# LONG ISLAND LIGHTING COMPANY

C-1679-B

175 E. OLD COUNTRY ROAD

HICKSVILLE, N. Y. 11801

PURCHASE ORDER

DESCRIPTION	M & S CODE	QUANTITY ORDERED	PRICE
<p>PQA Inspection/Documentation requirements in accordance with E&amp;DCR F46324, copy of which is attached</p> <p><u>IMPORTANT</u> This order is issued subject to the following stipulations:</p> <p>Nothing in this Order or Supplement shall be deemed to release or prejudice any claims or causes of action (whether in contract, tort or otherwise) or to waive any prior rights or remedies that LILCO may have against Transamerica Delaval. LILCO expressly reserves the right to pursue any such claims, causes of action, rights and remedies that it may have, including but not limited to damages or claims for refund of monies paid pursuant to this order.</p> <p>All other terms and conditions remain the same as stated in the original purchase order.</p> <p><u>COPIES ONLY:</u></p>			
TOTAL ESTIMATED LUMP SUM COST OF THIS ORDER THRU SUPPLEMENT	31	..	\$4,953,664.80
TOTAL LUMP SUM COST OF THIS SUPPLEMENT	..	..	183,634.00
TOTAL ESTIMATED LUMP SUM COST OF THIS ORDER TO DATE	..	..	5,137,298.80
TOTAL AUTHORIZED VALUE OF THIS PURCHASE ORDER	..	..	2,173,000.00

LINE NO	QUANTITY	UNIT	DESCRIPTION	TO BE USED FOR	ACCT. NO.	VENDOR	UNIT PR	TOTAL	CASH DIS.
1	EA		PISTON - SKIRT		2400.470000	6322-16A398			
2	EA		03-341-04-AE						
3	EA		Ø-FING						
4	EA		IF-023-000						
5	EA		Thrust Collar						
6	EA		03-341-09-ADLLC						
7	EA		SPRING GUIDE						
8	EA		03-341-04-AB						
9	EA		LOCK TAB						
10	EA		03-341-07-AD						
11	EA		LOCK PIN						
12	EA		G.C. 1023-000						
13	EA		COTTER PINS						
14	EA		GC-022-055						
15	EA		STUD						
16	EA		03-341-04-AB						
<p>ITEM # 1 ONLY - SHIP VIA</p> <p>COLECT SHI-89, PORT INJECTION</p>									
<p>ADDITIONAL REQUIREMENTS</p> <p>QUALITY CLAUSE ESTIMATED COST \$ 115.00</p> <p>PRF REQUIRED BY ASME MATERIAL <input type="checkbox"/></p> <p>PRF NOT REQUIRED BY NON ASME MATERIAL <input type="checkbox"/></p>									
<p>DATE APPLIED TO ORDER</p> <p>DATE DOES NOT APPLY <input type="checkbox"/></p>									
<p>DATE</p> <p>DATE</p>									
<p>DATE RECEIVED</p> <p>DATE</p>						<p>DATE</p> <p>DATE</p>			

NO. F 77679

JO NUMBER 11800.07

DATE RECEIVED 11/18/83

BUYER ASSIGNED

SHOREHAM NUCLEAR POWER STATION  
LONG ISLAND LIGHTING COMPANY

APPROVED (QUALITY CONTROL ENGINEER)

APPROVED (JOB MANAGEMENT)

APPROVED (CLIENT)

DATE 11/18/83

DATE 11/19/83

DATE

DATE

DATE

DATE



QTY	DESCRIPTION	UNIT	PRICE	TOTAL	DATE	BY	REMARKS
1	PISTON - SKIRT						
26 EA	03-341-09-AE						
	O-RING						
	IF-643						
3	Thrust Collar						
1/4 EA	03-341-09-AD						
4	SPRING GUIDE						
1/4 EA	03-341-04-AF						
	LOCK TRAD						
5	LOCK PIN						
1/4 EA	03-341-04-AD						
6	LOCK PIN						
1/4 EA	GC-023-000						
	LETTER PINS						
7	STUD						
1/4 EA	GC-002-055						
8	03-341-04-A.B						
9	COFC TO SH-19 PORT INJECTION P... ADDITIONAL REQUIREMENTS QUALITY CL USE... ESTIMATED COSTS... PRF REQUIRED <input type="checkbox"/> ASME MATERIAL <input type="checkbox"/> PRF NOT REQUIRED <input checked="" type="checkbox"/> NON ASME MATERIAL <input type="checkbox"/>						

ESC-70 APPLIES   
 ESC-70 DOES NOT APPLY

DELIVERY DATA  
 DATE: 11/18/89  
 BY: T. Brown  
 APPROVED BY: [Signature]

BASIS OF PURCHASE:  
 11/18/89  
 11/18/89

STONE & WEBSTER ENGINEERING CORPORATION  
ENGINEERING & DESIGN COORDINATION REPORT

NO. F-46324

PROJECT/CLIENT: SHOREHAM NUCLEAR POWER STATION UNIT 1  
LONG ISLAND LIGHTING COMPANY

JOB NO. 11600 03

REFERENCES: LDR-1811

R43 4-B

PROBLEM DESCRIPTION:

Inspections performed on piston skirts for Engine 101 revealed numerous indications in the machined area on Boss around bolt holes, reference LDR-1811.

TELECOPY UNIT  
(REQUESTING PARTY)

Sent:  
Rev'd:

Requested By: P. M. ...

Dept. or Div. 500

Tele. Ext. 500

Date: 11/18/83

Checked By:

PROBLEM SOLUTION:

To expedite the arrival of new piston skirts on site, should it be determined that new skirts are required, LCU will issue a purchase requisition for a complete set of piston skirts, part no. 03-341-04-NE, for each engine plus two spares (total-26). Purchase of new piston skirts is on a risk basis pending results of failure analysis by PAM, and submittal and evaluation of required documentation by TDI. Inspection and Documentation requirements per attached pages 2 to 4.

EFFECTS OF THIS MODIFICATION ARE:

IMPLEMENTATION VERIFICATION: YES / NO

Form with fields for Name, Title, Date, and Initials.

- 1) OPERATIONAL ONLY
2) DRAWING CHANGE
3) SPECIFICATION CHANGE
4) PROCEDURAL CHANGE
5) ENG. SERV. OR FIELD WORK CHANGE

Project Design Dept.
Project Engineer Approval & Date

DESIGN CHANGE: YES / NO
CLIENT APPROVAL: YES / NO
Reviewed Date: 11/18/83

- 2A Nuclear Safety Related (QA Cat I)
2B Not Nuclear Safety Related (QA Cat II)

Project Engineer Approval & Date

CLIENT DISTRIBUTION - CLIENT HEAD

Table with columns for HEADQUARTERS and FIELD DISTRIBUTION, listing various departments and their status.

Table with columns for HEADQUARTERS and FIELD DISTRIBUTION, listing various departments and their status.

Table with columns for HEADQUARTERS and FIELD DISTRIBUTION, listing various departments and their status.

Page 1

I - Shop Inspections/Verifications:

Prior to shipment, the engineer's inspector shall perform the inspections and verifications as described below. A Certificate of Conformance to specification SH1-089 is required for all parts:

(A) General:

(1) NDE

Verify all NDE documented on Shop routing ledger has been performed and results acceptable. Verify and document that NDE procedures used are the same as those approved for use in accordance with SH1-089 original requirements. If any procedure deviates from those approved under original contract (either revision level or alternate procedure) the procedure actually used shall become part of the as shipped documentation package on a risk basis and shall be submitted to S&W for review. Inspector shall provide a list of applicable discrepancies (i.e. procedure used but not approved) to S&W Boston directly.

Verify that personnel certified to appropriate SNT-TC-1A levels have performed NDE as required.

(2) HEAT TREATMENT

Verify that any heat treatment as documented on the Shop routing ledger has been performed and accepted. Procedures used shall be reviewed for changes (revision level or alternate procedure) from those approved for use under SH1-089. If any procedure deviates from those approved under original contract, the procedure actually used shall become part of the as shipped documentation package on a risk basis and shall be submitted to S&W for review. Inspection shall provide a list of applicable discrepancies (i.e. procedure used but not approved) to S&W directly.

(3) SHOP ROUTING LEDGER SHEETS

Verify Shop Routing Ledger Sheet has been properly filled out and each applicable station task has been performed. Review in detail for any non-conformance or rework required during the manufacturing-testing process. Complete details of any such defect/resolution acceptance criteria and final acceptance shall be obtained and become part of the as shipped documentation package on a risk basis. Copies of all such documentation, as well as the shop routing ledger shall be provided to S&W Boston for review.

Page 2

(4) SHIP CLEANING SHIPPING/CRATING

The inspector shall review and verify the method of cleaning, shipping and crating is appropriate and acceptable in accordance with SH1-089.

(5) VISUAL INSPECTION

The inspector shall perform a complete visual inspection of all parts for obvious defects and/or deviation from the detail shop fabrication drawings. A dimensional check of a sufficient number of points shall be performed to verify the parts are in accordance with the shop drawings.

All items checked shall be documented. Any deviations should be brought to the immediate attention of the engineers.

Surface finish as specified on the shop drawing shall be verified.

(6) NDE TEST REPORTS

All NDE Test Reports shall be reviewed for completeness and accuracy and shall become part of the documentation package.

(7) CMTRs (if applicable)

Certified Material Test Reports shall be reviewed for completeness and shall become part of the documentation package.

II Shoreham Specific NDE Requirements

In addition to the Standard TBI piston skirt NDE, a color contrast penetrant test will be performed on each piston skirt by TBI personnel, in accordance with approved procedures. This may be supplemented by the use of LILCO NDE procedures/personnel.

The location to be inspected is the machined area on the boss around the four bolt holes inside the piston skirt, with particular emphasis on the vertical blended radii surfaces.

The penetrant test will be witnessed by SWEC FQA & LILCO FQC. Acceptance criteria will be per TBI procedures or LILCO procedures as applicable, however linear indications will not be accepted without SWEC Engineering approval. All indications will be mapped by LILCO FQC personnel, clearly identifiable to the piston in question.

Page 3

III DOCUMENTATION

(A) The following documentation will be included with the shipment:

1. C of C to specification SH1-089 ✓
2. CNTRs if applicable
3. Heat Treatment records
4. Shop routing sheets ✓
5. Results of MPI

(B) Documentation to be supplied by TDI, following shipment:

1. Seismic qualification per SH1-089
2. IEEE-387 qualification, analysis or testing per Section 5.4.4.
3. Inst. Manual inserts.
4. Nonconformance & disposition records
5. 341-AP piston service history. To include details of both shop testing and field history (number in field, operating hours, etc).
6. TDI to perform review and document the effects, if any, of piston skirt changeout on the ability of the unit to achieve rated load and speed in the required time, and on the "Torsional and Lateral Critical Speed Analysis".

415 577 7573

P.O. 310552-32 TransAmirica Delaval  
 7th. Piston Skirts P/N 03-341-04-AE  
 S/N's F15, F24, F18, 042, F12, F21, F35

RECEIVING INSPECTION REPORT  
 SHOREHAM NUCLEAR POWER STATION  
 DATE: 11/12/83

DATE RECEIVED		MR. NUMBER	PARTIAL	QC CONTROL NO. (if required)
11-12-83	83-05046	COMPLETE		
STORAGE LEVEL	TO: HOLD/REJECT TAG NO	INBD REPORT NO		
A B C D	N/A	6108		
<input checked="" type="checkbox"/> SAT <input type="checkbox"/> UNSAT				
SIGNATURE		DOCUMENTATION	REVIEW	DATE
D. J. Ferary				11/12/83
REMARKS * P/A Doc Lacking At Treat. Records - Most Conditionally Released Inspected IAW P.O., Preplan, Lico TP 12.019.99 and E/DCR F-46324 C.R. #445 INSPECTOR SIGNATURE D. J. Ferary				
RELEASED FOR CONSTRUCTION USE <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO				
IDENTIFICATION <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO				
DOCUMENTATION <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO				
CONDITION <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO				
SOURCE INSPECTED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO				
SAT UNSAT				
SR.T 47258				

Transamerica Delaval Inc.  
Engine and Compressor Division  
880 85th Avenue  
P.O. Box 2161  
Oakland, California 94621

R-33615  
83-755

CERTIFICATE OF COMPLIANCE

TO: Long Island Lighting Company  
90 State & Webster Engineering Corp.  
P.O. Box 604  
Wading River N.Y. 11792



SHOREHAM NUCLEAR POWER STATION - UNIT 1

REFERENCE PURCHASE ORDER NUMBER: 310552-32

SUPPLIER: Transamerica Delaval Inc.

WE HEREBY CERTIFY THAT THE PRODUCTS OR SERVICES FURNISHED ON THE ABOVE REFERENCE PURCHASE ORDER MEET THE REQUIREMENTS OF THE APPLICABLE DRAWINGS AND/OR SPECIFICATIONS. SK1-89

- PARTS LISTED ON THE ATTACHED PACKING LIST ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- PARTS LISTED BELOW ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- DOCUMENTATION IN MANUFACTURERS FILE TO BE SUBMITTED AS REQUIRED AT A LATER DATE.
- DOCUMENTATION ATTACHED/SHIPPED SEPARATELY.
- PART NUMBER(S) (ITEM 3 ONLY) 03-341-04-AE IS/ARE EQUAL TO OR BETTER THAN THAT WHICH WAS ORIGINALLY ORDERED.

Q. Q. Mills MANAGER - Quality Engineering 11-11-83  
L. L. MILLS TRANSAMERICA DELAVAL, INC. REPRESENTATIVE DATE

NA NA  
CUSTOMER REPRESENTATIVE DATE

PURCHASE ORDER NUMBER:

R-33615

F. O. BOX 4101  
Oakland, California 94621  
(415) 877-7400 Telex 335-304

ORDER  
R-33615  
OUR NUMBER

DATE ENTERED

11/10/83

MAIL TO: 5415  
LONG ISLAND LIGHTING CO.,  
C/O STONE & WEBSTER ENG. CORP.,  
P.O. BOX 604  
WADING RIVER, N.Y. 11792

SHIP TO:  
LONG ISLAND LIGHTING CO.,  
SHOREHAM NUCLEAR POWER STATION  
1/2 MI. EAST OF WILLIAMS FLOYD  
PARKWAY, HIGHWAY 25A  
SHOREHAM, L.I., NEW YORK 11786

MARKINGS:

INVOICE NO.	INVOICE DATE	CUSTOMER REF NUMBER
Shipping TAG	DATE SHIPPED	310552-7132
CARRIER		11-11-83
REMARKS		NET 30 DAYS
FACTORY		FACTORY OAKLAND
DOMESTIC AIR		AIR FREIGHT

PHONE MODEL	SERIAL NUMBER	CODE	BASE TAX	PRODUCT	INC	TERRITORY	REGIONS	STATE
DSR-48	74010 12		0	55508	491	20 25 58		33

REV. 01-11-09-83 CHG. QTY'S  
ITEMS 1-6, ADD ITEM 7, TOTAL,  
CHG. CUST, P.O., & REQ. DATE.

INVOICE CUSTOMER FOR FREIGHT

1	104	03-341-04-AC
2	104	03-341-04-AD
3	26	03-341-04-AE
4	104	03-341-04-AF
5	104	GC-023-000
6	104	03-341-04-AB
7	100	GC-002-005

COLLAR, THRUST  
LOK-TAB  
SKIRT  
GUIDE, SPRING  
GROOVER, PIN  
STUD

COTTER PIN

ACCOUNTING INFORMATION

65,201 N-344-3

35.95	3,738.80
6.98	717.60
6,323.00	164,398.00
59.60	5,574.40
1.00	104.00
86.55	9,001.20
1.00	100.00
	183,634.00



ITEM(3) ONLY

ORDER WRITER

LP

We hereby certify that these goods were produced in compliance with all applicable requirements of Sections 6, 7 and 12 of the Fair Labor Standards Act, as amended, and of regulations and orders of the United States Department of Labor issued under Section 14 thereof. No goods returned without our written permission. Deliveries contingent upon strikes, fires, accidents or other delays beyond our control. Goods proving defective will be replaced. No claims for damages or labor will be allowed. We are not responsible for loss of patterns due to fire.

PAGE NUMBER

1

The Attached "Conditions Of Sale" Are Part Of This Document.



**STONE & WEBSTER ENGINEERING CORPORATION  
QUALITY ASSURANCE DEPARTMENT  
PRODUCT QUALITY CERTIFICATION**

T-376A-

PAGE OF

PURCHASER <i>Long Island Lighting Company</i>	J.O. <i>11600.37</i>	P.O. NO. <i>310552</i>	CHANGE NO. <i>-32-</i>
PROJECT <i>Sullivan Success Park Station #1</i>	SPEC. NO. <i>541-89</i>	REVISION <i>2 1-26-83</i>	ADDENDA <i>N/A</i>
SELLER/ADDRESS <i>Transamerica Delaware, Inc. 550 85th Avenue Orlando, CA. 94621</i>			
DOCUMENTATION REQUIRED  YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	QA CAT.  <i>1</i>	SHIPPING RELEASE TAG NUMBER(S)  <i>47258</i>	

I HEREBY CERTIFY THE PRODUCT (S) IDENTIFIED HEREIN HAVE BEEN INSPECTED IN ACCORDANCE WITH S&W PROCUREMENT QUALITY ASSURANCE REQUIREMENTS AND ARE ACCEPTABLE FOR SHIPMENT.

**CHECK BLOCKS  
AS APPLICABLE**

- AUTHORIZED DEVIATIONS AND NONCONFORMANCES HAVE BEEN NOTED BELOW.
- ALL SPECIFIED SUPPORTING DOCUMENTATION HAS BEEN REVIEWED AND FORWARDED TO S&W PROCUREMENT QUALITY ASSURANCE FOR DOCUMENTATION REVIEW.
- DOCUMENTATION PREVIOUSLY SUBMITTED.
- DOCUMENTATION TO REMAIN IN SELLER'S FILES.

<u>ITEM NO.</u>	<u>P/N</u>	<u>QUANTITY</u>
<i>3</i>	<i>03-341-04-AE</i>	<i>8 EA.</i>

<u>HT. NO.</u>	<u>SERIES</u>
<i>1. 200K</i>	<i>F15</i>
<i>2. 200K</i>	<i>F24</i>
<i>3. 200K</i>	<i>F18</i>
<i>4. 827J</i>	<i>C88X</i>
<i>5. 937J</i>	<i>D42</i>
<i>6. 181K</i>	<i>F12</i>
<i>7. 200K</i>	<i>F21</i>
<i>8. 205K</i>	<i>F35</i>

NAME (PRINTED) *W.F. Whitten* TITLE *DISTRICT MANAGER*

NAME (SIGNED) *W.F. Whitten* DATE *11/11/83* IN NO. *51105529011*

AUTHORIZED DEVIATIONS AND NONCONFORMANCES  
*E4DCK # F-40324, DTD. 11-9-83*

SNAP-OUT STRIP

# STONE & WEBSTER ENGINEERING CORPORATION SHIPPING RELEASE TAG

J. O. NO. 11600.37		P. O. NO. 310552-32	
SPECIFICATION TITLE DIESEL GENERATOR SETS			
SPEC. DATE 1-26-83		SPEC. NO. 541-89	ADDENDA THRU NO. —
SELLER OR CONTRACTOR TRANSAMERICA DELAVAL, INC.			
SHIPPER FLYING TIGERS			
EQUIPMENT OR MATERIAL LISTED IS HEREBY RELEASED FOR SHIPMENT:			
MARK NO. <u>SEE PIN BELOW</u>			
QUANTITY <u>8 EA.</u>			
DESCRIPTION <u>PISTON SKIRTS</u>			
HT #		PIN #	
1.	200K	F15	
2.	200K	F24	
3.	200K	F18	
4.	227J	C88X	
5.	937J	D42	
6.	181K	F12	
7.	200K	F21	
8.	205K	F35	
<input checked="" type="checkbox"/> REQUIRED DOCUMENTATION IS COMPLETE			
S & W INSPECTOR J.R. Whitten		DATE 11/83	TAG NO. 47258

ISSUED TO \_\_\_\_\_ DATE \_\_\_\_\_

\* OPA INSPECTED D. J. Hooley DATE 11/12/83

P.O. NO. 310552-32 REQ. NO. F77679 OF \_\_\_\_\_

VENDOR TRANSAMERICA DELAVAL

SHIPPER TRANSAMERICA DELAVAL SHIPPERS NO: R-33615

DATE REC'D 11/14/83 CHECKED BY B. D'AMBROSIO MRR NO. 05046

SHIPPED VIA FLYING TIGERS

PRO NO. 6311-4100 NO. OF CTNS 9 WEIGHT 2,688

STORAGE LOCATION \_\_\_\_\_ STORE REQ NO. \_\_\_\_\_

\* Conditionally Released CR # 445 - NED 6108

P.O. ITEM NO.	QTY	DESCRIPTION	COMP. ID
1	7	PISTON SKIRT P/N 03-341-04-AG	

P.O. 310552-32 Trans America Detail

1144 Piston Skirt P/N 03-341-04-AE

SN's G33, G34, G4, G2, G1, F87, F58, F56, F7, E8, C89

Cat I SHI-089

RECEIVING INSPECTION REPORT  
SHOREHAM NUCLEAR POWER STATION  
UNIT - 1

STONE & WEBSTER ENGINEERING CORPORATION

DATE RECEIVED	11-13-83	MR. NUMBER	83-5047	PARTIAL	<input checked="" type="checkbox"/>
STORAGE LEVEL	A B C D	QC NO./REJECT TAG NO.	N/A	COMPLETE	<input type="checkbox"/>
				INBD REPORT NO.	6110

SOURCE INSPECTED	YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	IDENTIFICATION	<input checked="" type="checkbox"/>	DOCUMENTATION	<input checked="" type="checkbox"/>	CONDITION	<input checked="" type="checkbox"/>	RELEASED FOR CONSTRUCTION USE	YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>
S.P.T.	4726										
SAT											
UNSAT											
SIGNATURE			DOCUMENTATION REVIEW			DATE			QC CONTROL NO. (if required)		
R. Porra			D. J. Wray for:			11-13-83			6/2		
REMARKS: POA Doc lacking Mt. Trent. Records - Mt. Trent. Conditionally Released.											
Inspected IAW P.O., Prepton, LILCO TP17.019, 99 and EIDCR F-46324											
C.B. #447			D. J. Wray for:			R. Porra			DATE		
11-13-83			11-13-83			11-13-83			11-13-83		

Transamerica Delaval Inc.  
Engine and Compressor Division  
880 80th Avenue  
P.O. Box 2181  
Oakland, California 94621

R-33615

83-756

(ORIGINAL)  
009A

CERTIFICATE OF COMPLIANCE

TO: Long Island Lighting Company  
96 John & Webster Engineering Corp  
P.O. Box 604  
Wading River N.Y. 11792



SHOREHAM NUCLEAR POWER STATION - UNIT 1

REFERENCE PURCHASE ORDER NUMBER: 310552-32

SUPPLIER: Transamerica Delaval Inc.

WE HEREBY CERTIFY THAT THE PRODUCTS OR SERVICES FURNISHED ON THE ABOVE REFERENCE PURCHASE ORDER MEET THE REQUIREMENTS OF THE APPLICABLE DRAWINGS AND/OR SPECIFICATIONS. 541-89

- PARTS LISTED ON THE ATTACHED PACKING LIST ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- PARTS LISTED BELOW ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- DOCUMENTATION IN MANUFACTURERS FILE TO BE SUBMITTED AS REQUIRED AT A LATER DATE.
- DOCUMENTATION ATTACHED/SHIPPED SEPARATELY.
- PART NUMBER(S) 03-341-04-AE IS/ARE EQUAL TO OR BETTER THAN THAT WHICH WAS ORIGINALLY ORDERED.

Q. L. Mills  
L. L. MILLS MANAGER - Quality Engineering  
TRANSAMERICA DELAVAL, INC. REPRESENTATIVE

11-12-83  
DATE

PURCHASE ORDER NUMBER:

NA  
CUSTOMER REPRESENTATIVE

NA  
DATE

STONE & WEBSTER ENGINEERING CORPORATION  
 QUALITY ASSURANCE DEPARTMENT  
 PRODUCT QUALITY CERTIFICATION

T-376A-

PAGE 1 OF 1

PURCHASER <i>Louisiana Lighting Company</i>	J.O. <i>11600.37</i>	P.O. NO. <i>310553</i>	CHANGE NO. <i>M/C 32</i>
PROJECT <i>SURCHAM Nucleonics SA #1</i>	SPEC. NO. <i>SM-89</i>	REVISION <i>2 1-26-83</i>	ADDENDA <i>N/A</i>
SELLER/ADDRESS <i>TRANSAMERICA DELAWARE INC 550 85TH ST. OAKLAND, CA 94621</i>			
DOCUMENTATION REQUIRED YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	QA CAT. <i>1</i>	SHIPPING RELEASE TAG NUMBER(S) <i>47260</i>	

I HEREBY CERTIFY THE PRODUCT(S) IDENTIFIED HEREIN HAVE BEEN INSPECTED IN ACCORDANCE WITH S&W PROCUREMENT QUALITY ASSURANCE REQUIREMENTS AND ARE ACCEPTABLE FOR SHIPMENT.

CHECK BLOCKS AS APPLICABLE

- AUTHORIZED DEVIATIONS AND NONCONFORMANCES HAVE BEEN NOTED BELOW.
- ALL SPECIFIED SUPPORTING DOCUMENTATION HAS BEEN REVIEWED AND FORWARDED TO S&W PROCUREMENT QUALITY ASSURANCE FOR DOCUMENTATION REVIEW.
- DOCUMENTATION PREVIOUSLY SUBMITTED.
- DOCUMENTATION TO REMAIN IN SELLER'S FILES.

<u>ITEM NO.</u>		<u>QUANTITY</u>
<i>3</i>	<i>P/N 03-341-04-AG</i>	<i>17 EA.</i>
	<u>S/N. No.</u> <u>HT. No.</u>	
	<i>G33 - 312K</i>	
	<i>G34 - 312K</i>	
	<i>G4 - 298K</i>	
	<i>G2 - 298K</i>	
	<i>G1 - 298K</i>	
	<i>F87 - 298K</i>	
	<i>F58 - 256K</i>	
	<i>F56 - 256K</i>	
	<i>F7 - 181K</i>	
	<i>E8 - 104K</i>	
	<i>C89 - 8115</i>	

NAME (PRINTED) *W.F. Whitten* TITLE *DISTRICT MANAGER*

NAME (SIGNED) *W.F. Whitten* DATE *1-4-83* IRI NO. *51105509012*

AUTHORIZED DEVIATIONS AND NONCONFORMANCES

STONE & WEBSTER ENGINEERING CORPORATION  
**SHIPPING RELEASE TAG**

J. O. NO. 11600137 P. O. NO. 310552-32

SPECIFICATION TITLE  
DIESEL GENERATOR 5675

SPEC. DATE 1-26-83 SPEC. NO. 541-89 ADDENDA THRU NO. N/A

SELLER OR CONTRACTOR  
TRANSAMERICA DELAWARE, INC

SHIPPED BY  
AMERICAN AIRLINES

EQUIPMENT OR MATERIAL LISTED IS HEREBY  
 RELEASED FOR SHIPMENT:

MARK NO. SEE SN BELOW

QUANTITY 11 EA.

DESCRIPTION PISTON SKIRTS

SN No.	HT. No.	SN No.	HT. No.
1. G33	- 312K	8. F56	- 256K
2. G34	- 312K	9. F7	- 181K
3. G4	- 298K	10. E8	- 104K
4. G2	- 298K	11. C89	- 811J
5. G1	- 298K		
6. F87	- 298K		
7. F58	- 256K		

REQUIRED DOCUMENTATION IS COMPLETE

S & W INSPECTOR H.F. Whitten DATE 11/12/83 TAG NO. 47260

4-8885-00

ORIGINAL  
WAYNE  
POLICE

ISSUED TO Martha Pulte DATE 11/13/83

COA INSPECTED [Signature] DATE 11/13/83

P.O. NO. 910552-32 REQ. NO. F 77679 OF T. BROWN

VENDOR TRANS. AMERICA. DE LAVAL.

SHIPPER TRANS AM. DE LAVAL SHIPPERS NO. 20338

DATE REC'D 11-13-83 CHECKED BY [Signature] MRR NO. 05047

SHIPPED VIA AMERICAN AIRLINES.

PRO NO. 001 5658745 NO. OF CTNS 11 WEIGHT 3553.

STORAGE LOCATION \_\_\_\_\_ STORE REQ NO \_\_\_\_\_

NOTED 6110 INITIATED DUE TO DOC. MISSING - HEAT TREAT CYCLE INFO MISSING - CONDITIONAL RELEASE 447 - INITIATED TO RELEASE ALL 11 SKIRTS.

P.O. ITEM NO.	QTY	DESCRIPTION	COMP. ID
1	11	PISTON SKIRT. P/N. 03-341-04 AE	<u>[Signature]</u>



**Transamerica**  
**Delaval**

R-33615

Engine and Compressor Division  
550 55th Avenue  
P.O. Box 2181  
Oakland, California 94621  
(415) 577-7400 Telex: 335-304

TAG  
R-33615

OUR NUMBER

DATE ENTERED  
11/09/83

MAIL TO: 5415  
LONG ISLAND LIGHTING CO.  
C/O STONE & WEBSTER ENG. CORP.  
P.O. BOX 604  
WADING RIVER, N.Y. 11792

ATTN:

SHIP TO:  
LONG ISLAND LIGHTING CO.  
SHOREHAM NUCLEAR POWER STATION  
1/2 MI. EAST OF WILLIAMS FLOYD  
PARKWAY, HIGHWAY 25A  
SHOREHAM, L.I. NEW YORK 11786

MARKINGS:

INVOICE NO.	INVOICE DATE	CUSTOMER REF. NUMBER
SHIPPING TAG	DATE SHIPPED	REQUESTED SHIP DATE
American Airlines 001 SFO 5668 7951		RECALL NO. OR TAX CODE
BL. OAK 11717	TERMS	NET 30 DAYS
PACKAGING	FOB POINT	ROUTING REQUEST
DOMESTIC AIR	FACTORY OAKLAND	AIR FREIGHT
PARTIAL SHIP YES	QUANTITY INSP NO	PPD/COL NO. INV PPD 04

ENGINE MODEL	SERIAL NUMBERS	CODE	SALES TAX	PRODUCT	BIG	TERRITORY	RENEW	STATE
DSR-48	74010 12		0	55508	491	20 25 58		33

ITEM	QTY	PART NUMBER	DESCRIPTION	SCHEDULED DATE	UNIT PRICE	QTY SHIPPED	ORDER BALANCE	BOX NO.	EXTENDED PRICE
INVOICE CUSTOMER FOR FREIGHT									
1	96	03-341-04-AC	COLLAR, THRUST						
2	96	03-341-04-AD	LOK-TAB						
3	24	03-341-04-AE	SKIRT						
4	96	03-341-04-AF	GUIDE, SPRING						
5	96	GC-023-000	GROOVER, PIN						
6	96	03-341-04-AB	STUD						
ACCOUNTING INFORMATION									
65,201 N-344-3									
<div style="font-size: 4em; font-weight: bold; opacity: 0.5;">NUCLEAR</div>									
<p>MRR-05047</p> <p>310 552-52</p> <p>F 77679</p> <p>T. Pro A.</p>									

ORDER WRITER  
LP

We hereby certify that these goods were produced in compliance with all applicable requirements of Sections 6, 7 and 12 of the Fair Labor Standards Act, as amended, and of regulations and orders of the United States Department of Labor issued under Section 14 thereof. No goods returned without our written permission. Deliveries contingent upon strikes, fires, accidents or other delays beyond our control. Goods proving defective will be replaced. No claims for damages or labor will be allowed. We are not responsible for loss of patterns due to fire.

PAGE NUMBER  
1

The Attached "Conditions Of Sale" Are Part Of This Document.

P.O. 310552-32 Trans America Deland

7ea. Piston Skirt # 03-341-04AE  
S/N's F-97, F-98, G-5, G-24, G-29, G-30  
and G-35

Cal. I

SMI-089

### RECEIVING INSPECTION REPORT

SHOREHAM NUCLEAR POWER STATION  
UNIT - 1

STONE B WEBSTER ENGINEERING CORPORATION

DATE RECEIVED	11-16-83	NRR NUMBER	83-15053	PARTIAL COMPLETE	<input checked="" type="checkbox"/>
STORAGE LEVEL	A B C D	DOC HOLD/REFLECT TO NO	N/A	NBD REPORT NO	6115
<input checked="" type="checkbox"/> SAT	<input type="checkbox"/> UNSAT	SIGNATURE <i>R. Perroy</i>		DOCUMENTATION REVIEW	DATE
REMARKS		POA Doc. Locking Mt. Treat. Record Mtl. Conditionally Released			
SRT #		47261			
SAT	UNSAT	INSPECTOR SIGNATURE <i>R. Perroy</i>		DATE	11-16-83
RELEASED FOR CONSTRUCTION USE		YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>		FORM NO I-58	

OC CONTROL NO. IF REQUIRED

N/A

R-33615

Transamerica Delaval Inc.  
Engine and Compressor Division  
550 85th Avenue  
P.O. Box 216T  
Oakland, California 94621

CERTIFICATE OF COMPLIANCE

TO: Long Island Lighting Company  
96 Stoe & Webster Engineering Corp.  
P.O. Box 604  
Wading River N.Y. 11792



SHOREHAM NUCLEAR POWER STATION - UNIT 1

REFERENCE PURCHASE ORDER NUMBER: 310552-32

SUPPLIER: Transamerica Delaval Inc.

WE HEREBY CERTIFY THAT THE PRODUCTS OR SERVICES FURNISHED ON THE ABOVE REFERENCE PURCHASE ORDER MEET THE REQUIREMENTS OF THE APPLICABLE DRAWINGS AND/OR SPECIFICATIONS. SM1-89

- PARTS LISTED ON THE ATTACHED PACKING LIST ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- PARTS LISTED BELOW ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- DOCUMENTATION IN MANUFACTURERS FILE TO BE SUBMITTED AS REQUIRED AT A LATER DATE.
- DOCUMENTATION ATTACHED/SHIPPED SEPARATELY.
- PART NUMBER(S) 03-341-04-AE (ITEM #3 ONLY) IS/ARE EQUAL TO OR BETTER THAN THAT WHICH WAS ORIGINALLY ORDERED.

L. L. Mills  
L. L. MILLS MANAGER - Quality Engineering  
TRANSAMERICA DELAVAL, INC. REPRESENTATIVE 11-15-83  
DATE

NA NA  
CUSTOMER REPRESENTATIVE DATE

PURCHASE ORDER NUMBER:

**STONE & WEBSTER ENGINEERING CORPORATION  
QUALITY ASSURANCE DEPARTMENT  
PRODUCT QUALITY CERTIFICATION**

T-376A-

PAGE 1 OF 1

PURCHASER <i>Louisiana Lignoring Company</i>	J.D. <i>11600.37</i>	P.O. NO. <i>310552</i>	CHANGE NO. <i>M/C 32</i>
PROJECT <i>SUREVAN Nuclear Power Sta. #1</i>	SPEC. NO. <i>SAI-89</i>	REVISION <i>2 1-26-83</i>	ADDENDA <i>N/A</i>
SELLER/ADDRESS <i>TRANSAMERICA DELAVAL, INC. 550 85th. AVENUE OAKLAND CA. 94621</i>			
DOCUMENTATION REQUIRED YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	QA CAT. <i>I</i>	SHIPPING RELEASE TAG NUMBER(S) <i>47261</i>	

I HEREBY CERTIFY THE PRODUCT(S) IDENTIFIED HEREIN HAVE BEEN INSPECTED IN ACCORDANCE WITH S&W PROCUREMENT QUALITY ASSURANCE REQUIREMENTS AND ARE ACCEPTABLE FOR SHIPMENT.

CHECK BLOCKS  
AS APPLICABLE

- AUTHORIZED DEVIATIONS AND NONCONFORMANCES HAVE BEEN NOTED BELOW.
- ALL SPECIFIED SUPPORTING DOCUMENTATION HAS BEEN REVIEWED AND FORWARDED TO S&W PROCUREMENT QUALITY ASSURANCE FOR DOCUMENTATION REVIEW.
- DOCUMENTATION PREVIOUSLY SUBMITTED.
- DOCUMENTATION TO REMAIN IN SELLER'S FILES.

<u>ITEM NO.</u>	<u>QUANTITY</u>
<i>3</i>	<i>7 EA.</i>
<i>P/N-03-341-04-AE</i>	
<i>S/N-F97</i>	<i>HT-289K</i>
<i>S/N-F98</i>	<i>HT-289K</i>
<i>S/N-G'5</i>	<i>HT-298K</i>
<i>S/N-G26</i>	<i>HT-312K</i>
<i>S/N-G29</i>	<i>HT-312K</i>
<i>S/N-G30</i>	<i>HT-312K</i>
<i>S/N-G35</i>	<i>HT-312K</i>

NAME (PRINTED) *W.F. Whitten* TITLE *DISTRICT MANAGER*

NAME (SIGNED) *W.F. Whitten* DATE *11-15-83* IN NO. *5110552-9013*

AUTHORIZED DEVIATIONS AND NONCONFORMANCES  
*EYDCR F-46324, DYO. 11-9-83*

ISSUED TO: \_\_\_\_\_ DATE \_\_\_\_\_  
 COA INSPECTED Osuna DATE 11-16-83  
 P.O. NO. 310 552-32 REQ. NO. F77679 OF \_\_\_\_\_  
 VENDOR Transamerica Delaval Inc  
 SHIPPER Transamerica Delaval Inc SHIPPERS NO. R-33615  
 DATE REC'D 11-16-83 CHECKED BY H. Allen MRR NO 83-05053  
 SHIPPED VIA Flying Tigers  
 PRO NO. 6311 4052 NO. OF CTNS. 8 WEIGHT 2337 (lbs)  
 STORAGE LOCATION \_\_\_\_\_ STORE REQ NO. \_\_\_\_\_  
 CONDITIONAL RELEASED ON #448  
 REQUIRE HEAT TREATS. Osuna #11/16/83

P.O. ITEM NO.	QTY	DESCRIPTION	COMP. ID
1	7	Piston skirt #03-341-04AE	

**Transamerica Delaval**  
R-33615

Transamerica Delaval Inc.  
Engine and Compressor Division  
550 85th Avenue  
P.O. Box 2181  
Oakland, California 94621  
(415) 577-7400 Telex: 335-304

**SHIPPING TAG**  
R-33615

DATE ENTERED  
11/10/83

MAIL TO: 5415  
LONG ISLAND LIGHTING CO.  
C/O STONE & WEBSTER ENG. CORP.  
P.O. BOX 604  
WADING RIVER, N.Y. 11792

SHIP TO:  
LONG ISLAND LIGHTING CO.  
SHOREHAM NUCLEAR POWER STATION  
1/2 MI. EAST OF WILLIAMS FLOYD  
PARKWAY, HIGHWAY 25A  
SHOREHAM, L.I. NEW YORK 11786

MARKINGS:

INVOICE NO.	INVOICE DATE	CUSTOMER REF. NUMBER
		310552-12
SHIPPING TAG	DATE SHIPPED	REQUEST TO SHIP DATE
	11-15-83	11-11-83
CARRIER FLYING TIGERS 18 BOXES @ 2.337# 11742		REBATE NO. OR TAX CODE
TERMS NET 30 DAYS		
PACKAGING DOMESTIC AIR		F.O.B. POINT FACTORY OAKLAND
PARTIAL SHIP	QTY SHIP	PPD/COL
YES	NO	PPD 04
ROUTING REQUEST AIR FREIGHT		

ENGINE MODEL	SERIAL NUMBER	CODE	SALES TAX	PRODUCT	QC	TERRITORY	REVISED	STATE
DSR-48	74010 12		0	55508	491	20 25 58		33

ITEM	QTY	PART NUMBER	DESCRIPTION	SCHEDULED DATE	UNIT PRICE	QTY SHIPPED	ORDER BALANCE	BOX NO.	EXTENDED PRICE
			REV. 01-11-09-83 CHG. QTY'S ITEMS 1-6, ADD ITEM 7. TOTAL CHG. CUST. P.O. & REQ. DATE.						
			INVOICE CUSTOMER FOR FREIGHT						
	104	03-341-04-AC	COLLAR, THRUST ✓						
	104	03-341-04-AD	LOK-TAB ✓						
	26	03-341-04-AE	SKIRT ✓						
	104	03-341-04-AF	GUIDE, SPRING ✓						
	104	GC-023-000	GROOVER, PIN ✓						
	104	03-341-04-AB	STUD ✓						
	100	GC-002-005	COTTER PIN 1/16X 1 1/4 ✓						
			ACCOUNTING INFORMATION						
			65,201 N-344-3						

MAR-83-0502  
310552-3  
F7X  
181C

**INVOICE**

310552-3



**STONE & WEBSTER ENGINEERING CORPORATION  
 QUALITY ASSURANCE DEPARTMENT  
 PRODUCT QUALITY CERTIFICATION**

T-376A- PAGE OF

PURCHASER <i>Lockport Housing Company</i>	J.O. <i>1155-87</i>	P.O. NO. <i>22557</i>	CHANGE NO. <i>-32--</i>
PROJECT <i>Lockport Housing Project #1</i>	SPEC. NO. <i>541-89</i>	REVISIONS <i>2 1-26-83</i>	ADDEND. <i>N/A</i>
SELLER/ADDRESS <i>550 85th Avenue Temperance Downs, Inc. Ocean City, NJ 08221</i>			
DOCUMENTATION REQUIRED YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	QA CAT. <i>1</i>	SHEET TO BE RELEASED TO BUYER <i>42297</i>	

I HEREBY CERTIFY THE PRODUCT(S) IDENTIFIED HEREIN HAVE BEEN INSPECTED IN ACCORDANCE WITH  
 NEW JERSEY PRODUCT QUALITY ASSURANCE REQUIREMENTS AND ARE ACCEPTABLE FOR SHIPMENT.

CHECK BLOCKS  
 AS APPLICABLE

- AUTHORIZED DEVIATIONS AND NONCONFORMANCES HAVE BEEN LISTED BELOW.
- ALL SPECIFIED SUPPORTING DOCUMENTATION HAS BEEN REVIEWED AND FORWARDED TO BUYER FOR DOCUMENTATION REVIEW.
- DOCUMENTATION PREVIOUSLY SUBMITTED.
- DOCUMENTATION TO REMAIN IN SELLER'S FILES.

ITEM NO. 3 P/N 03-341-04-RE QUANTITY 8 EA.

<u>HT. No.</u>	<u>Series</u>
1. 200K	F15
2. 200K	F24
3. 200K	F18
4. 827J	C88X
5. 937J	D42
6. 181K	F12
7. 200K	F21
8. 205K	F35

NAME (PRINTED) W.F. Whitten TITLE District Manager

NAME (SIGNED) W.F. Whitten DATE 11/11/83 IR NO. 51105529011

AUTHORIZED DEVIATIONS AND NONCONFORMANCES  
E#DCK # F-4032A, DTD. 11-9-83



STATE OF TEXAS  
 DEPARTMENT OF TRANSPORTATION  
 PUBLIC SAFETY DIVISION

J.C.T.D. 11600 37		P.O. # 310997-32	
COLLISION CODE Dist. Collision			
DATE 1-26-83	TIME 4:48	FILE NO.	
SHIPMENT CONTAINER Transportation Services, Inc. Houston, Texas			
EQUIPMENT OR MATERIAL LISTED IS HEREBY RELEASED FOR SHIPMENT:			
MARK NO.	500 D11 Balm		
QUANTITY	9 Pcs.		
DESCRIPTION	Auto Parts		
HT #	PL #		
1. 200K	F15		
2. 200K	F21		
3. 200K	F18 4		
4. 227J	C28X		
5. 937J	D42		
6. 181K	F12		
7. 200K	F21		
8. 205K	F35 5		
<input checked="" type="checkbox"/> REQUIRED DOCUMENTATION IS COMPLETE			
S & W INSPECTOR J.F. Whitten	DATE 1/11/83	TAG NO 47258	

Transamerica Delaval Inc.  
Engine and Compressor Division  
850 Bush Avenue  
P.O. Box 2101  
Oakland, California 94621

K-35615  
83-755

CERTIFICATE OF COMPLIANCE

TO: Long Island Lighting Company  
Electric Utility Engineering Dept.  
Part # 101  
Utility Dept. NY State



REFERENCE PURCHASE ORDER NUMBER: 310552-01  
SUPPLIER: Transamerica Delaval Inc.

WE HEREBY CERTIFY THAT THE PRODUCTS OR SERVICES REFERENCED ABOVE UNDER ABOVE REFERENCE PURCHASE ORDER MEET THE REQUIREMENTS OF THE APPLICABLE DRAWINGS AND/OR SPECIFICATIONS. 11-11-83

- PARTS LISTED ON THE ATTACHED PACKING LIST ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- PARTS LISTED BELOW ARE SPECIFICALLY COVERED BY THIS CERTIFICATE.
- DOCUMENTATION IN MANUFACTURERS FILE TO BE SUBMITTED AS REQUIRED AT A LATER DATE.
- DOCUMENTATION ATTACHED/SHIPPED SEPARATELY.
- PART NUMBER(S) 29-324-04-15 IS/ARE EQUAL TO OR BETTER THAN THAT WHICH WAS ORIGINALLY ORDERED.

Q. O. Mills  
L. L. HILLS MANAGER - Quality Engineering 11-11-83  
TRANSAMERICA DELAVAL, INC. REPRESENTATIVE DATE

4/3 11/3  
CUSTOMER REPRESENTATIVE DATE

2025 RELEASE UNDER E.O. 14176

LI 002281  
R-33615

P.O. Box 2161  
Oakland, California 94621  
(415) 577-7400 Telex 315-004

ORDER  
R-33615

OUR NUMBER  
REV. 1

DATE ENTERED  
11/10/83

MAIL TO: 5415  
LONG ISLAND LIGHTING CO.  
C/O STONE & WEBSTER ENG. CORP.  
P.O. BOX 604  
MADING RIVER, N.Y. 11792

SHIP TO:  
LONG ISLAND LIGHTING CO.  
SHOREHAM NUCLEAR POWER STATION  
1/2 MI. EAST OF WILLIAMS FLOYD  
PARKWAY, HIGHWAY 25A  
SHOREHAM, L.I. NEW YORK 11795

NO. OF TO	NO. OF DAY	310552-0000
NO. OF TAG	DATE	11-11-83
REMARKS		NET 30 DAYS
FACTORY ORDER NO.		FACTORY ORDER NO.
AIR FREIGHT		AIR FREIGHT

ENGINE MODEL	SERIAL NUMBER	CODE	TYPE	QUANTITY	UNIT PRICE	TOTAL
DSR-48	74010 12					

REV. 01-11-09-83 CIG. QTY'S  
ITEMS 1-8, ADD ITEM 7. TOTAL  
CHG. CUST. P.O. & REQ. DATE.

INVOICE CUSTOMER FOR FREIGHT

1	104	03-341-04-AC
2	104	03-341-04-AD
3	26	03-341-04-AE
4	104	03-341-04-AF
5	104	GC-023-000
6	104	03-341-04-AB
7	100	GC-002-005

COLLAR, THRUST  
LOK-YAB  
SKIRT  
GUIDE, SPRING  
GROOVER, PIN  
STUD  
CUTTER PIN

85.95  
16.00  
12.00  
12.00  
12.00  
12.00  
12.00

3,738.00  
717.60  
144,000.00  
52,778.40  
104.00  
9,001.20  
100.00  
133,634.00

ACCOUNTING IN OREGON

65.201 N-344-3



ITEM (3) ONLY

ORDER WRITER  
LP

We hereby certify that these goods were produced in compliance with all applicable requirements of Sections 6, 7 and 12 of the Fair Labor Standards Act, as amended, and of regulations and orders of the United States Department of Labor issued under Section 11 thereof. No goods returned without our written permission. Deliveries contingent upon strikes, fires, accidents or other delays beyond our control. Goods proving defective will be replaced. No claims for damages or labor will be allowed. We are not responsible for loss of patterns due to fire.

The Attached "Conditions Of Sale" Are Part Of This Document.

PAGE NUMBER  
1

ISSUED TO [Signature] DATE 12/9/83  
 OQA INSPECTED [Signature] DATE 12/8/83  
 P.O. NO. 310552-32 REQ. NO. F77679 OF 1  
 VENDOR TRANSAMERICA DELAVAL  
 SHIPPER TRANSAMERICA DELAVAL SHIPPERS NO. R-33615  
 DATE REC'D 11/12/83 CHECKED BY BDAMBROSIO MRR NO. 05046  
 SHIPPED VIA FLYING TIGERS  
 PRO NO. 6311-4100 NO. OF CTNS 9 WEIGHT 2,688  
 STORAGE LOCATION \_\_\_\_\_ STORE REQ NO. \_\_\_\_\_

Exempted - Tag # 19623 - NID 16107 of 11/12/83

P.O. ITEM NO.	QTY	DESCRIPTION	COMP. ID
1	1	PISTON SKIRT P/N 03-341-04-AE Released to el. US for check out 11/23/83 [Signature] OPS x271	





CERTIFICATE OF COMPLIANCE

REFERENCE: SPECIFICATION NO. SH1-89

Stone & Webster Engineering Corp.

FOR Shoreham Nuclear Power Station

Unit #1 Long Island Lighting Company

Long Island, New York


SUPPLIER: Transamerica Delaval Inc. - Engine & Compressor Division

COMPONENTS: Emergency Diesel Generator Engines fitted with:

- 3 ea. 1A-7046 Crankshaft Assembly
- 24 ea. 03-341-04-AE Skirts, Piston
- 24 ea. 1A-5718 Con Rod Assembly
- 48 ea. 03-340-05-AE Shells, Con Rod
- 2 ea. 03-310-03-AE Shell, Rear Main .080" O.S. on O.D.
- 24 ea. 03-441-01-OP Pipe, Cyl. Head to A/S Manifold
- 96 ea. 02-390-01-OJ Rocker Arm Shaft Bolt
- 3 ea. AK-007-000 Coupling
- 3 ea. 03-402-04-AA Coupling Adapter
- 3 ea. 03-402-04-AB Governor Drive Coupling
- 3 ea. 102568 Idler Gear Locknut (Field Rework).


We have reviewed the above drawings and made comparisons to those originally supplied. Since the engine generator system as originally supplied was covered by a Certificate of Compliance, this document will address only the above listed parts.

As detailed in the attachments, we conclude that the new components either retain or improve on their functional and seismic adequacy over those originally supplied. The attachments consist of eleven pages.

  
\_\_\_\_\_  
Roland T.M. Yang  
Manager, Applied Mechanics

Date

3-6-84

  
\_\_\_\_\_  
G.E. Trussell  
Manager, Engineering & Customer Service

Date

3-6-84

NOTED MAR 24 1984 A.J. ASQUINO



# Transamerica Engine Calculations Delaval

74010		
ENGINE	ASSY	NO

COMPARISON OF AS DELIVERED ENGINE COMPONENTS WITH  
REPLACEMENT ENGINE COMPONENTS

SHEET 1 OF 2

DATE: January 9, 1984

PART NO.

PISTON SKIRT

BY: David Beck

The engine components compared will be denoted as:

Old = As delivered engine components

New = Replacement engine components

Old:

03-340-04-AF

Wall thickness at ring grooves: .75"

Boss radius at piston pin: 4.375"

Pin bore hardness: 217-270-BHN

New:

03-341-04-AE

Wall thickness at ring grooves: .97"

Boss radius at piston pin: 4.5"

Pin bore hardness: 255-293 BHN

Material is the same for both piston skirts. Changes were made to improve rigidity, reduce stress and facilitate casting:

Section C-C on drawing 03-341-04-AE shows the boss outside radius to be 4-1/2", (from 4-3/8" for the old design). This was done to eliminate the rib in the old design and still maintain structural integrity.

Section Y-Y on drawing 03-341-04-AE shows the increased "Tie" between the bolt boss and the skirt. This was done to improve the bolt boss rigidity and reduce stress concentration.

Section C-C on drawing 03-341-04-AE shows a tapered rib to the left of the piston pin centerline. This tapered rib was added to improve the rigidity of the piston skirt.

The nodular iron skirt has passed through several design changes. The following identifies and describes several design iterations of the piston skirts:

1. "AF" piston, 03-340-04-AF

- a. This design was supplied in the LILCO/Shoreham, Southern California Edison/San Onofre and Mid South Energy/Grand Gulf engines.

During field testing several "AF" modified skirts at LILCO were found to have linear indications and one was found to have a crack near a stud bore. This crack finding is the reason for our LOCFR21 letter of November 16, 1983. At this writing, four (4) skirts have been examined at Grand Gulf where linear casting indications were found on two (2) skirts. The indications were easily removed by light grinding and polishing. There is absolutely no evidence of cracks with any depth.

Linear indications should not be taken lightly, however they should not be regarded indiscriminately as "failures". Indications may be casting surface imperfections, scratches, or machining marks. They could contribute to fatigue cracks and should therefore be tested by grinding or polishing. Generally faint indications are not crack contributors and through experience may be left as found. Overly zealous inspections with very sensitive instruments often mislead one to assume there are cracks where none exist.



# Transamerica Engine Calculations Delaval

74010  
ENGINE ASSY NO

COMPARISON OF AS DELIVERED ENGINE COMPONENTS WITH  
REPLACEMENT ENGINE COMPONENTS.

SHEET 2 OF 2

DATE January 9, 1964

PART NO.

PISTON SKIRT

BY David Beck

2. All "AF" style piston skirts were cast using the following heat treatment.
  - a. Heat to 1750 degrees F. (near the upper critical temperature) for 3 hours. Normalized (air cooled) in still air. Result: a pearlitic structure and 100,000 PSI tensile strength.
  - b. Re-heat to 1050 degrees F. (slightly below the lower critical temperature) for 3 hours and cool in still air. This is a tempering process used to produce the desired ductility in the nodular iron.
3. "AE" 03-341-04-AE  
This is the present standard R-4 piston skirt design. The design incorporates the knowledge we have gained through our field experience on the R-4 series engine as well as from our updated R-5 series engine, just concluding research and development testing.

All "AE" skirts are heat treated to product stress relieved 100,000 PSI tensile strength nodular iron. Successful operating experience with the "AE" skirts includes a 16 cylinder R-4 unit rated 7000 kw, 450 rpm, 225 bmep which has accumulated over 7000 hours of operating without a problem, and 687 hours operation on the R-5 test engine at 514 rpm, and 302 bmep.

The "AE" style skirt is interchangeable with existing R-4 piston crown and requires only minor hardware changes.

The connection of the bolt boss to the skirt wall with a more substantial section on piston skirt "AE" is an improvement designed to eliminate the indications found in this area on skirt "AF".

The new piston skirt's adequacy is improved as noted above and offers a substantial refinement in the "AE" skirt design.



Engine Cylinder Pressure Logs

EDG 101, 102, 103

Pre-crankshaft Failure

TCN #1

TABLE V

*Data Reviewed  
by WJ Cook  
7/5/83*

ENGINE CYLINDER PRESSURE LOG

Step Number Date/Time	STEP E.E.2							
ENGINE CYLINDER								
PRESSURE								
1	<del>1530</del>							
2	1500							
3	1550							
4	1550							
5	1560							
6	1550							
7	1570							
8	1530							
LOAD								

*Data recorded by  
[Signature] 6/29/83*

UNCONTROLLED  
For Information Only

PT. 307 011B-1

TCR 11

TABLE V

ENGINE CYLINDER PRESSURE LOG

Step Number	
Date/Time	8.82
ENGINE CYLINDER	
PRESSURE	
1	1550 <sup>psi</sup>
2	1610 <sup>psi</sup>
3	1600 <sup>psi</sup>
4	1548 <sup>psi</sup>
5	1628 <sup>psi</sup>
6	1638 <sup>psi</sup>
7	1688 <sup>psi</sup>
8	1678 <sup>psi</sup>
LOAD	3.5mw

*19.79*

LILCO O.  
REVIEWED  
BY *A. J. [unclear]*  
DATE 7/5/82

LILCO O.  
REVIEWED  
BY *[Signature]*  
DATE 7/8/82

UNCONTROLLED  
EDG Information Only

TCN 2

TABLE V

UNCONTROLLED  
Ext Information Only

ENGINE CYLINDER PRESSURE LOG

Step Number  
Date/Time

STEP 6.2  
6.

ENGINE CYLINDER

PRESSURE

1

1550  
\* 1600

2

1490

3

1520

4

1530

5

1580

6

1500

7

1500

8

1510

LOAD

3.5mm

M. D. Quaff  
6/23/83

Engine Cylinder Pressure Logs

EDG 101, 102, 103

Post-crankshaft Replacement

UNCONTROLLED  
For Information Only

PT.307.004A-2

EDG 101

APPENDIX F

ENGINE CYLINDER PRESSURE LOG

Step No.	8.8.2	
Date	4/11/84	
Time	2200	
ENGINE/CYLINDER PRESSURE (PSIG)	EDG 101	
1	1720	
2	1640	
3	1640	
4	1640	
5	1650	
6	1700	
7	1680	
8	1700	
Gen. Load (KW)	3500	
Var Loading (KVAR)	2700	

Data taken by: *[Signature]*

12

JTG APPROVED NOV 8 1983

PT.307.004B-3

UNCONTROLLED  
For Information Only

## APPENDIX F

ENGINE CYLINDER PRESSURE LOG

Step No.	8.14.2	
Date	3-17-84	
Time	02:25	
ENGINE CYLINDER PRESSURE (PSIG)		
1	1620	
2	1630	
3	1680	
4	1650	
5	1620	
6	1600	
7	1650	
8	1620	
GEN Load (KW)	3528	
Var Loading (KVAR)	2625	

Data taken by:

*John W. McCreedy* *John M. Walsh*

BTG APPROVED JAN 26 1984

UNCONTROLLED  
For Information Only

APPENDIX F

ENGINE CYLINDER PRESSURE LOG

Step No.		8.8.2	
Date		4-10-84	
Time		0555	
ENGINE CYLINDER PRESSURE (PSIG)			
1		1620	
2		1640	
3		1680	
4		1500	
5		1590	
6		1680	
7		1550	
8		1670	
Gen Load (KW)	PC	3595	
Var Loading (KVAR)	CR	2675	
Data taken by:	L. M. J. [Signature]		

12

RACK SETTING  
43.0 MM  
#3 DIESEL TEST



Sample Preoperational Test Procedure

SHOREHAM I  
NUCLEAR POWER STATION  
STARTUP FORM 8.3

Preoperational Test Results Review and Approval

1. System No.       R43A
2. Preoperational Test No. PT.307.004.A-2
3. System EDG 101 Qualification Preoperational Test
4. Test Engineer William J. Cook
5. Lead Startup Engineer M.W. Herlihy
6. Attached for your review are:

Preoperational Test Results and Analysis

William J Cook 4/19/84  
Prepared by / Performed by

JC Clifford 4/19/84  
Reviewed by

MM Melby 4/19/84  
Reviewed by

WJ Herlihy 4/23/84  
Startup Manager Approval, Date

Preoperational Test Approval/Release For Performance  
(Startup #8.1)

System Checkout & Initial Operations Tests

Test Change Notice(s) (Startup #8.2)

7. Preoperational Test Results attached are Approved by the JTG

[Signature] 4/23/84  
SS Site Operations Manager

William W. Matzke 4/23/84  
S&W Advisory Operations Engineer

[Signature] 4/23/84  
Startup Manager

[Signature]  
JTG Chairman

4/23/84  
Date

July 29, 1982

REVISION 17

SHOREHAM  
NUCLEAR POWER STATION

START-UP FORM 8.3

PT. 307.00 4A-2 (WPM)

8. Preoperation Test Results attached are DISAPPROVED for the following reasons: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
JTG Chairman: Date

9. Authorization granted to STARTUP MANAGER to review complete system status and area status for purpose of negotiating system turnover to Production Department.

\_\_\_\_\_  
JTG Chairman: Date

10. System described herein has been thoroughly reviewed regarding testing, status of outstanding items, etc., and is ACCEPTED by the Production Department for conditional operation.

K-7

\_\_\_\_\_  
Startup Manager Date

\_\_\_\_\_  
Plant Manager Date

- Distr: Original - Preoperational Test Procedures
- Copies - JTG Chairman
- Startup Manager
- Lead Startup Engineer
- Test Engineer
- S&W Lead Advisory Engineer
- GE Operations Manager
- Vice President - Nuclear
- OQA Engineer

K-7

# TRANSMITTAL RECORD

UNCONTROLLED  
Information Only

TO: J. RIVELLO	DATE: 11/9/83
LOCATION: SHOREHAM NUCLEAR POWER STATION - UNIT NO. 1	W.O. NO.: 44430
BRIEF: STARTUP TEST PROCEDURE	PROJECT NO.: K.71.340

ITEM NO.	NO. OF COPIES	BILLS OF MATERIAL, DRAWINGS, SPEC. PERMITS, ETC.	TITLE
2U		PT. 307.004A-2	EMERGENCY DIESEL GENERATOR QUALIFICATION TEST

Remarks: Controlled copy issued to responsible Test Engineer, must be returned to PRC, as Test Engineers responsibility changes.

TCN # 1 4/6/84 C. Slater

	TYPE	ITEM'S
G. BISHOP (G.E.)	U	1 Ea.
L. BETTENHAUSEN (NRC)	U	1 Ea.
C. SLATER (PRC)	U	2 Ea.
C. SLATER (PRC)	O	1 Ea.
<u>E.J. YOUNGLING</u> / T.E.	C	1 Ea.
<u>M.W. HERLIHY</u> / L.S.E.C	C	1 Ea.

O - ORIGINAL                      C - CONTROLLED  
 WC - WORKING COPY              U - UNCONTROLLED

Department: LILCO STARTUP
By: C. SLATER
Transmittal Number: 10219

Forwarded To:	By:	Date:
Remarks:		

Preoperational Test Approval/Release  
For Performance

- 1. System No. R43A
- 2. Preoperational Test No. PT.307.004A-2
- 3. System: Emergency Diesel Generator 101

Qualification Preoperational Test

- 4. Test Engineer: William J. Cook
- 5. Lead Startup Engineer: M. W. Herlihy
- 6. Attached Preoperational Test Procedure is submitted for your Approval of content, format, acceptability and/or revision.

JTG Meeting Date Scheduled                      Startup Manager                      Date

- 7. Preoperational Test Approved by Operational Q.A.

Operational QA Engineer                      Date

- 8. Preoperational Test Approved by JTG for content, format, acceptability and/or revision.

G.E. Site Operations Mgr.  
S&W Advisory Operations Engr  
Startup Manager

Approval: JTG Chairman                      Date  
(constitutes JTG approval)  
Disapproval: JTG Chairman  
Date

Remarks \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

SHOREHAM I  
NUCLEAR POWER STATION  
STARTUP FORM 8.1

9. Attached Preoperational Test Procedure and completed Check-out & Initial Operations Tests with pertinent documents and comments are submitted for your "RELEASE FOR PERFORMANCE".

William J Cook      4/7/84  
Test Engineer      Date

10. Preoperational Test attached RELEASED FOR PERFORMANCE.

Approval: [Signature]  
Lead Startup Engineer  
4/9/84  
Date

Disapproval: \_\_\_\_\_  
Lead Startup Engineer  
Date \_\_\_\_\_

Remarks\*: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\*Recommendations For Partial Preop. Test, Revisions, Clarification, etc.

Distr: Original - Startup Manager  
Copies - Plant Manager, S&W Lead Advisory Engineer,  
GE Operations Manager, Lead Startup Engineer,  
LILCO Operational Q.A.

PROCEDURE REVISION TRANSMITTAL - ATTACHMENT 2  
PT.307.004A-2

September 12, 1983

E. J. Youngling

RECOMMENDATION TO VOID EDG PREOPERATIONAL TEST RESULTS  
Shoreham Nuclear Power Station - Unit 1  
W. O. No. 44430/48923


In view of the recent crankshaft failure of the 102 emergency diesel generator, a recovery program has been established to teardown and inspect all three (3) emergency diesel generators. This is being done to determine the extent of the crankshaft problems with these engines. This requires that all three (3) engine/generators be removed from their rooms, be totally disassembled, reassembled with the appropriate new parts and reinstalled back into their respective rooms.

Based on the above scope of work, it is recommended that the following preoperational test results be voided:

PT.307.001A-1	EDG-101	Mechanical Preop Test
PT.307.001B-1	EDG-102	Mechanical Preop Test
PT.307.001C-1	EDG-103	Mechanical Preop Test
PT.307.003A-1	EDG-101	Electrical Preop Test
PT.307.003B-1	EDG-102	Electrical Preop Test
PT.307.003C-1	EDG-103	Electrical Preop Test
PT.307.004A-1	EDG-101	Reliability Qualification
PT.307.004B-1	EDG-102	Reliability Qualification
PT.307.004C-1	EDG-103	Reliability Qualification
PT.307.005A	EDG-101	Load Test
PT.307.005B	EDG-102	Load Test
PT.307.005C	EDG-103	Load Test

These preoperational test results should be maintained on file with their cover sheets marked void or some suitable means to identify this action. It is also recommended that the above preoperational tests be revised accordingly to incorporate, as required, the many test change notices and exceptions taken against them.

In closure, I suggest that the above recommendations be presented to the full Joint Test Group for consideration. The minutes of this meeting would provide the formal direction to the Startup Organization for proceeding with these actions in accordance with the Startup Manual.

  
William M. Matejka  
Project Advisory Engineer

WMM:reom

cc: W. R. Klein  
M. W. Herlihy

JTG APPROVED NOV 8 1983

A13527

Revision 17  
July 29, 1982

UNCONTROLLED  
Ext Information Only

PROCEDURE REVISION TRANSMITTAL

Messrs: Startup Manager  
Plant Manager  
S&W Lead Advisory Engineer  
GE Operations Manager  
Operating Quality Assurance Engineer

Date: October 12, 1983

Procedure Type: P eoperational Test

Approved Procedure # PT.307.004A-1

Revised Procedure # PT.307.004A-2

Procedure Title: EMERGENCY DIESEL GENERATOR QUALIFICATION TEST

Shoreham Nuclear Power Station - Unit 1

The subject approved procedure has been revised (the new revision number is indicated above) and is being transmitted for your review in black on pink form. The procedure changes are identified in the margin. Listed below are the changes and the reasons for the changes. See attachments to this letter.

This transmittal will serve as the approval form and will be routed to OQA, if required, for signoff before being submitted to the JTG for approval.

After the change has been approved, revised pages will be issued in black on white form.

Should you have any comments, please notify the undersigned before: October 26, 1983

E. J. Youngling *E. J. Youngling*  
Test Engineer/Date

OQA Approved: *[Signature]* 11/7/83 Not Required: Lead Startup Engineer  
Required: *[Signature]* 11/7/83 Lead Startup Engineer

*[Signature]* 11/8/83 Approved: *[Signature]* 11/8/83  
GE Operations Manager JTG CHAIRMAN Date

*[Signature]* 11/8/83 Remarks: \_\_\_\_\_  
S&W Lead Advisory Engineer

*[Signature]* 11-8-83  
Startup Manager



PT.307.004A-2

CONTROLLED  
Information Co.

PROCEDURE REVISION TRANSMITTAL  
ATTACHMENT 1  
PT.307.004A-2

Revision 2 to PT.307.004A incorporates TCN numbers 1 and 2 and appropriate exceptions taken against Revision 1. In addition, certain procedural requirements were added such as requirements to perform cylinder head leak check at 4, 8, and 12 hours after shutdown, update references, measure diesel room humidity before and during testing, and document baseline diesel generator performance at 0.8 power factor.

JTG APPROVED NOV 8 1983  
A13529

UNCONTROLLED  
For Information Only

# TRANSMITTAL RECORD

J. RIVELLO	DATE 04-06-83
LOCATION: SHOREHAM NUCLEAR POWER STATION - UNIT NO. 1	W.O. NO. 44430
BRIEF: STARTUP TEST PROCEDURE	PROJECT NO.: K.71.340

ITEM NO.	NO OF COPIES	BILLS OF MATERIAL, DRAWINGS, SPEC, PERMITS, ETC.	TITLE
2U			<u>PT. 307.004A-1 EMERGENCY DIESEL GENERATOR QUALIFICATION</u>

Remarks: Control copy issued to responsible Test Engineer, must be returned to PRC, as Test Engineers responsibility changes.

TCN #1 ~~99~~ 6/13/83  
TCN #2 ~~99~~ 6/15/83

	TYPE	ITEMS
G. BISHOP (G.E.)	U	1 Ea.
L. BETTENHAUSEN (NRC)	U	1 Ea.
C. SLATER (PRC)	U	2 Ea.
C. SLATER (PRC)	O	1 Ea.
<u>WM. COOK</u> / T.E.	C	1 Ea.
<u>WM. KERRIN</u> / L.S.E.C.	C	1 Ea.

O - ORIGINAL      C - CONTROLLED  
WC - WORKING COPY      U - UNCONTROLLED

Department: LILCO STARTUP
By: C. SLATER / J. BARONE
Transmittal Number: 9942

Forwarded To:	By:	Date:
---------------	-----	-------

Remarks:
----------

Revision 17  
July 29, 1982

UNCONTROLLED  
For Information Only

PROCEDURE REVISION TRANSMITTAL

Messrs: Startup Manager  
Plant Manager  
S&W Lead Advisory Engineer  
GE Operations Manager  
Operating Quality Assurance Engineer

Date: 2/22/83

17

Procedure Type: Preoperational Test  
Approved Procedure # PT.307.004A  
Revised Procedure # PT.307.004A-1  
Procedure Title: Emergency Diesel Generator Qualification

Shoreham Nuclear Power Station - Unit 1

The subject approved procedure has been revised (the new revision number is indicated above) and is being transmitted for your review in black on pink form. The procedure changes are identified in the margin. Listed below are the changes and the reasons for the changes.

This transmittal will serve as the approval form and will be routed to OQA, if required, for signoff before being submitted to the JTG for approval.

After the change has been approved, revised pages will be issued in black on white form.

Should you have any comments, please notify the undersigned before: March 4, 1983

William J Cook 2/22/83  
Test Engineer/Date

Not Required:

OQA Approved: W. M. Mulla 4/5/83 Required: W. R. Klein 4/5/83  
Lead Startup Engineer  
Lead Startup Engineer

17

[Signature] 4/5/83 Approved: J. Powell 4/5/83  
GE Operations Manager JTG CHAIRMAN Date

William M. Matusch 4/5/83  
S&W Lead Advisory Engineer

Remarks:

[Signature] 4/5/83  
Startup Manager

**VOID**

UNCONTROLLED  
For Information Only

# TRANSMITTAL RECORD

TO: J. RIVELLO	DATE: 11/9/81
LOCATION: SHOREHAM NUCLEAR POWER STATION - UNIT 1	WO. NO: 1430
BRIEF: STARTUP TEST PROCEDURE	PROJECT NO: K. 71.340

ITEM NO.	NO. OF COPIES	BILLS OF MATERIAL, DRAWINGS, SPEC, PERMITS, ETC.	TITLE
----------	---------------	--	-------

✓<sup>2U</sup> PT. 17.00.4A EMERGENCY DIESEL GENERATORS QUALIFICATION

Remarks: Controlled copy returned to PRC. d to responsible Test Engineer, must be returned to PRC. Test Engineers responsibility changes.

	TYPE	ITEMS
✓ R. PULSIFER (G.E.)	U	1 Ea.
✓ L. Bettenhausen (NRC)	U	1 Ea.
✓ C. Slater (PRC)	U	2 Ea.
✓ C. Slater (PRC)	O	1 Ea.
✓ <u>Wm. J. Cook</u> T.E.	C	1 Ea.
✓ <u>Wm. R. Klein</u> L.S.E.	C	1 Ea.

O - ORIGINAL      C - CONTROLLED  
WC - WORKING COPY      U - UNCONTROLLED

Department: LILCO STARTUP
By: C. SLATER
Transmittal Number: 9536

Forwarded To:	By:	Date:
Remarks:		

Preoperational Test Approval/Release  
For Performance

1. System No. R43  
2. Preoperational Test No. PT 307.004A  
3. System: EMERGENCY DIESEL GENERATORS QUALIFICATION

4. Test Engineer: William J Cook  
5. Lead Startup Engineer: William R Klein

6. Attached Preoperational Test Procedure is submitted for your Approval of content, format, acceptability and/or revision.

November 9, 1981 JTG Meeting Date Scheduled  
[Signature] Startup Manager 11/2/81 Date

7. Preoperational Test Approved by Operational Q.A.  
[Signature] Operational QA Engineer 11/2/81 Date

8. Preoperational Test Approved by JTG for content, format, acceptability and/or revision.

[Signature] 11/9/81  
S.S.W. Site Operations Mgr.  
[Signature] 11-9-81  
SSW Advisory Operations Engr  
[Signature] 11-9-81  
Startup Manager

Approval: [Signature] 11/9/81  
JTG Chairman Date  
(constitutes JTG approval)  
Disapproval: \_\_\_\_\_  
JTG Chairman  
\_\_\_\_\_  
Date

Remarks \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

SHOREHAM I  
NUCLEAR POWER STATION  
STARTUP FORM 8.1

UNCONTROLLED  
For Information Only  
REVISION 0

9. Attached Preoperational Test Procedure and completed Checkout & Initial Operations Tests with pertinent documents and comments are submitted for your "RELEASE FOR PERFORMANCE".

\_\_\_\_\_  
Lead Startup Engineer/Test Engineer      Startup Manager      Date

10. Preoperational Test attached RELEASED FOR PERFORMANCE.

\_\_\_\_\_  
G.E. Site Operations Mgr

\_\_\_\_\_  
S&W Advisory Operations Engr

\_\_\_\_\_  
Startup Manager

Approval: \_\_\_\_\_  
JTG Chairman  
(constitutes JTG approval)

\_\_\_\_\_  
Date

Disapproval: \_\_\_\_\_  
JTG Chairman

\_\_\_\_\_  
Date

Remarks\*: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\*Recommendations For Partial Preop. Test, Revisions, Clarification, etc.

Distr: Original - Startup Manager  
Copies - Plant Manager, S&W Lead Advisory Engineer,  
GE Operations Manager, Lead Startup Engineer,  
LILCO Operational Q.A.

PT.307.004A-2

## TEST ENGINEER'S ANALYSIS REPORT

EMERGENCY DIESEL GENERATOR 101 QUALIFICATION PREOP TEST

This revised Qualification Preoperational Test was "released for performance" on April 9, 1984 subsequent to the crankshaft replacement in the fall of 1983. The purpose of this test was to meet the testing requirements of USNRC Regulatory Guide 1.108, Rev. 1 section C.2.a (9) i.e. to demonstrate the ability of EDG101 to start, accept load, maintain load (greater than 50% of rated load) and to shutdown, without trips, 23 consecutive times.

Documentation of test parameters was accomplished via the use of General Electric's Transient Recording System (GETARS) which monitored and plotted start times and system parameters. GETARS produced numerical data (histograms) at selected periods during each of the 23 engine runs (i.e. start of 1 hour run,  $\frac{1}{2}$  hr. interval and 1 hour interval). GETARS plotted all engine shutdowns to verify no anomalies occurred which could have been interpreted as a failure of EDG101. Also during each engine run, operational logs (Appendix D) were maintained utilizing the process computer print out as the instrument of record for KW loads and GETARS as the instrument of record for all other electrical parameters (except Generator Field Voltage and Current) and engine speed. The remaining operating parameters were taken from local and control room indicators, or M&TE instruments. During engine operation, the Run Log (Appendix D) intervals were determined by use of a stop watch (M&TE) and not the engine hour meter.

All twenty-three (23) starts were completed in a successful consecutive manner. The "Quick Start" requirements (engine loaded  $> 3500$  KW  $\leq 60$  seconds) were met during Start 13, as a loading time of 21.4 seconds was obtained. All engine parameters were acceptable for operating conditions and no other items of concern were noted.

There were nine (9) exceptions taken against this procedure. These are summarized below. Full details of these exceptions are contained within the body of the procedure.

EXCEPTIONS 1; 5, 7, 9

These exceptions were taken to identify typographical errors, minor deviations from procedural step, and references that were updated. The "intent" of this procedure was not violated by these exceptions.

Page 2

EXCEPTIONS 2 & 3

These exceptions were taken to identify recorded values (Appendix D) which did not meet acceptable limits (Normal Operating Parameters (Table 1)). Since, these deviations, within acceptable limits, were only slight, they were dispositioned "accept as is" because test results were not impacted.

EXCEPTION 4

This exception was taken to identify that temporary test equipment was not removed because of additional testing requirements. The removal of temporary test equipment is to be tracked by Step 9.2 of PT.307.002-2 (IET) and is not an open item to this procedure.


EXCEPTION 6


This exception was taken to explain that TCN #1 was voided because additional testing requirements will be performed as part of PT.307.003A-2 (EDG101 Electric Preop).

EXCEPTION 8

This exception clarified the interpretation of the Technical Specification surveillance requirement criteria regarding engine loading to 3500 KW in less than 60 seconds (Quick Start).

Based on the results of this test and the above analysis, it is this test engineer's opinion that twenty-three (23) starts were successfully completed in accordance with Regulatory Guide 1.108 Rev. 1 Section C.2.a (9).

  
William J. Cook  
Test Engineer

  
Francis C. Clifford  
Test Results Reviewer

WJC/FCC:jl



SHOREHAM I.  
 NUCLEAR POWER STATION  
 TARTUP FORM 8.2

UNCONTROLLED  
 For Information Only  
 May 15, 1980  
 REVISION 11

Page 1 of 4

TEST CHANGE NOTICE #1 Exception #6

1. System Number: R43
2. Test Procedure Number: PT.307.004A-2
3. System Description: Emergency Diesel Generator 101 Qualification Test
4. Prepared By: R. I. Samson *R. I. Samson* Date 4/6/84  
 Cognizant System Test Engineer
5. Approved By: *[Signature]* Date 4/6/84  
 Lead Startup Engineer

Item	Test Step and Procedure Page Number Affected	Modification Reason	LILCO System Test Engineer/ Date
1	Insert pages 16a & 16b	Adding Section 8.9 for Post Outage load run.	<i>J. D. Kuo</i> 4/10/84
2	Remove page 13. Insert new page 18.	Provide Acceptance Criteria for Section 8.9.	<i>J. D. Kuo</i> 4/10/84

This form is attached to the original master copy of the test procedure.

Distribution: ORIGINAL: Project Resource Center  
 COPY TO: Test Procedure (Test Engineer Copy)  
 Cognizant Lead Startup Engineer  
 Startup Manager  
 JTG (For JTG approved procedures only)

WPA initials (if required): *WPA* 4/6/84 *[Signature]* 4/6/84  
 8-25 *[Signature]* 4/6/84 *[Signature]* 4/6/84  
*[Signature]* 4/6/84  
 A13537

10.0 ACCEPTANCE CRITERIA

10.1 The Emergency Diesel Generator 101 successfully completed 23 consecutive valid tests with no failures as defined in Regulation Guide 1.108, Rev. 1 paragraph C.2.e. A valid test shall be defined as achieving a successful start, followed by a loading to at least 50% of continuous rating and continued operation for at least one hour, as per reference 2.26.

V

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

NOTE: All charts will be available to backup readings of Appendix D. These charts will be submitted to the PRC with the approved procedure.

PER

TCN #  
|

1  
D

EMERGENCY DIESEL GENERATOR QUALIFICATION  
PREOPERATIONAL TEST

<u>Section</u>	<u>Description</u>	<u>Page</u>
1.0	Purpose	1
2.0	References	1
3.0	Prerequisites	4
4.0	Precautions	5
5.0	Initial Conditions	7
6.0	Environmental Conditions	13
7.0	Test Equipment	13
8.0	Procedure	14
9.0	System Return to Normal	17
10.0	Acceptance Criteria	18
11.0	Exception Sheet	19
Table I	EDG Normal Operating Parameters	20
Table II	EDG Shutdown/Prestart Parameters	21
Table III	Test Equipment Log	22
Appendix A	Valve Line-up Sheet	23
Appendix B	System Component Power Supply Checklist	27
Appendix C	EDG Qualification Test Start Sign Off Sheet	29
Appendix D	EDG Qualification Log	32
Appendix E	Diesel Generator Run Log	35
Appendix F	Engine Cylinder Pressure Log	37

TOTAL PAGES 37

JTG APPROVED NOV 8 1983

A13539

2

UNCONTROLLED  
For Information Only

PT.307.004A-2

UNCONTROLLED  
For Information Only

1.0 PURPOSE

- 1.1 The purpose of this procedure is to verify the qualification of emergency diesel generator 101 with respect to starting and loading reliability following repairs due to the failure of the crankshaft. | 2
- 1.2 This procedure will consist of starting the diesel, loading the diesel to at least 1,750 kW, and operating the diesel at load for at least one hour 23 consecutive time without a failure.
- 1.3 This procedure in conjunction with PT.307.003A-2 and PT.307.002 satisfies the intent of Regulatory Guide 1.108 (August 1977), Periodic Testing of Diesel Generator Units used as On-Site Electrical Power Systems at Nuclear Power Plants. | 2
- 1.4 At least one of the qualification runs will be used to demonstrate that the diesel generator is capable of performing its monthly surveillance requirement per Reference 2.27. | 2

NOTE: All equipment mark numbers are prefixed by 1R43, unless otherwise noted.

2.0 REFERENCES

- 2.1 FSAR Sections 8.3 and 14.1.3.7.24
- 2.2 FM-44A-15, Fuel Oil Transfer System
- 2.3 FM-44B-4, Diesel Generator Air Start System
- 2.4 LILCO Startup Manual
- 2.5 LILCO Safety Manual
- 2.6 ESK-5R2209-14, Elementary Diagram, Emergency Bus Normal Supply ACB 101-1
- 2.7 ESK-5R2210-15, Elementary Diagram, Emergency Bus Reserve Supply ACB 101-2
- 2.8 ESK-5R4301-19, Elementary Diagram, Emergency Generator Breaker ACB 101-8
- 2.9 ESK-6R4301-6, Elementary Diagram, G-101 Starting Air Compressors
- 2.10 ESK-6R4304-11, Elementary Diagram, G-101 Fuel Oil Transfer Pump

- 2.11 ESK-6R4307-~~8~~<sup>6</sup> <sup>as 4/10/84</sup>, Elementary Diagram, G-101 Before and After Lube Oil Pump and Heater
- 2.12 ESK-6R4310-~~8~~<sup>6</sup> <sup>as 4/10/84</sup>, Elementary Diagram, G-101 Jacket Water Heater and Pump
- 2.13 ESK-6R4313-2, Elementary Diagram, Diesel Generator G-101 Protection
- 2.14 ESK-8R4301-~~13~~<sup>14</sup> <sup>as 4/10/84</sup>, Elementary Diagram, Emergency Diesel Generator G-101 Protection
- 2.15 ESK-8R4304-7, Elementary Diagram, Emergency Diesel Synchronizing Circuit
- 2.16 ESK-8R4305-~~11~~<sup>13</sup> <sup>as 4/10/84</sup>, Elementary Diagram, G-101 Voltage Regulator
- 2.17 ESK-11R4301-~~6~~<sup>7</sup> <sup>as 4/10/84</sup>, Elementary Diagram, Emergency Diesel Generator 101 Sheet 1
- 2.18 ESK-11R4302-~~12~~<sup>14</sup> <sup>as 4/10/84</sup>, Elementary Diagram, Emergency Diesel Generator 101 Sheet 2
- 2.19 ESK-11R4307-~~8~~<sup>7</sup> <sup>as 4/10/84</sup>, Elementary Diagram, Fuel Booster Pump
- 2.20 Manufacturer's Drawings
- 2.20.1 11600.02-1.12-5H, Lube Oil Piping Schematic
- 2.20.2 11600.02-1.12-6M, Starting Air Piping Schematic
- 2.20.3 11600.01-1.12-~~7L~~<sup>N</sup> <sup>as 4/10/84</sup>, Jacket Water Piping Schematic
- 2.20.4 11600.02-1.12-74M, Engine Pneumatic Schematic
- 2.20.5 11600.02-1.12-~~75L~~<sup>M</sup> <sup>as 4/10/84</sup>, Panel Pneumatic Schematic
- 2.20.6 11600.02-1.12-~~91C~~<sup>73</sup> <sup>as 4/10/84</sup>, Panel Installation
- 2.20.7 11600.02-1.12-~~93L~~<sup>M</sup> <sup>as 4/10/84</sup>, Panel Electrical Schematic
- 2.20.8 11600.02-1.12-94P, Panel Electrical Schematic
- 2.20.9 11600.02-1.51-94J, Front View Layout for BOP Main Control Board
- 2.20.10 11600.02-1.12-43G, Wiring Diagram Static Exciter
- 2.21 System Description (S/D 1020.307), Emergency Diesel Generators Revision 1

A13541

EXCEPTION #1

- 2.22 Operating Procedure (SP.23.307.01), Emergency Diesel Generators Revision 5 <sup>ATS</sup> <sub>al/lye</sub>
- 2.23 Operating Procedure (SP.23.309.01), 4,160 V Emergency Bus Distribution Revision 4
- 2.24 Shoreham Specification SH1-89, Diesel Generator Sets, Revision 2, January 26, 1983
- 2.25 Manufacturer's Instruction Manual, R43-1 Volume I, II and III
- 2.26 Regulator Guide 1.108 "Periodic Testing of Diesel Generator Units as on site Electrical Power Systems at Nuclear Plant". Rev. 1 August, 1977. (Paragraphs C.2.a.9 and C.2.e)
- 2.27 SNPS Proof and Review Copy Tech Spec 3.8.1.1 and 4.8.1.1.2 dated July 22, 1983.
- 2.28 Operating Procedure (SP.27.307.02) Emergency Diesel Generator Cylinder Head Leak Detection Test, Revision 1.

2

NOTE: All personnel signing this procedure must fill out the following information for future reference:

Name (Written/Printed)	Initials (Written/Printed)	Title/ Organization	Level of Qualification I, II, III
J. D. Kocoff / L. DiLoro	J.D. / L.D.	TE/LSU	II
A. L. ... / AT. ...	ALB / ATS	TE/LSU	II
H. Raymond ...	H.R.S.	TE/LSU	II
G. Hazell	G.H.	OQA	II
C. ...	CSU / CSN	OQA	II
M.D. Bene	MDB / MDB	TE/LSU	II
James A. Mab	JAM / JAM	OQA	II
Raymond ...	RAV / RAV	TE/LSU	II
Sya	SYA / SYA	TE/LSU	II
E.S. ...	ESL / ESL	TE/LSU	II
F.C. ...	FCC / FCC	TE/LSU	II

A13542

PT. 307.004A-2

NAME (printed)	NAME (signed)	INITIALS PRINTED/WRITTEN	TITLE	LEVEL OF QUALIFICATION
MICHAEL M GORGONI	<i>Michael M Gorgoni</i>	MMG / MMG	OGPA	II
LARRY W ORELAND	<i>Larry W Oreland</i>	LW / LW	TECH / LSU	I
Stephen Cumming	<i>Stephen Cumming</i>	SC / SC	Tech LSU	I
Tony C. MASETTI	<i>Tony C. Masetti</i>	TCM / TCM	Tech LSU	I
AL MEYER	<i>Al Meyer</i>	AM / AM	TECH LSU	I
RAYMOND SIMON	<i>Raymond Simon</i>	RS / RS	Tech LSU	I
PAUL WARTZ	<i>Paul Warty</i>	PW / PW	Tech LSU	I
ROBERT I SMITH JR	<i>Robert I Smith Jr</i>	RTS / RTS	TECH LSU	I
Richard T. Gunt	<i>Richard T Gunt</i>	RTG / RTG	Tech LSSU	I
DOUGLAS E. CAMPBELL	<i>Douglas E. Campbell</i>	DEC / DEC	AGRICULTURAL TECHS. / LSU	II
WILLIAM R. YOUNG	<i>William R. Young</i>	WRY / WRY	TECH / LSU	I
REYNOLD W. KANDENIKS	<i>Reynold W. Kandenis</i>	RWK / RWK	TECH LSU	I
A. C. TOLSON	<i>A. C. Tolson</i>	AT / AT	OGPA	III

UNCONTROLLED  
For Information Only

3.0 PREREQUISITES

3.1 The master punch list contains no deficiencies that will affect this test. List any exceptions in Section 11.0.

2

[Signature] 4/10/84  
Verified Date

3.2 Verify applicable C&IO tests have been performed, and have been approved.

[Signature] 4/10/84  
Verified Date

3.3 The Lead Startup Engineer has released test for performance (SU Form 8.1).

[Signature] 4-10-84  
Verified Date

3.4 Emergency Diesel Generator Mechanical Preoperational Test Procedure PT.307.001A-2 and the Emergency Diesel Generator Electrical Preoperational Test Procedure PT.307.003A-2 have been completed.

2

[Signature] 4/10/84  
Verified Date

3.5 Notify the Watch Engineer and OQA prior to performing test.

[Signature] 4-10-84  
Verified Date

3.6 Notify the LILCO System Operator prior to performing test.

[Signature] 4-10-84  
Verified Date

3.7 Notify DeLaval representative that this procedure is about to commence.

[Signature] 4-10-84  
Verified Date

3.8 Establish communication between an operator at the Emergency Diesel Control Panel and an operator in the Main Control Room at the Emergency Diesel Generator portion of Panel 1H11\*MCB-01.

[Signature] 4-10-84  
Verified Date



- 3.9 Diesel engine inputs to the process computer need not be verified if the computer is not available.

Computer is is not available.

B. J. Summa 4-10-84  
Verified Date

- 3.10 Ensure all documents used at time of this test are of the latest revision.

Exception #1  
Verified Date

- 3.11 Verify valve lineup in accordance with Appendix A.

B. J. Summa 4-10-84  
Verified Date

#### 4.0 PRECAUTIONS

- 4.1 A sudden increase in lubrication oil temperature and amount of vapor from the crankcase ventilating discharge can indicate some overheated internal part of the engine. This could signal an approaching piston seizure and a possible crankcase explosion. A sudden increase in lube oil temperature requires immediate unloading and shutdown of the diesel.
- 4.2 Sustained operation of the diesel below 875 KW (critical load) should be avoided. However, when unloading unit, reduce load between 100 - 200 KW prior to opening diesel generator output breaker.
- 4.3 Sustained operation of the diesel in the range of 250 to 400 rpm (critical speed) should be avoided.
- 4.4 When starting a cool engine after shutdown, observe the manufacturer's starting procedure in Section 4 of Volume I of the manufacturer's instruction manual.
- 4.5 Ear protection should be worn by personnel in the Diesel Generator Room during diesel operation.
- 4.6 An operator should continuously monitor the operation of the diesel and auxiliary equipment throughout the entire test. At least one set of loc readings should be taken whenever the diesel is started.
- 4.7 Diesel Room air temperature and humidity should be frequently monitored during diesel testing (especially in the vicinity of the air dryers and fuel oil day tanks).

- 4.8 Any fuel oil or lube oil spills should be wiped up as soon as possible to avoid fire hazards.
- 4.9 Portable fire extinguishing equipment should be readily available during diesel testing.
- 4.10 When leaving a diesel generator room, ensure that the fire doors between individual diesel generator rooms are closed.
- 4.11 Lube oil strainers should be cleaned when the differential pressure across them reaches 20 psid.
- 4.12 Lube oil filters should be changed when the differential pressure across them reaches 20 psid.
- 4.13 Fuel oil strainers should be cleaned when the differential pressure across them reaches 2.0 psid.
- 4.14 Fuel oil filters should be changed when the differential across them reaches 20 psid.
- 4.15 Lube oil pressure should not exceed 65 psig, or drop below 50 psig.
- 4.16 Jacket water pressure should not exceed 30 psig, or drop below 20 psig.
- 4.17 Fuel oil pressure should not exceed 35 psig.
- 4.18 Lube oil and jacket water temperatures should not exceed 200°F.
- 4.19 The exhaust temperature limits for sustained operation is 150°F between any two cylinders at full load. The maximum temperature limit at any load is 1100°F. Should these limits be reached, reduce load and notify Test Engineer.
- 4.20 For sustained operation, 200 psig is maximum firing pressure difference between any two cylinders at any load. Should these limits be reached, reduce load and notify Test Engineer.
- 4.21 Turbocharger lube oil pressure should not drop below 25 psig.
- 4.22 If the diesel is to be shutdown for greater than 4 hours during any portion of this test, perform a cylinder head leakage surveillance per Reference 2.28 (SP.27.307.02).

2

5.0 INITIAL CONDITIONS

- 5.1 Engine 101 is shutdown ready for testing and its output breaker 1R22\*SWGR101-8 ACB is open.

A. J. Somma 4-10-84  
Verified Date

- 5.2 Verify equipment is energized in accordance with Appendix B, System Component Power Supply Checklist, by initialing next to each step.

A. J. Somma 4-10-84  
Verified Date

- 5.3 Service Water System is in operation to supply cooling water to the Jacket Water Cooler.

A. J. Somma 4-10-84  
Verified Date

- 5.4 Emergency Diesel Generator 101 HVAC System is in operation.

A. J. Somma 4-10-84  
Verified Date

- 5.5 Fire Protection (Cardox System) is available in diesel room 101, or Fire Watch has been provided in case of fire.

A. J. Somma 4-10-84  
Verified Date

- 5.6 Verify \*ENG101 has been barred over using barring device within one hour of first diesel start, and no presence of water was found.

A. J. Somma 4-10-84  
Verified Date

- 5.7 Diesel Generator Fuel Oil Storage and Transfer System is in operation.

A. J. Somma 4-10-84  
Verified Date

- 5.8 At emergency switchgear 1R22\*SWG101, check the following at diesel generator supply breaker ACB 101-8 compartment:

- 5.8.1 Local control switch midposition.

A. J. Somma 4-10-84  
Verified Date

5.8.2 Circuit Breaker closing springs charged.

A. J. Somma 4-10-84  
Verified Date

5.8.3 GREEN (Open) indication shown for breaker.

A. J. Somma 4-10-84  
Verified Date

5.8.4 Primary protection lockout relay 86P-101-8 reset.

A. J. Somma 4-10-84  
Verified Date

5.8.5 Backup protection lockout relay 86B-101-8 reset.

A. J. Somma 4-10-84  
Verified Date

5.9 Place or check the following switches at the emergency diesel generator \*G101 local diesel control panel \*PNL-DG1 in the positions indicated:

5.9.1 Mode selector switch in REMOTE.

A. J. Somma 4-10-84  
Verified Date

5.9.2 Before and after LO pump/heater (\*P-226A) and \*H-015A in AUTO.

A. J. Somma 4-10-84  
Verified Date

5.9.3 Fuel booster pump \*P-109A in AUTO.

A. J. Somma 4-10-84  
Verified Date

5.9.4 Jacket Water pump/heaters (\*P-238A and \*H-014A and D in AUTO.

A. J. Somma 4-10-84  
Verified Date

5.9.5 Both starting air compressors \*C-003A and \*C-004A in AUTO.

~~EXCEPTION #1~~  
25) A. J. Somma 4-10-84  
Verified Date

- 5.9.6 Primary fuel oil transfer pump \*P-201A in AUTO.  
A. J. Somma 4-10-84  
 Verified Date
- 5.9.7 Secondary fuel oil transfer pump \*P-202A in AUTO.  
A. J. Somma 4-10-84  
 Verified Date
- 5.9.8 White control power available light ON.  
A. J. Somma 4-10-84  
 Verified Date
- 5.10 Verify starting air pressure as indicated on local diesel control panel \*PNL-DG1 is greater than 220 psig.  
A. J. Somma 4-10-84  
 Verified Date
- 5.11 Verify Before and After Lube Oil Pump \*P-226A is operating.  
A. J. Somma 4-10-84  
 Verified Date
- 5.12 Verify Jacket Water Heater Circulating Pump \*P-238A is operating.  
A. J. Somma 4-10-84  
 Verified Date
- 5.13 Verify lube oil temperature is above 140°F.  
A. J. Somma 4-10-84  
 Verified Date
- 5.14 Verify jacket water standpipe level is greater than 10 o'clock and jacket water temperature is greater than 140°F. | 2  
A. J. Somma 4-10-84  
 Verified Date
- 5.15 At diesel generator \*G-101 hydraulic actuator/governor, record the following settings:
- 5.15.1 Speed Droop 0 Initials AJS  
 (0 - 10)

5.15.2 Load Limit Max Initials ajs  
(Fuel Setting)  
(Min - Max)

5.15.3 Speed Setting 14.08 Initials ajs  
(0 - 23)

- 5.16 Check air dryers \*AD-002A and \*AD-003A to ensure they are both running and that the cooling fin air passages are not blocked.

A. J. Somma 4-10-84  
Verified Date

- 5.17 Ensure the fire doors between the diesel generator rooms are closed.

A. J. Somma 4-10-84  
Verified Date

- 5.18 At the diesel generator \*G-101 section of control room control panel 1H11\*MCB-01, place or verify the following switches are in the positions indicated:

- 5.18.1 Diesel generator \*G-101 start control switch in AUTO.

A. J. Somma 4-10-84  
Verified Date

- 5.18.2 \*G-101 governor speed changer in mid position.

A. J. Somma 4-10-84  
Verified Date

- 5.18.3 Bus 101 program reset to RESET.

A. J. Somma 4-10-84  
Verified Date

- 5.18.4 Bus 101 program test switch in NORMAL.

A. J. Somma 4-10-84  
Verified Date

- 5.18.5 \*G10 voltage regulator control switch in mid position.

A. J. Somma 4-10-84  
Verified Date

5.18.6 Jacket Water cooler \*E-013A outlet valve  
1P41\*AOV-016A in AUTO.

A. J. Somma 4-10-84  
Verified Date

5.18.7 125V Bus A dc volts greater than or equal to  
125 volts.

A. J. Somma 4-10-84  
Verified Date

E. Howell 4/10/84  
OQA Witness Date

5.18.8 125V dc Bus A battery ground detector lights  
are both dim and alarm point 0357 (125V Bat A  
Ground) is not annunciated.

A. J. Somma 4-10-84  
Verified Date

E. Howell 4/10/84  
OQA Witness Date

5.19 Verify emergency bus 101 is being supplied from the  
NSST (101-1 closed)  or RSST (101-2  
closed) . Check one.

2

A. J. Somma 4-10-84  
Verified Date

5.20 Verify the Honeywell Visi recorder and/or the GE  
Transient Analysis Response Computer is connected to  
record the following 7 inputs as follows:

2

- Channel 1 - Engine Speed (RPM) @ output of tachometer
- Channel 2 - Generator AC Voltage @ \*PNLGP1
- Channel 3 - Generator AC Current (Amps) @  
1H11\*MCBC1
- Channel 4 - Generator Load (Watts) @ 1H11\*MCL01
- Channel 5 - Generator ACB 101-8 closure @ SWGR 101-2
- Channel 6 - Diesel start from start circuit *Exception # 7*
- Channel 7 - Generator freq. from 1H11\*MCB01

Indicate: Visirecord \_\_\_\_\_, GETARS  or  
Both \_\_\_\_\_ recording inputs.

2

A. J. Somma 4-10-84  
Verified Date

5.21 Wire a temporary selector switch (capable of handling 6 RTD's) to the Generator Winding RTD's. Connect the output off the selector switch to a digital volt meter. This setup will be used to determine the hottest Generator winding temperature. Record temporary hookup in SNPS lifted lead and jumper program.

*[Signature]* 4/10/84 | 2  
Verified Date

5.22 Verify no abnormal alarms are initiated, which would prevent a successful start.

*[Signature]* 4-10-84  
Verified Date

5.23 Connect a micromite to the output of the generator pedestal bearing RTD to permit measurement of bearing temperature. Record any necessary temporary connections in the lifted lead and jumper program.

*[Signature]* 4/10/84 | 2  
Verified Date



6.0 ENVIRONMENTAL CONDITIONS

- 6.1 Diesel room temperature below 120°F.
- 6.2 Diesel room humidity below 80% relative humidity.

At start of test:

Diesel Room Temperature: 90 °F

Diesel Room Humidity : 18 %

A. J. Summa 4-10-84  
 Verified Date

2

7.0 SPECIAL TEST EQUIPMENT

- 7.1 Stop watches.
- 7.2 High speed visirecorder with at least 7 channels.
- 7.3 Getars computer (if available).
- 7.4 Temporary RTD measuring switch box.
- 7.5 Psychrometer
- 7.6 Digital Voltmeter
- 7.7 Micromite

NOTE: All above used test equipment should be recorded on Table III.

2

8.0 PROCEDURE

NOTE: All KVAR values specified are lagging vars. | 2

- 8.1 All prerequisites in Section 3.0 and initial conditions in Section 5.0 have been satisfied. Any exceptions are listed in the Exception Section, Section 11.0.

A. J. Simons 4-10-84  
Verified Date  
Carl A. Prange 4-10-84  
OQA Witness Date

- 8.2 Verify that the emergency diesel shutdown parameters were recorded on Appendix D just prior to the next diesel start, are within tolerances per Table II, and engine is ready to be restarted. (If engine has been shutdown for more than 12 hours the initial conditions of paragraph 5.0 have been reverified).
- 8.3 Start emergency diesel generator 101 and load to at least 1750KW and 700 KVars.
- 8.4 Run the diesel generator at load for at least one (1) hour while completing all the data in Appendix D. The one (1) hour run at load shall be timed using a stop watch.

NOTE: The time to start, load and shutdown the engine shall not be included in the one hour. | 2

- 8.5 Reduce generator load to 100 - 200 KW, run at this load for 2 min to allow unit cooldown, open its output breaker 101-8 and then shutdown the diesel engine by depressing stop pushbutton.

NOTE: Prior to shutdown from the 23rd start, perform step 8.8.

- 8.6 Verify that the engine was successfully started, loaded to constitute a valid test and that the data recorded on Appendix D conforms to the ranges of Table I and Table II.
- 8.7 Repeat steps 8.2 through 8.6 until twenty three consecutive successful starts and qualification runs are accomplished.

NOTE 1: Sign-off of the above steps will be done in Appendix C. Should a start be considered a failure (per reference 2.26) indicate such on Appendix C, correct the problem and begin the first qualification start again. Any failures will be explained as an exception in Section 11.0.

8.7 - continued

NOTE 2: <sup>Exception #8</sup> At least one of the 23 consecutive starts should verify the diesel generator is capable of being ~~started~~ started, synchronized, loaded to greater than or equal to 3500KW/1500KVars in less than or equal to 60 seconds, and operated with this load for at least 60 minutes.

8.8 Final Baseline Data at Various Diesel Load Levels

8.8.1 Verify the emergency diesel generator is running at approximately full load (3500KW/2625 K Vars) then record running data in Appendix E.

J. J. Cotton 4/11/84 | 2  
Verified Date  
James A. Masley 4/11/84  
QA Witness Date

8.8.2 While still at full load, record cylinder pressure data in Appendix E.

J. J. Cotton 4/11/84 | 2  
Verified Date  
James A. Masley 4/11/84  
QA Witness Date

8.8.3 Reduce load to approximately 75% load, (2600KW/2000 K Vars) long enough for parameters to stabilize, then record data in Appendix E.

J. J. Cotton 4/11/84 | 2  
Verified Date  
James A. Masley 4/11/84 | 2  
QA Witness Date

8.8.4 Reduce diesel generator load to approximately 50% (1750 KW/1300 K Vars), run long enough to stabilize parameters, then record data in Appendix E.

J. J. Cotton 4/11/84 | 2  
Verified Date  
James A. Masley 4/11/84 | 2  
QA Witness Date

8.8.5 Reduce diesel generator load to approximately 25% (900 KW/650 K Vars), run long enough to stabilize parameters, then record data in Appendix E.

12  
12

W.D. Bove 4/11/84  
Verified Date

James A. Woolley 4/11/84  
QA Witness Date

8.8.6 Shutdown diesel generator in accordance with SP.23.307.01, paragraph 8.1.6 and leave engine in standby or as directed by test engineer.

W.D. Bove 4/11/84  
Verified Date

TCN #1

PT.307.004A-2

8.9 Post Outage Load Run (5 hours)

8.9.1 Start the Diesel Generator and parallel to its emergency bus. Load the Diesel to approximately 3500KW and 2000 KVARs as monitored by the main control room meters. Establish engine equilibrium conditions prior to continuing test.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

8.9.2 Block the governor load limit setting on the hydraulic actuator. Raise the electric speed setting above 4000KW.

Slowly raise the load limit until the load stabilizes at 3900KW + 0.25% - 1.0% (i.e. load between 3861KW and 3910KW) as measured by the watt hour meter over a minimum three minute time interval. The control room operator should simultaneously increase the Var loading to obtain a final reading between 2800 KVARs - 2900KVARs.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

*Voided  
Except 6*

*Jace  
4/21/84  
OQA  
EX # 6 NOTED  
4/16/84*

TCN #1

PT.307.004A-2

8.9.3 Run at this load for one hour, recording all parameters in Appendix E every 15 minutes. Cross out the existing step numbers on Appendix E and fill in step no. 8.9.3 for this run. Ensure generator field current does not exceed 305 amps and field resistance is less than .395 ohms.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

8.9.4 Reduce load to a value greater than or equal to 3500KW and 1900KVAR. Run at this load for at least four hours. Record all parameters listed in Appendix E every 20 minutes for the first two hours. For the remaining two hours record data every 30 minutes. Cross out the existing step numbers on Appendix E and fill in step no. 8.9.4 for this run.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

8.9.5 At the end of the 4 hour run, change the diesel load or shut down the diesel engine as directed by the Test Engineer.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

*Voided  
Except*

*Free  
analysis  
OQA 4/16/84  
EX#6 NOTED*

16b

9.0 SYSTEM RETURN TO NORMAL

9.1 Place the diesel generator in its normal standby condition as directed by Test Engineer.

JY Carter 4/12/84  
Verified Date  
James G. Masley 4/12/84  
OQA Witness Date

9.2 Indicate in Appendix A the as left condition of each valve at the completion of this test.

JY Carter 4/12/84  
Verified Date  
Carl Roujinski 4/12/84  
OQA Witness Date

9.3 Ensure all temporary test equipment has been removed.

Exception #4 JEP 4/12/84  
Verified Date  
Jim 4/12/84  
OQA Witness Date

9.4 Perform a cylinder head leakage surveillance per SP.27.307.02 (Ref. 2.28) at 4, 8 and 12 hours after shutdown.

After 4 hours: sat  unsat

JY Carter 4/12/84  
Verified Date  
James G. Masley 4/12/84  
OQA Witness Date

After 8 hours: sat  unsat

JY Carter 4/12/84  
Verified Date  
James G. Masley 4/12/84  
OQA Witness Date

After 12 hours: sat  unsat

A. J. Summa 4/12/84  
Verified Date  
Carl Roujinski 4/12/84  
OQA Witness Date

2

TCN #1

PT.307.004A-2

10.0 ACCEPTANCE CRITERIA

10.1 The Emergency Diesel Generator 101 successfully completed 23 consecutive valid tests with no failures as defined in Regulation Guide 1.108, Rev. 1 paragraph C.2.e. A valid test shall be defined as achieving a successful start, followed by a loading to at least 50% of continuous rating and continued operation for at least one hour, as per reference 2.26.

<u>Al Louma</u>	4-12-84
Verified	Date
<u>[Signature]</u>	4/16/84
OQA Witness	Date

NOTE: All charts will be available to backup readings of Appendix D. These charts will be submitted to the PRC with the approved procedure.

10.2 During the post outage load run, the diesel generator ran continuously for 5 hours at loads of 3900KW (1 hour), and 3500KW (4 hours), (Section 8.9);

Verified	Date
<u>[Signature]</u>	4/16/84
OQA Witness	Date

*Voided by  
Exception  
JFC  
4/12/84*

TCN #1



11.0 EXCEPTION SHEET

Item	Description of Exception	Initial/Date	Disposition	Initial/Date
EXCEPTION #1	STEP 3.10			
	References indicated on pages 2 and 3 of procedure are not of the latest Revision number.		Updated references as indicated on pages 2 and 3 of procedure. No effect Test Results Accept as is. 4-10-84	
EXC #2	QUAL RUN #12,13,14, Data Sheets STEP 86 - Generator Voltage out of spec per Table I	NJB 4/11/84	ULCO Grid feed was transferred from the NST to the RST to support plant maintenance on the NST. Grid disturbances on the RST feed caused the Generator Voltage to be slightly high. No effect on testing. Since this voltage can only be changed by ULCO System load dispatcher, it will be accepted as is. NJB 4/11/84 EPA 4/12/84	

11.0 EXCEPTION SHEET

Item	Description of Exception	Initial/Date	Disposition	Initial/Date
Exc #3	Qual Run #14. Data sheets Step 8.6 JW temp slightly out of spec per Table I	MRB 4/11/84	Due to the small initial loading (only about 2000 kW) on the Auto UV start the JW did not heat up. After sything to grid and loading to 2000 kW and running at this load the JW temp came into spec	
Exc #4	PT 307.004 A-2 page 17 step 9.3; All Temporary test-equipment will not be removed at this time.	JYA 4/2/84 DRAJOU	Temporary test equipment is being left installed to support the Integrated Elec. Test (PT 307002-2) and will be removed when the IET has been successfully completed	

TEMPORARY TEST EQUIPMENT TO BE REMOVED BY STEP 22 OF PT. 307002-2, see attached sheets  
4/17/84

11.0 EXCEPTION SHEET

Item	Description of Exception	Initial/Date	Disposition	Initial/Date
5	App D page 2 of 3 / App E page 2 of 2 The Generator Winding Temp is being monitored by PTD and the Bearing Temp is being monitored by TE073A	JFC 4/2/84	Type, description (App D, E) changed to indicate the correct temp monitoring device. Accept as is, but not affect test results	JFC 4/2/84 OQA 4/19/84
6	PT-307004A-2 TCN #1 pgs 2,3+4 Section 8.9 Post Outage Load Run (Shrs) The referenced section will not be performed as part of the Qual Test (PT-307004A-2)	JFC 4/2/84	Post Outage Load Runs will be performed by Stop/Restart #5 and TCN #4 to PT-307004A-2 (EOR in Electrical Prep) These additional engine runs will be reviewed and approved with PT-307004A-2. Accept as is, Post Outage Load runs were initiated by Lico as an additional reliability requirement. This is not an open item to this procedure.	JFC 4/2/84 OQA 4/16/84

11.0 EXCEPTION SHEET

Item	Description of Exception	Initial/ Date	Disposition	Initial/ Date
7	Step 5.20 Channel #6			
	GETARS did not monitor	JCC	GETAR operator	
	the diesel start automatically	4/19/84	will coordinate with	
			DC starts with	
			Control Room operator	
			and will manually	
			initiate a event	
			marker to indicate	
			when start occurred	
			Accept as is JCC 4/19/84	
			JCC	





UNCONTROLLED  
EXC#  
For Information Only

# TABLE 17-9

## RESISTANCE TEMPERATURE TABLE COPPER RESISTANCE THERMOMETER 9.035 OHMS AT 32°F.

# MINCO

7300 Commerce Lane | Minneapolis, Minnesota 55432 | TWX: 910-576-2848 | Telephone: (612) 766-3121

181	1.741	10.043
182	1.742	10.044
183	1.743	10.045
184	1.744	10.046
185	1.745	10.047
186	1.746	10.048
187	1.747	10.049
188	1.748	10.050
189	1.749	10.051
190	1.750	10.052
191	1.751	10.053
192	1.752	10.054
193	1.753	10.055
194	1.754	10.056
195	1.755	10.057
196	1.756	10.058
197	1.757	10.059
198	1.758	10.060
199	1.759	10.061
200	1.760	10.062
201	1.761	10.063
202	1.762	10.064
203	1.763	10.065
204	1.764	10.066
205	1.765	10.067
206	1.766	10.068
207	1.767	10.069
208	1.768	10.070
209	1.769	10.071
210	1.770	10.072
211	1.771	10.073
212	1.772	10.074
213	1.773	10.075
214	1.774	10.076
215	1.775	10.077
216	1.776	10.078
217	1.777	10.079
218	1.778	10.080
219	1.779	10.081
220	1.780	10.082
221	1.781	10.083
222	1.782	10.084
223	1.783	10.085
224	1.784	10.086
225	1.785	10.087
226	1.786	10.088
227	1.787	10.089
228	1.788	10.090
229	1.789	10.091
230	1.790	10.092
231	1.791	10.093
232	1.792	10.094
233	1.793	10.095
234	1.794	10.096
235	1.795	10.097
236	1.796	10.098
237	1.797	10.099
238	1.798	10.100
239	1.799	10.101
240	1.800	10.102
241	1.801	10.103
242	1.802	10.104
243	1.803	10.105
244	1.804	10.106
245	1.805	10.107
246	1.806	10.108
247	1.807	10.109
248	1.808	10.110
249	1.809	10.111
250	1.810	10.112
251	1.811	10.113
252	1.812	10.114
253	1.813	10.115
254	1.814	10.116
255	1.815	10.117
256	1.816	10.118
257	1.817	10.119
258	1.818	10.120
259	1.819	10.121
260	1.820	10.122
261	1.821	10.123
262	1.822	10.124
263	1.823	10.125
264	1.824	10.126
265	1.825	10.127
266	1.826	10.128
267	1.827	10.129
268	1.828	10.130
269	1.829	10.131
270	1.830	10.132
271	1.831	10.133
272	1.832	10.134
273	1.833	10.135
274	1.834	10.136
275	1.835	10.137
276	1.836	10.138
277	1.837	10.139
278	1.838	10.140
279	1.839	10.141
280	1.840	10.142
281	1.841	10.143
282	1.842	10.144
283	1.843	10.145
284	1.844	10.146
285	1.845	10.147
286	1.846	10.148
287	1.847	10.149
288	1.848	10.150
289	1.849	10.151
290	1.850	10.152
291	1.851	10.153
292	1.852	10.154
293	1.853	10.155
294	1.854	10.156
295	1.855	10.157
296	1.856	10.158
297	1.857	10.159
298	1.858	10.160
299	1.859	10.161
300	1.860	10.162
301	1.861	10.163
302	1.862	10.164
303	1.863	10.165
304	1.864	10.166
305	1.865	10.167
306	1.866	10.168
307	1.867	10.169
308	1.868	10.170
309	1.869	10.171
310	1.870	10.172
311	1.871	10.173
312	1.872	10.174
313	1.873	10.175
314	1.874	10.176
315	1.875	10.177
316	1.876	10.178
317	1.877	10.179
318	1.878	10.180
319	1.879	10.181
320	1.880	10.182
321	1.881	10.183
322	1.882	10.184
323	1.883	10.185
324	1.884	10.186
325	1.885	10.187
326	1.886	10.188
327	1.887	10.189
328	1.888	10.190
329	1.889	10.191
330	1.890	10.192
331	1.891	10.193
332	1.892	10.194
333	1.893	10.195
334	1.894	10.196
335	1.895	10.197
336	1.896	10.198
337	1.897	10.199
338	1.898	10.200
339	1.899	10.201
340	1.900	10.202
341	1.901	10.203
342	1.902	10.204
343	1.903	10.205
344	1.904	10.206
345	1.905	10.207
346	1.906	10.208
347	1.907	10.209
348	1.908	10.210
349	1.909	10.211
350	1.910	10.212
351	1.911	10.213
352	1.912	10.214
353	1.913	10.215
354	1.914	10.216
355	1.915	10.217
356	1.916	10.218
357	1.917	10.219
358	1.918	10.220
359	1.919	10.221
360	1.920	10.222
361	1.921	10.223
362	1.922	10.224
363	1.923	10.225
364	1.924	10.226
365	1.925	10.227
366	1.926	10.228
367	1.927	10.229
368	1.928	10.230
369	1.929	10.231
370	1.930	10.232
371	1.931	10.233
372	1.932	10.234
373	1.933	10.235
374	1.934	10.236
375	1.935	10.237
376	1.936	10.238
377	1.937	10.239
378	1.938	10.240
379	1.939	10.241
380	1.940	10.242
381	1.941	10.243
382	1.942	10.244
383	1.943	10.245
384	1.944	10.246
385	1.945	10.247
386	1.946	10.248
387	1.947	10.249
388	1.948	10.250
389	1.949	10.251
390	1.950	10.252
391	1.951	10.253
392	1.952	10.254
393	1.953	10.255
394	1.954	10.256
395	1.955	10.257
396	1.956	10.258
397	1.957	10.259
398	1.958	10.260
399	1.959	10.261
400	1.960	10.262
401	1.961	10.263
402	1.962	10.264
403	1.963	10.265
404	1.964	10.266
405	1.965	10.267
406	1.966	10.268
407	1.967	10.269
408	1.968	10.270
409	1.969	10.271
410	1.970	10.272
411	1.971	10.273
412	1.972	10.274
413	1.973	10.275
414	1.974	10.276
415	1.975	10.277
416	1.976	10.278
417	1.977	10.279
418	1.978	10.280
419	1.979	10.281
420	1.980	10.282
421	1.981	10.283
422	1.982	10.284
423	1.983	10.285
424	1.984	10.286
425	1.985	10.287
426	1.986	10.288
427	1.987	10.289
428	1.988	10.290
429	1.989	10.291
430	1.990	10.292
431	1.991	10.293
432	1.992	10.294
433	1.993	10.295
434	1.994	10.296
435	1.995	10.297
436	1.996	10.298
437	1.997	10.299
438	1.998	10.300
439	1.999	10.301
440	2.000	10.302

181	1.741	10.043
182	1.742	10.044
183	1.743	10.045
184	1.744	10.046
185	1.745	10.047
186	1.746	10.048
187	1.747	10.049
188	1.748	10.050
189	1.749	10.051
190	1.750	10.052
191	1.751	10.053
192	1.752	10.054
193	1.753	10.055
194	1.754	10.056
195	1.755	10.057
196	1.756	10.058
197	1.757	10.059
198	1.758	10.060
199	1.759	10.061
200	1.760	10.062
201	1.761	10.063
202	1.762	10.064
203	1.763	10.065
204	1.764	10.066
205	1.765	10.067
206	1.766	10.068
207	1.767	10.069
208	1.768	10.070
209	1.769	10.071
210	1.770	10.072
211	1.771	10.073
212	1.772	10.074
213	1.773	10.075
214	1.774	10.076
215	1.775	10.077
216	1.776	10.078
217	1.777	10.079
218	1.778	10.080
219	1.779	10.081
220	1.780	10.082
221	1.781	10.083
222	1.782	10.084
223	1.783	10.085
224	1.784	10.086
225	1.785	10.087
226	1.786	10.088
227	1.787	10.089
228	1.788	10.090
229	1.789	10.091
230	1.790	10.092
231	1.791	10.093
232	1.792	10.094
233	1.793	10.095
234	1.794	10.096
235	1.795	10.097
236	1.796	10.098
237	1.797	10.099
238	1.798	10.100
239	1.799	10.101
240	1.800	10.102
241	1.801	10.103
242	1.802	10.104
243	1.803	10.105
244	1.804	10.106
245	1.805	10.107
246	1.806	10.108
247	1.807	10.109
248	1.808	10.110
249	1.809	10.111
250	1.810	10.112
251	1.811	10.113
252	1.812	10.114
253	1.813	10.115
254	1.814	10.116
255	1.815	10.117
256	1.816	10.118
257	1.817	10.119
258	1.818	10.120
259	1.819	10.121
260	1.820	10.122
261	1.821	10.123
262	1.822	10.124
263	1.823	10.125
264	1.824	10.126
265	1.825	10.127
266	1.826	10.128
267	1.827	10.129
268	1.828	10.130
269	1.829	10.131
270	1.830	10.132
271	1.831	10.133
272	1.832	10.134
273	1.833	10.135
274	1.834	10.136
275	1.835	10.137
276	1.836	10.138
277	1.837	10.139
278	1.838	10.140
279	1.839	10.141
280	1.840	10.142
281	1.841	10.143
282	1.842	10.144
283	1.843	10.145
284	1.844	10.146
285	1.845	10

SURVEILLANCE REQUIREMENTS

4.8.1.1.1 Each of the above required independent circuits between the offsite transmission network and the onsite Class 1E distribution system shall be:

- a. Determined OPERABLE at least once per 7 days by verifying correct breaker alignments and indicated power availability, and
- b. Demonstrated OPERABLE at least once per 18 months during shutdown by transferring, manually and automatically, unit power supply from the normal circuit to the alternate circuit.

4.8.1.1.2 Each of the above required diesel generators shall be demonstrated OPERABLE:

- a. In accordance with the frequency specified in Table 4.9.1.1.2-1 on a STAGGERED TEST BASIS by:
  1. Verifying the fuel level in the day tank.
  2. Verifying the fuel level in the fuel storage tank.
  3. Verifying the fuel transfer pump starts and transfers fuel from the storage system to the day tank.
  4. Verifying the diesel starts from ambient condition and accelerates to at least 450 rpm in less than or equal to 13 seconds. The generator voltage and frequency shall be  $4160 \pm 420$  volts and  $60 \pm 3.0$  Hz within 10 seconds after the start signal. The diesel generator shall be started for this test by using one of the following signals:
    - (a) Manual
    - (b) Simulated loss of offsite power by itself
    - (c) Simulated loss of offsite power in conjunction with an ESF actuation test setpoint
    - (d) An ESF actuation test signal by itself *Exception #8*
  5. Verifying the diesel generator is synchronized, loaded to greater than or equal to 3500 kw in less than or equal to 60 seconds, and operates with this load for at least 60 minutes.
  6. Verifying the diesel generator is aligned to provide standby power to the associated emergency busses.
  7. Verifying the pressure in all diesel generator air start receivers to be greater than or equal to 215 psig.
- b. At least once per 31 days and after each operation of the diesel where the period of operation was greater than or equal to 1 hour by checking for and removing accumulated water from the day tank.



*Exemption # 4*

UNCONTROLLED  
For Information Only

PT.307.002-2

9.0 SYSTEMS RETURN TO NORMAL

9.1 Inform the Watch Engineer that the Integrated Electrical Test is complete and that the plant may be returned to Normal in accordance with station procedure at his direction.

\_\_\_\_\_  
Verified Date

9.2 Remove all temporary test equipment installed by section 5.10 and initial those portions of Appendix C. Attach a completed copy of Repair/Rework R43-713 to APPENDIX C as attachment C2.

\_\_\_\_\_  
Verified Date

9.3 Remove temporary test fixture installed in step 5.9 via Repair/Rework E32-67 and initial Appendix C. Attach completed copies of Repair/Rework E32-67 and MWR 83-0851 to Appendix C as attachment C1.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

9.4 Return LOCA level transmitter isolation valves to normal service position and initial as required:

<u>1H21*PNL-04</u>	<u>INITIAL/DATE</u>	<u>1H21*PNL-05</u>	<u>INITIAL/DATE</u>
1B21*LT-155A	_____	1B21*LT-155C	_____
1B21*LT-154A	_____	1B21*LT-154C	_____
1B21*LT-157A	_____	1B21*LT-155D	_____
1B21*LT-157C	_____	1B21*LT-154D	_____
1B21*LT-154B	_____	1B21*LT-157B	_____
1B21*LT-155B	_____	1B21*LT-157D	_____

CAUTION: When returning transmitter to service operate instrument valves slowly to preclude spurious LOCA signals.

\_\_\_\_\_  
Verified Date

Exception #4

PT.307.002-2

- 5.9 The loss of offsite power (LOOSP) event is initiated by simultaneously tripping the NSS and RSS transformer Primary Protection.

The loss of coolant (LOCA) event is initiated by simulating HIGH DRYWELL PRESSURE for Test 8.1 and by simulating LOW reactor water level for tests 8.2 through 8.5. Both LOOSP and LOCA events are selectable at the TEMPORARY TEST FIXTURE to be used as follows: The event must be selected by enabling LOOSP or LOCA or both. The event is then initiated by placing the event switch to the INITIATE position. Verify circuit modification is installed according to MWR #83-0851 and Repair/Reworks E32-067 (Appendix C) and initial Appendix C.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

- 5.10 Verify temporary cables for instrumentation are installed in accordance with Repair/Rework R43-713 (APPENDIX C2) and temporary test instrumentation test results (Appendix E2) to provide temporary GETARS computer points listed in Appendix A2 and initial Appendix C.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

- 5.11 Calibrate the GETARS computer points listed in Appendix A2 and attach the calibration data as Attachment E4.

\_\_\_\_\_  
Verified Date

\_\_\_\_\_  
OQA Witness Date

JTG APPROVED MAR 16 1984

A13570

TEMPORARY  
Exception # 4

SHOREHAM 1  
NUCLEAR POWER STATION  
STARTUP FORM 7.6

Shoreham Nuclear Power Station - Unit 1

REPAIR/REWORK REQUEST *W. Stank*

1. Request: R43-713 Initiated By: W. Maloney 1/19/83 System #: R-13  
Test Engineer/Date

Work performed under jurisdiction of: ( ) Unico Construction  LILCO Startup

Work to be performed by: ( ) Unico Construction  LILCO Startup *JP 1/19/83*

Quality Assurance function to be performed by:  OQA ( ) FQC ( ) Work Supervisor

System or Subsystem Description: INTEGRATED ELECTRICAL TEST

QA Category: I Completion Date Required: \_\_\_\_\_  
Perform the following work: INSTALL TEMPORARY CABLES AND REMOVE AFTER TEST  
Reason for Work: TO SUPPORT PT 307.002

2. Work to be performed in accordance with the following applicable construction or maintenance procedure: TEST ENGINEER DIRECTION AND ATTACHED SHEETS

3. Notify W. Maloney 373 E OQA 93-307 prior to performing work.  
Startup Engineer

4. Request Approved: William E. Kra 1/19/83 P. Lawrence 1/19/83  
Lead Startup Engineer / Date SSW Lead Advisory Eng./Date

5. This form must be signed and returned to the party requesting the work when the work is completed.  
The above work has been completed. A work summary and necessary documentation is attached.

\_\_\_\_\_  
Supervisor/Date Field QC or Operational QA/Date

6. The following retest(s) are required and completed: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

LILCO Operational QA Engineer/Date Startup Engineer/Date  
DISTRIBUTION: Original to: Organization Performing Work: ( ) Unico Construction Superintendent (via Turnover Coordinator), or  LILCO Startup.  
Copies To: Organization Not Performing Work:  Unico Construction Superintendent (via Turnover Coordinator), or ( ) LILCO Startup Operational QA

TABLE I

EDG NORMAL OPERATING PARAMETERS

<u>Parameter</u>	<u>Range</u>
Generator Voltage	4,160 + 190 volts, -310 volts
Generator Frequency	60 ± 1.2 Hz
Lube Oil Pressure	50 to 65 psig
Turbo Oil Pressure	25 to 35 psig
Jacket Water Pressure	20 to 30 psig
Fuel Oil Pressure	20 to 35 psig
Lube Oil Temperature (Outlet)	170°F to 180°F
Jacket Water Temperature (Outlet)	160°F to 170°F
Generator Winding Temperature	less than 320°F
Generator Bearing Temperature	less than 180°F
Generator Load	greater than 1750 KW
Generator Vars	greater than 700 KVar
Generator Current	greater than 250 Amps
Combustion Air Pressure	greater than 20" Hg
Diesel Generator Room Temperature	less than 120°F
Diesel Generator Room Humidity	less than 80% relative humidity



2

TABLE II



EDG SHUTDOWN/PRESTART PARAMETERS

<u>Parameter</u>	<u>Range</u>
Lube Oil Inlet Temperature	140°F - 170°F
Lube Oil Level	less than 10" from S/D mark
Jacket Water Inlet Temperature	140°F - 170°F
Jacket Water Level	9 - 1 o'clock
Starting Air Pressure	greater than 200 PSIG
Group I Shutdown Pressure	greater than 50 PSIG






$\sigma_{III}$  as a function of pressure for stud boss rosette C with conventional and modified crown.



Axial strain as a function of pressure for strain gage rosette R located at outer portion of wrist pin cavity.





Axial strain as a function of pressure for strain gage rosette P located at inner portion of wrist pin cavity.







Figure 3-8. Axial strain as a function of pressure for strain gage rosette N located near outer ring at 90° from wrist pin cavity.



Results of tempplug measurements of peak temperature as a function of position on crown (supplied by TDI).



Location of strain gage rosettes on instrumented AE skirt.

**SUMMARY OF EXPERIMENTAL OBSERVATIONS  
RELATED TO CROWN/SKIRT INTERACTION**

		AE
Gap, $g_0$ , mils	nominal	7.5
	min	7.0
	max	8.0
Gap closure pressure, $p^*$ , psig	nominal	1000
	min	820
	max	1050
$\sigma_{\text{closure}}/\sigma_{\text{(no closure)}}$ at 1670 psig	nominal	0.88
	min	--
	max	--

**STRAIN READINGS AND CALCULATED STRESSES FOR AE PISTON SKIRT  
FOR THE COMPLETE STUD BOSS ROSETTES AT 1600 PSIG WITH A  
CONVENTIONAL CROWN**

(all strain values are in  $\mu\text{in/in}$ )

	C	D	E	F	H
$\epsilon_z$	-1740	-1668	-1722	-1605	-1583
$\epsilon_\theta$	270	366	304	270	246
$\epsilon_{45}$	-732	-787	-815	-602	-632
$\epsilon_I$	270	375	310	272	247
$\epsilon_{II}$	-1740	-1677	-1728	-1607	-1584
$\sigma_{II}$ , ksi	-6.5	-3.3	-5.4	-5.5	-5.9
$\sigma_{III}$ , ksi	-43.0	-40.6	-42.4	-39.6	-39.24

The reported values are for 1600 psig, which differs slightly from the effective firing pressure of 1627 psig. This 1.7% difference in pressure is considered to be negligible.

COMPARISON OF EXPERIMENTAL AND NUMERICAL  
VALUES OF CYCLIC STRESSES FOR THE AE PISTON SKIRT

$g_0 = 0.0075$  inch  
load split = 88%

	Numerical	Experimental	
		largest observed value	smallest observed value
$*\sigma_{III}$	-68.1	-44	-54
$\sigma_{min} (= 0.88 \sigma_{III})$	-60.0	-38.7	-47.5
$\sigma_{max} = \left[ - \frac{\text{inertia load}}{\text{pressure load minus inertia load}} \right] \times \sigma_{III}$	1.77	1.1	1.4
$\sigma_a \left[ = \frac{1}{2} (\sigma_{max} - \sigma_{min}) \right]$	30.9	19.9	24.5
$\sigma_m \left[ = \frac{1}{2} (\sigma_{max} + \sigma_{min}) \right]$	-29.1	-18.8	-23.0

\*Only  $\sigma_{III}$  was observed. All other values were calculated.

COMPARISON OF EXPERIMENTAL OBSERVATIONS OF  
 PEAK STRESS AT 1627 psig FOR AE PISTON SKIRT  
 WITH CORRESPONDING FINITE ELEMENT RESULTS USING  
 EXTREMES OF WRIST PIN BEHAVIOR

		$\sigma_{III}$ , ksi
rigid wrist pin		68.1
experimental,	max	54
	min	44
	ave	49
soft wrist pin		-41.4



**CYCLIC STRESSES IN AE PISTON SKIRTS UNDER  
ISOTHERMAL AND STEADY-STATE CONDITIONS**

		AE				
		F.E.	nominal	min	max	
$\sigma_{min}$	1	<----- -68.1 ----->				
$\sigma_{max}$	lift-off	<----- 7.32 ----->				
	no lift-off	<----- 1.77 ----->				
$k'_i$	2	96.9	83.7	45.7	121	
$k'_o$	2	118	24.0	7.95	283	
		$g_o$				
$\delta_L$	3	7	1.999	1.403	0	2.140
		9	0.157	0	0	0.285
		11	0	0	0	0
$\sigma_{min, isothermal}$	4	7	-57.5	-59.7	-60.3	-58.4
		9	-62.1	-62.9	-62.0	-63.4
		11	-66.7	-66.2	-63.8	-68.1
$\sigma_{min, steady-state}$	4	7	-33.0	-42.7	-50.9	-31.5
		9	-37.6	-45.9	-52.7	-36.6
		11	-42.2	-49.1	-54.4	-41.6
$\sigma_{max, steady-state}$	5	7	7.91	7.74	1.77	7.96
		9	7.37	1.77	1.77	7.40
		11	1.77	1.77	1.77	1.77

all stresses in ksi,  $g_o$  and  $\delta_L$  in mils

**Notes:**

1. From isothermal finite element calculations of skirt with crown, no gap closure.
2. From finite element calculations and estimates based on experiments.
3. Maximum crown/skirt lift-off distance in mils based on crown/skirt model.
4. From crown/skirt interaction model.
5. Equals  $\sigma_{max}$  with no lift-off if  $\delta_L = 0$ , adjusted from finite element  $\sigma_{max}$  with lift-off if  $\delta_L > 0$  by use of crown/skirt interaction model.

COMPARISON OF PEAK STRESS IN STUD BOSS  
REGION OF AE PISTON SKIRT FOR LOADS  
APPLIED ON INNER AND OUTER CONTACT RINGS.

(Values calculated by finite element)

$\sigma_{III}$ , ksi

---

force pA applied by uniform displacement on:

inner ring	43.3
outer ring	3.3

---

p = 1627 psig  
A = bore area

**COMPARISON OF EXPERIMENTAL AND NUMERICAL  
GAP CLOSURE AND LOAD SPLIT**


		Experiment	Calculated
Gap, $g_0$ , mils	nominal	7.5	--
	min	7.0	--
	max	8.0	--
Gap Closure Pressure, psig	nominal	1000	1040
	min	820	970
	max	1050	1110
Load Split at 1670 psig	nominal	88%	85%
	min	--	83%
	max	--	87%

COMPARISON OF SKIRT STIFFNESSES AS EVALUATED FROM  
EXPERIMENTAL OBSERVATION AND CROWN/SKIRT INTERACTION MODEL  
WITH CORRESPONDING FINITE ELEMENT VALUES


			AE
<b>EXPERIMENTS</b>	$k'_i$ , kips/mil	nominal	83.7
		min	45.7
		max	121
	$k'_o$ , kips/mil	nominal	7.95
		min	24.0
		max	283
<b>FINITE ELEMENTS</b>	$k_i$		81.2
	$k_o$		95.3
	$k_{io}$		500
	$k'_i$		96.9
	$k'_o$		118

$$\frac{1}{k'_i} = \frac{1}{k_i} - \frac{1}{k_{io}}$$


$$\frac{1}{k'_o} = \frac{1}{k_o} - \frac{1}{k_{io}}$$



Mean and cyclic stresses for infinite fatigue life. The shaded region shows the combination of stress amplitude ( $\sigma_a$ ) and mean stress ( $\sigma_m$ ) that will not initiate cracks.



Stress states for isothermeal AE piston skirt for various gap sizes plotted on graph of allowable stress amplitude as a function of mean stress.



Stress states for AE piston skirt for various conditions plotted on graph of allowable stress amplitude as a function of mean stress for various gap sizes and for isothermal and steady-state temperature conditions.

SUMMARY OF FRACTURE TOUGHNESS DATA FROM THE LITERATURE FOR  
 NODULAR CAST IRON WITH STRENGTH LEVELS  
 SIMILAR TO 100-70-03

$K_{Ic}$ ksi-in <sup>1/2</sup>	T, °F	$\sigma_{ult}$ , ksi	$\sigma_{ys}$ , ksi	Elong. %	Reference
41	70	133	80	3.6	6-6
36	70	85.3	76	1.6	6-6
48	220	116	90	--	6-7
40	70	116	90	--	6-7
~85	70	90	58	--	6-7
25	75	>80	>62	>3.0	6-1
47	75	--	104	--	6-1


Nominal value for calculations: 40 ksi-in<sup>1/2</sup>.



□ STRESS RATIO, R (dimensionless)

△ THRESHOLD STRESS INTENSITY FACTOR RANGE,  $\Delta K_{TH}$  (ksi $\sqrt{in}$ )

○ STRESS INTENSITY FACTOR RANGE,  $\Delta K$  (ksi $\sqrt{in}$ )



EDG 101

## INTEROFFICE CORRESPONDENCE

TO: DISTRIBUTION	LOCATION SNPS-1	SUBJECT / REFERENCE / J.O. NO. 11600.37 Component No. 03-341A
FROM: R. MURRAY	LOCATION QEG	TRANSMITTAL OF SAT I.R.'s Att. 1

MESSAGE: —

*Att 1*

ATTACHED PLEASE FIND one SATISFACTORY INSPECTION REPORTS  
GENERATED BY THE QUALITY REVALIDATION INSPECTION GROUP AND REVIEWED BY  
THE QUALITY ENGINEERING GROUP. THEY ARE FORWARDED TO YOU FOR YOUR  
INFORMATION IN ACCORDANCE WITH EDG QR/DR PROGRAM MEMO R. NAJUCH

3-21-84

DATE



SIGNATURE

564

TELEPHONE

REPLY:

DIST. R. NAJUCH (IOC ONLY)  
G. ROGERS DRG W/ ATTACHMENTS  
J. E. KELLY LILCO FQA (NDE RELATED IR'S ONLY) W/ATTACHMENTS.

DATE

SIGNATURE

TELEPHONE

A 040 138

QUALITY CONTROL INSPECTION REPORT


JOB NUMBER 11600.37 DATE 3-21-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: Pistons  COMPONENT NO. 03-341A	DC-101	I.P. NO. 14 REV. 4 CHG 0 TER # N/A LILCO LP PROC. 6.2 REV. 1 DWG. NO. N/A

WG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	1	2	Performed LP on Piston Pin Bosses  Cylinder Nos 5 & 7 SAT  No Recordable Indications
M&TE NO. _____			

REVIEWED: H.F. Stettin 3/21/84

QUALITY CONTROL INSP./ENG. [Signature] DATE 3-21-84 PAGE 1 of 2



A. MATERIAL <i>Carbon Steel</i>		TYPE <i>n/a</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX MIN <i>n/a</i>	PIPE DIA. <i>n/a</i>	SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER
GEOMETRY		<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD	<input checked="" type="checkbox"/> OTHER:

B. NDE PROCEDURE No. <i>6.2 Rev 1</i>	SURFACE/MAT'L. TEMP. <i>78°F</i>	M&TE. NO. <i>7-11-708</i>	MWR/RR. No.
---------------------------------------	----------------------------------	---------------------------	-------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>MagnaFlux</i>	<i>SKC-NF/ZC-7B</i>	<i>84A028</i>
2. PENETRANT	<i>Spotcheck</i>	<i>SKL-HF/SL-5</i>	<i>81E180</i>
3. EMULSIFIER AND/OR REMOVER	<i>MagnaFlux</i>	<i>SKC-NF/ZC-7B</i>	<i>84A028</i>
4. DEVELOPER	<i>MagnaFlux</i>	<i>SKD-NF/ZP-9B</i>	<i>83HC-11</i>
5. POST EXAMINATION CLEANER	<i>MagnaFlux</i>	<i>SKC-NF/ZC-7B</i>	<i>84A028</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

*DG-101*

*LP on cylinders #5 & #7 Piston Pin Bosses*

*No Recordable Indications*

C. EVALUATION

REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
1			
2			
3			
4			

D. ACCEPTANCE CRITERIA	<i>4.2</i>	OPERATOR <i>David Wilson</i>	Level <i>II</i> Date <i>3-21-84</i>
------------------------	------------	------------------------------	-------------------------------------

E. ATTEST	<i>David Wilson</i>	RESPONSIBLE CERTIFIED	LEVEL <i>II</i>	DATE <i>3-21-84</i>
-----------	---------------------	-----------------------	-----------------	---------------------

PT

COMPONENT I.D. *03-341-A*

*Piston Pin Bosses*

SYSTEM

*R-43*

PLANT/LOCATION

# INTEROFFICE CORRESPONDENCE

TO: DISTRIBUTION	LOCATION SNPS-1	SUBJECT / REFERENCE / J.O. NO. 11600.37 <i>DB 101</i> <i>03-341A</i>
FROM: R. MURRAY	LOCATION QEG	TRANSMITTAL OF SAT I.R.'s <i>ATT #1</i>

MESSAGE: —

ATTACHED PLEASE FIND 1 SATISFACTORY INSPECTION REPORTS *2pgs*  
 GENERATED BY THE QUALITY REVALIDATION INSPECTION GROUP AND REVIEWED BY  
 THE QUALITY ENGINEERING GROUP. THEY ARE FORWARDED TO YOU FOR YOUR  
 INFORMATION IN ACCORDANCE WITH EDG QR/DR PROGRAM MEMO R. NAJUCH

3-22-84  
DATE

*R. D. Murray*  
SIGNATURE

562  
TELEPHONE

REPLY:

- DIST. R. NAJUCH (IOC ONLY)
- G. ROGERS DRG W/ ATTACHMENTS
- E. KELLY LILCO FQA (NDE RELATED IR'S ONLY) W/ATTACHMENTS.

\_\_\_\_\_  
DATE

\_\_\_\_\_  
SIGNATURE

\_\_\_\_\_  
TELEPHONE

A 040 138

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

1049 12

JOB NUMBER 11600.37	DATE 3-22-84
REFERENCE DOCUMENT(S)	
I.P. NO. <u>14</u> REV. <u>4</u> CHG <u>0</u>	
TER # <u>NA</u>	
LILCO LP PROC. <u>G.1/5.2</u> REV. <u>2/1</u>	
DWG. NO. <u>NA</u>	

SYSTEM(S) OR PART(S) NAME	LOCATION(S)
COMPONENT NAME: Piston Cyl #8 Reinspection Boss #1	DG- <u>101</u>
COMPONENT NO. <u>03-341A</u>	

WG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	1	1	PT performed per request of LILCO representative.  * Witnessed By Nelson C. IRVING; Lilco III Nelson C. Irving LIII 3-22-84
NOTE NO. <u>7-11-708</u>			



LIGUID PENETRANT EXAMINATION REPORT


A. MATERIAL		TYPE	FABRICATED PROCESS		
		GEOMETRY	<input type="checkbox"/> PIPE	<input type="checkbox"/> PLATE	<input type="checkbox"/> ROD
CROSS SECTION THICKNESS	MAX 6" MIN 1/8"	PIPE DIA. NA	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
				<input checked="" type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

PT  
COMPONENT I.D.  
03-30-74

B. NDE PROCEDURE No. <u>61/62</u>	SURFACE/MAT'L. TEMP. <u>73°F</u>	M&TE. NO. <u>7-11-78</u>	MWR/RR. No.
-----------------------------------	----------------------------------	--------------------------	-------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	Magnaflux	SKC-NF/ZC-7B	81A028
2. PENETRANT	Magnaflux	SKL-HF/SKL-S	81E180
3. EMULSIFIER AND/OR REMOVER	Magnaflux	SKC-NF/ZC-7B	81A028
4. DEVELOPER	Magnaflux	SKD-NF/ZP-9B	834041
5. POST EXAMINATION CLEANER	Magnaflux	SKC-NF/ZC-1P	81A028

SYSTEM  
Diesel Generator ID1



C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIT (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
1			No relevant indications exceeding acceptance criteria; no linear indications.
2			
3			
4			

PLANT/LOCATION  
Shoreham

D. ACCEPTANCE CRITERIA	proc. 6.2 para. 4.2	OPERATOR <u>Carl Jensen</u>	Level <u>II</u> Date <u>3-22-84</u>
------------------------	---------------------	-----------------------------	-------------------------------------

E. ATTEST	<u>Nelson Cole</u> RESPONSIBLE CERTIFIED PERSON	<u>III Lilco</u> LEVEL	<u>3-22-84</u> DATE
-----------	--	---------------------------	------------------------



# INTEROFFICE CORRESPONDENCE

TO: DISTRIBUTION	LOCATION SNPS-1	SUBJECT / REFERENCE / J.O. NO. 11600.37 Component No. 03-341A
FROM: R. MURRAY	LOCATION QEG	TRANSMITTAL OF SAT I.R.'s Att. 1

MESSAGE: ---

ATTACHED PLEASE FIND One SATISFACTORY INSPECTION REPORTS  
 GENERATED BY THE QUALITY REVALIDATION INSPECTION GROUP AND REVIEWED BY  
 THE QUALITY ENGINEERING GROUP. THEY ARE FORWARDED TO YOU FOR YOUR  
 INFORMATION IN ACCORDANCE WITH EDG QR/DR PROGRAM MEMO R. NAJUCH

3-26-84  
 DATE

*R. Murray*  
 SIGNATURE 564  
TELEPHONE

REPLY:

DIST. R. NAJUCH (IOC ONLY)  
 G. ROGERS DRG W/ ATTACHMENTS  
 J. E. KELLY LILCO FQA (NDE RELATED IR's ONLY) W/ATTACHMENTS.

DATE \_\_\_\_\_ SIGNATURE \_\_\_\_\_ TELEPHONE \_\_\_\_\_

▲ 040 118

QUALITY CONTROL  
INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3-26-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: <i>Piston</i>  COMPONENT NO. <u>03-341A</u>	DG- <u>101</u>	I.P. NO. <u>17</u> REV. <u>7</u> CHG <u>0</u>  TER # <u>Q91</u> LILCO LP PROC. <u>6.2</u> REV. <u>1</u>  DWG. NO. <u>n/a</u>

DWG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	1	1	Performed a Lhexam on Piston = 8 Buses A, C 10, SAT
M&TE NO. <u>N/A</u>			

REVIEWED: *AW. Samuel*  
3-21-84

QUALITY CONTROL INSPEC. ENG. *Michael J. [Signature]* DATE 3-26-84 PAGE 1 OF 2



LIIQUID PENETRANT EXAMINATION REPORT

page 2 of 2

A. MATERIAL		TYPE	FABRICATED PROCESS		PT	
Carbon Steel		GEOMETRY	<input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED			
		<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER:				
CROSS SECTION THICKNESS	MAX MIN	PIPE DIA.	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input checked="" type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER	COMPONENT I.D. Piston 03-5414	
	N/A	N/A				
B. NDE PROCEDURE No.	6.2	SURFACE/MAT'L. TEMP.	80°F	MATE. NO.		7-11-708
				MWR/RR. No.		N/A
INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.			
1. PRE-CLEANER	Magnaflux	SKC-NF/ZC-7B	84A028			
2. PENETRANT	Spotcheck	SKL-HF/SKL-S	81E180			
3. EMULSIFIER AND/OR REMOVER	Magnaflux	SKC-NF/ZC-7B	84A028			
4. DEVELOPER	Magnaflux	SKD-NF/ZP-7B	83H041			
5. POST EXAMINATION CLEANER	Magnaflux	SKC-NF/ZC-7B	84A028			
SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY Performed L. Preexam of Piston #8, Bases A, C, & D Sat						
C. EVALUATION		REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.				
LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)			
1			A			
2						
3						
4	N					
D. ACCEPTANCE CRITERIA	4.2	OPERATOR	Michael [Signature] Level 2    Date 3/26/84			
E. ATTEST	[Signature] RESPONSIBLE	[Signature] TEST PERSONNEL	[Signature] LEVEL	[Signature] DATE 3/26/84		

SYSTEM R43

PLANT/LOCATION DC-101

**LILCO**

**DEFICIENCY REPORT**

FIELD  
 OTHER

LDR RESPONSIBILITY

LDR NUMBER

M. Herlihy  
LSU

2266

101 OUTAGE

2	SYSTEM/COMPONENT <u>EMER Diesel Gen</u>	SYSTEM DESIGNATOR <u>1843</u>	MARK NO. <u>1843R EDG 101</u>	DATE <u>3/21/84</u>	Q CLASS <input checked="" type="checkbox"/> I <input type="checkbox"/> II <input type="checkbox"/> III
3	MFG./CONTRACTOR <u>TRE</u>	P.O. <u>310552</u>	MATERIAL LOCATION <u>TR 62' up down area</u>	REJECT TAG NO. <u>492</u>	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
4	SPEC. VIOLATED <u>SWI-089</u>	DRAWING VIOLATED <u>N/A</u>	PROCEDURE VIOLATED <u>N/A</u>	CODE/STANDARD VIOLATED <u>N/A</u>	

CONDITION DETAILS TAB 9 - 335 (03-341A) reports onset conditions. Attached OGER and LP exam report for piston Cyl #8 show conditions requiring engineering evaluation.

03-341A

FOR INFORMATION ONLY

6	ORIGINATOR <u>C. Romano</u> SIGNATURE	<u>3/21/84</u> DATE	OQAE <u>[Signature]</u> SIGNATURE	<u>3/21/84</u> DATE
---	---	------------------------	---	------------------------

7	RESPONSIBILITY <input type="checkbox"/> LSU <input checked="" type="checkbox"/> S & W ENG.	<u>[Signature]</u> SIGNATURE/LEAD SU ENG.	DATE <u>3/21/84</u>
---	--	--	------------------------

8	ACTION <input checked="" type="checkbox"/> ACCEPT AS IS <input type="checkbox"/> SCRAP	<input type="checkbox"/> REWORK <input type="checkbox"/> REPAIR	<input type="checkbox"/> MANUAL <input type="checkbox"/> PROCEDURE	<input type="checkbox"/> FSAR <input type="checkbox"/> OTHER
---	--	--	---	---

DISPOSITION DETAILS  
ACCEPT AS IS. AREA OF CONCERN, BOLT HOLE BOSS AREA, WAS REEXAMINED. REFERENCE ATTACHED INSPECTION REPORT DATED 3/22/84. NO RELEVANT INDICATIONS WERE IDENTIFIED.

10	APPROVALS <u>[Signature]</u> S & W LEAD ENG./LSU TEST ENG./DATE	<u>3/24/84</u> DATE	<u>[Signature]</u> PROJECT ENGINEER	<u>3/24/84</u> DATE
----	---	------------------------	--	------------------------

11	<u>[Signature]</u> LILCO BU ENG.	<u>3/24/84</u> DATE	<u>[Signature]</u> LILCO SITE OGA	<u>3/27/84</u> DATE	REPAIR/REWORK REQUEST NO. <u>N/A</u>
----	-------------------------------------	------------------------	--------------------------------------	------------------------	---

12	ENG. COMPLETE/DATE <u>N/A</u>	RRR COMPLETE <u>N/A</u>	REWORK INSPECTION <input type="checkbox"/> SAT. <input type="checkbox"/> UNSAT.	<u>N/A</u>	LILCO SITE OGA/DATE
----	----------------------------------	----------------------------	---	------------	---------------------

13	LDR CLOSED <u>[Signature]</u> LILCO SITE OGA/DATE	<u>3/27/84</u> DATE	NEW LDR REPORT NO. ISSUED <u>N/A</u>	REMARKS <u>N/A</u>
----	---	------------------------	---	-----------------------

SYSTEM/COMPONENT NO. CYL. # B DG 03-341A 101	TDI PART NO. 1A-6522 03-341A	INITIATOR <u>G. G. Gluka</u> SIGNATURE	DATE 3-20-84	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
--	------------------------------------	--	-----------------	---

CONDITION DETAILS: ATTACHED INSPECTION REPORT (2 PAGES) GENERATED BY C. LARSON  
DATED 3-20-84 REPORTS UNSATISFACTORY INSPECTION RESULTS FOR THIS PART.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR DISPOSITION. *in Attached is unsatisfactory - see sheet 2 for recommended disposition*

REQUIRED COMPLETION DATE:

ASSIGNMENT

DISPOSITION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>Michael Sturmy</u> SIGNATURE	DATE 3-20-84
---	---	-----------------

DISPOSITION

DISPOSITION DETAILS:

DISPOSITION ASSIGNED TO <input type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY <input type="checkbox"/> NONE REQUIRED					
APPLIED BY	DATE	REVIEWED BY	DATE	APPROVED BY	DATE
_____	_____	_____	_____	_____	_____
RESP. CHAIRPERSON			PROGRAM MANAGER		

ACTION

ACTION ASSIGNED TO	ACTION COMPLETED BY	DATE
_____	_____	_____

CKS/GWR/RJW/ZFM  
SER LOG

Distribute for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-335", for each component affected.
- 2) SPO (J. Kammerer) - distribute for information.
- 3) LSU/OJA - review for applicability and issue LDR as needed.
- 4) M. Schuster - obtain LDR number as issued for component files and closeout.







STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3-22-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
<p>COMPONENT NAME: Cyl #8</p> <p>COMPONENT NO. 03-341A</p>	<p>DC-101</p>	<p>I.P. NO. 14 REV. 4 CHG 0</p> <p>TER # NA</p> <p>LILCO LP PROC. 6.1/2 REV. 2'</p> <p>DWG. NO. NA</p>

DWG NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	1	1	<p>PT performed per request of LILCO representative.</p> <p>* Witnessed By Nelson C. IRVING: LILCO III</p> <p>Nelson C. Irving LIII.</p> <p>3-22-84</p>

DATE NO. 7-11-709



LIVID PENETRANT EXAMINATION REPORT


A. MATERIAL	TYPE	FABRICATED PROCESS: <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED		
	GEOMETRY	<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER:		
CROSS SECTION THICKNESS	MAX 6" MIN 1/2"	PIPE DIA. NA	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER

COMPONENT I.D. 03-341A

B. NDE PROCEDURE No. 61/62	SURFACE/MAT'L. TEMP. 72°F	MATE. NO. 7-1-78	MWR/RR. No.
----------------------------	---------------------------	------------------	-------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	Magnaflux	SKC-UF/ZC-7B	84A028
2. PENETRANT	Magnaflux	SKL-4F/SKL-S	81E180
3. EMULSIFIER AND/OR REMOVER	Magnaflux	SKC-UF/ZC-7B	84A028
4. DEVELOPER	Magnaflux	SKD-UF/ZP-7B	83H041
5. POST EXAMINATION CLEANER	Magnaflux	SKC-UF/ZC-7F	84A028

SYSTEM Diesel Generator ID1



C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
1			No relevant indications exceeding acceptance criteria; no linear indications.
2			
3			
4			

PLANT/LOCATION Shoreham

D. ACCEPTANCE CRITERIA	proc. C.2 para 4.2	OPERATOR <u>Carl Jensen</u>
		Level <u>II</u> Date <u>3-22-89</u>

E. TEST	<u>William C. ...</u>	<u>III Lico</u> 3-22-89
---------	-----------------------	-------------------------

EDG 102

# INTEROFFICE CORRESPONDENCE

102

TO: DISTRIBUTION	LOCATION SNPS-1	SUBJECT / REFERENCE / J.O. NO. 11600.37 03-34/4
FROM: R. MURRAY	LOCATION QEG	TRANSMITTAL OF SAT I.R.'s

MESSAGE: —

ATTACHED PLEASE FIND 2 SATISFACTORY INSPECTION REPORTS  
 GENERATED BY THE QUALITY REVALIDATION INSPECTION GROUP AND REVIEWED BY  
 THE QUALITY ENGINEERING GROUP. THEY ARE FORWARDED TO YOU FOR YOUR  
 INFORMATION IN ACCORDANCE WITH EDG QR/DR PROGRAM MEMO R. NAJUCH

2-23-84  
 DATE

*R. Murray*  
 SIGNATURE

TELEPHONE

REPLY:

- DIST. R. NAJUCH (IOC ONLY)
- G. ROGERS FAAA W/ ATTACHMENTS
- J. KAMMEYER SEO W/ ATTACHMENTS
- E. YOUNGLING LSU W/ ATTACHMENTS

ATT #2 LF 5, 6, 7, 8

DATE

▲ 040.138

SIGNATURE

TELEPHONE

QUALITY CONTROL  
INSPECTION REPORT

WGT NUMBER

1160037

DATE

2-12-84

SYSTEM(S) OR  
PART(S) NAME

LOCATION(S)

REFERENCE  
DOCUMENT(S)

PISTON  
03-341A REV D

DG-102

IP NO. 14  
PROC 62 REV 2

PER REQUEST OF  
MEL SCHUSTER CYCLE  
WAS TESTED.

WG NO  
OR P.O.

ITEM QTY.

DESCRIPTION(S) AND INSPECTION REMARK(S)

2 ~~4~~ PERFORMED A LP TEST OF PISTON SKIRT AT BOSSES  
3 FOR BOLT ATTACHMENT OF CROWN ALSO LP TESTED THE  
PISTON PIN BOSS

SAT NO INDICATIONS FOUND

QUALITY CONTROL INSPECTOR

Edward I. Downer

DATE

2/14/84

PAGE

OF

PT  
COMPONENT I.D.  
C2-24-A

A. MATERIAL <i>CAR BON STEEL</i>		TYPE	FABRICATED PROCESS	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		MAX <i>N/A</i>	MIN <i>N/A</i>	PIPE DIA. <i>N/A</i>	SURFACE CONDITION	
					<input type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
					<input checked="" type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

B. NDE PROCEDURE No. <i>LP 61462 REV1</i>	SURFACE/MAT'L. TEMP. <i>72 F</i>	M&E. NO. <i>7-17-469</i>	MWR/RR. No. <i>N/A</i>
--	----------------------------------	--------------------------	------------------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>SPOTCHECK</i>	<i>SKL-NI/20-7B</i>	<i>834095</i>
2. PENETRANT	<i>SPOTCHECK</i>	<i>SKL-NI/3405</i>	<i>81E180</i>
3. EMULSIFIER AND/OR REMOVER	<i>SPOTCHECK</i>	<i>SKL-NI/20-7B</i>	<i>834095</i>
4. DEVELOPER	<i>SPOTCHECK</i>	<i>SKL-NI/</i>	<i>81E092</i>
5. POST EXAMINATION CLEANER	<i>SPOTCHECK</i>	<i>SKL-NI/20-7B</i>	<i>834095</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

*PISTON 5, 7 & 8 PERFORMED LP TEST OF PISTON SKIRT AT BOSSES FOR BOLT ATTACHMENT AND ALSO LP TESTED THE PISTON PIN BOSS*

SYSTEM  
Piston Skirt Bosses  
D6102  
Piston Pin Boss  
Piston Pin Boss

C. EVALUATION

REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>1 NO INDICATIONS</i>			<i>ACCEPT</i>
<i>2 N/A</i>			
<i>3 N/A</i>			
<i>4 N/A</i>			

D. ACCEPTANCE CRITERIA	OPERATOR <i>Clayton D. Mason</i>
	Level <i>II</i> Date <i>2-2-74</i>

E. ATTEST	<i>Robert J. Barnes</i>	<i>II</i>	<i>2-2-74</i>
	RESPONSIBLE CERTIFIED PERSONNEL	LEVEL	DATE

PLANT/LOCATION  
ME

QUALITY CONTROL  
INSPECTION REPORT

STATE & WEBSTER ENGINEERING CORPORATION

JOB NUMBER

11500.37

DATE

2-12-84

SYSTEM(S) OR  
PART(S) NAME

#6 Piston Assembly  
03-341 A  
REV 0

LOCATION(S)

DG-102

REFERENCE  
DOCUMENT(S)

Per Request of M. Schuster

WG NO  
OR PO

ITEM

QTY.

DESCRIPTION(S) AND INSPECTION REMARK(S)

2 1

Performed L.P. inspection on #6 piston pin boss.  
No Indications found.

QUALITY CONTROL INSPECTOR

*[Signature]*

DATE

2-12-84

PAGE

1 of 2

COMPONENT I.D.

SYSTEM #6 Piston Assembly

PLANT/LOCATION DG-102

A. MATERIAL		TYPE	FABRICATED PROCESS	
			<input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED	
		GEOMETRY	<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER:	
CROSS SECTION THICKNESS	MAX MIN	PIPE DIA.	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input checked="" type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER

B. NDE PROCEDURE No.	SURFACE/MAT'L. TEMP. 72°F	M&TE. NO. 7-11-699	MWR/RR. No.
----------------------	---------------------------	--------------------	-------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	Spotcheck	SKC-AF/2C-7B	83H095
2. PENETRANT	Spotcheck	SKL-HF/SKL-5	81E180
3. EMULSIFIER AND/OR REMOVER	Spotcheck	SKC-AF/2C-7B	83H095
4. DEVELOPER	Spotcheck	SKD-AF	81G092
5. POST EXAMINATION CLEANER	Spotcheck	SKC-AF/2C-7B	83H095

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

Performed L.P. inspection on #6 piston pin boss, per request M. Schuster. No Indications found.

C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
1 N/A			
2 N/A			
3 N/A			
4 N/A			

D. ACCEPTANCE CRITERIA	OPERATOR _____
	Level _____ Date _____

E. ATTEST	<i>[Signature]</i>	LEVEL	DATE
	RESPONSIBLE OFFICIAL PERSONNEL	I	2-17-54



EDG 103

# INTEROFFICE CORRESPONDENCE 103

TO: DISTRIBUTION	LOCATION SNPS-1	SUBJECT / REFERENCE / J.O. NO. 11600.37
FROM: R. MURRAY	LOCATION QEG	03 341A TRANSMITTAL OF SAT I.R.'s AT #1

MESSAGE: —

ATTACHED PLEASE FIND 1 SATISFACTORY INSPECTION REPORTS (2pgs)  
 GENERATED BY THE QUALITY REVALIDATION INSPECTION GROUP AND REVIEWED BY  
 THE QUALITY ENGINEERING GROUP. THEY ARE FORWARDED TO YOU FOR YOUR  
 INFORMATION IN ACCORDANCE WITH EDG QR/DR PROGRAM MEMO R. NAJUCH

3/12/84  
DATE

*R. Murray*  
SIGNATURE

564  
TELEPHONE

REPLY:

DIST. R. NAJUCH (IOC ONLY)  
 G. ROGERS DRG W/ ATTACHMENTS

DATE

SIGNATURE

TELEPHONE

**QUALITY CONTROL  
INSPECTION REPORT**

JOB NUMBER 1:600.37 DATE 3-12-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: <u>PISTONS</u>	DG- <u>103</u>	I.P. NO. <u>14</u> REV. <u>3</u> CHG <u>0</u>
COMPONENT NO. <u>03-341A</u>		TER # _____
		LILCO LP PROC. <u>6</u> REV. <u>1</u>
		DWG. NO. _____

OWG. NO OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	<u>2</u> <u>1</u>	<u>3</u>	PERFORMED LP EXAM ON PISTON SKIRT AT THE BOSSES FOR BOLT ATTACHMENT OF CROWN  DE 103 PISTONS # 5,74-8  <u>SAT.</u>
M&TE NO. <u>7-11-708</u>			

*Inspected by [Signature]*



LIQUID PENETRANT EXAMINATION REPORT

114225

<b>A. MATERIAL</b> CARBON		<b>TYPE</b>	<b>FABRICATED PROCESS</b> <input type="checkbox"/> WELDED <input type="checkbox"/> CAST <input type="checkbox"/> WORKED	
<b>CROSS SECTION THICKNESS</b> MAX $\frac{N}{A}$ MIN $\frac{N}{A}$		<b>GEOMETRY</b> <input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input type="checkbox"/> OTHER:	<b>SURFACE CONDITION</b> <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER	
<b>PIPE DIA.</b> $\frac{N}{A}$				

<b>B. WDE PROCEDURE No.</b> 6.2 REV 1	<b>SURFACE/MAT'L. TEMP.</b> 71°	<b>M&amp;E. NO.</b> 71170	<b>MWR/RR. No.</b>
--	------------------------------------	------------------------------	--------------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	MAGNAFLUX	SK-11/70-70	83H100
2. PENETRANT	SPECTHECK	SK-2-11/70-75	81E100
3. EMULSIFIER AND/OR REMOVER	MAGNAFLUX	SK-11/70-75	83H100
4. DEVELOPER	MAGNAFLUX	SK-11/71-96	83H041
5. POST EXAMINATION CLEANER	MAGNAFLUX	SK-11/70-75	83H100

**SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY**  
 EPD 3-1284  
 DE103 CYLINDER HEAD PISTONS # 5, 718  
 PERFORMED L.P. OF PISTON SKIRT AT THE LOSSES FOR BOLT ATTACHMENT OF CROWN

**C. EVALUATION**  
 REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
1	$\frac{N}{A}$	$\frac{N}{A}$	ACCEPT
2			
3			
4			

<b>D. ACCEPTANCE CRITERIA</b>	<b>OPERATOR</b>	<b>Level</b>	<b>Date</b>
-------------------------------	-----------------	--------------	-------------

<b>E. ATTEST</b>	<u>Edna M. Johnson</u>	<u>J</u>	<u>3-12-84</u>
	RESPONSIBLE CERTIFIED PERSONNEL	LEVEL	DATE

PT COMPONENT I.D. 0-20014

SYSTEM 103

PLANT/LOCATION DE103

EDG 101

# INTEROFFICE CORRESPONDENCE


TO: DISTRIBUTION	LOCATION SNPS-1	SUBJECT / REFERENCE / J.O. NO. 11600.37 Component No. 03-341A
FROM: R. MURRAY	LOCATION QEG	TRANSMITTAL OF SAT I.R.'s <u>Att 3</u>

MESSAGE: —

ATTACHED PLEASE FIND one SATISFACTORY INSPECTION REPORTS  
 GENERATED BY THE QUALITY REVALIDATION INSPECTION GROUP AND REVIEWED BY  
 THE QUALITY ENGINEERING GROUP. THEY ARE FORWARDED TO YOU FOR YOUR  
 INFORMATION IN ACCORDANCE WITH EDG QR/DR PROGRAM MEMO R. NAJUCH

3-26-87

DATE



SIGNATURE

568

TELEPHONE

REPLY:

DIST. R. NAJUCH (IOC ONLY)  
 G. ROGERS DRG W/ ATTACHMENTS  
 J. E. KELLY LILCO FQA (NDE RELATED IR's ONLY) W/ATTACHMENTS.

DATE

SIGNATURE

TELEPHONE

A 040138

# INTEROFFICE CORRESPONDENCE


TO: Ken Morrow	LOCATION	SUBJECT / REFERENCE / J.O. NO. FaAA Report # 840321-2
FROM: Don Johnson	LOCATION FaAA	ET of DG 101 Pistons #5,7,&8

MESSAGE:—

Attached is FaAA Report # 840321-2, Eddy Current Examination of DG 101 Pistons # 5, 7, & 8.

No relevant indications were observed.

3/21/84  
DATE

  
SIGNATURE

582  
TELEPHONE

REPLY:

DATE

SIGNATURE

TELEPHONE





EDDY CURRENT CALIBRATION REPORT

Job No. 03340A Date 2-21-84 Report No. 830321-2  
 Material Description NODULAR IRON  
 Code or Specification NDE 11.5 REV. 1 Full On N/A Full Off N/A  
 Reference Standard PAO-C-1 Instrument MIZ 17 S/N B133867

Instrument

Freq. 2 MHz Gain 30 Volts/div 0.5 Phase 210  
 Test Probe FaAA ECP 100P S/N 100P  
 Reference Probe FaAA ECP 100P S/N 100P-1

CALIBRATION

<u>4</u> units @ <u>-1.5</u> L/O	<u>3.5</u> units @ <u>+0.2</u> L/O
<u>4</u> units @ <u>-0.75</u> L/O	<u>2.6</u> units @ <u>+1.25</u> L/O

STRIP CHART RECORDER

Type N/A S/N N/A

Channel 1

Channel 2


Sen N/A Sen N/A  
 Position @ Null Point N/A Position @ Null Point N/A  
 Chart Speed N/A mm/sec

Calibration Check

Time <u>12:21 PM</u>	Phase <u>210</u>	Gain <u>30</u>
Time <u>12:27</u>	Phase <u>210</u>	Gain <u>30</u>
Time <u>12:35</u>	Phase <u>210</u>	Gain <u>30</u>
Time <u>12:41 EOT</u>	Phase <u>210</u>	Gain <u>30</u>
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____


Examiner [Signature] Level II Examiner \_\_\_\_\_ Level \_\_\_\_\_  
 R&D-KR-3

Diesel engine  $\leftrightarrow$  D6101  
 Piston  $\leftrightarrow$  8  
 Condition SAT




Notch side

Overhead view




Side views, looking out from inside




11.5.8.4


Diesel engine # D5101  
Piston # 7  
Condition SAT




Overhead view



Side views, looking out from inside




Diesel engine  $\clubsuit$  R6101  
Piston  $\clubsuit$  5  
*Condition - SAT*




Notch side

Overhead view



Side views, looking out from inside



EDG 102

Q-38 s.p.

INFO

COMPONENT TASK EVALUATION REPORT

ATT #4

ITEM/COMPONENT NO. 23-341A	TDI PART NO. 1A-6522	INITIATOR <i>[Signature]</i>	DATE 2/20/84	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
-------------------------------	-------------------------	---------------------------------	-----------------	---

CONDITION DETAILS: ATTACHED INSPECTION REPORT (5 PAGES) BY D. O. JOHNSON AT D2-14-84 WAS GENERATED AS INFORMATIONAL, AS NO ACCEPTANCE CRITERIA WAS PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION. SUBJECT I.R. GENERATED BY F.A.A. (EDDY CURRENT).  
 RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION AND ALSO TO SEO AND LSU FOR INFORMATION ONLY.

REQUIRED COMPLETION DATE: 2/21/84

ASSIGNMENT

POSITION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>R. Fraser</u> SIGNATURE	DATE 2-21-84
--	--	-----------------

DISPOSITION

DISPOSITION DETAILS: Send copy to C. Wells / FAA, SEO, and LSU. See TER N2 Q-50.gj

DISPOSITION ASSIGNED TO <input type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY <input type="checkbox"/> NONE REQUIRED					
APPLIED BY <u>Nelson</u>	DATE 2/25/84	REVIEWED BY <u>S. [Signature]</u> RESP. CHAIRPERSON	DATE 2/23/84	APPROVED BY <u>[Signature]</u> PROGRAM MANAGER	DATE 2/25/84

ACTION

ACTION ASSIGNED TO <u>C. Wells / FAA</u>	ACTION COMPLETED BY <u>[Signature]</u>	DATE 03-06-84
---	---	------------------

CKS/GWR/RJN/EFM  
TER LOG  
E.T. FOR 5,6,7,8

120530

11.4.10

EDDY CURRENT CALIBRATION REPORT

Failure Analysis Associate  
03-341A <sup>mmB</sup> 2/14/84

Job No. PAO 7396 Date 2-13-84 Report No. 831302-1  
Material Description NODULAR CAST IRON PISTON SKIRTS  
Code or Specification NDE 11.5 Full On -1.5 Full Off +1.5  
Reference Standard PAO-C-1 Instrument MIZ 17 S/N 8133867

Instrument

Freq. 2 MHz Gain 30 Volts/div 0.5 Phase 218  
Test Probe FAM ECP-100-P1 S/N ECP 100-P1  
Reference Probe FAM ECP-100 B-1 S/N ECP 100 B1

CALIBRATION

4 units @ -1.5 L/O      3.2 units @ -0 L/O  
3.5 units @ -1 L/O      2.6 units @ +1 L/O

STRIP CHART RECORDER

Type N/A S/N N/A

Channel 1      Channel 2  
Sen N/A      Sen N/A  
Position @ Null Point N/A      Position @ Null Point \_\_\_\_\_  
Chart Speed N/A mm/sec

Calibration Check

Time <u>11:20</u>	Phase <u>218</u>	Gain <u>30</u>
Time <u>11:23</u>	Phase <u>218</u>	Gain <u>30</u>
Time <u>11:26</u>	Phase <u>218</u>	Gain <u>30</u>
Time <u>11:32</u>	Phase <u>218</u>	Gain <u>30</u>
Time <u>11:35</u>	Phase <u>218</u>	Gain <u>30</u>
Time <u>11:40</u>	Phase <u>218</u>	Gain <u>30</u>
Time <u>11:45</u>	Phase <u>218</u>	Gain <u>30</u>
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____


Examiner D. J. Johnson Level II Examiner A. J. 0535 Level \_\_\_\_\_  
R&D-KR-3

11.5.8.4

03-54/A

Diesel engine + D6 102

Piston + 8




RELINQ Overhead view

NON INDICATION


EXEM IS SAT

2-25-86

DDF 2-13-84




Side views, looking out from inside





11.5.8.4

03-341A  
Diesel engine # DG 102  
Piston # 7





Notch side

Overhead view



REHMAT  
NONINDICATION  
ETAM is SAT

DD of 2-13-84

20537



Side views, looking out from inside




11-6-8-4

03-541A

Diesel engine # DG 102

Platon # 5




Notch side


Overhead view

RELCMAT  
RECONDICITION  
EXAM IS SAT.

DDF 2-13-84



Side views, looking out from inside



11.1.10

Failure Analysis Associates

EDDY CURRENT CALIBRATION REPORT

03-341A ~~1118~~

Job No. PAO 7396 Date 2-13-84 Report No. 831302-2  
 Material Description NODULAR CAST IRON PISTON SKIRTS  
 Code or Specification NDE 115 Full On -1.5 Full Off +1.5  
 Reference Standard PAO-C-1 Instrument MIZ 17 S/N 5133867

Instrument

Freq. 2 MHz Gain 30 Volts/div 0.5 Phase 218  
 Test Probe BWA ECP-100-P-1 S/N ECP-100-P-1  
 Reference Probe FMECP-100-B-1 S/N ECP-100-B-1

CALIBRATION

4 units @ -1.5 L/O      3.2 units @ -0 L/O  
3.5 units @ -1 L/O      2.6 units @ +1 L/O

STRIP CHART RECORDER

Type N/A S/N N/A

Channel 1

Channel 2





Sen N/A Sen N/A  
 Position @ Null Point N/A Position @ Null Point N/A  
 Chart Speed N/A mm/sec

Calibration Check

Time <u>2:21 PM</u>	Phase <u>217</u>	Gain <u>30</u>
Time <u>2:25 PM</u>	Phase <u>217</u>	Gain <u>30</u>
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____

Examiner DM Johnson Level II Examiner 110539 Level \_\_\_\_\_  
 R&D-KR-3

03-341A




Side views, looking out from inside

03-341A

Diesel engine # DG 102

Piston # 6



Notch side

Overhead view

NO RELEVANT INDICATIONS

EXAM IS SAT.

DDP 2-13-84

Q-38  
03-341A

( This inspection report is acceptable for  
design review

K. Lohr for C. Wells  
Conversation 3/6/84

(  
  
(  
  
(  
A30502

EDG 103


# INTEROFFICE CORRESPONDENCE

TO: DISTRIBUTION	LOCATION SNPS-1	SUBJECT / REFERENCE / J.O. NO. 11600.37 Component No. 03-341A
FROM: R. MURRAY	LOCATION QEG	TRANSMITTAL OF SAT I.R.'s

MESSAGE: —

ATTACHED PLEASE FIND one SATISFACTORY INSPECTION REPORTS  
 GENERATED BY THE QUALITY REVALIDATION INSPECTION GROUP AND REVIEWED BY  
 THE QUALITY ENGINEERING GROUP. THEY ARE FORWARDED TO YOU FOR YOUR  
 INFORMATION IN ACCORDANCE WITH EDG QR/DR PROGRAM MEMO R. NAJUCH

3-13-84  
 DATE

  
 SIGNATURE

TELEPHONE

REPLY:

DIST. R. NAJUCH (IOC ONLY)  
 G. ROGERS DRG W/ ATTACHMENTS

DATE

SIGNATURE

TELEPHONE

▲ 040138

EDDY CURRENT CALIBRATION REPORT

Job No. 03341A Date 3-13-84 Report No. 840313-1  
Material Description MODULAR IRON PISTON SKIRTS  
Code or Specification NDE 11.5 Full On -1.5 Full Off +1.5  
Reference Standard PH09396-840227 Instrument M12 17 S/N 033833

Instrument

Freq. 2 MHz Gain 30 Volts/div 0.5 Phase 202  
Test Probe FAM ECP 100P S/N 100P  
Reference Probe FAM ECP 100P S/N 100 P-1

CALIBRATION

2.2 units @ 0 L/O      1.8 units @ +1.5 L/O  
2.0 units @ +1 L/O      1.6 units @ +2.0 L/O

STRIP CHART RECORDER

Type N/A S/N N/A

Channel 1

Channel 2

Sen N/A Sen N/A  
Position @ Null Point N/A Position @ Null Point N/A  
Chart Speed N/A .mm/sec

Calibration Check

Time <u>16:37</u>	Phase <u>202</u>	Gain <u>30</u>
Time <u>16:45</u>	Phase <u>202</u>	Gain <u>30</u>
Time <u>16:52</u>	Phase <u>202</u>	Gain <u>30</u>
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____
Time _____	Phase _____	Gain _____

Examiner [Signature] Level II Examiner \_\_\_\_\_ Level \_\_\_\_\_  
R&D-KR-3




EDDY CURRENT EXAMINATION REPORT

Material NODULAR IRON PISTON SKIRT		Type: <u>PISTON SKIRT</u>	Fabricated process: <input type="checkbox"/> Welded <input type="checkbox"/> Worked	<input type="checkbox"/> Cast <input checked="" type="checkbox"/>	ET Component I.D. <u>PISTON SKIRTS ON</u> <u>D6103 #5 #7 #8</u>
Cross section thickness:		Max. <u>N/A</u> Inch	Min. <u>N/A</u> Inch	Surface condition: <input checked="" type="checkbox"/> Machined <input type="checkbox"/> As fabricated	
NDE Procedure no. <u>11.5</u>		Job no. <u>03341A</u>		Report no. <u>841313-1</u>	
Test condition: Ver <u>+1</u> Hor <u>0</u>		<u>2.2</u> Unit at <u>0</u> Lo			
Unit # <u>033823</u> Sen <u>30</u> Frq <u>2MHz</u>		<u>2.0</u> Unit at <u>+1</u> Lo			
Full-on <u>-1.5</u> Full-off <u>+1.5</u>		<u>1.8</u> Unit at <u>+1.5</u> Lo			
Reference no. <u>100P-1</u> Probe type <u>100P</u>		<u>1.6</u> Unit at <u>+2.0</u> Lo			
Indication no.	Magnitude of indication	Length of indication	Remarks		
			NO RECORDABLE INDICATIONS		
Specific examination area					
<u>SCAN AREA IN SIDE BELVILLE WASHER AREA, AROUND RADIUS.</u>					
Sketch or other data (use other side)					
Acceptance criteria	<u>Indication Greater than 50% of Reference Standard</u>		Operator: <u>DOU JOHNSON</u>	Level: <u>II</u>	Date: <u>3-24-81</u>
Attest	<u>[Signature]</u> Responsible certified personnel		Level: <u>II</u>	Date: <u>3-24-81</u>	<u>11 RRS</u>

Job name & no. PISTONS 03341A


Plant/location DIESEL GENERATORS ELU, G3

Diesel engine → 103  
Piston → 5




Overhead view

*NO RELEVANT INDICATORS*




Side views, looking out from inside




11.6.6.4

Diesel engine  $\leftrightarrow$  103  
Piston  $\leftrightarrow$  7




Overhead view


*NO RELEVANT INDICATIONS*



Side views, looking out from inside




Diesel engine # 103  
Piston # \_\_\_\_\_




Notch: 0.015

Overhead view



Side views, looking out from inside



*No RELEVANT INDICATION 10/23*

FaAA NDE Procedure

11.5, Rev. 0

# Failure Analysis Associates

## NONDESTRUCTIVE EXAMINATION PROCEDURE

Title: EDDY CURRENT INSPECTION PROCEDURE  
FOR NODULAR PISTON SKIRTS

NDE: 11.5

Page 1 of 2

Revision: 0

Date: 11/02/83

Reviewed - NDE Level III: Duan P Johnson

Date: 11-18-83

### 1.0 Purpose and Scope

- 1.1 To establish calibration, scanning and evaluation techniques for eddy current examination of nodular iron piston-skirts.
- 1.2 This instruction covers the eddy-current examination of the boss areas near the 4-bolt-holes inside the piston skirt.

### 2.0 Personnel Certification

- 2.1 Personnel performing eddy-current examination shall be certified to SNT-TC-1A Level II.

### 3.0 Equipment

- 3.1 Eddy-current instrument used with this instruction shall be an impedance-plane display instrument.
- 3.2 The eddy-current test probe shall be a FaAA-ECP-100-P or FaAA-ECP-200-P.
  - 3.2.1 The reference crack standard shall be PAO-C-1.

### 4.0 Examination Surface

- 4.1 Only those surfaces that have a machined or ground finish shall be tested.

### 5.0 Calibration Procedure

- 5.1 Set frequency to 2 MHz for ECP-100P probe or to 500 KHz for ECP-200P probe.
- 5.2 Set volts per division at 0.5.
- 5.3 Set gain at 30.
- 5.4 Adjust vertical and horizontal positioning controls such that balance point is at (0v, 1v).

# Failure Analysis Associates

## NONDESTRUCTIVE EXAMINATION PROCEDURE

Title: EDDY CURRENT INSPECTION PROCEDURE  
FOR NODULAR PISTON SKIRTS

NDE: 11.5  
Page 2 of 2  
Revision: 0  
Date: 11/02/83

- 5.5 Balance with probe on test piece.
- 5.6 Adjust horizontal attenuator such that horizontal saturation is greater than 1.5v and less than -1.5v.
- 5.7 Adjust phase angle such that probe lift-off causes the beam to move horizontally to the right on the CRT.
- 5.8 Adjust gain such that the crack in reference standard PAO-C-1 gives a 2v  $\pm$  0.2v negative signal at the horizontal center of the CRT.
- 5.9 Repeat steps 5.4 through 5.8 until items 5.4 through 5.8 are accomplished without further instrument adjustments.

### 6.0 Examination

- 6.1 Examination shall be of machined areas on the boss where color contrast penetrant show linear indications greater than 1/32 inch.

### 7.0 Recording Criteria

- 7.1 All indication showing a crack indication greater than 10% of the crack signal in the reference standard PAO-C-1 shall be recorded.
- 7.2 The length and orientation of the indication shall be recorded.

### 8.0 Records

- 8.1 The results of the examination shall be recorded on eddy current examination reports. All required entries shall be addressed. A "N/A" shall indicate when a response is not applicable.
- 8.2 All recorded signals shall be located by measurement from a specific point to center of probe.
- 8.3 All calibration data sheets and examination records shall be filed according to job number.

FaAA NDE Procedure

11.5, Rev. 1



# Failure Analysis Associates

## NONDESTRUCTIVE EXAMINATION PROCEDURE

Title: EDDY-CURRENT INSPECTION PROCEDURE

FOR MODULAR IRON PISTON-SKIRTS

NDE: 11.5

Page 1 of 3

Revision: 1

Date: 11/02/83

Approved by NDE Manager: Duane B. Johnson

Date: 1/31/84

Reviewed - NDE Level III: Duane B. Johnson

Date: 1/31/84

### 1.0 PURPOSE AND SCOPE

- 1.1 To establish calibration, scanning and evaluation techniques for eddy-current examination of nodular iron piston-skirts.
- 1.2 This instruction covers the eddy-current examination of the boss areas near the 4-bolt-holes inside the piston skirt.

### 2.0 PERSONNEL CERTIFICATION

- 2.1 Personnel performing eddy-current examination shall be at least a certified Level II Eddy-Current Inspector, as per "FaAA Practice for Certification and Qualification of NDT Personnel."

### 3.0 EQUIPMENT

- 3.1 Eddy-current instrument used with this instruction shall be an impedance-plane display instrument.
- 3.2 The eddy-current test probe shall be a FaAA-ECP-100-P.
  - 3.2.1 The reference standard shall be PA0-7396-831230.

### 4.0 EXAMINATION SURFACE

- 4.1 Only those surfaces that have a machined or ground finish shall be tested.

### 5.0 CALIBRATION PROCEDURE

- 5.1 Set frequency at  $2.0 \pm 0.2$  MHz.
- 5.2 Set volts per division at 0.5.
- 5.3 Set gain at 30.
- 5.4 Adjust horizontal and vertical positioning controls such that balance point is at (0 V, 1 V).

# Failure Analysis Associates

## NONDESTRUCTIVE EXAMINATION PROCEDURE

Title: EDDY-CURRENT INSPECTION PROCEDURE

FOR MODULAR IRON PISTON-SKIRTS

NDE: 11.5

Page 2 of 3

Revision: 1

Date: 11/02/83

- 5.5 Balance with probe on test piece.
- 5.6 Adjust horizontal attenuator such that horizontal saturation is greater than 1.5 V and less than -1.5 V.
- 5.7 Adjust phase angle such that probe lift-off causes the beam to move horizontally to the right on the CRT.
- 5.8 Adjust gain such that the 1/16 × 1/32 inch EDM notch in reference standard PAO-7396-831230 gives a  $1.0 \pm 0.1$  V negative signal at the horizontal center of the CRT.
- 5.9 Repeat steps 5.4 through 5.8 until steps are accomplished without further instrument adjustments.
- 5.10 Recalibration shall be completed at least once an hour.
- 5.11 Eddy-current instrument should be on at least 10 minutes before calibration or testing.

### 6.0 EXAMINATION

- 6.1 Examination shall be of the legs on the boss where color contrast penetrant show linear indications greater than 1/32 inch length.


### 7.0 RECORDING CRITERIA

- 7.1 All eddy-current crack indications with signal magnitude greater than 50% of the signal magnitude obtained from the 1/16 × 1/32 inch EDM notch in the reference standard PAO-7396-831230 shall be recorded.
- 7.2 The magnitude, location and orientation of the indication shall be recorded.

### 8.0 RECORDS



- 8.1 Set-up and calibration shall be recorded on report form 11.1.10.
- 8.2 All recordable indication shall be recorded on report form 11.5.8.4 (see next page).
- 8.3 All records shall be filed according to job number.

Diesel engine  $\leftrightarrow$  \_\_\_\_\_  
Piston  $\leftrightarrow$  \_\_\_\_\_






Notch side

Overhead view



Side views, looking out from inside





Slot width less than 0.005"

Fractions  $\pm 1/64$ "

**Chemical Analysis**

Iron 92.568%

Carbon 3.48%

Silicon 2.43%

Other 1.542%

Note: Material from TDI piston skirt.

DESCRIPTION: Nodular iron reference standard

PA0-7396-831230

EDM on machine surface

TOLERANCES UNLESS OTHERWISE SPECIFIED

x.xx -  $\pm$

x.xxx -  $\pm 0.002$ "

DRAWN

*ESK*

CHECKED

*[Signature]*

APP'D

*[Signature]*

**Failure Analysis Associates**

2225 East Bayshore Road

P.O. Box 51470

Palo Alto, California 94303

DATE  
1-3-84

CASE  
PA07396

DWG. 831230



# Iron Castings Handbook

*Covering data on Gray,  
Malleable, Ductile, White, Alloy  
and Compacted Graphite Irons*

*Edited by*

**Charles F. Walton**

*Iron Castings Society*

*Co-Editor*

**Timothy J. Opar**

*Iron Castings Society*

*Published by*

**Iron Castings Society, Inc.**



Two of these ductile iron truck mount castings hold the cab-over-engine cab in proper relation to the truck frame. This redesign from a complex welded steel fabrication resulted in reduced costs, and improved strength and fatigue characteristics.

mental to fatigue life but the speed of the loading cycle and the occurrence of rest periods are not significant.

As the maximum stress is reduced, the number of cycles necessary to produce a failure becomes much larger. The highest stress at which the number of cycles for failure approaches infinity (generally in excess of ten million cycles) is called the *endurance limit*. The *endurance ratio* is the relation between the endurance limit and the tensile strength. Most of the data on fatigue strength have been obtained with the rotating beam type test where the maximum stress alternates between tension and compression. A typical S-N curve on which the stress is plotted against the number of cycles to failure<sup>16</sup> is shown in Fig. 13. From these results, the unnotched endurance limit is indicated to be 28,000 psi (193 MPa). This is the maximum stress at which a fatigue failure should not occur under similar conditions in any number of cycles. Since this particular ductile iron has a tensile strength of 68,500 psi (472 MPa), its endurance ratio is 0.41.

The effect of stress raisers on the endurance limit has been evaluated by the use of notched test bars. For this purpose, a notch is usually turned into the circumference of an oversize bar so that the base of the notch leaves a cross-section equal to the regular unnotched bars to which the notched bars are compared. The ratio of the unnotched to the notched endurance limit is termed the notch sensitivity factor or the dynamic stress concentration factor. Several investigations have obtained endurance ratios of from .33 to .52 for the different types of ductile iron. The endurance limit increases with tensile strength, but as with other ferrous metals, the increase is less than proportional. The relation between tensile strength and the endurance ratio is different for the annealed, ferritic irons than for the irons with a matrix of pearlite or tempered martensite<sup>17,18</sup>, Fig. 14.




Fig. 13 The unnotched and notched fatigue properties of an annealed ductile iron<sup>16</sup> with a tensile strength of 65,800 psi (454 MPa). The endurance ratio is .41 and the notch sensitivity ratio is 1.67.




Fig. 14 The endurance ratios for ductile irons as influenced by tensile strength and matrix microstructure<sup>17,18</sup>.

MEMORANDUM

TO: Mike Milligan  
Bill Judge

DATE: February 17, 1984

FROM: Donald O. Johnson *DOJ*

RE: Shoreham Nuclear Power Station  
FaAA Job # PA07396

SUBJECT: Report on trip to Kodiak Electric Association, Inc. on January 22  
to 27, 1984.

---

The trip to Kodiak, Alaska, with Bill Judge from Long Island Lighting Project Office (LILCO) at the Shoreham Nuclear Power Plant Station included inspection of AE pistons and gathering of operating information on their Transamerica Delaval (TDI) diesel engines.

The people we contacted at Kodiak Electric Association, Inc. (KEA) were Rosahul Baldurn and Carl Gronn. They were very helpful in our inspection and gathering of information.

The piston skirts that were examined came from engine number 4, serial number 79026-3029, model DSRV 16-4, date of manufacturing 8 August 1980, horse power 8750BHP, RPM 450. There were two pistons that were pulled for inspection, one piston was for LILCO and the other for TDI to inspect. I did an informational inspection on the replacement pistons for KEA. I found no crack-like indications above the recording threshold.

February 17, 1984

Page -2-

The AE piston that was designated for LILCO was penetrant tested to NDE-5.2 and Eddy-Current tested to NDE-11.5. The penetrant test was the first part of the inspection and eddy-current was to verify any penetrant indications.

The inspection was of the boss areas as directed by NDE Procedures 6.2 and 11.5. One area was found to have a penetrant indication 3/4" long. Upon inspection with eddy-current there were no crack-like indications noted. The piston was shipped to Palo Alto to be examined at FaAA's lab. In the laboratory, I reinspected the piston to both NDE-6.2 and NDE-11.5 and found no crack-like indications.





PEAK FIRING PRESSURE ON ENGINE #4



March 31, 1983, 4000 kW, 7200 hours


1R	890	1L	970
2R	790	2L	960
3R	1000	3L	980
4R	970	4L	940
5R	990	5L	920
6R	990	6L	930
7R	890	7L	910
8R	930	8L	920



March 2, 1982, 5600 kW, 4201 hours


1R	1320	1L	1320
2R	1300	2L	1280
3R	1300	3L	1280
4R	1310	4L	1260
5R	1340	5L	1300
6R	1300	6L	1240
7R	1340	7L	1240
8R	1300	8L	1240






















EDDY CURRENT CALIBRATION REPORT

Job No. 03341A Date 3-13-84 Report No. 840313-1
Material Description NODULAR IRON PISTON SKIRTS
Code or Specification NOE 11.5 Full On -1.5 Full Off +1.5
Reference Standard PH07396-840227 Instrument M12 17 S/N 033833

Instrument

Freq. 2 MHz Gain 30 Volts/div 0.5 Phase 202
Test Probe FAA ECP 100P S/N 100P
Reference Probe FAA ECP 100P S/N 100 P-1

CALIBRATION

2.2 units @ 0 L/O 1.8 units @ +1.5 L/O
2.0 units @ +1 L/O 1.6 units @ +2.0 L/O

STRIP CHART RECORDER

Type N/A S/N N/A

Channel 1

Channel 2

Sen N/A Sen N/A
Position @ Null Point N/A Position @ Null Point N/A
Chart Speed N/A mm/sec

Calibration Check


Table with 3 columns: Time, Phase, Gain. Contains 10 rows of calibration data points.

Examiner Dan [Signature] Level II Examiner Level

EDDY CURRENT EXAMINATION REPORT

Material <i>NODULAR IRON PISTON SKIRT</i>		Type: <i>PISTON SKIRT</i>		Fabricated process: <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Cast <input type="checkbox"/> Worked		ET Component I.D. <i>PISTON SKIRTS 040</i> <i>D6103 #5 #7 #8</i>																
		Geometry: <input type="checkbox"/> Pipe <input type="checkbox"/> Plate <input type="checkbox"/> Rod <input checked="" type="checkbox"/> Other: <i>COUNTER BORE</i>																				
Cross section thickness:	Max. <i>N/A</i> Inch	Min. <i>N/A</i> Inch	Surface condition: <input checked="" type="checkbox"/> Machined <input type="checkbox"/> Ground <input type="checkbox"/> As fabricated <input type="checkbox"/> Other:																			
NDE Procedure no. <i>11.5</i>		Job no. <i>03341A</i>		Report no. <i>840313-1</i>																		
Test condition: Ver <i>+1</i> Hor <i>0</i>			<table style="width:100%; border-collapse: collapse;"> <tr> <td style="text-align: center;"><u>2.2</u></td> <td>Unit at</td> <td><u>0</u></td> <td>Lo</td> </tr> <tr> <td style="text-align: center;"><u>2.0</u></td> <td>Unit at</td> <td><u>+1</u></td> <td>Lo</td> </tr> <tr> <td style="text-align: center;"><u>1.8</u></td> <td>Unit at</td> <td><u>+1.5</u></td> <td>Lo</td> </tr> <tr> <td style="text-align: center;"><u>1.6</u></td> <td>Unit at</td> <td><u>+2.0</u></td> <td>Lo</td> </tr> </table>			<u>2.2</u>	Unit at	<u>0</u>	Lo	<u>2.0</u>	Unit at	<u>+1</u>	Lo	<u>1.8</u>	Unit at	<u>+1.5</u>	Lo	<u>1.6</u>	Unit at	<u>+2.0</u>	Lo	
<u>2.2</u>	Unit at	<u>0</u>	Lo																			
<u>2.0</u>	Unit at	<u>+1</u>	Lo																			
<u>1.8</u>	Unit at	<u>+1.5</u>	Lo																			
<u>1.6</u>	Unit at	<u>+2.0</u>	Lo																			
Unit # <i>033823</i> Sen <i>30</i> Frq <i>2MHz</i>																						
Full-on <i>-1.5</i> Full-off <i>+1.5</i>																						
Reference no. <i>100P1</i> Probe type <i>100P</i>																						
Indication no.	Magnitude of indication	Length of indication	Remarks																			
			<i>NO RECORDABLE INDICATIONS</i>																			
Specific examination area																						
<i>SCAN AREA IN SIDE BELVILLE WASHER ABRA, AROUND RADIUS.</i>																						
Sketch or other data (use other side)																						
Acceptance criteria		<i>INDICATION Greater than 50% of Reference Standard</i>		Operator: <i>Don Johnson</i>		Job name: <i>PISTONS 03341A</i>																
				Level: <i>II</i> Date: <i>3-14-84</i>																		
Attest		<i>[Signature]</i>		Level: <i>II</i> Date: <i>3-14-84</i>		Plant/location <i>DIESEL Generators ELU, G3</i>																
		Responsible certified personnel		Date																		


Diesel engine # 103  
Piston # 5




Notch side

Overhead view

*NO RELEVANT INDICATORS*




Side views, looking out from inside





11.5.8.4

Diesel engine # 103  
Piston # 7





Notch side

Overhead view




Side views, looking out from inside



*NO RELEVANT INDICATIONS*


11-5-8-4

Diesel engine # 103  
Piston # \_\_\_\_\_




Notch side

Overhead view



Side views, looking out from inside



*No RESULT INDICAT 1033*

MEMORANDUM

TO: Mike Milligan  
Nelson Irvine

DATE: February 3, 1984

FROM: Donald O. Johnson *DOJ*

RE: Shoreham Nuclear Power  
Station FaAA Job # PA07396

SUBJECT: Report of Trips on 1/10/84 to Transamerica Delaval,  
Oakland, California

---

I went to Transamerica Delaval (TDI) in Oakland on January 10, 1984, to inspect two AE-type piston as representative of Long Island Lighting Company (LILCO). I used a color contrast penetrant method of inspection described in the FaAA Nondestructive Examination Procedure, NDE 6.2, Revision 0, dated October 12, 1983. The procedure was accepted by LILCO's Nelson Irvine, Level III inspector of their Field Quality Assurance Division.

Al Fleischer at TDI arranged the tests of two pistons that were run 687 hours. The two pistons were crated when we went to their training center to do the inspection. There was a description of the material on top of one crate.

R5 Test Pistons - 03-341-04-AE

Piston Skirts were tested in R5-V12 for 687 hours at 302 BMEP and 514 RPM. Testing included 51 start-and-stop sequences. Heat numbers were 7085 C-31 and 7085 C-33. The crates were opened, and I photographed the pistons showing the heat numbers and other markings. I noted that these pistons were the old style: the wrist pin boss area was thin, and the first rib above the boss area where the crown bolts to the skirt was very narrow, the same as the AN-type pistons.

The next step was to complete the color contrast penetrant test to FaAA Procedure, NDE 6.2. During the inspection I observed that there was a layer of plating on the inside of the skirt and that the casting was very smooth, different from general production runs of cast material. The inside of the skirt was cleaned, and all the flash was removed. The boss area was very smooth, as if polished by cratex, and all the ground areas were very carefully polished, with smooth radius into boss.

There were no indications noted according to our acceptance criteria. The next step was to use eddy-current to inspect the boss areas and the lower web. I also checked plating inside and out. There was evidence of plating on the inside below normal areas. The plating was very thin, approximately 0.0005 inch to 0.0001 inch.

I found three indications with eddy-current on piston C-31 as shown on drawing 11.5.8.4. The attached reports and a photo pack will document the report.

EDDY CURRENT CALIBRATION REPORT

Job No. PA07396 Date 1-10-84 Report No. PA07396-841001
Material Description NODULAR CAST IRON
Code or Specification NDE 18.5 Full On -1.5 Full Off +1.5
Reference Standard PA0-C-1 Instrument M12 17 S/N

Instrument

Freq. 2MHz Gain 30 Volts/div 0.5 Phase 218
Test Probe FAHA EEP-100-P-1 S/N ECP-100-P-1
Reference Probe FAHA ECP-100-B-1 S/N ECP 100 B-1

CALIBRATION

4 units @ -1.5 L/O 3.2 units @ -0 L/O
3.5 units @ -1 L/O 2.6 units @ +1 L/O

STRIP CHART RECORDER

Type N/A S/N N/A

Channel 1

Channel 2

Sen N/A Sen N/A
Position @ Null Point N/A Position @ Null Point N/A
Chart Speed N/A mm/sec

Calibration Check


Table with 3 columns: Time, Phase, Gain. Contains handwritten entries for 2 PM and 2:15 PM, and several blank rows.

Examiner R&D-KR-3 Level Examiner [Signature] Level II




11.5.8.4

Diesel engine \* N/A  
Piston \* C-31




Notch side

Overhead view




1



2


1 DIV at -1.5° 25%

Side views, looking out from inside



3

0.8 DIV at -1.5° 20%




4


1.2 DIV at -1.5° 30%

LIQUID PENETRANT EXAMINATION REPORT



A. Material		Type: <i>NODULAR CAST IRON</i>	Fabricated Process: <i>N/A</i>	<input type="checkbox"/> Welded <input checked="" type="checkbox"/> Cast	PT Component I.D. <i>N/A</i>
		Geometry: <input type="checkbox"/> Pipe <input type="checkbox"/> Plate <input type="checkbox"/> Rod <input checked="" type="checkbox"/> Other: <i>AE PISTON SKIRT</i>			
Cross Section Thickness: <i>N/A</i>	Max <i>N/A</i> Inch	Min <i>N/A</i> Inch	Surface Condition: <input checked="" type="checkbox"/> Machined <input type="checkbox"/> As Fabricated	<input type="checkbox"/> Ground <input checked="" type="checkbox"/> Other: <i>AS CAST</i>	
B. NDE Procedure No. <i>6.2</i>		Surface/Mat'l. Temp. <i>110°C</i>	M & TE. No. <i>N/A</i>	MWR/RR. No. <i>N/A</i>	
Inspection Materials	Brand	Designation	Batch No.		
1. Pre-Cleaner	<i>aydrox</i>	<i>9 PR551</i>	<i>C-846</i>		
2. Penetrant	<i>"</i>	<i>966</i>	<i>01-3551</i>		
3. Emulsifier and/or Remover		<i>9 PR551</i>	<i>C-864</i>		
4. Developer		<i>906</i>	<i>1032</i>		
5. Post Examination Cleaner		<i>9 PR551</i>	<i>C-864</i>		
Sketch or other detail (use other side if necessary): <i>PISTON # C 31</i> <i>PISTON # C 33</i>					System <i>Emergency Diesel Generator for Piston Skirts</i>
C. Evaluation		Report below those indications observed and the pertinent information required. Where additional space is required, use other side.			
Location	Size (Inches)	Description	Action (Accept/Reject, and comment as necessary)		Plant/Location <i>TDI - OAKLAND CA.</i>
1. <i>NONE FOUND</i>					
2.					
3.					
4.					
D. Acceptance Criteria		<i>NDE 6.1 + 6.2</i>	Operator: <i>D O JOHNSON</i> Level: <i>II</i> Date: <i>1-10-84</i>		
E. Attest		Responsible Certified Personnel	Level	Date	



NEW YORK  
PA07396









SITOR PHAM  
PA07396






SECRET  
PA07396









PAW 7 306






PA07396



PM07396



EDDY CURRENT CALIBRATION REPORT

Job No. PAO 7396 Date 1-13-84 Report No. PAO 7396-841301
Material Description NODULAR IRON PISTON SKIRT
Code or Specification NDE 11.5 Full On -1.5 Full Off +3
Reference Standard Instrument M12 17 S/N B133867

Instrument

Freq. 2 MHz Gain 15 Volts/div 0.5 Phase 218
Test Probe 100 ECP-1 S/N 100-P-1
Reference Probe 100 ECP S/N 100-B-2

Large

CALIBRATION

med

2.4 units @ -1.5 L/O 2 units @ -1.5 L/O
2.0 units @ -1 L/O 1.4 units @ +1 L/O

STRIP CHART RECORDER

Type N/A S/N N/A

Channel 1

Channel 2

Sen N/A Sen N/A

Position @ Null Point N/A Position @ Null Point N/A

Chart Speed N/A mm/sec

Calibration Check

Time 2:20 PM Phase 218 Gain 15 (NO CHANGE)
Time 2:45 PM Phase 218 Gain 15 (NO CHANGE)
Time Phase Gain
Time Phase Gain
Time Phase Gain
Time Phase Gain
Time Phase Gain
Time Phase Gain
Time Phase Gain
Time Phase Gain

Examiner D O Johnson Level II Examiner Level

## COMMENTS

These two pistons were plated on the inside completely

1. Machine areas were very smooth in boss area.
2. Grinding was done very carefully on boss area.
3. Piston # C33 one of the boss areas where lip on outside show smashing like a washer hit edge. The edge was rolled over.
4. These castings look better visually in boss area. Also I could not see any cast material without coating.

C-31            Cylinder #6

C-33            Cylinder #4

John Gee            577-7000

01/10/83

PA07396

Penetrant Inspection at TDI Oakland.

- 1) Meet with Al Fleisher
- 2) Inspected 2 Pistons
- 3) Could Not Pick Up Blue Prints
- 4) Tested Pistons No Relevant Indication



Piston Temperature 11°C

Note on Crate

R5 TEST PISTON

03-341-04-AE Piston Skirt  
Tested in R5-V12 for  
687 hours at 302 BMEP & 514 RPM  
and Stop Sequences

Heat Numbers

708 J

Piston#	C-31
	or
Piston#	C-33

Time of Penetrant was 3:00 p.m. on piston C-31, 3:10pm on piston C-33

cleaning till rag showed no oil

Drying time for cleamer after light wiping 15 minutes before penetrant applied

**LUBRICATING OIL SYSTEM.**

The lubricating oil system is of the dry sump type which has a sump tank for holding the oil supply. Oil is circulated through the system by an engine-driven pump. Refer to the lubricating oil piping schematic drawing in the "Drawings" section of this manual for the specific details of the system, relative location of major components, direction of flow, and notes relative to installation of the system.

**FLOW PRINCIPLE.**

Pump suction draws the lubricating oil from the sump tank and discharges it to the lubricating oil cooler. Flow from the cooler is through a lubricating oil filter and pressure strainer to the engine main headers. A branch line from the strainer takes oil to the turbochargers. Return is by gravity flow from the engine base to the sump tank. Separate lines direct return flow from the turbochargers from the sump tank. A relief valve, set at 70 psi, provides protection to the system, and pressure regulating valves regulate the system pressure.

**KEEP WARM CIRCUIT.**

A "keep warm" circuit is provided to maintain the lubricating oil charge, and thereby the engine, in a warmed and lubricated condition when in the standby status. Heaters at the sump tank warm the oil which is then pumped by the keep-warm pump to the keep-warm filter and strainer and then to the main engine lubricating oil header. To prevent flooding of the turbochargers, there is no supply to the turbochargers in this circuit. The lubricating oil heater thermostat should be set at 150° F.

**PLACING LUBRICATING OIL SYSTEM IN SERVICE.**

Before the engine is first started, the assembled lubricating oil piping system must be thoroughly flushed with oil. Disconnect the pipe at the pressure strainer inlet and arrange a temporary bypass from this pipe to the sump tank. The bypass will permit oil circulation through the pipes without filling the internal lubricating oil system of the engine. Several thickness of cloth sack should be secured to the outlet of the bypass to catch debris as it is flushed out. The sump tank and engine base must be thoroughly cleaned before being filled. The auxiliary lubricating oil pump, or any other continuous duty pump of sufficient capacity, can be used to pump oil during flushing operations. Flushing should continue for at least eight hours if care was exercised during fabrication of the system. As much as 24 hours of flushing may be required for a dirty system. When oil is circulating through the system, the pipes should be thoroughly pounded several times with a heavy hammer to loosen dirt and debris. Hot flushing oil will clean better than cold oil. Piping around the oil cooler requires special attention to insure that the pipes and oil cooler are properly flushed. Precautions must be taken to insure the complete removal of testing fluids, water or other liquids before attempting to flush the cooler.

**Note**

Engines may be received with the strainer mounted on the engine and connected to the engine lubricating oil header. If it is certain that the connections between the strainer and the engine oil header have not been disconnected since the engine left the factory, the following paragraph may be omitted.

Disconnected jumper tubes between the engine lubricating oil header and the main bearings, and between main headers and auxiliary headers. Secure a fine screen such as a nylon stocking over each main header fitting to catch debris that may be washed through as the system is flushed. Cover main bearing fittings and open ends of auxiliary header feeders to prevent the entry of dirt. Engine oil should be pumped through the open system for at least four hours to be sure that any foreign material remaining in the headers is removed. Reassemble internal tubes and brackets as required.

## PART K – LUBRICATING OIL SYSTEM

### FILTERS AND STRAINERS.

The full flow filter continuously filters all of the lubricating oil from the pump before it passes to the oil strainer. The length of time that the lubricating oil and the filter elements may remain in service can best be determined by carefully watching the result of oil analysis and the pressure drop across the oil filter. Change period will vary with the operating conditions to which each individual engine is subjected. During the first two or three days of engine operation after initial installation, or after a major overhaul, the strainer at the pump suction and the strainer at the oil header inlet should be checked and cleaned as necessary to remove any debris and other foreign matter that may be present. If at any time the oil pressure gauge shows a low reading, the following should be done to the degree necessary to correct the situation.

- a. Check the oil level in the sump tank.
- b. Inspect strainer, filter and lubricating oil cooler. A leak in the cooler may be detected by a sudden increase in oil consumption, and by the presence of oil in the cooling water system. Leakage may occur in the packing between the tubes and the tube sheet, or may be due to tube erosion, depending on the construction of the cooler.
- c. Inspect all external and internal piping for tightness and freedom from obstructions.
- d. Dismantle and inspect pump.

### LUBRICATING OIL PUMP.

The engine-driven lubricating oil pump is a positive displacement, rotary type. As the pump rotates, the unmeshing of the teeth of the two gears produces a vacuum which draws oil between the tooth spaces. Oil is confined in the space between the gear teeth and the housing, and is carried to the discharge side of the pump. The meshing of the gears forces the oil into the discharge line by displacing the oil from the tooth spaces as the opposite gear enters the space. The pump is mounted on the engine gearcase by means of an adapter, and is driven by the idler gear through a gear carrier assembly. A spline on the pump shaft engages internal splines on the gear carrier shaft coupling. Refer to figure 6-K-1 for mounting details.

### REMOVING PUMP.

To remove the pump from the engine, do the following.

- a. Remove the inlet and discharge piping as well as any other interfering piping or accessories.
- b. Position a sling on the pump and attach to a chainfall and take up the slack.
- c. Remove the capscrews that secure the pump to the adapter and pull the pump directly away from the engine until it is clear.

## PART K - LUBRICATING OIL SYSTEM (Continued)




Figure 6-K-1. Lubricating Oil Pump Assembly

### PUMP DISASSEMBLY (See Figure 6-K-1).

If it is necessary to disassemble the pump, exercise care to keep the parts clean so that no dirt, grit or other foreign matter will be present when the pump is assembled. Disassemble as follows.

- a. Remove spline from pump shaft, taking care not to exert any internal forces on the pump parts.
- b. Remove hex head screws from the faceplate end of the pump and remove the faceplate which contains two bearings.
- c. Remove idler gear and shaft, then the drive gear and shaft.
- d. Remove hex head screws from backplate end of pump housing and remove backplate which contains two bearings.
- e. Carefully examine the surfaces of the gears. Slight burrs or feather edges may be removed with a hand stone.
- f. Examine bearings and clean oil grooves and passages.
- g. Remove burrs and foreign matter on gasketed surfaces of end plate and case.
- h. Check bearing wear, using the table of clearances provided on next page.

## PART K – LUBRICATING OIL SYSTEM (Continued)

<b>TABLE OF CLEARANCES</b>	
Roper Pump Company Figure 2877 Type 1	
<b>SHAFT OUTSIDE DIAMETER TO BEARING INSIDE DIAMETER*</b>	
Bearing Inside Diameter . . . . .	2.0050" – 2.0055"
Shaft Outside Diameter . . . . .	2.0000" – 1.9995"
Diametric Clearance . . . . .	0.0050" – 0.0055"
Maximum permissible operating clearance . . . . .	0.0100"
<i>NOTE: Wear can occur in bearing ID or shaft OD. Total of both not to exceed 0.010".</i>	
<b>GEAR OUTSIDE DIAMETER TO CASE BORE*</b>	
Case Bore . . . . .	5.657" – 5.669"
Gear Outside Diameter . . . . .	5.658" – 5.657"
Initial Clearance . . . . .	0.009" – 0.012"
<b>PUMP LATERAL CLEARANCE**</b>	
Case Width . . . . .	8.751" – 8.750"
Gear Width . . . . .	8.750" – 8.749"
Total Compressed Gasket Thickness . . . . .	0.014" – 0.016"
Total Initial Lateral Clearance . . . . .	0.018" – 0.014"
*Not considering roundness, concentricity and positioning tolerance.	
**Not considering squariness, perpendicularity and positioning tolerance.	

### PUMP REASSEMBLY.

Assembly is the reverse of disassembly. The spline must be mated to the shaft without exerting any internal forces on the pump parts. The tapered end of the idler gear should be meshed to the opposite end of the drive gear. Taper ends are designated by the letter "T" appearing in the root area of the gear teeth.

### INSTALLATION OF PUMP.

Before mounting pump on engine, make sure pump rotates freely. Mount pump to adapter, engaging dowel and the pump shaft spline with that of the gear carrier shaft. Use a gasket between the pump and the adapter. Assemble nuts on studs, and capscrews. Tighten. Lubricate pump through ports with any good grade of light weight oil to insure pump will not be dry at the time of initial starting. When installing piping, do not force as the strain imposed will cause undue wear on the pump. No external lubrication is required as the pump is self lubricated by the oil it pumps during operation.

### PUMP GEAR CARRIER ASSEMBLY.

The pump gear carrier assembly consists of a shaft, supported by two bronze bushings, pressed in the carrier assembly with their flanges to the inside. The pump end of the shaft has an internally splined adapter, attached to the shaft with a roll pin, which accepts the spline on the pump shaft. The drive gear is mounted on the shaft between the two bushings and engages the idler gear. The carrier assembly is secured to the engine block by capscrews and locking clips.

R/RV [Roper 2877] .75

## PART K – LUBRICATING OIL SYSTEM (Continued)

### DISASSEMBLY AND ASSEMBLY OF GEAR CARRIER ASSEMBLY.

To remove the pump gear carrier assembly, the pump must be removed as outlined above, then the gearcase removed.

- a. Remove lubricating oil lines from carrier assembly.
- b. Bend back locking clips and remove capscrews. Remove carrier assembly.
- c. To remove gear, shaft and bushings from carrier assembly, remove gear-to-shaft roll pin then press shaft out of gear. With shaft and gear removed, press bushings out of drive bracket.
- d. Assembly is the reverse of disassembly. Use new locking clips.

## PART K - LUBRICATING OIL SYSTEM (Continued)




Figure 6-K-2. Oil Pressure Regulating Valve

### PRESSURE REGULATING VALVE.

Lubricating oil header pressure in the engine is regulated by a pressure regulating valve, mounted on the pump discharge piping so that the pump discharge is directed to this valve before reaching any other system components. Set at 50 psig, it senses header pressure and regulates the bypass volume to maintain the set header pressure. Besides regulating header pressure, the valve protects the system from excessive pressure during starts with cold oil, or when flow in the system is restricted between the pressure regulating valve and the header pressure sensing point. The functioning of the valve is as follows.

a. The "IN" port of the valve is connected to the pump discharge line and the "OUT" port is connected to a bypass line leading back to the engine base. A sensing tube, connecting the valve seal cap to a point on the main engine oil header, applies header pressure to the valve pressure sensing chamber.

b. The pressure in the sensing chamber acts against the end of a spool valve, compressing a spring at the adjusting screw end of the assembly. If the sensed pressure rises above the set point, the lands of the spool valve will clear the lands on a sleeve. Oil then flows from the inlet section to the outlet-section of the regulating valve and back to the engine base to bypass a part of the pump discharge to reduce the pressure in the header.

c. A drilled passage connects the inlet section of the valve to the annular space around the spool valve at the adjusting screw end. This allows pump discharge pressure to act against the end of the sleeve and oppose the spring force at the other end. When an excessive pressure differential exists between the pump discharge and the header pressures, such as when starting with cold oil, or because of an obstruction in the system between the regulating valve and the header pressure sensing point, the sleeve is forced towards the sensing chamber end, compressing the spring. This will uncover the lands of the spool valve and the excess oil will bypass through the spool valve and the excess oil will bypass through the outlet side of the valve back to the engine base.

## PART K – LUBRICATING OIL SYSTEM (Continued)

d. The oil in the annular space around the spool valve, at the adjusting screw end, will leak past the sealing grooves of the spool valve and into a cavity in the cap. This cavity functions as a buffer chamber. To stop valve oscillation, an adjustable needle valve controls oil spillage from the buffer cavity to the outlet-section of the valve.

e. The oil header pressure is set by increasing or decreasing the spring force acting against the header pressure in the valve sensing chamber. Turning the adjusting screw in will increase header pressure, and backing it out will decrease pressure.

f. Normal lubricating oil pressure is 50 psi, measured between the engine lubricating oil strainer and the engine oil header which is also the pickup point for all gauges and other instrumentation that show or indicate engine lubricating oil pressure. Lubricating oil pressure shutdown devices may take their sensing point at the opposite end of the engine in which case the shutdown set pressure will take into account the normal change in pressure between the supply end of the engine and the shutdown sensor under all conditions of engine speed and lubricating oil temperature.

### ADDING LUBRICATING OIL.

The lubricating oil sump tank is provided with a fill connection and a dipstick, located on the top of the intake section of the tank. A level indicator may be provided at the control panel for monitoring purposes, however, the level in the sump tank should be verified by means of a visual reading of the dipstick before oil is added to the system, and the expected rise in the level in the sump tank must be verified by means of the dipstick. Oil may be added to the system with the engine running or with the engine stopped. The dipstick has two sets of marks, one for the static condition and one for the running condition. The markings are "Full Static" and "Low Static" on one side of the dipstick, and "Full Run" and "Low Run" on the other. Before oil is added, it should be determined that the correct oil is available. Appendix VI of this manual contains the recommended specifications for the lubricating oil to be used.

### CAUTION

Oil must never be added from any location other than the fill connection on the sump tank. Do not overfill. Attempting to fill from any other location could result in oil reaching other than design locations.



## PART K – LUBRICATING OIL SYSTEM (Continued)

### SELECTION OF A LUBRICATING OIL.

The selection of a lubricating oil to be used in the engine is a complex matter, and is very important to the engine's successful operation. The recommendations of both the oil supplier and the engine manufacturer should be carefully considered. Transamerica Delaval's recommendations for a suitable lubricating oil are stated in Section 8, Appendix VI. Other factors to be considered include the price, service life, load factor and fuel sulphur content as well as the filtration and oil purification system used.

### CHANGING LUBRICATING OIL.

Once an oil has been selected the engine user, in consultation with the oil supplier, should map out a plan for periodic sampling and laboratory analysis of the oil. A careful review of these results by the owner, the oil supplier and the testing laboratory can then become the basis for deciding whether or not the oil needs to be changed. Transamerica Delaval recommends that oil be changed on the basis of condition of the used oil rather than on a time schedule.

### ANALYSIS OF OIL.

Various chemical and physical tests have been developed to classify and identify new oil, and to determine what changes have occurred in these oils while in service. The American Society for Testing Materials (ASTM) has standardized these tests, and certain of these tests have been approved as an American National Standard by the American National Standards Institute, Inc. (ANSI). Transamerica Delaval, as stated in Section 5, recommends that representative oil samples be submitted to a qualified laboratory for analysis on a monthly basis, or oftener if operating conditions indicate. The following tests should be conducted.

- a. **OIL VISCOSITY** – Tested in accordance with ASTM D88, D445, ANSI Z11.2 and ANSI Z11.107. The viscosity test will indicate whether the proper grade of oil is being used, and will indicate oxidation (by increased viscosity) or fuel dilution (decreased viscosity). The oil supplier can provide advice regarding the significance of the specific values obtained.
- b. **WATER/GLYCOL CONTAMINATION** – A measure of water and/or glycol contamination of the oil can give warning of potential problems. Water or glycol contamination can come from liner seals, turbocharger casings or faulty lubricating oil heat exchangers.
- c. **NEUTRALIZATION VALUE** – Test in accordance with ASTM D664, D974, ANSI Z11.59 and ANSI Z11.131. Engine oils are intentionally formulated slightly alkaline so that they are capable of neutralizing the acidic compounds that form from products of combustion and of oil oxidation. Generally this reserve alkalinity is depleted and the weak organic acids that attack bearing surfaces can be destructive. Periodic evaluation of Total Base Number (TBN) and Total Acid Number (TAN) are an important measure of oil degradation. As time goes on, TBN is depleted and TAN begins to rise.
- d. **PENTANE AND BEZINE INSOLUBLES** – ASTM D893. This test is a measure of oil insoluble materials, oil resinous matter from oil or additive degradation, external contamination, fuel carbon and highly carbonized materials from degradation of fuel, oil, additives, engine wear and corrosive materials.
- e. **SPECTROGRAPHIC ANALYSIS** – This test is used to measure quantitatively the mineral elements in the oil, including wear or corrosion metals such as aluminum, chromium, iron, copper, silver, lead and tin. Also, dirt contaminants from the coolant such as boron, potassium and sodium.

### Note

The Transamerica Delaval Customer Service Department in Oakland, California will welcome any correspondence regarding oil selection and/or testing. Although Transamerica Delaval cannot recommend a specific lubricant, nor accept any responsibility for the performance of the lubricant selected by the owner, it will be pleased to discuss its experience with a given oil product, or review your oil analysis and offer comments.

## PART K - LUBRICATING OIL SYSTEM (Continued)




Figure 6-K-5. Turbocharger Bearing Drip Lubrication System

### TURBOCHARGER BEARING LUBRICATION.

The turbocharger bearings are lubricated by the engine lubricating oil system during normal engine operation. On the other hand, when the engine is in standby status oil is not circulated to the turbocharger. The design features of the Elliott BCO 90G turbocharger are such that the prolonged circulation of oil to the bearings while the turbocharger is at rest will result in oil intruding past the bearings into the turbine section. To prevent failure of the bearings during a start, however it is essential that the bearings be properly lubricated during prolonged periods in standby. A drip lubrication system is provided to perform this function (see figure 6-K-3). Lubricating oil from the "Pre-warm" supply is passed through a 60 micron filter then through a 0.014 inch diameter orifice to a sight glass. The sight glass, one for each turbocharger, provides a means for positive determination of oil flow to the bearings. This flow is sufficient to provide for proper lubrication of the bearings without flooding the turbocharger. Little maintenance should be required other than the possible replacement of filter elements.

# **DIESEL ENGINE DESIGN**

By

**T. D. WALSHAW**

**B.Sc.(Eng.), D.L.C. (Hons.), A.M.I.Mech.E., A.M.I.P.E.  
Lecturer in Mechanical Engineering  
University of Liverpool**

*With 290 Illustrations  
and 31 Engine Sections*

<sup>W.</sup>  
LONDON

**GEORGE NEWNES LIMITED**  
TOWER HOUSE, SOUTHAMPTON STREET  
STRAND, W.C.2

## Chapter 3

### ENGINE TYPES

**D**IESEL engines may be classified roughly into the following categories :

- (1) Two-stroke or four-stroke working cycle.
- (2) High, medium, or low-working speed.
- (3) Single or double-acting.
- (4) Vertical, horizontal, vee, opposed piston, etc.
- (5) Duty – generating, marine, locomotive, road vehicle, etc.
- (6) Supercharged or unsupercharged.

Considering these in more detail :

#### (1) Two-stroke or Four-stroke Working Cycle

Classification as to the mechanical cycle followed is, of course, general. At one time it was usual to assume all engines to be four-strokes " unless otherwise stated," but to-day it is necessary to be quite clear on the point, as there are as many of one type as the other. The fundamental difference between the two types is that in the case of the two-stroke, a separate pump is required to recharge the cylinder with air, whilst in the four-stroke engine the working cylinder itself performs that duty. This fundamental difference leads to a host of consequent problems, most of which are concerned with the twin subjects of higher rate of heat flow and the shorter time available for exhaust and air induction in the two-stroke. Owing to the fact that a firing impulse is received twice as frequently in a two-stroke, and that valves can be done away with, this type of engine is used universally for the higher powers, say above 3,000 B.H.P. per unit. Between 1,000 and 3,000 B.H.P., the supercharged four-stroke and the two-stroke are in equal competition, the two-stroke being possibly the favourite. Below 1,500 B.H.P. the four-stroke holds the field at present, chiefly owing to lower fuel and lubricating-oil consumption, but the new highly rated valve-exhausted two-strokes are rapidly gaining favour. It will be noted that in all cases of high-duty two-strokes, up to 1,000 B.H.P. at any rate, exhaust valves have been found to be essential, and it can no




Fig. 4-1

pump power. A great deal will depend on scavenging efficiency. The old-fashioned "crankcase compression" engine rarely exceeded a B.M.E.P. of 60 lb./sq. in., whilst engines built under the Kadenacy patents have exceeded 120 lb./sq. in. on test. A plot of two-stroke B.M.E.P. is also shown in Fig. 4-1, but it should be noted that these are on the one-hour rating.

#### Piston Speeds

As the piston speed,  $N_p = 2LN$ , the horse-power expression may be rewritten :

TABLE IX

Bore, in.	16	12	10	8	6	4
Speed, r.p.m.	300	428	500	600	800	1,250
Max. pressure, lb./sq. in.	700	740	790	850	900	1,050
Compression pressure, lb./sq. in.	420	430	440	460	490	510
Cylinder pressure at half stroke lb./sq. in.	75	75	80	90	90	100

The figures for compression pressure will, of course, depend to some extent on the pressure at the beginning of compression, but may be taken as a fair approximation. Similarly, the values for pressure at half stroke will depend on the value of "n" (and on the expansion ratio), but they have some interest, as it is near this point that the transverse stress due to the inertia of the connecting rod is a maximum.

The cylinder pressure ought to be regarded as a shock load when designing the running gear. Some reference has already been made to the rate of pressure rise in the cylinder, and from the point of view of fatigue stressing, the rates of rise per *second*, even in cases where the rise per degree is small, are quite serious. At 1,200 r.p.m., a rate of pressure rise of 40 lb./sq. in./degree is not far short of 300,000 lb./sq. in./sec. As will be pointed out later, under these conditions the *shape* of the part is almost as important as its strength if serious concentrations of stress are to be avoided.

## (2) Inertia and Centrifugal Loads

Inertia forces increase with the *square* of the speed. Those due to the piston and connecting rod are in *opposition* to the gas loading at top dead centre, and their effect is to reduce the downward loading on the connecting rod and bearings. On T.D.C. of the exhaust stroke in four-strokes, the inertia forces introduce a *tension* load in the rod, and this means that the rod has to withstand some reversal of stress.

In the valve gear, almost the whole of the load is due to inertia, and the effect is cumulative. High accelerations require heavy valve springs to cope with them. This means that stronger gear is required to resist the stress due to spring forces, and this in turn increases the inertia loading. The exhaust-valve system of two-stroke engines is particularly troublesome in this respect.

Centrifugal forces due to rotating unbalanced masses impose loads on the bearings which travel round the bearing with the rotation of the crankshaft. They are often in opposition to the gas loading, but cause stresses in other parts of the engine, due to

# INTERNAL-COMBUSTION ENGINES

THEORY AND DESIGN

BY

V. L. MALEEV, M.E., Dr. A.M.

*Member A.S.M.E., S.A.E.;*

*Professor of Mechanical Engineering,*

*Oklahoma Agricultural and Mechanical College;*

*Formerly Senior Mechanical Engineer (Diesel),*

*U.S.N. Engineering Experiment Station, Annapolis;*

*Formerly Chief Engineer, Western-Enterprise Engine Company*

SECOND EDITION

McGRAW-HILL BOOK COMPANY, Inc.

NEW YORK AND LONDON

1945

period is the third stage or *gradual, or controlled, combustion*. The fourth stage, or *afterburning*, is burning of the fuel after injection terminates. This stage cannot be controlled and is very undesirable as its efficiency is comparatively low.

Figure 10-1 illustrates the process by a pressure-time diagram: the fuel is injected at point 1, but ignition does not start until point 2. Angle  $a$  represents the delay period also called *ignition lag*. For a certain engine the delay period depends upon many factors, as will be shown later. From point 2 to point 3, corresponding to a crank angle  $b$ , the flame spreads from the initial nucleus to the main body of the fuel charge. Similar to the conditions of spark-ignition engines, the flame velocity and




FIG. 10.1—Combustion diagram of a high-speed oil engine.

the pressure rise depend upon turbulence; this second phase of the process is very important for a smooth operation of an engine. During the third stage, crank angle  $c$ , from point 3 to 4, the fuel burns as it leaves the fuel nozzle and the pressure may either increase, remain constant, or decrease, depending upon the rate at which it is delivered to the combustion chamber. The angle  $c$  is a function of the load which the engine is carrying. The fourth stage, afterburning, is not apparent on the indicator diagram. On a diagram taken from an engine, the dividing points 2, 3, and 4 are not pronounced, and the four stages merge one into another gradually.

**10-3. Delay Period.**—This period itself is made up of two parts: a heating period when the cold fuel droplets are heated, vaporized, and brought up to their ignition temperature and a period of true ignition delay that ends when the first particles actually ignite. However, in engines it is difficult to distinguish between these two periods, so the delay period is measured from the beginning of the injection to the moment of ignition.

The delay period presents a great interest, as it materially influences the operation of an engine: A shorter delay period gives a smoother operation; a longer delay period results in a rougher




FIG. 10-2.—Effect of inlet temperature on delay angle.

and noisier running engine. The factors that influence the length of the delay period are:

- temperature of the air charge,
- pressure of the charge,
- atomization of the fuel,
- timing of injection,
- engine speed, and finally,
- ignition quality of the fuel, its cetane number.




FIG. 10.3.—Effect of injection timing and jacket temperature on pressure curves. Curves *A* and *B*—injection starts 20 and 10° B.T.C., respectively; solid and broken-line curves—jacket temperature 150 and 300F, respectively.

*Temperature.*—Figure 10-2 shows the typical effect of inlet temperature on the delay angle of an experimental engine.<sup>1</sup> The same condition is confirmed by another engine, Fig. 10-7.

<sup>1</sup> ROTHROCK, A. M., *SAE Journal*, vol. 34, June, 1934.



Cooper-Bessemer compression-ignition oil engine equipped with a Buchi-Elliott turboblower. In this engine the mep when supercharged was limited not by available air but by the fuel-pump delivery.

Finally, Fig. 19-8 presents data about the increase of bmep in two compression-ignition aircraft oil engines as a function of the supercharging pressure.<sup>1</sup> Curve *c* gives the same data in respect to a large oil engine running at 300 rpm with an unchanged valve overlap of 30°.<sup>2</sup>




FIG. 19-8.—Effect of supercharging pressure on mean effective pressure.

**Mechanical Efficiency.**—The increase of friction losses with a supercharger driven by the engine itself is considerably smaller than the power gained through supercharging. As a result the mechanical efficiency, referred to the maximum load, increases with supercharging. Figure 19-9 shows the mechanical efficiencies of a 7-in.  $\times$  10-in. six-cylinder compression-ignition Cummins engine at different speeds and mean effective pressures when operating, supercharged with a Roots blower.<sup>3</sup> The mechanical efficiency of the same engine with natural aspiration at 1000 rpm when developing a bmep of 84 psi was found to be 73 per cent. The influence of supercharging upon the mechanical efficiency of two aircraft engines is brought out by Fig. 19-10.

<sup>1</sup> MALEEV, V. L., *Mech. Eng.*, vol. 63, p. 446, 1941.

<sup>2</sup> *Diesel Power*, vol. 18, p. 877, October, 1940.

<sup>3</sup> KNUDSEN, H. L., Problems and Possibilities of Mechanical Supercharging of Diesel Engines, *Diesel Power*, vol. 19, p. 856, October, 1941.

**Fuel Economy.**—Owing to better combustion because of increased turbulence, better mixing of the fuel and air, and of an increased mechanical efficiency, the specific fuel consumption in most cases, though not in all, is lowered by supercharging.




FIG. 19-9.—Mechanical efficiencies of a Cummins supercharged oil engine.

Figure 19-11 gives an interesting comparison of the performance of a three-cylinder 9½-in.  $\times$  10½-in. Alco oil engine at 1000 rpm: curve *c*, unsupercharged; curve *d* supercharged with




FIG. 19-10.—Effect of supercharging on mechanical efficiency of compression-ignition aircraft engines.

a Roots blower, power increase about 75 per cent, fuel consumption 5 per cent lower; curve *c* supercharged by a Buchi turboblower, power increase about 87 per cent, fuel consumption 13 per cent lower than in the unsupercharged engine.

Curves *a* and *b* show also how the performance of this engine was improved by putting in turbulence-creating pistons.

Figure 19-6, on the other hand, shows that the fuel consumption of that particular gasoline engine was improved very little and only at the maximum supercharged horsepower.

**Fuel Knock.**—In compression-ignition oil engines, increasing the inlet pressure decreases the ignition lag and consequently the rate of pressure rise in the cylinder, which results in an increasing smoothness of operation.<sup>1</sup> On the other hand, in a gasoline engine, if the engine is operated with a compression ratio that causes incipient detonation when supercharging and if a




FIG. 19-11.—Performance development of Alco 9½-in. × 10½-in. engine.

fuel with the same antiknock characteristics is used, in order to prevent objectionable detonation, the compression ratio must be lowered so that the compression pressure of the supercharged engine will remain about the same as before supercharging. This will slightly lower the thermal efficiency, but the power output will be increased, as a greater amount of fuel will be burned. An engine operating with natural aspiration with a compression ratio 7:1, when supercharged should have a compression ratio about 6:1.

**19-4. Limitations.**—The permissible amount of supercharging depends upon the ability of the engine to withstand the increased pressure and heat stresses.

**Pressures.**—The increase of the mean effective pressure naturally increases the mean bearing pressures and mechanical

<sup>1</sup> NACA Tech. Notes 509, 1936, p. 8.

friction losses. On the other hand, the maximum pressures and temperatures will go up too. Thus a six-cylinder 12-in. × 15-in. by 650 rpm Enterprise oil engine unsupercharged develops continuously 670 bhp, or a bmeep of 80 psi, with a maximum pressure of about 680 psi. When equipped with a Buchi turbine-driven blower, the engine can develop a maximum bmeep of 162 psi and a continuous bmeep of 125 psi, or a power increase of 56 per cent; the maximum pressure goes up to about 850 psi, the specific fuel consumption goes down from 0.40 lb/hp-hr to 0.375 lb/hp-hr, or an improvement of 6 per cent.




FIG. 19-12.—Effect of supercharging pressure on various characteristic pressures.

Figure 19-12 gives the relation between supercharging pressures, compression pressures, maximum combustion pressures, and obtained mean indicated pressures for sea-level operation. The curves represent computed values but are corrected on the basis of corresponding test data and give an idea of the limit of supercharging.

**Temperatures.**—The above-mentioned Enterprise engine has an exhaust temperature of 720 F unsupercharged and 960 F supercharged. The Cummins engine mentioned before has exhaust temperatures as shown on Fig. 19-13; Fig. 19-14 shows the temperatures for the Alco three-cylinder 9½-in. × 10½-in. engine at different loads.<sup>1</sup> Finally Fig. 19-15 gives a very complete picture of the performance of a six-cylinder 12½-in. × 13-in. Alco engine, which supercharged is rated 1000 bhp at 740 rpm. The exhaust temperature goes up from 720 F, at 80 psi mep, to 1100 F, at 120 psi mep.

<sup>1</sup> Diesel Power, vol. 19, p. 864, October, 1941.

## CHAPTER 27

### RUNNING GEAR

**27-1. Trunk Pistons.**—*The functions of a trunk piston are:*

1. To transmit the gas pressure to the crankshaft.
2. To take the side pressures due to angularity of the connecting rod.
3. To seal the inside of the cylinder from the crankcase.
4. To dissipate heat absorbed by the piston top during combustion and early part of expansion stroke.

*Design Objects.*—In designing a piston to meet these requirements the following objects must be sought:

1. Strength of the piston, particularly of its head.
2. Sufficient projected side area, and rigidity of the barrel.
3. Minimum work of friction.
4. Sealing of the working space against escape of gases.
5. Preventing the entrance of lubricating oil into the combustion space.
6. Good dissipation of the heat to the cylinder walls.
7. Minimum weight.

The design objects are listed not in the order of their importance but to conform with the order of functions as listed above. Good heat dissipation is one of the most important design requirements.

*Materials* used to make trunk pistons are in the order of their importance: cast iron, cast aluminum, forged aluminum, cast steel, and forged steel.

Cast iron is an excellent material; its main drawback is that it gives a slightly heavier piston than aluminum. However, with a proper design the difference is only about 10 to 20 per cent. Cast-iron pistons produce less cylinder-liner wear than aluminum ones,<sup>1</sup> especially if they are tin-plated.

<sup>1</sup> *Automotive Ind.*, Jan. 16, 1937, p. 81; *Z. Ver. deut. Ing.*, vol. 81, p. 610, 1937.

Cast aluminum alloy gives better heat dissipation and lighter weight but costs considerably more than cast iron. The strength is about the same as that of cast iron.

Forged-aluminum pistons are stronger and still lighter. They are used for aircraft engines and heavy-duty high-speed compression-ignition oil engines.

Alloy cast-steel pistons are used in some automotive engines and require liners of great surface hardness. The same is true of forged-steel pistons used in some aircraft engines.

*Piston Head.*—The thickness  $t_1$  of the head or crown can be computed, considering it a flat round plate of uniform thickness fixed at the edges, from the formula

$$t_1 = 0.43D \sqrt{p/S} \quad (27-1)$$

where  $D$  is the cylinder bore, in.,

$p$  is the maximum pressure during combustion, psi,

$S$  is the allowable stress in bending, psi.

A stress of 5500 psi can be allowed when using a good close-

grained cast iron or an aluminum alloy with an ultimate tensile strength of 20,000 psi. If the material used has an ultimate strength of 30,000 psi, such as nickel cast iron, semisteel, or special aluminum alloy, normalized, then  $S$  can be taken as 8000 psi. For forged-steel heads  $S$  can be raised to 12,000 psi.

The piston head has often four or six radial ribs  $a$ , Fig. 27-1, of a

thickness  $t_2$ , one-third to one-half the thickness  $t_1$  of the head, but it is safer not to consider these ribs when computing  $t_1$ .




FIG. 27-1. Trunk piston of a gas engine.

TABLE 27-1.—THICKNESS OF PISTON HEAD

Type of engine	Piston material	Thickness	
		Four-stroke	Two-stroke
Compression-ignition oil engines	Cast iron	0.11D-0.13D	0.16D-0.18D
Compression-ignition oil engines	Aluminum	0.13D-0.16D	0.17D-0.20D
Spark-ignition gas engines	Cast iron	0.12D-0.14D	0.20D-0.23D

INSAT

PRIORITY

TERM Q-326  
1/3

COMPONENT TASK EVALUATION REPORT

20 MAR 26 1984

101 Piston, Book

ITEM/COMPONENT NO. <u>03-341A</u> D.G. 101	TDI PART NO. <u>03-341A</u>	INITIATOR <u>[Signature]</u> SIGNATURE	DATE <u>3-21-84</u>	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
--	--------------------------------	--	------------------------	---

CONDITION DETAILS: ATTACHED INSPECTION REPORT (1 PAGES) GENERATED BY B. Hayes  
DATED 3-21-84 REPORTS UNSATISFACTORY INSPECTION RESULTS FOR THIS PART.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR DISPOSITION.

*Attached IR is unsatisfactory  
See Sheet 2 for recommended disposition.*

REQUIRED COMPLETION DATE: 3-21-84

ASSIGNMENT

POSITION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>[Signature]</u> SIGNATURE	DATE <u>3-21-84</u>
--	--	------------------------

DISPOSITION

DISPOSITION DETAILS: Follow Procedure 1 outlined on page 2

DISPOSITION ASSIGNED TO  ENGINEERING  QUALITY  NONE REQUIRED

APPLIED BY <u>K. Solon</u>	DATE <u>3-21-84</u>	REVIEWED BY <u>[Signature]</u> RESP. CHAIRPERSON	DATE <u>3-21-84</u>	APPROVED BY <u>[Signature]</u> PROGRAM MANAGER	DATE <u>3/25/84</u>
-------------------------------	------------------------	--	------------------------	--	------------------------

ACTION

POSITION ASSIGNED TO <u>C. Wells</u>	ACTION COMPLETED BY <u>[Signature] for C. Wells</u>	DATE <u>3-29-84</u>
---	--	------------------------

CKS/GWP/RJN/EFM  
TER LOG

A34462

RECOMMENDED  
UNSAT TER DISPOSITION

TER # Q-326

PAGE 2 OF 3

Distribute for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-326", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.
- 3) LSU/OQA - review for applicability and issue LDR as needed.
- 4) M. Schuster - obtain LDR number as issued for component files and closeout.

114463

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL  
INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3-20-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
<p>COMPONENT NAME:</p> <p>PISTONS</p> <p>COMPONENT NO. 03-341A</p>	<p>DG- 101</p>	<p>I.P. NO. 14 REV. 4 CHG 0</p> <p>TER # N/A</p> <p>LILCO LP PROC. N/A REV. N/A</p> <p>DWG. NO. N/A</p>

DWG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	2	3	<p>A VISUAL INSPECTION OF THE SKIRT AND CROWN O.D. FOR SCUFFING, AND THE COMBUSTION BOWL IN CROWN FOR PITTING WAS PERFORMED. THE FOLLOWING WAS NOTED:</p> <p>COMBUSTION BOWL - CYL 5 AND 7 VERY SLIGHT SIGNS OF PITTING. CYLINDER 8 DISPLAYS A MORE SUBSTANTIAL AMOUNT OF PITTING.</p> <p>PISTON SKIRT - CYLINDERS 5, 7, AND 8 ALL DISPLAYED SIGNS OF SCUFFING</p>
			<p>NOTE NO. N/A</p>

11600.37

This inspection report is acceptable for design  
review .

Q-326

03-341A

K. John for C. Wells  
3/29/84

P

A34465

DEFICIENCY REPORT	<input checked="" type="checkbox"/> FIELD <input type="checkbox"/> OTHER	LDR RESPONSIBILITY <u>M. HERJNY</u>	LDR NUMBER <u>2275</u>	
	COMPONENT <u>DESC: GEN</u>	SYSTEM DESIGNATOR <u>R43A</u>	MARK NO. <u>1R43 * EDG-101</u>	DATE <u>3/22/84</u>
CONTRACTOR <u>TDI</u>	P.O. <u>310552</u>	MATERIAL LOCATION <u>TB 63'ELEV</u>	REJECT TAG NO.	Q CLASS <input checked="" type="checkbox"/> I <input type="checkbox"/> II <input type="checkbox"/> III <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
RELATED <u>SHI-089</u>	DRAWING VIOLATED <u>NA</u>	PROCEDURE VIOLATED <u>NA</u>	CODE/STANDARD VIOLATED <u>NA</u>	

ICN DETAILS  
 TER Q-326 (03-341A) REPORTS UNSATISFACTORY CONDITIONS ON  
 PISTONS. THE COMBUSTION BOWLS OF PISTONS 5, 7 AND 8 DISPLAY  
 LARGE AMOUNTS OF PITTING. PISTON SKIRTS ON PISTONS 5, 7 AND 8  
 ARE SCUFFED. QCIR ATTACHED.  
**(03-341A) 102**

LEADER <u>A. Rolano</u> SIGNATURE	DATE <u>3.22.84</u>	JOAE <u>[Signature]</u> SIGNATURE	DATE <u>3/22/84</u>
---	------------------------	---	------------------------

LEADER <input type="checkbox"/> LDR <input checked="" type="checkbox"/> DRAWING <u>A. Rolano</u> SIGNATURE LEAD ENGINEER	DATE <u>3.22.84</u>
<input checked="" type="checkbox"/> ACCEPT AS IS <input type="checkbox"/> SCRAP <input type="checkbox"/> REWORK <input type="checkbox"/> REPAIR <input type="checkbox"/> MANUAL <input type="checkbox"/> PROCEDURE <input type="checkbox"/> FSAR <input type="checkbox"/> OTHER	

NOTICE DETAILS  
 IN ACCORDANCE WITH THE ATTACHED TDI  
 AND THE ABOVE CONDITION IS ACCEPTABLE AS IS.  
 CONDITION IS NOT DETRIMENTAL. COMPONENTS  
 SHOULD BE CLEANED AND REINSTALLED.

LOW LEAD ENGR <u>[Signature]</u> DATE <u>3/24/84</u>	PROJECT ENGINEER <u>[Signature]</u> DATE <u>3/24/84</u>	REPAIR/REWORK REQUEST NO.
LEAD ENGR DATE	LILCO SITE OOA DATE	REWORK INSPECTION <input type="checkbox"/> SAT. <input type="checkbox"/> UNSAT. <u>120513</u>
COMPLETE/DATE	WHY COMPLETE	
LEAD ENGR DATE	LILCO SITE OOA DATE	LILCO SITE OOA/DATE
LILCO SITE OOA/DATE	NEW LDR REPORT NO. <u>[Number]</u>	REMARKS



T

ATTACHMENT TO  
LDR 3198

FRM. LER

Date: March 17, 1984 Page 5 of 5  
 To: John Thompson  
 From: Robert Tabares  
 Subject: Waste Generators, T-121 thru T-401Q/1R  
T-401R Waste Assemblies  
 Reference: L-128 2198

Reference L-128 reports unsatisfactory conditions found during inspection of numbers 5, T and R waste assemblies due to scuffing, pitting and scratches. The number 5 meter has scuffing evident to the tin plating on the meter skirt in the normal thrust surfaces. The condition is attributed to the excessive wear found in that cylinder and reported in L-128 2188. No overhauling is evident on the meter skirt and sufficient tin plate remains to provide an adequate break-in to a new liner. Scuffing to a basic degree is also noted on the number 8 skirt and is not an unusual condition to occur during break-in. Excessive wear in the combustion bowl and circumference of the 5, T and R waste cranes was found to be very close and an acceptable condition for a steel casting. Scratches in the combustion bowl of number 8 meter crane are attributed to handling and are not detrimental to the crane. Recommended Disposition: Close inspection and action to occur.

*Robert Tabares*

Memo

C. H. Tabares 1/1/84

FORM C-1088-2 (R-1) 5/81



COMPONENT TASK EVALUATION REPORT

DG 102 Pistons, Book 2

TER NO. Q-4

UNSAT

COMPONENT NO. 341A	TDI PART NO. 03-341-04-AE	INITIATOR <i>[Signature]</i>	DATE 2/20/84	ORGANIZATION <input checked="" type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY -RTF
-----------------------	------------------------------	---------------------------------	-----------------	--

CONDITION DETAILS: ATTACHED INSPECTION REPORTS (4 PAGES) BY M. TORMINA/H. RITURIA WAS GENERATED AS INFORMATIONAL, AS NO ACCIDENT WAS PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION

REQUIRED COMPLETION DATE: 2/21/84

ASSIGNMENT

FUNCTION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>R Fraser</u> SIGNATURE	DATE 2-21-84
--	---	-----------------

DISPOSITION

DISPOSITION DETAILS: See attached sheet 2 of 6  
Attached IR. is UNSAT

DISPOSITION ASSIGNED TO <input checked="" type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY <input type="checkbox"/> NONE REQUIRED					
APPLIED BY <u>R Fraser</u>	DATE 12/22/84	REVIEWED BY <u>R Fraser</u>	DATE 12/22/84	APPROVED BY <u>[Signature]</u>	DATE 2/22/84
RESP. CHAIRPERSON			PROGRAM MANAGER		

ACTION

FUNCTION ASSIGNED TO <u>[Signature]</u> <u>[Signature]</u>	ACTION COMPLETED BY _____	DATE
--	------------------------------	------

CC: CKS/GWR/RJN/EFM  
TER LOG

TER DISPOSITION

Distribute for action as follows:

- 1) Design Review (G. Rogers) - Review as part of site experience. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER \_\_\_\_\_", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.
- 3) LSU/OCA - review for applicability and issue LDR as needed.
- 4) M. Schuster - obtain LDR number as issued for component files and closeout.

...

INSPECTION REPORT


JOB NUMBER  
1160057

DATE  
2-11-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
PISTON SKIRT 3 (03-341-04-AE) DIAL IND. 2801h	DG. 102	SHI-089 <del>I.P.-03-341-A</del> -14 2/12/84

ITEM QTY DESCRIPTION(S) AND INSPECTION REMARK(S)

PERFORMED VISUAL IND. ON O.D. OF PISTON SKIRT AREA FOR ABOVE REF. PISTON BELOW FIND THE IND. RESULTS.



REPORT

JOB NUMBER  
1163337

DATE  
2-11-84

ITEM(S) OR PART(S) NAME

LOCATION(S)

REFERENCE DOCUMENT(S)

PISTON SKIRT  
(03-341-04-AE)  
VISUAL INSP.

DL 102

SHI-089

I.P. - 03-341-A  
-14 2/12/84

273 lbs

ITEM QTY


DESCRIPTION(S) AND INSPECTION REMARK(S)

PERFORMED VISUAL INSP ON O.D. OF PISTON SKIRT AREA FOR ABOVE REF. PISTON. BELOW FIND THE INSP. RESULTS.





O.D. SURFACE:

SLIGHT WEARMARKS, SHALLOW  
SCORES & SCRATCHED AREAS

TINNED SURFACE WHEN IN SPOTS



THIS SURFACE APPEARS TO BE HEATED



A

B

C

D

INSPECTION REPORT

LOG NUMBER

DATE

1 2/11/54

SYSTEM(S) OR PART(S) NAME

LOCATION(S)

REFERENCE DOCUMENT(S)

PISTON SKIRTS  
#7 (03-341-04-AE)  
VISUAL INSP.

DC. 102

SHI-089  
~~IP-03-341-A~~ QNA  
-14 2/12/54

278: 100.

ITEM QTY

DESCRIPTION(S) AND INSPECTION REMARK(S)

PERFORMED VISUAL INSP. ON O.D. OF PISTON SKIRT AREA. FOR ABOVE REF. PISTON. BELOW FIND THE INSP. RESULTS

BOTTOM SECTION - LENGTHWISE CONTAINS SHALLOW SCRAT ON THE O.D. (4" TO 15 1/2" LONG - HEAVIEST ON SIDES BETWEEN Wrist PIN HOLES, SOME SCUFFING ALSO EVID WITH MINOR METAL UPSET.

A44184

ROL  
REPORT

FILE NUMBER

11600.71

DATE

3/2/84

SYSTEM(S) OR  
PART(S) NAME

LOCATION(S)

REFERENCE  
DOCUMENT(S)

03-341 A  
PISTONS

DG-102

I.P. NO 14

DESCRIPTION(S) AND INSPECTION REMARK(S)

ITEM QTY

3 1

DURING OUR INSPECTION OF PISTONS NO. 5, 7, AND 8 IT WAS NOTED THAT THE CROWN ON NUMBER 6 PISTON WAS DROPPED ON THE FLOOR DURING DISASSEMBLY. A VISUAL INSPECTION WAS PERFORMED ON THE CROWN ONLY. A GOUGE WAS NOTED IN THE RADIUS NEXT TO A EYE BOLT HOLE  $\frac{1}{2}$ " LONG X  $\frac{1}{8}$ " WIDE X  $\frac{1}{16}$ " DEEP.

A24185

DATE

DATE

PAGE

3/2/84

1

Transamerica  
Delaval



Transamerica Delaval Inc  
Engine and Compressor Division  
550 85th Avenue  
P O Box 2181  
Oakland, California 94621

Date: 1 MARCH 1984 S-42  
To: JOHN KAMMEYER  
From: DON SCHMITZ  
Subject: EMERGENCY DIEZEL GEN #102- SN 74011  
MECHANICAL WEAR ON VARIOUS COMPONENTS  
LDR- 2147, 2146, 2145, 2144, 2143

THE WEAR REPORTED ON SUBJECT LDR'S  
WAS INSPECTED BY MR. M. LOWREY  
OF DELAVAL ENGINEERING AND A DETERMINATION  
WAS MADE THAT THE WEAR WAS  
NORMAL AND COMPONENT SHOULD BE  
USED IN THE 'AS IS' CONDITION.

Donald L Schmitz

A14486

Memo



COMPONENT TASK EVALUATION REPORT

W-26  
Q82  
Pg 1/8  
ATT #3

UNSAT

ATT #3

EM/COMPONENT NO. 350C	TDI PART NO. 02-350-01-0A	INITIATOR R. Fraser for	DATE 2/28/84	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
3341A	03-341-04-AE	<u>S. Rothkewicz</u> SIGNATURE		

CONDITION DETAILS: The attached I.R. by E. Kuhns and J. Dolan, dated 2/15/84 (pg 2,3 attached) was transmitted as Information. It is an unsatisfactory Inspection Report (03-350C, DR-175)  
 and 2/13/84 (pgs 4-7 attached) was transmitted as Information. It is an unsatisfactory Inspection Report (03-341A, DR-183)  
 RECOMMENDATIONS: This TER supercedes DR-175, DR-183) in its entirety.

Forward to Design Group for evaluation and SEO-LSU for INFO.

REQUIRED COMPLETION DATE:

ASSIGNMENT

POSITION ASSIGNED TO ENGINEERING <input checked="" type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>R. Fraser</u> SIGNATURE	DATE 2-28-84
---	--	-----------------

DISPOSITION

DISPOSITION DETAILS: The attached I.R.s (referenced above) are unsatisfactory. See Sheet 2.

THIS TER SUPERCEDES TERs DR-175 & DR-183 IN THEIR ENTIRETY

DISPOSITION ASSIGNED TO	<input checked="" type="checkbox"/> ENGINEERING	<input checked="" type="checkbox"/> QUALITY	<input type="checkbox"/> NONE REQUIRED
APPLIED BY <u>E. Youngling</u>	DATE 2/28/84	REVIEWED BY <u>R. Fraser</u> RESP. CHAIRPERSON	DATE 2/28/84
		APPROVED BY <u>J. C. K. Jones</u>	DATE 2/28/84
		PROGRAM MANAGER	

ACTION

POSITION ASSIGNED TO Rogers, M. Schuster, Jones, E. Youngling L. Kammerer	ACTION COMPLETED BY <u>[Signature]</u>	DATE 03-06-84
--	---	------------------

CKS/GWR/RJN/EFM  
TER L G

VISUAL 5,7 & 8  
2/13/84

110515

UNSAT TER DISPOSITION

Q-82  
2/8

Distribute for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-82", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.
- 3) LSU/OQA - review for applicability and issue LDR as needed.
- 4) M. Schuster - obtain LDR number as issued for component files and closeout.

120516

STONE & WEBSTER ENGINEERING CORPORATION

082

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER

11600.37

DATE

2/13/84

SYSTEM(S) OR PART(S) NAME

LOCATION(S)

REFERENCE DOCUMENT(S)

PISTON CROWN

OG 102

OG INSP PLAN #14

COMPONENT 03-341A  
REV 0

DWG NO OR P.O.

ITEM

QTY.

DESCRIPTION(S) AND INSPECTION REMARK(S)

3 3

Performed a visual inspection of the crown outside diameter and combustion bowl. All surfaces were found satisfactory. No signs of pitting or scuffing were noticed. NUMBERS 5, 7, AND 8

110517

QUALITY CONTROL INSP./ENG.

DATE

PAGE

*John R. Borden / [Signature]*

2/13/84

1 of 1

Q-82  
03-3500  
03-341A

This inspection report is acceptable for design  
review

K. Adlan for C. Wells  
Conversation 3/6/84

A10518

102 Pistons Book 1  
Q-83  
14 1/4

COMPONENT TASK EVALUATION REPORT

ATTR. #3

SYSTEM/COMPONENT NO. <i>Piston</i> <i>CS-341-A</i>	TDI PART NO. <i>1A-6522</i>	INITIATOR <i>[Signature]</i> SIGNATURE	DATE <i>2/18/84</i>	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
--	--------------------------------	--	------------------------	---

CONDITION DETAILS:  
*VISUAL INSPECTION PERFORMED ON PISTON SKIRTS*  
*INSPECTION REPORTS FOR SKIRT #5, 7, 8 ATTACHED.*

RECOMMENDATIONS:  
*Submit FOR FAA REVIEW & ACTION AND SEO-LSU*  
*FOR INFO*

REQUIRED COMPLETION DATE: *2/19/84*

ASSIGNMENT

POSITION ASSIGNED TO <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <i>R. Fraser</i> SIGNATURE	DATE <i>2-28-84</i>
--	--	------------------------

DISPOSITION

DISPOSITION DETAILS: *Attached I.R. is unsatisfactory.*  
*See Sheet 2.*

*THIS TER SUPERCEDES TER # DR-183 IN ITS ENTIRETY*

POSITION ASSIGNED TO	<input checked="" type="checkbox"/> ENGINEERING	<input checked="" type="checkbox"/> QUALITY	<input type="checkbox"/> NONE REQUIRED
INITIATED BY <i>[Signature]</i>	DATE <i>2/28/84</i>	REVIEWED BY <i>R. Fraser</i> RESP. CHAIRPERSON	DATE <i>2/28/84</i>
APPROVED BY <i>[Signature]</i>		DATE <i>2/28/84</i>	
PROGRAM MANAGER			

ACTION

ACTION ASSIGNED TO <i>[Signature]</i> <i>J. [Signature]</i>	ACTION COMPLETED BY <i>K. Adon for C. Wells</i>	DATE <i>3/1/84</i>
---	--	-----------------------

CCI CKS/GWR/PJH/EFM  
TER LOG

*DUPLICATE ISSUE OF*  
*IRS ON Q-41*

A14520

UNSAT TER DISPOSITION

Q-83  
2/4

Distribute for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-83", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.
- 3) LSU/OQA - review for applicability and issue LDR as needed.
- 4) M. Schuster - obtain LDR number as issued for component files and closeout.

A10530

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER # DATE 2/11/54

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
PISTON SKIRTS #7 (03-341-04-AE) VISUAL INSP.  278 lbs.	DG. 102.	3 SHI-089 <del>IP-03-341-A QNA</del> -14 2/12/54

DWG. NO. OR P.O.	ITEM QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
		<p>PERFORMED VISUAL INSP. ON O.D. OF PISTON SKIRT AREA. FOR ABOVE REF. PISTON. BELOW FIND THE INSP. RESULTS.</p> <p>BOTTOM SECTION - LENGTHWISE CONTAINS SHALLOW SCRATCH ON THE O.D. (4" TO 15 1/2" LONG - HEAVIEST ON SIDES BETWEEN WREST PIN HOLES, SOME SCUFFING ALSO EVIDENT WITH MINOR METAL UPSET.</p>

44533

STONE & WEBSTER ENGINEERING CORPORATION

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600-37

DATE 2-11-84

SYSTEM(S) OR PART(S) NAME  
 PISTON SKIRT  
 #B (03-341-04-AE)  
 VISUAL INSP.  
 273 lbs.

LOCATION(S)  
 DG 102



REFERENCE DOCUMENT(S)  
 SHI-089  
 I.P. - 03-341-A  
 -14 2/12/84

DWG. NO. OR P.O.  
 ITEM  
 QTY.

DESCRIPTION(S) AND INSPECTION REMARK(S)

PERFORMED VISUAL INSP. ON O.D. OF PISTON SKIRT AREA FOR ABOVE REF. PISTON. BELOW FIND THE INSP. RESULTS.

O.D. SURFACE:  
 SLIGHT WEARMARKS, SHALLOW SCORED & SCRATCHED AREAS.  
 TINNED SURFACE WORN IN SPOTS.





No More Information is required for  
Design Review

K. Solon for C. Wells  
Conversation 3/1

A40533

INFO

Q-109  
1/3

QAE 30-25

STEM/COMPONENT NO. 3-341 A	TDI PART NO. 1A-6522	INITIATOR B. N. Lopez SIGNATURE	DATE 3-6-84	ORGANIZATION <input type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY
-------------------------------	-------------------------	---------------------------------------	----------------	--

CONDITION DETAILS: ATTACHED INSPECTION REPORT (1 PAGES) BY DATED 2-13-84 WAS GENERATED AS INFORMATIONAL, AS NO ACCEPTANCE CRITERIA WAS PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION

Attached IR is informational only.  
See Sheet 2 for recommended disposition.

REQUIRED COMPLETION DATE: 3-7-84

ASSIGNMENT

POSITION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON R. Fraser SIGNATURE	DATE 3-7-84
--	---	----------------

DISPOSITION

DISPOSITION DETAILS: FOLLOW PROCEDURE 1 OUTLINED ON PAGE 2

DISPOSITION ASSIGNED TO		<input checked="" type="checkbox"/> ENGINEERING	<input type="checkbox"/> QUALITY	<input type="checkbox"/> NONE REQUIRED
APPLIED BY Kenney A. ...	DATE 3-7-84	REVIEWED BY Kenney A. ... RESP. CHAIRPERSON	DATE 3-7-84	APPROVED BY J. ... for C. K. ... PROGRAM MANAGER
			DATE 3/3/84	

ACTION

ACTION ASSIGNED TO C. Wells Info: K. Simon	ACTION COMPLETED BY <i>[Signature]</i>	DATE 03-09-84
--	---	------------------

C: CKS/GWR/RJN/EFM  
TER LOG

VISUAL 5, 7 1/8

2/13/84

110519

DUPLICATE ISSUE OF  
IR'S ON Q-82  
CHANGED FROM INFO Q109  
TO UNSAT ON Q82

RECOMMENDED  
INFORMATION TER DISPOSITION

Q-109  
2/3

Distribution for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-109", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.

A10520

QUALITY CONTROL SECTION REPORT		JOB NUMBER 11600-37	DATE 2/13/84
SYSTEM(S) OR PART(S) NAME  PISTON CROWN  COMPONENT 03-341A REV 0	LOCATION(S)  DG 102	REFERENCE DOCUMENT(S)  DG Insp PLAN #14	

WG. NO. OR P.O.	ITEM	QTY.	DESCRIPTION(S) AND INSPECTION REMARK(S)
	3	3	Performed a visual inspection of the crown outside diameter and combustion bowl. All surfaces were found satisfactory. No signs of pitting or scuffing were noticed. NUMBERS 5, 7, AND 8


A14521

Q-109  
03-341A

This inspection Report is satisfactory  
for design Review

*[Handwritten Signature]*

A14522

1	 <b>DEFICIENCY REPORT</b>	<input checked="" type="checkbox"/> FIELD <input type="checkbox"/> OTHER	LDR RESPONSIBILITY  M. Herlihy LSU	LDR NUMBER 2147 <del>1047</del>	
2	SYSTEM/COMPONENT Emer. Diesel Gen.	SYSTEM DESIGNATOR 1R43B	MARK NO. 1R43*ENG-02	DATE 2/29/84	Q CLASS <input checked="" type="checkbox"/> I <input type="checkbox"/> II <input type="checkbox"/> III
3	MFG./CONTRACTOR TDI	P.O. 310552	MATERIAL LOCATION EDG-102 Rooms	REJECT TAG NO. <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	
4	SPEC. VIOLATED SHI-039	DRAWING VIOLATED N/A	PROCEDURE VIOLATED N/A	CODE/STANDARD VIOLATED N/A	
5	CONDITION DETAILS  The enclosed DGQRG TER#Q-41 dated 2/22/84 identifying discrepancies on pistons #5, #7, & #8 for Diesel Generator #102 requires resolutions.				
6	ORIGINATOR <i>M. Herlihy</i> 2/29/84 SIGNATURE DATE		<i>[Signature]</i> 2/29/84 SIGNATURE DATE		
7	RESPONSIBILITY <input type="checkbox"/> LSU <input checked="" type="checkbox"/> S & W ENG.	<i>[Signature]</i> SIGNATURE/LEAD SU ENG.		DATE 2/29/84	
8	ACTION <input checked="" type="checkbox"/> ACCEPT AS IS <input type="checkbox"/> REWORK <input type="checkbox"/> MANUAL <input type="checkbox"/> FSAR <input type="checkbox"/> SCRAP <input type="checkbox"/> REPAIR <input type="checkbox"/> PROCEDURE <input checked="" type="checkbox"/> OTHER SEE BELOW FOR PISTON #10				
9	DISPOSITION DETAILS THE CONDITIONS IDENTIFIED IN THE ATTACHMENTS ARE ACCEPTABLE AS IS. CONDITIONS HAVE BEEN EVALUATED AND ARE NOT TO BE NORMAL WEAR, NOT CONSIDERED A UNSATISFACTORY CONDITION. <del>SEE ATTACHMENT</del> REFERENCE: THE ATTACHED TDI MEMO. * NOTE - THE CONDITION DESCRIBED FOR THE # 6 PISTON WAS ADDRESSED ON LDR-2081				
10	APPROVALS <i>[Signature]</i> 3/1/84 S & W LEAD ENG./LSU TEST ENG./DATE		<i>[Signature]</i> FOR J. CANDEY 3/1/84 PROJECT ENGINEER DATE		
11	LILCO SU ENG. _____ DATE _____	LILCO SITE OGA _____ DATE _____	REPAIR/REWORK REQUEST NO. _____		
12	ENG. COMPLETE/DATE _____	RRR COMPLETE _____		RERWORK INSPECTION <input type="checkbox"/> SAT. <input type="checkbox"/> UNSAT.	
13	LDR CLOSED _____ LILCO SITE OGA/DATE _____	NEW LDR REPORT NO. ISSUED _____	REMARKS A14778		

Transamerica  
Delaval



Transamerica Delaval Inc  
Engine and Compressor Division  
550 85th Avenue  
P O Box 2161  
Oakland, California 94621

Date: 1 MARCH 1984 3-42  
To: JOHN KAMMEYER  
From: DON SCHMITZ  
Subject: EMERGENCY DIESEL GEN #102- SN 74011  
MECHANICAL WEAR ON VARIOUS COMPONENTS  
LDR- 2147, 2146, 2145, 2144, 2143

THE WEAR REPORTED ON SUBJECT LDR'S  
WAS INSPECTED BY MR. M. LOWREY  
OF DELAVALL ENGINEERING AND A DETERMINATION  
WAS MADE THAT THE WEAR WAS  
NORMAL AND COMPONENT SHOULD BE  
USED IN THE 'AS IS' CONDITION.

Donald L Schmitz

114156

Memo

COMPONENT TASK EVALUATION REPORT

ITEM/COMPONENT NO. D 3-34/A D.G. 103	TDI PART NO. 1A-5522	INITIATOR <u>Kenneth M. Fitch</u> SIGNATURE	DATE 3-12-84	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
--	-------------------------	---	-----------------	---

DISPOSITION DETAILS: Attached Inspection Report (1 page) by B Hayes dated 3-12-84 was generated as informational, as no acceptance criteria was provided prior to the performance of the inspection.

RECOMMENDATIONS: Forward to Design Review for evaluation. Attached IR is unsatisfactory. See Sheet 2 for recommended amendments.

REQUIRED COMPLETION DATE: 3-12-84

ASSIGNMENT

DISPOSITION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <u>B. Frazer</u> SIGNATURE	DATE 3-12-84
---	--	-----------------

DISPOSITION

DISPOSITION DETAILS:

DISPOSITION ASSIGNED TO <input type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY <input type="checkbox"/> NONE REQUIRED					
APPLIED BY	DATE	REVIEWED BY	DATE	APPROVED BY	DATE
		RESP. CHAIRPERSON		PROGRAM MANAGER	

ACTION

DISPOSITION ASSIGNED TO	ACTION COMPLETED BY	DATE

CKS/GWR/RJN/EFM  
TER LOC

ATTACHMENT TO LDR 2198

PAGE 2 OF 5

A15121



RECOMMENDED  
UNSAT TER DISPOSITION

Q-159

2/3

Distribute for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group a statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-159", for each component affected.
- 2) SEO (J. Kammeyer) - distribute for information.
- 3) LSU/OQA - review for applicability and issue LDR as needed.
- 4) M. Schuster - obtain LDR number as issued for component files and closeout.

ATTACHMENT TO LDR 2198

PAGE 3 OF 5

A15-122


QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 3-12-84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME:  Piston	DG- 103	I.P. NO. _____ REV. 3 CHG 0
COMPONENT NO. 03-3414		TER # _____
		LILCO LP PROC. _____ REV. _____
		DWG. NO. _____

ATTACHMENT TO LDR 2198  
PAGE 4 OF 5

NO	ITEM	QTY	DESCRIPTION(S) AND INSPECTION REMARK(S)
2	2		<p>A VISUAL WAS PERFORMED ON THE SKIRT AND CROWN O.D FOR SCUFFING AND THE SKIRT AREA BELOW FOR PITTING. THE FOLLOWING WAS NOTED:</p> <p>CYLINDER 5 - SCUFFING ON INTAKE AND EXHAUST SIDE OF SKIRT - ONE SIDE MORE SEVERE THAN OTHER NOTED - BY SHINY AREA. CROWN O.D HAS VARIOUS AMOUNTS OF PITTING AND THE COMBUSTION BOWL IS VERY SLIGHT IN PITTING.</p> <p>CYLINDER 7 - SKIRT AND CROWN O.D APPEAR SATISFACTORY BUT COMBUSTION BOWL HAS VERY SLIGHT PITTING.</p> <p>CYLINDER 8 - SCUFFING APPEARS ON INTAKE AND EXHAUST SIDE OF SKIRT, CROWN SOME MINOR SCUFFING. COMBUSTION BOWL SHOWS THREE SMALL SCRATCH MARKS RANGING FROM 1/16 TO 3/16".</p>
MSTE NO. _____			

 <b>DEFICIENCY REPORT</b>		<input checked="" type="checkbox"/> FIELD <input type="checkbox"/> OTHER	LDR RESPONSIBILITY <u>M. Herlihy</u> LSU	LDR NUMBER <u>2198</u> <del>1098</del> 103 Outage
SYSTEM/COMPONENT <u>Emerg. Diesel Gen.</u>	SYSTEM DESIGNATOR <u>1R43C</u>	MARK NO. <u>1R43 * EXG-103</u>	DATE <u>3/12/84</u>	CLASS <input checked="" type="checkbox"/> I <input type="checkbox"/> II <input type="checkbox"/> III
MFG./CONTRACTOR <u>TDE</u>	P.O. <u>310552</u>	MATERIAL LOCATION <u>TR elev 63'</u>	REJECT TAG NO. <u>A/A</u>	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
SPEC. VIOLATED <u>541-089</u>	DRAWING VIOLATED <u>N/A</u>	PROCEDURE VIOLATED <u>N/A</u>	CODE/STANDARD VIOLATED <u>N/A</u>	
CONDITION DETAILS <u>TER Q-159 (03-341A) reports unsatisfactory conditions. QCIP for #5, 7 &amp; 8 pistons identifies scuffing of piston skirts, pitting on piston crowns and <del>on</del> combustion bowl and scratch marks on #8 piston combustion bowl. Evaluation of these conditions is required.</u>				
ORIGINATOR <u>B. J. Beyti</u> SIGNATURE	<u>3/12/84</u> DATE	OOAE <u>[Signature]</u> SIGNATURE	<u>3-12-84</u> DATE	
RESPONSIBILITY <input type="checkbox"/> LSU <input checked="" type="checkbox"/> S & W ENG.	<u>B. J. Beyti</u> SIGNATURE	LEAD SU ENG.	DATE <u>3/12/84</u>	
ACTION <input checked="" type="checkbox"/> ACCEPT AS IS <input type="checkbox"/> SCRAP	<input type="checkbox"/> REWORK <input type="checkbox"/> REPAIR	<input type="checkbox"/> MANUAL <input type="checkbox"/> PROCEDURE	<input type="checkbox"/> FSAR <input type="checkbox"/> OTHER	
DISPOSITION DETAILS <u>THE ABOVE CONDITIONS DESCRIBED FOR PISTONS #5, 7, &amp; 8 ARE ACCEPTABLE AS IS PER ATTACHED TDI MEMO. PISTON COMPONENTS TO BE CLEANED BEFORE REASSEMBLY IN ACCORDANCE WITH TDI MANUAL, VOL I.</u>				
APPROVALS <u>[Signature]</u> S & W LEAD ENG./LSU TEST ENG./DATE	<u>3/17/84</u> DATE	<u>[Signature]</u> PROJECT ENGINEER	<u>3/17/84</u> DATE	
<u>B. J. Beyti</u> LILCO SU ENG.	<u>3/17/84</u> DATE	<u>[Signature]</u> LILCO SITE OQA	<u>3/20/84</u> DATE	REPAIR/REWORK REQUEST NO. <u>N/A R43-1571</u>
ENG. COMPLETE/DATE <u>SEO</u> <u>3/17/84</u>	RRR COMPLETE <u>N/A</u>	REWORK INSPECTION <input type="checkbox"/> SAT. <input type="checkbox"/> UNSAT. <u>[Signature]</u> <u>5/12/84</u>	LILCO SITE OQA/DATE	
LDR CLOSED <u>[Signature]</u> LILCO SITE OQA/DATE	<u>5/14/84</u> DATE	NEW LDR REPORT NO. ISSUED <u>N/A</u>	REMARKS <u>N/A</u>	



ATTACHMENT TO  
LDR 2198

Date: March 17, 1984 PAGE 5 OF 5  
To: John Kammerer  
From: Robert Johnston  
Subject: Diesel Generators, T111 5/11 74010/12  
74012 Piston Assemblies

Reference: LDR 2198

Referenced LDR reports unsatisfactory conditions found during inspection of numbers 5, 7 and 8 piston assemblies due to scuffing, pitting and scratches. The number 5 piston has scuffing evident in the tin plating on the piston skirt in the normal thrust surfaces. The condition is attributed to the excessive wear found in that cylinder and reported in LDR 2188. No overheating is evident on the piston skirt and sufficient tin plate remains to provide an adequate break-in in a new liner. Scuffing to a lesser degree is also noted on the number 8 skirt and is not an unusual condition to occur during break-in. Pitting reported in the combustion bowls and circumference of the 5, 7 and 8 piston crowns was found to be very minor and an acceptable condition for a steel casting. Scratches in the combustion bowl of number 8 piston crown are attributed to handling and are not detrimental to the crown. Recommended Disposition: Clean components and return to service.

**Memo**

A15124

TER # Q-500  
 84/13

COMPONENT TASK EVALUATION REPORT

DG 103 R.

ITEM/COMPONENT NO. <i>Pistons -</i> <b>03-341</b>	TDI PART NO. <b>1A-6522</b>	INITIATOR <i>J. Heas</i> SIGNATURE	DATE <b>5/14/84</b>	ORGANIZATION <input type="checkbox"/> ENGINEERING <input checked="" type="checkbox"/> QUALITY
---	--------------------------------	--	------------------------	---

CONDITION DETAILS: ATTACHED INSPECTION REPORT ( 1 PAGES) GENERATED BY J. Heas DATED 4/30/84 IS CONSIDERED INFORMATIONAL AS NO ACCEPTANCE CRITERIA WAS PROVIDED PRIOR TO THE PERFORMANCE OF THE INSPECTION.

RECOMMENDATIONS: FORWARD TO DESIGN REVIEW FOR EVALUATION AND ALSO TO SEO AND LSU FOR INFORMATION ONLY. *Attached IR is unsatisfactory - see pg 2 for recommended disposition.*

REQUIRED COMPLETION DATE:

ASSIGNMENT		
POSITION ASSIGNED TO ENGINEERING <input type="checkbox"/> QUALITY	RESPONSIBLE CHAIRPERSON <i>M. J. ...</i> SIGNATURE	DATE <b>5/15/84</b>

DISPOSITION

DISPOSITION DETAILS:

DISPOSITION ASSIGNED TO <input type="checkbox"/> ENGINEERING <input type="checkbox"/> QUALITY <input type="checkbox"/> NONE REQUIRED					
SUPPLIED BY	DATE	REVIEWED BY	DATE	APPROVED BY	DATE
		RESP. CHAIRPERSON		PROGRAM MANAGER	

ACTION		
ACTION ASSIGNED TO	ACTION COMPLETED BY	DATE

CC: CKS/GWR/RJN/EFM  
 TER LOG

A15799

Distribute for action as follows:

- 1) Design Review (G. Rogers) - Review as part of Design Review Task. Return to Quality Group's statement of acceptability (i.e., inspection information is sufficient for Design Review Group and no further inspections are required) or provide further detailed inspection/criteria, and add to Task Description "review information provided on TER Q-500", for each component affected.
- 2) SDO (J. Kammeyer) - distribute for information.
- 3) LSU/OQA - review for applicability and issue LDR as needed.
- 4) W. Schuster - obtain LTR number as issued for component files and closeout.

A15791

QUALITY CONTROL INSPECTION REPORT

JOB NUMBER 11600.37 DATE 4/30/84

SYSTEM(S) OR PART(S) NAME	LOCATION(S)	REFERENCE DOCUMENT(S)
COMPONENT NAME: Pistons 1 thru 8	DG- 103	I.P. NO. _____ REV. _____ CHG _____
COMPONENT NO. 03-341		ITER # _____
		LILCO LP PROC. _____ REV. _____
		DWG. NO. _____

P. NO.	ITEM QTY	DESCRIPTION(S) AND INSPECTION REMARK(S)
		<p>During visual inspection of the assembled pistons 1 through 8 from engine 103, the following has been observed.</p> <p>Carbon caking has been found along the outside edge of the crown and down along the top ring typical on all pistons. The #6 piston had a bit heavier carbon crusting and the top ring was bound at about 2 o'clock locking down from the top with the notch at 6 o'clock.</p> <p>On the #2 piston the top ring was wearing off center to the top edge of the ring.</p> <p>No unusual skuffing or scratching was observed on the outboard portions of the piston and piston skirts.</p>
		<p style="text-align: right;">A15792</p> <p>PHOTOGRAPHIC DOCUMENTATION TAKEN ALL PISTONS</p>
		<p>M&amp;E NO. <u>N/A</u> NOTES APR 30 1984</p>

<b>LILCO</b> <b>DEFICIENCY REPORT</b>	<input checked="" type="checkbox"/> FIELD <input type="checkbox"/> OTHER	LDR RESPONSIBILITY <i>M. Herlihy</i> LSU	LDR NUMBER 2407
SYSTEM/COMPONENT <i>Emex Diesel Gen</i>	SYSTEM DESIGNATOR 1R43	MARK NO. R43#EDS 102	DATE 5/16/84
MFG./CONTRACTOR TDE	P.O. 310552	MATERIAL LOCATION TB W' 1st down area	Q CLASS <input type="checkbox"/> I <input type="checkbox"/> II <input type="checkbox"/> III REJECT TAG NO. <i>N/A</i> <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
SPEC VIOLATED SHI-054	DRAWING VIOLATED N/A	PROCEDURE VIOLATED N/A	CODE/STANDARD VIOLATED
CONDITION DETAILS <i>TER # Q-500 (03-341A) Reports unsat conditions. Attached QCIR for pistons 1-8 reports various conditions requiring evaluation</i>			
ORIGINATOR <i>M. Herlihy</i> SIGNATURE	DATE 5/16/84	OQAE <i>[Signature]</i> SIGNATURE	DATE 5/16/84
RESPONSIBILITY <input type="checkbox"/> LSU <input checked="" type="checkbox"/> S & W ENG.	DATE 5/21/84	ACTION <input type="checkbox"/> ACCEPT AS IS <input type="checkbox"/> SCRAP <input checked="" type="checkbox"/> REWORK <input type="checkbox"/> REPAIR <input type="checkbox"/> MANUAL <input type="checkbox"/> PROCEDURE <input type="checkbox"/> FSAR <input type="checkbox"/> OTHER	
DISPOSITION DETAILS <i>ALL PISTON ASSEMBLIES WILL BE CLEANED TO REMOVE CARBON DEPOSITS PRIOR TO REASSEMBLY. UPON REASSEMBLY OF ALL PISTON ASSEMBLIES, ALL RING SETS WILL BE REPLACED WITH NEW MUSKEGIN RING SETS.</i>			
APPROVALS <i>[Signature]</i> S & W LEAD ENG./LSU TEST ENG./DATE	DATE 5/23/84	PROJECT ENGINEER <i>[Signature]</i> DATE 5/23/84	
LILCO SU ENG. DATE 5/24/84	LILCO SITE OQA DATE 6/5/84	REPAIR/REWORK REQUEST NO. R43-1844	
ENG. COMPLETE/DATE N/A	RRR COMPLETE N/A CONST. SUPT./DATE	LILCO SU/DATE <i>[Signature]</i> 7/9/84	REWORK INSPECTION <input checked="" type="checkbox"/> SAT. <input type="checkbox"/> UNSAT. <i>R. Catore 7-9-84</i> LILCO SITE OQA/DATE
LDR CLOSED <i>[Signature]</i> 7/16/84 LILCO SITE OQA/DATE	NEW LDR REPORT NO. ISSUED N/A	REMARKS	



EDG 101



LIQUID PENETRANT EXAMINATION REPORT

AF PISTONS

A. MATERIAL		TYPE <i>CS</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX — INCH	MIN — INCH	SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER

4. DYE PROCEDURE No. <i>6.1+6.2</i>	TEMP. / MAT'L. TEMP. <i>73°F</i>	<i>367</i>	Supp-1 <i>R43-1172</i>
--	-------------------------------------	------------	---------------------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/EC-7B</i>	<i>82D119</i>
2. PENETRANT		<i>SKL-HF/SK4</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/EC-7B</i>	<i>82D119</i>
4. DEVELOPER		<i>SKD-NF/EP-9B</i>	<i>83C042</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/EC-7B</i>	<i>82D119</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
 Examined machined area *on C.11* *boss*. *101 Diesel Piston-SPARE*

C. EVALUATION  
 REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>1</i>	<i>N/A</i>	<i>None</i>	<i>Accept (No relevant inds)</i>
<i>2</i>			
<i>3</i>			
<i>4</i>			

D. ACCEPTANCE CRITERIA	<i>Lilco NDE 6.2 Para 4.2.2</i>	<i>E. Hassell / Asst J. Pink</i> <i>11/4/83</i>
------------------------	---------------------------------	--

E. ATTEST	<i>Earl Hassell</i> RESPONSIBLE CERTIFIED PERSONNEL	<i>II</i> LEVEL	<i>11/4/83</i> DATE
-----------	--	--------------------	------------------------

COMPONENT I.D. 101 Diesel  
 SYSTEM  
 Piston Skirt # SPARE R43\*Emerg Piston Gen  
 PLANT/LOCATION  
 SPS-1 Turb Dept

PT  
COMPONENT I.D. 101 Diesel  
Piston Skirt #1A  
SYSTEM  
R43X Energy Dies Gen  
PLANT/LOCATION  
SNPS-1/Turbine Deck

A. MATERIAL		TYPE <i>c/s</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX — INCH	MIN — INCH	SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER
GEOMETRY		<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD	<input type="checkbox"/> OTHER: <i>Piston Skirt</i>

B. NDE PROCEDURE No. <i>6.1 + 6.2</i>	SURFACE / MAT'L. TEMP. <i>73°F</i>	Due <i>4.22.84</i>	INSTR. NO. <i>R43-1152</i>
---------------------------------------	------------------------------------	--------------------	----------------------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/ZC-7B</i>	<i>82D119</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/ZC-7B</i>	<i>82D119</i>
4. DEVELOPER		<i>SKD-NF/ZP-9B</i>	<i>83C042</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/ZC-7B</i>	<i>82D119</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area on 101 Diesel around boss. Piston 1A*


C. EVALUATION  
 REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>1 See Sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>1/4" C.N.</i>	<i>linear</i>	<i>Reject (L.P.R. Issued)</i>
<i>3</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>4</i>	<i>5/32</i>	<i>linear</i>	<i>Reject (LDR Issued)</i>

D. ACCEPTANCE CRITERIA  
*Like NDE 62 Para 4.2.2*  
 Inspected by *Earl Hassell / Asst. by J. Pink*  
 Date *11/4/73*





E. ATTEST  
*Earl Hassell*  
 RESPONSIBLE CERTIFIED PERSONNEL  
 LEVEL *II* DATE *11/4/73*

Diesel #101 Piston #1A



Overhead View

Side Views, looking out from inside




5/32" line

A. MATERIAL		TYPE <u>C/S</u>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED	
		GEOMETRY <input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER: <u>Piston</u>		
CROSS SECTION THICKNESS	MAX — INCH	MIN — INCH	SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER	
B. NDE PROCEDURE Inv. <u>6.1+6.2</u>		SURFAC. / MAT'L. TEMP. <u>73° F</u>	Due: <u>4-22-84</u>	NO. <u>843-1142</u>
INSPECTION MATERIALS		BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER		<u>Magnaflux</u>	<u>SKC-NF/ZC-7B</u>	<u>82D119</u>
2. PENETRANT			<u>SKL-HF/SKLS</u>	<u>7D073</u>
3. EMULSIFIER AND/OR REMOVER			<u>SKC-NF/ZC-7B</u>	<u>82D119</u>
4. DEVELOPER			<u>SKD-NF/ZP-9B</u>	<u>83C042</u>
5. POST EXAMINATION CLEANER			<u>SKC-NF/ZC-7B</u>	<u>82D119</u>
SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY <u>Examined machined area on P.M. 101 Diesel Piston-2A</u>				
C. EVALUATION		REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.		
LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)	
<u>Bolt Hole</u> <u>See sketch</u>	<u>1/4</u>	<u>linear</u>	<u>Reject (LDR Issued)</u>	
<u>2</u>	<u>N/A</u>	<u>None</u>	<u>Accept</u>	
<u>3</u>	<u>1/8, 3/16</u>	<u>linear</u>	<u>Reject (LDR Issued)</u>	
<u>4</u>	<u>N/A</u>	<u>None</u>	<u>Accept</u>	
D. ACCEPTANCE CRITERIA	<u>ILCO NDE 6.2 Para 4.2.2</u>		<u>E. Hassell / Asst. J. Pink</u> <u>II</u> <u>11/4/83</u>	
E. ATTEST	<u>Earl Hassell</u> RESPONSIBLE CERTIFIED PERSONNEL		<u>II</u> LEVEL	<u>11/4/83</u> DATE





COMPONENT I.D. 101 Diesel  
 Piston Skirt #2A  
 SYSTEM  
 1843x Emergency Diesel Gen.  
 PLANT/LOCATION  
 SNPS-1/Turbine Deck

Diesel #101 Piston #2A



Overhead View

Side Views, looking out from inside



LIQUID PENETRANT EXAMINATION REPORT

COMPONENT I.D. 101 Diesel  
Piston Skirt #3A

A. MATERIAL		TYPE <u>c/s</u>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX — INCH	MIN — INCH	SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER
		GEOMETRY <input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER: <u>Piston Skirt</u>	

B. NDE PROCEDURE No. <u>61462</u>	SURF. / MAT'L. TEMP. <u>73°F</u>	DATE: <u>4-22-84</u>	TIME: <u>11:42</u>
-----------------------------------	----------------------------------	----------------------	--------------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<u>Magnaflux</u>	<u>SKC-NF/ZC-7B</u>	<u>82D119</u>
2. PENETRANT		<u>SKL-HF/SKLS</u>	<u>7D073</u>
3. EMULSIFIER AND/OR REMOVER		<u>SKC-NF/ZC-7B</u>	<u>82D119</u>
4. DEVELOPER		<u>SKD-NF/EP-9B</u>	<u>83C042</u>
5. POST EXAMINATION CLEANER		<u>SKC-NF/ZC-7B</u>	<u>82D119</u>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
Examined machined area on E. of boss. 101 Diesel  
Piston-3A

SYSTEM  
101 Diesel Piston-3A


C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
1 Bolt Hole See Sketch	N/A	N/A	Accept
2	3/16	linear	Reject (LDR Issued)
3	N/A	N/A	Accept
4	N/A	N/A	Accept



PLANT/LOCATION  
SNPS-1/Turbine Deck

D. ACCEPTANCE CRITERIA <u>Lilco NDE G-2 Para 4.2.2</u>	E. ATTEST <u>Carl Hassell</u> RESPONSIBLE CERTIFIED PERSONNEL	LEVEL <u>II</u>	DATE <u>11/4/83</u>
---	---	--------------------	------------------------



Diesel #101 Piston #3A



Overhead View



Side Views, looking out from inside







LIQUID PENETRANT EXAMINATION REPORT

A. MATERIAL		TYPE <i>C/S</i>	FABRICATED PROCESS	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX INCH	MIN INCH	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND	<input type="checkbox"/> OTHER
3. NDE PROCEDURE No. <i>61462</i>		TEMP. <i>73°F</i>		<i>367</i>	Due: <i>4/22/84</i> No. <i>R43-1142</i>	
INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.			
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/ZC-7B</i>	<i>82D119</i>			
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>			
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/ZC-7B</i>	<i>82D119</i>			
4. DEVELOPER		<i>SKD-NF/EP-9B</i>	<i>83C042</i>			
5. POST EXAMINATION CLEANER		<i>SKC-NF/ZC-7B</i>	<i>82D119</i>			

COMPONENT I.D. 101 Diesel  
 Piston Skirt #4A

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area on S.H. around boss. Piston-4A*

SYSTEM  
 1R43 Emergency Piston Cap.


C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i>	<i>(2) (2)</i>		
<i>See Sketch</i>	<i>1/8, 1/4</i>	<i>linear</i>	<i>Reject (LDR Issued)</i>
<i>2</i>	<i>1/8</i>		
<i>3</i>	<i>3/16, 7/16</i>		
<i>4</i>	<i>1/4</i>		
D. ACCEPTANCE CRITERIA	<i>Lilco NDE 6.2 Para 4.2.2</i>		<i>E. Hassell / Asst. J. Pink II 11/4/83</i>


PLANT/LOCATION  
 SPS-1 Turbine Deck

E. ATTEST  
*Carl Hassell*  
 RESPONSIBLE C: *ED PERSONNEL* LEVEL: *II* DATE: *11/4/83*




# Diesel #101 Piston #4A



Overhead View



Side Views, looking out from inside



LIQUID PENETRANT EXAMINATION REPORT

A. MATERIAL		TYPE <i>C/S</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX INCH	MIN INCH	SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER
		GEOMETRY <input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER: <i>Piston Skirt</i>	

COMPONENT I.D. 101 Diesel  
Piston Skirt # 5A

B. NDE PROCEDURE No. <i>6.1+6.2</i>	SURFACE / MAT'L. TEMP. <i>73°F</i>	INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
		1. PRE-CLEANER			
		2. PENETRANT	<i>Magnaflux</i>	<i>SKC-NF/3C-7B</i>	<i>82D119</i>
		3. EMULSIFIER AND/OR REMOVER		<i>SKL-HE/SKLS</i>	<i>7D073</i>
		4. DEVELOPER		<i>SKC-NF/2C-7B</i>	<i>82D119</i>
		5. POST EXAMINATION CLEANER		<i>SKD-NF/2P-9B</i>	<i>83C047</i>
				<i>SKC-NF/2C-7B</i>	<i>82D119</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area on C.H. around boss. 101 Diesel Piston-5A*

SYSTEM  
IR 35 + Energy Dies. Gen


C. EVALUATION  
 REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i>			
<i>1 See Sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>5/16</i>	<i>Linear</i>	<i>Reject (LDR Issued)</i>
<i>3</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
D. AUTHORITY <i>CH 19.2.1a</i>	<i>Lilconde 6.2</i>		<i>E. Hassel / Asst. J. Pink</i> <i>11/4/83</i>



E. ATTEST	<i>Carl Hassel</i>	LEVEL <i>II</i>	DATE <i>11/4/83</i>
-----------	--------------------	--------------------	------------------------

PLANT/LOCATION  
ENPS-1 Turb. Deck



Diesel #101 Piston #5A



Overhead view



Side Views, looking out from inside



A. MATERIAL		TYPE	FABRICATED PROCESS		
		<i>C/S</i>	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		MAX	MIN	SURFACE CONDITION	
— INCH		— INCH	— INCH	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
				<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

PT  
Piston Skirt # GA  
COMPONENT I.D. 101 Diesel

B. NDE PROCEDURE No. <i>G.1+G.2</i>	TEMP. <i>73°F</i>	<i>367</i>	NO. <i>R43-1142</i>
		DATE <i>4/22/84</i>	

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/2C7B</i>	<i>82D119</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/2C7B</i>	<i>82D119</i>
4. DEVELOPER		<i>SKD-NF/EP-9B</i>	<i>83C042</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C7B</i>	<i>82D119</i>

SYSTEM  
101 Diesel  
Piston-GA  
RUSH Emerg Dies Gen

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area around boss on C.4*  
*101 Diesel*  
*Piston-GA*


C. EVALUATION  
 REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>1 See Sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>(2) 3/32, 1/8</i>	<i>Linear</i>	<i>Reject (LDR Issued)</i>
<i>3</i>	<i>1/8</i>		
<i>4</i>	<i>3/16, 1/4</i>		
D. ACCEPTANCE CRITERIA	<i>Lilco NDE G.2 Para 4.2.2</i>		<i>E. Hassell / Asst. J. Pink</i> <i>II 11/4/83</i>

PLANT/LOCATION  
SVPS-1 Turb Deck



E. ATTEST	<i>Carl Hassell</i>	<i>II</i>	<i>11/4/83</i>
RESPONSIBLE C:	ED PERSONNEL	LEVEL	DATE

Diesel #101 Piston # GA





Notch side

Overhead view



Side Views, looking out from inside



A. MATERIAL		TYPE <i>c/s</i>	FABRICATED PROCESS	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		MAX	MIN	SURFACE CONDITION		
— INCH		— INCH	— INCH	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND	<input type="checkbox"/> OTHER: <i>Piston Skirt</i>
				<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER	

PT  
COMPONENT I.D. 101 Diesel  
Piston Skirt # 7A

B. NDE PROCEDURE No. <i>C.1 + C.2</i>	TEMP. <i>73°F</i>	<i>367</i>	NO. <i>R43-1142</i>
INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/ZC-7B</i>	<i>82D119</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/ZC-7B</i>	<i>82D119</i>
4. DEVELOPER		<i>SKD-NF/EP-9B</i>	<i>83C042</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/ZC-7B</i>	<i>82D119</i>

SYSTEM  
IR43\*Emergency Dies Gen.

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
Examined machined area <sup>on c/s</sup> around boss. *101 Diesel Piston-7A*


C. EVALUATION  
REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole 1</i> <i>See sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>2/16 5/32</i>	<i>Linear</i>	<i>Reject (LDR Issued)</i>
<i>3</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>4</i> <i>↓</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
D. ACCEPTANCE CRITERIA	Lilco NDE C.2 <i>Para 4.2.4</i>		<i>E. Hassell / asst. J. Pink</i> <i>II</i> <i>11/4/83</i>

PLANT/LOCATION  
*SURS-Turb Inlet*



E. ATTEST	<i>E. Hassell</i>	<i>II</i>	<i>11/4/83</i>
RESPONSIBLE PERSONNEL	LEVEL	DATE	

Diesel #101 Piston # 7A





Notch Side

Overhead view



Side Views, looking out from inside





LIQUID PENETRANT EXAMINATION REPORT

A. MATERIAL		TYPE <i>c/c</i>	FABRICATED PROCESSES	
		GEOMETRY	<input type="checkbox"/> PIPE	<input type="checkbox"/> PLATE
			<input type="checkbox"/> ROD	<input checked="" type="checkbox"/> OTHER: <i>PISTON SKIRT</i>
CROSS SECTION THICKNESS	MAX <i>2"</i> INCH	MIN <i>2"</i> INCH	SURFACE CONDITION	
			<input type="checkbox"/> MACHINED	<input checked="" type="checkbox"/> GROUND
			<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

<i>6.2</i>	TEMP. <i>720</i>	MATE # <i>367</i>	SUFF. # <i>1</i>
		<i>RE 4/22/84</i>	<i>R43-1142</i>

INSPECTION MATERIALS	BRAND	REGISTRATION	BATCH NO.
1. PRE-CLEANER	<i>MAGNAFLUX</i>	<i>SKC-NF/ZC-7B</i>	<i>820119</i>
2. PENETRANT	<i>"</i>	<i>SKL-HF/SKLS</i>	<i>70073</i>
3. EMULSIFIER AND/OR REMOVER	<i>"</i>	<i>SKC-NF/ZC-7B</i>	<i>820119</i>
4. DEVELOPER	<i>"</i>	<i>SKL-NF/ZP-9B</i>	<i>83C042</i>
5. POST EXAMINATION CLEANER	<i>"</i>	<i>SKC-NF/ZC-7B</i>	<i>820119</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

*PERFORMED L.P. INSPECTION IN ACCORDANCE WITH ATTACHED IOC # 34 AFTER GRINDING AND BUFFING ON PREVIOUSLY REJECTED AREA (SEE ATTACHED SKETCH)*

C. EVALUATION


REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHEN ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>1 N/A</i>			
<i>2 BOLT HOLE #2</i>	<i>2-1/16"</i> <i>4-1/32"</i>	<i>6 ROUNDED INDICATIONS</i>	<i>ACCEPTABLE ROUNDED INDICATIONS MEET WITH ACCEPTANCE CRITERIA OF NDE 6.2</i>
<i>3 N/A</i>			
<i>4 N/A</i>			
	<i>NDE 6.2</i>		<i>RENNIS PIETROUX</i> <i>II</i> <i>11/5/83</i>

E. ATTEST	<i>R. Pietrowski</i>	<i>II</i>	<i>11/5/83</i>
	RESPONSIBLE CERTIFIED PERSONNEL	LEVEL	DATE


COMPONENT I.D. 101 VESSEL  
 PISTON SKIRT # 7A  
 SYSTEM  
 1R43K  
 NAME/LOCATION  
 SNR / 63 TURBINE DECK

Diesel # 101 Piston # 7A



Notch Side

Overhead View



Side View, looking out from inside

# INTEROFFICE CORRESPONDENCE #34

<b>TO</b> M. Herlihy	<b>LOCATION</b>	<b>SUBJECT / REFERENCE / J.O. NO.</b>
<b>FROM</b> J. C. Kammeier	<b>LOCATION</b>	EDG 101 Piston Skirt Inspection

**MESSAGE: —**

The purpose of this memo is to provide guidelines for NDE to be performed on the piston skirts for the 101 engine. Note, upon disassembly of the piston assemblies for inspection, breakaway torques will be recorded for piston crown to skirt hold down studs.

Piston inspection will be as follows:

1. OQA will perform a color contrast penetrant test. Reference attached FaAA memo.
2. FaAA will perform an informational focused field eddy current test to confirm any rejectable indications found during PT. Reference attached FaAA memo.
3. Based on the information provided by the FaAA inspection, SEO will determine whether or not indications can be removed by additional surface preparation and cleanup.
4. OQA should perform another inspection after completion of any additional surface preparation and cleanup to determine if indications still exist.

If you have any questions, please call me.

11/4/83  
DATE

*J. C. Kammeier*  
SIGNATURE

X404  
TELEPHONE

**REPLY:**

CC MMH WJM  
EDY G Rogers  
PAH  
R Nych  
P Martin

After review of indications documented on LPR #1811, the #7A piston indication (which appears to be casting related) will be explored as required. Final LP to be documented. Work to be supervised by M. Schuster.

11/5/83 *J. C. Kammeier*

DATE


SIGNATURE

TELEPHONE

A. MATERIAL		TYPE <i>els</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED	PT
CROSS SECTION THICKNESS		MAX — INCH	MIN — INCH	GEOMETRY <input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER: <i>Piston Skirt</i>
B. NDE PROCEDURE No. <i>G.1 + G.2</i>		SURF. / MAT'L. TEMP. <i>73°F</i>		<i>367</i> DUE <i>4/22/83</i> R43-1142
INSPECTION MATERIALS		BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER		<i>Magnaflux</i>	<i>SKC-NF/ZC 7B</i>	<i>82D119</i>
2. PENETRANT			<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER			<i>SKC-NF/ZC 7B</i>	<i>82D119</i>
4. DEVELOPER			<i>SKD-NF/ZP-9B</i>	<i>83C042</i>
5. POST EXAMINATION CLEANER			<i>SKC-NF/ZC-7B</i>	<i>82D119</i>
SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY <i>Examined machined area <sup>on ch</sup> around boss. 101 Diesel Piston-8A</i>				
C. EVALUATION		REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.		
LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)	
<i>Bolt Hole</i> <i>see sketch</i>	<i>3/16, 3/32</i>	<i>Linear</i>	<i>Reject (LDR Issued)</i>	
<i>2</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>	
<i>3</i>				
<i>4</i>				
D. ACCEPTANCE CRITERIA	<i>Filco NDE G.2</i> <i>Para 4.2.2</i>		<i>E. Hassell / Asst. J. Pink</i> <i>II</i> <i>11/4/83</i>	
E. ATTEST	<i>Earl Hassell</i> RESPONSIBLE C: <i>ED PERSONNEL</i>		<i>II</i> LEVEL	<i>11/4/83</i> DATE


COMPONENT I.D. 101 Diesel  
 Piston Skirt # 8A  
 SYSTEM  
 R43 \* Engng Diesel Gen  
 PLANT/LOCATION  
 SVP5-1/Turb. Bldg.

# Diesel #101 Piston # 8A




Notch Side

Overhead View



Side Views, looking out from inside



EDG 102



LILCO LIQUID PENETRANT EXAMINATION REPORT

AF PISTONS

A. MATERIAL		TYPE	FABRICATED PROCESS		
		c/s	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		GEOMETRY	SURFACE CONDITION		
MAX	MIN	<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND	
— INCH	— INCH	<input checked="" type="checkbox"/> OTHER: Piston Skirt	<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER	

B. NDE PROCEDURE No. 6.1 + 6.2	TEMP. 69°F	367	Supp 2 No. R43-1144
INSPECTION MATERIALS		DESIGNATION	BATCH NO.

1. PRE-CLEANER	Magnaflux	SKC-NF/AC-7B	82JOB3
2. PENETRANT		SKL-HF/SKLS	7D073
3. EMULSIFIER AND/OR REMOVER		SKC-NF/AC-7B	82T083
4. DEVELOPER		SKD-NF	82D111
5. POST EXAMINATION CLEANER		SKC-NF/AC-7B	82T083

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
 Examined machined area on boss. 102 Diesel Piston #1B



C. EVALUATION	REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.
---------------	--

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
Bolt Hole 1 See sketch	3/16"	Crack	Reject (LPR Issued)
2	N/A	None	Accept
3	1/4" Ø	Rounded	Reject (LPR Issued)
4	N/A	None	Accept
DRAWN BY	Lilco NDE 6.2	Checked by	E. Hassell
DATE	Para 4.2.2	LEVEL	II 11/8/83




E. ATTEST	Carl Hassell	LEVEL	DATE
	RESPONSIBLE CERTIFIED PERSONNEL	II	11/8/83

COMPONENT I.D. SYSTEM LOCATION  
 Piston Skirt #1B  
 R43+EPG-102B  
 SUPS-1/Turb. Deck E. 63

Diesel #102 Piston #1B



Side Views, looking out from inside



Note Side

Overhead View



COMPONENT I.D. **Piston Skirt #2B**  
 SYSTEM **1R43+EDG-102B**  
 LOCATION **SNPS-1/Turb-Deck E1-C3**

A. MATERIAL		TYPE <b>c/s</b>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		GEOMETRY <input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER:	
MAX	MIN	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER
— INCH	— INCH		

3. NDE METHOD <b>G.1+G.2</b>	TEMP. <b>69°F</b>	<b>367</b> Due 4/22/84	Supp. 2 <b>R43-1144</b>
---------------------------------	-------------------	---------------------------	----------------------------

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<b>Magnaflux</b>	<b>SKC-NF/ZC-7B</b>	<b>82J083</b>
2. PENETRANT		<b>SKL-HF/SKLS</b>	<b>7D073</b>
3. EMULSIFIER AND/OR REMOVER		<b>SKC-NF/ZC-7B</b>	<b>82J083</b>
4. DEVELOPER		<b>SKD-NF</b>	<b>82D111</b>
5. POST EXAMINATION CLEANER		<b>SKC-NF/ZC-7B</b>	<b>82J083</b>


SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
 Examined machined area on boss **102 Diesel Piston #2B**

C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.



LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<b>Bolt Hole</b> 1 <b>See sketch</b>	<b>N/A</b>	<b>None</b>	<b>Accept</b>
2	<b>1/4"</b>	<b>crack</b>	<b>Reject (LDR-Issued)</b>
3	<b>1/8"</b>	<b>Linear</b>	<b>Reject (LDR Issued)</b>
4	<b>N/A</b>	<b>None</b>	<b>Accept</b>
D. ACTION	<b>Lilco NDE G.2</b>		<b>E. Hassell</b>
	<b>Para 4.2.2</b>		<b>II</b>
			<b>11/3/83</b>

E. ATTEST  
**Earl Hassell**  
 RESPONSIBLE CERTIFIED PERSONNEL      LEVEL **II**      DATE **11/3/83**

Diesel #102 Piston #2B




Side Views, looking out from inside.



Notch Side

Overhead View



LIQUID PENETRANT EXAMINATION REPORT

COMPONENT I.D. Piston Skirt #3B SYSTEM 102 Diesel Piston #3B LOCATION SVPS-1/Turb. Dr. 6163

A. MATERIAL		TYPE	FABRICATED PROCESS		
		<i>c/s</i>	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		MAX	MIN	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED
—		—	—	<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> GROUND
				<input type="checkbox"/> OTHER	<input type="checkbox"/> OTHER

B. NON FERROUS	MATERIAL	TEMP	367	Supp 4
<i>614G2</i>	<i>69°F</i>		Due 4/22/84	R43-1144

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/2C-7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/2C-7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C-7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

*Examined machined <sup>area</sup> on boss.*

*102 Diesel Piston #3B*


C. EVALUATION

REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>1 see sketch</i>	<i>1/4"</i>	<i>Crack</i>	<i>Reject (LDR Issued)</i>
<i>2</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>3</i>	<i>1/4" x 1/2"</i>	<i>Rounded</i>	<i>Reject (LDR Issued)</i>
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
Drawn by	<i>Lilco NDEC-2</i>		<i>E. Hassell</i>
Inspected by	<i>Para 4.2.2</i>		<i>II</i>
			<i>11/3/83</i>



E. ATTEST	<i>Earl Hassell</i>	<i>II</i>	<i>11/3/83</i>
	PERSONNEL CERTIFIED PERSONNEL	LEVEL	DATE

Diesel #102 Piston #3B






Notch Side

Overhead View



Side Views, looking out from inside





LILCO LIQUID PENETRANT EXAMINATION REPORT

COMPONENT I.D. SYSTEM LOCATION

Piston Skirt #4B

R43KEDG-102B

SWPS-1/Tab DE E1.03

A. MATERIAL		TYPE <i>c/s</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		MAX INCH	MIN INCH
		SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER	

1. NDE METHOD *G.1 + G.2*      2. TEMP. / MAT'L. *69°F*      3. *.367*      4. *Supp. 4*  
 Due *4/22/73*      R43-1144

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/EC-7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/3KLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/EC-7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/EC-7B</i>	<i>82J083</i>


SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined <sup>area</sup> on boss. 102 Diesel Piston #4B*

C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>see sketch</i>	<i>3/16"</i>	<i>Crack</i>	<i>Reject (LDR Issued)</i>
<i>2</i>	<i>9/16"</i>	<i>Crack</i>	<i>Reject (LDR Issued)</i>
<i>3</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
REWORKED BY	<i>Lilco NDE G.2 Para 4.2.2</i>		EXAMINER <i>E. Hassell</i> LEVEL <i>II</i> DATE <i>4/2/73</i>


E. ATTEST *Carl Hassell*      *II*      *11/3/73*  
 POSSIBLE CERTIFIED PERSONNEL      LEVEL      DATE

Diesel #102 Piston #4B





Notch Side

Overhead View



Side Views, looking out from inside



COMPONENT I.D. SYSTEM IRU3\*EDG-102B SUPS-1/TurbPr. E1.53

A. MATERIAL	TYPE	FABRICATED PROCESS		
	<i>C/S</i>	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX	MIN	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED
	— INCH	— INCH		
GEOMETRY		<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER <i>Piston Skirt</i>		
		<input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER		

B. NON FERROUS	TEMP. / MATH'L.	357	SUPP 2
No. <i>G.1 + G.2</i>	TEMP. <i>69°F</i>	Due <i>4/22/84</i>	<i>842-1144</i>

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/ZC-7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/ZC-7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/ZC-7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

*Examined machined area on boss, 102 Diesel Piston # 5B*


C. EVALUATION

REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>See Sketch</i>	<i>5/8"</i>	<i>Crack</i>	<i>Reject (LDR-issued)</i>
<i>2</i>	<i>5/16"</i>	↓	↓
<i>3</i>	<i>1/2"</i>	↓	↓
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
REMARKS	<i>Lilco NDE C 2 Para 4.2.2</i>		<i>E. Hassell</i> <i>II</i> <i>11/2/83</i>


E. ATTEST	<i>Earl Hassell</i>	<i>II</i>	<i>11/2/83</i>
	RESPONSIBLE CERTIFIED PERSONNEL	LEVEL	DATE

Diesel #102 Piston #5B




Notch Side

Overhead View



Side Views, looking out from inside





FT  
COMPONENT I.D.  
Piston Skirt #6B  
SYSTEM  
1R43+EPG-102  
ACTION  
SWPS-1/Turb Deck 15153

A. MATERIAL		TYPE	FABRICATED PROCESS		
		<i>c/s</i>	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		MAX	MIN	SURFACE CONDITION	
— INCH		— INCH	— INCH	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
				<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

B. NON FERROUS	MAT'L	TEMP.	Supp. 2
No. <i>G.1TG.2</i>		<i>69°F</i>	<i>367</i>
			<i>Due 4/22/83</i>

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/2C7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/3KLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/2C-7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area on boss. 102 Diesel Piston #6B*


C. EVALUATION	REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.
---------------	--

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>1 See sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>5/16 + 5/8</i>	<i>Crack</i>	<i>Reject (LDR Issued)</i>
<i>3</i>	<i>7/8</i>	<i>Crack</i>	
<i>4</i>	<i>7/8</i> <i>3/16</i>	<i>Crack</i> <i>Linear</i>	

D. APPROVAL	<i>Lileo NDE G.2</i>	<i>E. Hassell</i>
	<i>Para 4.2.2</i>	<i>11/3/83</i>


E. ATTEST	<i>Carl Hassell</i>	<i>CTI</i>	<i>11/3/83</i>
	CONSULE CERTIFIED PERSONNEL	LEVEL	DATE

Diesel #102 Piston #GB





Notch Side

Overhead View



Side Views, looking out from inside





LIQUID PENETRANT EXAMINATION REPORT

A. MATERIAL		TYPE	FABRICATED PROCESS		
		<i>c/s</i>	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS		MAX	MIN	SURFACE CONDITION	
— INCH		— INCH	— INCH	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
				<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

COMPONENT I.D.  
Piston Skirt #7B

SYSTEM  
1R437 EDG-102

LOCATION  
SUPS-1/Turb. Dh. E1.63

4. INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/ZC-7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/ZC-7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/ZC-7B</i>	<i>82J83</i>


SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area on boss.* *102 Diesel Piston #7B*

C. EVALUATION  
 REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>1 see sketch</i>	<i>1/2</i>	<i>Crack</i>	<i>Reject (LDR Issued)</i>
<i>2</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>3</i>	<i>1</i>	<i>Crack</i>	<i>Reject (LDR Issued)</i>
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
DRAWN BY <i>Lilco NDE 62</i>	REVIEWED BY <i>E. Hassell</i>		DATE <i>11/9/83</i>
PART <i>Para 4.2.2</i>		LEVEL <i>II</i>	


E. ATTEST	<i>Earl Hassell</i>	<i>II</i>	<i>11/9/83</i>
	CONSOLE CERTIFIED PERSONNEL	LEVEL	DATE

Diesel #102 Piston #7B




Notch Side

Overhead View



1/2" Crack

Side Views, looking out from inside



1" Crack

A. MATERIAL		TYPE <i>c/s</i>	FABRICATED PROCESS	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
		GEOMETRY	<input type="checkbox"/> PIPE	<input type="checkbox"/> PLATE	<input type="checkbox"/> ROD	<input checked="" type="checkbox"/> OTHER <i>Piston skirt</i>
CROSS SECTION THICKNESS	MAX INCH	MIN INCH	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND	<input type="checkbox"/> OTHER

4. NDE METHOD	5. TEMP	6. DATE	7. SUPP. NO.
No. <i>6.1 + 6.2</i>	<i>69°F</i>	<i>4/22/74</i>	<i>Supp. 2</i> <i>R43:1144</i>

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/ZC-7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7DC73</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/ZC-7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/ZC-7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

*Examined machined area on boss. 102 Diesel Piston #8B*


C. EVALUATION	REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.
---------------	--

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>1 See sketch</i>	<i>1/2</i> <i>3/16</i>	<i>Linear crack</i>	<i>Reject (LDR Issued)</i>
<i>2</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>3</i>			
<i>4</i>			
D. Inspector	<i>Lilco NDE 62</i> <i>Para 4.2.2</i>	<i>E. Hassell</i> <i>IP</i>	<i>11/8/83</i>

E. ATTEST	<i>Carl Hassell</i> CONSULE CERTIFIED PERSONNEL	<i>IP</i> LEVEL	<i>11/8/83</i> DATE
-----------	--	--------------------	------------------------


PT  
 COMPONENT I.D.  
 Piston Skirt #8B  
 SYSTEM  
 102 Diesel Piston #8B  
 PLAN/LOCATION  
 SWP-1 Turb Diesel 63

Diesel #102 Piston #88




Notch Side

Overhead view



Side Views, looking out from inside



EDG 103

# AF Pistons

A. MATERIAL		TYPE <i>c/s</i>	FABRICATED FRAGILE	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WOUND
CROSS SECTION THICKNESS	MAX — INCH	MIN — INCH	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND	<input type="checkbox"/> OTHER
		GEOMETRY	<input type="checkbox"/> PIPE	<input type="checkbox"/> PLATE	<input type="checkbox"/> ROD	<input checked="" type="checkbox"/> OTHER <i>Piston Skirt</i>

<i>61+62</i>	TEMP <i>69°F</i>	<i>367</i>	<i>Supp 2</i>
INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.

1. PRE-CLEANER	↓ magnaflox	<i>SKC-NF/2C7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7DC73</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/2C7B</i>	<i>92J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAILS: USE OTHER SIDE IF NECESSARY

*Examined machined area around boss*

*103 Diesel  
Piston #2C*

C. EVALUATION

REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED, USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENTS AS NECESSARY)
<i>Bolt Hole</i>	<i>(3) 7/32, 1/16</i>	<i>linear cracks</i>	<i>Reject (LDR Issued)</i>
<i>1 See Sketch</i>	<i>1/8, 3/16, 1/4</i>		
<i>2</i>	<i>3/8</i>		
<i>3</i>	<i>1/4 x 3/16</i>		
<i>4</i>	<i>5/32</i>		
	<i>3/8</i>	<i>rounded</i>	
	<i>1/2</i>	<i>linear</i>	
	<i>3/32</i>	<i>crack</i>	
	<i>5/16</i>	<i>linear</i>	
	<i>3/32, 5/16</i>	<i>cracks</i>	

*Lilco NDE G 2*

*Para 4.2.2*

*E. Haswell / Asst. J. Pink*  
*11/9/93*

E. ATTEST


*Carl Haswell*

*11/9/93*

PISTON SKIRT #2C  
 103 Diesel  
 Piston #2C  
 SUPS-1/16-103  
 11/9/93




# Diesel #103 Piston #20





Notch Side

## Overhead View




Side Views, looking out from inside



A: MATERIAL		TYPE <i>c/s</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED	PT Piston Skirt #1C COMPONENT I.D.
CROSS SECTION THICKNESS		GEOMETRY <input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD <input checked="" type="checkbox"/> OTHER: <i>Piston Skirt</i>		
MAX	MIN	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER	
B. INSPECTION CODE <i>6.1 + 6.2</i>		MAT'L. TEMP. <i>69°F</i>	<i>367</i> Due <i>4/22/84</i>	<i>Supp. 2</i> <i>R43-1143</i>
INSPECTION MATERIALS		BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER		<i>magnaflux</i>	<i>SKC-NF/ZC7B</i>	<i>82J083</i>
2. PENETRANT			<i>SKL-HF/SKL5</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER			<i>SKC-NF/ZC7B</i>	<i>82J083</i>
4. DEVELOPER			<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER			<i>SKC-NF/ZC7B</i>	<i>82J083</i>
SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY <i>Examined machined area around boss</i>				
<i>103 Diesel Piston #1C</i>				
C. EVALUATION		REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.		
LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)	
<i>Bolt Hole</i> <i>1 See sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>	
<i>2</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>	
<i>3</i>	<i>3/16</i>	<i>Linear</i>	<i>Reject (LDR Issued)</i>	
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>	
DEVELOPER	<i>Likonde 6.2</i>		<i>E. Hassell / Asst. J. Cozz...</i>	
CONSOLE	<i>Para 4.2.2</i>		<i>II</i> <i>11/9/83</i>	
E. ATTEST	<i>E. Hassell</i>		<i>II</i>	<i>11/9/83</i>
	RESPONSIBLE CERTIFIED PERSONNEL		LEVEL	DATE

SYSTEM  
IR43\*EDG-103  
PLA. TION  
SVP-1/Hub Dr E1.67


Diesel #103 Piston #1C




Notch Side


Overhead View

3/16" Linear  
 Note: Started as 2 indications that bled into one "distinct" linear indication after 5 min dwell time.



Side Views, looking out from inside





LIQUID PENETRANT EXAMINATION REPORT

A. MATERIAL	TYPE	FABRICATED PROCESS		
	<i>C/S</i>	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX	MIN	SURFACE CONDITION	OTHER
—	—	—	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
INCH	INCH	INCH	<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

COMPONENT I.D. Piston Skirt #1C

B. SERIAL NO. <i>6.1 + 6.2</i>	MAT'L. TEMP. <i>69°F</i>	<i>367</i>	Supp. 2 <i>R43-1143</i>
INSPECTION MATERIALS		DESIGNATION	BATCH NO.

1. PRE-CLEANER	<i>magnaflux</i>	<i>SKC-NF/2C7B</i>	<i>82J083</i>
2. PENETRANT	↓	<i>SKL-HF/SKL5</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/2C7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82P111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C7B</i>	<i>82J083</i>

SYSTEM R43-EDG-103

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY

*Examined machined area around boss*

*103 Diesel Piston #1C*

C. EVALUATION	REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.
---------------	--


LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole</i> <i>See sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>3</i>	<i>3/16</i>	<i>Linear</i>	<i>Reject (LDR Issued)</i>
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>

PLAN. ACTION SWP-1/Temp Dr. E. G. 2

D. APPROVAL	<i>Lilco NDE 6.2</i>	OPERATOR <i>E. Hassell / Asst. J. Cocuzza</i>
	<i>Para 4.2.2</i>	DATE <i>11/9/83</i>

E. ATTEST	<i>E. Hassell</i>	<i>II</i>	<i>11/9/83</i>
	PERSONNEL CERTIFIED PERSONNEL	LEVEL	DATE


Diesel #103 Piston #1C



Notch Side


Overhead View

3/16" Linear  
 Note: Started as 2 indications that bled into one "distinct" linear indication after 5 min dwell time.




1


Side Views, looking out from inside




2



3



4



LIQUID PENETRANT EXAMINATION REPORT

A. MATERIAL		TYPE <i>c/s</i>	FABRICATED PROCESS <input type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> WORKED
CROSS SECTION THICKNESS	MAX — INCH	MIN — INCH	SURFACE CONDITION <input checked="" type="checkbox"/> MACHINED <input type="checkbox"/> GROUND <input type="checkbox"/> AS FABRICATED <input type="checkbox"/> OTHER
GEOMETRY		<input type="checkbox"/> PIPE <input type="checkbox"/> PLATE <input type="checkbox"/> ROD	<input checked="" type="checkbox"/> OTHER: <i>Piston Skirt</i>

Q. PART NO. <i>6.1 + 6.2</i>	MAT'L. TEMP. <i>67°F</i>	<i>367</i>	Supp. 2 <i>R43-1143</i>
INSPECTION MATERIALS		DESIGNATION	BATCH NO.

1. PRE-CLEANER	<i>magnaflux</i>	<i>SKC-NF/3C7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7D073</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/3C7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82P111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/3C7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area around boss* *103 Diesel  
Piston #1C*


C. EVALUATION  
 REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT AS NECESSARY)
<i>Bolt Hole 1 See sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>3</i>	<i>3/16</i>	<i>Linear</i>	<i>Reject (LDR Issued)</i>
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>Likon DE 6.2</i>	<i>Para 4.2.2</i>	<i>OPERATOR E. Hassell / Asst. J. Cochran I. Pink</i>	<i>II 11/9/83</i>

E. ATTEST  
*Earl Hassell*  
 RESPONSIBLE CERTIFIED PERSONNEL      LEVEL *II*      DATE *11/9/83*

COMPONENT I.D. *Piston Skirt #1C*  
 SYSTEM *R43REDG-103*  
 PLANT ACTION *SVPS-1/Temp D/E/63*



Diesel #103 Piston #1C





Notch Side

Overhead View

3/16" Linear  
Note: Started as 2 indications that bled into one "distinct" linear indication after 5 min dwell time.



Side Views, looking out from inside



A. MATERIAL		TYPE <i>C/S</i>	FABRICATED FINISHED	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> MACHINED
CROSS SECTION THICKNESS		MAX —	MIN —	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
				<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER	

ITEM # *61+62* TEMP *69°F* DATE *4/22/84* SUPP # *2*  
 BRAND *Magnaflux* DESIGNATION *SKC-NF/2C7B* BATCH # *R43-1143*

1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/2C7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7DC73</i>
3. FOGGERS AND/OR REMOVER		<i>SKC-NF/2C7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAILS: USE OTHER SIDE IF NECESSARY  
*Examined machined area around boss* *103 Pieces*  
*Piston #3C*

C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL SPACE IS REQUIRED, USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT IF NECESSARY)
<i>Bolt Hole</i>			
<i>1 See Sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>5/32</i>	<i>linear</i>	<i>Reject (LDR Issued)</i>
	<i>5/32</i>	<i>crack</i>	
<i>3</i>	<i>1/8</i>	<i>linear</i>	<i>Reject (LDR Issued)</i>
	<i>3/16, 1/4</i>	<i>Crack</i>	
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>Lilco NDE G 2</i> <i>Para 4.2.2</i>			<i>E. Hassell / Asst. J. Cooney</i> <i>J. Pink</i> <i>II</i> <i>11/9/83</i>

E. ATTEST *Carl Hassell* *II* *11/9/83*


Piston Skirt #3C

R43-1143-103

SUPS-1/11/83 P 11/9/83




Diesel #103 Piston #3c




Notch side

Overhead view



Side Views, looking out from inside



A. MATERIAL		TYPE <i>c/s</i>	FABRICATED FINISHED	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> FORGED
CROSS SECTION THICKNESS	MAX — INCH	MIN — INCH	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND	<input type="checkbox"/> OTHER
		GEOMETRY	<input type="checkbox"/> PIPE	<input type="checkbox"/> PLATE	<input type="checkbox"/> ROD	<input checked="" type="checkbox"/> OTHER <i>Piston SKIRT</i>

1. PART NUMBER	<i>61+62</i>	TEMP	<i>367</i>	Supp 2
INSPECTION MATERIALS	BRAND	DESIGNATION	DATE <i>4/22/84</i> R-31143	

1. PRE-CLEANER	<i>Magnaflux</i>	<i>SKC-NF/2C7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/SKLS</i>	<i>7DC73</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/2C7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAIL: USE OTHER SIDE IF NECESSARY  
*Examined machined area around boss*  
*103 Pieces*  
*Piston #4C*

C. EVALUATION  
 REPORT BELOW THESE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL CRACK INDICATIONS USE OTHER SIDE.


LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENTS NECESSARY)
<i>Bolt Hole</i> <i>1 See sketch</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>2</i>	<i>3/32, 3/16</i>	<i>linear</i>	<i>Reject (LDR Issued)</i>
<i>3</i>	<i>1/4</i>	<i>linear</i>	
<i>4</i>	<i>7/16</i>	<i>Crack</i>	

1. LILCO NDE G 2  
 Para 4.2.2  
 E. Hassell / ASST. J. Pink  
 II 11/9/83

E. ATTEST  
*Earl Hassell*  
 II 11/9/83



PISTON SKIRT #4C  
 SYSTEM  
 IR13-EPG-103  
 SUPS-1/1-4 P  
 R-31143

Diesel #103 Piston #4C





Notch side

Overhead View



Side Views, looking out from inside.



A. MATERIAL		TYPE <i>c/s</i>	FABRICATED <input type="checkbox"/> FORGED <input checked="" type="checkbox"/> WELDED <input checked="" type="checkbox"/> CAST <input type="checkbox"/> MACHINED
CROSS SECTION THICKNESS		MAX — INCH	MIN — INCH
SURFACE CONDITION		<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
		<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

Piston SKIT # 5C

Q. NUMBER <i>G1 + G2</i>	TEMP <i>69°F</i>	367	Supp 2
INSPECTION MATERIALS	BRAND	DESTINATION <i>DAE 4/22/84</i>	BATCH NO. <i>R431143</i>

1. PRE-CLEANER	↓	<i>magnaflux</i>	<i>SKC-NF/ZC7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-NF/SKLS</i>	<i>7DC73</i>	
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/ZC7B</i>	<i>82J083</i>	
4. DEVELOPER		<i>SKD-NF</i>	<i>82D111</i>	
5. POST EXAMINATION CLEANER		<i>SKC-NF/ZC7B</i>	<i>82J083</i>	

SKETCH OR OTHER DETAILS: USE OTHER SIDE IF NECESSARY  
*Examined machined area around boss*

1R13\*EDG-103

*103 Diesel  
Piston #5C*


C. EVALUATION REPORT BELOW THOSE INDICATIONS OBSERVED AND THE RELEVANT INFORMATION REQUIRED. WHERE ADDITIONAL CLARIFICATION IS NECESSARY USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENTS AS NECESSARY)
<i>Bolt Hole</i>			
<i>1 See sketch</i>	<i>1/8, 1/4</i>	<i>Cracks</i>	<i>Reject (LDR Issued)</i>
<i>2</i>	<i>1/16</i>	<i>linear</i>	
	<i>5/16</i>	<i>Cracks</i>	<i>Reject (LDR Issued)</i>
<i>3</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
<i>4</i>	<i>3/16, 1/4</i>	<i>Cracks</i>	<i>Reject (LDR Issued)</i>
	<i>Like NDE G 2</i>		
	<i>Para 4.2.2</i>		

SNP-1/Hub P 4103


E. ATTENT *Carl Howell* *II* *11/9/93*

Diesel #103 Piston # 5c




Notch side

Overhead view



Side Views, looking out from inside



A. MATERIAL		TYPE <i>c/s</i>	FABRICATED FINISHED	<input type="checkbox"/> WELDED	<input checked="" type="checkbox"/> CAST	<input type="checkbox"/> FORGED
CROSS SECTION THICKNESS		MAX — INCH	MIN — INCH	SURFACE CONDITION	<input checked="" type="checkbox"/> MACHINED	<input type="checkbox"/> GROUND
					<input type="checkbox"/> AS FABRICATED	<input type="checkbox"/> OTHER

*G1+G2*      *TEMP 67°F*      *367*      *Supp 2*  
*DATE 4/22/84*      *R43-1143*

INSPECTION MATERIALS	BRAND	DESIGNATION	BATCH NO.
1. PRE-CLEANER	<i>magnaflux</i>	<i>SKC-NF/2C7B</i>	<i>82J083</i>
2. PENETRANT		<i>SKL-HF/3KL5</i>	<i>7DC73</i>
3. EMULSIFIER AND/OR REMOVER		<i>SKC-NF/2C7B</i>	<i>82J083</i>
4. DEVELOPER		<i>SKD-NF</i>	<i>32D111</i>
5. POST EXAMINATION CLEANER		<i>SKC-NF/2C7B</i>	<i>82J083</i>

SKETCH OR OTHER DETAILS: USE OTHER SIDE IF NECESSARY  
*Examined machined area around boss*      *103 Pieces*  
*Piston #6C*


C. EVALUATION      REPORT BELOW THOSE INDICATIONS OBSERVED AND THE PERTINENT INFORMATION REQUIRED. WHERE ADDITIONAL CLARIFICATION IS NECESSARY, USE OTHER SIDE.

LOCATION	SIZE (INCHES)	DESCRIPTION	ACTION (ACCEPT/REJECT, AND COMMENT IF NECESSARY)
<i>Bolt Hole</i>	<i>1/8, 3/16</i>	<i>linears</i>	<i>Reject (LDR Issued)</i>
<i>1 See Sketch</i>	<i>3/8</i>	<i>Crack</i>	
<i>2</i>	<i>3/32</i>	<i>linear</i>	
<i>3</i>	<i>3/8</i>	<i>Crack</i>	
<i>4</i>	<i>N/A</i>	<i>None</i>	<i>Accept</i>
	<i>Like NDE G2</i>		<i>E. Hassell / Asst. J. Colwell</i> <i>J. Pink</i>
	<i>Para 4.2.2</i>		<i>II</i> <i>11/9/83</i>

E. ATTEST      *Carl Hassell*      *II*      *11/9/83*


PISTON SKIRT #6C  
 IR43REDG-103  
 SUPP-1/10-84 DR E103

Diesel #103 Piston # 66



Notch Side

Overhead View



1

$\frac{1}{8}$ " linear


$\frac{3}{16}$ " linear

$\frac{3}{8}$ " crack

2


$\frac{3}{32}$ " linear

Side Views, looking out from inside



3

$\frac{3}{8}$ " crack



4

$\frac{3}{32}$ " linear

**MINIMUM AND MAXIMUM STRESSES IN AE PISTON  
 SKIRT FOR VARIOUS PEAK FIRING PRESSURES  
 FOR ISOTHERMAL AND STEADY-STATE  
 OPERATING CONDITIONS**

(initial gap equals 0.007 inch, uses "nominal" stiffnesses)

peak firing pressure, psig	isothermal		steady-state	
	$\sigma_{min}$ ksi	$\sigma_{max}$ ksi	$\sigma_{min}$ ksi	$\sigma_{max}$ ksi
1670	-59.7	1.77	-42.7	7.74
2000	-69.4	1.77	-52.3	7.74
2200	-75.1	1.77	-58.1	7.74



- STRESS RATIO, R (dimensionless)
- △ THRESHOLD STRESS INTENSITY FACTOR RANGE,  $\Delta K_{TH}$  (ksi $\sqrt{in}$ )
- STRESS INTENSITY FACTOR RANGE,  $\Delta K$  (ksi $\sqrt{in}$ )

