



ENTERGY

Entergy Operations, Inc.
P.O. Box 756
Port Jackson, MS 39150
Tel: 601 437 6408

W. T. Cottle
Vice President
Operations
Grand Gulf Nuclear Station

April 30, 1992

U.S. Nuclear Regulatory Commission
Mail Station P1-137
Washington, D.C. 20555

Attention: Document Control Desk

Subject: Grand Gulf Nuclear Station
Unit 1
Docket No. 50-416
License No. NPP-29
Resolution of High Groundwater Levels

GNRO-92/00046

Gentlemen:

Grand Gulf Nuclear Station (GGNS) has monitoring and dewatering wells located around the power block and the Standby Service Water Basins. The purpose of the wells is to monitor and dewater the perched aquifer which underlies the power block. GGNS has experienced incidents where groundwater levels in excess of the current design basis value of 109.0 feet Mean Sea Level (MSL) have been reported.

On December 21, 1990 Entergy Operations, Inc. provided a status report on the efforts by GGNS to resolve the groundwater level issues at the site (reference: GNRO-90/00006, dated December 21, 1990). GGNS also committed to provide resolution of the groundwater issue by April 30, 1992.

The attached report summarizes the outstanding issues as they relate to the determination of groundwater exceedance problems at the GGNS; development of a post-construction groundwater level contour map; determination of the maximum expected post-construction groundwater level within the power block area; and actions that will be taken to resolve the high groundwater level problems at the site. Also, Appendix 1 to the attached report is provided in response to your August 6, 1990 "Request for Additional Information: Groundwater Level Control".

G9204232/SNLICFJE - 1
9205050004 920430
PDR ADOCK 05000416
P PDR

*Pool
11*

April 30, 1992
GNRO-92/00046
Page 2 of 3

Energy Operations feels that every effort has been made to ensure issues associated with groundwater have been adequately and effectively addressed. Following completion of the activities delineated in the attached, no further actions will be required to maintain the design basis groundwater level due to recharge from natural sources at the GGNS.

Yours truly,

W. S. C. C. C.

WTC/JS/mtc
attachment:
cc:

Mr. D. C. Hintz (w/a)
Mr. J. L. Mathis (w/a)
Mr. R. B. McGehee (w/a)
Mr. N. S. Reynolds (w/a)
Mr. H. L. Thomas (w/o)

Mr. Stewart D. Ebueter (w/a)
Regional Administrator
U.S. Nuclear Regulatory Commission
Region 11
101 Marietta St., N.W., Suite 2900
Atlanta, Georgia 30323

Mr. P. W. O'Connor, Project Manager (w/2)
Office of Nuclear Reactor Regulation
U.S. Nuclear Regulatory Commission
Mail Stop 13H3
Washington, D.C. 20555

CERTIFICATION DOR FOR GNRO-92/00046

<u>GNRO Section</u>	<u>Organization Responsibility</u>
Cover Letter (all)	NS&RA
Final Report	
Section 1	NPE-Civil
Section 2	"
Section 3	"
Section 4	"
Section 5	"
Section 6	"
Section 7	"
Section 8	"
Section 9	"
Appendix 1, Question #1	"
Appendix 1, Question #2	"
Appendix 1, Question #3	NS&RA

CONCURRENCE REVIEW FORM

SECTION I

GNRO-92/00046 Rev. 0

RESPONSE DUE: 04/30/92
(NRC Required or Target)

SUBJECT: Resolution of High Groundwater Levels

J. Summers

NRC Document Preparer

Date

R. L. Patterson

Responsible Section
Manager/Supintendent

Date

Commitment Concurrence

SECTION II

Locations	Commitment	Responsible Organization Primary/Secondary	Due Date
Section VII.4, Para 3, Sen. 3	A visual inspection of the cooling tower will be performed ... to identify potential leakage paths that may exist	NPE-Civil	Each Refueling Outage
Section IX, Para 5, Sen. 2 & 3	The DGWL will be raised ... A UFSAR change will be submitted to reflect this change ...	NPE-Civil	06/93 12/93
Section IX, Para 5, Sen. 4	Studies and assessment will be incorporated into plant calculations	NPE-Civil	12/92
Section IX, Para 5, Sen. 5	Cooling tower leakage will be repaired during RF05	NPE-Civil	End of RF05
Section IX, Para 5, Sen. 6	Groundwater levels will be monitored in the future until sufficient data is available ...	NPE-Civil	10/31/92

This letter contains commitments requiring procedural implementation
YES () NO (X)