

NUCLEAR REGULATORY COMMISSION

May 1, 1992

Docket Nos.: 50-254 and 50-265

> Commonwealth Edison Company ATTN: Mr. Cordell Reed Senior Vice President 1400 Opus Place - Suite 300 Downers Grove, Illinois 60515

Dear Mr. Reed:

SUBJECT: SERVICE WATER SYSTEM OPERATIONAL PERFORMANCE INSPECTION (50-254/92-201; 50-265/92-201)

I have enclosed the report of the service water system operational performance inspection (SWSOPI) conducted by the Special Inspection Branch of the U.S. Nuclear Regulatory Commission (NRC) from March 2 through 20, 1992. At the exit meeting on March 20, 1992, the inspection team discussed its findings with you and members of your staff.

The inspection team assessed the operational performance of the service water system (SWS). In particular, the team reviewed in detail the design, maintenance, operation, surveillance and testing of the SWS. The team also assessed the planned or completed actions for Quad Cities in response to Generic Letter 89-13, "Service Water System Problems Affecting Safety-Related Equipment," issued on July 18, 1989.

The team found that there was a reduced margin of safety for the diesel generator cooling water (DGCW) system. Based on existing data, your staff could not conclusively demonstrate that the Unit 1 and the shared (1/2) DGCW pumps were capable of performing their required safety function in the existing Unit 1 flow configuration. At the time of the inspection, we believed that the system would meet its operability requirements based on seasonally low river water temperature and high river water level. However, you did not provide calculations that assure system operability over the entire range of river water seasonal temperatures and levels. Several other items require prompt attention: completion of heat load calculations for the RHRSW/DGCW vaults and applicable ECCS pump rooms; environmental qualification of the RHR heat exchanger discharge valves; requalification of equipment to 120°F in applicable areas and verification of cooling water pump capability to deliver sustained high flows. Please inform us when each of these items will be complete and available for inspection.

The team determined that the lack of adequately staffed and experienced technical departments resulted in insufficient technical support. This contributed to significant weaknesses in your ability to identify, evaluate and correct potential safety issues. Some examples were reduced flow to

DO

Your implementation of the Generic Letter (GL) 89-13 actions was not fully satisfactory. While several of your initiatives such as development of an implementation plan and completion of a design review report were positive, significant work is needed in response to required actions of the GL, particularly for Actions III and IV.

With regard to the service water system, the team noted strengths in operations and maintenance and the training programs for both areas.

The deficiencies described in the enclosed inspection report will be reviewed by the Region III office for possible enforcement action. In accordance with 10 CFR 2.790 of the Commission's regulations, a copy of this letter and its enclosures will be placed in the MRC Public Document Room.

No response is required for this letter. Should you have any questions concerning this inspection, we will be pleased to discuss them with you. Contact the Team Leader. Peter Koltay, or me at (301) 504-2977 or (301) 504-1354, respectively.

Sincerely,

Bruce A. Böger, Director

Division of Reactor Projects, III/IV/V Office of Nuclear Reactor Regulation

Enclosure: Inspection Report 50-254/92-201; 50-265/92-201

cc w/encl.: See next page

cc:

Mr. Stephen E. Shelton Vice President Iowa-Illinois Gas and Electric Company P. O. Box 4350 Davenport, Iowa 52808

Michael I. Miller, Esquire Sidley and Austin One First National Plaza Chicago, Illinois 60690

Mr. Richard Bax Station Manager Quad Cities Nuclear Power Station 22710 206th Avenue North Cordova, Illinois 61242

Resident Inspector
U. S. Nuclear Regulatory Commission
22712 206th Avenue North
Cordova, Illinois 61242

Chairman
Rock Island County Board
of Supervisors
1504 3rd Avenue
Rock Island County Office Bldg.
Rock Island, Illinois 61201

Illinois Department of Nuclear Safety Office of Nuclear Facility Safety 1035 Outer Park Drive Springfield, Illinois 62704

Regional Administrator, Region III U. S. Nuclear Regulatory Commission 799 Roosevelt Road, Bldg. #4 Glen Ellyn, Illinois 60137

Robert Neumann Office of Public Counsel State of Illinois Center 100 W. Randolph Suite 11-300 Chicago, Illinois 60601 Unit 1 emergency core cooling system pump rooms; partial flow blockage in residual heat removal (RHR) heat exchanger room coolers; single-failure vulnerability due to check va've failing to close; and reliance on non-environmentall; qualified valves to control RHR heat exchanger flow. Weaknesses in technical support were also evident in the poor quality of engineering documents (such as calculations), and inadequate evaluation of the results of contractor generated documents and self-assessment reports.

Your implementation of the Generic Letter (GL) 89-13 actions was not fully satisfactory. While several of your initiatives such as development of an implementation plan and completion of a design review report were positive, significant work is needed in response to required actions of the GL, particularly for Actions III and IV.

With regard to the service water system, the team noted strengths in operations and maintenance and the training programs for both areas.

The deficiencies described in the enclosed inspection report will be reviewed by the Region III office for possible enforcement action. In accordance with 10 CFR 2.790 of the Commission's regulations, a copy of this letter and its enclosures will be placed in the NRC Public Document Room.

No response is required for this letter. Should you have any questions concerning this inspection, we will be pleased to discuss them with you. Contact the Team Leader, Peter Koltay, or me at (301) 504-2977 or (301) 504-1354 respectively.

Sincerely,

ORIGINAL SIGNED BY

Bruce A. Boger, Director Division of Reactor Projects, III/IV/V Office of Nuclear Reactor Regulation

Enclosure: Inspection Report 50-254/92-201; 50-265/92-201

cc w/encl.: See next page

Distribution: See page 4

SEE PREVIOUS CONCURRENCE RSIB:DRIS SC:RSIB:DRIS PSKoltay:jb DPNorkin 04/30/92 04/28/92

EVImbro 04/29/92

C:RSIB:DRIS*

D:DRIS:NRR* BKGrimes 04/30/92

DRPM ARR RJBarrett 047 /92 SPLB:NRR JETatum 04/3°/92

SPLB:NRR SJones 04/3°/92 CPhillips 04/30/92

RIII or ADun Pap 04/30/92 [quad.rpt] D:DRPW:NRR BABoger 04/ /92 Unit 1 emergency core cooling system pump rooms; partial flow blockage in residual heat removal (RHR) heat exchanger room coolers; single-failure vulnerability due to check valve failing to close; and reliance on non-environmentally qualified valves to control RHR heat exchanger flow. Weaknesses in technical support were also evident in the poor quality of engineering documents (such as calculations), and inadequate evaluation of the results of contractor generated documents and self-assessment reports.

Your implementation of the Generic Letter (GL) 89-13 actions was not fully satisfactory. While several of your initiatives such as development of an implementation plan and completion of a design review report were positive, significant work is needed in response to required actions of the GL, particularly for Actions III and IV.

With regards to the service water system, the team noted strengths in operations and maintenance and the training programs for both areas.

The efficiencies described in the enclosed inspection report will be reviewed by the Region III office for possible enforcement action. In accordance with 10 CFR 2.790 of the Commission's regulations, a copy of this letter and its enclosures will be placed in the NRC Public Document Room.

No response is required for this letter. Should you have any questions concerning this inspection, we will be pleased to discuss them with you. Contact the Team Leader, Peter Koltay or me at (301) 504-2977 or (301) 504-1354 respectively.

Sincerely,

Bruce A. Boger, Director Division of Reactor Projects, III/IV/V Office of Nuclear Reactor Regulation

Enclosure: Inspection Report 50-254/92-XXX; 50-265/92-XXX

cc w/encl.: See next page

Distribution: See page 4

RSIB:DRIS PSKoltay:jb 04/70/92

SC:RSIB:DRIS
DPNorkin
04/5/92

EVImbro 047-6/92 D: DRIS: NRR BKGrimes 04/20/92

SPLB:NRR JETatum 04/ /92 SPLB:NRR SJones 04/ /92

RIII CPhillips 04/ /92 RIII ADunlap 04/32/92

D:DRPW:NR BABoger 04/ /92 [quad.rpt]

Distribution: Docket Files 50-254; 50-265 RSIB R/F DRIS R/F TEMurley, NRR
FJMiraglia, NRR
WTRussell, NRR
JGPartlow, NRR
BKGrimes, NRR
EVImbro, NRR DPNorkin, NRR PSKoltay, NRR RLSpessard, AEOD BABoger, NRR RJBarrett, NRR LNOIshan, NRR ALMoore, NRR Sr. Resident Inspector Regional Administrators Regional Division Directors Inspection Team LPDR PDR ACRS (3) OCG (3) 15 Distribution