

November 15, 1984

DOCKETED
USNRC

UNITED STATES OF AMERICA
NUCLEAR REGULATORY COMMISSION

'84 NOV 16 A10:37

BEFORE THE ATOMIC SAFETY AND LICENSING BOARD

OFFICE OF SECRETARY
DOCKETING & SERVICE
BRANCH

| | | |
|-------------------------------|---|----------------------|
| In the Matter of |) | |
| |) | |
| TEXAS UTILITIES GENERATING |) | Docket Nos. 50-445-2 |
| COMPANY, et al. |) | 50-446-2 |
| |) | |
| (Comanche Peak Steam Electric |) | |
| Station, Units 1 and 2) |) | |

CASE'S FURTHER EVIDENCE OF A QUALITY CONTROL
BREAKDOWN IN THE CONSTRUCTION, INSTALLATION
AND INSPECTION OF THE STAINLESS STEEL LINER PLATE

On September 27, 1984 CASE filed a brief delineating specific quality control/quality assurance problems which it had identified through review and analysis of documentation provided during the operating license hearings on harassment and intimidation. (CASE's Evidence of a Quality Control Breakdown)

Due to the unexcused lateness of the Applicants' response to this CASE filing, CASE requested and was granted the opportunity to supplement its initial brief outlining the QC problems it had identified. It does so with this filing.

Subsequent to the September 27th filing CASE completed a more thorough document review and analysis of the regulations and industry codes and standards applicable to the stainless steel liner plate. The result of that review is attached as Exhibit 1 to this filing. This attachment delineates the breakdown of procedures regarding the stainless steel liner plates installation and inspection.

8411190454 841115
PDR ADOCK 05000445
G PDR

DS03

Additionally, CASE asserts that Applicant continues to mischaracterize the major issue regarding the liner plate construction, installation, and inspection.

The stainless steel liner plate was constructed, installed and inspected as an ASME (safety-related) function prior to being turned over to the non-ASME side, therefore Applicants improperly assert (apparently with the Nuclear Regulatory Commission Staff's approval) that there is no safety significance to the problems identified during construction, installation and inspection of the liner plate.

This characterization is not correct. (See NUREG-0404, Vol. 2; General Design Criteria 1, "Quality Standards and Records" of Appendix A to 10 C.F.R. 50; Reg. Guide 1.25, Reg. Guide 1.26; Reg. Guide 1.29; Reg. Guide 1.13 General Design Criteria 61; ANSI/ASME N45.2-1977, Section 2; Section 7, Section 9, Section 11; CP-QAP-11.1, Rev. 0, 1, 2, 3 and 4 Paragraphs 2.2 and 3.1)

Additionally, the Applicants' assertion that the wrong traveller was consistently used in the construction, installation and inspection of the stainless steel liners is untrue.

Exhibit 2 to this brief was obtained by CASE through its independent investigation of this matter, not through discovery in this case.

The exhibit is proof that at least in one instance the proper form, as required by CP-QAP-11.1 was used for inspection purposes. It is clear from a review of the liner plate package number 988 that the "old form" identifies the first four hold points as they were initially completed, and the "new form"


incorporates those inspections by reference to pages 2 and 3 of the traveller.

Either Mr. Brandt's testimony of September 13, 1984 was erroneous because Mr. Brandt does not know what really happened during the construction, inspection, and installation of the liner plates. Or Mr. Brandt does know what happened and has failed to disclose to the Board the location, and existence or non-existence of the rest of the proper forms. (Hearing transcript, pp. 16,047-16,052)

Conclusion

Applicant may be either ignorant or knowingly deceptive about certain irregularities regarding the stainless steel liner plate. Their inability or unwillingness to produce adequate, plausible explanations for the quality control breakdown of the stainless steel liner plates indicates to CASE that our worst fears are correct -- the condition of the entire structure is hopelessly indeterminate.

Respectfully submitted,



ANTHONY S. ROISMAN
Trial Lawyers for Public Justice, PC
2000 P Street, N.W., Suite 611
(202) 463-8600

Counsel for CASE

November 15, 1984

UNITED STATES OF AMERICA
NUCLEAR REGULATORY COMMISSION

BEFORE THE ATOMIC SAFETY AND LICENSING BOARD

In the Matter of)
)
TEXAS UTILITIES GENERATING)
COMPANY, et al.) Docket Nos. 50-445-2
) and 50-446-2
(Comanche Peak Steam Electric)
Station, Units 1 and 2))

CERTIFICATE OF SERVICE

By my signature below, I hereby certify that true and correct copies of CASE's Further Evidence of a Quality Control Breakdown in the Construction, Installation and Inspection of the Stainless Steel Liner Plate have been sent to the names listed below this 15th day of November, 1984, by: Express mail where indicated by *; Hand-delivery where indicated by **; and First Class Mail unless otherwise indicated.

Administrative Judge Peter B. Bloch
U.S. Nuclear Regulatory Commission
4350 East-West Highway, 4th Floor
Bethesda, Maryland 20814

Herbert Grossman
Alternate Chairman
ASLB Panel
U.S. Nuclear Regulatory Commission
4350 East-West Highway, 4th Floor
Bethesda, Maryland 20814

Dr. Kenneth A. McCollom, Dean
Division of Engineering, Architecture
and Technology
Oklahoma State University
Stillwater, Oklahoma 74074

Dr. Walter H. Jordan
881 W. Outer Drive
Oak Ridge, Tennessee 37830

Ms. Ellen Ginsberg, Law Clerk
U.S. Nuclear Regulatory Commission
4350 East/West Highway, 4th Floor
Bethesda, Maryland 20814

Nicholas S. Reynolds, Esquire
Bishop, Liberman, Cook,
Purcell & Reynolds
1200 17th Street, N.W.
Washington, D.C. 20036

Stuart Treby, Esquire
Geary S. Mizuno, Esquire
Office of Executive Legal Director
U.S. Nuclear Regulatory Commission
7735 Old Georgetown Rd., 10th Floor
Bethesda, Maryland 20814

Docketing & Service Section
Office of the Secretary
U.S. Nuclear Regulatory Commission
Washington, D.C. 20555

Renea Hicks, Esquire
Assistant Attorney General
Environmental Protection Division
Supreme Court Building
Austin, Texas 78711

Mrs. Juanita Ellis
President, CASE
1426 S. Polk
Dallas, Texas 75224

Anthony B. Roisman
ANTHONY B. ROISMAN

RA

ANALYSIS OF LINER PLATE DOCUMENTATION

INDEX

| | PAGE |
|--|---------|
| PART I: <u>MISSING HOLD POINT 1</u> : Fit-up/Cleanliness Of Backside (Concrete Side) Welds | |
| Governing Codes and Standards that were violated | 1 |
| NDT chits insufficient to show QC verification of Step 1 | 2 |
| Date and Signature on NDT chit used to verify step 1 is the same date and signature shown on traveler for Step 3 and/or 2 that are signed off, but step 1 is blank | 3 |
| Additional welds that lack QC verification for Step 1 | 3 |
| Step 3 and/or 2 signed off prior to date shown on chit produced to show verification of step 1 | 4 |
| WFML's referenced on NDT chit used to show verification of step 1 for Embed to Plate, is not the welding procedure required for Embed to Plate. | 5 |
| | |
| PART II: <u>MISSING HOLD POINT 5</u> : Fit-up/Cleanliness Of Inside (Waterside) Welds | |
| 184 welds that lack QC verification for Step 5 | 6 |
| NCR's written against 48 welds that lack QC verification for fit-up and cleanliness of inside (waterside) welds. | 6 |
| | |
| PART III: <u>MISSING HOLD POINT 5</u> : Final V.T. Of Inside Weld | |
| Welding performed that lacks QC verification of Step 7 | 7 - 8 |
| | |
| PART IV: <u>NO QC VERIFICATION FOR WELDS PERFORMED</u> | |
| WFML's referenced on package - No QC verification | 9 - 15 |
| WFML's attached to traveler showing welds performed, but does not have QC verification for re-welding | 16 - 20 |

INDEX

PAGE

PART V: INCOMPLETE WELDS SIGNED OFF AS COMPLETED

| | |
|--|----|
| NCR's written against welds signed off by James Cole on which he had N/A'd the vacuum box test | 21 |
| Failure to perform vacuum box and/or P.T. test | 22 |
| 1. P.T. and vacuum box test not performed | 23 |
| 2. No NDE report, no PT, and no vacuum box | 23 |
| 3. James Cole N/A'ed vacuum box test - | 24 |
| 4. PT test performed but no vacuum box test | 24 |

PART VI: NON CONFORMING CONDITIONS DISPOSITIONED BY NCR's

| | |
|--|----|
| Welds signed off by James that had major defects | 25 |
| Major weld defects not detected by QC inspector | 25 |
| Steps 2, 3, and 4 N/A'ed and insufficient documentation | 26 |
| Lack of QC verification for fit-up/cleanliness of inside (waterside) welds | 26 |
| Backing bar not installed but was accepted by QC | 26 |
| Welding performed without QC inspection | 27 |
| P.T. reports filled out using wrong procedure number | 28 |

PART I: MISSING HOLD POINTS:

Mandatory hold points that lack QC verification prior to completion of subsequent activities being performed violate the following Codes and Regulations:

10CFR50 Appendix B:

Criteria II: States in part that activities affecting quality are to be accomplished under suitable environmental conditions for accomplishing the activity; which includes adequate Cleanliness; and assurance that all prerequisites for the given activity have been satisfied. The program shall take into account the need for special controls, which includes the need for verification of quality by inspection and test.

Criteria V: States that Instructions, Procedures, and Drawings shall include appropriate quantitative or acceptance criteria for determining that important activities have been satisfactorily accomplished.

ANSI/ASME N45.2-1977

Section 2: Requires that the Quality Assurance Program shall provide assurance that activities affecting quality are documented and accomplished in accordance with written instructions and procedures. The program is required to assure that prerequisites for the given activities have been satisfied, and the program shall take into account the need for the verification of quality by inspection, examination or test.

Section 11: Requires that work shall not proceed beyond mandatory hold points, and work shall not proceed without the consent of the designated representative before work continues.

STEP 1: Fit-up and Cleanliness of Channel Side (Concrete Side) Welds

A large number of welds lack QC verification of the required fit-up and cleanliness of backside (concrete side) welds. The failure to perform this function leaves the quality of these welds indeterminate. The S/S Liner has been installed and it is now impossible to re-examine or test these welds to determine their acceptability.

NDT chits have been produced in an effort to show the fit-up/cleanliness was performed, but there are facts that indicate the use of the chits is not sufficient to show this step was performed, since they may have been intended for verification of other steps signed off on the traveler.

1. Many of the NDT chits produced to verify that step 1 was performed have the same date and signature that was signed off on the traveler to verify the performance of step 3 and/or 2. If all these steps had been verified the same day by the same QC inspector they would all have been signed off on the traveler at the same time, but step 1 was left blank. It cannot be assumed that the chits included the verification of step 1 since the inspector did not sign that step off on the traveler.

a. There was no reference on the NDT chit showing what step was being signed off when Sue Ann Neumeyer was ordered to use the chit to sign off the missing hold point on the traveler.

b. The note "first fit-up and cleanliness" is in the handwriting of two people, it was not put on the chit by the inspector or the person who filled out the other information on the chit. The note was added to the chit when it was discovered that step 1 lacked QC verification and may not have been performed.

2. Although the travelers reference the WMR numbers on these chits as being for the fit-up and cleanliness it doesn't mean they were intended for that purpose. Travelers 398 thru 543 have steps signed off by the QC inspector but the information side of the traveler is blank. This is sufficient to show the WMR No., Welder Symbol, Weld Procedure, and Hold Points are not always filled in when the inspector signs the traveler, and may not have been filled in until the chits were added to it.

Step 1: Fit-up and Cleanliness of Channel Side (Concrete Side) Welds

The following welds lack QC verification of the fit-up and Cleanliness of backside (concrete side) welds. The Stainless Steel Liner has been installed. The welds cannot be re-inspected or tested to determine if they are acceptable. The condition of these welds are indeterminate.

1. Welds that have the same date and QC signature for step 3 and/or 2 that is shown on the NDT chit that was produced to show QC verification of step 1. It is evident the chits were not intended to verify step 1, weld but was intended to verify Step 3 and/or 2 only.

| | | | | | | | | | | | | | | |
|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 4 | 9 | 12 | 14 | 16 | 17 | 21 | 23 | 24 | 28 | 29 | 32 | 33 | 36 | 38 |
| 39 | 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 49 | 51 | 53 | 54 | 56 | 57 |
| 59 | 60 | 63 | 65 | 66 | 67 | 68 | 69 | 70 | 72 | 73 | 74 | 75 | 77 | 78 |
| 82 | 84 | 85 | 87 | 89 | 91 | 92 | 93 | 95 | 96 | 99 | 100 | 107 | 108 | 109 |
| 111 | 112 | 113 | 114 | 124 | 125 | 127 | 129 | 130 | 131 | 132 | 134 | 135 | 136 | 138 |
| 140 | 141 | 143 | 153 | 162 | 170 | 175 | 180 | 185 | 187 | 188 | 191 | 192 | 194 | 196 |
| 197 | 198 | 199 | 200 | 202 | 203 | 208 | 212 | 213 | 218 | 222 | 225 | 230 | 232 | 236 |
| 237 | 250 | 252 | 266 | 267 | 268 | 269 | 271 | 280 | 284 | 291 | 293 | 294 | 295 | 296 |
| 297 | 298 | 301 | 302 | 307 | 313 | 318 | 319 | 323 | 324 | 330 | 331 | 340 | 341 | 349 |
| 351 | 661 | 662 | 663 | 664 | 686 | 689 | 696 | 697 | 709 | 720 | | | | |

total 147

2. The following welds also lack QC verification for step 1:
weld

| | | | | | | | | | | | | | | |
|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 1A | 3 | 6 | 10 | 11 | 13 | 15 | 19 | 20 | 22 | 25 | 26 | 27 | 30 | 31 |
| 34 | 35 | 37 | 48 | 61 | 62 | 71 | 80 | 86 | 88 | 101 | 102 | 103 | 104 | 105 |
| 110 | 115 | 116 | 117 | 118 | 119 | 120 | 121 | 122 | 126 | 142 | 144 | 146 | 147 | 150 |
| 151 | 152 | 154 | 156 | 158 | 160 | 163 | 164 | 165 | 167 | 168 | 169 | 171 | 172 | 173 |
| 174 | 176 | 177 | 178 | 179 | 181 | 182 | 183 | 184 | 186 | 190 | 193 | 195 | 201 | 206 |
| 210 | 211 | 214 | 215 | 216 | 217 | 219 | 220 | 223 | 224 | 227 | 228 | 229 | 229 | 231 |
| 234 | 240 | 242 | 244 | 246 | 248 | 251 | 253 | 256 | 257 | 259 | 261 | 263 | 264 | 265 |
| 270 | 273 | 275 | 276 | 278 | 279 | 281 | 282 | 285 | 286 | 287 | 288 | 289 | 290 | 292 |
| 300 | 303 | 305 | 306 | 308 | 309 | 310 | 312 | 314 | 315 | 316 | 317 | 320 | 321 | 322 |
| 325 | 326 | 328 | 329 | 333 | 334 | 335 | 336 | 337 | 338 | 339 | 342 | 352 | 660 | 687 |
| 688 | 691 | 694 | 695 | 698 | 699 | 700 | 701 | 702 | 710 | 711 | 729 | 842 | 851 | 852 |
| 854 | 855 | 856 | 857 | 858 | | | | | | | | | | |

total 170

QC verification of fit-up/cleanliness for channel side (concrete side) welds was not performed on the following welds prior to welding, which makes the condition of the welds indeterminate. This was a violation of procedure and 10CFR50 Appendix B Criteria V.

Weld

- 26 Step 2: V.T. of backing strip tack/fillet welds
Signed off by S.M. McCoy on 9/8/78
- Step 3: Cleanliness of channel, liner, and backing strip
Signed off by S. M. McCoy on 9/8/78
- Step 1: Fit-up and Cleanliness of plate to plate
NDT Chit produced to show QC verification of this step was signed off by S.M. McCoy on 10/13/78 after Steps 2 and 3 were completed.
- 88 Step 2: V.T. of backing strip tack/fillet welds
Signed off by S.M. McCoy on 8/30/78
- Step 1: Fit-up and Cleanliness of plate to plate
NDT Chit produced to show QC verification of this step was signed off by S.M. McCoy on 9/5/78 after Step 2 had been completed.
- 146 Step 2: V.T. of backing strip tack/fillet welds
Signed off by Larry Wilkerson on 8/11/78
- Step 3: Cleanliness of channel, liner, and backing strip
Signed off by Larry Wilkerson on 8/11/78
- Step 1: Fit-up and Cleanliness of plate to plate
NDT Chit produced to show QC verification of this step was signed off by Larry Wilkerson on 8/14/78 after Step 2 and 3 were completed.
- 195 Step 2: V.T. of backing strip tack/fillet welds
Signed off by S.M. McCoy on 9/27/78
- Step 1: Fit-up and Cleanliness of Embed to Plate
NDT Chit produced to show QC verification of this step was signed off by S.M. McCoy on 9/28/78 after step 2 had been completed.
- 196 Step 2: V.T. of backing strip tack/fillet welds
Signed of by Larry Wilkerson on 9/27/78
- Step 1: Fit-up and Cleanliness of Embed to Plate
NDT Chit produced to show QC verification of this step was signed off by Larry Wilkerson on 9/28/78 after step 2 had been completed

NDT chits produced for Step one reference wrong procedure for Embed to Plate

Fit-up and Cleanliness for Embed to Plate:

The correct welding procedure used for Embed to Plate is 88025. The following welds were done using the wrong welding procedure, or the NDT Chits used to verify Step 1 (Fit-up/Cleanliness) of Embed to plate are not the Chits signed off for that step of the welding operation.

Welds:

| | | | | | | | |
|----|-----|-----|-----|-----|-----|-----|-----|
| 20 | 100 | 216 | 291 | 699 | 740 | 755 | 786 |
| 24 | 120 | 217 | 295 | 700 | 741 | 756 | 800 |
| 32 | 124 | 218 | 298 | 706 | 742 | 757 | 822 |
| 33 | 125 | 219 | 314 | 710 | 743 | 759 | 884 |
| 51 | 127 | 220 | 317 | 711 | 744 | 761 | 885 |
| 53 | 129 | 251 | 319 | 722 | 746 | 762 | 880 |
| 59 | 131 | 266 | 321 | 723 | 747 | 766 | 886 |
| 66 | 132 | 275 | 328 | 724 | 748 | 773 | 888 |
| 67 | 196 | 276 | 330 | 725 | 749 | 775 | 889 |
| 68 | 200 | 277 | 333 | 735 | 750 | 776 | 890 |
| 69 | 206 | 278 | 337 | 736 | 751 | 780 | 891 |
| 72 | 209 | 279 | 342 | 737 | 752 | 783 | 892 |
| 73 | 210 | 283 | 352 | 738 | 753 | 784 | 897 |
| 74 | 211 | 287 | 698 | 739 | 754 | 785 | |

The above welds were done using welding procedure 88023.

PART III:MISSING HOLD POINT 7: Final V.T. Of Inside Weld

Welding has been done but lacks QC verification for welds completed

| Weld | Date | Welder | WFML | Rods | Weld | Date | Welder | WFML | Rods | |
|------|-------------------|--------|--------|--------|------|-------------------|---------|--------|--------|---|
| | | Symbol | Number | Burned | | | Symbol | Number | Burned | |
| 544 | 5/14/81 | FF AEO | A-007 | 1 | 554 | 5/14/81 | FF AEO | A-007 | 1 | |
| | 5/18/81 | AEO | A-012 | 4 | | 5/18/81 | AEO | A-012 | 4 | |
| | 5/18/81 | AYZ | A-013 | 4 | | 5/26/81 | AEO | A-036 | 6 | |
| | 5/19/81 | AEO | A-019 | 4 | | 5/26/81 | BEN | A-037 | 8 | |
| | 5/19/81 | BEN | A-020 | 6 | | Total Rods Burned | | | 19 | |
| | 5/21/81 | AEO | A-032 | 5 | | 555 | 5/14/81 | FF AEO | A-007 | 1 |
| | 5/26/81 | AEO | A-036 | 6 | | | 5/18/81 | AEO | A-012 | 4 |
| | 5/26/81 | BEN | A-037 | 8 | | | 5/19/81 | AEO | A-019 | 4 |
| | Total Rods Burned | | | 38 | | Total Rods Burned | | | 9 | |
| 545 | 5/14/81 | FF AEO | A-007 | 2 | 556 | 5/14/81 | FF AEO | A-007 | 1 | |
| | 5/19/81 | BYZ | A-013 | 4 | | 5/18/81 | AEO | A-012 | 4 | |
| | 5/19/81 | BEN | A-020 | 6 | | 5/19/81 | AEO | A-019 | 4 | |
| | Total Rods Burned | | | 12 | | Total Rods Burned | | | 9 | |
| 546 | 5/14/81 | FF AEO | A-007 | 2 | 557 | 5/14/81 | FF AEO | A-007 | 1 | |
| | 5/18/81 | BYZ | A-013 | 4 | | 5/18/81 | AEO | A-012 | 4 | |
| | 5/19/81 | BEN | A-020 | 6 | | 5/19/81 | AEO | A-019 | 4 | |
| | 5/20/81 | AEO | A-023 | 5 | | Total Rods Burned | | | 9 | |
| | 5/21/81 | AEO | A-032 | 5 | 558 | 5/14/81 | FF AEO | A-007 | 1 | |
| | Total Rods Burned | | | 22 | | 5/18/81 | BYZ | A-013 | 4 | |
| 547 | 5/14/81 | FF AEO | A-007 | 1 | | 5/19/81 | AEO | A-019 | 2 | |
| | 5/18/81 | AEO | A-012 | 4 | | 5/19/81 | BEN | A-020 | 6 | |
| | 5/19/81 | AEO | A-019 | 4 | | 5/20/81 | AEO | A-023 | 5 | |
| | 5/19/81 | BEN | A-020 | 6 | | Total Rods Burned | | | 18 | |
| | 5/21/81 | AEO | A-032 | 5 | 559 | 5/14/81 | FF AEO | A-007 | 1 | |
| | Total Rods Burned | | | 20 | | 5/18/81 | BYZ | A-013 | 4 | |
| 551 | 5/14/81 | FF AEO | A-007 | 1 | | 5/19/81 | AEO | A-019 | 3 | |
| | 5/18/81 | AEO | A-012 | 4 | | 5/19/81 | BEN | A-020 | 6 | |
| | 5/19/81 | AEO | A-019 | 4 | | Total Rods Burned | | | 14 | |
| | Total Rods Burned | | | 9 | 560 | 5/14/81 | FF AEO | A-007 | 1 | |
| 552 | 5/14/81 | FF AEO | A-007 | 1 | | 5/18/81 | BYZ | A-013 | 4 | |
| | 5/19/81 | AEO | A-019 | 4 | | 5/19/81 | AEO | A-019 | 2 | |
| | Total Rods Burned | | | 5 | | 5/19/81 | BEN | A-020 | 5 | |
| 553 | 5/14/81 | FF AEO | A-007 | 1 | | 5/20/81 | AEO | A-023 | 5 | |
| | 5/18/81 | AEO | A-012 | 4 | | Total Rods Burned | | | 17 | |
| | 5/19/81 | AEO | A-019 | 4 | | | | | | |
| | Total Rods Burned | | | 9 | | | | | | |
| 554 | | A-007 | | | | | | | | |
| | | A-012 | | | | | | | | |
| | | A-036 | | | | | | | | |

PART IV:

NO QC VERIFICATION:

WFML's referenced on travelers indicate that new welding was done, but there is no supporting documentation in the package to show there was any QC verification or involvement when the welding was done.

| Weld | WFML Number | Step | Weld | WFML Number | Step | Weld | WFML Number | Step |
|------|------------------------------|-------------|------|--|--------------------------------------|------|---|--------------------------------------|
| 6 | D-4117 | 5 | 36 | B-195 D-4187 | 5 5 | 49 | A-433 B-173 | 1 5 |
| 10 | *D-2073 B-332 | 5 5 | 37 | D-4021 D-4007 D-4044 *A-425 | 5 4 5 5 | 51 | B-173 | 1 |
| 11 | B-317 | 5 | | | | 56 | D-4007 D-4021 D-4063 D-4044 | 1,4 1,4 1,4 1,4 |
| 12 | D-1502 D-1549 | 1,5 1,5 | 38 | D-4063 D-4073 | 5 5 | | | |
| 13 | D-1477 D-1502 | 1 5 | 39 | B-241 | 1 | 57 | D-3028 D-3027 D-3035 D-3046 D-3047 B-3075 D-3088 B-339 | 1 1 1 1 5 5 5 5 |
| 14 | D-1566 D-1586 | 1 5 | 40 | A-425 | 1,5 | | | |
| 16 | D-0725 D-5730 | 1 ? | 41 | D-3024 A-425 | 5 5 | | | |
| | | | 42 | D-2098 | 5 | 58 | B-180 B-193 | 1,5 5 |
| 17 | D-1284 D-1502 | 1 1,5 | 43 | D-1507 D-1531 D-1547 D-1566 D-1582 D-1670 *A-425 *A-438 | 1 1 1 1 1 1 5 5 | 60 | D-1547 D-1531 D-1586 D-1602 D-1561 B-339 | 1 1 1 5 5 5 |
| 20 | *D-4135 | 5 | | | | | | |
| 21 | D-4020 D-4046 D-4188 | 1 5 5 | 44 | D-1317 | 1 | 63 | B-1033A B-1038A B-1090A B-1577 | 1 1 1 5 |
| 22 | D-4188 | 5 | 46 | D-1355 D-1353 D-1373 D-1488 D-1837 | 1 1 1 5 5 | 65 | A-440 | 4 |
| 23 | *D-4136 *D-4188 D-2033 | 5 5 1 | | | | 66 | A-440 A-452 | 4 ? |
| 24 | B-314A B-332 | 1 1 | 47 | D-1317 | ? | | | |
| 26 | D-1477 B-314A | 1,5 1,5 | 48 | D-4912 D-4925 D-4936 B-262 | 1 5 5 5 | 71 | D-4903 D-4912 D-4925 D-4936 | 1 1 1 1 |
| 27 | D-1549 | 5 | | | | | | |
| 28 | D-1818 | 5 | | | | | | |

PART IV:NO QC VERIFICATION: For Rewelding

WFML's referenced on travelers that do not show QC verification.

| Weld | WFML Number | Step | Weld | WFML Number | Step | Weld | WFML Number | Step |
|------|----------------|------|------|----------------|------|------|----------------|------|
| 74 | D-4936 | 1 | 87 | D-4022 | 1 | 103 | D-1391 | 1 |
| | D-4945 | 5 | | D-4090 | 5 | | D-1413 | 1 |
| 75 | D-4936 | 1 | | D-4092 | 5 | 104 | D-1444 | 1 |
| | D-4945 | 1 | | D-4107 | 5 | | D-1461 | 1 |
| 77 | B-329A | 1 | 88 | D-4009 | 5 | 105 | B-502 | 1 |
| 80 | D-021 | 1 | | D-4022 | 5 | 107 | *B-463 | 1 |
| | D-035 | 1 | | B-502 | 1 | | B-477 | 1 |
| | D-043 | 1 | 89 | D-1178 | 1 | 108 | D-1264 | 1 |
| | D-046 | 1 | | D-1582 | 5 | | D-1488 | 1 |
| | D-065 | 1 | | D-1586 | 5 | | D-1472 | 5 |
| | D-4298 | 7 | | D-1945 | 5 | 109 | D-1284 | 1 |
| | D-4302 | 7 | | B-580 | 5 | | D-5730 | 1 |
| | B-590 | 7 | 90 | D-4022 | 1 | 111 | D-5715 | 1 |
| | B-599 | 7 | | | | | D-5724 | 1 |
| 81 | D-4283 | 1,5 | 91 | D-1391 | 1,5 | | D-5730 | 1 |
| | B-590 | 1,5 | 92 | D-4945 | 1 | 112 | D-1301 | 1 |
| 82 | D-4992 | 1 | | | | | D-5730 | ? |
| | D-4107 | 1,5 | 93 | D-1733 | 1 | 113 | D-1264 | 1 |
| | B-532 | 5 | | D-1840 | 1 | | D-1488 | 5 |
| | B-549 | 5 | | D-1862 | 1 | | D-1472 | 5 |
| | B-568 | 5 | | D-1837 | 1 | 114 | D-1731 | 1 |
| 84 | D-1204 | 1 | 94 | D-1945 | 1 | | D-1767 | 1 |
| | D-4063 | 1,5 | | D-1994 | 1 | 115 | D-1477 | 1 |
| | D-4090 | 5 | | B-460 | 1 | | D-1633 | 5 |
| | D-4123 | 5 | 96 | D-1818 | 1 | 116 | D-1731 | 1 |
| | D-4125 | 5 | | | | | D-1754 | 5 |
| 85 | D-4009 | 1 | 97 | D-1840 | 1 | 117 | D-1413 | 1 |
| | D-4022 | 5 | | D-1821 | 1 | | B-447 | 1 |
| | D-4090 | 5 | 98 | D-1493 | 1 | 119 | D-1731 | 1,5 |
| | D-4123 | 5 | | D-1493 | 1 | | D-1754 | 5 |
| 86 | D-1178 | 1 | | D-1710 | 5 | | D-1767 | 5 |
| | D-1187 | 1 | | D-1733 | 5 | | D-1801 | 5 |
| | D-3046 | 1 | | D-1752 | 5 | | D-1818 | 5 |
| | D-3075 | 5 | 99 | D-1862 | 1 | | D-1821 | 5 |
| | D-3076 | 5 | | B-460 | 5 | | | |
| | D-3088 | 5 | 101 | D-1413 | 1 | | | |
| | D-3096 | 5 | | D-1444 | 1 | | | |
| | D-580 | 5 | | | | | | |

PART IV:NO QC VERIFICATION: For Rewelding

WFML's referenced on travelers that do not show QC verification.

| Weld | WFML Number | Step | Weld | WFML Number | Step | Weld | WFML Number | Step |
|------|----------------|------|------|----------------|------|------|----------------|------|
| 120 | B-447 | 1 | 142 | D-1733 | 5 | 157 | D-3095 | 1 |
| 121 | D-1508 | 5 | | D-1752 | 5 | 158 | D-1963 | 1 |
| | D-1633 | 5 | | B-407 | 5 | | D-1983 | 1 |
| | D-1653 | 5 | | B-405A | 5 | | A161476 | 1 |
| 122 | B-392A | 1 | 143 | B-405A | 1 | | A161732 | 1 |
| | B-394 | 1 | 144 | D-1461 | 1 | | A161764 | 1 |
| 124 | D-4254 | 1,5 | | D-1733 | 5 | | A161784 | 1 |
| 125 | D-4254 | 1,5 | | D-1752 | 5 | | A161810 | 1 |
| 126 | D-035 | 1 | 145 | B-437 | 1 | 159 | D-1963 | 5 |
| | D-018 | 1 | 146 | D-1444 | 1 | | D-1983 | 5 |
| | D-043 | 7 | | D-1461 | 1 | 160 | D-1532 | 1 |
| | D-046 | 7 | 147 | B-629 | 1 | | D-1908 | 1 |
| | D-065 | 7 | | B-644 | 1 | | A161475 | 1 |
| | B-568 | 7 | 150 | D-021 | 1 | | A161733 | 1 |
| | B-580 | 7 | | D-032 | 1 | | A161764 | 1 |
| 127 | D-4275 | 5 | | D-018 | 1 | | A161810 | 1 |
| | D-4283 | 5 | | D-043 | 7 | | A161843 | 1 |
| 128 | D-4107 | 5 | | D-046 | 7 | 163 | B-450 | 5 |
| | D-4125 | 5 | | D-065 | 7 | | D-021 | 1 |
| | D-4211 | 5 | 151 | D-4133 | 5 | | D-032 | 1 |
| 129 | B-532 | 5 | | D-4124 | 7 | | D-043 | 1 |
| 130 | D-4092 | 1 | | D-4212 | 7 | | D-065 | 7 |
| 132 | B-493 | 1 | | | | | D-4404 | 7 |
| | B-502 | 1 | 152 | D-3059 | 1 | | D-4406 | 7 |
| 133 | D-4107 | 5 | | D-3076 | 1 | 165 | D-1263 | 1 |
| | D-4125 | 5 | | D-4267 | 5 | | D-1268 | 1 |
| 134 | D-3076 | 1 | | D-4275 | 5 | | D-1269 | 5 |
| | D-3087 | 5 | 153 | D-4267 | 5 | | D-1282 | 5 |
| 138 | D-1933 | 1 | | | | | D-4077 | 5 |
| 140 | B-477 | 1 | 155 | D-3095 | 5 | | D-4091 | 5 |
| | | | | D-4133 | 7 | 167 | D-4124 | 5 |
| | | | | D-4124 | 7 | | D-4124 | 5 |
| | | | 156 | A161476 | 5 | | D-4111 | 5 |
| | | | | A161732 | 5 | | D-4111 | 1 |
| | | | | A161763 | 5 | | D-4124 | 1 |
| | | | | A161784 | 5 | | D-4353 | 5 |
| | | | | A161809 | 5 | | D-4360 | 5 |
| | | | | A161844 | 5 | 169 | B-658 | 1 |

PART IV:NO QC VERIFICATION: For re-welding

WFML's referenced on travelers that do not show QC verification

| Weld | WFML Number | Step | Weld | WFML Number | Step | Weld | WFML Number | Step | |
|------|-------------|------|------|-------------|--------|------|-------------|---------|-------|
| 213 | D-1477 | 1 | 229 | D-4020 | 1 | 246 | B-248 | 1 | |
| | D-1477 | 1 | | D-4046 | 5 | | | | |
| | D-1477 | 1 | | D-4061 | 5 | 247 | B-112 | 1,7 | |
| | D-1477 | 1 | | D-4188 | 5 | | B-900A | 1,7 | |
| | D-4062 | 5 | | | | | B-905A | 1,7 | |
| 214 | D-2057 | 1 | 230 | D-3023 | 5 | 248 | B-237 | 1 | |
| | D-2072 | 5 | 231 | D-2033 | 1 | | B-225 | 1 | |
| | | | | D-2046 | 1 | | B-237 | 1 | |
| 215 | D-1585 | 1 | | D-2058 | 1 | | | | |
| | D-1837 | 1,5 | | D-2058 | 1 | 249 | B-112 | 1,7 | |
| | B-285 | 1,5 | | D-2099 | 1 | | B-900A | 1,7 | |
| | B-295A | 1,5 | | D-3001 | 5 | | RBL-249 | 7 | |
| | | | | D-3011 | 5 | | | | |
| 216 | B-71A | 1,5 | | D-4201 | 5 | 250 | A-727 | 4 30* | |
| | B-92A | 1,5 | 20* | | | | A-735 | 4 35* | |
| | B-71A | 1,5 | | 232 | D-2046 | 1 | | A-750 | 4 20* |
| | | | | | D-2058 | 1 | | A-777 | 4 20* |
| 219 | B-260 | 1 | | D-2058 | 1 | | A-801 | 4 25* | |
| | B-285 | 1 | | D-3011 | 1 | | | | |
| | B-295A | 1 | | D-3023 | 1 | 252 | D-4155 | 1 4r* | |
| | | | | D-4201 | 1 | | D-4169 | 1 | |
| 220 | B-71A | 1,5 | | | | | D-4179 | 1 | |
| | | | 234 | D-3023 | 4,1 | | A-750 | 5 10* | |
| 222 | B-1038A | 1 | | | | | A-801 | 5 1* | |
| | B-1062A | 1 | 237 | D-1301 | 1 | | A-819 | 5 5* | |
| | B-1090A | 1 | | D-1317 | 1 | | | | |
| | B-1577 | 5 | | | | 253 | D-5775 | 5 | |
| | | | 241 | B-35 | 7 | | D-5788 | 5 | |
| 225 | D-1317 | 1 | | B-39 | 7 | | D-5784 | 5 | |
| | | | | B-581 | 7 | | D-5788 | 5 | |
| 227 | D-008 | 5 | | B-591 | 7 | | D-5788 | 5 23* | |
| | D-021 | 5 | | RBL-241 | 7 | | | | |
| | N-010 | 5 | | | | 254 | B-581 | 7 | |
| | D-032 | 5 | 242 | A-883 | 1 15* | | | | |
| | N-020 | 5 | | A-891 | 1 13* | 256 | N-003 | 1 | |
| | D-043 | 5 | | A-901 | 1 | | D-043 | 1 | |
| | D-065 | 5 | | A-914 | 1,5 | | A-655 | 1 | |
| | D-4148 | 7 | | | | | A-667 | 1 | |
| | D-4165 | 7 | 244 | A-914 | 1 30* | | | | |
| | D-4175 | 7 | | A-922 | 1 20* | 257 | A-674 | 1 20* | |
| | D-4187 | 7 | | B-214 | 5 | | A-675 | 1 20* | |
| | D-4136 | 7 | | B-248 | 5 | | A-683 | 1 20* | |
| | | | | | | | A-695 | 1 12* | |
| 228 | D-022 | 5 | 245 | B-905A | 1,7 | | | | |
| | D-0476 | 5 | | RBL-245 | 7 | 258 | B-955A | 1,7 51* | |
| | D-4152 | 5 | | RBL-245 | 7 | | | | |

PART IV:

NO QC VERIFICATION: For re-welding

WFML's referenced on travelers that dosen't show QC verification

| Weld | WFML Number | Step | Weld | WFML Number | Step | Weld | WFML Number | Step |
|------|-------------|-------|------|-------------|---------|------|-------------|---------|
| 309 | B-569A | 1 | 332 | A-901 | 1 26* | 352 | A-750 | 1 20* |
| | B-580A | 1 66* | | B-418A | 1 | | A-791 | 1 11* |
| | | | | B-431A | 1 | | RBL-352 | 5 1* |
| 310 | B-868A | 1 32* | | B-472A | 1 39* | 696 | D-1361 | 1 |
| | | | | B-484A | 1 | | D-1386 | 1 |
| 312 | D-003 | | | B-472A | 5 | | D-1402 | 1 |
| | D-043 | | 333 | A-854 | 1 10* | | D-1422 | 1 |
| | N-024 | | | | | | D-1437 | 1 |
| | D-056 | | 335 | A-839 | 1 70* | | D-1456 | 1 |
| 313 | B-530 | 1 | | A-854 | 1 9* | | D-1462 | 1 |
| | B-559 | 1 | | B-961A | 1 33* | | D-1472 | 1 |
| | | | | | | | D-5619 | 1 |
| 314 | RBL-314 | 1 10* | 334 | A-922 | 4 20* | 697 | D-1361 | 1 |
| | | | | B-94 | 4 26* | | D-1386 | 1 |
| 315 | B-537A | 1 | | B-214 | 1 | | D-1402 | 1 |
| | B-546A | 1 | 337 | D-578 | 4 | | D-5619 | 1 |
| | | | | B-821A | 1 | 703 | A-321 | 1 11* |
| 316 | B-537A | 1 | | B-831A | 1 | | A-325 | 1,5 28* |
| | B-546A | 1 | | RBL-337 | 5 1* | | | |
| | | | 339 | B-3 | 4 20* | 709 | B-137 | 39* |
| 318 | B-510A | 1 | | B-63 | 4 | | | |
| | B-520A | 1 | | B-76 | 4 | 721 | D-5625 | 1,2,3 |
| | | | | B-225 | 1 | | D-5653 | 1,2,3 |
| 319 | B-816A | 5 5* | | B-431A | 1 | | D-5653 | 5 |
| | B-821A | 5 | | B-499A | 1 | 725 | D-5625 | 1,2,4 |
| | | | | B-510A | 1 | | D-5653 | 1,2,4 |
| 320 | B-842A | 1 | | RBL-339 | 5 | | D-5653 | 5 |
| | B-860A | 1 | 340 | B-053 | 1,4 29* | 727 | D-5626 | 1,2,4 |
| | | | | B-063 | | | D-5653 | 1,2,4 |
| 322 | D-4193 | 1 | | B-842A | | | D-5653 | 5 |
| | A-330 | 1 33* | | B-A46A | | 728 | D-5625 | 1,2,4 |
| | | | 341 | B-016 | 1 | | D-5653 | 1,2,4 |
| 323 | D-4193 | 1 | | B-069 | 1 | | D-5653 | 5 |
| | B-842A | 5 | | B-076 | 1 | | | |
| | B-846A | 5 | | B-225 | 1 | | | |
| | | | | | | | | |
| 325 | D-4193 | 5 | | | | | | |
| | RBL-325 | 5 30* | 342 | B-831A | 1 | | | |
| | | | | B-835A | 1 | | | |
| 330 | A-866 | 1 55* | 351 | RBL-351 | 4 5* | | | |
| 331 | D-008 | 1 | | | | | | |
| | A-883 | 1 | | | | | | |
| | A-891 | 1 39* | | | | | | |

PART IV:NO QC VERIFICATION:

WFML's attached to travelers indicate welding was done on the following welds but no QC verification or involvement is shown. WFML's attached to but not referenced on the travelers:

| Weld | Date | WFML Number | Welder Symbol | Welding Procedure | Heat Number | Rods/Spools Iss. Rt'd | |
|------|---------|-------------|---------------|-------------------|-------------|-----------------------|---|
| 1A | 5/3/83 | B-2426 | ABF | 88025 | 463516 | 8 | 0 |
| 14 | 3/23/83 | B-2427 | ABF | 88025 | 463516 | 2 | 0 |
| 16 | 3/22/83 | D-5711 | ABF | 88025 | 463516 | 10 | 0 |
| 26 | 6/7/83 | B-2428 | BZG | 88025 | 463516 | 5 | 2 |
| 28 | 3/17/83 | B-2429 | ABF | 88025 | 463516 | 10 | 0 |
| | 3/23/83 | " | ABC | " | " | 4 | 0 |
| | 4/6/83 | " | CFA | " | " | 4 | 0 |
| 37 | 7/10/81 | A-425 | AUB | 88025 | 463638 | 2 | 0 |
| 43 | 3/28/83 | B-1869 | CFA | 88025 | 463516 | 6 | 0 |
| 44 | 8/6/84 | B-2551 | CDP | 88025 | 463516 | 2 | 0 |
| | 8/7/84 | " | CDP | " | " | 2 | 1 |
| 45 | 3/1/83 | B-1768 | ABF | 88025 | 463516 | 5 | 3 |
| 46 | 8/6/84 | B-1752 | CDP | 88025 | 463516 | 2 | 0 |
| 47 | 3/14/83 | B-1834 | ABF | 88025 | 463516 | 10 | 5 |
| 48 | 3/1/83 | B-275 | ABF | 88025 | 463516 | 5 | 3 |
| 54 | 3/23/83 | B-2450 | CDP | 88025 | 463516 | 3 | 2 |
| 56 | 3/11/80 | D-3061 | BEY | 99020 | 434788 | 2 | 1 |
| 65 | 9/12/81 | *A-440 | ACH | 88025 | 463638 | 20 | 3 |
| | 9/14/81 | A-452 | ACH | 88025 | 463638 | 20 | 3 |
| 66 | 9/14/81 | A-452 | ACH | 88025 | 463638 | 20 | 3 |
| 67 | 3/29/83 | B-1873 | CFA | 88025 | 463516 | 1 | 0 |
| 68 | 3/29/83 | B-1874 | CFA | 88025 | 463516 | 1 | 0 |
| 69 | 2/24/83 | B-1756 | ABF | 88025 | 463516 | 2 | 0 |

*Referenced on traveler

PART IV:NO QC VERIFICATION:

| Weld | Date | WFML Number | Welder Symbol | Welding Procedure | Heat Number | Rods / Rolls Iss. Rt'd |
|------|---------|----------------|------------------|----------------------|----------------|---------------------------|
| 71 | 2/28/83 | B-1753 | ABF | 88025 | 463516 | 15 5 |
| 73 | 7/16/84 | B-2547 | BZG | 88025 | 463516 | 20 10 |
| | 7/17/84 | " | BZG | 88025 | 463516 | 20 9 |
| 74 | 2/24/83 | B-1755 | ABF | 88025 | 463516 | 1 0 |
| 80 | 5/1/80 | D-4290 | AUB | 88023 | 463638 | 40 10 |
| | " | D-4293 | AEO | 88023 | " | 40 10 |
| | 5/16/80 | D-4303 | AUB | 88023 | " | 40 27 |
| | 2/23/82 | B-608 | CFA | 88025 | 463516 | 40 5 |
| 86 | 12/3/79 | D-1187 | BBI | 99020 | 434788 | 2 rl 1 rl |
| | 3/17/80 | D-3096 | BEY | 88023 | " | 1 rl 0 rl |
| 89 | 2/14/80 | D-1954 | AWK | 99020 | 434788 | 1 rl 1/2rl |
| 90 | 2/10/82 | B-511 | CFA | 88025 | 463516 | 40 34 |
| | 2/11/82 | B-522 | CFA | 88025 | 463516 | 40 36 |
| 91 | 4/20/83 | B-1920 | AIM | 88025 | 463516 | 10 7 |
| 92 | 5/2/83 | A-79 | BEN | 88025 | 463638 | 20 4 |
| | 5/2/83 | A-79 | BFF | 88025 | 463516 | 10 9 |
| 94 | 4/22/80 | D-2003 | AWK | 99020 | 434788 | 1 rl 0 rl |
| 95 | 2/11/82 | B-524 | CCG | 88025 | 463516 | 40 0 |
| | " | " | " | " | " | 10 8 |
| 98 | 3/24/83 | B-1862 | ABF | 88025 | 463516 | 15 1 |
| 100 | 1/21/82 | B-368 | CCG | 88025 | 463516 | 40 19 |
| 101 | 3/29/83 | B-1867 | ABF | 88025 | 463516 | 15 0 |
| | 3/28/83 | " | ABF | " | " | 10 2 |
| | 3/29/83 | " | AGF | " | " | 10 0 |
| 104 | 3/29/83 | B-1877 | ABF | 88025 | 463516 | 8 3 |
| 107 | 2/3/82 | B-463 | CCG | 88025 | 463516 | 40 0 |
| 108 | 3/14/83 | B-1835 | ABF | 88025 | 463516 | 8 0 |
| | 3/15/83 | " | " | " | " | 10 5 |
| | 3/28/83 | " | CFA | " | " | 1 0 |
| | 3/14/83 | " | ABF | " | " | 8 0 |
| | 3/15/83 | " | " | " | " | 10 5 |

PART IV:NO QC VERIFICATION:

| Weld | Date | WFML Number | Welder Symbol | Welding Procedure | Heat Number | Rods / Iss. | Rolls Rt'd |
|------|---------|----------------|------------------|----------------------|----------------|----------------|---------------|
| 109 | 3/16/83 | B-1844 | ABF | 88025 | 463516 | 4 | 0 |
| | 3/17/83 | " | " | " | " | 10 | 0 |
| 111 | 2/19/81 | *D-5724 | BYZ | 88025 | 463638 | 40 | 0 |
| | 2/19/81 | " | " | " | " | 40 | 0 |
| | 3/22/83 | " | ABF | " | 463516 | 10 | 5 |
| 113 | 3/9/83 | B-1816 | CFA | 88025 | 463516 | 10 | 6 |
| 115 | 3/31/83 | B-1881 | ABF | 88025 | 463516 | 15 | 3 |
| | 4/7/83 | " | CFA | " | " | 20 | 12 |
| | 4/7/83 | " | BBU | " | " | 10 | 3 |
| | 4/8/83 | " | CFA | " | " | 10 | 0 |
| | 4/19/83 | " | CFA | " | " | 4 | 0 |
| 116 | 4/18/83 | B-1916 | CFA | 88025 | 463516 | 9 | 0 |
| 117 | 4/18/83 | B-1917 | CFA | 88025 | 463516 | 9 | 0 |
| 122 | 3/30/83 | *B-394 | ABF | 88025 | 463516 | 5 | 0 |
| 143 | 1/27/82 | *B-411 | CCG | 88025 | 463516 | 40 | 14 |
| | 1/28/82 | *B-424 | CCG | " | " | 40 | 20 |
| 147 | 2/26/82 | *B-644 | CFA | 88025 | 463516 | 40 | 9 |
| | 2/25/82 | *B-629 | " | " | " | 40 | 7 |
| 163 | 5/30/80 | D-4404 | AUB | 88023 | 463638 | 40 | 0 |
| | 6/2/80 | D-4406 | AUB | " | " | 40 | 11 |
| 168 | 6/27/83 | B-2161 | BZO | 88025 | 463516 | 20 | 3 |
| 169 | 6/7/83 | B-2117 | BZO | 88025 | 463516 | 30 | 5 |
| | 6/8/83 | " | ABF | " | " | 10 | 4 |
| | 6/8/83 | " | BFF | " | " | 25 | 10 |
| 173 | 5/3/83 | B-355 | ABF | 88025 | 463516 | 40 | 11 |
| 175 | 1/27/82 | B-407 | CFO | 88025 | 463516 | 40 | 2 |
| | 1/28/82 | B-420 | CFO | " | " | 40 | 7 |
| 177 | 4/19/83 | *D-1692 | CFA | 88025 | 463516 | 4 | 0 |
| 179 | 6/28/83 | B-2144 | BZG | 88025 | 463516 | 20 | 2 |
| 183 | 4/19/83 | B-1918 | CFA | 88025 | 463516 | 10 | 0 |

*Referenced on traveler

PART IV:

NO QC VERIFICATION: WFML's Attached To But Not Referenced On Traveler.
Welding was done with no QC inspections.

| Weld | Date | WFML Number | Welder Symbol | Welding Procedure | Heat Number | Rods/Rolls Iss. Rt'd |
|-------------------|---------|----------------|------------------|----------------------|----------------|-------------------------|
| 199 | 4/20/83 | B-2433 | AIM | 88025 | 463516 | 15 7 |
| 200 | 3/2/83 | B-1773 | ABF | 88025 | 463516 | 5 0 |
| 201 | 3/07/83 | B-1772 | ABF | 88025 | 463516 | 5 2 |
| 202 | 4/13/83 | B-1908 | CFA | 88025 | 463516 | 3 0 |
| 216 | 3/28/83 | B-092A | CFA | 88025 | 463516 | 2 0 |
| 217 | 3/29/83 | B-0307 | CFA | 88025 | 463516 | 1 0 |
| 218 | 3/09/83 | B-1814 | ABF | 88025 | 463516 | 2 0 |
| | 3/17/83 | " | CFA | " | " | 3 0 |
| | 3/28/83 | " | CFA | " | " | 1 0 |
| 219 | 3/15/83 | B-1838 | CFA | 88025 | 463516 | 2 0 |
| 220 | 3/15/83 | B-1839 | CFA | 88025 | 463516 | 2 1 |
| 222 | 3/09/83 | B-1815 | ABF | 88025 | 463516 | 2 0 |
| 223 | 3/02/83 | D-1355 | ABF | 88025 | 463516 | 10 4 |
| 253 | 3/09/83 | D-5788 | CFL | 88025 | 463516 | 2 0 |
| 257 | 4/21/83 | B-RBL-257 | ABF | 88025 | 463516 | 15 0 |
| 237 | 3/02/83 | B-1774 | ABF | 88025 | 463516 | 10 5 |
| | 3/09/83 | " | CFA | " | " | 2 1 |
| 200 | 3/02/83 | B-1773 | ABF | 88025 | 463516 | 5 0 |
| 697 | 3/15/83 | B-1831 | CFA | 88025 | 463516 | 5 0 |
| | 3/31/83 | " | CFA | " | " | 2 0 |
| | 4/04/83 | " | CFA | " | " | 8 0 |
| | 4/04/83 | " | CFA | " | " | 10 0 |
| Total Rods Burned | | | | | | 25 |
| 713 | 7/12/84 | B-2545 | BZO | 88025 | 463516 | 5 3 |
| 714 | 7/12/84 | B-2543 | BZO | 88025 | 463516 | 20 19 |

PART IV:

NO QC VERIFICATION: WFML's Attached To But Not Referenced On Traveler
Welding performed with no QC inspections.

| Weld | Date | WFML Number | Welder Symbol | Welding Procudere | Heat Number | Rods/Rolls Iss. Rt'd |
|------|---------|----------------|------------------|----------------------|----------------|-------------------------|
| 852 | 3/29/83 | B-1875 | CFA | 88025 | 463516 | 1 0 |
| 853 | 3/16/83 | B-1842 | CFA | 88025 | 463516 | 6 1 |
| 854 | 3/16/83 | B-1843 | CFA | 88025 | 463516 | 6 0 |
| | 3/17/83 | " | CFA | " | " | 2 0 |
| | 3/21/83 | " | CFA | " | " | 3 0 |
| 857 | 3/01/83 | B-1770 | ABF | 88025 | 463516 | 5 1 |
| | 3/17/83 | " | CFA | " | " | 1 0 |
| 858 | 3/01/83 | B-1771 | ABF | 88025 | 463516 | 5 0 |
| | 3/16/83 | " | CFA | " | " | 3 0 |
| 1217 | 5/20/82 | B-1068A | AAR | 18013 | 50067-1 | 25 13 |
| | 5/20/82 | " | AAR | " | " | 10 0 |

JAMES W. COLE

In 1981 James W. Cole signed off the following travelers as complete. Step 8 (Completion of Weld Inspection) was signed off but the required vacuum box test were not done. The PT test had been performed but the vacuum box block was N.A'd.

Several NCR's were written against these welds because they are pressure boundary welds and require vacuum box testing. The NCR's referenced QI-QP 11.14-6, Para. 3.4.4. The disposition of the NCR's re-established the holdpoints and required that these welds be vacuum box tested. The NCR's and weld numbers are as follows:

NCR M-84-00647 dated: 2/24/84

Weld: 1098, 1099, 1100, 1101, 1102, 1103, 1104, and 1105

NCR M-84-00669 dated: 2/27/84

Welds: 1087, 1088, 1089, 1090, 1091, 1092, 1144, 1145

NCR M-84-00670 dated: 2/27/84

Weld: 1111, 1112, 1117, 1118, 1121, 1122, 1123, 1129, 1127, 1130
1132, 1133, 1134 and 1128

NCR M-84-2-00038 dated: 7/30/84

Weld: 1082, 1083, 1084, 1096, 1097, 1106, 1107, 1108, and 1109

NCR M-84-2-00039 dated: 7/30/84

Weld: 1085, 1086, 1093, 1094, 1095, 1110, 1113, 1114, 1115, 1116
1119, 1120, 1124, 1125, 1126, and 1131

PART II: Failure to Perform and Document Inspections

VIOLATIONS OF: 10CFR50 Appendix B Criteria V
ANSI/ASME N45.2-1977 Section 2

Procedures: CP-QCI-2.11-1; QI-QAP-10.1-4; QI-QAP-11.1-4

Procedures require the QC inspector to inspect all interior surfaces of the Stainless Steel liner and document the results on the S/S Liner NDE Report.

NDE on Seam Welds:

Procedure requires a final visual examination of seam welds; a final liquid pentrant examination of seam welds; and final vacuum box test of seam welds.

Final V.T. of inside welds has been signed off on the following welds without the vacuum box and/or pentrant examination being performed as required by procedure.

No NDE Reports included in package: 655 713 714 719
NDE Report for V.T. only: 665 804 805 847 848 849 850
V.T. and P.T. examination performed: 690 888 887 989

The final V.T. of inside welds were signed off by James Cole for the following welds without the P.T. examination or vacuum box test being performed.

| | | | | | | | | | | | |
|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 354 | 355 | 356 | 359 | 360 | 365 | 366 | 367 | 370 | 371 | 373 | 375 |
| 378 | 381 | 383 | 385 | 386 | 387 | 396 | 392 | 567 | 571 | 572 | 575 |
| 576 | 583 | 584 | 586 | 587 | 590 | 591 | 594 | 595 | 596 | 597 | 598 |
| 599 | 601 | 602 | 603 | 604 | 605 | | | | | | |

The final V.T. of inside welds were signed off on the following welds by other inspectors.

610 612 613 617 778 1229 1263 1264 1265 1266 1267

PART V: IMPROPER SIGN OFF OF INCOMPLETE WELDS, FAILURE TO COMPLY WITH MANDATORY HOLD POINTS, AND LACK OF NDE S/S LINER TEST REPORTS

VIOLATIONS OF: 10CFR50 Appendix B, Criteria II and V
ANSI/ASME N45.2-1977, Section 11 and 18
CPSES SITE PROCEDURES 1/9/78 - 3/26/82

The following welds have the completion of weld inspection block on Attachment 1 signed off as completed prior to the completion on welds prior to vacuum box testing and/or P.T. inspection being performed.

1. NDE report sheet was included in package for V.T., but P.T. test and vacuum box test was not performed.

| | | | | | | | | | |
|------|------|------|------|------|------|------|------|------|------|
| 678 | 679 | 680 | 681 | 682 | 683 | 684 | 685 | 712 | 718 |
| 933 | 937 | 938 | 1139 | 1140 | 1141 | 1142 | 1146 | 1147 | 1148 |
| 1149 | 1150 | 1151 | 1152 | 1159 | 1169 | 1170 | 1171 | 1172 | 1175 |
| 1176 | 1177 | 1178 | 1179 | 1181 | 1182 | 1183 | 1184 | 1185 | 1186 |
| 1187 | 1188 | 1189 | 1190 | 1191 | 1192 | 1193 | 1194 | 1195 | 1196 |
| 1197 | 1198 | 1199 | 1200 | 1201 | 1202 | 1203 | 1204 | 1205 | 1206 |
| 1209 | 1210 | | | | | | | | |

2. No NDE report sheets, no P.T. examination, and no vacuum box test

| | | | | | | | | | |
|------|------|------|------|------|------|------|------|------|------|
| 5 | 7 | 8 | 715 | 716 | 889 | 890 | 891 | 892 | 896 |
| 900 | 934 | 936 | 939 | 940 | 941 | 942 | 943 | 953 | 953 |
| 954 | 955 | 956 | 957 | 958 | 959 | 960 | 961 | 962 | 963 |
| 964 | 966 | 967 | 968 | 969 | 970 | 991 | 992 | 993 | 994 |
| 995 | 1154 | 1155 | 1156 | 1157 | 1158 | 1218 | 1219 | 1220 | 1221 |
| 1222 | 1223 | 1224 | 1239 | 1240 | 1241 | 1242 | 1243 | 1245 | 1246 |
| 1247 | 1248 | 1249 | 1250 | 1251 | 1252 | 1260 | 1261 | 1262 | |

IMPROPER SIGN OFF OF INCOMPLETE WELDS:

3. Signed off as complete by James Cole with vacuum box test N/A'ed. Many NCR's were written for welds that James Cole had N/A'ed the vacuum box test on. The vacuum box test has been re-established on all but the ones below.

| | | | | | | | | | |
|------|------|------|------|------|------|------|------|------|------|
| 722 | 723 | 724 | 725 | 726 | 730 | 731 | 732 | 733 | 734 |
| 735 | 736 | 737 | 738 | 739 | 740 | 741 | 742 | 751 | 752 |
| 753 | 754 | 759 | 760 | 761 | 762 | 765 | 766 | 770 | 773 |
| 774 | 775 | 776 | 779 | 780 | 781 | 782 | 783 | 784 | 785 |
| 786 | 787 | 800 | 807 | 820 | 821 | 822 | 823 | 824 | 825 |
| 826 | 827 | 828 | 829 | 830 | 831 | 832 | 833 | 877 | 878 |
| 879 | 880 | 881 | 882 | 883 | 884 | 886 | 913 | 915 | 932 |
| 996 | 997 | 998 | 999 | 1135 | 1137 | 1138 | 1161 | 1162 | 1163 |
| 1165 | 1166 | 1167 | 1168 | 1211 | 1212 | 1213 | 1215 | | |

4. P.T. test has been performed on these welds but vacuum box has not

| | | | | | | | | | |
|------|------|------|------|------|------|------|------|-----|------|
| 901 | 902 | 903 | 904 | 905 | 906 | 907 | 908 | 909 | 910 |
| 929 | 930 | 944 | 945 | 946 | 947 | 948 | 950 | 961 | 952 |
| 971 | 972 | 973 | 974 | 975 | 976 | 977 | 978 | 979 | 980 |
| 981 | 982 | 983 | 984 | 985 | 986 | 987 | 988 | 990 | 1230 |
| 1231 | 1232 | 1233 | 1234 | 1235 | 1236 | 1237 | 1238 | | |

PART VI: NON CONFORMING CONDITIONS DISPOSITIONED BY NCR'sNCR M-83-01188 WELDS SIGNED OFF BY JIM COLE THAT HAD MAJOR DEFECTS:

2 Welds involved 324 and 694

PROBLEM: Documentation in the vault indicates weld 324 (plate D-32 to angle C-6) is complete. Contrary to the above, weld 324 also continues around the corner to join plates D-32 to A-7 as shown on the attached sketch and is not complete. Welded portion of weld 324 is 3/16" short of corner.

Documentation in the vault indicates weld 694 is complete. Weld 694 is not complete as shown on the attached sketch. Welded portion of weld 694 is one inch short of the corner. Incomplete fusion was also noted (see sketch)

DISPOSITION: 1. Complete weld 324. Inspect and document the weld as required.

2. Repair weld defect with RPS. Complete weld 694. Inspect and document the weld as required.

NOTE: James Cole either did not inspect these welds before he signed them off, or he did not have the ability to perform inspections properly. It is clear to see that the welds were not properly done and were not completed.

NCR M-83-01847 dated 7/7/83

Weld 166 and 154

PROBLEM: While performing a cleanliness inspection of welds 166 and 154 the following conditions were noted.

Condition #1 The backing bar at the intersection of welds 166 and 153 has been ground through.

Condition #2 The backing bar at the intersection of welds 154 and 151 lacks 3/8" of running the full length of the weld. Hold tag Applied

DISPOSITION: Issue RPS to repair hole in backing strip. The area of weld without backing shall be prepped for disposition of a full pen weld without backing using the GTAW process.

NOTE: The NCR was written in 1983 and a hold tag applied. It has not been dispositioned yet, and there is no copy of this NCR in traveler 151. There is no RPS in package for weld 154. 154 was signed off by Don Vogt, S.M. McCoy, for steps 2, 3, and 4. Jim Cole inspected 151 on 4/20/80, and 153 on 4/24/80.

M-83-00907

QI-QP-11.14-6 Rev. 3, para. 3

3/28/83

The quality of field welds 243, 859, and 871 is indeterminate due to the following:

- ITEM 1 - Steps 2, 3, and 4 on (inspection traveler) weld No. 243 have been N/A'ed. These attributes are applicable to weld 243, and it cannot be determined whether this work was previously accomplished and accepted by QC.
- ITEM 2 - On (inspection traveler) weld Nos. 859 and 871, hold points have been previously signed by QC personnel. No controlled document can be produced delineating the location and/or orientation of said weld nos., and piece to piece entries are incomplete or incorrect, therefore, indeterminate (these welds are not identified on any design document).

Disposition: Steps 2, 3, and 4 are covered on welds number 859 and 860.

Per CCP-38 craft shall assign weld numbers to welds and the numbers shall be shown, on marked up copy of the drawing. After completion of the liner, the drawing will be submitted to the vault.

M-83-00795

QI-QP-11.14-6 Rev. 2, para: Attach. I

Step 5 3/17/83

A review of Stainless Steel Liner Travelers, for RB#2 Cavity welds, has found that the required Fit-up/Cleanliness inspection of inside (waterside) welds cannot be verified as being performed. Quality of welds indeterminate.

Disposition: Subject welds are seam welds utilized to provide leak tightness of the liner. Acceptability of welds shall be based on vacuum box and hydrostatic tests.

M-83-01316

CP-QP-16.0 8 2.2.1
QI-QP-11.14-6 Rev. 3 para 3.4.1

5/11/83

During inspection of refueling liner, weld seam #256 weld repair found backing bar not installed as required. Area ground out has concrete in contact with plate in required weld area. Review of travelers and documentation on 256, dates on fit-up and cleanliness, VT of backing strip tack/fillet welds is inconsistent.

DISPOSITION: Issue RPS to install back-up bar and edge, prepar base metal for deposition of full penetration weld. Chip concrete of required, up to 1/4" deep behind back-up bar to facilitate back-up bar to facilitate back-up bar installation.

PART VI: NON CONFORMING CONDITIONS DISPOSITIONED BY DCA's AND NCR'sNCR M-84-01969 & DCA 20,814 WELDING PERFORMED WITHOUT QC INSPECTION

15 Welds involved

Problem: Per the NCR referenced below, the following welds shown on Bostrom-Bergen drawing 2401-A sheet E2, did not have their fit-up inspected prior to welding: Weld Numbers 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 632, 650, 651, 652, and 653. Therefore their conformance with SS-18, Sect. 6.6 is in question.

Solution: The requirements of section 6.6 are waived for the above welds. The welds listed are acceptable without a QC inspection of their fit-up. All other QC inspections remain Applicabe.

See Exhibit #1

NCR M-84-00498 P.T. REPORTS FILLED OUT USING WRONG PROCEDURE NUMBER

41 Welds involved

Problem: During review of Documentation of welds and Inspection in S/S Liner in RB#2 it was noted that PT reports were filled out using procedure #QI-QP 11.14-1 rev. 1 as a NDE Procedure. At this time QI-QP 11.14-1 was in Rev. 3. The proper procedure to be used at that time was QI-QAP 10.2-1 rev. 1. These reports were used in closing NCR# M-82-00059. The following welds are affected by this error: 1169, 1170, 1171, 1172, 1175, 1176, 1177, 1178, 1179, 1181, 1182, 1183, 1184, 1185, 1186, 1187, 1188, 1187, 1188, 1189, 1190, 1191, 1193, 1192, 1194, 1195, 1196, 1197, 1198, 1199, 1200, 1201, 1202, 1203, 1204, 1205, 1206, 1207, 1208, 1209, 1210, 1355, and 1356.

Disposition: QC shall correct PT Reports to show proper NCE procedure number and reference this NVR number on those reports.

NOT: There was no copy of NCR M-82-00059 in any of the packages. Rev. 1 was issued for the above NCR to delete welds 1355 and 1356.

See Exhibit #2

Lack of QC Verification for Fit-up and Cleanliness - No QC Surveillance at all.

NCR M-84-01969: The following welds did not have the Fit-up Inspection required prior to welding.

DCA NO. 20,814: Per the NCR referenced below the following welds shown on Bestrom-Bergen dwg. 2401-A sheet E2, did not have their Fitup inspected prior to welding: Therefore their conformance with SS-18 sect. 6.6 is in question.

Solution: DCA waived the requirements of section 6.6

| | | | | | | | | |
|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 618 | 619 | 620 | 621 | 622 | 623 | 624 | 625 | 626 |
| 627 | 632 | 650 | 651 | 652 | 653 | | | |

NCR M-84-00498: P.T. Reports filled out using the wrong procedure No.

"During review of Document of inspections it was noted that QI-QP-11.14-1 was used as a NDE procedure. The correct procedure at that time was QI-QAP-10.2-1. These reports were used to close out NCR M-82-00059. The following welds were affected by this error."

| | | | | | | | | |
|------|------|------|------|------|------|------|------|------|
| 1169 | 1170 | 1171 | 1172 | 1175 | 1176 | 1177 | 1178 | 1179 |
| 1180 | 1181 | 1182 | 1183 | 1184 | 1185 | 1186 | 1187 | 1188 |
| 1190 | 1191 | 1192 | 1193 | 1194 | 1195 | 1196 | 1197 | 1198 |
| 1199 | 1200 | 1201 | 1202 | 1203 | 1204 | 1205 | 1206 | 1207 |
| 1209 | 1210 | | | | | | | |

Brown & Root, Inc.

Weld Inspection Form

988

WELD NO.


B&R Stainless Steel Liner Inspection Traveler

PROJECT: CPSES JOB NO: 35-1195 UNIT 2 PAGE 1 OF 3

WJF00851 N. TRANS. CANAL STAINLESS STEEL 7/16" Angle to R A41
 Drawing No. Pool Metal Type Mtl. Tnk. PC. to PC.
 Plate to Plate Insert to Plate Angle to Plate Other

| Welder Symbol | WFIL No. | Weld Proced. | Hold Point |
|--|----------|--------------|------------|
| AEO | D-080 | 88023 | 5 |
| BAG | D-251 | 88023 | 5 |
| BAF | D-255 | 88023 | 7 |
| BAF | D-282 | 88023 | 7 |
| BAG | D-717 | 88023 | 7 |
| BAG | D-1378 | 88023 | 7 |
| BAG | D-1438 | 88023 | 7 |
| BROWN & ROOT RECEIVED | | | |
| MAR 10 1980 | | | |
| FILES NOTED | | | |
| QUALITY ASSURANCE | | | |
| PERM. PLT. RECORD RTN <u>L</u> FILE LOC <u>17.198.7</u> SUBFILE NO. <u>988</u> | | | |

- Fit up and Cleanliness of Above:
NA Results NA Inspector Signature NA Date
- V.T. of Backing Strip Tack/Fillet Welds:
NA Results NA Inspector Signature NA Date
- Cleanliness of Channel, Liner, and B. Strip:
NA Results NA Inspector Signature NA Date
- Final V.T. of Channel Fillet Weld:
NA Results NA Inspector Signature NA Date
- Inside Fit Up and Cleanliness:
Sat. Results Whitebrook Inspector Signature 8-27-79 Date
- V.T. of Fillet Prior to Grinding:
NA Results NA Inspector Signature NA Date
- Final V.T. of Inside Weld:
Sat. Results Robert J. Kearney Inspector Signature 2-26-80 Date
- Completion of Weld Inspection: (NDE P200)
Sat. Results James W. Cole Inspector Signature 3-6-80 Date



QUALITY ASSURANCE DEPARTMENT
STAINLESS STEEL LINER INSPECTION TRAVLER/NDE REPORT

JWC
3.3.80
2
3
7

PROJECT: CPSES JOB NO.: 35-1195 UNIT 2 PAGE 7 OF 7

| | | | | | | | |
|-----------------------------|-------------------------------------|------------------------------|---|--------------|----------------|----------------|--------------|
| DRAWING <u>WEB 00931</u> | POOL <u>Euel Bida Canal</u> | North MTL TYPE <u>SIS</u> | MTL. THICKNESS <u>3116"</u> | | | | |
| WELD/ITEM NO. <u>988</u> | PC. TO PC. <u>ANGLE TO R A41</u> | | <input type="checkbox"/> Plate to Plate <input type="checkbox"/> Insert to Plate <input checked="" type="checkbox"/> Angle to Plate | | | | |
| WER NO. | <u>42903</u> | <u>42903</u> | <u>54066</u> | <u>54018</u> | <u>54029</u> | <u>61660</u> | <u>61672</u> |
| WELD PROCEDURE | <u>88023</u> | <u>88023</u> | <u>88023</u> | <u>88023</u> | <u>88023</u> | <u>88023</u> | <u>88023</u> |
| WELDER SYMBOL | <u>A1H</u> | <u>A1H</u> | <u>AEP</u> | <u>A1H</u> | <u>AEP</u> | <u>NET</u> | <u>A1H</u> |
| STAGE OF MANUFACTURE | <u>FIT-UP</u> | <u>TACK BS</u> | <u>TACK BS</u> | <u>FINAL</u> | <u>CHANNEL</u> | <u>STAPLES</u> | <u>BS-00</u> |


| DESCRIPTION(S) and INSPECTION REMARK(S) | RESULTS | SIGNATURE | DATE |
|---|---------|--------------------|--------|
| 1. Fit up of liner <u>plate</u> to plate, <u>angle</u> insert. Cleanliness of liner and backing | SAT | <i>[Signature]</i> | 5-2-78 |
| 2a. V.T. of backing strip <u>and</u> filler welds. | SAT | <i>[Signature]</i> | 5-2-78 |
| 2b. Cleanliness of channel, liner and backing strip. | SAT | <i>[Signature]</i> | 5-2-78 |
| 3. Final V.T. of Channel Welds. | SAT | <i>[Signature]</i> | 5-2-78 |
| 4. Liner Fit-up Verification. Cleanliness Verification | | | |
| 5a. Final V.T. | X | X | X |
| 5b. Permanent Mfg. Magnaflex-Spotcheck-Batch _____ Dwell Time _____ Clean up Mfg. Magnaflex-Spotcheck-Batch _____ Developer Mfg. Magnaflex-Spotcheck-Batch _____ Developing Time _____ NDE procedure Surface _____ 300-10-5850 Attach. 63 As Welded _____ Ground _____ Other _____ Final P.T. _____ 5c. Vacuum Box _____ Gasket Type _____ Solution Type _____ by _____ Post Test Cleaning _____ Pressure _____ Temperature _____ NDE Procedure 600 _____ Solution Application Method _____ Post Test Cleaning _____ Serial Number _____ Pressure Differential _____ Maintained for _____ Sec. _____ Min. _____ Final V.T. _____ N/A - Not Applicable. Satisfactory _____ Unsatisfactory _____ INSPECTOR _____ DATE _____ CERT. LEVEL _____ | | | |

988

Weld No.

Acceptance Std.
Gibbs & Hill 2323-SS-18

- 5b. Penetrant Mfg. Magnaflux-Spotcheck
- Cleaner Mfg. Magnaflux-Spotcheck
- Developer Mfg. Magnaflux-Spotcheck



NDE Procedure
300-NB-5350 Attach. 63

Final P.T. Level II SAT. Robert F. Karney 2-26-80
RESULTS INSPECTOR SIGN. DATE

5c. Vacuum Box GASKET TYPE SOLUTION TYPE
24" by 5" rubber SNOOP
 Pretest Cleaning Sat. Pressure 2-5 Temperature 74° NDE Procedure 600
 Solution Application Method Squeeze B. Post Test Cleaning Sat.
 Gauge Serial Number 898 Pressure Differential
 Maintained for 20 Sec. 0 Min.

Final V.B. James W. Cole

N/A - Not Applicable

Satisfactory Unsatisfactory Level II
Inspector JWC Date 3-5-80