



**WOLF CREEK GENERATING STATION  
CYCLE 8**

**CORE OPERATING LIMITS REPORT  
Revision 1**

November 8, 1995

Prepared by:

*Michael E. Howard*  
Michael E. Howard

Reviewed by:

*Jeff Y. Blair*  
Jeff Y. Blair

Approved by:

*R. D. Flannigan*  
R. D. Flannigan

2.0 OPERATING LIMITS

The cycle-specific parameter limits for the specifications listed in Section 1.0 are presented in the subsections below:

2.1 Moderator Temperature Coefficient (MTC) EOL Limit

(Tech Spec 3.1.1.3.b)

The EOL MTC shall be less negative than -50 pcm/deg F. |

(Tech Spec 4.1.1.3.b)

The 300 PPM MTC Surveillance Limit is -41 pcm/deg F (all rods withdrawn, Rated Thermal Power condition). |