Attachment IV to WO 95-0187 Page 2 of 7

DEFINITIONS

CONTAINMENT INTEGRITY

1.7 CONTAINMENT INTEGRITY shall exist when:

- a. All penetrations required to be closed during accident conditions are either
 - 1) Capable of being closed by an OPERABLE containment automatic isolation valve system, or
 - 2) Closed by manual valves, blind flanges, or deactivated automatic valves secured in their closed positions, except as provided in Table 3.6-1 of Specification 3.6.3.
- b. All equipment hatches are closed and sealed.
- c. Each air lock is in compliance with the requirements of Specification 3.6.1.3.
- d. The sealing mechanism associated with each penetration (e.g., welds, bellows, or O-rings) is OPERABLE, and
- e. The containment leakage rates determined by Specification 4.6.1.1.d 4.6.1.1.c are within the limits listed in the Bases of Specification 3/4.6.1.1



CONTROLLED LEAKAGE

1.8 CONTROLLED LEAKAGE shall be that seal water flow from the reactor coolant pump seals

CORE ALTERATION

1.9 CORE ALTERATION shall be the movement or manipulation of any component within the reactor vessel with the vessel head removed and fuel in the vessel. Suspension of CORE ALTERATION shall not preclude completion of movement of a component to a safe conservative position.

CORE OPERATING LIMITS REPORT

1.10 The CORE OPERATING LIMITS REPORT (COLR) is the unit-specific document that provides core operating limits for the current operating reload cycle These cycle-specific core operating limits shall be determined for each reload cycle in accordance with Specification 6.9.1.9. Plant operation within these operating limits is addressed in individual Specifications.

WOLF CREEK - UNIT 1 1-2

Amendment No. 61, 89

9601020290 951220 FDR 0482 ADOCK 0 PDR

Attachment IV to WO 95-0187 Page 3 of 7

3/4.6 CONTAINMENT SYSTEMS

3/4.6.1 PRIMARY CONTAINMENT

CONTAINMENT INTEGRITY

LIMITING CONDITION FOR OPERATION

3.6.1.1 Primary CONTAINMENT INTEGRITY shall be maintained.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTION:

Without primary CONTAINMENT INTEGRITY, restore CONTAINMENT INTEGRITY within 1 hour or be in at least HCT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.6.1.1 Primary CONTAINMENT INTEGRITY shall be demonstrated:

- At least once per 31 days by verifying that all penetrations* not capable of being closed by OPERABLE containment automatic isolation valves and required to be closed during accident conditions are closed by valves, blind flanges, or deactivated automatic valves secured in their positions, except as provided in Table 3.6-1 of Specification 3.6.3;
- By verifying that each containment air lock is in compliance with the requirements of Specification 3.6.1.3;
- c. After each closing of each penetration subject to Type B testing, except the containment air locks, if opened following a Type A or B test, by leak rate testing the seal with gas at a pressure not less than Pa, 48 psig, and verifying that when the measured leakage rate for these seals is added to the leakage rates determined pursuant to Specification 4.6.1.1d. for all other Type B and C penetrations, the combined leakage rate is less than 0.60 La;
- c.)d. By performing containment leakage rate testing, except for containment air lock testing in accordance with 10 CFR 50, Appendix J, as modified by approved exemptions; and (the Containment Leakage Rate Testing Program of Specification 6.8.4)

 By verifying containment structural integrity in accordance with the Containment Tendon Surveillance Program of Specification 6.8.5.c.

*Except valves, blind flanges, and deactivated automatic valves which are located inside the containment and are locked, sealed, or otherwise secured in the closed position. These penetrations shall be verified closed during each COLD SHUTDOWN except that such verification need not be performed more often than once per 92 days.

WOLF CREEK - UNIT 1

d.

3/4 6-1 (Next page is 3/4 6-4) Amendment No. 89

Attachment IV to WO 95-0187 Page 4 of 7

CONTAINMENT SYSTEMS

CONTAINMENT AIR LOCKS

LIMITING CONDITION FOR OPERATION

- 3.6.1.3 Each containment air lock shall be OPERABLE with both doors closed except when the air lock is being used for normal transit and exits through the containment, then at least one air lock door shall be closed.
 - a. Both doors closed except when the air lock is being used for normal transit entry and exits through the containment, then at least one air lock door shall be closed, and
 - An overall air lock leakage rate of less than or equal to 0.05 La at Pa, 48 psig.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTION

- a. With one containment air lock door inoperable:
 - Maintain at least the OPERABLE air lock door closed and either restore the inoperable air lock door to OPERABLE status within 24 hours or lock the OPERABLE air lock door closed.
 - Operation may then continue until performance of the next required overall air lock leakage test provided that the OPERABLE air lock door is verified to be locked closed at least once per 31 days,
 - Otherwise, be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours, and
 - 4. The provisions of Specification 3.0.4 are not applicable
- b. With the containment air lock inoperable, except as the result of an inoperable air lock door, maintain at least one air lock door closed; restore the inoperable air lock to OPERABLE status within 24 hours or be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

Attachment IV to WO 95-0187 Page 5 of 7

CONTAINMENT SYSTEMS

b.

SURVEILLANCE REQUIREMENTS

4.6.1.3 Each containment air lock shall be demonstrated OPERABLE:

- a. By verifying leakage rates in accordance with the Containment Leakage Rate Testing Program of Specification 6.8.4i; and
 - a. Within 72 hours following each closing, except when the air lock is being used for multiple entries, then at least once per 72 hours, by verifying that the seal leakage is less than 0.005 La as determined by precision flow measurements when measured for at least 30 seconds with the volume between the seals at a constant pressure of greater than or equal to 10 psig;
 - By conducting overall air lock leakage tests at not less than Pa, 48 psig, and verifying the overall air lock leakage rate is within its limit.
 - 1) At least once per 6 months,# and
 - Prior To establishing CONTAINMENT H: TEGRITY when maintenance has been performed on the air lock that count affect the air lock sealing capability.*
 - At least once per 6 months by verifying that only one door in each air lock can be opened at a time.

#The provisions of Specification 4.0.2 are not applicable. *This represents an exemption to Appendix J. Paragraph III.D.2.(b)(ii), of 10 CFR Part \0.

WOLF CREEK - UNIT 1 3/4 6-5

ADMINISTRATIVE CONTROLS

PROCEDURES AND PROGRAMS (Continued)

- Limitations on the annual and quarterly air doses resulting from noble gases released in gaseous effluents to areas beyond the SITE BOUNDARY conforming to Appendix I to 10 CFR Part 50,
- Limitations on the annual and quarterly doses to a MEMBER OF THE PUBLIC from Iodine-131, Iodine-133, tritium and all radionuclides in particulate form with half-lives greater than 8 days in gaseous effluents released to areas beyond the SITE BOUNDARY conforming to Appendix I to 10 CFR Part 50,
- Limitations on the annual dose or dose commitment to any MEMBER OF THE PUBLIC due to releases of radioactivity and to radiation from uranium fuel cycle sources conforming to 40 CFR Part 190.
- f. Radiological Environmental Monitoring Program

A program shall be provided to monitor the radiation and radionuclides in the environs of the plant. The program shall provide (1) representative measurements of radioactivity in the highest potential exposure pathways, and (2) verification of the accuracy of the effluent monitoring program and modeling of environmental exposure pathways. The program shall (1) be contained in the ODCM, (2) conform to the guidance of Appendix I to 10 CFR Part 50, and (3) include the following:

- Monitoring, sampling, analysis, and reporting of radiation and radionuclides in the environment in accordance with the methodology and parameters in the ODCM.
- A Land Use Census to ensure that changes in the use of areas at and beyond the SITE BOUNDARY are identified and the modifications to the monitoring program are made if required by the results of this census, and
- 3) Participation in an Interlaboratory Comparison Program to ensure that independent checks on the precision and accuracy of the measurements of radioactive materials in environmental sample matrices are performed as part of the quality assurance program for environmental monitoring.

INSERT "A"

6.8.5 a. Explosive Gas and Storage Tank Radioactivity Monitoring Program

This program provides controls for potentially explosive gas mixtures contained in the WASTE GAS HOLDUP SYSTEM, the quantity of radioactivity contained in gas storage tanks, and the quantity of radioactivity contained in unprotected outdoor liquid storage tanks.

The program shall include:

- The limits for concentrations of hydrogen and oxygen in the WASTE GAS HOLDUP SYSTEM and a surveillance program to ensure the limits are maintained.
- A surveillance program to ensure that the quantity of radioactivity contained in each gas storage tank is less than the amount that would result in a whole body exposure of ≥0.5 rem to any individual in an UNRESTRICTED AREA in the event of an uncontrolled release of the tank's

WOLF CREEK UNIT 1

6-18

Amendment No. 42, 89

* Attachment IV to WO 95-0187 Page 7 of 7

INSERT "A"

i. Containment Leakage Rate Testing Program

A program shall be established to implement the leakage rate testing of the containment as required by 10 CFR 50.54(o) and 10 CFR 50, Appendix J, Option B, as modified by approved exemptions. This program shall be in accordance with the guidelines contained in Regulatory Guide 1.163, "Performance-Based Containment Leak-Test Program," dated September 1995.

The peak calculated containment internal pressure for the design basis loss of coolant accident, P_a , is 48 psig.

The maximum allowable containment leakage rate, L_a , at P_a , shall be 0.20% of containment air weight per day.

Leakage rate acceptance criteria are:

- a. Containment leakage rate acceptance criterion is $\leq 1.0 L_a$. During the first unit startup following testing in accordance with this program, the leakage rate acceptance criteria are $\leq 0.60 L_a$ for the Type B and C tests and $\leq 0.75 L_a$ for Type A tests;
- b. Air lock testing acceptance criteria are:
 - 1) Overall air lock leakage rate is $\leq 0.05 L_a$ when tested at $\geq P_a$;
 - 2) For each door, leakage rate is \leq 0.005 $\rm L_a$ when pressurized to \geq 10 psig.

The provisions of Technical Specification 4.0.2 do not apply to the test frequencies specified in the Containment Leakage Rate Testing Program.

The provisions of Technical Specification 4.0.3 are applicable to the Containment Leakage Rate Testing Program.