TENNESSEE VALLEY AUTHORITY CHATTANCOGA TENNESSTE 3740" 500C Chestnut Street Tower II MAR 21 1979 Harold R. Denton, Director Office of Nuclear Reactor Regulation U.S. Nuclear Regulatory Commission Washington, DC 20555 Dear Mr. Denton: ) Docket Nos. STN 50-518 In the Matter of the Application of STN 50-519 Tennessee Valley Authority. STN 50-520 STN 50-521 STN 50-553 STN 50-554 STN 50-566 STN 50-567 For piping to be embedded in concrete at TVA's Hartsville, Phipps Bend, and Yellow Creek Nuclear Plants, a conflict exists between ACI Standard 318-71 and mechanical piping codes, such as, ANSI B31.1, and ASME Section III. The conflict involves minimum test pressures and holding times for leak testing of piping to be embedded in concrete. A typical leak test requirement from ANSI B31.1 and ASME Section III requires a minimum test pressure of 1.5 times the design pressure to be maintained for a minimum of 10 minutes. However, ACI 318-71 Section 6.3.2.4 requires leak testing to be performed at a test pressure of 1.5 times the design pressure, with a minimum of 150 psig to be maintained for four hours. TVA believes the leak test requirements, for pressure and time identified in the mechanical piping codes, are sufficiently conservative for leak testing of piping to be embedded in concrete. The leak test requirements specified in ACI-318 will be adopted where no piping code or standard applies. TVA PSAR's typically state, when referring to ACI-318 for construction of structures, that "modifications to these codes, standards, and specifications are made where necessary to meet the specific requirements of the structures." Also for additional consideration, we are providing the enclosure, a copy of a February 1, 1979, letter to the Secretary of the Commission from the ACI-349 Committee. This letter proposes a revision to ACI-349-76 which agrees with TVA's position on leak testing of piping to be embedded in concrete. 7903290009 AT INC. I INCOME AT STREET