

LIMITING CONDITIONS FOR OPERATION

SURVEILLANCE REQUIREMENT

3) Type C Tests

Type C tests shall be performed during each reactor shutdown for major refueling or other convenient interval but in no case at intervals greater than two years.

4) Additional Periodic Tests

Additional purge system isolation valve leakage integrity testing shall be performed at least once every three months in order to detect excessive leakage of the purge isolation valve resilient seats. The purge system isolation valves will be tested in three groups, by penetration: drywell purge exhaust group (CV-4302 and CV-4303), torus purge exhaust group (CV-4300 and CV-4301), and drywell/torus purge supply group (CV-4307, CV-4308 and CV-4306).

e. Seal Replacement

The T-ring inflatable seals for purge isolation valves CV-4300, CV-4301, CV-4302, CV-4303, CV-4306, CV-4307 and CV-4308 shall be replaced at intervals not to exceed four years.

The baseline for this requirement shall be established during the 1982 refueling outage.

f. Containment Modification

Any major modification, replacement of a component which is part of the primary reactor containment boundary, or resealing a seal-welded door, performed after the preoperational leakage rate test shall be followed by either a Type A, Type B, or Type C test, as applicable, for the area affected by the modification.

8411010101 841010
PDR ADOCK 05000331
PDR

LIMITING CONDITIONS FOR OPERATION

SURVEILLANCE REQUIREMENT

The measured leakage from this test shall be included in the test report. The acceptance criteria as appropriate, shall be met. Minor modifications, replacements, or resealing of seal welded doors, performed directly prior to the conduct of a scheduled Type A test do not require a separate test.

g. Reporting

100

Periodic tests shall be the subject of a summary technical report submitted to the Commission approximately 3 months after the conduct of each test. The report will be titled "Reactor Containment Integrated Leakage Rate Test."

106

The results of the periodic testing performed to satisfy the requirements of 4.7.A.2.d.4 shall be reported with the summary technical report prepared to provide the results of the testing performed in accordance with Section 4.7.A.2.d.3.

100