

Document No.

**ALPHA-604**


Document Title

**PANDA Transient Tests**

**M3A Integral System Test  
Apparent Test Results**

Revision Status						
Rev.	Prepared / Revised by	Approval / Date			Issue Date	Remarks
		P-PM	G-PM	G-SQR		
0	C. Aubert	<i>J. Torbeck</i> 28-III-96	J. Torbeck 28 March 96	G. Wingate 28 March 96	29 March 96	G-PM & G-SQR approvals on file (P-ERM-36, p.2)



 <b>PAUL SCHERRER INSTITUT</b>		Registrierung TM-42-96-06 ALPHA-604-0
Titel	<b>PANDA Transient Tests          M3A Integral System Test          Apparent Test Results</b>	
Autoren/ Autorinnen	C. Aubert, J. Dreier, O. Fischer, M. Huggenberger, S.Lomperski, H.J. Strassberger	
		Ersetzt ---
		Erstellt 26.03.96

**Summary:**

This Apparent Test Results (ATR) report is compiled in accordance with the requirements specified in the Test Plan (TP) 25A5764R2 (GE document) section 10. The report covers the results for the PANDA Transient Test M3A. The ATR summarizes the apparent results and includes: test number, test objective, test date and time, data recording period, data analysis period, name of data file and ORACLE data tables, list of failed or unavailable instruments considered to be required for the test, list of required instruments with zero or reference check points not in tolerance or in over-range or under-range during test, deviations from test procedure and problems which occurred during test. Statements are made whether or not the test objective has been reached and the data were recorded correctly. A table of actual initial conditions based on average and standard deviation over one minute time period just before the test start for all parameters with a specified acceptance criteria in section 9.2 of TP is provided as well as time history plots over test duration for all top priority measurements.

Verteiler	Abt.	Empfänger/Empfängerinnen	Expl.	Abt.	Empfänger/Empfängerinnen	Expl.		Expl.
	42	G. Yadigaroglu G. Varadi C. Aubert T. Bandurski J. Dreier O. Fischer J. Heilzer M. Huggenberger S. Lomperski H.J. Strassberger PANDA Documentation	1 1 1 1 1 1 1 1 1 1 2		<u>GE San Jose CA</u> J.E. Torbeck (for distribution at GE to J.R. Fitch, G.A. Wingate, B.S. Shiralkar, DRF No. T10-00005)	1	Bibliothek Reserve Total Seiten Beilagen Informationsliste D 1 2 3 4 5 8 9 A Visum Abt./Laborleitung:	6 19 22 -

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

<b>Contents:</b>	<b>Page</b>
1. Test Objectives	5
2. Reference Documents	5
3. Test Date/Time	5
4. Data Recording Period	5
5. File Names	5
6. ORACLE Data Tables	5
7. RPV Power Curve	6
8. Test Instrumentaion	6
9. Deviations from Test Procedure	6
10. List of Deviations from Reuquested Initial Conditions	7
11. Test Processing	7
12. Water Temperature for PCC Pool Refilling	7
13. Requested Initial Conditions	7
Data Analysis Period for Initial Conditions	7
Environment Parameters	8
RPV Parameters	8
DRYWELL Parameters	8
SUPPRESSION CHAMBER Parameters	9
GDCS Parameters	10
PCC1 Pool Parameters	11
PCC2 Pool Parameters	11
PCC3 Pool Parameters	12
14. Graphs	
M3A Test - Vacuum Breaker Opening	13
M3A Test - RPV, Drywell and Wetwell Pressures	14
M3A Test - Drywell and Wetwell Air Partial Pressures	15
M3A Test - RPV Heater Power	16
M3A Test - RPV and Drywell Temperatures	17
M3A Test - Wetwell Temperatures	18
M3A Test - PCC Lower Drum and GDCS Return Line Water Temperatures	19
M3A Test - PCC Vent Line Gas Temperatures	20
M3A Test - PCC Main Steam Line & PCC Feed Line Flows	21
M3A Test - PCC Pool Refilling	22

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS

TEST M3A

**1. TEST OBJECTIVES:**

The objectives of the PANDA integral system tests are to provide additional data to: a) confirm the capability of TRACG to predict SBWR containment system performance, including potential systems interaction effects (*Integral System Tests*) and b) demonstrate startup and long-term operation of a passive containment cooling system (*Concept Demonstration*).

The specific objective of test M3A which was conducted with nominal post-LOCA conditions after a Main Steam Line Break is to establish the base case and demonstrate transient system response and repeatability.

**2. REFERENCE DOCUMENTS:**

Test Plan: GE document 25A5764R2  
Test Procedure: ALPHA-520-2

**3. TEST DATE/TIME:**

Test Start: 25-OCT-95 / 22:46:42  
Test Stop: 26-OCT-95 / 18:54:57  
Test Duration: 20:08:15  
Test Period: 0 to 72495 sec

**4. DATA RECORDING PERIOD:**

Start: 25-OCT-95 / 22:35:50  
Stop: 26-OCT-95 / 18:54:57  
Data Recording Period: -652 to 72495 sec

**5. FILE NAMES:**

Raw Data: panda\_M3A.dat  
DAS-Configuration / Channel List: kbt99999999.o12

**6. ORACLE DATA TABLES:**

PANDA\_M3A\_MT\_LINE  
PANDA\_M3A\_MT\_POOL  
PANDA\_M3A\_MT\_REF  
PANDA\_M3A\_MT\_VESSEL  
PANDA\_M3A\_M\_OTHER  
PANDA\_M3A\_M\_TIME  
PANDA\_M3A\_KBT  
INFO\_TESTS

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS

TEST M3A

**7. RPV POWER CURVE:**

Power analysis<sup>1</sup> period: 20 to 72495 sec

Maximum negative deviation:

Maximum positive deviation:

Standard deviation:

Power curve tolerance: +25.0 [kW]

Definition of RPV power deviation ( $\Delta$ Power) and standard deviation ( $\sigma$ ):

$$\Delta \text{Power} = \text{Power}_{\text{th}} - \sum_{j=1}^6 \text{MW.RP.j}$$

$$\sigma = \sqrt{\frac{1}{n} \sum_{k=1}^n \left( \text{Power}_{\text{th}}^k - \sum_{j=1}^6 \text{MW.RP.j}^k \right)^2}$$

$\text{Power}_{\text{th}}$ : theoretical power

$\sum_{j=1}^6 \text{MW.RP.j}$ : measured power

$n$ : # of measurements throughout the test

**8. TEST INSTRUMENTATION**

**LIST OF FAILED OR UNAVAILABLE REQUIRED INSTRUMENTS:**

Air partial pressure in DW1	MPG.D1.3	Back-up instrument: MPG.D1.2
Air partial pressure in DW2	MPG.D2.3	Back-up instrument: MPG.D2.2

**LIST OF REQUIRED INSTRUMENTS WITH ZERO NOT IN TOLERANCE OR OVER-RANGE OR UNDER-RANGE DURING TEST:**

None

**9. DEVIATIONS FROM TEST PROCEDURE:**

Non

<sup>1</sup> The power curve analysis has been performed without considering power spikes due to switching between rod groups (see NCR p-013).

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

**10. LIST OF DEVIATIONS FROM REQUESTED INITIAL CONDITIONS:**

**11. TEST PROCESSING**

**PROBLEMS:**

None

**HAS THE TEST OBJECTIVE BEEN REACHED:**

Yes

**HAVE THE DATA BEEN CORRECTLY RECORDED:**

Yes

**12. WATER TEMPERATURE FOR PCC POOL REFILLING**

**13. REQUESTED INITIAL CONDITIONS**

**DATA ANALYSIS PERIOD FOR INITIAL CONDITIONS:**

Data analysis period: -212 to -152 sec

Initial conditions are calculated over one minute just before connection of Drywells to RPV (phase n°123.9 of Test Procedure)

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS

TEST M3A

TABLE OF INITIAL CONDITIONS

VARIABLE	PROCESSID	UNIT	Average Value	Standard Deviation	Requested Tolerance Value
----------	-----------	------	---------------	--------------------	---------------------------

ENVIRONMENT PARAMETERS

Atmospheric pressure	MP.EN	bar			
Temperature of saturation for atmospheric pressure ( $T_{sat\_EN}$ )		C			

RPV PARAMFTERS

Total pressure	MP.RP.1	bar			
Fluid temperatures:					
Spatial average	$TF_{mean}(RP)$	C			
Local	MTF.RP.1	C			
	MTF.RP.2	C			
	MTF.RP.3	C			
	MTF.RP.4	C			
	MTF.RP.5	C			
Water level	ML.RP.1	m			

DRYWELL PARAMETERS Total pressure  
2.94 +/- 0.19

Air partial pressure	MPG.D1.1	bar			
	MPG.D1.2	bar			
	MPG.D2.1	bar			
	MPG.D2.2	bar			

Gas temperatures:

Spatial average	$TG_{mean}(D1)$	C			
Local	MTG.D1.1	C			
	MTG.D1.2	C			
	MTG.D1.3	C			
	MTG.D1.4	C			
	MTG.D1.5	C			
	MTG.D1.6	C			

\* The Drywell total pressures are not independant variables, they are given by temperatures and air partial pressures. The corresponding tolerance is calculated from temperature and gas partial pressure tolerances.



PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS

TEST M3A

TABLE OF INITIAL CONDITIONS (Cont'd)

VARIABLE	PROCESSID	UNIT	Average Value	Standard Deviation	Requested Value	Tolerance
----------	-----------	------	---------------	--------------------	-----------------	-----------

DRYWELL PARAMETERS (Cont'd)

Gas temperatures:

Spatial average	TG_mean(D2)	C				
Local	MTG.D2.1	C				
	MTG.D2.2	C				
	MTG.D2.3	C				
	MTG.D2.4	C				
	MTG.D2.5	C				
	MTG.D2.6	C				
Water level	ML.D1	m				
	ML.D2	m				

SUPPRESSION CHAMBER PARAMETERS

Total pressure	MP.S1	bar				
partial pressure	MPG.S1	bar				
	MPG.S2	bar				

Water temperatures:

Spatial average	TW_mean(S1)	C				
Local	MTL.S1.1	C				
	MTL.S1.2	C				
	MTL.S1.3	C				
	MTL.S1.4	C				
	MTL.S1.5	C				
	MTL.S1.6	C				
Spatial average	TW_mean(S2)	C				
Local	MTL.S2_1	C				
	MTL.S2.2	C				
	MTL.S2.3	C				
	MTL.S2.4	C				

TABLE OF INITIAL CONDITIONS (Cont'd)

\*\*The Suppression Chamber air partial pressures are not independent variables, they are given by temperatures and total pressures. The corresponding tolerance is calculated from temperature and total pressure tolerances.

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS

TEST M3A

VARIABLE	PROCESSID	UNIT	Average Value	Standard Deviation	Requested Value	Tolerance
----------	-----------	------	---------------	--------------------	-----------------	-----------

SUPPRESSION CHAMBER PARAMETERS (Cont'd)

Water Temperatures:

	MTL.S2.5	C
	MTL.S2.6	C

Gas temperatures:

Spatial average	TG_mean(S1)	C
-----------------	-------------	---

Gas temperatures:

Local	MTG.S1.1	C
	MTG.S1.2	C
	MTG.S1.3	C
	MTG.S1.4	C
	MTG.S1.5	C
	MTG.S1.6	C

Spatial average	TG_mean(S2)	C
-----------------	-------------	---

Local	MTG.S2.1	C
	MTG.S2.2	C
	MTG.S2.3	C
	MTG.S2.4	C
	MTG.S2.5	C
	MTG.S2.6	C

Water level	ML.S1	m
	ML.S2	m

GDCS PARAMETERS

Total pressure	MP.GD	bar
----------------	-------	-----

Fluid temperatures:

Spatial average	TF_mean(GD)	C
-----------------	-------------	---

Local	MTF.GD.1	C
	MTF.GD.2	C
	MTF.GD.3	C

TABLE OF INITIAL CONDITIONS (Cont'd)

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS

## TEST M3A

VARIABLE	PROCESSID	UNIT	Average Value	Standard Deviation	Requested Value	Tolerance
----------	-----------	------	---------------	--------------------	-----------------	-----------

GDCS PARAMETERS (Cont'd)

	MTF.GD.4	C				
	MTF.GD.5	C				
	MTF.GD.6	C				
	MTF.GD.7	C				
Water level	ML.GD	m				

PCC1 PARAMETERS

Water temperatures:

Spatial average	tw_mean(U1)	C				
Local	MTL.U1.1	C				
	MTL.U1.2	C				
	MTL.U1.3	C				
	MTL.U1.4	C				
	MTL.U1.5	C				
	MTL.U1.6	C				
	MTL.U1.7	C				
Water level	ML.U1	m				

PCC2 PARAMETERS

Water temperatures:

Spatial average	tw_mean(U2)	C				
Local	MTL.U2.1	C				
	MTL.U2.2	C				
	MTL.U2.3	C				
	MTL.U2.4	C				
	MTL.U2.5	C				
	MTL.U2.6	C				
	MTL.U2.7	C				
Water level	ML.U2	m				

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS

TEST M3A


TABLE OF INITIAL CONDITIONS (Cont'd)

VARIABLE	PROCESSID	UNIT	Average Value	Standard Deviation	Requested Value	Tolerance
----------	-----------	------	---------------	--------------------	-----------------	-----------

PCC3 PARAMETERS


Water temperatures:

Spatial average	tw_mean(U3)	C				
Local	MTL.U3.1	C				
	MTL.U3.2	C				
	MTL.U3.3	C				
	MTL.U3.4	C				
	MTL.U3.5	C				
	MTL.U3.6	C				
	MTL.U3.7	C				
	MTL.U3.8	C				
	MTL.U3.9	C				
	MTL.U3.10	C				
	MTL.U3.11	C				
	MTL.U3.12	C				
	MTL.U3.13	C				
	MTL.U3.14	C				
	MTL.U3.15	C				
	MTL.U3.16	C				
	MTL.U3.17	C				
	MTL.U3.18	C				
	MTL.U3.19	C				
Water level	ML.U3	m				




PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A




# M3A Test – Drywell and Wetwell Air Partial Pressures




PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A






# M3A Test – RPV and Drywell Temperatures




PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A




# M3A Test – PCC Lower Drum and GDCS Return Line Water Temperatures




PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A



# M3A Test – Main Steam Line & Feed Line Flows



PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

PANDA INTEGRAL SYSTEM TEST  
APPARENT TEST RESULTS  
TEST M3A

M3A Test - PCC Pool Water Level

