- F. A sample of reactor conlant shall be analyzed at least every 72 hours for the purpose of determining the content of chloride ion and to check the conductivity.
- *G. Primary Coofant System Pressure Isolation Valves
 Specification:
 - 1. Periodic leakage testing (a) on each valve listed in table 4.3.1 shall be accomplished prior to exceeding 600 psig reactor pressure every time the plant is placed on the cold shutdown condition for refueling, each time the plant is placed in a cold shutdown condition for 72 hours if testing has not been accomplished in the preceding 9 months, and prior to returning the valve to service after maintenance, repair or replacement work is performed.

H. Reactor Coolant System Leakage

- Unidentified leakage rate shall be monitored at least once every 4 hours.
- Total leakage rate (identified and unidentified) shall be monitored at least once every 8 hours.
- A channel calibration of the primary containment sump flow integrator and the primary containment equipment drain tank flow integrator shall be conducted at least once per 18 wonths.

⁽a) To satisfy ALARA requirements, leakage may be measured indirectly (as from the performance of pressure indicators) if accomplished in accordance with approved procedures and supported by computations showing that the method is capable of demonstrating valve compliance with the leakage criteria.

Mr. P. B. Fiedler Oyster Creek Nuclear Generating Station Oyster Creek Nuclear Generating Station

cc: G. F. Trowbridge, Esquire Shaw, Pittman, Potts and Trowbridge 1800 M Street, N.W. Washington, D.C. 20036

J.B. Liberman, Esquire Bishop, Liberman, Cook, et al. 1155 Avenue of the Americas New York, New York 10036

Regional Administrator, Region I U.S. Nuclear Regulatory Commission 631 Park Avenue King of Prussia, Pennsylvania 19406

BWR Licensing Manager GPU Nuclear 100 Interpace Parkway Parsippany, New Jersey 07054

Deputy Attorney General State of New Jersey Department of Law and Public Safety 36 West State Street - CN 112 Trenton, New Jersey 08625

Mayor Lacey Township 818 West Lacey Road Forked River, New Jersey 08731

D. G. Holland Licensing Manager Oyster Creek Nuclear Generating Station Post Office Box 388 Forked River, New Jersey 08731 Resident Inspector c/o U.S. NRC Post Office Box 445 Forked River, New Jersey 08731

Commissioner
New Jersey Department of Energy
101 Commerce Street
Newark, New Jersey 07102

Eugene Fisher, Assistant Director Division of Environmental Quality Department of Environmental Protection 380 Scotch Road Trenton, New Jersey 08628