

Walter S. Wilgus Vice President Nuclear Operations

May 9, 1988 3F0588-06

U.S. Nuclear Regulatory Commission Attention: Document Control Desk Washington, D.C. 20555

Subject: Crystal River Unit 3 Docket No. 50-302 Operating License DPR-72 ULITIMATE HEAT SINK TEMPERATURE

Dear Sir:

Florida Power Corporation's (FPC) letter dated November 16, 1987 (3F1187-18) committed not to operate Crystal River Unit 3 (CR-3) with a seawater (Ultimate Heat Sink) temperature greater that 85°F until technical justification of a higher temperature could be provided. This letter provides the justification for raising the Ultimate Heat Sink temperature limit for CR-3 to 92°F. FPC commits to operate CR-3 with a maximum seawater temperature of 92°F. If the seawater temperature exceeds 92°F, the action statement of Technical Specification 3.7.5 will be implemented.

FPC has worked with our architect-engineer, Gilbert Commonwealth, Inc. (G/C, Inc.) and other vendors to varify the operability of components cooled by the Nuclear Services Closed Cycle Cooling System (SW) and the Decay Heat Closed Cycle Cooling System (DC) both of which reject heat to the Nuclear Service and Decay Heat Seawater System (NW). Methods employed include system transient thermal analyses, flow balance testing, verification of component operability at SW system and DC system temperatures above  $105^{\circ}F$ , and an extensive search of the historical seawater temperature data, to demonstrate that when the seawater did exceed  $85^{\circ}F$ , sufficient margin still existed to assure that the system performed within equipment design limits.

The original design requirements of the SW system and the DC system limited the maximum allowable temperature to  $105^{\circ}F$  following an accident, based on a RW temperature of  $85^{\circ}F$ . To envelop the worst case RW temperature ever recorded at CR-3 (90.5°F) and to ensure that all required analyses would not have to be repeated in the future, FPC directed G/C, Inc. to assume a RW temperature of  $95^{\circ}F$  for all SW and DC systems thermal analyses.

8805170227 880509 PDR ADOCK 05000302 P DCD

May 9, 1988 3F0588-06 Page 2

With the temperature of the RW system fixed, transient temperature profiles were developed for both the SW and the DC system as a function of time. These worst case analyses established peak temperatures of  $110^{\circ}$ F and  $120^{\circ}$ F for the SW and DC systems, respectively. FPC has received confirmation from all of its vendors who supplied equipment serviced by either the SW system or the DC system that their equipment meets all design requirements with the increased temperatures. Consequently, CR-3 has never operated in an unsafe condition.

FPC has reviewed ten (10) years of historical plant data on the intake canal water temperature to quantify the worst case RW temperature experienced to date. FPC measures and logs intake and discharge canal water temperature on an hourly basis to satisfy U.S. Environmental Protection Agency (EPA) requirements. The temperature recorded is an average of four (4) thermocouples located at the condenser water box inlet, each thermocouple is calibrated every six (6) months to an accuracy of  $\pm 0.5^{\circ}$ F. A review of this data showed the intake canal water temperature has averaged 85.9°F and 85.5°F during the months of July and August, respectively. Intake canal water temperature peaked at 90.5°F for only three (3) hours during the same ten year period.

To assure CR-3 would not have operated outside its design limits, a thermal analysis was performed to determine the maximum RW inlet temperature which could occur while maintaining the SW system at or below  $105^{\circ}$ F. This maximum RW temperature was determined to be  $92.4^{\circ}$ F. Since CR-3 has not experienced a RW temperature in excess of  $90.5^{\circ}$ F, the 3W system will not operate outside its design limits. FPC is working with G/C, Inc. to determine the comparable RW temperature for the DC system. Since this temperature will be less than the  $95^{\circ}$ F RW limit used to establish the  $120^{\circ}$ F operability limit of the DC system certified by our suppliers, FPC considers it acceptable to operate CR-3 at a seawater temperature of less than, or equal to  $92^{\circ}$ F. The evaluation of the DC system will be completed by July 29, 1988 and FPC will advise the NRC of the results.

During the evaluation of equipment serviced by either the SW system or the DC system, FPC determined the performance of the control complex water chillers (CHHE-1A, 1B) is affected by SW cooling water temperature. Although the chillers will be capable of performing their safety function, the increased SW temperature may result in a phenomenon called "surge." As SW temperature rises, the load requirement on the chiller to maintain stable operation and to prevent "surge" increases. If the non-essential loads now supplied by the control complex water chillers were inadvertently isolated following a LOCA, the load on the chiller would not be sufficient for stable operation. To avoid this remote possibility, FPC will install a "hot-gas bypass" on the chillers. This device puts a false load on the chiller compressor to stabilize operation should building heat load fall below minimum required levels. FPC is working with our chiller supplier to establish equipment qualification and delivery schedules so that a qualified hot-gas bypass can be added to the chillers. We will advise the NRC by June 10, 1988 when the

May 9, 1988 3F0588-06 Page 3

181

1 ...

hot-gas bypass hardware will be installed on the CR-3 control complex water chillers.

FPC is developing test procedures to verify the service water heat exchangers performance is within the assumptions used in the thermal analyses. Testing will be performed by July 18, 1988.

These actions complete those items discussed in the Confirmation of Action letter (NRC letter dated November 17, 1987) on these subjects.

Sincerely,

W. S. Wilgus, Vice President Nuclear Operations

WSW/JWT/sdr

xc: Dr. J. Nelson Grace Regional Administrator, Region II

> Mr. T. F. Stetka Senior Resident Inspector