

Duquesne Light Company

Beaver Valley Power Station
P.O. Box 4
Shippingport, PA 15077-0004

SUSHIL C. JAIN
Senior Vice President
Nuclear Services
Nuclear Power Division

October 13, 1998
L-98-191

(412) 393-5512
Fax (724) 643-8069

U. S. Nuclear Regulatory Commission
Attention: Document Control Desk
Washington, DC 20555-0001

Subject: Beaver Valley Power Station, Unit No. 2
Docket No. 50-334, License No. DPR-66
Response to NRC Generic Letter No. 96-01

Reference: 1. BVPS Unit 1's Response to Generic Letter 96-01, S. C. Jain to USNRC, November 5, 1997
2. Response to Generic Letter 96-01, S. C. Jain to USNRC, April 4, 1996
3. Generic Letter 96-01 Plan for Reportable Conditions, T. Noonan to USNRC, April 23, 1996, NPD1VPO:0465

This letter confirms completion of the requested actions of Generic Letter 96-01 for Beaver Valley Power Station (BVPS) Unit 2. These actions were completed, as scheduled, prior to the completion of the first refueling outage for BVPS Unit 2 following January 10, 1997, and included the following instrumentation:

- The Reactor Protection System, *BVPS Technical Specification 4.3.1.1.1*
- Emergency Diesel Generator Load Shedding and Sequencer and, *BVPS Technical Specification 4.8.1.1.2*
- Engineered Safety Features Actuation System, *BVPS Technical Specification 4.3.2.1.1*

These actions included a comparison of electrical schematic drawings and logic diagrams against plant surveillance test procedures to ensure that all portions of the logic circuitry, including the parallel logic, interlocks, bypasses and inhibit circuits were covered by surveillance procedures to fulfill the Technical Specification requirements.

Appropriate testing was conducted to address deficiencies identified during the review to ensure compliance with the requirements of the Technical Specifications.

9810210077 981013
PDR ADOCK 05000334
P PDR



11
A067

Reportable testing deficiencies identified during the review were reported in the following Unit 2 Licensee Event Reports (LERs):

LER 96-003-00	LER 96-003-01	LER 98-008-02
LER 98-008-00	LER 98-008-01	LER 98-008-03


Testing deficiencies for BVPS Unit 2 that were reported as a result of the BVPS Unit 1 review were:

LER 1-96-004-01	LER 1-96-004-02
LER 1-96-004-04	LER 1-97-001-03

Closure of issues identified during the review is being addressed through the Condition Report program.

If you have any questions concerning this response, please contact Mr. Sam Hobbs, Director, Safety & Licensing Department at (412) 393-5203.

Sincerely,



Sushil C. Jain

c: Mr. D. S. Brinkman, Sr. Project Manager
Mr. D. M. Kern, Sr. Resident Inspector
Mr. H. J. Miller, NRC Region I Administrator

