

## CONTAINMENT SYSTEMS

### CONTAINMENT COOLING SYSTEM

#### LIMITING CONDITION FOR OPERATION

---

---

3.6.2.2 Two independent groups of containment cooling fans shall be OPERABLE with two fan systems to each group.

APPLICABILITY: MODES 1, 2, 3, and 4.

#### ACTION:

With one group of the above required containment cooling fans inoperable, restore the inoperable group of cooling fans to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours; restore the inoperable group of containment cooling fans to OPERABLE status within the next 48 hours or be in COLD SHUTDOWN within the following 30 hours.

#### SURVEILLANCE REQUIREMENTS

---

---

4.6.2.2 Each group of containment cooling fans shall be demonstrated OPERABLE:

- a. At least once per 31 days by:
  1. Starting each fan group not already running from the control room and verifying that each fan group operates for at least 15 minutes.
  2. Verifying a cooling water flow rate of greater than or equal to 625 gpm to each cooler.
- b. At least once per 18 months by:
  1. Verifying that each fan group starts automatically on an SIAS test signal.
  2. Verifying a cooling water flow rate of greater than or equal to 1325 gpm to each cooler.

ATTACHMENT B

## CONTAINMENT SYSTEMS

### CONTAINMENT COOLING SYSTEM

#### LIMITING CONDITION FOR OPERATION

---

---

3.6.2.2 Two independent groups of containment cooling fans shall be OPERABLE with ~~two~~ fan systems to each group.

APPLICABILITY: MODES 1, 2, 3, and 4.

#### ACTION:

With one group of the above required containment cooling fans inoperable, restore the inoperable ~~group of~~ cooling fans to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours; restore the inoperable ~~group of~~ containment cooling fans to OPERABLE status within the next 48 hours or be in COLD SHUTDOWN within the following 30 hours.

#### SURVEILLANCE REQUIREMENTS

---

---

4.6.2.2 Each group of containment cooling fans shall be demonstrated OPERABLE:

- a. At least once per 31 days by:
  1. Starting each fan group not already running from the control room and verifying that each fan group operates for at least 15 minutes.
  2. Verifying a cooling water flow rate of greater than or equal to 625 gpm to each cooler.
- b. At least once per 18 months by:
  1. Verifying that each fan group starts automatically on an SIAS test signal.
  2. Verifying a cooling water flow rate of greater than or equal to 1325 gpm to each cooler.