

FINAL REPORT

MAIN STEAM ISOLATION VALVE

3-WAY DUAL SOLENOID VALVE FAILURES

December 30, 1987

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1. Executive Summary	2
2. Introduction	5
A. Brief Description of Applicable Systems	5
B. Purpose and Scope of the Recovery Effort	7
C. Brief Description of Report Contents	7
3. October 29 and November 3 Event Description	8
A. Chronology of Events	8
B. Troubleshooting Activities	9
C. Data Analysis and Root Cause Determination	11
D. Corrective Actions	12
E. Safety Evaluation/Significance	20
F. Conclusion	24
4. November 29 Event Description	26
A. Chronology of Events	26
B. Troubleshooting Activities	27
C. Data Analysis and Root Cause Determination	31
D. Corrective Actions	34
E. Safety Evaluation/Significance	35
F. Conclusion	36
5. Overall Conclusion	37
6. Diagram 1 3-Way Dual Solenoid	
Diagram 2 Energized & Deenergized Solenoid Valve	
Diagram 3 Physical Arrangement of MSIV Lines	
Appendix A: Photos of Affected Solenoid Components	
Appendix B: Analysis Plan for EPDM Solenoid Components	
Appendix C: Foreign Material From Solenoid Plunger Area	
Microscopic Evaluations: Ricera, Inc.	
Appendix D: Summary of Instrument Air Testing	
Appendix E: Baseline Temperatures	

Executive Summary

Executive Summary

This report summarizes the findings and conclusions resulting from investigations following Main Steam Isolation Valve (MSIV) failures on October 29, November 3 and November 29, 1987.

Initial Event

On October 29, 1987 the Perry Nuclear Power Plant was completing the final stages of the Startup Test Program. One of these tests involved fast closing a Main Steam Isolation Valve (MSIV). During this test, the valve (1B21-F022D) failed to stroke closed within the required time. All other MSIVs (7) were cycled in order to verify adequate stroke times. Two of the other MSIVs failed to satisfy the required stroke time (1B21-F028D, 1B21-F028B).

The three valves that initially failed were stroked satisfactorily upon subsequent demand. The problem was attributed to a one time deposit of debris in the respective solenoids which was exhausted as shown by the subsequent successful strokes. The debris was believed to have caused a delay in the solenoid responses. Based upon a satisfactory stroke, the valves were considered Operable and startup testing resumed. Plant management decided to perform the MSIV stroke tests again prior to the last startup test, the full MSIV isolation scram. This approach was discussed with NRC Region III.

On November 3, in preparation for the final startup test, additional stroke timing tests of MSIVs were performed. During the first stroke attempt, two of the same MSIVs (1B21-F022D, 1B21-F028D) that previously stroked slowly, again failed to close within the required time. The valves were subsequently recycled satisfactorily within minutes of their first tests. However, because the valves again failed to meet the required closure time on the first attempt, the basis for an isolated failure was no longer considered valid. NRC Region III was informed of the problem. The decision was made to shutdown the plant and troubleshoot the problem.

On November 4, an NRC Augmented Inspection Team (AIT) arrived on site. A troubleshooting plan was established and implemented. The air actuators of the three valves which had exhibited slow closing times were disassembled and the inspection results documented. The conclusion drawn is that the dual solenoids exhibited sluggish action after operating in localized high temperature conditions. It is believed that steam leaks caused an elevated temperature environment in the vicinity of the solenoids. The elevated temperatures degraded the Ethylene Propylene Diene Monomer (EPDM) material causing the solenoid to stick or to be sluggish. Corrective actions included replacing or rebuilding all 8 MSIV dual solenoids and implementing additional testing. Repair work and necessary retests were completed satisfactorily and plant startup conducted on November 13.

Second Event

On November 29, the plant was conducting periodic stroke tests of the MSIV in accordance with commitments originating from the previous event. The tests were performed by fully closing each MSIV individually utilizing the test solenoid, followed by placing the control switch to the "close" position. Performance of this test verifies proper operation of the MSIV dual solenoid, since the MSIV will only remain closed if the dual solenoid de-energizes and properly repositions.

During this test, the 1B21-F022B valve failed to remain closed after two separate attempts using the sequence described above. In accordance with commitments documented in our letter, PY-CEI/OIE-0289 L dated November 13, 1987, the plant was shutdown and notifications made to the NRC Operations Center and Senior Resident Inspector. The remaining seven MSIVs satisfactorily passed the test requirements.

On November 29 and 30, an NRC Augmented Inspection Team (AIT) arrived onsite. A troubleshooting plan was established and implemented. The plan included various MSIV solenoid valve disassemblies, visual inspection of valve parts, chemical analysis of as found materials, Instrument Air System analysis and microscopic examinations. The root cause analysis conclusion is that a sliver of foreign material, discovered in the 1B21-F022B solenoid valve body, caused mechanical binding of the valve.

This binding caused the solenoid to remain in the normally energized position, after it was verified that the solenoid was deenergized, which then prevented air bleed off from the MSIV actuator and valve (MSIV) closure. The foreign material was Ethylene Propylene Diene Monomer (EPDM) which was demonstrated to have come loose during previous valve rebuild activity. Corrective actions included complete replacement of all MSIV solenoid valves with new valves. Replacement work and necessary retests were completed satisfactorily and plant startup performed on December 9.

Introduction

Introduction

A. Brief Description of Applicable Systems

Perry Nuclear Power Plant is a boiling water reactor supplied by the General Electric Company and designated BWR/6 with a Mark III containment. The main steam system consists of four main steam lines (A, B, C, and D) each consisting of a flow restrictor and two redundant Main Steam Isolation Valves (MSIVs) (see Diagram 3). The combination of two MSIVs in each steam line provides a highly reliable means of isolating the reactor vessel to minimize the loss of reactor coolant inventory and to limit the release of radioactive materials. The inboard valves are labeled 1B21-F022A-D and the outboard valves 1B21-F028A-D. The upper end of each valve's stem is attached to an actuator with a combination air cylinder/dashpot. The cylinder provides the motive force to open and close the valve, while the dashpot controls the speed of valve operation. The hydraulic dashpot consists of an oil filled cylinder, hydraulic piston, two external speed control valves and piping. The valve actuator also contains helical springs which provide valve closing force.

The MSIVs are opened by air pressure supplied by the Instrument Air System. Air pressure is directed to the bottom of the air cylinder in the opening operation by the positioning of various control valves. To close an MSIV, air pressure is applied to the top of the air cylinder piston while air is bled off the bottom of the piston.

The solenoid valve which directs air pressure to and from the MSIV actuator during fast closure is an ASCO 3-way dual solenoid (Model NP8323A20E; see Diagrams 1 and 2). When deenergized, the core assembly and seat of solenoid A are held against the inlet port orifice by the core spring. The core assembly also forces the disc holder subassembly down, compressing the disc holder spring of solenoid B and unseating the disc from the exhaust port orifice. This allows air to pass from the cylinder through the exhaust port orifice to the atmosphere. When energized, the solenoid A core assembly is lifted from its seat on the inlet port orifice.

This allows the solenoid "B" disc spring to lift the disc-holder subassembly and seat against the exhaust port orifice. Air then passes through the inlet port orifice and pressurizes the process cylinder. When solenoid B is energized, the core is forced upwards, pushing the stem against the bottom of the disc-holder subassembly. The disc-holder subassembly forces the solenoid A core assembly to its energized position, unseating the core assembly from the process pilot orifice and seating the disc-holder subassembly against the exhaust pilot orifice.

In the event of a failure of the air supply, the helical closing springs along with an air accumulator provide sufficient forces to close the valve. In addition, steam flow through the valve assists in valve closure. The closing speed can be adjusted over a required range of 3 to 5 seconds which is fast enough to provide sufficient protection in the event of a main steam line rupture, but slow enough to prevent imposing an excessive pressure transient on the reactor vessel.

The Instrument Air System provides clean, dry, oil free air for control purposes throughout the plant. The system meets the guidelines of ANSI Standard MC-11-1 (ISA-S7.3) with the exception (as documented in FSAR Section 9.3.1.2) that the maximum allowable particle size for air to safety related equipment is 40 microns. The normal supply of air pressure to the instrument air system is from one of four air compressors (2 service and 2 instrument air compressors). The instrument air (from any of the sources) passes through an after cooler, a receiver tank, a pre-filter, an air dryer, an after-filter and a piping network prior to distribution to various plant components. The instrument air system has no safety-related function. Depressurization of this system will not compromise any safety-related systems or component and will not prevent safe reactor shutdown.

B. Purpose and Scope of the Recovery Effort

The purpose of the followup effort was to (1) conduct a timely, thorough and systematic investigation of the events surrounding the MSIV failures; (2) collect, analyze and document the factual information and evidence sufficient to determine the probable root and contributing causes to the failures; and (3) review the actions taken at the time of the events and assess their compliance with applicable requirements.

The scope of this effort included conditions preceding the events (e.g. maintenance histories, past surveillance tests), event chronology, system response, human factors considerations, equipment performance, possible precursors to the events, previous industry experiences, the shifts response to the events, the safety significance (including radiological considerations), and whether proper regulatory guidelines and/or requirements were followed.

C. Brief Description of Report's Contents

A summary is provided for each of the two events, October 29-November 3 and November 29, documenting the significant evidence, analyses and conclusions identified from the initial MSIV failures through the final determination and restart action items. Briefly, the following is included:

- o A chronology of events
- o An assessment of the actions taken
- o Equipment performances/failures
- o Relationship to previous similar events
- o An assessment of the safety significance
- o Corrective actions
- o Plans for restart

October 29 and November 3 Event Description

October 29 and November 3 Event Description

A. Chronology of Events

On October 29, at 1837 Startup Test Instruction (STI)-B21-025A, "MSIV Functional Test" was being performed on 1B21-F022D, inboard MSIV. The D Main Steam Line (MSL) inboard MSIV closed in 22.14 seconds, in excess of the required closure time of Technical Specifications 3.4.7 and 3.6.4.. At 2103 and 2106 the D inboard MSIV was satisfactorily cycled twice with closure times of 3.24 and 2.94 seconds. All other MSIVs were then cycled to verify closure time. The B and D outboard MSIVs closed in 11.9 and 77 seconds respectively, and each was recycled with satisfactory results. The cause of the slow closures was thought to be a one time deposit of debris in the respective solenoid valves causing a delay in their response. Once the valves were cycled and the stroke times passed, the debris was assumed to be exhausted. Since initial conditions causing MSIV slow closure could not be repeated, all MSIVs were declared Operable and plant startup testing continued.

On November 3 at 1150, MSIV stroke timing commenced in preparation for performing a full MSIV closure scram as part of the startup test program. At 1157 the D inboard MSIV closed in 18 seconds but recycled satisfactorily at 1159. At 1208 the D outboard MSIV failed to close. A second attempt was satisfactory at 1213 with a closure time of 3.4 seconds. Based on repeat failures a plant shutdown was commenced at 1330. The Reactor Recirculation (RRC) Pumps were shifted to slow speed at 1630, resulting in a reactor power decrease from 32 percent to 23 percent of rated. With reactor power below the Low Power Set Point (LPSP)(26 percent), the Rod Pattern Controller (RPC) generated control rod insert and withdrawal blocks. Preparations were made and the reactor was manually scrammed by placing the Mode Switch in "Shutdown" at 1819.

On November 4, the Nuclear Regulatory Commission (NRC) issued a Confirmatory Action Letter (CAL) detailing various actions to take in preparation for an NRC Augmented Inspection Team (AIT). The team arrived onsite November 4.

B. Troubleshooting Activities

Prior to performing any work in the field, a troubleshooting plan was written. Based on the symptoms shown on October 29 and November 3, it was felt that the component with the highest probability of causing the slow closures was the ASCO model number NP-8323A20E dual solenoid found on each MSIV air actuator. The troubleshooting plan was set up to determine what the root cause was and whether any secondary problems had an impact.

On November 5 "As Found" conditions were documented wherein a more detailed troubleshooting plan was developed to establish the root cause of the MSIV failures and corrective actions necessary to restore the valves to operable condition. The revised plan was agreed to by the NRC AIT. On November 5 through November 8 various troubleshooting activities were carried out.

- (1) Tests conducted on the 1B21-F022D, F028D and F028B solenoids included the following:
 - a. Solenoid voltages and solenoid air exhaust port samples were taken as the valves were cycled and all results were satisfactory. Next, the field wiring and air lines were disconnected from the air actuator or air pack. All connections and pipe openings were inspected. The air pack was then removed from the valve actuator and taken to the I&C hotshop for disassembly. The 1B21-F022D single (slow close) solenoid was inspected and no problems were found. Any discrepancy no matter how small was documented for further evaluation. Whenever possible, pictures were taken of what was found.

Results:

- a. All dual solenoids disassembled had impact marks on the star shaped disk subassembly and a deep depression (dimple) on the disc holder seal (EPDM), with the solenoids of the B21-F028D valve indicating the most degradation (see Appendix A).
 - b. Many of the EPDM Body Assembly O-Rings were hard, flattened, and adhering to metal valve body surfaces.
 - c. In the 1B21-F028D valve rust was found inside the solenoid housing cover and the B solenoid coil was badly corroded. (This was incorrectly identified as 1B21-F022D in our letter PY-CEI/OIE-0288 L dated November 13, 1987).
- (2) In addition to the component disassembly, other analyses were performed to determine what contribution, if any, instrument air quality may have had in the failure of the MSIV valves. Instrument air dew point temperature was measured in the supply to both the inboard and outboard MSIV's. Air supply particle size distribution was measured. Various unknown substances observed in or collected from internal component surfaces were analyzed using infrared spectroscopy to determine the origin of the material. Grab samples of the air supply were analyzed by gas chromatography for hydrocarbon content, and quantification of organic contaminants, if present in significant quantities.

Results:

The measured dew point temperatures were well below the maximum -40°F allowable. Initially a particle counter was used to measure air particle size distribution. Due to a recent change in vendor calibration standards, the maximum range of

quantification was greater than 15 microns. Testing did indicate a small number of particles in the greater than 15 micron range. In an effort to quantify those particles, an alternate sampling method using filter paper was attempted. Samples were taken and particle sizes measured using a microscope. This did indicate a few particles in the greater than 40 micron range, but this sampling method is susceptible to contamination from the sampling environment which may have been the reason for the greater than 40 micron particles measured. Analyses of the substances collected during disassembly identified the presence of thread sealant and silicone lubricant, both of which are normally used during assembly of solenoid valves and air lines. Air supply grab samples revealed no detectable condensable hydrocarbons greater than 0.1 PPM.

Based on the information and analysis conducted it appears that the EPDM material used in various parts of the solenoid was interfering with solenoid valve movement. Thus, the decision was made to remove the dual solenoids on all 8 MSIVs, and replace/refurbish as necessary.

C. Root Cause of Failures

The cause of the MSIV delayed closures has been isolated to a failure of the ASCO dual solenoid valves. This failure is attributed to EPDM elastomer degradation due to elevated temperatures in the vicinity of the air packs resulting from steam leaks. This condition caused the disc holder assembly to intermittently wedge in place and the solenoid valve to stick in the normally energized position. The observed hardened dimples on the disc holder assembly and core assembly hardened elastomer seals is consistent with high temperature conditions. Other evidence of localized steam effects include degradation of the solenoid valve O-rings and observed rust/moisture contamination of the 1B21-F028D solenoid.

Localized high temperature conditions existed during the plant cycle due to steam leakage as evidenced by elevated area temperature indications. Steam leakage is known to have occurred in MSIV 1B21-F022B packing and the MSIV leakage control system isolation valves. This leakage was in the direct vicinity of those MSIV's which exhibited slow closure. Steam is suspected of leaking in the direct location of the subject MSIV air packs based upon the degradation of the EPDM.

D. Corrective Actions

As a result of the findings and conclusions identified subsequent to the October 29 and November 3 events, the following evaluations and corrective actions have been or will be completed:

- (1) For the dual (fast closure) solenoids, the total 1B21-F028D air pack, including a new solenoid unit, has been replaced and a new dual solenoid was installed on the 1B21-F022D valve. Additionally, the 1B21-F022A dual solenoid valve was replaced due to a frayed wire at the termination. No other dual solenoids showed significant degradation or required replacement. All of the remaining MSIV dual solenoids were rebuilt.
- (2) The single (slow closure) test solenoid was replaced on the 1B21-F028D valve since the whole air pack was replaced. Additionally, the 1B21-F028B single solenoid valve was replaced due to a frayed wire at the termination. Based on the inspection results above, no other replacements were necessary.

- (3) An evaluation has been performed of other ASCO solenoid valves required for Class 1E harsh environment applications in the plant, including those which may have been subject to the steam leak environment which affected the MSIV solenoids. The review identified two normally deenergized solenoids which were subject to the same conditions as the MSIV solenoids. Since the solenoids are normally deenergized no further action was considered necessary because in this state, the suspected failure modes were not expected to occur.

The two solenoids were 1B21-F0451 (solenoid for valve 1B21-F0069) and 1M14-F0063A (solenoid for valve 1M14-F0060A). A work history review of all other applications has shown no solenoid failures, indicating the ASCO solenoid degradation appears to be limited to the MSIV solenoid valves. Further reviews are described in Item 11 below.

The 1M14-F0060A valve is a normally closed valve and has no safety function to mitigate an accident. It is associated with a drywell purge system damper that is closed during normal operation with a water seal in place for shielding purposes. This valve was satisfactorily cycled during the recent shutdown. The 1B21-F0069 valve is a one inch "before" seat drain valve that is closed at greater than 50% main steam flow (at which time the solenoid is deenergized). The valve was subsequently cycled on November 7, 1987 with no deficiencies identified. In addition, this valve was satisfactorily cycled again during the November 13 plant startup.

- (4) An evaluation has been performed of other equipment in the vicinity of the 1B21-F022D, 1B21-F028D, and 1B21-F028B valves, to assess any impact that the steam leaks may have had on these components. This evaluation revealed that there were six valve operators in the steam tunnel and two in the drywell that were in close proximity to the known steam leaks. These actuators were inspected and no steam/heat degradation was observed.

Wiring, terminal blocks, torque switches, limit switches, splices, gaskets, and limit switch gear box lubricants were inspected by a team that included EQ personnel. There was no evidence of a thermal degradation from a steam environment that would affect valve operability. It should be noted that the Limatorque actuators do not contain EPDM material. In addition, a further review for qualified life adjustment has been completed (described in Item (11) below). There is no concern of Limatorque motor operators qualified life in the drywell or steam tunnel areas.

- (5) Following the November 13 startup, temperatures in the vicinity of the MSIVs were initially monitored using permanently installed plant instrumentation. Monitoring was later accomplished using additional temporary instrumentation. The historical readings of the existing permanent steam tunnel and drywell temperature elements in the vicinity of the MSIVs were reviewed, and a baseline was determined for each element.

Until the temporary temperature monitoring baseline values were determined, the existing permanent temperature elements were used. It was determined that a 10% rise above these baseline values may be indicative of a localized steam leak and would require investigation. This value was conservatively selected since it is approximately one half of the temperature rise expected for the Technical Specification trip value for leak detection. It was sufficiently conservative for the interim period until the MSIV area and surface temporary temperature element readings were fully baselined. This temperature rise would have indicated the steam leaks which impacted the inboard MSIV (24 degrees F differential temperature). A lower threshold temperature rise could have resulted in unnecessary actions or reduction in power operation due to minor temperature fluctuations.

A procedure was established specifying necessary actions to be taken upon exceeding the interim temperature values. The interim temperature thresholds were established and based on area temperature plus a 10% rise or a selected 225 degrees F for the temporary temperature elements in the area surrounding the MSIVs in the steam tunnel and drywell. The NRC Senior Resident Inspector will be notified if any of the following corrective actions are to be taken:

- o Reduce power, as necessary, to perform a visual inspection to determine the equipment affected.
- o Immediately repair the leakage or shield the adjacent Class 1E components to limit the impact until a repair is possible.
- o Note components being affected and assess the thermal impact (EQ). Evaluate and determine the necessary time frame for taking additional action, such as increasing surveillance frequency or changing replacement interval.
- o At least 1 temporary temperature element in the area of each MSIV will be maintained in service in Operating Conditions 1, 2 and 3. If all temporary temperature elements fail for a specific MSIV, the adjacent temperature elements will be utilized in an interim period not to exceed 7 days. In the interim a correlation will be established between the adjacent temperature elements and the specific MSIV without individual monitoring. After 7 days, reactor power will be reduced in order to repair/replace the failed element within 24 hours or the plant will be placed in Hot Shutdown within 12 hours and Cold Shutdown within the following 24 hours.

- o If the local temperature monitoring in the area of an MSIV exceeds 284 degrees F, the affected MSIV will be declared inoperable in accordance with Technical Specification 3.6.4.a or cycled daily consistent with the EQ test parameters. This remains in effect until the additional environmental testing is completed (see Appendix B).

The temporary steam tunnel and drywell temperature monitoring equipment was installed at preselected locations in the MSIV area. In the steam tunnel, this included placement on the dual and the single solenoid bodies, and in the vicinity of the MSIVs to monitor ambient air temperatures. The drywell temperature elements were located on the dual solenoid bodies, along with ambient air monitoring.

- (6) The temporary temperature elements installed in the drywell and steam tunnel were monitored during full power operation until baseline temperatures were established (see Appendix E). The procedure outlined in Item (5) was then revised to monitor the temporary temperature elements in lieu of the permanent elements. A temperature rise of 10% above the baseline was determined and included in the procedure. The actions to be taken upon exceeding this temperature limit were the same as outlined in Item (5).

The temporary temperature monitoring program will continue until the final analysis results of the environmental testing (see Appendix B) are fully evaluated. At this time, possible design improvements will be evaluated and a determination will be made on future actions, including replacement frequencies or correlation to permanent area temperature elements. The NRC will be notified prior to removal of the temporary temperature elements.

- (7) A test has been performed which shows that air does not flow between the instrument air compressor reduction gear vents and the air compressor intake. Consequently, it was determined that there was no need for any equipment modification.
- (8) To further substantiate the high temperature root cause, laboratory analyses will be performed to confirm the failure mechanism of the EPDM degradation. A review of industry experiences and discussions with various industry sources will continue to be conducted in order to input into our analysis plan. The preliminary analysis plan, which included these industry contacts, is completed, with a summary provided in Appendix B.

We have completed an initial evaluation of industry experience. The initial industry review did not change our preliminary conclusion that the root cause of the problem was primarily localized elevated temperatures near the ASCO solenoid valves. The visual inspection of the EPDM did not exhibit the normal signs of hydrocarbon degradation (stickiness, sponginess, or swelling), however, we have not eliminated the potential of hydrocarbons having a deleterious effect. We plan to use data obtained from other plant experiences as described in IEN 86-57, along with our own analysis, to confirm the root cause.

Our preliminary schedule is to have initial infrared analysis for hydrocarbon degradation by the end of January 1988 with the remaining results and analyses by end of the first quarter 1988. Any further analyses required will be determined at that time. We plan to use a local research laboratory, as our primary analyses contractor. Results will be provided to the NRC. With respect to environmental testing, a test plan has been provided to the NRC (CEI/OIE-0292 L, dated November 23, 1987). Interim test results will be provided to the NRC as they become available during the 92 day test duration.

Following completion of the analysis program, possible design improvements will be evaluated and a determination will be made on future actions, including replacement frequencies.

- (9) Presently, in order to minimize the potential for introducing hydrocarbons to the air system, a preventive maintenance requirement has been established for periodic replacement of the instrument air system prefilters. The maintenance frequency is consistent with replacement of the instrument air system after filters. Additionally, a generic precaution will be added to all work orders requiring piping/tubing systems to be opened regarding the use of thread sealants and lubricants. If the outcome of the chemical analyses indicates the presence of hydrocarbons, we will immediately implement an appropriate hydrocarbon sample and analysis program for the instrument air system. This will include weekly sampling of the supply lines to the MSIV's at the containment penetration connection as well as other main J-headers throughout the air supply system. The Senior NRC Resident Inspector will be notified upon implementation of this action.

Dew point and particulate sampling of the instrument air system will continue in accordance with the existing plant administrative procedure. Any unacceptable results will be evaluated and system blowdowns will be conducted until satisfactory results are obtained.

- (10) Until the first refueling outage, the fast closure dual solenoids will be checked for proper operation during the monthly slow closure check. The existing monthly surveillance instructions were revised to reflect the following test procedure. The test will be performed by fully closing each MSIV individually utilizing the test solenoid, followed by placing the control switch to the "close" position.

Performance of this test will verify the proper operation of the dual solenoid, since the MSIV will remain closed only if the dual solenoid deenergizes and properly repositions. If any MSIV should reopen during the test, indicating failure of a dual solenoid, the associated MSIV will be declared inoperable and the plant will be placed in Hot Shutdown within 12 hours and Cold Shutdown within the following 24 hours. The NRC will be notified upon discovery of such a failure.

Also during this time frame (until the first refueling outage) the MSIVs will be cycled individually on a quarterly basis regardless of plant operating conditions, and the fast closure time verified. If a failure is detected during this quarterly test due to a temperature related problem with a dual solenoid, or associated air pack components, the plant will be shutdown and the NRC will be notified as described above. The monthly slow closure test described above will not be performed during those months when the quarterly fast closure test is performed.

Prior to exceeding a six month period an inspection will be performed during an outage of opportunity, on the dual solenoid experiencing the highest temperature profile. This inspection will visually verify no degradation of the solenoid valve internals. If accelerated heat degradation is observed, a complete investigation will be initiated and the NRC notified.

- (11) A review has been completed of all known steam leaks in the plant which could have affected Class 1E equipment. For all of the potentially affected equipment identified, there is no configuration where elastomer compression set or degradation could result in the equipment not being able to perform its intended function. These components were also evaluated to determine if there has been any affect on their long term qualified life based on the environment under which they were subjected. The results of this evaluation are documented in

our letter PY-CEI/OIE-0294 L dated November 30, 1987. An additional review will be conducted for potentially high temperature area environments for all Class 1E solenoids and related equipment with EPDM subcomponents where elastomer compression set or degradation could result in equipment not being able to perform its intended function. This review will be completed by the end of the first quarter 1988.

E. Safety Evaluation/Significance

The safety significance of the event has been divided into two parts; the immediate safety significance of having one or more MSIVs with isolation times outside their Technical Specification Limit, and the effect on accident analysis of having one Main Steam Line isolate at a time greater than five and one-half seconds.

(1) Immediate Safety Significance

On October 29, 1987 Main Steam Isolation Valve (MSIV) 1B21-F022D exceeded it's allowable stroke time during performance of a startup test and was declared inoperable at 1900. Technical Specification 3.6.4 Action (a) then became applicable. This required the plant to make the valve operable within four (4) hours or isolate the penetration. At 2103 and 2106, 1B21-F022D was cycled and stroked closed within the 5 second isolation time required by Technical Specification 3.6.4. The D Main Steam line was isolated at approximately 2240 as required by the Technical Specification.

Subsequent to the 1B21-F022D valve testing, all MSIVs were cycled in order to verify adequate stroke times. At 2144, the 1B21-F028D failed it's stroke time test and was considered inoperable. At this point, Technical Specifications required the plant to be shutdown within 12 hours. (One other MSIV, 1B21-F028B, also failed it's first stroke time test at 2216).

By 2310, all MSIVs that failed their initial stroke times had successfully completed subsequent tests and the results evaluated. The valves were considered Operable. The bases for this decision was that the cause of the slow closures was attributed to be a one time deposit of debris in the respective solenoids causing a delay in their response. Once the valves were cycled and the stroke times passed, the debris was assumed to have been exhausted. This conclusion was believed to be consistent with known industry problems regarding air systems and MSIV solenoid valves. In addition, a full MSIV closure test was to be performed in less than one week. These factors were considered heavily in the final decision. No further actions per Technical Specifications were required. None of the Technical Specification Limiting Conditions for Operation (LCO) were violated.

On November 3, 1987 another series of stroke timing tests were performed on the MSIVs. At 1157, the 1B21-F022D failed it's stroke time and was declared inoperable. At 1208 the 1B21-F028D failed to close. Both valves were subsequently recycled satisfactorily within minutes of their first tests. However, because the valves again failed to properly actuate on the first attempt, the bases for an isolated failure was no longer considered valid. The plant commenced a shutdown at 1330 and the D and B lines were isolated by 1354. The plant was shutdown within the 12 hours required by Technical Specification 3.6.4 Action (a).

Since no LCO was violated during either event, the plant remained within the constraints of the analytical bases contained in the operating license. Consequently, the incidents resulted in no immediate safety significance.

(2) Effects on Accident Analysis

It was determined that two accident scenarios and three transients described in the FSAR took credit for closure of the MSIVs. The events were as follows:

- a. Steamline break outside containment
- b. Inside containment breaks which reach RPV Level 1
- c. Pressure regulator failure transient
- d. Loss of condenser vacuum transient
- e. Loss of AC power transient

If Regulatory Guide 1.3 assumptions were used a delay or failure to isolate one steamline substantially effects the radiological evaluation of the DBA recirculation line break inside containment since it requires the assumption that 100% of all activity in the core is released. This activity would then be available for transport outside the containment until all steamlines are isolated. However, the Perry FSAR Chapter 15 analysis concluded that for the original accident scenarios (a and b), no fuel failure would occur. Using this premise, FSAR Table 15.6-17 values were used for isotopic content of the reactor coolant when performing the evaluations.

The bounding event of those described above was determined to be the steamline break outside containment since this event would permit the largest amount of activity to reach the site boundary. An analysis was performed to determine what the mass flow would be for a main steam line break outside containment given the as found conditions that existed on November 3, 1987 (i.e. three main steam lines isolate with proper times, and the remaining main steam line isolates in 18 seconds). The analysis was done using the GE's SAFE 06 Code, a NRC approved code which has been previously used by Perry in the ECCS

performance analyses (FSAR Chapter 6). The mass release determined by this code was much less than the mass release discussed in FSAR 15.6.4.4 for the main steam line break outside containment. This was due to the conservative assumptions used in the FSAR analysis, such as assuming that level rise time is 1.0 seconds, that mixture quality is a constant 7.0%, and that the system pressure remains constant at 1060 psig throughout MSIV closure.

However, it was decided that two calculations would be done. The first would use the mass release given in the FSAR (FSAR page 15.6-10) for the first 5.5 seconds and then use the GE supplied flow data after 5.5 seconds when only one main steamline is open. The second calculation used the GE supplied data throughout the event. For each calculation two results were determined. First the postulated amount of radiation which would be released in the 18 seconds it took for the D line to isolate on November 3, and secondly the total time it would take with one main steam line unisolated before 10CFR Part 100 limits were exceeded. For these calculations it was conservatively assumed that there would be no plateout or hold up time for the release.

For the calculation using the FSAR mass release the following conclusions were drawn:

Exclusive Boundary Area Iodine dose with 18 second single MSIV closure - 192 Rem

Exclusive Boundary Area Iodine dose with 79 second single MSIV closure - 300 Rem

For the calculation using the GE data the following conclusions were drawn:

Exclusive Boundary Area Iodine dose with 18 second single MSIV closure - 82 Rem

Exclusive Boundary Area Iodine dose with 120 second single MSIV closure - 300 Rem

As shown above for either calculation the slow closure (18 second) of the D MSIV line on November 3 would not have resulted in a release exceeding 10CFR100 guidelines. Also, depending on which calculation was used, it was determined that the plant would have had between 79 and 120 seconds to isolate that line under accident conditions prior to exceeding 10CFR100 guidelines. Therefore, the 18 second slow closure of the D main steam line penetration has been shown to be within the bounds of accident guidelines. In conclusion, the Technical Specifications were followed negating any immediate safety significance, and analyses using appropriate assumptions showed that had an accident occurred on November 3, 1987, the plant would have responded in a manner which would have met NRC guidelines.

F. Conclusion

In summary, the MSIV slow closure problem was thoroughly evaluated and diagnosed. The actions taken by the operations staff during the initiating events were evaluated as proper and in accordance with plant procedures and regulatory requirements. The root cause was determined to be a failure of the respective MSIV 3-way dual solenoid valves. This failure resulted from a hardening and dimpling of the EPDM rubber disc seat material and other EPDM seals, causing the disc holder assembly to wedge in place when the solenoid energized.

Following troubleshooting, extensive short and long term evaluations and corrective actions were initiated. These included solenoid valve replacement, work history reviews, environmental evaluations, installation of additional temperature monitoring, instrument air laboratory analysis, and a followup laboratory analysis of the solenoid valves to confirm the failure mechanism.

An evaluation of this event was performed and concluded that since the plant remained within the constraints of the analytical bases contained in the operating license the incidents resulted in no immediate safety significance. In addition, the effects on the design bases accident analysis were reviewed and also determined to not be significant. The repairs to the MSIV solenoids have been completed and the plant successfully restarted.

November 29 Event Description

November 29 Event Description

A. Chronology of Events

On November 29, 1987 at 0240, modified Surveillance Instruction, SVI-C71-T0039 "Main Steam Line Isolation Valve (MSIV) Closure Channel Functional" was being performed on 1B21-F022B, Main Steam Line (MSL) B inboard MSIV. The test is performed by fully closing each MSIV individually, utilizing the test solenoid, followed by taking the control switch to close. Performance of the test in this manner verifies proper operation of the MSIV dual solenoid, since the MSIV will remain closed only if the dual solenoid de-energizes and properly repositions (see Diagrams 1 and 2). When the 1B21-F022B control switch was taken to the closed position (following slow closure), the valve stroked open, indicating a failure of the dual solenoid. Approximately three minutes later, the test was repeated with the same result. Two more attempts were made utilizing only the control switch. The valve failed to close during both attempts and was subsequently declared inoperable.

At 0410, a reactor shutdown was commenced in accordance with commitments documented in our letter PY-CEI/OIE-0289 L dated November 13, 1987. In addition, at 0509, MSL B was isolated in accordance with Technical Specification Action requirement 3.6.4.a. After reducing reactor power, a manual scram was initiated at 1114. Operators commenced a plant cooldown in preparation for entering Operational Condition 4, Cold Shutdown.

During the plant cooldown, personnel entered the Drywell to visually inspect the 1B21-F022B valve while operators again attempted to stroke the valve using the control switch. At 1303, with assistance from drywell personnel (providing a slight tap on the solenoid body), the valve was successfully stroked closed. The valve was then reopened and at 1306, again stroked satisfactorily from the control switch. By 1720, the plant was in cold shutdown.

On November 30, the Nuclear Regulatory Commission (NRC) issued a Confirmatory Action Letter (CAL) detailing various actions to take in preparation for an NRC Augmented Inspection Team (AIT). The team arrived on site November 29 and 30.

B. Troubleshooting Activities

On November 30, the 1B21-F022B dual solenoid valve (ASCO Model Number NP-8323A20E) was removed from the field, disassembled and visually inspected. While the visual inspections were underway, a troubleshooting plan was developed. The plan's purpose was to conduct a thorough, timely and systematic investigation of the circumstances surrounding the MSIV failure. The plan was comprised of three major segments; (1) collection and documentation of pertinent information (2) analysis of that data for root cause determination and (3) implementation of corrective action necessary to prevent recurrence. The troubleshooting plan and associated work orders were presented to and approved by the NRC AIT. The details of the plan are discussed below.

The information collection and documentation of results included visual and microscopic examinations of various valve parts and foreign materials. In addition, chemical analysis was performed on these samples which included destructive and consumptive tests. Specifically:

- (1) Tests conducted on the 1B21-F022B solenoid included the following:
 - a. The solenoid was disassembled and visual inspections performed. The visual inspections were intended to identify surface defects, impurities or the presence of foreign material.

Results:

A sliver and two other small segments of foreign material were discovered in the B solenoid valve body area (see Diagram 1 and Appendix A). The seating surface was also inspected and no evidence found of hardening of the discs or O-rings. The discs and O-rings remained flexible and non-rigid. There was only slight dimpling of the exhaust port disc and a minor depression on the inlet port disc. There was no resemblance to the extruded hardened dimples observed on the seats identified during the November 3, 1987 event.

- b. Chemical analysis was performed of the foreign material identified above (see Appendix C). The chemical analysis included infrared analysis to determine material composition, and microscopy, intended to enhance the ability to conduct visual inspections.

Results:

- (i) The infrared analysis indicated the presence of EPDM and small amounts of silicone on the sliver and on the only other particle found capable of analysis. Both materials are part of the solenoid valve assembly. This analysis also concluded that there was no evidence of oxidation. Oxidation if present, would be indicative of the presence of hydrocarbons.
- (ii) The microscopy indicated that the material was black in color, spongy in construction and exhibited a compression set similar to EPDM material. This supports the conclusion that the material was EPDM.

- (iii) Microscopy Dimensional Analysis of the foreign material and that of the pre-rebuild O-ring from the 1B21-F022B solenoid valve were compared. The results indicated that the foreign material was similar to a gouge identified in one of the pre-rebuild O-rings in it's shape and overall dimension (0.8 mm X 4.2 mm X 0.3 mm).
 - (iv) An infrared analysis was performed on the pre-rebuild O-ring and confirmed that the foreign material organic chemical composition matched that of the O-ring (EPDM).
 - (v) Further chemical composition analysis for metallics was performed by Scanning Electron Micrograph (SEM) on all particles (e.g. foreign material) and the pre-rebuild O-ring. This analysis provided further confirmation of material source by comparing trace metal catalysts and cross linking agents present in the samples. The results of this analysis document that the microstructure of the O-ring and sliver are the same.
 - (vi) Microscopy evaluation of both the pre-rebuild and existing O-rings was performed and verified no other potential sources of the foreign material.
- (2) The 1B21-F022C and F022D ASCO solenoid valves were disassembled and visual inspections performed. (The F022C solenoid valve was previously rebuilt while the F022D solenoid valve was replaced with a new valve as a result of the November 3, 1987 event).
- Results:
- No foreign materials were identified. Only minor seat impressions were visible on the disk (similar to 1B21-F022B disk).

- (3) Evaluations conducted on the pre-replacement 1B21-F022A solenoid valve included seat leakage tests followed by disassembly and visual inspection.

Results:

No seat leakage was observed. No significant foreign materials (other than small particulate) or other discrepancies were identified.

- (4) Air blows were performed on the Instrument Air System followed by dew point and particle count analysis.

Results:

- a. The air blow was conducted using a pillowcase as the filter medium. Although slight discoloration was noted, no visible particulate was identified. Additional particulate count analysis demonstrated that Instrument Air quality was within design requirements. The largest particle measured was in the less than 20 micron range.
- b. A dew point check was performed at the air supply line to the F022B solenoid. The results (-42 degrees F) were satisfactory.
- c. Samples were collected and results concluded that no hydrocarbons were present within the Instrument Air System.

- (5) A review was performed on solenoid valve construction, allowable tolerances and dimensional analysis for thermal affects which may have contributed to the solenoid valve failure. The solenoid valve spring constants including any resulting heat effects on these values were also evaluated to determine if they had contributed to the solenoid valve failure.

Results:

The vendor has provided written certification documenting that spring characteristics and valve dimensions are within design tolerances and are bounded by the results of the Environmental Qualification Tests. In addition, it was determined that the particles found were of sufficient size to become lodged between sliding surfaces around the solenoid core thus inhibiting movement and causing the valve to malfunction.

- (6) A review of the Air Quality Standard for the Instrument Air System was performed. Included in this review was a justification of previous data collected on November 7, 1987 which documents greater than 40 micron size particles.

Results:

Because of the probability of some contamination occurring due to the large amount of exposed sample handling involved with the filter paper collection method, it is not easily ascertained what percentage of these results were due to contamination. It is suspected that the majority of fibers found are dust particles from room air. As a more accurate method, the particle counter instrument was recalibrated to detect and quantify particles in the 40-50 micron and >50 micron range and was used to test the validity of the filter paper collection results. The results of this analysis concluded that Instrument Air quality was within design requirements for particulate (see Appendix D).

C. Data Analysis and Root Cause Determination

(1) Summary

A detailed root cause analysis was performed with a draft report provided to the NRC AIT. It concluded that the root cause of the MSIV failure was binding of the "B" solenoid (refer to Diagram 1) due to the presence of foreign material.

During visual examination, a sliver of foreign material (EPDM) was discovered in the 1B21-F022B solenoid valve body core cavity. The material was demonstrated to have originated from rebuild activities conducted during the previous MSIV outage (early November 1987). This sliver was inadvertently dropped into the core area of the "B" solenoid and since that portion of the solenoid was not disassembled, it was not detected until the current investigation. Inspection of the "B" solenoid core area required removing the "B" coil. However, the leads for the "B" coil would have required cutting to remove the coil. By the time this solenoid valve was being rebuilt, the root cause had already been determined to be heating of EPDM material. Consequently it was decided that the "B" solenoid core area would not require inspection.

The sliver of foreign material caused mechanical binding of the solenoid valve. This binding caused the solenoid to remain in the normally energized position which prevented the air bleed off from the MSIV actuator and thus valve (MSIV) closure.

(2) Supporting Analysis

Microscopic and infrared analysis performed on this foreign material and on the pre-rebuild O-ring from the 1B21-F022B valve support this root cause determination. A summary of other analysis demonstrates no other reasonable cause or contributing factor. Specifically;

- a. Visual inspections of other solenoid valves and associated parts revealed no other discrepancies which could have contributed to the valve failure.
- b. Instrument air samples and analysis identified no problems which could have contributed to the solenoid failure. Although earlier filter collection samples identified some amount of particles in excess of the 40 micron limit,

subsequent samples using a particulate counter found the air quality within design requirements. Consequently, particulate in the Instrument Air System are not believed to be a contributing factor to the solenoid valve failure.

The system is designed to meet the guidelines of ANSI Standard MC-11-1 (ISA-S7.3) with the exception that the maximum allowable particulate size for air to safety related equipment is 40 microns. Recent instrument air analysis has confirmed the dew point, hydrocarbon levels and particulate to be within required limits.

- c. A variety of destructive and chemical tests were performed on many pre-rebuild and new solenoid valve parts. The results of these tests identified no discrepancies which could have contributed to the solenoid valve failure.

(3) Relationship of November 29, 1987 Event to Previous Events

As discussed in Section 3 of this report, MSIV solenoid valves experienced failures to shift in the past (also refer to our letter PY-CEI/OIE-0288 L dated November 9, 1987 and 0289 L dated November 13, 1987). During the October 29 and November 3 events, the root cause was determined to be failure of the solenoid valves due to EPDM elastomer degradation of the seating surface. This degradation was caused by elevated temperatures resulting from steam leaks in the vicinity of the MSIV air packs.

The root cause of these previous events is unchanged by any of the post November 29 event investigations completed to date. This conclusion is based on the following:

- a. Temporary instrumentation mounted on the ASCO valve and contact readings taken during the November 29 drywell entry indicated temperatures below the maximum allowable values documented in the existing Environmental Qualification Report.
- b. Subsequent disassembly (post November 29 event) of the 1B21-F022B ASCO solenoid valve and examination of elastomers indicted no evidence of hardening of the discs or O-rings. The discs and O-rings remained flexible and non-rigid. There was only slight dimpling of the exhaust port disc and a minor depression on inlet port disc. These indications are expected due to the operational design of the solenoid valve. In addition, O-rings installed during the rebuild were removed freely.

D. Corrective Actions

To prevent recurrence, all MSIV dual solenoid valves have been replaced with new valves and were cycled 10 times as part of the retest activity prior to the December 9 reactor startup. In addition, administrative controls will be instituted on future Class 1E ASCO solenoid valve work to require the use of new valves or complete disassembly and cleanout to ensure no particles are introduced during the rebuild process.

Previous corrective actions discussed in Section 3.D of this report and documented in our earlier letter, PY-CEI/OIE-0289 L dated November 13, 1987, will be completed as planned with the following clarifications:

- (1) The dual solenoid valve inspection discussed in Section 3.D. (10) and on page 5 of the enclosure to our previous letter will be performed during an outage of opportunity prior to the end of October 1988. This is based on the complete replacement of all MSIV solenoid valves discussed above.
- (2) The modified monthly slow closure surveillance test discussed in Section 3.D. (10) and on page 5 of the enclosure to our previous letter will be performed on a staggered basis as follows:
 - a. Until the January 4, 1988 outage, the test will be performed weekly, staggered between the inboard and outboard MSIV's.
 - b. For a one month period following the January outage this test will be performed once every two weeks, again staggered between the inboard and outboard MSIV's.
 - c. A revision to the baseline temperatures for a few selected points was necessary following removal and reattachment of the temporary temperature monitoring elements required for the solenoid replacement discussed above.

E. Safety Evaluation/Significance

Throughout the November 29 event, the outboard B MSL isolation valve remained operable and capable of performing its intended safety function. There was no loss of safety system function.

In addition, operator actions were in accordance with Technical Specification requirements and previous commitments. Within three hours following the discovery of the failure, the affected Main Steam Line was isolated and a reactor shutdown commenced.

Consequently, the event was not safety significant.

F. Conclusions

This section describes the event chronology, troubleshooting efforts and evaluations performed to determine the cause of events on November 29, 1987 when one Perry Unit 1 Main Steam Isolation Valve (MSIV), 1B21-F022B, failed to remain closed during performance of a modified surveillance test to verify the MSIVs would fast close on command. The cause was attributed to the failure of an Automatic Switch Company (ASCO) Model NP8323A20E 3-way dual solenoid valve.

The root cause was binding of the "B" solenoid due to the presence of foreign material in the solenoid core area. The source of foreign material has been identified by visual examination and laboratory testing as a sliver of EPDM material which separated from an O-ring. This occurred during the solenoid rebuild process conducted subsequent to the events of November 3, 1987. This sliver was inadvertently dropped into the core area of the "B" solenoid and, since that portion of the solenoid was not disassembled, it was not detected until the current investigation.

Overall Conclusion

Overall Conclusion

This report summarizes the findings and conclusions reached during investigations following the MSIV solenoid valve failures of October 29, November 3 and November 29. The first event (October 13 and November 3) identified the cause of failure to be EPDM elastomer degradation due to elevated temperatures in the vicinity of the air packs resulting from steam leaks. The second event (November 29) was discovered during special testing initiated as a result of the first event. The cause of this event was determined to be binding of the MSIV ASCO solenoid valve due to the presence of foreign material. The material was demonstrated to have originated from rebuild activities which occurred following the November 3 event. No evidence was discovered during the latest investigation which changed the root cause determination of the previous event.

Evaluations for safety significance were performed during the investigation of both events. In neither case were there any significant safety hazards identified nor any risk to the health and safety of the public.


Corrective actions were initiated following both events. As a result of the corrective actions generated from the November 29 event, it was appropriate to modify several of those actions initiated following the October 29/November 3 event.

In summary, each MSIV solenoid problem was thoroughly evaluated and diagnosed. A review of operator decision making during each event identified no actions which were contrary to existing commitments or requirements. The final corrective actions initiated will ensure that (1) the probability of recurrence of either failure type is minimal (2) that detection of any such problem will be rapid and (3) upon detection of such a problem, administrative controls will ensure that the plant is placed in a safe condition.


Diagrams




FO 288



D




DX-FOCDD


	<p>PERRY NUCLEAR POWER PLANT THE CLEVELAND ELECTRIC ILLUMINATING COMPANY</p>
<p>Hardened Dimples on Disc Holder Assemblies for the three Failed Solenoids.</p>	



Appendix A

PY-CEI/OIE-0297 L



<p>PERRY NUCLEAR POWER PLANT THE CLEVELAND ELECTRIC ILLUMINATING COMPANY</p>	<p>Non-Legraded Disc Holder Assembly (US&D).</p>
--	--

 <p>PERRY NUCLEAR POWER PLANT THE CLEVELAND ELECTRIC ILLUMINATING COMPANY</p>	<p>Foreign Material Discovered in 1B71-F022B Solenoid.</p>
--	--



ANALYSIS PLAN FOR EPDM SOLENOID COMPONENTS

I. INTRODUCTION

To determine the cause for failure of solenoid pilot valves which resulted in the slow closing of MSIV'S, two approaches will be taken. Both approaches involve analyses of the EPDM elastomer gasket material. The physical properties of the elastomeric material which was in service will be compared to new material to observe degradation, loss of material, deformation, anomalies in surface characteristics, and reduced performance. In addition, the gasket material will be subjected to chemical analyses to discover changes from original material at the molecular level. Data obtained from the analysis regimen along with data from a similar failure experienced at Brunswick in 1985 will be used to determine cause.

II. PERSONNEL CONTACTED

Interviews with the Harris Research Personnel and NRR provided information regarding analyses performed and resulting postulations. PNPP analyses will include methods to confirm or deny these postulated failures. The full Brunswick Failure Analysis Report has been sent and will be used as guidance. A meeting with Ricerca, Inc. personnel regarding this failure analysis program resulted in the following proposed course of testing.

III. ANALYSIS PROGRAM

A. Samples

1. Unused Elastomer Gasket material.
2. Used Elastomer from pilot solenoids which did not fail.
3. Used, degraded Elastomer Material from failed pilot solenoids.
4. Pilot Solenoid valve bodies with elastomer residue.

B. Physical Testing

1. Profilometric analysis to compare indentations in EPDM discs (sample nos. 3, and 2)
2. Optical Microscopy to determine the presence of foreign material, or loss of material from surfaces.
3. Hardness testing to compare with original specifications.
4. Compression set to compare with unused material and note performance degradation.

C. Chemical Testing

1. Infrared survey to determine carbonile content. This will provide information about mode of attack (organic acids from the presence of hydrocarbons) and extent of oxidation.
2. Scanning Electron Microscopy/X-Ray dispersion Spectrometry to confirm or negate copper-catalyzed accelerated oxidation. (Which was a postulated Failure Mode at Brunswick)

D. Environmental Testing

Six new dual coil solenoids will be sent to a laboratory for additional environmental testing. The solenoids will be placed in three separate environmental chambers (two per chamber) at various elevated temperatures in an energized condition. The solenoids will remain energized to demonstrate that they will perform their safety function at a variety of elevated temperatures for a specific length of time.

IV. SUMMARY

The above analyses and their results will provide evidence of failure mode and will describe any further confirming analyses which may be needed. In addition, recommendations will be made in order to preclude recurrence.

Ricerca, Inc.

7528 Auburn Road, P.O. Box 1000
Painesville, Ohio 44077
216-357-3300

TO: J. J. Grimm - CEI
FROM: K. A. Krutyholowa
DATE: December 3, 1987

SUBJECT: FOREIGN MATERIAL FROM SOLENOID PLUNGER
AREA MICROSCOPIC EVALUATIONS

SAMPLE NO.

Three particles identified as MSIV 32 and o-ring MSIV 23 were to be compared.

METHODS

The particles and o-ring were examined under a Zeiss Universal stereo widefield optical microscope (SV-8) equipped with indirect reflected light. All particle size measurements were taken from the optical micrographs.

Scanning electron micrographs were taken on the JEOL 35 SEM, equipped with Tracor Northern Energy Dispersive X-ray Spectroscopy (EDS) detector. Before examination, the o-ring and particles were mounted on carbon stubs and carbon coated. Elements from Na (Z=11) thru U (Z=92) can be detected by EDS.

Backscatter electron imaging (BEI) was used on both the o-ring and particles. In this technique, the contrast is dependent upon the average atomic number. The brighter areas reflect the presence of relatively heavier elements. For example, Pb will have a brighter image than Cu and Zn which will have a brighter image than Si.

RESULTS

OPTICAL MICROSCOPY (OM)

Particles MSIV 32

The particles are black and spongy in appearance. A few fibers are attached to the particles (Figures 1, 2 & 3). The approximate particle dimensions are listed in Table I.

TABLE I

	<u>Length</u>	<u>Width</u>	<u>Depth</u>
Particle 1	4.2 mm	0.8 mm	0.3 mm
Particle 2	0.6 mm	0.4 mm	0.1 mm
Particle 3	0.9 mm	0.3 mm	0.3 mm

O-ring MSIV 23

The brittle side of o-ring MSIV 23 has a piece missing whose length would be 4.2 mm. The indentation or gap is narrower at the edges and bent in the middle (Figure 4). The size and shape of this gap is similar to the largest particle (Particle 1).

SEM/EDS OF O-RING MSIV 23 (FIGURES 5 & 6)


The edge of the o-ring has numerous areas where pieces of material are missing. Examination of the o-ring by backscatter electron imaging (BEI) reveals numerous brighter areas indicating the presence of heavier elements (Figure 5d). The bright areas contain primarily Cu, Zn & Si. Spot mode analysis of areas A, B, C & D in Figure 5d have corresponding EDX spectra attached.

SEM/EDS OF PARTICLES MSIV 32 (FIGURES 7-10)

The particles contain many of the same elements present in the o-ring. Copper, Zn and Si are present in both the o-ring and particles. Iron is present in both the o-ring and the particles but the Fe counts are significantly higher in the particles. Cr is present only in the particles and not in the o-ring.

Note the morphology at higher magnification of the particles (Figures 10a, 8c & d, 7c) and compare this to the higher magnification micrographs of the gap in the o-ring (Figure 6a). The microstructures of the two materials are very similar.


Kathy A. Krutyholowa



MSIU 32
Particles 1, 2 + 3

9.5x
1mm = 102µm

Figure 1 MSIU.32 OM



MSIV 32 Particle 1 24.6x
1mm = 41µm



MSIV 32 Particle 1 35.5x
1mm = 28µm



MSIV 32 Particle 2+3 24.6x



MSIV 32 Particle 2+3 35.5x
1mm = 28µm

Figure 0M

Figure 3
depth of
particles
18.8x
1mm = 53µm
OM




a Particle 1



b Particle 2



c Particle 3



a MSIV 23


9.5x
1mm = 102µm



b MSIV 23

24.6x
1mm = 41µm


Figure 4 O-ring MSIV 23 OM




c NOTE GAP




b BEI



c 10 see Figure 6a




d BEI Area A, B, C, D see p. 10.




a Area 1 in Fig 5C
NOTE MICROSTRUCTURE
COMPARE TO PARTICLES

Figure 6 O-RING MSIV 23


Figure 7
Particle 1
MS10-32



a




b BEI



c



a




"C" Area A of 8b

... a. t. l. n. ...



b BET

See correspond in plots Area A + B



d Area B of 8b



a




b BEI



c BEI



a




b BEI OF Fig 10a
A+B see corresponding plots

Figure 10 MSIV.32 Particle 3

TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 23 100X 21 LT= 160 SECS 0.020 KEV


COUNTS F.S. = 4096



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 23 AREA A 600 LT= 160 SECS 0.020 KEV


COUNTS F.S. = 4096



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 23 AREA B1000 LT= 160 SECS 0.020 KEV


COUNTS F.S.= 4896



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 23 AREA C1000 LT= 160 SECS 0.020 KEV


COUNTS F.S. = 4096



TRACOR-NORTHERN SPECTRAL PLOT

FJLL MEM: MSIV 23 AREA D1000 LT= 160 SECS 0.020 KEV


COUNTS F.S.= 4896



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: PARTICLE/1000X 32 LT= 160 SECS 0.020 KEV


COUNTS F.S.= 4896



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 32 PART 2 340X LT= 160 SECS 0.020 KEV

COUNTS F.S. = 4096




SDMP2 10/33 S.DUMP

TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV_32 PART_2A1000X LT= 160 SECS 0.020 KEV


COUNTS F.S. = 4096



COLOUR-NORTHERN SPELICAL PLOT

FULL MEM: MSIV 32 PART 2B1000X LT= 160 SECS 0.020 KEV


COUNTS F.S.= 4096



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 32 PART3 340 X LT= 160 SECS e.020 KEV


COUNTS F.S.= 4096



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 32 PART3 34 A LT= 160 SECS 0.020 KEV


COUNTS F.S.= 4096



TRACOR-NORTHERN SPECTRAL PLOT

FULL MEM: MSIV 32 PART3 34 B LT= 160 SECS 0.020 KEV

COUNTS F.S.= 4096



SUMMARY OF AIR QUALITY TESTING

Introduction

Work Order 87-9983 was generated to perform dewpoint temperature measurements and air particle size distribution for the Instrument Air (IA) supply to the "B" inboard MSIV (1B21F022B). The WO was initiated to help in determining if air quality could have contributed to the failure of the ASCO dual solenoid valve that occurred 11/29/87.

Method

Testing was performed at the 3/8" air supply to the ASCO dual solenoid valve and at the 1 5/8" air supply from the MSIV accumulator to the air pack. Prior to performing the dew point temperature check, an air blow of approximately 8 minutes through a pillow case was performed. The pillow case was affixed so that the air was blown through an area equal in size to the end of the connection. Dewpoint temperatures were determined using a dewpoint hygrometer sensor (MPL L70N502B). Air particle size distribution was determined using a HIAC/ROYCO particle counter (MPL L70Y091A).

Results

Dewpoint temperature measurement satisfied the acceptance criteria of -40 degrees F. The measured dewpoint temperature of the 3/8" air supply to the ASCO dual solenoid was -49 degrees F, and to the 1 5/8" supply from the accumulator was -42 degrees F. This is approximately 165 degrees F below the normal ambient area temperature during operations.

Air particle size distribution measurements satisfied the acceptance criteria of zero particles in the greater than 40 micron range at both of the sample points. The largest particle measured was in the less than 20 micron range. Attachment 1 presents the measured particle distributions. A uniform light grey stain was observed on the pillowcase. This is similar to what was previously observed when air blows were performed on 11/06/87 following the original ASCO solenoid failures.

Conclusion

The instrument air supply to the "B" inboard MSIV was tested to determine if dewpoint temperature and air particle distribution met acceptance criteria of -40 degrees F and zero particles greater than 40 microns. This acceptance criteria was satisfied. Based on

these acceptable results, it does not appear that the failure of the ASCO dual solenoid was related to the instrument air supply.

PARTICLE SIZE DISTRIBUTION

Sample 1 : Instrument Air supply from MSIV accumulator to air pack for 1B21F022B performed 12/04/87 at 0452.

Sample 2 : Instrument Air supply to ASCO dual solenoid for 1B21F022L performed 12/04/87 at 0505.

<u>CHANNEL</u>	<u>SIZE</u>	<u>SAMPLE 1</u>	<u>SAMPLE 2</u>
1	> 3 μ M	37	9
2	>10 μ M	1	0
3	>20 μ M	0	0
4	>30 μ M	0	0
5	>40 μ M	0	0
6	>50 μ M	0	0

MSIV SOLENOID AND AREA TEMPERATURES

Outboard

<u>Temporary Monitoring Point</u>	<u>Baseline (°F)</u>	<u>Action Level (°F)</u>
1B21-F028B		
At solenoid 2 coil	193	212
At solenoid 2/3 body	186	205
At solenoid 3 coil	185	204
Behind actuator	133	146
At solenoid 1 body	133	146
At top of actuator	132	145
Between air pack and actuator	133	146
Bottom of actuator	134	147
At air pack	136	150
1B21-F028D		
At solenoid 2/3 body	189	208
At solenoid 1 body	131	144
1B21-F028A		
At solenoid 2/3 body	194	214
At solenoid 1 body	129	142
1B21-F028C		
At solenoid 2 coil	168	185
At solenoid 2/3 body	168	185
At solenoid 3 coil	165	182
Top of actuator	122	134
Bottom of actuator	104	114
At solenoid 1 body	117	129
At air pack	107	118
Between air pack and actuator	112	123
Behind actuator	113	124
1E12-F008C		
Point 33	117	129

MSIV SOLENOID AND AREA TEMPERATURES

Inboard

1B21-F022A		
Six inches from airpack solenoid	130	143
Mounted to airpack solenoid	165	182
Between F022A and F022D	127	140
1B21-F022B		
Six inches from airpack solenoid	132	146
Mounted to airpack solenoid	167	184
1B21-F022C		
Six inches from airpack solenoid	132	145
Mounted to airpack solenoid	167	184
1B21-F022D		
Six inches from airpack solenoid	130	143
Mounted to airpack solenoid	167	184

SAMPLE	DATE/TIME	DESCRIPTION	ANALYSIS
MSIV-1	11/6/87:1115	B21-F028B Deposits from 1 5/8" air hose.	IR
MSIV-2	11/6/87:1545	B21-F028B exhaust port (unknown fluid)	IR
MSIV-3	11/6/87:1115	Fitting from B21-F028B w/foreign mat'l inside (black solids and oily fluid)	IR
MSIV-4	11/6/87:2101	B21-F022D: $\approx 0.1 \text{ ft.}^3$ solenoid supply collected on 0.45μ filter paper.	PSC
MSIV-5	11/6/87:2108	B21-F022D: $\approx 0.1 \text{ ft.}^3$ solenoid supply collected on 0.45μ filter paper.	PSC
MSIV-6	11/6/87:2125	B21-F022D: $\approx 0.1 \text{ ft.}^3$ actuator supply collected on 0.45μ filter paper.	PSC
MSIV-7	11/6/87:2135	B21-F022D: $\approx 0.1 \text{ ft.}^3$ actuator supply collected on 0.45μ filter paper.	PSC
MSIV-8	11/7/87:0800	Rectorseal tm Thread sealant sample.	IR
MSIV-9	11/7/87:0800	Neverseeze tm Thread lubricant sample	IR
<i>Destroyed (consumed in analysis)</i> MSIV-10	11/7/87:0730	P52-F556: Instr. air at Containment penetration (outside). 10 min. blow-down, 5 min. purge of sampler.	GC
<i>MSIV-11 consumed</i>	11/7/87:0745	P52-F556: Instr. air at Containment penetration (outside). 10 min. blow-down, 15 min. purge of sampler.	GC
MSIV-12	11/7/87:1151	B21-F028B: Solenoid supply, $\approx 0.1 \text{ ft.}^3$ on 0.45μ particulate filter.	PSC
MSIV-13	11/7/87:1202	B21-F028B: Solenoid supply, $\approx 0.1 \text{ ft.}^3$ on 0.45μ particulate filter.	PSC
MSIV-14	11/7/87:1214	B21-F028B: Actuator supply, $\approx 0.1 \text{ ft.}^3$ on 0.45μ particulate filter.	PSC
MSIV-15	11/7/87:1220	B21-F028B: Actuator supply, $\approx 0.1 \text{ ft.}^3$ on 0.45μ particulate filter.	PSC
MSIV-16	11/7/87:1503	B21-F028B: Solenoid supply, $\approx 0.1 \text{ ft.}^3$ on 0.45μ particulate filter.	PSC

SAMPLE	DATE/TIME	DESCRIPTION	ANALYSIS
MSIV-17	11/7/87:1521	B21-F028B: Solenoid supply, $\approx 0.5\text{ft.}^3$ on 0.45 μ particulate filter.	PSC
MSIV-18	11/7/87:1537	B21-F028B: Actuator supply, $\approx 0.1\text{ft.}^3$ on 0.45 μ particulate filter.	PSC
MSIV-19	11/7/87:1553	B21-F028B: Actuator supply, $\approx 0.5\text{ft.}^3$ on 0.45 μ particulate filter.	PSC
MSIV-20	11/16/87:1600	B21-F028D: Solenoid valve body.	
MSIV-21	11/16/87:1600	Solenoid Rebuild Kits (3 kits w/ elastomer parts)	
MSIV-22	11/16/87:1600	B21-F028A: Gaskets, disc, core assembly.	
MSIV-23	11/16/87:1600	B21-F022B: Gaskets, disc, core assembly.	
MSIV-24	11/16/87:1600	B21-F028B: Gaskets, disc, core assembly.	
MSIV-25	11/16/87:1600	B21-F022C: Gaskets, disc, core assembly.	
MSIV-26	11/16/87:1600	B21-F028C: Gaskets, disc, core assembly.	
MSIV-27	11/16/87:1600	B21-F022D: Gaskets, disc, core assembly.	
MSIV-28	11/16/87:1600	B21-F028D: Gaskets, disc, core assembly.	
MSIV-29	11/30/87:1230	B21-F022B: Plungers, solenoid "B"	
MSIV-30	11/30/87:1230	B21-F022B: Core Assembly, seats & gaskets.	
MSIV-31	11/30/87:1230	B21-F022B: Valve body.	
MSIV-32	11/30/87:1230	B21-F022B: Foreign Material from Plunger area "B" solenoid (3 particles total)	
MSIV-33	11/30/87:2200	B21-F022B: Instrument Air grab sample from 2" supply.	
MSIV-34	11/30/87:2215	B21-F022B: Instrument Air grab sample from Solenoid supply line.	




FIGURE M47-1 STEAM TUNNEL COOLING SYSTEM

58

Roger Lanksbury
NRC Office 59
—

CLASS 1E SOLENOID VALVES
(ASCO NP SERIES)

EXCLUDING THE MSIV APPLICATIONS, PNPP EMPLOYS A TOTAL OF 55 OF THE SUBJECT VALVES.

OF THIS 55, 37 ARE EITHER LOCATED IN MILD ENVIRONMENTS OR HAVE NO DESIGN BASIS EVENT SAFETY FUNCTION AND ARE VERIFIED NOT TO FAIL IN A MANNER DETRIMENTAL TO OTHER SAFETY SYSTEMS, ie, ARE CLASSIFIED AS "A3" (NUREG 0588 APPENDIX E, PARA.2.C.)

EXCLUDING THESE 37 LEAVES A TOTAL OF 18 WITH DESIGN BASIS EVENT SAFETY FUNCTIONS FOR WHICH THEY ARE CURRENTLY QUALIFIED. OF THIS 18 THERE ARE A TOTAL OF 5 WHICH ARE OF NORMALLY-ENERGIZED CONFIGURATION.

TECH. SPEC REQUIREMENTS REQUIRE THAT THESE 5 BE CYCLED PER THE APPLICABLE SVI'S AT FREQUENCIES OF 92 DAYS (QUARTERLY) OR LESS.

BASED ON MAINTENANCE HISTORIES REVIEW, THE SVI'S HAVE BEEN PERFORMED PROPERLY, AS SCHEDULED. NONE OF THE WORK HISTORIES SHOW ANY PROBLEMS WITH THE OPERABILITY OF THESE SOLENOID VALVES WITH RESPECT TO SEAT/DISC "STICKING".

Roger
If you have any questions
on this, I can be reached
on X 5183.

Kim Matheny

0-59

← LEAK HISTORY →

60

F028D → 90



NEXT

DO COMPLETE WD

F028B → START WITH

① TEMP COMPARED TO LOCATION OF RESERVOIR
AND COMPARED TO LEAKS LOCATIONS

② LOOK AT ARI DATES FOR STEAM
LEAK OFF DATES

BUI - PACKAGES

D-60

REPORT ON PARTICLES-
INSTRUMENT AIR AT MSIV'S

D. L. ... 12/2/57
Prepared By Date

INTRODUCTION

Samples were collected on instrument air supply lines on November 7, 1987 to visually inspect and measure particles collected on 0.45 micron, gridded filter paper. The samples were then logged and sent to Ricerca Inc. for visual inspection and sizing.

METHOD

The samples were collected by installing a filter paper holder assembly in series with a rotameter to determine flow rate. The filter paper holder assembly with rotameter was then connected to the MSIV instrument air supply line with tygon tubing. Air was then admitted to the filter paper until a total of 0.1 cubic feet was collected (0.5 cubic feet for samples MSIV-17 & MSIV-19). This total volume was selected as this is the standard volume drawn for sample collection by the laboratory particle counter. Results obtained could then be more closely correlated to past data collected by use of the particle counter.

The samples were then transported to Ricerca Inc. for inspection and measurement. The particles were inspected and measured by Ricerca laboratory personnel using a Zeiss Universal optical microscope at a magnification power of 125x for particles < 40 microns and at 161x for particles > 40 microns.

The calibrated eyepiece used to measure the particles was calibrated against a stage micrometer. Any fibers found were classified as fibers (instead of particles) if their length to width ratio was greater than 10:1.

Each filter had an effective filtering area of 980 square millimeters. For each sample, this entire area was evaluated.

RESULTS

Table 1 lists the samples by number, total number of particles >20 microns and the actual particle size.

The particle characteristics could be described as follows:

- 1. Clear, crystalline-like particles *
- 2. White, cloudy particles *
- 3. Dark particles *
- 4. Metallic-like particles
- 5. Fibers

DSS

* indicates the type of particles making up the majority of the particles >40 microns. Non-asterisked particles and fibers were relatively few in number by comparison, but several were greater than 40 micron in size.



CONCLUSION

Because of the probability of some contamination occurring due to the large amount of exposed sample handling involved with the filter paper collection method, it is not easily ascertained what percentage of these results may be due to contamination. It is suspected that the majority of fibers found are dust particles from room air. The particle counter instrument is currently being recalibrated to detect and quantify particles in the 40-50 micron and >50 micron range and will be used to test the validity of the filter paper collection results.

Table 1

MSIV-4 (22b)

Particle #1	43	μm
2	43	
3	56	
4	62	
5	68	
6	68	

No fibers found

MSIV-6 (21b)

Particle #1	37	μm
2	56	
3	68	
4	68	
5	68	
6	87	
7	93	
8	124	
9	155	
10	260	
Fiber #1	143	
2	>160	
3	>600	
4	NM	
5	NM	

NM=not measured

MSIV-12 (28B)

Particle #1	38	μm
2	50	
3	62	
4	74	
5	>186	
6	280	

No fibers found

MSIV-14 (28B)

Particle #1	40	μm
2	43	
3	50	
4	50	
5	62	
6	62	
7	81	
8	87	
9	105	
10	130	

No fibers found

MSIV-5 (22b)

Particle #1	56	μm
2	130	
3	167	
4	186	
Fiber #1	>500	

MSIV-7 (210)

Particle #1	38	μm
2	40	
3	50	
4	62	
5	81	
6	93	
7	93	

No fibers found

MSIV-13 (28B)

Particle #1	43	μm
2	50	
3	68	
4	87	
5	174	
6	174	
Fiber #1	217	
2	279	
3	400	
4	3000	

MSIV-15 (28B)

Particle #1	43	μm
2	50	
3	136	
Fiber #1	>700	
2	>6000	

MSIV-16 (2e3)

Particle #1	56 μ m
2	56
3	87

No fibers found

MSIV-18 (2e3)

Particle #1	38 μ m
2	62
3	68
4	74
5	124

No fibers found

MSIV-17 (2e3)

Particle #1	43 μ m
2	62
3	62
4	43
5	68
6	68

No fibers found

MSIV-19 (2e3)

Particle #1	74 μ m
2	143
3	217
4	NM

Fiber #1 NM

NM=not measured

ISEG Review of R61 & C91 for MSIV Failure

The Independent Safety Engineering Group was asked to review the Sequence of Events Recorder and Process Computer Sequence of Events Log over the time period that the Main Steam Isolation Valves (MSIVs) were being tested. The October 29 and November 3, 1987 printouts were reviewed for any alarms associated with the MSIVs. There were no alarms associated with the MSIVs on the Sequence of Events Recorder. The Process Computer Sequence of Events Log appropriately listed those times when the MSIVs moved past the ninety percent open position.

Stephen K. Wagner
ISEG Supervisor

D-57

10-23-87

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
10:33:53.914	H21MC050	MSL ISULATION CH D	TRIPPED
10:33:53.930	H21MC047	MSL ISULATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
18:39:36.167	B2INC047	MSE ISULATION CH A	RESET
18:39:36.337	B2INC050	MSE ISULATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
21:01:01.268	B2INC050	MSL ISOLATION CH D	TRIPPED
21:01:01.294	B2INC047	MSL ISOLATION CH A	TRIPPED
21:03:25.506	B2INC047	MSL ISOLATION CH A	RESET
21:03:25.467	B2INC050	MSL ISOLATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
21:04:50.029	02INC050	MSL ISOLATION CH D	TRIPPED
21:04:50.054	02INC047	MSL ISOLATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
21:05:27.769	B2INC047	MSL ISULATION CH A	RESET
21:05:27.923	B2INC050	MSL ISULATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
21:42:00.562	B21NCL050	MSL ISOLATION CH D.	TRIPPED
21:42:00.582	B21NCL047	MSL ISOLATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
21:43:09.081	B2INC047	MSL ISOLATION CH A	RESET
21:43:09.146	B2INC050	MSL ISOLATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
21:49:08.592	021MC050	MSL ISOLATION CH D	TRIPPED
21:49:08.615	021MC047	MSL ISOLATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS

TIME	PT ID	NAME	STATUS
21:49:54.751	H21NC047	MSL ISOLATION CH A	RESET
21:49:54.815	B21NC050	MSL ISOLATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
22:09:59.097	B21M048	MSL ISOLATION CH B	TRIPPED
22:09:59.105	B21M049	MSL ISOLATION CH C	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LUB

TIME	PT ID	NAME	STATUS
22:10:52.509	H2INC049	MSL ISOLATION CH C	RESET
22:10:52.521	H2INC048	MSL ISOLATION CH B	RESET

END SEQUENCE OF EVENTS LUB

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
22:11:52.824	B2INC048	MSL ISOLATION CH B	TRIPPED
22:11:52.854	B2INC047	MSL ISOLATION CH A	TRIPPED
22:12:19.730	B2INC047	MSL ISOLATION CH A	RESET
22:12:19.763	B2INC048	MSL ISOLATION CH B	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
22:13:17.567	B2INC049	MSL ISOLATION CH C	TRIPPED
22:13:17.589	B2INC050	MSL ISOLATION CH D	TRIPPED
22:13:37.218	B2INC050	MSL ISOLATION CH D	RESET
22:13:37.252	B2INC049	MSL ISOLATION CH C	RESET

END SEQUENCE OF EVENTS LOG

11

22:14:27.120
22:14:27.758

PI 10

821MC049
821NC046

MSL ISOLATION CH C
MSL ISOLATION CH B

TRIPPED
TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
22:15:21.447	B2INC048	MSL ISOLATION CH B	RESET
22:15:21.490	B2INC049	MSL ISOLATION CH C	RESET
22:15:48.798	B2INC049	MSL ISOLATION CH C	TRIPPED
22:15:48.814	B2INC048	MSL ISOLATION CH B	TRIPPED
22:16:13.251	B2INC048	MSL ISOLATION CH B	RESET
22:16:13.291	B2INC049	MSL ISOLATION CH C	RESET
22:16:42.202	B2INC047	MSL ISOLATION CH A	TRIPPED
22:16:42.241	B2INC048	MSL ISOLATION CH B	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
22:17:28.832	B2INC048	MSL ISOLATION CH B	RESET
22:17:28.999	B2INC047	MSL ISOLATION CH A	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
22:18:10.585	H2INC050	MSL ISOLATION CH D	TRIPPED
22:18:10.647	H2INC049	MSL ISOLATION CH C	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
22:19:12.770	B2INC049	MSL ISOLATION CH C	RESET
22:19:13.011	B2INC050	MSL ISOLATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
22:33:21.383	B2INC050	MSL ISULATION CH D	TRIPPED
22:33:21.753	B2INC047	MSL ISULATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
23:37:01.582	021NC047	MSL ISOLATION CH A	RESET
23:37:01.647	021NC050	MSL ISOLATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
11:55:59.454	021NC048	MSL ISULATION CH B	TRIPPED
11:55:59.463	021NC049	MSL ISULATION CH C	TRIPPED

-END-SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
11:57:08.313	02INC049	MSL ISOLATION CH C	RESET
11:57:08.317	02INC048	MSL ISOLATION CH H	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
11:58:17.452	B2INC050	MSL ISOLATION CH D	TRIPPED
11:58:17.475	B2INC047	MSL ISOLATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
11:59:22.881	B21NC047	MSL ISOLATION CH A	RESET
11:59:23.040	B21NC050	MSL ISOLATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:00:21.535	B21NC050	MSL ISOLATION CH D	TRIPPED
12:00:21.559	B21NC047	MSL ISOLATION CH A	TRIPPED
12:01:17.993	B21NC047	MSL ISOLATION CH A	RESET
12:01:18.153	B21NC050	MSL ISOLATION CH D	RESET
12:02:08.251	B21NC046	MSL ISOLATION CH B	TRIPPED
12:02:08.259	B21NC047	MSL ISOLATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	GAME	STATUS
12:03:28.942	B2INC047	MSL ISOLATION CH A	RESET
12:05:28.977	H2INC048	MSL ISOLATION CH H	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:04:16.599	B21MC049	MSL ISOLATION CH C	TRIPPED
12:04:16.605	B21MC050	MSL ISOLATION CH D	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:05:49.436	02INC050	MSL ISOLATION CH D	RESET
12:05:49.451	02INC049	MSL ISOLATION CH C	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:07:53.458	B2INC049	MSL ISOLATION CH C	TRIPPED
12:07:53.475	B2INC048	MSL ISOLATION CH B	TRIPPED

END SEQUENCE OF EVENTS LOG

UNIT PAGE 1

11-03-87 12:09

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:08:44.256	H21NC048	MSL ISOLATION CH B	RESET
12:08:44.298	H21NC049	MSL ISOLATION CH C	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
12:14:28.474	B21NC050	MSL ISOLATION CH D	TRIPPED
12:14:28.498	B21NC007	MSL ISOLATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:15:52.688	321MC047	MSL ISOLATION CH A	RESET
12:15:52.755	021MC050	MSL ISOLATION CH D	RESET

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:18:15.284	B21NC050	MSL ISOLATION CH D	TRIPPED
12:18:15.307	B21NC047	MSL ISOLATION CH A	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:19:23.161	02INC047	MSL ISOLATION CH A	RESET
12:19:23.247	02INC050	MSL ISOLATION CH B	RESET

- END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:20:18.753	H2INC047	MSL ISOLATION CH A	TRIPPED
12:20:18.790	H2INC048	MSL ISOLATION CH B	TRIPPED

END SEQUENCE OF EVENTS LOG

RESEI
RESEI

MSL ISULATION C/A

MCINLU007

SEQUENCE OF EVENTS LOG

END

UNIT PAGE 1

11-03-07 12:22

SEQUENCE OF EVENTS LOG

TIME	PT ID	NAME	STATUS
12:22:21.050	021NC050	MSL ISULATION CH D	TRIPPED
12:22:21.114	021NC049	MSL ISULATION CH C	TRIPPED

END SEQUENCE OF EVENTS LOG

SEQUENCE OF EVENTS LOG

TIME	PI ID	NAME	STATUS
12:23:58.567	821NC049	MSL ISOLATION CH C	RESET
12:23:58.806	821NC050	MSL ISOLATION CH D	RESET

--END SEQUENCE OF EVENTS LOG

PNPP No. 7310
Rev 2/87

INTENT INSTRUCTION TEMPORARY CHANGE

PAP-0522-2

TEMPORARY CHANGE NO.
TCN- 10

INSTRUCTION NO. OM/A: SVI-C71-T0039	REV 1	INSTRUCTION TITLE MAIN STEAM LINE ISOLATION VALVE CLOSURE CHANNEL FUNCTIONAL
UNCL'S TCN(S): NONE		

ORIGINATOR <i>Paul A. White</i>	DATE 9/14/87	LIST EACH ATTACHED PAGE: 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 14, 15, 16, 17, 18, 19, 20
------------------------------------	-----------------	---

REASON: Half Scrums and associated annunciators will not occur as described by this instruction. Deleted those steps that were not in accordance with the system logic.	ADMIN USE ONLY INFORMATION ONLY
REVIEWED <i>William T. S... ..</i>	DATE 9-14-87

10CFR50.59 APPLICABILITY CHECK	YES	NO
Is there a change to the plant as described in the FSAR? REASON: <u>NO CHANGE TO PLANT IS INVOLVED.</u>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Is there a change to a procedure/instruction as described in the FSAR? REASON: <u>THIS INSTRUCTION IS NOT DETAILED IN THE FSAR.</u>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Is there a test or experiment not described in the FSAR? REASON: <u>NO TEST OR EXPERIMENT IS INVOLVED.</u>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Is there a change to Technical Specifications?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Is there an effect on the environment or change to the Environmental Protection Plan? REASON: <u>NO EFFECT ON THE ENVIRONMENT OR CHANGE TO THE EPP IS INVOLVED.</u>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input checked="" type="checkbox"/> Answers to all questions are 'NO'. No potential for an Unreviewed Safety or Environmental Question exists. No further review required.		
<input type="checkbox"/> Answers to one or more questions is 'YES'. Further review required.		

PREPARED <i>W.D. S... ..</i>	DATE 9-14-87	REVIEWED <i>Joseph C. Hale</i>	DATE 9/14/87	APPROVED <i>D. Phillips FOR RAN</i>	DATE 9-14-87
---------------------------------	-----------------	-----------------------------------	-----------------	--	-----------------

APPROVAL	RESPONSIBLE GS/GSE <i>D. Phillips FOR RANENKIRK</i>	DATE 9-14-87
----------	--	-----------------

APPROVAL	PORC MTD. NO.:	MANAGER PPTD	DATE
	RECOMMENDED FOR <input type="checkbox"/> APPROVAL <input type="checkbox"/> DISAPPROVAL	MANAGER PPOD	DATE

EFFECTIVE DATE
9-14-87

DISAPPROVAL	REASON FOR DISAPPROVAL	DATE
		BY <i>Miled C.</i> DATE 9-14-87

FORM NO. 7329
Rev. 2-87
REF. C522-1

NON-INTENT INSTRUCTION TEMPORARY CHANGE

TEMPORARY CHANGE NO. **9**
TCN-

INSTRUCTION NO. DM7A.SVI-C71-T0039	REV. 1	INSTRUCTION TITLE MSL ISOL VLV CLOSURE CH. FUNCT
CANCELS TCN(S) N/A		
ORIGINATOR Jerry Wood	DATE 3-25-87	LIST EACH ATTACHED PAGE: 4.15

PROCESS FOR: CONDITIONAL APPROVAL FINAL APPROVAL ONLY

ADMIN. USE ONLY

REASON
**DELETE STEPS THAT REQUIRE MSIN VALVE
STEMS TO BE LUBRICATED AS PER SYSTEM ENG.**

CONDITIONAL APPROVAL/IN DEPTH REVIEW

CONDITIONAL APPROVAL

(F. NO. OF APPROVALS)
- Robert Muzzi DATE **3/27/87**

(SS OF US) **N/A** DATE

EFFECTIVE DATE
4-7-87

FINAL APPROVAL	APPROVED	RESPONSIBLE GS/GSE DB Philips FOR RANWEIRE	DATE 4-2-87
	RECOMMENDED FOR: <input type="checkbox"/> APPROVAL <input type="checkbox"/> DISAPPROVAL	MANAGER PPTD MANAGER PPOD	DATE DATE
DISAPPROVAL	REASON FOR DISAPPROVAL		DATE
			BY J. Brinnick DATE 4/7/87

INTENT

INSTRUCTION TEMPORARY CHANGE

PAP-C522-2

TEMPORARY CHANGE NO.
TCN- 8

INSTRUCTION NO. D017A-SVI-C71-10039	REV 1	INSTRUCTION TITLE MSIV CLOSURE CH FUNCTIONAL
CANCELS TCN(S) 1, 2, 5, 6, 7		

ORIGINATOR Jonny Wozett	DATE 3-4-87	LIST EACH ATTACHED PAGE: 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 14, 14a, 4a, 15, 16, 17, 18, 19, 20, 21
----------------------------	----------------	--

REASON: ADD STEP TO INFORM U.S. THAT MSIV'S MAY NEED LUBRICATING; CANCEL & INCORP. ALL TC'S TO EASE IN PERFORMANCE OF SVI.	ADMIN USE ONLY
--	----------------

REVIEWED Robert Murray	DATE 3-11-87
---------------------------	-----------------

DOCS/SG: APP. TCABILITY CHECK

Is there a Change to the plant as described in the FSAR? YES NO

REASON: The design of the plant is not changed by this SVI or TCN

Is there a Change to a procedure/instruction as described in the FSAR? YES NO

REASON: The details of this instruction aren't defined in the FSAR

Is there a Test or experiment not described in the FSAR? YES NO

REASON: This is not a Test or Experiment. The responsibility for cycling MSIV's is directed to Operators by this TCN.

Is there a Change to Technical Specification? YES NO

Is there an effect on the environment or change to the Environmental Protection Plan? YES NO

REASON: No impact on environment

Answers to all questions are 'NO'. No potential for an Unreviewed Safety or Environmental Question exist. No further review required.

Answers to one or more questions is 'YES'. Further review required.

PREPARED Robert Murray	DATE 3-11-87	REVIEWED Jonny Wozett	DATE 3/11/87	APPROVED R. Steel for R.A.	DATE 3-12-87
---------------------------	-----------------	--------------------------	-----------------	-------------------------------	-----------------

APPROVAL	RESPONSIBLE OFFICER Robert H. Steel for R.A. Newland	DATE 3-12-87
----------	---	-----------------

APPROVAL	RECOMMENDED FOR <input type="checkbox"/> APPROVAL <input type="checkbox"/> DISAPPROVAL	MANAGER PPTC	DATE
		MANAGER PPOC	DATE

EFFECTIVE DATE
3-13-87

DISAPPROVAL	REASON FOR DISAPPROVAL	DATE
	BY J. Barnhart	DATE 3/13/87

OM7A: SVI-C71-T0039
Page: 1
Rev.: 1

THE CLEVELAND ELECTRIC ILLUMINATING COMPANY
PERRY NUCLEAR POWER PLANT OPERATIONS MANUAL

Surveillance Instruction

TITLE: MAIN STEAM LINE ISOLATION
VALVE CLOSURE CHANNEL FUNCTIONAL

REVISION: 1

EFFECTIVE DATE: 10/23/85

		DATE
PREPARER:	T.B. SHAFFER/ R.C. MILLER	10/15/85
REVIEWER:	<i>Donald Bushart</i>	10/16/85
PORC MEETING NO:	<i>N/A</i>	
APPROVED:	<i>[Signature]</i>	10/17/85

10CFR50.59 Applicability Check

	<u>Yes</u>	<u>No</u>
Is there a change to the plant as described in the FSAR?	—	✓
Is there a change to a procedure/instruction as described in the FSAR?	—	✓
Is there a test or experiment not described in the FSAR?	—	✓
Is there a change to the Technical Specification?	—	✓
(If yes, perform a 10CFR50.59 Safety Evaluation per PAP-0305).		

Applicability Check Performed by <u><i>S. Anderson</i></u>		Date <u><i>10/16/81</i></u>

- SCOPE OF REVISION:
1. Instruction revised to incorporate format changes of TAP-0503.
 2. Numerous corrections were made throughout the instruction.

Main Steam Line Isolation
Valve Closure Channel Functional

1.0 DESCRIPTION

1.1 Scope:

The Main Steam Line Isolation Valve Closure instrumentation channels are functionally tested by stroking the MSIV's and monitoring each trip relay and their common annunciator.

This instruction fully satisfies the functional surveillance requirements of Technical Specification 4.3.1.1 Table 4.3.1.1-1 Item 6.

TC
8

This instruction fully satisfies the functional surveillance requirements of Technical Specification 4.3.1.1 Table 4.3.1.1-1 Item 6, and the fail safe function and partial exercise testing of valves 1B21-F022A, 1B21-F022B, 1B21-F022C, 1B21-F022D, 1B21-F026A, 1B21-F026B, 1B21-F026C and 1B21-F026D per Technical Specification 4.0.5.

This instruction will verify the operability of the following:

- | | |
|---------------|----------------|
| 1. 1C71-N700A | 9. 1C71-N702A |
| 2. 1C71-N700B | 10. 1C71-N702B |
| 3. 1C71-N700C | 11. 1C71-N702C |
| 4. 1C71-N700D | 12. 1C71-N702D |
| 5. 1C71-N701A | 13. 1C71-N703A |
| 6. 1C71-N701B | 14. 1C71-N703B |
| 7. 1C71-N701C | 15. 1C71-N703C |
| 8. 1C71-N701D | 16. 1C71-N703D |

1.2 Frequency: At least once per 31 days

TC
8

1.3 Technical Specification Applicable Operational Conditions:
1(c)

(c) This function shall be automatically bypassed when the REACTOR MODE SWITCH is not in the RUN position.

1.4 Cross-Reference: N/A

2.0 PRECAUTIONS AND LIMITATIONS

- Step numbers marked with a dollar sign (\$) immediately to the left are required by Technical Specifications. Such items, if found to exceed their Allowable Value may be NRC reportable and shall be brought to the attention of the Unit Supervisor.
- Those steps of this instruction designated by an "at" sign (@) are to be initialed or signed on the appropriate data sheet or Data Package Cover Sheet as data is entered or as each step is completed.

TC
8

3. All steps are to be performed in sequence and the instruction carried through to completion, unless otherwise indicated.
4. The Unit Supervisor or designated alternate must be notified immediately whenever an instructional step cannot be completed as stated, or if problems develop during the performance of this instruction.
5. This instruction should be read in its entirety before proceeding with the performance of the instructional steps.
6. During the performance of this SYI the INBD and OTBD MSIV's will be stroked, in modes 1, 2 or 3 a steam sink may be required.

DELETED

8. Channel(s) will be made inoperable in section 5.0 of this instruction.
9. To avoid unnecessary valve wear, full stroking of MSIV's must be kept to a minimum.

3.0 MANPOWER AND EQUIPMENT

3.1 Manpower/Communications

1. Two I&C technicians are required to perform this instruction.
 - a. Two technicians in Control Room to monitor the trip relays at the following panels:
 1. DIV 1 RPS INSTRUMENTATION & AUXILIARY RELAY PANEL (1H13-P691)
 2. DIV 2 RPS INSTRUMENTATION & AUXILIARY RELAY PANEL (1H13-P692)
 3. DIV 3 RPS INSTRUMENTATION & AUXILIARY RELAY PANEL (1H13-P693)
 4. DIV 4 RPS INSTRUMENTATION & AUXILIARY RELAY PANEL (1H13-P694)
2. Establish communications between the technicians and the Supervising Operator.

3.2 Required Measuring and Test Equipment (M&TE)

1. 2 Digital Multimeters (DMM-1 & DMM-2), Fluke 77.

3.3 Additional Tools and Equipment

1. Keys needed for P691, P692, P693 and P694.

TC
8 |

4.0 PREREQUISITES

- 0 1. Obtain the Unit Supervisor's "Authorization to Start Prerequisites" signature on the Data Package Cover Sheet.

TC
8 |

- 0 2. This instruction may be performed in Operational Condition 1, 2, 3, 4 or 5. Attachment 1.

- 0 3. Verify that no testing or maintenance is being performed which would initiate a half scram RPS signal. Attachment 1.

4. Verify the following annunciators are reset:
Attachment 1.

- 0 a. 1/2 SCRAM A/C (P680-5A-A9)
- 0 b. 1/2 SCRAM B/D (P680-5A-B9)

R
17 |

5. a. DELETED

6. If Unit is in MODE 3, 4, or 5, verify the following:
Attachment 2.

- 0 a. C95 computer point RPS CHANNEL ISOLATION A STATUS, B21EC013 indicates NORM.
- 0 b. C95 computer point RPS CHANNEL ISOLATION B STATUS, B21EC014 indicates NORM.
- 0 c. C95 computer point RPS CHANNEL ISOLATION C STATUS, B21EC015 indicates NORM.
- 0 d. C95 computer point RPS CHANNEL ISOLATION D STATUS, B21EC016 indicates NORM.

TC
8 |

- 0 7. A RWP may be required for performance of this instruction. Attachment 1.

TEMP CHANGE
10
PAGE 3 OF 17

TEMP CHANGE
9
PAGE 1 OF 2

TEMP CHANGE
8
PAGE 4 OF 21

OM7A: SVI-C71-T0039
Page: 4
Rev.: 1

TC
8

8. Verify the Calibration Due Date is current on all test equipment. Attachment 1.
9. Record all test instruments, MPL, Cal Date, and Cal Due Date. Attachment 2.
10. Verify the following: Attachment ~~2~~ ¹.
 - a. Switch 1C71A-S6A MAIN STEAM LINE ISOL VALVE TEST (P691) is in the NORM position.
 - b. Switch 1C71A-S6B MAIN STEAM LINE ISOL VALVE TEST (P692) is in the NORM position.
 - c. Switch 1C71A-S6C MAIN STEAM LINE ISOL VALVE TEST (P693) is in the NORM position.
 - d. Switch 1C71A-S6D MAIN STEAM LINE ISOL VALVE TEST (P694) is in the NORM position.

5.0 SURVEILLANCE INSTRUCTION

5.1 Surveillance Test

1. Obtain the Supervising Operator's "Authorization to Start Test" signature on the Data Package Cover Sheet.
2. ~~Inform Supervising Operator that the following annunciators will come on and reset during this surveillance:~~
 - a. ~~RPS RSTV CLOSURE (P680-5A-A6) (MODE 1 only)~~
 - b. DELETED
 - c. DELETED

TC
10
TC | TC
9 | 8

TC

8

TEMP CHANGE
• 8
PAGE 5 OF 21

OM7A: SYI-C71-T0039
Page : 4a
Rev. : 1

(PAGE INTENTIONALLY LEFT BLANK)

TC
8

5. Connect Digital Multimeter (DMM-1) to terminals B and C of relay 1C71A-K3A (P691) (set to ohms).
6. Connect Digital Multimeter (DMM-2) to terminals B and C of relay 1C71A-K3B (P692) (set to ohms).
- e 7. Inform Unit Supervisor that the MSIV's will be stroked. Record time and date. Obtain U.S. signature. Attachment 2.
- e 8. Request Supervising Operator to place MSL A INBD MSIV 1B21-F022A switch (P601-18C) to TEST. Attachment 2.
- e 9. Request Supervising Operator to place MSL A OTBD MSIV 1B21-F028A switch (P601-19C) to TEST. Attachment 2.

TC
10

10. Request Supervising Operator to depress and hold MSL A INBD MSIV TEST switch 1B21H-S3A (P601-18C) until the following occurs, when release switch:
Attachment 2.

- e a. MSL A INBD MSIV 1B21-F022A green indicating light (P601-18C) is on.
- b. DMM-1 indicates relay 1C71A-K3A contact closed.
- c. DMM-2 indicates relay 1C71A-K3B contact closed.
- d. DELETED

11. After MSL A INBD MSIV 1B21-F022A green indicating light (P601-18C) is off, verify the following:
Attachment 2.

- e a. MSL A INBD MSIV 1B21-F022A green indicating light (P601-18C) is off.
- e b. DMM-1 indicates relay 1C71A-K3A contact open.
- e c. DMM-2 indicates relay 1C71A-K3B contact open.

TC
8
101

TC
8

TC
10 |

12. Request Supervising Operator to depress and hold MSL A OTBD MSIV TEST switch 1B21H-S4A (P601-19C) until the following occurs, then release switch:
Attachment 2.

TC
10 | TC
8 | se
se

- a. MSL A OTBD MSIV 1B21-F028A green indicating light (P601-19C) is on.
- b. DMM-1 indicates relay 1C71A-K3A contact closed.
- c. DMM-2 indicates relay 1C71A-K3B contact closed.
- d. DELETED

13. After MSL A OTBD MSIV 1B21-F028A green indicating light (P601-19C) is off, verify the following:
Attachment 2.

TC
10 | TC
8 |

- a. MSL A OTBD MSIV 1B21-F028A green indicating light (P601-19C) is off.
- b. DMM-1 indicates relay 1C71A-K3A contact open.
- c. DMM-2 indicates relay 1C71A-K3B contact open.
- d. DELETED

TC
8 |

14. If in Mode 1, 2 request Supervising Operator to place MSL A INBD MSIV 1B21-F022A switch (P601-18C) to AUTO.
Attachment 2.

TC
8 |

15. If in Mode 1, 2 request Supervising Operator to place MSL A OTBD MSIV 1B21-F028A switch (P601-19C) to AUTO.
Attachment 2.

16. If in Mode 3, 4, or 5, request Supervising Operator to place MSL A INBD MSIV 1B21-F022A switch (P601-18C) to CLOSE. Attachment 2.

17. If in Mode 3, 4, or 5, request Supervising Operator to place MSL A OTBD MSIV 1B21-F028A switch (P601-19C) to CLOSE. Attachment 2.

TC
8 |

18. Connect Digital Multimeter (DMM-1) to terminals B and C of relay 1C71A-K3C (P693) (set to Ω).

19. Connect Digital Multimeter (DMM-2) to terminals B and C of relay 1C71A-K3H (P694) (set to Ω).

20. Request Supervising Operator to place MSL C INBD MSIV 1B21-F022C switch (P601-18C) to TEST. Attachment 2.

TEMP CHANGE
10
PAGE 6 OF 17

TEMP CHANGE
8
PAGE 2 OF 21

OM7A: SVI-C71-T0039
Page: 7
Rev.: 1

- 21. Request Supervising Operator to place MSL C OTBD MSIV 1B21-F028C switch (P601-19C) to TEST. Attachment 2.
- 22. Request Supervising Operator to depress and hold MSL C INBD MSIV TEST switch 1B21H-S3C (P601-18C) until the following occurs, then release switch:
Attachment 2.
 - a. MSL C INBD MSIV 1B21-F022C green indicating light (P601-18C) is on.
 - b. DMM-1 indicates relay 1C71A-K3C contact closed.
 - c. DMM-2 indicates relay 1C71A-K3H contact closed.
 - d. DELETED
- 23. After MSL C INBD MSIV 1B21-F022C green indicating light (P601-18C) is off, verify the following:
Attachment 2.
 - a. MSL C INBD MSIV 1B21-F022C green indicating light (P601-18C) is off.
 - b. DMM-1 indicates relay 1C71A-K3C contact open.
 - c. DMM-2 indicates relay 1C71A-K3H contact open.
 - d. DELETED
- 24. Request Supervising Operator to depress and hold MSL C OTBD MSIV TEST switch 1B21H-S4C (P601-19C) until the following occurs, then release switch:
Attachment 2.
 - a. MSL C OTBD MSIV 1B21-F028C green indicating light (P601-19C) is on.
 - b. DMM-1 indicates relay 1C71A-K3C contact closed.
 - c. DMM-2 indicates relay 1C71A-K3H contact closed.
 - d. DELETED
- 25. After MSL C OTBD MSIV 1B21-F028C green indicating light (P601-19C) is off, verify the following:
Attachment 2.
 - a. MSL C OTBD MSIV 1B21-F028C green indicating light (P601-19C) is off.
 - b. DMM-1 indicates relay 1C71A-K3C contact open.
 - c. DMM-2 indicates relay 1C71A-K3H contact open.
 - d. DELETED
- 26. If in Model 2 request Supervising Operator to place MSL C INBD MSIV 1B21-F022C switch (P601-18C) to AUTO.
Attachment 2.

TC 8 | se
TC 8 | se
10 |

TC 8 | e
TC 8 | e
10 |

TC 8 | se
TC 8 | se
10 |

TC 8 | e
TC 8 | e
TC 8 | e
0 | TC 8 |

TC
8

- 27. If in Mode 1, 2 request Supervising Operator to place MSL C OTBD MSIV 1B21-F028C switch (P601-19C) to AUTO. Attachment 2.
- 28. If in Mode 3, 4, or 5, request Supervising Operator to place MSL C INBD MSIV 1B21-F022C switch (P601-18C) to CLOSE. Attachment 2.
- 29. If in Mode 3, 4, or 5, request Supervising Operator to place MSL C OTBD MSIV 1B21-F028C switch (P601-19C) to CLOSE. Attachment 2.

TC
10

- 30. DELETED
- 31. DELETED.

TC
8

- 32. Connect Digital Multimeter (DMM-1) to terminals B and C of relay 1C71A-K3G (P693) (set to ohms).
- 33. Connect Digital Multimeter (DMM-2) to terminals B and C of relay 1C71A-K3F (P692) (set to ohms).
- 34. Request Supervising Operator to place MSL B INBD MSIV 1B21-F022B switch (P601-18C) to TEST. Attachment 2.
- 35. Request Supervising Operator to place MSL B OTBD MSIV 1B21-F028B switch (P601-19C) to TEST. Attachment 2.

TC
10

- 36. Request Supervising Operator to depress and hold MSL B INBD MSIV TEST switch 1B21H-S3B (P601-18C) until the following occurs, then release switch: Attachment 2.

TC
8
TC
10

- a. MSL B INBD MSIV 1B21-F022B green indicating light (P601-18C) is on.
- b. DMM-1 indicates relay 1C71A-K3G contact closed.
- c. DMM-2 indicates relay 1C71A-K3F contact closed.
- d. DELETED

TC
8
TC
10

37. After MSL B INBD MSIV 1B21-F022B green indicating light (P601-18C) is off, verify the following: Attachment 2.

- e a. MSL B INBD MSIV 1B21-F022B green indicating light (P601-18C) is off.
- e b. DMM-1 indicates relay 1C71A-K3G Contact open.
- e c. DMM-2 indicates relay 1C71A-K3F Contact open.
- d. DELETED

38. Request Supervising Operator to depress and hold MSL B OTBD MSIV TEST switch 1B21H-S4B (P601-19C) until the following occurs, then release switch: Attachment 2.

TC
8
TC
10

- e a. MSL B OTBD MSIV 1B21-F028B green indicating light (P601-19C) is on.
- e b. DMM-1 indicates relay 1C71A-K3G Contact closed.
- e c. DMM-2 indicates relay 1C71A-K3F Contact closed.
- d. DELETED

39. After MSL B OTBD MSIV 1B21-F028B green indicating light (P601-19C) is off, verify the following: Attachment 2.

TC
8
TC
10

- e a. MSL B OTBD MSIV 1B21-F028B green indicating light (P601-19C) is off.
- e b. DMM-1 indicates relay 1C71A-K3G Contact open.
- e c. DMM-2 indicates relay 1C71A-K3F Contact open.
- d. DELETED

TC
8

e 40. If in Mode 1 or 2 request Supervising Operator to place MSL B INBD MSIV 1B21-F022B switch (P601-18C) to AUTO. Attachment 2.

e 41. If in Mode 1 or 2 request Supervising Operator to place MSL B OTBD MSIV 1B21-F028B switch (P601-19C) to AUTO. Attachment 2.

e 42. If in Mode 3, 4, or 5, request Supervising Operator to place MSL B INBD MSIV 1B21-F022B switch (P601-18C) to CLOSE. Attachment 2.

e 43. If in Mode 3, 4, or 5, request Supervising Operator to place MSL B OTBD MSIV 1B21-F028B switch (P601-19C) to CLOSE. Attachment 2.

TC
8

- 44. Connect Digital Multimeter (DMM-1) to terminals B and C of relay 1C71A-K3E (P691) (set to ON/OFF).
- 45. Connect Digital Multimeter (DMM-2) to terminals B and C of relay 1C71A-K3D (P694) (set to ON/OFF).
- 46. Request Supervising Operator to place MSL D INBD MSIV 1B21-F022D switch (P601-18C) to TEST. Attachment 2.
- 47. Request Supervising Operator to place MSL D OTBD MSIV 1B21-F028D switch (P601-19C) to TEST. Attachment 2.
- 48. Request Supervising Operator to depress and hold MSL D INBD MSIV TEST switch 1B21H-S3D (P601-18C) until the following occurs, then release switch:
Attachment 2.

TC
8
TC
10

- a. MSL D INBD MSIV 1B21-F022D green indicating light (P601-18C) is on.
- b. DMM-1 indicates relay 1C71A-K3E contact closed.
- c. DMM-2 indicates relay 1C71A-K3D Contact closed.
- d. DELETED

49. After MSL D INBD MSIV 1B21-F022D green indicating light (P601-18C) is off, verify the following:
Attachment 2.

TC
8
TC
10

- a. MSL D INBD MSIV 1B21-F022D green indicating light (P601-18C) is off.
- b. DMM-1 indicates relay 1C71A-K3E contact open.
- c. DMM-2 indicates relay 1C71A-K3D Contact open.
- d. DELETED

50. Request Supervising Operator to depress and hold MSL D OTBD MSIV TEST switch 1B21H-S4D (P601-19C) until the following occurs, then release switch:
Attachment 2.

TC
8
TC
10

- a. MSL D OTBD MSIV 1B21-F028D green indicating light (P601-19C) is on.
- b. DMM-1 indicates relay 1C71A-K3E Contact closed.
- c. DMM-2 indicates relay 1C71A-K3D Contact closed.
- d. DELETED

51. After MSL D OTBD MSIV 1B21-F028D green indicating light (P601-19C) is off, verify the following:
Attachment 2.

TC
10 |

TC
8 |

- e a. MSL D OTBD MSIV 1B21-FC28D green indicating light (P601-19C) is off.
- e b. DMM-1 indicates relay 1C71A-K3E contact open.
- e c. DMM-2 indicates relay 1C71A-K3D contact open.
- d. DELETED

TC
10 |

- e 52. If in Mode 1, request Supervising Operator to place MSL D INBD MSIV 1B21-F022D switch (P601-18C) to AUTO. Attachment 2.
- e 53. If in Mode 1, request Supervising Operator to place MSL D OTBD MSIV 1B21-F028D switch (P601-19C) to AUTO. Attachment 2.
- e 54. If in Mode 3, 4, or 5, request Supervising Operator to place MSL D INBD MSIV 1B21-F022D switch (P601-18C) to CLOSE. Attachment 2.
- e 55. If in Mode 3, 4, or 5, request Supervising Operator to place MSL D OTBD MSIV 1B21-F028D switch (P601-19C) to CLOSE. Attachment 2.

56. DELETED

57.

58. DISCONNECT DMM-1 and DMM-2.

TC
8 |

- e 60. Inform Unit Supervisor that the stroking of the MSIV's is completed. Record time and date. Obtain U.S. signature. Attachment 2.

5.2 Plant/System Restoration

- e 1. Complete the System Restoration Checklist (Attachment 3) using the methods of Independent Verification. Upon completion, inform Supervising Operator of system restoration and return the keys for P691, P692, P693 and P694.

5.3 Acceptance Criteria

1. If any Technical Specification required items as indicated by dollar signs (\$) on the Data Sheet have not been performed satisfactorily, notify the Unit Supervisor.
2. If any other items checked in this surveillance did not perform satisfactorily, notify the I&C Supervisor.
3. Satisfactory completion of the surveillance will be based on Technical Specification items (marked with a dollar sign) only.
- ④ 4. Check the appropriate block on the Data Package Cover Sheet as to whether the test results were acceptable or unacceptable and obtain Unit Supervisor's signature.

5.4 Records

The following documents are generated by this instruction:

1. Quality Assurance Records:

Data Package Cover Sheet
Prerequisites Sign-off Sheet
Data Sheets
System Restoration Checklist

2. Non Quality Records:

None

Records identification and disposition are accomplished in accordance with Records Retention/Disposition Schedule (RR/DS) and handled in accordance with PAP-1701, Plant Records Management.

6.0 REFERENCES

6.1 CEI Perry Technical Specifications

6.2 CEI Prints

B-208-013
B-108-040
B-208-222

OM7A: SVI-C71-T0039
Page: 13
Rev.: 1

7.0 ATTACHMENTS

- 7.1 Attachment 1-Prerequisites Sign-off Sheet
- 7.2 Attachment 2-Data Sheets
- 7.3 Attachment 3-System Restoration Checklist
- 7.4 Attachment 4-Relay Base Diagram

TEMP CHANGE
10
PAGE 11 OF 17

Attachment 1
Sheet 1 of 1

TEMP CHANGE
8
PAGE 13 OF 21

OM7A: SVI-C71-T0039
Page: 14
Rev.: 1

Main Steam Line Isolation
Valve Closure Channel Functional
Prerequisite Sign-off Sheet

Initials

- TC-10 | 4.0.2. This instruction may be performed in Operational Condition 1, 2, 3, 4 or 5. _____
- 4.0.3. No testing or maintenance is being performed which would initiate a half scram RPS signal. _____
- 4.0.4. The following annunciators are reset:
a. 1/2 SCRAM A/C (P680-5A-A9) _____
b. 1/2 SCRAM B/D (P680-5A-B9) _____
- TC-10 | 4.0.5. DELETED
- 4.0.6. If unit is in MODE 3, 4, or 5:
a. C95 computer point, RPS CHANNEL ISOLATION A STATUS, B21EC013 indicates NORM. _____
b. C95 computer point, RPS CHANNEL ISOLATION B STATUS, B21EC014 indicates NORM. _____
c. C95 computer point, RPS CHANNEL ISOLATION C STATUS, B21EC015 indicates NORM. _____
d. C95 computer point, RPS CHANNEL ISOLATION D STATUS, B21EC016 indicates NORM. _____
- TC-8 | 4.0.7 An RWP in effect: YES NO _____
- 4.0.8. Calibration Due Date is current on all test equipment. _____
- TC-8 | — SEE ATTACHED PAGE 14a —

Performed by: _____
Signature Initials Date

TC
8

TEMP CHANGE
PAGE 14 OF 21

OM7A: SYI-C71-T0039

Page : 14a

Rev. : 1

Attachment 1 (Cont.)

Sheet 1a of 1

Initials

4.0.10.a. Switch 1C71A-S6A MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.

4.0.10.b. Switch 1C71A-S6B MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.

4.0.10.c. Switch 1C71A-S6C MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.

4.0.10.d. Switch 1C71A-S6D MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.

TEMP CHANGE
* 10
PAGE 12 OF 17

TEMP CHANGE
* 9
PAGE 2 OF 2

TEMP CHANGE
* 8
PAGE 15 OF 21

Attachment 2
Sheet 1 of 6

OM7A: SVI-C71-T0039
Page: 15
Rev.: 1

Main Steam Line Isolation
Valve Closure Channel Functional
Data Sheet

SECTION 5.1

Initials

TC
8

TC
9

7. Unit Supervisor informed that the MSIV's will be stroked. _____
Time / Date _____
U.S. Signature _____
8. MSL A INBD MSIV 1B21-F022A switch (P601-18C) placed to TEST. _____
9. MSL A OTBD MSIV 1B21-F028A switch (P601-19C) placed to TEST. _____
- 10.a. MSL A INBD MSIV 1B21-F022A green indicating light (P601-18C) is on. _____
- TC 8 | § 10.b. DPM-1 indicates relay 1C71A-K3A contact closed. _____
- TC 10 | § 10.c. DPM-2 indicates relay 1C71A-K3B contact closed. _____
- 10.d. DELETED
- 11.a. MSL A INBD MSIV 1B21-F022A green indicating light (P601-18C) is off. _____
- TC 8 | 11.b. DPM-1 indicates relay 1C71A-K3A contact open. _____
- 11.c. DPM-2 indicates relay 1C71A-K3B contact open. _____

§ Denotes Technical Specification requirement.

TEMP CHANGE
* 10
PAGE 13 OF 17

Attachment 2 (Cont.)
Sheet 2 of 6

TEMP CHANGE
* 8
PAGE 16 OF 21

OM7A: SVI-C71-T0039
Page: 16
Rev.: 1

SECTION 3.1

Initials

TC
10

11.d DELETED

12.a. MSL A OTBD MSIV 1B21-F028A green indicating light (P601-19C) is on. _____

TC
8

§ 12.b. DMM-1 indicates relay 1C71A-K3A contact closed. _____

§ 12.c. DMM-2 indicates relay 1C71A-K3B contact closed. _____

TC
10

12.D DELETED

13.a. MSL A OTBD MSIV 1B21-F028A green indicating light (P601-19C) is off. _____

TC
8

13.b. DMM-1 indicates relay 1C71A-K3A contact open. _____

13.c. DMM-2 indicates relay 1C71A-K3B contact open. _____

(TC
10

13.d DELETED

TC
8

14. MSL A INBD MSIV 1B21-F022A switch (P601-18C) placed to AUTO. (Mode 1 or 2) _____

15. MSL A OTBD MSIV 1B21-F028A switch placed (P601-19C) to AUTO. (Mode 1 or 2) _____

16. MSL A INBD MSIV 1B21-F022A switch (P601-18C) placed to CLOSE. (Mode 3, 4, or 5) _____

17. MSL A OTBD MSIV 1B21-F028A switch placed (P601-19C) to CLOSE. (Mode 3, 4, or 5) _____

20. MSL C INBD MSIV 1B21-F022C switch (P601-18C) placed to TEST. _____

21. MSL C OTBD MSIV 1B21-F028C switch (P601-19C) placed to TEST. _____

22.a. MSL C INBD MSIV 1B21-F022C green indicating light (P601-18C) is on. _____

TC
8

§ 22.b. DMM-1 indicates relay 1C71A-K3C contact closed. _____

§ 22.c. DMM-2 indicates relay 1C71A-K3H contact closed. _____

§ Denotes Technical Specification requirement.

SECTION 5 1

Initials

TC
10

22.d DELETED

23.a. MSL C INBD MSIV 1B21-F022C green indicating light (P601-18C) is off.

TC
8

23.b. DMM-1 indicates relay 1C71A-K3C contact open.

23.c. DMM-2 indicates relay 1C71A-K3H contact open.

TC
10

23.d DELETED

24.a. MSL C OTBD MSIV 1B21-F028C green indicating light (P601-19C) is on.

TC
8

\$ 24.b. DMM-1 indicates relay 1C71A-K3C contact closed.

\$ 24.c. DMM-2 indicates relay 1C71A-K3H contact closed.

TC
10

24.d DELETED

25.a. MSL C OTBD MSIV 1B21-F028C green indicating light (P601-19C) is off.

TC
8

25.b. DMM-1 indicates relay 1C71A-K3C contact open.

25.c. DMM-2 indicates relay 1C71A-K3H contact open.

TC
10

25.d DELETED

TC
8

26. MSL C INBD MSIV 1B21-F022C switch (P601-18C) placed to AUTO. (Mode 1 or 2)

27. MSL C OTBD MSIV 1B21-F028C switch placed (P601-19C) to AUTO. (Mode 1 or 2)

28. MSL C INBD MSIV 1B21-F022C switch (P601-18C) placed to CLOSE. (Mode 3, 4, or 5)

29. MSL C OTBD MSIV 1B21-F028C switch placed (P601-19C) to CLOSE. (Mode 3, 4, or 5)

TC
10

30. DELETED

31.

\$ Denotes Technical Specification requirement.

SECTION 5.1

Initials

- 34. MSL B INBD MSIV 1B21-F022B switch (P601-18C) placed to TEST. _____
- 35. MSL B OTBD MSIV 1B21-FC28B switch (P601-19C) placed to TEST. _____
- 36.a. MSL B INBD MSIV 1B21-F022B green indicating light (P601-18C) is on. _____
- TC 8 | \$ 36.b. DMM-1 indicates relay 1C71A-K3G Contact closed. _____
- TC 10 | \$ 36.c. DMM-2 indicates relay 1C71A-K3F Contact closed. _____
- 36.d. DELETED
- 37.a. MSL B INBD MSIV 1B21-F022B green indicating light (P601-18C) is off. _____
- TC 8 | 37.b. DMM-1 indicates relay 1C71A-K3G Contact open. _____
- TC 10 | 37.c. DMM-2 indicates relay 1C71A-K3F Contact open. _____
- 37.d. DELETED
- 38.a. MSL B OTBD MSIV 1B21-F028B green indicating light (P601-19C) is on. _____
- TC 8 | \$ 38.b. DMM-1 indicates relay 1C71A-K3G Contact closed. _____
- TC 10 | \$ 38.c. DMM-2 indicates relay 1C71A-K3F Contact closed. _____
- 38.d. DELETED
- 39.a. MSL B OTBD MSIV 1B21-F028B green indicating light (P601-19C) is off. _____
- TC 8 | 39.b. DMM-1 indicates relay 1C71A-K3G Contact open. _____
- TC 10 | 39.c. DMM-2 indicates relay 1C71A-K3F Contact open. _____
- 39.d. DELETED
- TC 8 | 40. MSL B INBD MSIV 1B21-F022B switch (P601-18C) placed to AUTO. (Mode 1 or 2) _____

\$ Denotes Technical Specification requirement.

TEMP CHANGE
10
PAGE 16 OF 17

Attachment 2 (Cont.)
Sheet 5 of 6

TEMP CHANGE
8
PAGE 19 OF 21

OM7A: SVI-C71-T0039
Page: 19
Rev.: 1

SECTION 5.1

Initials

TC
8

- 41. MSL B OTBD MSIV 1B21-F028B switch placed (P601-19C) to AUTO. (Mode 1 or 2) _____
- 42. MSL B INBD MSIV 1B21-F022B switch (P601-18C) placed to CLOSE. (Mode 3,4, or 5) _____
- 43. MSL B OTBD MSIV 1B21-F028B switch placed (P601-19C) to CLOSE. (Mode 3,4, or 5) _____
- 46. MSL D INBD MSIV 1B21-F022D switch (P601-18C) placed to TEST. _____
- 47. MSL D OTBD MSIV 1B21-F028D switch (P601-19C) placed to TEST. _____
- 48.a. MSL D INBD MSIV 1B21-F022D green indicating light (P601-18C) is on. _____

TC
8

TC
10

- \$ 48.b. DMM-1 indicates relay 1C71A-K3E contact closed. _____
- \$ 48.c. DMM-2 indicates relay 1C71A-K3D contact closed. _____
- 48.d. DELETED
- 49.a. MSL D INBD MSIV 1B21-F022D green indicating light (P601-18C) is off. _____

TC
8

TC
10

- 49.b. DMM-1 indicates relay 1C71A-K3E contact open. _____
- 49.c. DMM-2 indicates relay 1C71A-K3D contact open. _____
- 49.d. DELETED

TC
8

TC
10

- 50.a. MSL D OTBD MSIV 1B21-F028D green indicating light (P601-19C) is on. _____
- \$ 50.b. DMM-1 indicates relay 1C71A-K3E contact closed. _____
- \$ 50.c. DMM-2 indicates relay 1C71A-K3D contact closed. _____
- 50.d. DELETED
- 51.a. MSL D OTBD MSIV 1B21-F028D green indicating light (P601-19C) is off. _____

\$ Denotes Technical Specification requirement.

TEMP CHANGE
10
PAGE 17 OF 17

Attachment 2 (Cont.)
Sheet 6 of 6

TEMP CHANGE
8
PAGE 20 OF 21

OM7A: SVI-C71-T0039
Page: 20
Rev.: 1

SECTION 5.1

Initials

TC
8
TC
10

51.b. DM-1 indicates relay 1C71A-K3E CONTACT OPEN.

51.c. DM-2 indicates relay 1C71A-K3D CONTACT OPEN

51.d DELETED

TC
8

52. MSL D INBD MSIV 1B21-F022D switch (P601-18C)
placed to AUTO. (Mode 1 or 2)

53. MSL D OTBD MSIV 1B21-F028D switch
placed (P601-19C) to AUTO. (Mode 1 or 2)

54. MSL D INBD MSIV 1B21-F022D switch (P601-18C)
placed to CLOSE. (Mode 3, 4, or 5)

55. MSL D OTBD MSIV 1B21-F028D switch
placed (P601-19C) to CLOSE. (Mode 3, 4, or 5)

TC
(10)

56. DELETED

57.

TC
8

58. Unit Supervisor informed that stroking
the MSIV's completed.

_____/_____
Time Date

U.S. Signature

SECTION 4.0

TEST INSTRUMENTS:

MPL NUMBER CAL. DATE CAL DUE DATE IN%

DIGITAL MULTIMETER _____

DIGITAL MULTIMETER _____

COMMENTS: _____

Performed by: _____

Independent Verifier: _____

Initials Date

\$ Denotes Technical Specification requirement.

TEMP CHANGE
 # 8
 PAGE 27 OF 21

SYSTEM RESTORATION CHECKLIST

Title: Main Steam Line Isolation Valve Closure
Channel Functional

Verified By: _____


		Signature/Initials		Date	
LOCATION	COMPONENT MPL OR NAME	REQUIRED POSITION	INITIALS		REMARKS
			FIRST VERIF	SECOND VERIF	
007	Control Rm P601-18C	MSL A INBD MSIV 1B21-F022A switch	*		
	Control Rm P601-18C	MSL B INBD MSIV 1B21-F022B switch	*		
	Control Rm P601-18C	MSL C INBD MSIV 1B21-F022C switch	*		
	Control Rm P601-18C	MSL D INBD MSIV 1B21-F022D switch	*		
	Control Rm P601-19C	MSL A OTBD MSIV 1B21-F028A switch	*		
	Control Rm P601-19C	MSL B OTBD MSIV 1B21-F028B switch	*		
	Control Rm P601-19C	MSL C OTBD MSIV 1B21-F028C switch	*		
	Control Rm P601-19C	MSL B OTBD MSIV 1B21-F028B switch	*		
	Control Rm P691	DMM	removed		
	Control Rm P692	DMM	removed		
	Control Rm P693	DMM	removed		
	Control Rm P694	DMM	removed		

TC
8 | * As directed by Supervising Operator.

RELAY DRAWING

POTTER & BRUMFIELD

MDR RELAY



DATA PACKAGE COVER SHEET

FORM NO. 6687 REV 10/86

PP-1105-1

INSTRUCTION NO.

SVI-C71-T0039

TEST PERFORMANCE

AUTHORIZATION TO START PREREQUISITES:

OPERATIONS UNIT SUPERVISOR

11-2-87 1933

DATE AND TIME

AUTHORIZATION TO START TEST:

SUPERVISING OPERATOR

11/2/87 1942

DATE AND TIME

INSTRUCTION COMPLETION

FULL PARTIAL*

*See comments for extent of testing

TECH. SPEC. ACCEPTANCE CRITERIA

ACCEPTABLE UNACCEPTABLE NA

When both As Left and As Found data are taken, acceptance will be based on As Left data only.

OTHER DATA CRITERIA

ACCEPTABLE UNACCEPTABLE NA

When both As Left and As Found data are taken, acceptance will be based on As Left data only.

TASK COMPLETION

CREDIT** NO CREDIT

**Task fully completed or all failed/not completed items tracked per LCD Tracking, Work Orders, etc.

TON'S IN EFFECT: 010, 209 & 005

COMMENTS: NONE

LEAD PERFORMER'S SIGNATURE

Steve O'Neill

SOE

11-2-87 8150

DATE AND TIME

OPERATIONS UNIT SUPERVISOR

main J. Messina

11-2-87 2210

DATE AND TIME

SHIFT SUPERVISOR

JH

DATE AND TIME

(Required if Tech. Spec. Acceptance Criteria Is Not Met, Otherwise Mark N/A)

TEST RESULTS REVIEW

COMMENTS

SYSTEM ENGINEER/RESPONSIBLE SECTION REVIEWER

DATE

501

Main Steam Line Isolation
Valve Closure Channel Functional
Prerequisite Sign-off Sheet

Initials

TC
8

4.0.2. This instruction may be performed in Operational Condition 1,2,3,4 or 5.

[Handwritten initials]

4.0.3. No testing or maintenance is being performed which would initiate a half scram RPS signal.

[Handwritten initials]

4.0.4. The following annunciators are reset:

a. 1/2 SCRAM A/C (P680-5A-A9)

b. 1/2 SCRAM B/D (P680-5A-B9)

[Handwritten initials]

TC
10

4.0.5. DELETED

4.0.6. If unit is in MODE 3, 4, or 5:

a. C95 computer point, RPS CHANNEL ISOLATION A STATUS, B21EC013 indicates NORM.

b. C95 computer point, RPS CHANNEL ISOLATION B STATUS, B21EC014 indicates NORM.

c. C95 computer point, RPS CHANNEL ISOLATION C STATUS, B21EC015 indicates NORM.

d. C95 computer point, RPS CHANNEL ISOLATION D STATUS, B21EC016 indicates NORM.

[Handwritten initials]
11-2-87

TC
8

4.0.7. An RWP in effect: YES NO

[Handwritten initials]

4.0.8. Calibration Due Date is current on all test equipment.

[Handwritten initials]
11-2-87

TC
8

— SEE ATTACHED PAGE 14a —

Performed by:

[Handwritten signature]

[Handwritten initials]

11-3-87

Signature

Initials

Date

TC 1

8

TEMP CHANGE
PAGE 14 OF 21

OM7A: SYI-C71-T0039

Page : 14a

Rev. : 1

Attachment 1 (Cont.)
Sheet 1e of 1

- 4.0.10.a. Switch 1C71A-S6A MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.
- 4.0.10.b. Switch 1C71A-S6B MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.
- 4.0.10.c. Switch 1C71A-S6C MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.
- 4.0.10.d. Switch 1C71A-S6D MAIN STEAM LINE ISOL VALVE TEST is in the NORM position.

Initials

[Handwritten initials for each item]

TEMP CHANGE
10
PAGE 12 OF 17

TEMP CHANGE
9
PAGE 2 OF 2

TEMP CHANGE
8
PAGE 15 OF 21

Attachment 2
Sheet 1 of 6

OM7A: SVI-C71-T0039
Page: 15
Rev.: 1

Main Steam Line Isolation
Valve Closure Channel Functional
Data Sheet

SECTION 5.1

Initials

TC
700

TC
9

7. Unit Supervisor informed that the MSIV's will be stroked. 2050 / 11-2-87

Time Date

U.S. Signature

8. MSL A INBD MSIV 1B21-F022A switch (P601-18C) placed to TEST.

9. MSL A OTBD MSIV 1B21-F028A switch (P601-19C) placed to TEST.

10.a. MSL A INBD MSIV 1B21-F022A green indicating light (P601-18C) is on.

TC 8 | \$ 10.b. EDCM-1 indicates relay 1C71A-K1A contact closed.

\$ 10.c. EDCM-2 indicates relay 1C71A-K1B contact closed.

10.d. DELETED

11.a. MSL A INBD MSIV 1B21-F022A green indicating light (P601-18C) is off.

TC 8 | 11.b. EDCM-1 indicates relay 1C71A-K1A contact open.

11.c. EDCM-2 indicates relay 1C71A-K1B contact open.

\$ Denotes Technical Specification requirement.

TC
10

[Handwritten signatures and initials for each step]

SECTION 5.1

Initials

TC
10

11. d DELETED.

12. a. MSL A OTBD MSIV 1B21-F028A green indicating light (P601-19C) is on.

TC
B

§ 12. b. DMM-1 indicates relay 1C71A-K3A contact closed.

TC
10

§ 12. c. DMM-2 indicates relay 1C71A-K3B contact closed.

12. d DELETED

13. a. MSL A OTBD MSIV 1B21-F028A green indicating light (P601-19C) is off.

TC
B

13. b. DMM-1 indicates relay 1C71A-K3A contact open.

13. c. DMM-2 indicates relay 1C71A-K3B contact open.

TC
10

13. d DELETED

TC
B

14. MSL A INBD MSIV 1B21-F022A switch (P601-18C) placed to AUTO. (Mode 1 or 2)

15. MSL A OTBD MSIV 1B21-F028A switch placed (P601-19C) to AUTO. (Mode 1 or 2)

16. MSL A INBD MSIV 1B21-F022A switch (P601-18C) placed to CLOSE. (Mode 3, 4, or 5)

17. MSL A OTBD MSIV 1B21-F028A switch placed (P601-19C) to CLOSE. (Mode 3, 4, or 5)

20. MSL C INBD MSIV 1B21-F022C switch (P601-18C) placed to TEST.

21. MSL C OTBD MSIV 1B21-F028C switch (P601-19C) placed to TEST.

22. a. MSL C INBD MSIV 1B21-F022C green indicating light (P601-18C) is on.

TC
B

§ 22. b. DMM-1 indicates relay 1C71A-K3C contact closed.

§ 22. c. DMM-2 indicates relay 1C71A-K3E contact closed.

§ Denotes Technical Specification requirement.

SECTION 5.1

Initials

TC
10

22.2 DELETED

TC
8

23.a. MSL C INBD MSIV 1B21-F022C green indicating light (P601-18C) is off.

23.b. DMY-1 indicates relay 1C71A-K3C contact open.

23.c. DMY-2 indicates relay 1C71A-K3H contact open.

TC
10

23.2 DELETED

24.a. MSL C OTBD MSIV 1B21-F028C green indicating light (P601-19C) is on.

TC
8

\$ 24.b. DMY-1 indicates relay 1C71A-K3C contact closed.

\$ 24.c. DMY-2 indicates relay 1C71A-K3H contact closed.

(TC
10

24.2 DELETED

25.a. MSL C OTBD MSIV 1B21-F028C green indicating light (P601-19C) is off.

TC
8

25.b. DMY-1 indicates relay 1C71A-K3C contact open.

25.c. DMY-2 indicates relay 1C71A-K3H contact open.

TC
10

25.2 DELETED

TC
8

26. MSL C INBD MSIV 1B21-F022C switch (P601-18C) placed to AUTO. (Mode 1 or 2)

27. MSL C OTBD MSIV 1B21-F028C switch placed (P601-19C) to AUTO. (Mode 1 or 2)

28. MSL C INBD MSIV 1B21-F022C switch (P601-18C) placed to CLOSE. (Mode 3, 4, or 5)

29. MSL C OTBD MSIV 1B21-F028C switch placed (P601-19C) to CLOSE. (Mode 3, 4, or 5)

TC
10

30. DELETED

31.

\$ Denotes Technical Specification requirement.

SECTION 5.1

Initials

- 34. MSL B INBD MSIV 1B21-F022B switch (P601-18C) placed to TEST. [Handwritten Initials]
- 35. MSL B OTBD MSIV 1B21-F028B switch (P601-19C) placed to TEST. [Handwritten Initials]
- 36.a. MSL B INBD MSIV 1B21-F022B green indicating light (P601-18C) is on. [Handwritten Initials]
- TC 8 | \$ 36.b. DMX-1 indicates relay 1C71A-K3G Contact closed. [Handwritten Initials]
- TC 10 | \$ 36.c. DMX-2 indicates relay 1C71A-K3F Contact closed. [Handwritten Initials]
- 36.d. DELETED
- 37.a. MSL B INBD MSIV 1B21-F022B green indicating light (P601-18C) is off. [Handwritten Initials]
- TC 8 | 37.b. DMX-1 indicates relay 1C71A-K3G Contact open. [Handwritten Initials]
- TC 10 | 37.c. DMX-2 indicates relay 1C71A-K3F Contact open. [Handwritten Initials]
- 37.d. DELETED
- 38.a. MSL B OTBD MSIV 1B21-F028B green indicating light (P601-19C) is on. [Handwritten Initials]
- TC 8 | \$ 38.b. DMX-1 indicates relay 1C71A-K3G Contact closed. [Handwritten Initials]
- TC 10 | \$ 38.c. DMX-2 indicates relay 1C71A-K3F Contact closed. [Handwritten Initials]
- 38.d. DELETED
- 39.a. MSL B OTBD MSIV 1B21-F028B green indicating light (P601-19C) is off. [Handwritten Initials]
- TC 8 | 39.b. DMX-1 indicates relay 1C71A-K3G Contact open. [Handwritten Initials]
- TC 10 | 39.c. DMX-2 indicates relay 1C71A-K3F Contact open. [Handwritten Initials]
- 39.d. DELETED
- TC 8 | 40. MSL B INBD MSIV 1B21-F022B switch (P601-18C) placed to AUTO. (Mode 1 or 2) [Handwritten Initials]

\$ Denotes Technical Specification requirement.

SECTION 5.1

Initials

TC
8

- 41. MSL B OTBD MSIV 1B21-F028B switch placed (P601-19C) to AUTO. (Mode 1 or 2)
- 42. MSL B INBD MSIV 1B21-F022B switch (P601-18C) placed to CLOSE. (Mode 3, 4, or 5)
- 43. MSL B OTBD MSIV 1B21-F028B switch placed (P601-19C) to CLOSE. (Mode 3, 4, or 5)
- 46. MSL D INBD MSIV 1B21-F022D switch (P601-18C) placed to TEST.
- 47. MSL D OTBD MSIV 1B21-F028D switch (P601-19C) placed to TEST.
- 48.a. MSL D INBD MSIV 1B21-F022D green indicating light (P601-18C) is on.

[Handwritten initials and signatures]

TC
8

TC
10

- \$ 48.b. DMM-1 indicates relay 1C71A-X3E contact closed.
- \$ 48.c. DMM-2 indicates relay 1C71A-X3D contact closed.

48.d DELETED

- 49.a. MSL D INBD MSIV 1B21-F022D green indicating light (P601-18C) is off.

TC
8

TC
10

- 49.b. DMM-1 indicates relay 1C71A-X3E contact open.
- 49.c. DMM-2 indicates relay 1C71A-X3D contact open.

49.d DELETED

- 50.a. MSL D OTBD MSIV 1B21-F028D green indicating light (P601-19C) is on.

TC
8

TC
10

- \$ 50.b. DMM-1 indicates relay 1C71A-X3E contact closed.
- \$ 50.c. DMM-2 indicates relay 1C71A-X3D contact closed.

50.d DELETED

- 51.a. MSL D OTBD MSIV 1B21-F028D green indicating light (P601-19C) is off.

\$ Denotes Technical Specification requirement.

TEMP CHANGE
10
PAGE 17 OF 17

Attachment 2 (Cont.)
Sheet 6 of 6

TEMP CHANGE
8
PAGE 20 OF 21

OM7A: SVI-C71-T0039
Page: 20
Rev.: 1

SECTION 3.1

Initials

TC
8
TC
10

51.b. DMM-1 indicates relay 1C71A-K3E CONTACT OPEN

[Handwritten initials]

51.c. DMM-2 indicates relay 1C71A-K3D CONTACT OPEN

51.d. Deleted

TC
8

52. MSL D INBD MSIV 1B21-F022D switch (P601-18C placed to AUTO. (Mode 1 or 2)

[Handwritten initials]

53. MSL D OTBD MSIV 1B21-F028D switch placed (P601-19C) to AUTO. (Mode 1 or 2)

[Handwritten initials]

54. MSL D INBD MSIV 1B21-F022D switch (P601-18C) placed to CLOSE. (Mode 3, 4, or 5)

N/A

55. MSL D OTBD MSIV 1B21-F028D switch placed (P601-19C) to CLOSE. (Mode 3, 4, or 5)

N/A

TC
10

56. Deleted

57.

TC
8

60. Unit Supervisor informed that stroking the MSIV's completed.

2142 / 11-2-87
Time Date

[Handwritten initials]

[Handwritten signature]
U.S. Signature

SECTION 4.0
TEST INSTRUMENTS:

	MPL NUMBER	CAL. DATE	CAL DUE DATE	INT
DIGITAL MULTIMETER	L70-N052F	N/A	N/A	<i>[Handwritten initials]</i>
DIGITAL MULTIMETER	L70-R248A	N/A	N/A	<i>[Handwritten initials]</i>

COMMENTS: None

Performed by:

[Handwritten signature] *[Handwritten initials]* 1-2-87

Independent Verifier:

None
Signature Initials Date

S Denotes Technical Specification requirement.

SYSTEM RESTORATION CHECKLIST

Title: Main Steam Line Isolation Valve Closure
Channel Functional

Verified By:

[Handwritten Signature]
Signature/Initials

11-2-87

11-7-87

Date

LOCATION	COMPONENT MPL OR NAME	REQUIRED POSITION	INITIALS		REMARKS
			FIRST VERIF	SECOND VERIF	
Control Rm P601-18C	MSL A INBD MSIV 1B21-F022A switch	*	ABC	SQA	SW IN AUTO
Control Rm P601-18C	MSL B INBD MSIV 1B21-F022B switch	*	ABC	SQA	
Control Rm P601-18C	MSL C INBD MSIV 1B21-F022C switch	*	ABC	SQA	
Control Rm P601-18C	MSL D INBD MSIV 1B21-F022D switch	*	ABC	SQA	
Control Rm P601-19C	MSL A OTBD MSIV 1B21-F028A switch	*	ABC	SQA	
Control Rm P601-19C	MSL B OTBD MSIV 1B21-F028B switch	*	ABC	SQA	
Control Rm P601-19C	MSL C OTBD MSIV 1B21-F028C switch	*	ABC	SQA	
Control Rm P601-19C	MSL B OTBD MSIV 1B21-F028B switch	*	ABC	SQA	↓
Control Rm P691	DMY	removed	ABC	SQA	NONE
Control Rm P692	DMY	removed	ABC	SQA	
Control Rm P693	DMY	removed	ABC	SQA	
Control Rm P694	DMY	removed	ABC	SQA	↓

TO
8

* As directed by Supervising Operator.

① Sequence of Events

- copy of UNIT logs for 10/29/87
and 11/3/87

- Handwritten sequence - (FURTHERING)

MSIV-Chronology of Events

October 29, 1987

- 1835 - Stroked INED MSIV 1B21-F0022D for STI-B21-025A Section 8.3, per EPIS valve did not close for 16 seconds. Level 1 Test Exception Report written (STA Log)
- 1842 - Re-opened 1B21-F0022D (Plant Log)
- 1900 - Declared 1B21-F0022D Inop, closing time was 22.8 seconds from STI data (Plant Log) (LCO written, 87-2031)
- 2103 - Re-stroked 1B21-F0022D - time to close 3.2 seconds (Plant Log)
- 2106 - Stroked 1B21-F0022D again - time to close 2.9 seconds (Plant Log)
- 2144 - Stroked 1B21-F0026D - time to close 77 seconds (Plant Log)
- 2150 - 2200 stroked all MSIVs (Unit Log)
- 2221 - Decision had been made by Plant Management to stroke all MSIV's to check for common mode failure. Found 1B21-F0028B had an initial slow stroke time of 11.9 seconds, second stroke was 3.9 seconds (Plant Log)
- 2230 - 1B21-F0022D was re-stroked, valve closed in less than 3 seconds. Valve was stroked again and stroke time was less than 3 seconds (STA Log) 1B21-F0026D and F0028B also experienced long closing times (77 seconds and 12 seconds). When restroked valves had times of approx. 3 seconds each. In all cases the solenoid lights on 1B13-Pt22 and 1B23 de-energized (STA-Log) Isolated "D" Main Steam Line (STA Log)
- 2236-2250 - Isolated "D" MSL (Unit Log)
- 2250 - Isolated "D" MSL (Plant Log)
- 2310 - All MSIVs were verified to stroke within 3-5 seconds. Could not repeat the initial condition causing MSIV to slow close. Stroking the MSIV has freed up the Solenoid/Pneumatic valves, which control MSIV stroking, of any foreign matter or moisture. In 5 to 7 days MSIV Isolation Scram test is scheduled, if this is delayed we'll fast stroke the MSIV's again to see if event is repeatable. Declared 1B21-F0022D, F0026D and F0028B operable. (Plant Log)
- 2340 - Restored "D" MSL (Plant Log)

October 30, 1987

- 0010 - Made 4hr. report on slow closing MSIV's (Plant Log)
- 0300 - Test Exception Report (TER) 451-1 for MSIV closure was approved. All MSIV's restored. (STA Log)

October 30, 1987

- 0330 - TER 451-1 (MSIV Fast Closure) was resolved and closed. No restrictions to going back to 10-7 (Plant Log)
- 0355 - Increasing power (Plant Log)

November 2, 1987

- 1942 - Commenced SVI C71-T0039, MSL Isol Valve Closure Channel functional (Unit Log) (10% stroke - partial closure - RPS)
- 2142 - Completed SVI C71-T0039 - Sat

November 3, 1987

- 11-5 - Decreased power to 80% to stroke MSIVs (Plant Log)
- 1154-1222 - stroked MSIVs (Unit Log)
- 1157 - 1B21-F022D took 18 seconds to close (Plant Log)
- 1158 - Unit Supervisor declared F022D Inop (Unit Log)
- 1159 - 1B21-F022D restroked in 3.0 seconds (Plant Log)
- 1200 - Unit Supervisor declared F022D operable (Unit Log)
- 1212 - 1B21-F022D did not close in the 2 minute 49 seconds that the control switch was in "close". Took switch back to "Auto", then to "close", valve shut in 3.4 seconds (Plant Log)
- 1212 - Unit Supervisor declared F022D Inop (Unit Log)
- 1230 - Declared MSL "D" Inop based on repeated failure of 1B21-F022D and F028D to stroke in required time. (see 10-29-87 20-24 shift entry) (Plant Log) (ALCO written, 87-2128)
- 1330 - Informed System Operation Center of intended plant shutdown (Unit Log)
- 1337 - Commenced PWR decrease (Unit Log)
Commenced a normal Rx shutdown (Plant Log)
- 1353 - Closed 1B21-F022D 3.4 seconds (Unit Log)
- 1354 - Closed 1B21-F028D 3.3 seconds (Unit Log)
- 1355 - Shut 1B21-F022D and F028D, out of T.S. 3.4.7 and 3.6.4. Made 4hr. report (Plant Log)

Attachments: Unit Log
Plant Log
STA Log (2)
CR 87-503
CR 87-513

10/22/87

- 1331 - NOTIFIED SEC (WASH) OF APPROX 100MW E LOAD DECREASE. S-2433C INCREASE DUE TO STI CBS-022
- 1343 - DECREASED LOAD SET TO OPEN 2.5 SUPPLY VALVES INITIAL 10MW 203 MW. POWER 2453 MWTA.
- 1347 - COMMENCED SUI - CSI - T0028F - 917
- 1350 - DISABLING AUTO SWIFT OF CBS PRESSURE CONTROL
- 1408 - COMPLETED SUI 1331. T0027D - 917
- 1400 - RELAYED CBS SYSTEM TO DUAL CHANNEL OPERATION. S-2433 CBS TO 2 CHANNEL. DISABLING AUTO SWIFT OF CBS SYSTEM
- 1413 - UNIT ENVI. RW APPROXIMATED DISCH OF CURT A TO LIKE 330
- 1416 - RESTORED CBS SYSTEM TO DUAL CHANNEL OPERATION. NOTIFIED SEC (WASH) OF POWER (UNIT INCREASE TO 700-800 MW)
- 1425 - RESUME TURBINE LOAD SET TO 125 MW. TURBINE LOAD ALL 0. VALVES CLOSED - PRELIMINARY POWER 42500 MWTA - NO CONTROL - 200
- ~~1430 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1435 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1440 - COMPLETED SUI 1331. T0027D - 917~~
- ~~1445 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1450 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1455 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1460 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1465 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1470 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1475 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1480 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1485 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1490 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1495 - COMMENCED SUI 1331. T0027D - 917~~
- 1500 - COMMENCED SUI 1331. T0027D - 917
- 1505 - SECURED UNIT IN MANUAL MODE. COMMENCED SUI 1331. T0027D - 917
- ~~1510 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1515 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1520 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1525 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1530 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1535 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1540 - COMMENCED SUI 1331. T0027D - 917~~
- ~~1545 - COMMENCED SUI 1331. T0027D - 917~~
- 1550 - SHIFTS 333 TO FLUX MANUAL
- 1602 - COMPLETED RTI N32 POOL - UNIT FOR ESOP DATA
- 1604 - CORE FLOW > 45%
- 1705 - COMMENCED SUI G50 - T9266 - LOW RELEASE PERMIT FOR FTS-8
- 1716 - SHIFTED 333 TO FLUX AUTO
- 1721 - RW SHEDDING 34K FROM FAST A 10 CST
- 1725 - SHIFTED 333 TO FLUX MANUAL
- 1731 - COMMENCED SUI M16 - T2001 - SW VAC BKR / ISOL OLV OF MSR
- 1748 - SHIFTED 333 TO FLUX AUTO
- 1813 - SECURED AGENCY 4.6 GIGAWATT
- 1828 - COMMENCED SUI 321 T0272 425/803 62/68 RW LEAK FUNDAMENTAL (S21 - U)
- 1837 - SHIFTS 321 T022D - 7.55 CLOSURE 09.2 S-1 321 025A SEC - 0.3
- 1012 - OPERATOR 321 T022D - VALUE DID NOT RESPOND TO CLOSE WITHIN 5 TO 30 MIN - EVALUATING DATA



10/29/91

- 1972 Completed SWI - B21 - T018712 - SWI
- 1900 - LANE PEN21 - B21 - F0220 DECLARED INOP, UNIT NOT TO 75% IN 51
- 1940 - SHIFED B33 TO FLUX INFLUX
- 1955 - CORE FROM REDUCED TO 53% , DECODE 2009 IN TO 100% , 2009 UNIT
- 1957 Reopened the Shift
- 2055 Shift C/PD Camp A Sourced CRD pump B
- 2103 CLOSED B21-F0220 FOR STEADY TEST FOR SWI-B21 3.245 Sourced 170-N302P
- 2104 OPENED B21-F0220
- 2106 CLOSED B21-F0220 FOR STEADY TEST FOR SWI-B21 3.445 Sourced 170-N302P
- 2107 OPENED B21-F0220
- 2107 Commenced SWI-N17-T2002
- 2144 Closed B21-F0280 In 175 Sourced L70-N302C
- 2145 Closed B21-F0280
- 2152 Closed B21-F0280 Sourced L70-N302C
- 2153 Closed B21-F0280
- 2211 Closed B21-F022B 3.075 Sourced L70-N302P
- 2211 Opened B21-F022B
- 2213 Closed B21-F022A 3.375 Sourced L70-N302P
- 2213 Opened B21-F022A
- 2215 Closed B21-F022C 3.455 Sourced L70-N302P
- 2215 Opened B21-F022C
- 2216 Closed B21-F028B 3.955 Sourced L70-N302P
- 2216 Opened B21-F028B
- 2218 Closed B21-F028B 3.965 Sourced L70-N302P
- 2218 Opened B21-F028B
- 2219 Closed B21-F028A 3.485 Sourced L70-N302P
- 2219 Opened B21-F028A
- 2220 Closed B21-F028C 4.125 Sourced L70-N302P
- 2221 Opened B21-F028C
- 2236 Closed B21-F028D and B21-F067D
- 2240 Deenergized 1E32-F001N in closed position and
1B21-F067D closed & deenergized
- 2257 Deenergized B21-F028D Silencers in all the levels
- 2310 Relanded back to B21-F028D Deenergized B21-F0220
B21-F0280 and B21-F028B available
- 2352 Run on fault 22:59 In 48
- 2353 Completed SWI-N14-T2001 & SWI-N17-T2002

PERRY NUCLEAR
POWER PLANT

COPY

UNIL LOG
Unit I - Vol 22

No 78

11-2-87

- 1909 Commenced SUI-810-T5217
- 1914 Completed SUI 810-T5217 partial - SAT.
- 1942 Commenced SUI-671-T0039, main Isol SUI 7 Closure
Chem Fuel
- 2015 Completed No. 1 WTS A to end.
- 2029 Bypassed APRM C 7. allowing bypassing LPM
24-25-48.
- 2050 Unbypassed APRM C.
- 2050 - Fanned by MW
- 2121 Completed adding H₂ to the generator.
- 2122 CWCW Chiller A tripped Investigating
- 2127 Unable to determine why CV Chiller A tripped
- due to 850 A CV being sent on 1013-810.
- 2150 Attempted to start CV Chiller A. Chiller immediately
~~tripped~~
- ~~2151 Completed SUI-671-T0039 - SAT~~
- ~~2154 Completed SUI-671-T0039 - SAT~~
- ~~2159 Shutdown SSE of steam generator~~
- ~~2201 Bypassed APRM C. no bypassed stability Green 24-25-48~~
- ~~2214 Started SSE of steam generator~~
- ~~2240 SSE requested Main Flow of 2339.5~~
- 2241 SSE requested Main Flow of 2339.5
- 2242 Unbypassed APRM C.
- 2320 SSE requested Main Flow of 2339.5
L. Bond
- 2357 ASSUMED THE SHIFT.
- 2400 NO FURTHER ENTRIES THIS DATE

L. Bond

11/3/87

07-5 assumed the shift

PNPP UNIT I	
SS	Henry Kelly
US	Joe Harvey
US	David Gardner
SO	Scott Davis
SO	John Mikolaj
SO	John Stewart
EXTRA LICENSED OPERATORS	
C-P	Pat Curran

~~0707~~ ~~Completed~~ ~~...~~

~~0719~~ ~~Completed~~ ~~...~~

~~0729~~ ~~Completed~~ ~~...~~

~~0734~~ ~~Completed~~ ~~...~~

~~0748~~ ~~Completed~~ ~~...~~

~~0750~~ ~~Completed~~ ~~...~~

~~0805~~ ~~Completed~~ ~~...~~

~~0818~~ ~~Completed~~ ~~...~~

~~0825~~ ~~Completed~~ ~~...~~

~~0841~~ ~~Completed~~ ~~...~~

1st Vent. ~~...~~

2nd Vent. ~~...~~

1046 Completed CIV testing for STE N31-0024

1105 Entered 30C parts levels & intended 15%
1 swe degree

1107 Completed CIV testing, commenced for degree

1127 Placed G30 A+B in hold

1150 Completed shake down of MISIVS w/ L2A w/ 2
L73-AP33V Cal due 11-29-87

1151 Closed R:1-FO22B 3 = AC

1156 Closed R:1-FO22B

1157 Closed B:1-FO22D 1 = AC

→	1158	US Declared MSL D Unavailable (B21-F022 D)	
→		Opened = B21-F022D	
→	1154	Closed #2 B21-F022D	3.0 RC
→	1200	Opened B21-F022D	
→		US Declared MSL D operator	
→	1201	Closed B21-F022A	3.1 RC
→	1202	Opened B21-F022A	
→	1203	Closed B21-F022C	3.6 RC
→	1204	Opened B21-F022C	
→	1206	Closed B21-F022B	4.0 RC
→	1207	Opened B21-F022B	
→	1208	Closed B21-F022 D., B21-F022 D drain	
		Close 2 min 49 RC later placed B21-F022 D	
		Auto - at 12:11	
	1213	Closed B21-F022D	3.7 RC
	1214	Opened B21-F022D	
	1215	Closed B21-F022D	3.8 RC
	1216	Opened B21-F022D	
→	1219	Closed B21-F022A	3.6 RC
→	1220	Opened B21-F022A	
→	1221	Closed B21-F022C	
→	1222	Opened B21-F022C	
→	1226	Started CS1-T0026	
→	1227	Commenced CS1-T0026	Flow Valve
→	1233	RW commenced xfer of FOST A to the CST	
→	1235	Started RHR pump A in S.P. Cooling	
→	1236	Opened E12-F024A at 1000 gpm	
→	1245	Commenced xfer of S.P. water to RW	
→	1255	Completed pumping the Suppression Pool. xfered 5500 gallons to Radwaste	
→	1327	SVI CS1-T0026 Completed Sat	
→	1330	Interviewed SAC operator Herold of Intended plant 2/D	
→	1335	S/D RHR A Closed E12-F024A	200 gpm
→	1337	Commenced FWR Venturi, 5th ECCS	
→	1341	Commenced SVI CS1-T0026	
→	1353	Closed B21-F022 D	3.7 RC

1354	Closed B21-F02 & D	3.3 AM.
1357	Placed G50 'B' F/W in service	
1418	Removed N23 "CF" and N29 "AB" from service	
1431	Commenced SVE C11-T1022	RPC RUN
1436	SVE C11-T1022 Completed	2.45
1447	S/D CBY 'C'	
1453	S/D RFBP 'D'	
1503	Rate in bar 115F US discharge M22 C. in op. due to flow closure found on B21-F02 & D	
1510	RW completed pumping FDSTH to H21 C	
1519	Commenced SVE C51-T0030 C	APRM C low 45. release of LPRM 4B-24.25
1531	Placed the MFP to the off & KWDOR "dry" & on MFP to low control	
1515		
1516		
1517		
1518		
1519		
1520		
1521		
1522		
1523		
1524		
1525		
1526		
1527		
1528		
1529		
1530		
1531		
1532		
1533		
1534		
1535		
1536		
1537		
1538		
1539		
1540		
1541		
1542		
1543		
1544		
1545		
1546		
1547		
1548		
1549		
1550		
1551		
1552		
1553		
1554		
1555		
1556		
1557		
1558		
1559		
1560		
1561		
1562		
1563		
1564		
1565		
1566		
1567		
1568		
1569		
1570		
1571		
1572		
1573		
1574		
1575		
1576		
1577		
1578		
1579		
1580		
1581		
1582		
1583		
1584		
1585		
1586		
1587		
1588		
1589		
1590		
1591		
1592		
1593		
1594		
1595		
1596		
1597		
1598		
1599		
1600		

00-08

THUR

10-29-87

0125

STARTED 'B' - RFP

0142

STARTED 'C' - CBF

0216

RSE - 50% FLOW DRAIN PUMPING FORWARD, Chem. is

0449

Rx Pur 78.9%, Rod Wdr 114.6%, GMWT 8204

Core Flow 55.5%, ENTERED MGD BOUNDARY AT TC-7.

PREP. TO COMMENCE ST1-C91-09 P.1 - Thermal and Def. monitor
P.2 - Thermal limit Def. monitor.

0452

CO1 - CRASHED - Holding Bin LOWEST LEVEL \approx 79%

0520

CO1 - Ended L Service

0530

EX-02 auto stop RRV Cond. .220 cond. t.

0553

Commenced to Decrease Core Flow to min. FC setting
in FAULT STOP Pumps

0607

Commenced Blw H₂ Purge

0625

Core Flow 45%, ENTERED TJ 34.11, min

Perioden ST-032 - ST33 auto stop & has end within 30min
recirculation & full measure at least 5% of total flow.

Rudolph

05-20

0835 Started RTR in suppression pool 150% max

1027 Authorized release of MWT

1033 Placed A Purge Reg. in control for ST-085-02/S1

1110 Restored RNR A to standby readiness

1136 Placed B Purge Reg. in control for ST-085-022/S1

1230 Inop. RNR B in prep. for going into SPCH

returning thru 1812-F024B.

1305 Started SPCH pump in recirculation mode
to improve Supr. Pool Chemistry.

1340 Opened 22 bypass valves as prep. for ST-085-22/S1

Verified requirements of T.S. 3.1.41.

1431 All bypass closed, ST-085-22/S1 complete,
min. Pool water temp. was 395°F (originally 360°F).

→ 1537 Closed 1821-F022D for ST 1821-T025A/R.3
Valve took an extremely long time to close.

→ 1542 Reopened 1821-F022D.

→ 1900 Declared 1821-F022D INOP - closure time
from ST data was 22.8secs.
CR and TER initiated. Rx done = 75%

Rudolph
11/2/87

05-20

Thurs

10/29/57

→ 1900 cont. Core Flow = 53% - limiting plant load
→ close valves until TENDIS is

20-24

1940 B33 → Flux max.

1955 Reduce core flow to 53%, Draw 201 to 400% Red Limit,
66% Pur.

2055 Started A cell pump, started B cell pump.

~~2100 Started F0220 control valve at 10:24~~

→ 2103 Started F0220 Fast close - 3.21 sec and responded.

→ 2106 Started F0220 Fast close 2.97 sec and responded.

→ 2108 Started F0220 Fast close 77 Sec and responded.

→ 2132 Started F0220 Fast close 3.19 sec and responded.

→ 2221 Decision made by plant management to stroke all MSIV.
→ check in Control room fail.

Found in addition to F0220, F0280 having initial
slow stroke time that [B21 F028 B] (11.19 sec) initial
took massive time but later stroked at 3.9 sec.

→ 2245 Isolated D MSIV. F02 22. Action.

→ 2300 All MSIV now isolated. To stroke within 3-5 sec a
could not expect the initial condition causing MSIV to stroke close.
Stroke in MSIV has involved the sol/pneumatic valves which control
MSIV movement by surge under pressure. In 5 to 7 days MSIV
DO. serum test is scheduled, if this is delayed will fast stroke
the MSIV again to see if condition is repeatable.

DECLARED F0220, F0280 and F028B OPERABLE.

PAV
10/29/57

→ 2340 Restored D MSIV to service

R. Matiff

~~Signature~~

08-16
11:45
11:57
11:59
12:12
12:30
12:37
13:55

00-28 11/3/87
0032- Plant RHR 'A' in Supp Pool Coolin
0510- Second Supp Pool Coolin, Plant RHR 'A' in 5th W
M. G. Wesley
08-16
→ 1145 Decreased in rod to 90% to stroke MSIVs
→ 1157 B21-F022D to stroke to stroke -
→ 1159 Restacked F:221 time 3.0 sec
→ 1212 B21-F028D did not close in the 3 min 49 sec time
the valve control switch was in CLOSE took
switch back to. With then back to close valve
shut in 34 sec
→ 1230 Declared BMSL penetration INOP based on
recent failure of F022D and F028D to stroke
in required time (SEE ENTRY 10-29-87 20-24 shift)
→ 1237 Commenced a normal Rx shutdown
→ 1355 Shut B21-F022D AND F028D, out of TS 34.7 and 3.64
made 4 hour report on B21-F022D and 28D being INOP
1500 Authorized discharge of EAST 'B'

M. G. Wesley

16-24

1540 REMOVED REPT 'B' FROM THE MASTER LEVEL CONTROLLER
AND IDLE IT AT 1100 RPM.
1600 COMMENCED POWER REDUCTION FROM 45% POWER.
1630 REACTOR POWER AT 35%. DOWNSHIFTED RECIRC
PUMPS TO SLOW. RECEIVED BOTH WITHDRAW AND
INSERT ROD BLOCKS WITH POWER LESS THAN THE
LOW POWER SET POINT. VERIFIED PULL SHEET ROD
SEQUENCE CORRECT.
1640 DISCUSSION WITH REACTOR ENGINEERING (STILES & DONOVAN)
ROD PATTERN CONTROL BLOCKS DUE TO RODS BEING
OUT OF SEQUENCE FOR THE RPCS THOUGH CORRECT
BY THE PULL SHEET # 11-3-A7 SHEET. ROD PULL
SHEET SPECIFIED THAT BEYOND A CERTAIN STEP RODS
WOULD BE OUT OF THE RPCS PATTERN CONSTRAINTS.
RODS HAD NOT YET BEEN INSERTED BEYOND THIS
STEP WHEN POWER WENT LESS THAN THE LPSP.
CONDITION EXPECT TO BE PRODUCED BY REACTOR CONT



UNIT 1
SHIFT TECHNICAL ADVISOR LOG

ERRY NUCLEAR POWER PLANT

PAGE 1112

DATE	TIME	KEYWORD	REMARKS
10-20-97	1835	Continued	74% with 45% loop flow. Left Loss Ants Monitor in alarm.
	1835	MSIV's	Fast stroked valve FOZ20 for startup. Per ERIS the valve did not start to move for 15 seconds and then took 2 seconds to close. Level 1 Tel written limits 75% power 53% flow.
OFF GOING		<u>M. H. ...</u>	DATE <u>10-20-97</u> TIME <u>2007</u>
OC	1	PRESS <u>240</u> SIG BPV PJS <u>POWER</u>	<u>66</u> % CORE FLOW <u>55</u> VLS --
GEN	<u>771</u>	WINE FCID	S/R HPCS S/R DIV 3 DG S/R
LFC A	S/R	LFC1 S/R	SLOA S/R ADSA S/R DIV 1 DG S/R
LFC B	<u>1200</u>	LFC2 S/R	SLOB S/R ADSB S/R DIV 2 DG S/R
REMARKS	<u>RHR</u>	<u>W</u>	S/PCU ON COMING <u>S. H. ...</u>
10-20-97	2230	MSIV's	1B21-FOZ20 was restroked in less than 3 seconds twice. 1B21-FOZ20 and 1B21-FOZ3B experienced long stroke times of 1 min 17 sec and 11.9 seconds when tested. These were stroked again with stroke times of approx. 3 sec. The 1B21-FOZ20 and FOZ3B solenoid lights de-energized in all cases, indicating the slow stroke - this occurred most probably from slow



ERRY NUCLEAR POWER PLANT

DATE	TIME	KEYWORD	REMARKS
10-22-87	2230	MSIV's	movement of one of the air solenoid control valves. MSC 0 was isolated per T.S. notations and a 4 hr report was generated.
10-22-87	0015 0130	4 hr notif E31	4 hour notification completed. During E31 SVT, Relay KUD failed. RCIC was declared INOP & is exceeding 2 hr time limit.
	0300	MSIV's	TER 451.1 for MSIV closure to slow has been approved. All MSIV's are restored.
	0400	Plant	Raising power to 85%.
<p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p> <p>10-22-87 10:30 AM 957 81</p>			
10-30-87	0820	Chemistry	Reactor Water Conductivity is greater than .3 ordered out.
10-30-87	1315	G36	Both G36 filters are now back in service.
10-30-87	1545	Plant	Completed TC 7 testing, reduced rod line from 15% to 100% and increasing power to 100% until entry into TC-8 is approved.



UNIT 1
SHIFT TECHNICAL ADVISOR LOG

PERRY NUCLEAR POWER PLANT

PAGE 1120

DATE	TIME	KEYWORD	REMARKS
11-2-87	OFF DOWNG	R. Steinhilber	DATE 11-2-87 TIME 2342
	1106	987	92 % OPERATION 73
		SIR	SIR SIR SIR
		SIR	SIR SIR SIR SIR
		SIR	SIR SIR SIR SIR
		Reviewed Unit Log	
11-3-87		Steinhilber	DATE 11-3-87 TIME 0800
	1066	1000	90 % OPERATION 70
		SIR	SIR SIR SIR SIR
		SIR	SIR SIR SIR SIR
		SIR	SIR SIR SIR SIR
		Reviewed Unit Log	
11-3-87	1250	MSIV's	Fast stroke test MSIV's. The K020 took 18 seconds and the K0280 took 48 seconds after 2 minutes and 48 seconds on. The second stroke the K020 took 3.0 seconds and the K0280 took 3.4 seconds. Recommend to the Shift Supervisor & GSO.
			A. The valves not to called
			B. The STE Action Full Isolation not to performed. Do not want to be challenged with MSIV's with a known problem.





UNIT 1
SHIFT TECHNICAL ADVISOR LOG

PERRY NUCLEAR POWER PLANT

DATE	TIME	KEYWORD	REMARKS
11-3-87	1520	MSIV's	Both F0221 and F0281 have been isolated, inoperable and isolated and de-energized. Current plans are to shut down and investigate.
<p>Handwritten: <u>Handwritten</u> DATE <u>11-3-87</u> TIME <u>1540</u></p> <p>Handwritten: <u>950</u> <u>45</u> <u>53</u></p> <p>Handwritten: <u>488</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u></p> <p>Handwritten: <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u></p> <p>Handwritten: <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u> <u>SIR</u></p> <p>Handwritten: ON COMING <u>R Street</u></p>			
11-3-87	1543	Stokes	Normal plant shutdown in progress. RFP A is on the MLC, RFP B is idling and the WFD control switch is in OFF. Reactor control is Flux Manual.
	1626	B33	Transferred Reactor pumps to slow
	1741	Stokes	Preparing to manually screw the reactor. After Reactor pumps were transferred and FCV's opened power was below LPSP. Unknown to the operators when the LPAP was reached was that the control rod sequence step had the rods not sequenced by the RPC. So now that the plant is below LPSP RCIS has insert inhibits (This crew did not realize that the rod sequence sheets deviate from RPC sequence

Form No. 6640
Rev. 5/87

CONDITION REPORT

(Use back of form for additional space.)

UNIT NO.	CR-87-503	DATE
----------	-----------	------

EVENT DATE/TIME 10-29-87 / 10:20 AM	DISCOVERY DATE/TIME 10-29-87 / 10:20 AM	METHOD OF DISCOVERY INS-PCOI INDICATIONS
--	--	---

EVENT DESCRIPTION (10/29/87) (10/29/87)

DURING PERFORMANCE OF STI-B21-025A WHILE FAST CLOSING 1B21-F022D, OPERATORS OBSERVED AN APPROX. 18 SEC TIME DELAY BEFORE THE VALVE BEGAN TO STROKE ONCE THE CONTROL SWITCH WAS PLACED IN THE "CLOSE" POSITION. THE VALVE THEN STROKED CLOSE IN LESS THAN 3 SEC. AT 2103 THE VALVE WAS STROKED SUCCESSFULLY 2 TIMES USING SC1-B21. (EVENT DESCRIPTION CONTINUED ON ATTACHED SHEET)

IMMEDIATE CORRECTIVE ACTION (INCLUDE SVI'S)

REDUCED POWER TO 275% AND FLOW# 53%
TER 451-1 (LEVEL 1 FAILURE)

SYSTEM COMPONENTS AFFECTED (INCLUDE #.) 1B21-F022D, 1B21-F023D, 1B21-F023B	REDUNDANT EQUIPMENT IN SAME SYSTEM AVAILABLE 1B21-F022 A, B, C 1B21-F023 A, C
---	---

ACTIVITIES AND CONDITIONS PRIOR TO EVENT PERFORMING STI-B21-025A, 9.3 IN TO 7	OPERATIONAL CONDITION: REACTOR POWER (MW) 275% REACTOR PRESSURE 9.7 MPa RX WATER TEMP (IF NONSATURATED)
--	--

INITIATION CRITERIA 1.4	ORIGINATOR D.G. Phillips	DATE 10-29-87	SECTION PDC-21-025A
----------------------------	-----------------------------	------------------	------------------------

TECH SPEC INVOLVED 3.6.4 3.4.7	LER INITIATED (ATTACH COPY) <input checked="" type="checkbox"/> ACTUAL <input type="checkbox"/> POTENTIAL	WORK INITIATED? (INCLUDE NO.) <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO 9)-903
-----------------------------------	--	---

US REVIEW <i>[Signature]</i>	DATE 10/30/87	STA REVIEW <i>[Signature]</i>	DATE 10-31-87
---------------------------------	------------------	----------------------------------	------------------

NOTIFICATION (INCLUDE REPORTING REQUIREMENT) (ATTACH ENF)	REPORTS	TECH SPEC VIOLATION? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
<input type="checkbox"/> IMMEDIATE <input type="checkbox"/> ONE HOUR <input checked="" type="checkbox"/> FOUR HOUR 5012 0.6 W. 10 <input type="checkbox"/> 24 HOUR	<input checked="" type="checkbox"/> POTENTIAL LER (PP-062) <input type="checkbox"/> POTENTIAL RSF (PP-164) RSF: _____ <input type="checkbox"/> MANAGEMENT PRELIMINARY REPORT (CS-OPERATIONS NOTIFIED)	REMARKS SEE PLANT AND UNIT LOG FOR STRIKE TIMES

REVIEWED, REQUIRED ACTIONS TAKEN SS <i>[Signature]</i>	DATE 10-30-87
---	------------------

COMPLIANCE REVIEW#	DATE	LER NO.	ASSIGNED SECTION
--------------------	------	---------	------------------

REVIEW	DATE	PORC	REVIEWER/APPROVED	DATE
		<input type="checkbox"/> YES <input type="checkbox"/> NO		

PORC REVIEW MEETING NO.	APPROVED	DATE	APPROVED	DATE
-------------------------	----------	------	----------	------

OR CLOSED	DATE	REMARKS	CAUSE CODE P
-----------	------	---------	-----------------

EVEN-DESCRIPTION (continued)

PER THE SC= AND US(SS) DIRECTION (WITH SS OPERATORS CONCURRENT) THE REMAINING MSIV'S WERE FAST CLOSED. ALL MSIV'S STROKED SATISFACTORILY EXCEPT 1B21-FO25B AND 1B21-FO29C. AT 2154 1B21-FO29C FAST STROKED CLOSE UNSATISFACTORILY IN 1 MINUTE, IT SECONDS. AT 2152 THE VALVE WAS RE-STROKED WITH A CLOSURE TIME OF APPROX. 3 SEC. AT 2216 1B21-FO25B FAST STROKED CLOSE UNSATISFACTORILY IN 11.9 SECONDS. AT 2218 THE VALVE WAS RE-STROKED WITH A CLOSURE TIME OF APPROX. 3 SEC.

DURING ALL MSIV CLOSURES THE SOLENOID LIGHTS ON 1413-P622 AND 1413-P623 WERE OBSERVED TO EXTINGUISH IMMEDIATELY, INDICATING THAT POWER WAS DEENERGIZED TO THE SOLENOIDS AT THE AFFECTED VALVE.

EVENT NOTIFICATION
Perry Nuclear Power Plant
UNIT 1

Page 1

Caller's Name: Rosen, Stephen Title: SS

Event Time: 2100 Zone: EST EDT Event Date: 10-29-87

EVENT CLASSIFICATION	Y	N	EVENT CATEGORY	INITIATION SIGNAL	CAUSE OF FAILURE
GENERAL EMERGENCY			REACTOR TRIP/SCRAM	POZZ D, P023D and P023D	<input checked="" type="checkbox"/> MECHANICAL
SITE AREA EMERGENCY			ESF ACTUATION	FAST STRUCK	<input type="checkbox"/> ELECTRICAL
ALERT			ECCS ACTUATION	CLASS TO LOW	<input type="checkbox"/> PERSONNEL ERROR
UNUSUAL EVENT			SAFETY INJECTION FLOW	> 5 in	<input type="checkbox"/> PROCEDURE INADEQUATE
SECURITY NON-EMERGENCY			LOI ACTION STATEMENT		OTHER:
SECURITY/SAFEGUARDS	<input checked="" type="checkbox"/>		OTHER:		
TRANSPORTATION EVENT					
OTHER:					

SYSTEM: B21
COMPONENT: POZZ D F023D B-9C

EVENT DESCRIPTION
(Use OR if completed) (SEE CR)

POWER PRIOR TO EVENT(S): 64% DID ALL SYSTEMS FUNCTION AS REQUIRED? YES NO IF "NO", EXPLAIN ABOVE
CURRENT POWER OR MODE: 111 64% ANYTHING "UNUSUAL" OR NOT UNDERSTOOD? YES NO IF "YES", EXPLAIN ABOVE

OUTSIDE AGENCY OR PERSONNEL NOTIFIED	CORRECTIVE ACTION(S)
STATE(S): <u>NO</u>	① Restored All VWS - SAT - , FROD UP SEC/Pneumatic vws which control MSIV stricking.
LOCAL: <u>NO</u>	② Looking AT Possibility of incremental slow FROD, if stricking MSIV's.
RESIDENT YES NO <u>WILL BE</u>	MODE OF OPERATION UNTIL CORRECTION: <u>(1)</u> ESTIMATE TIME TO RESTART: <u>NA</u>
OTHER: <u>NO</u>	
PRESS RELEASE <u>NO</u>	

OTHER INFORMATION REQUESTED BY NRC:
① what was cause of slow stroke? ② Poss. by slow/pneumatic vws down UP B.T in subsequent strokes FROD up. Control system under condition on subsequent strokes

TIME/DATE OF CALL: <u>NOV 10 10:30:87</u>	CR NO.: <u>CR-87-503 per Sof</u>
NAME OF INDIVIDUAL CONTACTED: <u>MARKSBERG</u>	CALLER'S SIGNATURE: <u>R. M. Stoller</u> <u>OU</u>

K028D
F028B

C287-503
pg 102

TIME

22:11:05 C B21-F22B CLOSURE
TIME 3:57 sec

22:11:45 C

22:13:20 C B21 F028A 3:37

22:13:30 C

22:15:45 C B21 F028C 3:45

22:15:55 C

22:16:45 C B21 F028B 11.9

22:17 C F028D

22:18:10 C F028D 3.96

22:18:40 C F028D

22:19:07 C B21 F028A 3:48

22:19:35 C

22:20:37 C B21 F028C 4.12

22:21:40 C

ACTIVE LOO TRACKING SHEET 872031

Rev. 1.87

T.S. SECTION 3.6.4 : 3.4.7	#L(S) 321	OPERATIONAL CONDITION 1
ENTRY TIME/DATE 1800 10/20/97	TECH SPEC 3.0.3 <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	
IMPACT TIME/DATE 2300 10/20/97	TECH SPEC 3.0.4 <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	
	CCP WORK RELATED <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	

PROBLEM DESCRIPTION

1321 - 8022 > while closing during the performance of ST-611-0257A/B.5 valve closure was slow. (22 sec. & 50% calc. error)
 (Also it appears that valve was to fact valve for started moving at 2:58:11 by 52.5)

ACTION REQUIREMENT

3.4.7 maintain one or more MSIV in open position of least one MSIV operable in each affected main steam line that is open and within 8 hrs, either:

- a) Restore the any valve to operable status, or
- b) Isolating the affected main steam line by use of a disconnected MSIV in the clean position

3.6.4 maintain at least one isolation valve operable in each affected penetration that is open and within 4 hrs either:

- i. Ensure each affected penetration is used at least one plant operator with valve secured in the open position.

REFERENCE FORMS

CR87-503 pg 304

ADDITIONAL INFORMATION	STRUCTURE SAT
B 21 F0028D FAILED 2144 10/29/97	2152 10/29/97
B 21 F0028B FAILED 2216 10/29/97	2218 10/29/97

<p>ENTRY REVIEW</p> <p><i>[Signature]</i></p> <p><i>[Signature]</i></p> <p style="text-align: center;">630</p>	<p>CLEARANCE</p> <p>2310 10/20/97 M. / US</p> <p><i>[Signature]</i></p> <p style="text-align: center;">630</p>
---	---

CONDITION REPORT

(USE ONLY IF NOT FOR REGULATORY REPORT)

UNIT NO.

CR-87-513

PAGE 1 OF 1

EVENT DATE/TIME: 1230 / ~~11-3-87~~ DISCOVERY DATE/TIME: 1230 / ~~11-3-87~~ METHOD OF DISCOVERY: Observation

EVENT DESCRIPTION:
Fault tripped MSIV F0220 closed the valve took 18 seconds to close.
Fault tripped MSIV F0280 closed the valve did not move after ~~11-3-87~~ 2 minutes and 49 seconds.

IMMEDIATE CORRECTIVE ACTION (INCLUDE SVI'S):
Retried valve
F0220 closed in 3.0 seconds.
F0280 closed in 3.4 seconds.

SYSTEM COMPONENTS AFFECTED (INCLUDE NP.):
MSIV's F0220, F0280
REDUNDANT EQUIPMENT IN SAME SYSTEM AVAILABLE:

ACTIVITIES AND CONDITIONS PRIOR TO EVENT:
TL-8 Testing
Power 80%
Temperature 90%
Full Reactor Transition Test
OPERATIONAL CONDITION: ① 2 3 4 5
REACTOR POWER (MWTM): 80
REACTOR PRESSURE: 96
RX WATER TEMP (IF NONSATURATED): NH

INITIATION CRITERIA: 3
ORIGINATOR: H. Yaman
DATE: 11-3-87
SECTION: Test

TECH SPEC INVOLVED: 3.6.4/3.4.7
LOS INITIATED (ATTACH COPY): ACTUAL POTENTIAL
WORK INITIATED? (INCLUDE NO.): YES NO

LE REVIEWER: [Signature] DATE: 11/3/87
STA REVIEWER: [Signature] DATE: 11-3-87

NOTIFICATION (INCLUDE REPORTING REQUIREMENT) (ATTACH ENF):
 IMMEDIATE
 ONE HOUR
 FOUR HOUR: INCREASED TO 72 HOURS
 24 HOUR
REPORTS/
 POTENTIAL LER (PMP-662)
 POTENTIAL RSF (PMP-664)
RSF: _____
 MANAGEMENT PRELIMINARY REPORT (CS-OPERATIONS NOTIFIED)

REVIEWED, REQUIRED ACTIONS TAKEN BY: [Signature]
DATE: 11-3-87

COMPLIANCE REVIEW: DATE: / LER NO.: ASSIGNED SECTION:

REVIEW: DATE: PORC: YES NO REVIEWER/ APPROVED: DATE:

PORC REVIEW MEETING NO.: APPROVED: DATE: APPROVED: DATE:

CR CLOSED: DATE: REMARKS: CAUSE CODE: P

EVENT NOTIFICATION

Perry Nuclear Power Plant
Unit 1

Page 1

Caller's Name: HENRY KELLY Title: SLC2 Supv

Event Time: 1157 Zone: EST EDT Event Date: 11-3-87

EVENT CLASSIFICATION	Y	N	EVENT CATEGORY	INITIATION SIGNAL	CAUSE OF FAILURE:
GENERAL EMERGENCY			REACTOR TRIP/SCRAM		MECHANICAL
SITE AREA EMERGENCY			ESF ACTUATION		ELECTRICAL
ALERT			ECS ACTUATION		PERSONNEL ERROR
UNUSUAL EVENT			SAFETY INJECTION FLOW		PROCEDURE INADEQUATE
<input checked="" type="checkbox"/> SO. TO NON-EMERGENCY			LOG ACTION STATEMENT		OTHER:
SECURITY/SAFEGUARD			OTHER:		<input checked="" type="checkbox"/> unknown
TRANSPORTATION EVENT					
OTHER:					
			SYSTEM: <u>B21 (MSIV.) F025D</u>		
			COMPONENT: <u>B21-F022D AND F023D</u>		

EVENT DESCRIPTION
(USE OR IF COMPLICATED) (PLAIN OR)

POWER PRIOR TO EVENT(S): <u>80%</u>	DID ALL SYSTEMS FUNCTION AS REQUIRED? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO IF "NO", EXPLAIN ABOVE
CURRENT POWER OR MODE: <u>83%</u>	ANYTHING "UNUSUAL" OR NOT UNDERSTOOD? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO IF "YES", EXPLAIN ABOVE

OUTSIDE AGENCY OR PERSONNEL NOTIFIED	CORRECTIVE ACTION(S)
STATE(S): <u>NA</u>	<u>commencing Rx shutdown</u>
LOCAL: <u>NA</u>	<u>It shut both - MSIVs (F020 & F025) at 75%</u>
RESIDENT: <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> WILL BE	<u>while's shut BT 1255</u>
OTHER: <u>NONE</u>	
PR/SS RELEASE	MODE OF OPERATION UNTIL CORRECTION: <u>4</u> ESTIMATE TIME TO RESTART: <u>unknown</u>

OTHER INFORMATION REQUESTED BY NRC:
 *Strike Time of 9:15:05
 history - was operation in control of problem Fri? - No, indications were 76
 Region on Fri valves were not considered INOP - 1970 Review of log
 showed that at the call was made - I informed the NRC CP Center

TIME/DATE OF CALL: <u>1355 11-3-87</u>	CR NO.: <u>CR-87-513</u>
NAME OF INDIVIDUAL CONTACTED: <u>RON YOUNG</u>	CALLER'S SIGNATURE: <u>Henry Kelly</u>

OK 87-210

862120

FORM NO. 7157
REV. 1/87

ACTIVE LCO TRACKING SHEET

OF 12

T.S. SECTION 26.4 - 2.4.7	WPL(S) B21	OPERATIONAL CONDITION 1
------------------------------	---------------	----------------------------

ENTRY TIME/DATE 1157 11/3/87	TECH SPEC 3.0.3 <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
IMPACT TIME/DATE 1557 11/3/87	TECH SPEC 3.0.4 <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
	OOP WORK RELATED <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO

PROBLEM DESCRIPTION

B21-R0280 FAILED TO STROKE ONCE,
BUT STROKED SUCCESSFULLY THE SECOND &
THIRD TIME

B21-R0220 STROKED @ 18 SECONDS 155 &
THEN STROKED SH

ACTION REQUIREMENT

ISOLATE PENETRATION OK
HOT SID IN 12 HRS &
COLD SID IN 24 HRS

REFERENCE FORMS

WO 87-9285
87-9293
T/O 1-87-4207

ADDITIONAL INFORMATION

B21-R0220 & R0280 DISABLED 1530 11/3/87
Transferred to R00 @ OOSC 11-4-87 910N

ENTRY REVIEW

[Signature]
US

[Signature]
SS

[Signature]
SSO

CLEARANCE

OOSC TIME 11-4-87 OESC US
DATE

[Signature]
SS

[Signature]
SSO

Partial Sequence of Events

October 29, 1987

- 1837 Shut IB21-F022D per STI-B21-035A 22.14 sec
- 2100 IB21-F022D declared inoperable
- 2103 IB21-F022D closed 3.24 seconds
- 2104 IB21-F022D closed 2.94 seconds
- 2144 IB21-F028D closed 1 minute 17 seconds
- 2152 IB21-F028D closed 3.19 seconds
- 2210 IB21-F028B closed 11.9 seconds
- 2218 IB21-F028B closed 3.96 seconds
- 2310 IB21-F022D, F028D, F028B declared Operable

October 30, 1987

- 010 Notified NRC of slow closure of MSIVs

November 3, 1987

- 1150 Commenced stroke timing MSIVs
- 1157 Closed IB21-F022D 18 seconds
- 1158 Declared IB21-F022D Inoperable
- 1159 Closed IB21-F022A 3.0 seconds
- 1200 IB21-F022D declared Operable
- 1208 Attempted to close IB21-F028D, control switch held in shut position for 3 minutes 49 seconds
- 1212 IB21-F028D declared Inoperable
- 1213 IB21-F028D closed 3.4 seconds
- 1217 IB21-F028D closed 3.4 seconds
- 1300 Commenced plant shutdown
- 1318 Shut IB21-F022D
- 1324 Shut IB21-F028D

November 3, 1987

1558 Notified NRC of slow closure of MSIVs

1630 Shifted Reactor Recirculation Pumps to slow speed
Received withdraw and insert Rod Blocks from
Rod Pattern Control System

1819 Manually Scrammed the reactor - Reaction
from 2% percent of water.

2120 Notified NRC of reactor scram

10/29/87

- 1334 - NOTIFIED SOC (HEALTH) OF APPROX 100 MW E LOAD DECREASE & SUBSTANTIAL INCREASE DUE TO STI CBS-022
- 1343 - DECREASED LOAD SET TO OPEN 2.5 BYPASS VALVES INITIAL LOAD 803 MW, POWER 2453 MWTH.
- 1347 - COMPLETED SUI - CSI - T0028F - SAT
- 1350 - DISTURBANCE AUTO SHIFT OF CBS PRESSURE CONTROL
- 1408 - COMPLETED SUI 1931 - T0087D - SAT
- 1409 - RESTORED CBS SYSTEM TO DUAL CHANNEL OPERABILITY, SHIFTED CBS TO T5 CHANNEL, DISTURBANCE AUTO ^{SHIFT} OF CBS SYSTEM
- 1313 - LOAD RAMP. RW PERFORMED DISC OF CURT A TO LOAD 33%.
- 1426 - RESTORED CBS SYSTEM TO DUAL CHANNEL OPERABILITY. NOTIFIED SOC (HEALTH) OF POWER (LOAD) INCREASE TO 790-800 MW.
- 1435 - RESTORED TURBINE LOAD SET TO 125 MW = TURBINE LOAD, ALL 6 VALVES CLOSED - PWR. RPV POWER 2506 MWTH - NO CONTROL ROOM MONITORING WITH ^{SHIFTS} BYPASS VALVES OPEN. ~~VERIFIED~~
- 1437 - COMMENCED PUMPING SPENT PWR WASTE VIA ~~SEC~~ ~~SEC~~
- 1477 - COMPLETED SUI B21 T0187R HPCS/HCS HIGH RW PRESSURE FUNC. (1521-16572)
- 1444 - COMPLETED ~~TRANSFERRING~~ ~~WASTE~~ ~~FROM~~ ~~SP~~ ~~OR~~ ~~RW~~ - ~~EB~~ ~~20~~ ~~gal~~ ~~transferred~~
- 1459 - Doug Sheliga (E. AT) ENTERED MAIN (TIME NO/UT) FOR INSPECTION
- 1500 - COMPLETED SUI 1522 T1222 HPCS LOW FLOW FUNC (1522-1656)
- 1500 - SECURED MINIMUM LIMIT TO MODE OPS - COMMENCED 34% H. FLOW
- 1509 - Doug Sheliga ~~ENTERED~~ ~~MAIN~~ ~~FOR~~ ~~INSPECTION~~
- 1527 - COMPLETED SUI B21 T0189R - SAT
- 1545 - COMPLETED SUI - K22 - T202 - SAT
- 1557 - SHIFTS 33% TO FLUX MANUAL
- 1602 - COMPLETED RTI N32 POOL - UNSAT FOR ESOP DATA
- 1604 - CO2 FLOW > 45%
- 1705 - COMPLETED SUI G50-T5266 - LOW RELEASE PERMIT FOR FAST B
- 1716 - SHIFTS 33% TO FLUX AUTO
- 1721 - RW STANDING 34% FROM FAST A TO CST
- 1725 - SHIFTS 33% TO FLUX MANUAL
- 1737 - COMPLETED SUI M16-T2001 - DW HPC BVR / ISOL OLV OF HEST
- 1748 - SHIFTS 33% TO FLUX AUTO
- 1813 - SECURED AILING H. to GENERATOR
- 1828 - COMPLETED SUI B21 T0187R HPCS/HCS L2/L3 RPV LEAK FUNCTIONAL (1521-16572)
- 1837 - SHUT. B21 T022D - FIRST CLUSTER PER STI B21 025A SECT 8.3
- 1840 - OPENED B21 F022D - VALUE DOES NOT APPEAR TO CLOSE WITHIN 5 SEC CRITERIA - EVALUATING DATA

MIN
10-29-87
3:19 PM

**PERRY NUCLEAR
POWER PLANT**

COPY

UNIT LOG
Unit 1 - Vol. 7

No

58

10/29/67

1932 Completed SUI - B21 - T018712 - SAT
 1900 - LANE ENTRY - B21 - F0220 DECLARED INOP, LIMITED TO 75% FLOW, 55%
 1940 - SHIFED B21 TO FLOW MANUAL
 1955 - CORE FLOW REDUCED TO 53% , DROVE 2009 IN TO 100% B21 UNIT
 1957 Assumed the Shift
 2055 Started CRD pump A Sounded CRD pump B
 2103 CLOSED B21-F0220 FOR STROKE TEST PER S01-B21 3.245 Stroke: 170 L
 2105 OPENED B21-F0220
 2106 CLOSED B21-F0220 FOR STROKE TEST PER S01-B21 2.945 Stroke: 170 L
 2107 OPENED B21-F0220
 2127 Commenced SUI-M117-T2002
 2144 Closed B21-F0280 In 175 Stroke: 170 N302C
 2145 Closed B21-F0280
 2152 Closed B21-F0280 Stroke: 170 N302C
 2153 Closed B21-F0280
 2211 Closed B21-F022B 3.075 Stroke: 170 N302P
 2211 Opened B21-F022B
 2213 Closed B21-F022A 3.375 Stroke: 170 N302P
 2213 Opened B21-F022A
 2215 Closed B21-F022C 3.455 Stroke: 170 N302P
 2215 Opened B21-F022C
 2216 Closed B21-F028B 3.935 Stroke: 170 N302P
 2218 Opened B21-F028B
 2218 Closed B21-F028B 3.965 Stroke: 170 N302P
 2218 Opened B21-F028B
 2219 Closed B21-F028A 3.485 Stroke: 170 N302P
 2219 Opened B21-F028A
 2220 Closed B21-F028C 4.125 Stroke: 170 N302P
 2221 Opened B21-F028C
 2236 Closed B21-F028D and B21-F067D
 2240 Designated 1E32-F001N in closed position and
 1B21-F067D closed & designat
 2250 Designated B21-F028D Sounded in lifting device
 2310 Relanded back to B21-F028D, Declared B21-F0220
 B21-F0280 and B21-F028B operable
 2322 A-cum fault 22.59 Pa. 48
 2323 Completed SUI-M116-T2001 & SUI-M117-T2002

2340 Opened 1B21-F0280

2343 Accumulator Fault Rod 22-59 Clear
pressure was good. Just black led small amount
of moisture.

2400 Continued the Shift No Further entries
this date

~~W. L. [unclear]~~

~~[The remainder of the page is crossed out with a diagonal line.]~~

1/3/87

0745 Assumed the Shift

PNPP UNIT I	
SS	Henry Kelly
US	Joe Harkley
US	Doug Gaedard
SO	Scott David
SO	John Mikolaj
SO	DeA Stewer
EXTRA LICENSED OPERATORS	
STA	Pat Curran

0807 Commenced STI Test #54 - P0027 120V rec'd & response.
Battery test

0829 Commenced SVE B2 - T0369A SRV. Status
Actuation change of function

0841 Informed SOC operators jercks of intended
50% We. increase

0929 SVE B2 - T0369A Completed Sat

0944 Inb. SOC operators. Order of intended turn
down of B2 - T0369A

1018 Commenced BPV testing for STI N31-0024

1025 Performs 24 hr Post SVO engine roll on DIV II

1041 Completed BPV testing, 70% rod motion. Verified by
1st Vent. Spheros
2nd Vent. Spheros

1046 Commenced CIV testing for STI N31-0024

1105 Informed SOC photo jercks of intended 15%
power decrease

1107 Completed CIV testing, Commenced power decrease

1127 Placed G36 A+B in hold

1150 Commenced shake timing of MISIVS w/ liquid water
L73 - R833V Cal due 11-24-87

1151 Closed 821-F022B 3.2 AC

1156 opened 421-FJ22B

1157 Closed 821-F022D 1.0 AC

1158	US Disclosed MSL D Inoperable (B21-F022D)
	Opened B21-F022D
1159	Closed B21-F022D 3.0 REC
1200	Opened B21-F022D
	US Disclosed MSL D Inoperable
1201	Closed B21-F022A 3.1 REC
1202	Opened B21-F022A
1203	Closed B21-F022C 3.6 REC
1204	Opened B21-F022C
1206	Closed B21-F022B 4.0 REC
1207	Opened B21-F022B
1208	Closed B21-F022D, B21-F022E 3.0 REC
	Close 2 min 49 sec later placed B21-F022D in Auto at 1211
1212	US Disclosed MSL D Inoperable (B21-F022D)
1213	Closed B21-F022D 3.4 REC
1214	Opened B21-F022D
1217	Closed B21-F022D 3.4 REC
1218	Opened B21-F022D
1219	Closed B21-F022A 3.6 REC
1220	Opened B21-F022A
1221	Closed B21-F022C
1222	Opened B21-F022C
1226	Started ECC pump A
1227	Commenced CSI-70026 Pump/Flow Valve
1233	RW commenced xfer of FOSTA to the CST
1235	Started RHR pump A in S.P. Cooling
1238	Opened E12-F024A at 1000 gpm
1245	Commenced xfer of S.P. water to RW
1255	Completed pumping the Suppression Pool. xfered 5500 gallons to Radwaste
1327	SVI CSI-70026 Completed Sat
1330	Informed SOC operators Verbal of Intended Plant SPD
1335	S.P. RHR A Closed E12-F024A 200 gpm
1337	Commenced FWR Venturi, SM ECCA
1341	Commenced SVI CSI-70026 Discharge/Flow
1353	Closed B21-F022D 3.4 REC
1354	Closed B21-F022D

Reportable Event Number 10815

Facility : BFRAL
Unit : 1
Request :
Vendor : S1/01
Operating Condition : For Maintenance
Mod Request : 1 FOUR STARTED
Mod Release :
Cause : Unknown
Component :

Date Notified : 10/30/78
Time Notified : 0110
Date of Event : 10/30/78
Time of Event : 2114
Classification : 10 OF 1071
Category 1 : 100 Action Code
Category 2 :
Category 3 :
Category 4 :

EVENT DESCRIPTION :

WITH THE REACTOR AT 42A, FULL CLOSURE TESTS ON MAIN FLOW THREE VALVE AND
CLOSURE TIMES EXCEEDED THE 2 SECOND LIMIT. THE FIRST MAIN FLOW-2 VALVE
CLOSED IN 22 SECONDS. AFTER FURTHER TESTS THE CLOSURE TIMES WERE
WITHIN 20 SECONDS. AS THE RESULT OF THE TEST, THE OPERANT MSV, FLOW-1
VALVE, WAS A CLOSURE TIME OF 20 SECONDS. THE VALVE WAS CLOSED SEVERAL
TIMES WITHIN 20 SECONDS. ALL OTHER MSV'S WERE TESTED AND
ONE OTHER VALVE, FLOW-2-B, CLOSED IN 22 SECONDS AND FURTHER TESTS
WAS 20 SECONDS WITHIN 20 SECONDS. AFTER ONE TEST THE
SLOW CLOSURE TIME COULD NOT BE REPEATED. SUSPICION WAS IN THE
CYCLING TIME. A CYCLING TEST WAS MADE WHERE THE CYCLING TIME WAS
OBTAINED BY MEANS OF SURVEILLANCE FACILITY FOR FLOW CLOSURE TESTS
(SLOW CLOSURE TESTS - ADDITIONAL)

② Class Times

- STI Package for Tests on 10/29/97

D-65

Valve	Time	Date	Closure Time
1B21-FC224	2213	10/29	3.37 seconds
	1201	11/3	3.1 seconds
1B21-FC223	2211	10/29	3.07 seconds
	1154	11/3	3.2 seconds
1B21-FC22C	2215	10/29	3.45 seconds
	1207	11/3	3.6 seconds
1B21-FC22L	1877	10/29	22.14 seconds per STI-B21-L25A
	2103	10/29	3.24 seconds
	2106	10/29	2.94 seconds
	1157	11/3	18 seconds
	1159	11/3	3.0 seconds
	1353	11/3	3.4 seconds
1B21-FC25A	2219	10/29	3.48 seconds
	1219	11/3	3.6 seconds
1B21-FC25B	2216	10/29	11.9 seconds
	2218	10/29	3.96 seconds
	1206	11/3	4.0 seconds
1B21-FC25C	2220	10/29	4.12 seconds
	1221	11/3	Not recorded

Valve	Time / Date	Closure Time
1B21-F0252	2144 10/29	1 minute 17 seconds
	2152 11/29	3.19 seconds
	2236 10/29	Not recorded
	1208 11/3	Did not close
	1213 11/3	3.4 seconds
	1254 11/3	Not recorded

Startup Test Results Package Cover Sheet
Perry Unit 1 Startup Test Program

Rev.: 4
Form: PAF-1104-7

Doc No./Rev. B21-025A/3	Doc Title MSIV FUNCTION TEST	Doc Section No./Title 18.3/Full Cl. of Fast MSIV 8703 451 IC 3045	Date 10/30/87
Reason for Test: <input checked="" type="checkbox"/> Scheduled Test <input type="checkbox"/> Retest per TER _____ <input type="checkbox"/> Other _____			
Initial Conditions Test Plateau: <input type="checkbox"/> OV <input type="checkbox"/> HD <input type="checkbox"/> Low Pwr <input type="checkbox"/> Mid Pwr <input checked="" type="checkbox"/> Hi Pwr Test Condition: <input type="checkbox"/> OV <input type="checkbox"/> HD <input type="checkbox"/> 1 <input type="checkbox"/> 2 <input type="checkbox"/> 3 <input type="checkbox"/> 4 <input type="checkbox"/> 5 <input type="checkbox"/> 6 <input checked="" type="checkbox"/> 7 <input type="checkbox"/> 8 Core Pwr <u>75</u> % Plant MWe <u>885</u> Other: _____ Core Flow <u>53</u> % Rx Press <u>962</u> psig _____			
TER'S (list) Attach all open and closed TER's <u>451-01, 02, 03, 04, 05, 06, 07, 08, 09, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100</u>		STOV'S (list) Attach all applicable STOV'S <u>3-1, 2, 2</u>	
Acceptance Criteria Results Level 1: <input type="checkbox"/> Sat. <input checked="" type="checkbox"/> Exceptions <input type="checkbox"/> N/A <input checked="" type="checkbox"/> GE Level 2: <input checked="" type="checkbox"/> Sat. <input checked="" type="checkbox"/> Exceptions <input type="checkbox"/> N/A <input type="checkbox"/> GE Level 3: <input type="checkbox"/> Sat. <input type="checkbox"/> Exceptions <input checked="" type="checkbox"/> N/A <input type="checkbox"/> Other		Resp. Vendor <input checked="" type="checkbox"/> Results Package Index Comp. <input checked="" type="checkbox"/> Proc./Inst Sat or None Used M & TE USE: <input type="checkbox"/> Yes, M&TE Report submitted <input checked="" type="checkbox"/> None Used	
Other Analysis Sat <input checked="" type="checkbox"/> Exceptions <input checked="" type="checkbox"/> N/A <input type="checkbox"/>			
Summary of Test and Test Results (incl. results of any upset plant proc./inst. eval.) <p>This test closed the fastest MSIV as determined from previous testing at approximately 75% power. The valve, 1B21 F022D was slow to start closing (time from solenoid deenergization to valve movement indicated by limit switch) however closing time (time from 90% to 10% limit switch actuation extrapolated to 100%) was within specification. TER 451-01 was generated to address this. This TER was resolved before testing was secured. All other analysis was satisfactory.</p>			
TEST Status: <input type="checkbox"/> Complete <input checked="" type="checkbox"/> Complete/TER's (X if any TER's) <input type="checkbox"/> Cancelled			
Prepared By/Date: <u>E. J. Miller/10/30/87</u> Reviewed By ID/Date: <u>G. J. Chatterjee/10/30/87</u> S/U Ele Supr/Date: <u>J. J. .../10/30/87</u> S/U Pr Dr/Date/Time: <u>10/30/87</u>			
Approval Status: <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Approved with comments <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
PERC Meeting No: <u>E7-238</u> Date: <u>10/30/87</u> Plant Tech Mgr/Date: <u>T. J. .../10/30/87</u> Plant Ops. Mgr/Date: <u>V. J. .../10/30/87</u>			

TEST COPY

000000

STARTUP TEST CHANGE NOTICE

Sheet 1 of 1

Rev.: 4
Form: PAF-1104-3a

STC No./Title 02-025A / MSIV Function Test		Rev. STCN No. Date 3 1025A-5-3 10/29/97
Reason for change To utilize most recent data on stroke time and limit switch positions.		
Affected steps, sections, or paragraphs 6.6.3, 9.9.2.1.c		
Change Change 6.6.3 to ^{latest} latest MSIVs: From the latest SVI-021-T2001, record the MSIV with the fastest stroke time. Then record the actual valve positions AP ₁₀ and AP ₂₀ associated with the fastest MSIV, from the instrument file folder (filed by MSIV number). Obtain the maximum isolation instrumentation delay time from the completed Attachment 1 of Section 8.1, completed during TC 3. Attach copies of the SVI and file folder data.		
Does STCN change intent of the STC (if yes is checked, conditional approval is not allowed)		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Originator/Date K. Burch 10/29/97
Conditional Approval	Test Director/Date Gary Schmidt 10-29-97	Shift or Unit Supervisor/Date J. G. [Signature] 10/29/97
50.59 Applicability Ck Completed per PAF-0305 Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		(Attach Applicability Ck Form) STCN Log <input checked="" type="checkbox"/> Updated
S/U Test Ele Supr/Date	S/U Prog. Director/Date	GE SCM:
	OCS:	
Final Approval: <input type="checkbox"/> Approved <input type="checkbox"/> Disapproved	PCRC Meeting No. N/A At 10-2-97	Plant Tech. Manager/Date: Plant Ops Manager/Date:

TSN 451

STANDARD TEST CHANGE NOTICE

STANDARD TEST CHANGE NOTICE

Sheet 1 of 1

Rev.: 4
Form: STP-1104-22

221-DESA / MSIV Function Test | 3 | 0258-3-2 | 5-17-87

Reason for Change: Delete the requirement to evacuate containment. The unit supervisor feels this is unnecessary.

Affected steps, sections, or paragraphs: 6.3.3, 6.5.3, 8.1.2.2.c, 8.2.2.2.c

Change: Delete the above steps. Mark "Deleted" adjacent to the steps and in signoffs of 8.1.2.2.c and 8.2.2.2.c.

Does STCN change intent of the STC? Yes No (If yes is checked, conditional approval is not allowed) | Operator/Date: J.E. King / 5-17-87

Conditional Approval: Test Director/Date: [Signature] / 5-17-87 | Shift or Unit Supervisor/Date: [Signature] 5/17/87

30.27 Applicability of Completed per STP-1305 Yes No | Attach Applicability of Form | STCN Log Updated

S/O Test E.L. Sign/Date: John Cantoni / 5-20-87	S/O Prog. Director/Date: [Signature] / 5-20-87	GE SCH: [Signature] 5-22-87
---	--	-----------------------------

Final Approval: <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Disapproved	PRC Meeting No.: 87-114	Plant Tech Package/Date: [Signature] 5/21/87
		Plant Ops Manager/Date: [Signature] 5/21/87

STCW TEST CHANGE NOTICE

Sheet 1 of 1

Rev.: 4
Form: EAF-1104-3a

STCW NO./TITLE 577-821-025A/STCW Function Test	REV. 3	STCW NO. 025A-3-1	DATE 5/24/87
Reason for change To transfer testing per Sections 8.1 and 8.2 from TC-2 to TC-3. This change previously approved by PCRC via STCW-203-2-5 and S.E. #87-260.			
Affected steps, sections, or paragraphs 2.0, 6.1, 6.1 note 2, 6.3.1, 6.4.2, 6.5.1, 6.6.3, 6.8.2, 8.1.2.2.a, 8.1.39.4.a.2, 8.2 (note), 8.2.2.1.b, 8.2.2.2.a, 8.2.3.1, 8.3.2.1.c, 8.4.2.1.b, Attachment 7 - No. 1.			
Change For the above steps change Test Condition 2 to Test Condition 3.			
Does STCW change intent of the STCW (if yes is checked, conditional approval is not allowed)		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Originator/Date <i>W.E. Smith</i> / 5-15-87
Conditional Approval	Test Director/Date <i>W.E. Smith</i> 5-15-87	Shift or Unit Supervisor/Date <i>W.E. Smith</i> 5/15/87	
50.59 Applicability Cx Completed per PAF-0305 Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		(Attach Applicability Cx/Form)	STCW Log <input checked="" type="checkbox"/> Updated
STCW Test File Supp/Date <i>John H. Cantini</i> / 5-22-87	STCW Prog. Director/Date <i>John H. Cantini</i> / 5-22-87	GE STCW <i>John H. Cantini</i> / 5-22-87	
Final Approval: <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Disapproved	PCRC Meeting No. 87-114	PLANT Tech Manager/Date: <i>Steve Lambert</i> / 5/21/87	PLANT Ops Manager/Date: <i>W.E. Smith</i> / 5/21/87

TSN 451



8.3 Full Closure of the Fastest MSTV at 70% Power

8.3.1 Precautions Applicable to All Sections

1. Reviewed (5.1)

RLB 10/29/87
Init./Date

8.3.2 Prerequisites and Initial Condition

1. Prerequisites

- a. ERS sample plan (6.6.1)

RLB 10/20/87
Init./Date

- b. Scram and isolation margins verified. (6.6.2)

RLB 10/29/87
Init./Date

- c. Record (6.6.3):

Fastest MSTV F0220, t_d .28 sec.

AP₁₀ 9.8%, AP₉₀ 9.1%

RLB 10/29/87
Init./Date

RLB 10/29/87
Verified By/Date

2. Initial Conditions

- a. Test Condition 7, reactor power 70-75% (6.7.1)

RLB 10/29/87
Init./Date/Time

- b. Recirculation system in Master Manual Mode (6.7.2)

RLB 10/29/87
Init./Date/Time

- c. Evacuate Containment (6.7.3)

RLB 10/29/87
Init./Date/Time

8.3.3 Authorization to test

1. Test Condition 7 and Test Plateau EP are approved per STI-EP-204, High Power Plateau.

RLB 10/29/87
Init./Date

OFFICIAL TEST COPY

OM 5: STI-B21-025A
 Page: 30
 Rev.: 3

2. Test included in TPOD

PTD 10/24/72
 Init/Date

or

Test not in TPOD, approved to test (and QA notified)

NA - P.P. P.P.P.

 Startup Test Program Director Date

3. ~~Approved~~

Donald K. P.P.

10/15/72
 Date Time

 Unit Supervisor

NOTE: All controls and indicators used in this section are located on panel 1E13-P601, unless specified otherwise.

8.3.4 Record the following:

<u>P680 Instrument</u>	<u>Parameter</u>	<u>Data</u>	<u>Alternate Inst./Units</u>
APRM <u>A</u>	Core Power	<u>75</u> %	<u>NA</u>
1N41-R018	Plant MWe	<u>885</u> MWe	<u>K.C.</u>
1C34-P609	Reactor Press	<u>262</u> psig	<u>10/24/72</u>
1E33-P613	Core Flow	<u>55</u> Mlb/hr = <u>52</u> %	
1C34-P601	NF Rx Level (A/B (Circle Channel Used))	<u>12</u> inches	

PTD 10/24/72
 Init/Date

NOTE: Starting and stopping of ERIS and archiving of ERIS data is at the discretion of the Test Director.

8.3.5 Start ERIS recording at least 10 seconds prior to the MSIV closure.

P.P. 10/27/72
 Init/Date

Serial No. 451

OFFICIAL TEST COPY

OM 5: STI-B21-025A
Page: 31
Rev.: 3

8.3.6 Manually close the fastest MSIV (recorded in step 8.3.2-1c) by turning its control switch to the "CLOSE" position.

J.P.B. 10/20/82
Init./Date

8.3.7 When the reactor pressure and power transient has stabilized, stop ERIS. Archive the ERIS data and record the information necessary for data retrieval.

Tape No. 45121
449

J.P.B. 10/29/82
Init./Date

8.3.8 Plant Restoration

1. Open the tripped MSIV by returning its control switch to the "AUTO" position.

J.P.B. 10/20/82
Init./Date

2. Plant operations may continue as directed by the Unit Supervisor.

J.P.B. 10/20/82
Init./Date

8.3.9 Level 1 Analysis

1. Times t'_0 , t_{10} , and t_{90} equal the time the MSIV pilot valve solenoid is de-energized and actuation of the 10% and 90% closed limit switches, respectively.

From the ERIS data (ERIS signals B21EC069 through B21EC071), record values for t'_0 , t_{90} , and t_{10} .

$t'_0 = \frac{55.333}{1000}$ sec.

$t_{90} = \frac{1.14}{1000}$ sec. $t_{10} = \frac{11.424}{1000}$ sec.

J.P.B. 10/20/82
Init./Date

2. Calculate the valve stroke time t_s .

$$t_s = \frac{(t_{90} - t_{10})}{(AP_{90} - AP_{10})} \times 100\%$$

$$t_s = \frac{(0.00114 \text{ sec} - 0.011424 \text{ sec})}{(91 - 8)} \times 100\%$$

$$t_s = 2.58 \text{ sec.}$$

Serial No. 451

OFFICIAL TEST COPY

000000

CM 5: STI-221-025A
Page: 32
Rev.: 3

NOTE: Values for AP₁₀ and AP₉₀ are from step 8.3.2-1.

9.0 10/29/87
Init/Date

3. Verify the MSTV stroke time (t) is greater than or equal to 2.5 seconds and less than or equal to 5.0 seconds: Acceptance Criteria 3.1.1.

9.0 10/29/87
Init/Date

4. Calculate closure time t_{sol} from the following:

$$t_{sol} = (t_{90} - t_0') + \frac{(t_{90} - t_{10})}{(AP_{90} - AP_{10})} (100\% - AP_{50})$$

$$t_{sol} = (1.22 \text{ sec} - 0.22 \text{ sec}) + \frac{(20.20 \text{ sec} - 17.42 \text{ sec})}{(91\% - 91\%)} (100\% - 91\%)$$

$$t_{sol} = 21.76 \text{ sec.}$$

9.0 10/29/87
Init/Date

5. The total effective MSTV closure time equals t_{sol} plus the maximum instrumentation delay time (i.e., t_{sol} + t_d). Calculate the total effective closure time.

$$\text{Total Effective Closure Time} = t_{sol} + t_d$$

$$\text{Total Effective Closure Time} = 21.76 \text{ sec.} + 29 \text{ sec.}$$

$$\text{Total Effective Closure Time} = 22.14 \text{ sec.}$$

NOTE: The value for t_d is from Step 8.3.2-1.

9.0 10/29/87
Init/Date

6. Verify the total effective closure time, is not greater than 5.5 seconds. Acceptance Criteria 3.1.1.

$$t_{sol} + t_d \text{ is less than or equal to } 5.5 \text{ sec.}$$

TER 451-1 9.0 10/29/87
Init/Date

John Smith 10/29/87
Level 1 Analysis Verified By/Date

Serial No. 451

OFFICIAL TEST COPY

000010

CR 5: STI-B21-025A
Page: 33
Rev.: 3

8.3.10 Secure from Test

1. Approved

Tom Ahn 11/27/17
Test Director Date

2. Approved

Mike Remick 11/26/17 0328
Unit Supervisor Date Time

8.3.11 Level 2 Analysis

1. Verify the reactor did not scram or isolate during the MSTV closure: Acceptance Criteria 3.2.1.

9.0 11/1/17
Init/Date

2. Scram Avoidance - Flow Biased Scram

a. Determine the Peak transient value for simulated thermal power (STP). The Peak Transient STP is the value at point of closest approach of ERIS Heat Flux channels CS1EA019 or 20 to either of ERIS channels C71A0003 or C71A0004, respectively.

Peak Transient STP = $\frac{76.209}{77.105}$ 11/1/17

Using: CS1EA019 (CS1EA020) (Circle)

dSTP = Peak Transient STP - Initial STP

dSTP = $\frac{76.209}{77.105} - 76.2924$

dSTP = $\frac{1.117}{77.105}$

9.0 11/3/17
Init/Date

b. Determine APRM Upscale Simulated Thermal Power Trip Setpoint. The Setpoint is the value of ERIS Channels C71A0003 or C71A0004 at the point of the Peak Transient STP. 92.929

Setpoint = $\frac{92.929}{93.510}$ 11/20/17

9.0 11/20/17
Init/Date

Serial No. 451

CONFIDENTIAL

c. Compute the Simulated Thermal Power margin to scram:

Margin to Scram = Setpoint - Peak Transient STP

Margin to Scram = 92.929 % - 78.209 %

Margin to Scram = 14.72 % J. R. / 10/2/157
Init./Date

d. Verify the simulated thermal power (STP) margin to scram for each channel is greater than or equal to 5.0%. Acceptance Criteria 3.2.2.

J. R. / 10/2/157
Init./Date

3. Scram Avoidance - Reactor Pressure

a. Calculate the transient reactor pressure margin to scram.

Initial Pressure = 964.00 psig (ERIS C34EA028)

Margin to Scram = Scram Setpoint - Peak transient pressure (ERIS signal C34EA028 or C34EA030 as appropriate)

Margin to Scram = 1064.7 psig - 984.8 psig

Margin to Scram = 80.9 psi J. R. / 10/2/157
Init./Date

b. Verify the reactor pressure margin to scram is greater than or equal to 10 psi: Acceptance Criteria 3.2.2.

J. R. / 10/2/157
Init./Date

4. Scram Avoidance - Neutron Flux

a. Calculate the transient neutron flux margin to scram:

1) From the ERIS data, determine the peak transient neutron flux. Use highest of ERIS signals CS1EA003 thru CS1EA010 and record the channel used.

Using AFPM B :

Peak Flux = 84.08 %

J. R. / 10/2/157
Init./Date

2) Compute the margin to Scram as follows:

Margin to scram = Setpoint - Peak Flux

Margin to scram = 118% - 84.08 %

Margin to Scram = 33.92 %

10/30/87
Init./Date

b. Verify the neutron flux margin to scram is greater than or equal to 7.5% Acceptance Criteria 3.2.2.

10/30/87
Init./Date

5. Main Steam Line Isolation Avoidance

a. Calculate the transient individual MSL flow margin to isolation:

Margin to Isolation = Setpoint - $\frac{\text{Peak Individual MSL Flow}}{\text{Rated MSL Flow}} \times 100\%$

NOTE: The Peak Individual MSL flow in the above equation is the maximum steam flow observed in all unisolated steam lines.

Margin to Isolation = 137% - $\frac{3.85 \times 10^6 \text{ lbm/hr}}{3.85 \times 10^6 \text{ lbm/hr}} \times 100\%$

Margin to Isolation = 38.149%

Where: Peak transient individual MSL Flow is determined from ERIS signals C34EA014, C34EA015, C34EA016 and C34EA017.

$3.85 \times 10^6 \frac{\text{lbm}}{\text{hr}}$ is one fourth of rated steam flow,

$15.4 \times 10^6 \frac{\text{lbm}}{\text{hr}}$

10/20/87
Init./Date

b. Verify the margin to isolation to greater than or equal to 10%: Acceptance Criteria 3.2.2.

10/30/87
Init./Date

C.B. Miller 10/30/87
Level 2 Analysis Verified By/Date

OFFICIAL TEST COPY

CM 5: STI-E21-025A
Page: 36
Rev.: 3

8.3.12 Verify that any ERIS printouts, other computer or recorder printouts, and any other plant data required is available for inclusion in the Test Results Package.

PTM 10/30/87
Init/Date

***** END OF SECTION 8.3 *****

(INTENTIONALLY BLANK)

Serial No. 451

OFFICIAL TEST 3077

000014

QM 5: STI-B21-025A
Page: 59
Rev.: 3

Attachment 6

EPIS Sample Plan

Function ID	Function Description	Scan Interval (msec)
B21EA001	Rx Wide Range Level C	8
B21EA002	Rx Wide Range Level A	8
B21EA003	Rx Wide Range Level L	8
B21EA004	Rx Wide Range Level B	8
B21EC013	RPS Isolation Status Channel A	5
B21EC014	RPS Isolation Status Channel B	5
B21EC015	RPS Isolation Status Channel C	5
B21EC016	RPS Isolation Status Channel D	5
*B21EC021	SRV Initiation Status	4
*B21EC022	SRV Initiation Status	4
*B21EC023	SRV Initiation Status	4
*B21EC024	SRV Initiation Status	4
*B21EC025	SRV Initiation Status	4
*B21EC026	SRV Initiation Status	4
*B21EC027	SRV Initiation Status	4
*B21EC028	SRV Initiation Status	4
*B21EC029	SRV Initiation Status	4
*B21EC030	SRV Initiation Status	4
*B21EC031	SRV Initiation Status	4
*B21EC032	SRV Initiation Status	4
*B21EC033	SRV Initiation Status	4
*B21EC034	SRV Initiation Status	4
*B21EC035	SRV Initiation Status	4
*B21EC036	SRV Initiation Status	4
*B21EC037	SRV Initiation Status	4
*B21EC038	SRV Initiation Status	4
*B21EC039	SRV Initiation Status	4
B21EC041	SRV Position	10
B21EC043	SRV Position	10
B21EC044	SRV Position	10
B21EC045	SRV Position	10
B21EC046	SRV Position	10
B21EC047	SRV Position	10
B21EC048	SRV Position	10
B21EC049	SRV Position	10
B21EC050	SRV Position	10
B21EC051	SRV Position	10
B21EC052	SRV Position	10
B21EC053	SRV Position	10

TSN 451

ORIGINAL TEST COPY

000015

OP 5: STI-B21-02BA
 Page: 60
 Rev.: 3

Attachment 6 (Cont.)

ERIS Sample Plan

Function ID	Function Description	Scan Interval (msec)
B21EC054	SRV Position	10
B21EC055	SRV Position	10
B21EC056	SRV Position	10
B21EC057	SRV Position	10
B21EC058	SRV Position	10
B21EC059	SRV Position	10
B21EC060	SRV Position	10
*B21EC069+✓	INBD MSIV Solenoid Status (22A)	4
*B21EC070+✓	INBD MSIV Position (22A)	4
*B21EC071+✓	INBD MSIV Position (22A)	4
*B21EC072+✓	INBD MSIV Solenoid Status (22B)	4
*B21EC073+✓	INBD MSIV Position (22B)	4
*B21EC074+✓	INBD MSIV Position (22B)	4
*B21EC075+✓	INBD MSIV Solenoid Status (22C)	4
*B21EC076+✓	INBD MSIV Position (22C)	4
*B21EC077+✓	INBD MSIV Position (22C)	4
*B21EC078+✓	INBD MSIV Solenoid Status (22D)	4
*B21EC079+✓	INBD MSIV Position (22D)	4
*B21EC080+✓	INBD MSIV Position (22D)	4
*B21EC081+✓	OUTBD MSIV Solenoid Status (28A)	4
*B21EC082+✓	OUTBD MSIV Position (28A)	4
*B21EC083+✓	OUTBD MSIV Position (28A)	4
*B21EC084+✓	OUTBD MSIV Solenoid Status (28B)	4
*B21EC085+✓	OUTBD MSIV Position (28B)	4
*B21EC086+✓	OUTBD MSIV Position (28B)	4
*B21EC087+✓	OUTBD MSIV Solenoid Status (28C)	4
*B21EC088+✓	OUTBD MSIV Position (28C)	4
*B21EC089+✓	OUTBD MSIV Position (28C)	4
*B21EC090+✓	OUTBD MSIV Solenoid Status (28D)	4
*B21EC091+✓	OUTBD MSIV Position (28D)	4
*B21EC092+✓	OUTBD MSIV Position (28D)	4
*B33EA021+✓	Reactor Core Flow	8
*B33EA028	Recirc Pump Elbow Tap 14A DP	4
*B33EA029	Recirc Pump Elbow Tap 14C DP	4
*B33EA030	Recirc Pump Elbow Tap 24A DP	4
*B33EA031	Recirc Pump Elbow Tap 24C DP	4
B33EC003	LPMG Set Gen CB 2A Status	5
B33EC004	LPMG Set Gen CB 2B Status	5
B33EC009	LPMG Set Gen CB 5A Status	4
B33EC010	LPMG Set Gen CB 5B Status	4

TSU 451

OPTIONAL TEST COPY

000018

CM 5: STI-B21-025A
Page: 61
Rev.: 3

Attachment 6 (Cont.)

ERIS Sample Plan

Function ID	Function Description	Scan Interval (msec)
*C34EA013+ ✓	Total Reactor Steam Flow	8
*C34EA014+ ✓	Steam Line A Flow	8
*C34EA015+ ✓	Steam Line B Flow	8
*C34EA016+ ✓	Steam Line C Flow	8
*C34EA017+ ✓	Steam Line D Flow	8
*C34EA019	Feedwater Flow A	8
*C34EA020	Feedwater Flow B	8
*C34EA024	Rx Narrow Range Level A	8
*C34EA025	Rx Narrow Range Level B	8
*C34EA026	Rx Narrow Range Level C	8
*C34EA028+ ✓	Narrow Range Rx Dome Pressure	8
*C34EA030- ✓	Wide Range Rx Dome Pressure	6
C34EA031	Turbine Steam Flow	8
C34EC001	TDFP A Trip Status	5
C34EC002	TDFP B Trip Status	5
*C34EC003	MDFP C Trip Status	5
*CS1EA003+ ✓	APRM A Flux	8
*CS1EA004+ ✓	APRM B Flux	8
*CS1EA005- ✓	APRM C Flux	8
*CS1EA006- ✓	APRM D Flux	8
*CS1EA007- ✓	APRM E Flux	8
*CS1EA008- ✓	APRM F Flux	8
*CS1EA009+ ✓	APRM G Flux	8
*CS1EA010- ✓	APRM H Flux	8
*CS1EA019+ ✓	Heat Flux A	4
*CS1EA020- ✓	Heat Flux B	4
*C71EC001	Channel Scram A Status	2
*C71EC002	Channel Scram B Status	2
*C71EC003	Channel Scram C Status	2
*C71EC004	Channel Scram D Status	2
C71EC009	RPT Logic A Status	4
C71EC010	RPT Logic B Status	4
C85EA011	Main Turbine Total EVP Valve Position	4
E22EA001	HPCS Flow	8
E22EC001	HPCS System Initiation Status	5
E51EA004	RCIC Pump Flow	8
E51EA014	RCIC Turbine Speed	8
E51EC001	RCIC System Initiation Status	10
N21EA019	Condenser Pressure A	100
N21EA020	Condenser Pressure B	100
N21EA021	Condenser Pressure C	100

TSN 451

OFFICIAL TEST COPY

000017

CM 5: STI-B21-025A
Page: 62
Rev.: 3

Attachment 6 (Cont.)

ERIS Sample Plan

Function ID	Function Description	Scan Interval (msec)
*N31EA002	Main Turbine Total CV Position	4
*N32EA005	Main Turbine Cont Valve A Position	4
*N32EA006	Main Turbine Cont Valve B Position	4
*N32EA007	Main Turbine Cont Valve C Position	4
*N32EA008	Main Turbine Cont Valve D Position	4
*C71A0003+ ✓	Flow Bias Simulated Thermal Power Trip Setpoint A	8
*C71A0004+ ✓	Flow Bias Simulated Thermal Power Trip Setpoint B	8

*Required point for test.
+Printout required in Test Results Package.

TSN 451

TC-7 Margin Verification

1. From the completed level 2 analysis of section 8.2 performed at TC-7, record the following:

a) From 8.2.11.2a (Simulated Thermal Power) record the largest transient change in simulated thermal power (STP).

$$dSTP = \underline{.55} \%$$

b) Verify the following:

$$10\% - dSTP \geq 5\%$$

$$10\% - \underline{.55} \% \geq 5\%$$

$$\underline{9.45} \% \geq 5\%$$

c) From 8.2.11.3 (Reactor Pressure) record the following:

1. Initial Pressure = 939 psig

2. Peak Transient Pressure = 948 psig

$$\Delta P = \text{Initial Pressure} - \text{Peak Transient Pressure} = \underline{9} \text{ psig}$$

d) Verify the following:

$$55 \text{ psig} - \Delta P \geq 10 \text{ psig}$$

$$55 \text{ psig} - \underline{9} \text{ psig} \geq 10 \text{ psig}$$

$$\underline{46} \text{ psig} \geq 10 \text{ psig}$$

e) From 8.2.11.4 (Neutron Flux) record the following:

$$dAPRM = \underline{2} \%$$

f) Verify the following:

$$38\% - dAPRM \geq 7.5\%$$

$$38\% - \underline{2} \% \geq 7.5\%$$

$$\underline{36} \% \geq 7.5\%$$

TC-7 Margin Verification

g) From 8.2.11.5 (MSL Isolation Avoidance) record the following:

Initial MSL flow = 1.44×10^6 lbm/hr
Peak Individual MSL flow = 1.98×10^6 lbm/hr

Δ MSL Flow = $\frac{\text{Peak Individual MSL Flow} - \text{Initial MSL flow}}{3.85 \times 10^6 \text{ lbm/hr}}$

h) Verify the following:

52% - Δ MSL Flow $\geq 10\%$

52% - $\frac{14}{38} \geq 10\%$

$\frac{38}{38} \geq 10\%$

Robert Burchwick
Completed By/Date

Robert Burchwick 10/1/87
Verified By/Date

Reportability Review

<u>Date/Time</u>	<u>Event</u>
10-29-87/2144	Both MSL D Isolation Valves Failed.
10-30-87/0010	4 hour ENS call made to NRC regarding slow MSIVs. *Call made within the Requirements of 10 CFR 50.72 (b)(2)(iii) - Loss of a safety function.
11-03-87/1212	Both MSL D Isolation Valves Failed.
11-03-87/1337	Commenced Plant Shutdown.
11-03-87/1355	ENS call made on Plant shutdown and slow MSIVs. *Call satisfied 4 hour requirements of 10 CFR 50.72 (6)(2)(iii) and 1 hour requirement of 50.72 (b)(1)(i)A - Plant shutdown required by Technical Specification.
11-3-87/1619	Plant scrambled to shutdown.
11-03-87/2130	ENS call made on RPS/ESF Actuation. *2130 call was unnecessary since the plant scram was planned, not unexpected. Never-the-less call was within 4 hour requirement per 10 CFR 50.72 (b)(2)(ii) - RPS/ESF Actuations.
Conclusion:	Three calls were made. All immediate Notification Requirements were satisfied. One call was made unnecessarily. A 30 day written report, in accordance with 10 CFR 50.73, was initiated and is forthcoming.

1. History

On October 29, 1987 at 1900, Main Steam Isolation Valve (MSIV) 1B21-F022D exceeded it's allowable stroke time during performance of a startup test and was declared inoperable. Technical Specification 3.6.4 Action (a) then became applicable and the penetration was to be isolated within 4 hours unless the valve could be returned to Operable status. At 2103 and 2106, 1B21-F022D was cycled and stroked closed within the 5 second isolation time required by 3.6.4.

Subsequent to the 1B21-F022D valve testing, all MSIVs were cycled in order to verify adequate stroke times. At 2144, the 1B21-F028D failed it's stroke time test and was considered inoperable. At this point, Technical Specifications required the plant to be shutdown in 12 hours. (One other MSIV, 1B21-F028E, also failed it's first stroke time test at 2216).


By 2310, all MSIVs that failed their initial stroke times had successfully completed subsequent tests and an evaluation of the results was complete. The valves were now considered operable. The bases for this decision was that the cause of the slow closures was a one time deposit of debris in the respective solenoids causing a delay in their response. Once the valves were cycled and the stroke times passed, the debris was assumed to be blown away. This conclusion was consistent with known industry problems regarding air systems and MSIV solenoid valves. These previous experiences were considered heavily in the final decision. No further actions per Technical Specifications were required. None of the Technical Specification Limiting Conditions for Operation (LCO) were violated.


On November 3, 1987 another series of stroke timing tests were performed on the MSIVs. At 1157, the 1B21-F022D failed it's stroke time and was declared inoperable. At 1208 the 1B21-F028D failed to close. Both valves were subsequently recycled satisfactorily within minutes of their first tests. However, because the valves again failed to properly actuate on the first attempt, the original hypotheses for the isolated failures was no longer considered valid. The plant commenced a shutdown at 1330 and the D and B lines were isolated by 1354. At 1819, in order to complete the shutdown the reactor was manually scrammed. The plant was shutdown within the 12 hours required by Technical Specification 3.6.4 Action (a).

Since no LCO was violated during either event, the plant remained within the constraints of the analytical bases contained in the operating license. Consequently, the incidents resulted in no immediate safety significance.

020

89





THE CLEVELAND ELECTRIC ILLUMINATING COMPANY
 10000 MARKET STREET, CLEVELAND, OHIO

STATE: OHIO

DATE: _____

SCALE: _____

PROJECT: _____

DESIGNED BY: _____

CHECKED BY: _____

APPROVED BY: _____

Sheet # 2

NO.	REV.	DATE	BY	CHKD.

<u>W.O.</u>	<u>DESCRIPTION</u>
85-12198	Nuclear Boiler NSSS - Repair Leaking Instrument Air Fitting.
86-312	Nuclear Boiler NSSS - Determined Sol Leads Form MSIV's.
86-512	Area Rad Monitor - Rework Local Meter.
86-806	Nuclear Boiler NSSS - Rework Swagelock Fittings on MSIVs.
86-12963	Nuclear Boiler NSSS - Sol currently reads "0" Panel 1H13-P622.
86-14977	Nuclear Boiler NSSS - Valve wouldn't slow close per SVI.
87-82	Nuclear Boiler NSSS - MSIV "C" will not close in Test position.
87-3153	Nuclear Boiler NSSS - Perform Test of Valve as per NR.
87-3156	Nuclear Boiler NSSS - Remove O-ring and Clean Valve Seats.
87-5841	Nuclear Boiler NSSS - Elect. Support (1B21-F0022C).
87-8290	Nuclear Boiler NSSS - Rework Valve to assure proper operation.

0-70

W.O.SUMMARY

85-0572 Checked calibration of 1P52-N0140, Recalibrated.

85-3756 Machined valve poppet on 1B21-F0022B.

85-4174 Machined valve poppet on 1B21-F0022B.

85-4320 Machined valve poppet on 1B21-F0022B.

85-4413 Machined Stem Seat per NR P038-6105 for 1B21-F0022B.

85-5198 Machined Valve poppet on 1B21-F0022B.

85-11486 Performed loss of air test per GEN-M-038 on 1B21-F0022B.

85-11512 Performed loss of air test per GEN-M-038 on 1B21-F0022B.

85-11839 Performed loss of air test per GEN-M-038 on 1B21-F0028D.

85-11943 Installed flood & moisture seals in cable transits & MSIVs per DCP 85-618.

86-0312 Determined MSIV Solenoid leads to allow disconnection of conduit.

86-0522 Replaced 1B21 Solenoid valves with spares.

86-0806 Reworked Swagelock fittings on MSIVs (1B21-F022 B & D and F028 A, B, C & D).

86-7637 Replaced screws and gasket for 1B21-F0022b.

86-12734 Voided - to close out DAR-269.

86-12963 Troubleshoot Solenoid - replaced rectifier with new diode bridge on 1B21-F0022D (NR MMQS-1382).

86-14977 Troubleshoot - 1B21-F0022D wouldn't slow close per SVI-C71-T038D. Replaced relay 1B21-K0077D.

87-0729 Reworked 1B21-F0022B due to failed LLRT.

87-0735 Contingency W.O. - Not needed.

87-0763 Performed Repetitive Task R85-10868/DCP 87-216. Performed SVI-C71-T0038H, Rebuilt limit switches, & completed SVI-B21-T2001 all for 1B21-F0028D.

87-0769 Performed Repetitive Task R85-10954/DCP 87-216 for 1B21-F0022B. Rebuilt limit switches. Performed SVI-C71-T0038B & SVI-B21-T2001.

W.O.SUMMARY

87-5839 Contingency W.O. - Not needed (See W.O. 87-769 for retest).

87-5842 Contingency W.O. - Not needed (See W.O. 87-770 for retest).

87-5846 Contingency W.O. - Not needed (See W.O. 87-763 for retest).

87-8149 1B21-F0022B stem threaded out of stem plate. Reworked per NR NEDS-2863. Performed SVI-B21-T2001.

87-8206 1B21-F0022B failed LLRT. Reworked, reassembled, and retest.

87-8236 Adjusted actuator stroke & calibrated limit switches for 1B21-F0022D.

87-8618 1B21-F0028D had no close indication due to loose terminal on switch #1.

P = Prior to startup

P 1. Solenoid Work - Fast Closure

Replace total air pack 28D ^{Worst actor}

Replace whole solenoid on 22D ^{Rush solenoids}

Rebuild Kits for 6 additional ^{Fast closure solenoids}

Bisco on all spares in manner to allow rebuild (IS) ^{Dual ASCO's}

~~Replace any solenoids showing other than normal temp. degradation (rust, etc)~~

P 2. Solenoid Work - Slow Closure

1 Replaced due to air pack replacement 28D

Bisco all spares (8)

~~Replace solenoids if fast closure solenoid inspection indicates need~~

3. Solenoid Research - Others experience & efforts

Excessive Aging (Temp., Brass, E PDM, Hydrocarbons)

Review Design for Improvement possibilities

Consider exhaust port screen installation

Replacement frequency

For details see 10/10/04 report by [unclear]

D-11

4. Air System Efforts

Provide Sampling plan intent & results

Continue Dewpoint & particle sampling

Implement PM for periodic replacement of filters

Implement generic caution in air system work packages for lubricants or sealants.

Offsite and
in-plant
testing
to be
determined.

✓ Examine reduction gear vent and compressor intake
More frequent replacement of filters on compressor intake.

P 5. Other ASCO Applications in Plant

50 class 1E, 40 Harsh Environment, 2 in DW or Steam Tunnel

Energized state applications

Maintenance History

P 6. Other equipment impacts

vicinity of 22 D, 28 B & D.

EPDM applications in High Temp. areas

P7. Additional Temp. Monitoring

Steam Tunnel

MSIV area

Solenoid body, coil etc.

Test solenoid

Evaluate DW potential ~ Study hot spot penetration

^{10 constant}

P8. Additional Surveillance

Until 1st refuel

During monthly slow closure check full closure solenoids

Perform Quarterly timing regardless of shutdown condition

^{10 constant}

P9. Inspection of ASCO dual solenoids prior to next refuel outage.

• Jan. / March / Oct. operations.

• Establish criteria.

- Water intrusion in FO2SB indicates problem potential with EQ, other EQ
as problems (temp., etc.)
- Inconit wiring diag (most likely the ^{as built} chemistry logic diag).

- ~~Act~~ PM on IA/SA + other in action list

- Complete analysis of samples.

F022D

- WO 9323^{Rev. 1} - Airpack blow down ~~*~~, visual & voltages
- WO 9293^{Rev. 2} - Removal of air pack
- WO 9405^{Rev. 1} - Blow down airline
- WO 9372^{Rev. 1} - Airpack disassy. except slow closure solenoid.
 Cylinder in 2nd stop

F028D

- WO 9285^{Rev. 3} - Removal of air pack
- WO 9440^{Rev. 0} - Blowdown airline
- WO 9443^{Rev. 1} - Complete air pack disassy.
- ~~WO 9444~~ ^{Rev. 0} Removal of air pack
- WO 9456^{Rev. 0} - Bench Test Airpack

F028B

- WO 9324^{Rev. 0} - Removal of air pack
- WO 9439^{Rev. 0} - Blowdown Airline
- WO 9433^{Rev. 4} - Airpack disassy. except slow closure solenoid

D-72

72

OPERATING DATA	
1	
2	
3	
4	
5	
6	
7	
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	
21	
22	
23	
24	
25	
26	
27	
28	
29	
30	

REVISIONS

1. INITIAL DESIGN

2. REVISIONS TO ACCOMMODATE

3. REVISIONS TO ACCOMMODATE

4. REVISIONS TO ACCOMMODATE

5. REVISIONS TO ACCOMMODATE

6. REVISIONS TO ACCOMMODATE

7. REVISIONS TO ACCOMMODATE

8. REVISIONS TO ACCOMMODATE

9. REVISIONS TO ACCOMMODATE

10. REVISIONS TO ACCOMMODATE

SYSTEM DESIGNATION

1. SYSTEM DESIGNATION

2. SYSTEM DESIGNATION

3. SYSTEM DESIGNATION

4. SYSTEM DESIGNATION

5. SYSTEM DESIGNATION

6. SYSTEM DESIGNATION


7. SYSTEM DESIGNATION

8. SYSTEM DESIGNATION

9. SYSTEM DESIGNATION

10. SYSTEM DESIGNATION

DESIGN DATA	
1	
2	
3	
4	
5	
6	
7	
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	
21	
22	
23	
24	
25	
26	
27	
28	
29	
30	



A30 IE Arch

Ascom. 1#

NP-8320-A185E
NP-8323-A20E

NP-8320-A185E
NP-8323-A20E

NP-8320-A185E
NP-8323-A20E

NP-8320-A185E
NP-8323-A20E

NP-8320-A185E
NP-8323-A20E

NP-8320-A185E
NP-8323-A20E

C EQUIPMENT	DESCRIPTIONS	DIAGRAM REV C
D NUMBER	SERVICE (2)	LOCATION
S	EQUIPMENT (2)	SUPPORT
		ZONE M/H

*1B21 F 0460	NUCLEAR STEAM SUPPLY SHUTOFF SYSTEM MAIN STEAM ISOLATION VALVE-INBOARD TEST/PILOT SOLENOIDS (3)	1B21H010 R D C 1/00-630 1B21 F 0022A DW-1 HARSH
--------------	--	--

NO WORK HISTORY

*1B21 F 046	NUCLEAR STEAM SUPPLY SHUTOFF SYSTEM MAIN STEAM ISOLATION VALVE-INBOARD TEST/PILOT SOLENOIDS (3)	1B21H010 R D C 1/00-630 1B21 F 0022B DW-1 HARSH
-------------	--	--

NO WORK HISTORY

*1B21 F 0462	NUCLEAR STEAM SUPPLY SHUTOFF SYSTEM MAIN STEAM ISOLATION VALVE-INBOARD TEST/PILOT SOLENOIDS (3)	1B21H010 R D C 1/00-630 1B21 F 0022C DW-1 HARSH
--------------	--	--

NO WORK HISTORY

*1B21 F 0460	NUCLEAR STEAM SUPPLY SHUTOFF SYSTEM MAIN STEAM ISOLATION VALVE-INBOARD TEST/PILOT SOLENOIDS (3)	1B21H010 R D C 1/00-630 1B21 F 0022D DW-1 HARSH
--------------	--	--

NO WORK HISTORY

*1B21 F 0480	NUCLEAR STEAM SUPPLY SHUTOFF SYSTEM MAIN STEAM ISOLATION VALVE-OUTBOARD TEST/PILOT SOLENOIDS (3)	1B21H011 S C AXC/05-620 1B21 F 0028A AB-7 HARSH
--------------	---	--

NO WORK HISTORY

*1B21 F 0481	NUCLEAR STEAM SUPPLY SHUTOFF SYSTEM MAIN STEAM ISOLATION VALVE-OUTBOARD TEST/PILOT SOLENOIDS (3)	1B21H011 S D AXC/05-620 1B21 F 0028B AB-7 HARSH
--------------	---	--

NO WORK HISTORY

Asco Model #

NP 8316 A75E

NP 8316 A75E

NP 8316 A75E

NP 8316 A75E

NP 8316 A75E

NP 8316 A75E

		DATE	ZONE	M/H
*1M14 F 0043	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F040 SOLENOID	1M14 008 G	D1	
		C 0/12-689		
		1M14 F 0040		
		CT-0 HARSH		
	NO WORK HISTORY			
*1M14 F 0048	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F045 SOLENOID	1M14 008 G	D2	
		C 0/12-689		
		1M14 F 0045		
		CT-1 HARSH		
	WO B 6-1698 Repl - A - Take L&L			
*1M14 F 0058A	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F055A SOLENOID	1M14 009 K	D1	
		C 1/07-630		
		1M14 F 0058A		
		DW-1 HARSH		
	NO WORK HISTORY			
*1M14 F 0058B	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F055B SOLENOID	1M14 010 J	D2	
		C 0/07-630		
		1M14 F 0058B		
		CT-3 HARSH		
	NO WORK HISTORY			
*1M14 F 0063A	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F060A SOLENOID	1M14 009 K	D1	
		C 1/16-630		
		1M14 F 0060A		
		DW-1 HARSH		
	NO WORK HISTORY			
*1M14 F 0063B	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F060B SOLENOID	1M14 010 J	D2	
		C 0/16-630		
		1M14 F 0063B		
		CT-3 HARSH		
	NO WORK HISTORY			

ASCO M.I.1 H

NP8316A75E

NP8316A75E

NP8316A75E

NP8316A75E

NP8316A75E

NP8316A74E

NP8316A75E

NP8316A74E

C EQUIPMENT D NUMBER S	DESCRIPTIONS SERVICE (2) EQUIPMENT (2)	DIAGRAM REV. LOCATION SUPPORT ZONE M/H
*1M14 F 0068	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F065 SOLENOID	1M14 011 H C 0/12-652 1M14 F 0065 CT-7 HARSH
NO WORK HISTORY		
*1M14 F 0073	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F070 SOLENOID	1M14 012 G C 0/12-652 1M14 F 0070 CT-7 HARSH
NO WORK HISTORY		
*1M14 F 0088	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F085 SOLENOID	1M14 011 H C 0/12-664 1M14 F 0085 CT-7 HARSH
NO WORK HISTORY		
*1M14 F 0093	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F090 SOLENOID	1M14 012 G C 0/12-664 1M14 F 0090 CT-0 HARSH
NO WORK HISTORY		
*1M14 F 0192	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F190 SOLENOID	1M14 013 F C 0/12-688 1M14 F 0197 CT-1 HARSH
NO WORK HISTORY		
*1M14 F 0202	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F200 SOLENOID OFFN W.O. 86-3552 Tubing Air LEAK	1M14 013 F C 0/12-664 1M14 F 0200 CT-7 HARSH
NO WORK HISTORY		
1M14 F 0207		
W.O. 86-3553. Tubing Air Leak (None found)		

ASCO M.A.I.H

EQUIPMENT LIST

C EQUIPMENT	DESCRIPTIONS	DIAGRAM REV
D NUMBER	SERVICE (2)	LOCATION
S	EQUIPMENT (2)	SUPPORT
		ZONE M/H

NP8316A74E

*1M14 F 0197	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F195 SOLENOID	1M14 016 D D C 0/12-689 1M14 F 0195 CT-1 HARSH
--------------	--	---

NO WORK HISTORY

NP8316A74E

*1M14 F 0207	CONTAINMENT VESSEL AND DRYWELL PURGE OP AIR TO F205 SOLENOID	1M14 016 D D C 0/12-664 1M14 F 0205 CT-7 HARSH
--------------	--	---

W.O. 66-3553 T.G.W. A. ...
V.O. B.P.K. ...

AS to Mod. 1 B

AS OF 00761
SORT : 01
TITLE : EQPL/SP 607-000

C EQUIPMENT	DESCRIPTIONS	DIAGRAM REV D:
-------------	--------------	----------------

D NUMBER	SERVICE (2)	LOCATION
S	EQUIPMENT (2)	SUPPORT
		ZONE M/H

NPS 320 A 185E

*1821 F 0451	NUCLEAR BOILER SYSTEM SOLENOID FOR VALVE F069 SOLENOID	1B21A004 U D: AXB/04-620 1B21 F 0069 AB-7 HARSH
--------------	--	--

W.O. B5-1674

NPS 320 C 94E

*1833 F 0419	REACTOR RECIRCULATION SYSTEM CONTROLS OPERATING AIR TO F019 SOLENOID VALVE	1B21H008 U D: C 0/02-620 1B33 F 0019 CT-3 HARSH
--------------	--	--

W.O. B6-3559

NPS 320 94E

*1833 F 0420	REACTOR RECIRCULATION SYSTEM CONTROLS OPERATING AIR TO F020 SOLENOID	1B21H009 U D: C 0/02-620 1B33 F 0020 CT-3 HARSH
--------------	--	--

NO WORK HISTORY

NPS 320 A 185E

*1E12 F 0451A	RESIDUAL HEAT REMOVAL SYSTEM CONTROLS OPERATING AIR TO F051A SOLENOID VALVE	1E12A041 F D: AXB/06-620 1E12 F 0051A AB-4 HARSH
---------------	---	---

NO WORK HISTORY

NPS 320 A 185E

*1E12 F 0451B	RESIDUAL HEAT REMOVAL SYSTEM CONTROLS OPERATING AIR TO F051B SOLENOID VALVE	1E12A042 H D: AXB/04-620 1E12 F 0051B AB-4 HARSH
---------------	---	---

NPS 320 A 185E

*1E12 F 0465A	RESIDUAL HEAT REMOVAL SYSTEM CONTROLS OPERATING AIR TO F065A SOLENOID VALVE	1E12A041 F D: AXB/06-574 1E12 F 0065A AB-4 HARSH
---------------	---	---

NO WORK HISTORY

ASG m.l.l.H

TITLE : EQPL/SP 607-000

C EQUIPMENT	DESCRIPTIONS	DIAGRAM REV
D NUMBER	SERVICE (2)	LOCATION
S	EQUIPMENT (2)	SUPPORT
		ZONE M/H

NP 8320 A155E	*1E12 F 0465B	RESIDUAL HEAT REMOVAL SYSTEM CONTROLS OPERATING AIR TO F065B SOLENOID VALVE	1E12 042 F AXC/04-574 1E12 F 0065E AB-4 HARSH
NO WORK HISTORY			

NP 8320 A155E	*1E51 F 0404	REACTOR CORE ISOLATION COOLING CONTROLS OPERATING AIR TO F004 SOLENOID VALVE	1E51A007 P AXB/05-574 1E51 F 0004 AB-3 HARSH
NO WORK HISTORY			

NP 8320 A155E	*1E51 F 0405	REACTOR CORE ISOLATION COOLING CONTROLS OPERATING AIR TO F005 SOLENOID VALVE	1E51A007 P AXB/05-574 1E51 F 0005 AB-3 HARSH
NO WORK HISTORY			

NP 8320 A155E	*1E51 F 0425	REACTOR CORE ISOLATION COOLING CONTROLS OPERATING AIR TO F025 SOLENOID VALVE	1E51A007 P AXC/05-574 1E51 F 0025 AB-3 HARSH
NO WORK HISTORY			

NP 8320 A155E	*1E51 F 0426	REACTOR CORE ISOLATION COOLING CONTROLS OPERATING AIR TO F026 SOLENOID VALVE	1E51A007 P AXC/05-574 1E51 F 0026 AB-3 HARSH
NO WORK HISTORY			

NP 8320 A155E	*1E51 F 0454	REACTOR CORE ISOLATION COOLING CONTROLS OPERATING AIR TO F054 SOLENOID VALVE	1E51A007 P AXC/05-574 1E51 F 0054 AB-3 HARSH
NO WORK HISTORY			

TITLE : EURL/SUM-ENV

C EQUIPMENT	DESCRIPTIONS	DIAGRAM REV D:
D NUMBER	SERVICE (2)	LOCATION
S	EQUIPMENT (2)	SUPPORT
		ZONE M/H

*1C11 D 0001	REACTOR PROTECTION SYSTEM	1C71A010 H VA
	CRD-HCV/SCRAM SOLENOID PILOT VALVE	C 0/14-620
	SOLENOID(TYPICAL-177	LOCAL-CF
	CRDS-2 SSPV PER CRD)	CT-3 HARSH

Search Hand

ASCO MODEL # HVA-176-816-1

Computer Search results -
Identify Solenoid works

Automatic Switch Co.

FLORHAM PARK, NEW JERSEY

Printed in U.S.A.

KEDC-30208

PRODUCTION SPECIFICATION

BILL OF MATERIAL

FVP-176-816

PAGE 1 OF 4 PAGE

CHG
LTR

CATA. NO.

HV176-816-1 & HV176-816-2

SHOP ORDER NO

BULL. NO.

HV176-816, 1/2 NPT, PACKLESS, 3 WAY
DIAPHRAGM OPERATED, QUICK EXH. VALVE WITH
REDUNDANT PILOTED SOLENOID, NEMA TYPE 4
WATERTIGHT SOL. ENCL. WATTS: 15.4 AC (FT)
EACH.NO OF PARTS
LIST PER ASSY

1

ASSEMBLY REF

HVA-176-816

70	K		
71	H		
72	H		
73	H		
74	H		
75	H		
76	H		
77	H		
78	H		
79	H		
80	H		
81	H		
82	H		
83	H		
84	H		
85	H		
86	H		
87	H		
88	H		
89	H		
90	H		
91	H		
92	H		
93	H		
94	H		
95	H		
96	H		
97	H		
98	H		
99	H		
100	H		
101	H		
102	H		
103	H		
104	H		
105	H		
106	H		
107	H		
108	H		
109	H		
110	H		
111	H		
112	H		
113	H		
114	H		
115	H		
116	H		
117	H		
118	H		
119	H		
120	H		
121	H		
122	H		
123	H		
124	H		
125	H		
126	H		
127	H		
128	H		
129	H		
130	H		
131	H		
132	H		
133	H		
134	H		
135	H		
136	H		
137	H		
138	H		
139	H		
140	H		
141	H		
142	H		
143	H		
144	H		
145	H		
146	H		
147	H		
148	H		
149	H		
150	H		
151	H		
152	H		
153	H		
154	H		
155	H		
156	H		
157	H		
158	H		
159	H		
160	H		
161	H		
162	H		
163	H		
164	H		
165	H		
166	H		
167	H		
168	H		
169	H		
170	H		
171	H		
172	H		
173	H		
174	H		
175	H		
176	H		
177	H		
178	H		
179	H		
180	H		
181	H		
182	H		
183	H		
184	H		
185	H		
186	H		
187	H		
188	H		
189	H		
190	H		
191	H		
192	H		
193	H		
194	H		
195	H		
196	H		
197	H		
198	H		
199	H		
200	H		

ITEM	PART NUMBER	CHG LTR	NOTE	MATERIAL	PART NAME	QUANTITY		
						UNIT	REQD	DELVD
1	HVA-176-454	F	1		SOL. ASS'Y A (M-12)	1		
1A	GV-176-593-1	H		ST. STEEL	RETAINING CLIP	1		
1B	FV-99-033-1	H		STEEL	SLEEVE	2		
1D	GV-172-739-1	E		ALUM.	NAMEPLATE	1		
1E	HV-96-815-1	N		STEEL	YOKE	1		
1F	GV-39-619-5-WT	CV		ETHYLENE PROPYLENE	GASKET, HOUSING	1		
1G	FV-168-808-1	F		STEEL	COVER	1		
1I	FV-172-788-1	C		STEEL	SCREW, COVER	3		
1J	FV-172-759-1	D		BUNA-N	GASKET, COVER	1		
1K	FV-93-233-1 FV-93-233-1	B		STEEL	FLUX WASHER	1		
2	HVA-176-730	A	2		SOL. ASS'Y. B (M-12)	1		
2A	GV-176-593-1	H		ST. STEEL	RETAINING CLIP	1		
2B	FV-176-357-1	C		STEEL	SPACER	1		
2C	FV-172-788-1	C		STEEL	SCREW, COVER	3		
2D	FV-172-759-1	D		BUNA-N	GASKET, COVER	1		
2E	FV-168-808-1	F		STEEL	COVER	1		
2F	FV-99-033-1	H		STEEL	SLEEVE	2		
2H	HV-96-815-1	N		STEEL	YOKE	1		
2K	FV-180-769-3	B		ETHYLENE PROPYLENE	GASKET, HOUSING	1		
7	GV-39-619-6-VI	DU		VITON-A	GASKET	3		
0	GH-70-022-9C1	P		ST. STEEL	WASHER	4		
4	GH-73-102-3C1	N		ST. STEEL	SCREW	4		
8	GH-88-224-133A	Y		BUNA-N	GASKET			

THIS INFORMATION IS SUPPLIED IN ACCORDANCE WITH ARTICLE VIII OF THE NUCLEAR STEAM SUPPLY SYSTEM CONTRACT BETWEEN GENERAL ELECTRIC COMPANY AND CLEVELAND ELECTRIC SUPPLYING COMPANY DATED JUNE 7, 1972. THE USE OF THIS INFORMATION BY ANYONE OTHER THAN ACCEPTED EMPLOYEES OF CLEVELAND ELECTRIC SUPPLYING COMPANY FOR ANY PURPOSE OTHER THAN THE DESIGN, CONSTRUCTION, OPERATION OR MAINTENANCE OF THE PLANT NUCLEAR POWER PLANT IS NOT AUTHORIZED BY THE GENERAL ELECTRIC COMPANY.

Automatic Switch Co.
FLORHAM PARK, NEW JERSEY
Printed in U.S.A.

PRODUCTION SPECIFICATION
BILL OF MATERIAL

AE	100
AL	100
AM	100
AN	100
AO	100
AP	100
AQ	100
AR	100
AS	100
AT	100
AU	100
AV	100
AW	100
AX	100
AY	100
AZ	100

FVP-176-816
PAGE 2 OF 4 PAGE

CHG LTR	7	10	10	10	10	10	10	10	10
---------	---	----	----	----	----	----	----	----	----

CATA. NO. HV176-816-1 & HV176-816-2

SHOP ORDER NO

BULL. NO. HV176-816

NO. OF PARTS LIST PER ASSY
1

ASSEMBLY REF
HVA-176-816

70577	F		
69132	D		
68347	C		
67826	E		
ER NO	CHG LTR	ER NO	CHG LTR

FVP-176-816

ITEM	PART NUMBER	CHG LTR	NOTE	MATERIAL	PART NAME	QUANTITY		
						UNIT	REQD	DELVD
3	GV-89-653-5	EA			CORE ASS'Y. SOL. A	1		
	FV-91-084-1	G		ST. STEEL	CORE	1		
	GV-60-452-9	EM		VITON-A WATER-PROOF	DISC	1		
	GV-60-452-9				ADAPTER PLUGNUT ASSY.	1		
	GV-60-452-9			BRASS	ADAPTER	1		
	GV-60-452-9				PLUGNUT ASSY.	1		
	GV-60-452-9			ST. STEEL	PLUGNUT	1		
	GV-60-452-9			COPPER	SHADING COIL	1		
12	FV-101-749-4K	Z			DISC HOLDER ASS'Y	1		
	GV100-820-4	R		VITON A	DISC	1		
	GV-174-682-1	C		ST. STEEL	DISC. HOLDER	1		
19	FV-160-219-2	C		ST. STEEL	SUPPORT	1		
13	FV-162-939	-		ST. STEEL	SPRING, DISC	1		
6	FV-96-678-4	H			SOL. BASE SUB-ASS'Y. B	1		
	FV-172-472-1	A		ST. STEEL	DISC, FORMING	1		
	FV-166-960-2	F		ST. STEEL	CORE TUBE	1		
	FV-96-677-3	H		ST. STEEL	BONNET	1		
14	FV-178-088	-		ST. STEEL	SPRING, DIAPH.	1		
23	FV-186-495	A	3	—	SPARE PARTS KIT	—		
25	GV-200-153-1	J		BRASS	ADAPTER	1		
	FV-206-048-1	F			PLUGNUT ASSY	1		
	FV-158-248-1	E		COPPER	SHADING COIL	1		
	GV-200-152-1	J		ST. ST.	PLU.			

THIS INFORMATION IS SUPPLIED IN ACCORDANCE WITH ARTICLE XVII OF THE NUCLEAR FUEL SUPPLY SYSTEM CONTRACT BETWEEN GENERAL ELECTRIC COMPANY AND CLEVELAND ELECTRIC ILLUMINATING COMPANY DATED JUNE 2, 1972. THE USE OF THIS INFORMATION BY ANYONE OTHER THAN EMPLOYEES OF CLEVELAND ELECTRIC ILLUMINATING COMPANY FOR ANY PURPOSE OTHER THAN THE DESIGN, CONSTRUCTION, LICENSING OR OPERATION OF THE HEART HULLER POWER PLANT IS NOT AUTHORIZED BY THE GENERAL ELECTRIC COMPANY.

Automatic Switch Co.

FLORHAM PARK, NEW JERSEY

Printed in U.S.A.

PRODUCTION SPECIFICATION

BILL OF MATERIAL

AE	CH
CA	AI
AL	
AM	
KA	

FVP-176-816

PAGE 3 OF 4 PAGE

CHG LTR

7241

7242

7243

7244

7245

7246

7247

7248

7249

7250

7251

7252

7253

7254

7255

7256

7257

7258

7259

7260

7261

7262

7263

7264

7265

7266

7267

7268

7269

7270

7271

7272

7273

7274

7275

7276

7277

7278

7279

7280

7281

7282

7283

7284

7285

7286

7287

7288

7289

7290

7291

7292

7293

7294

7295

7296

7297

7298

7299

7300

7301

7302

7303

7304

7305

7306

7307

7308

7309

7310

7311

7312

CATA. NO.

HV176-816-1 / HV176-816-2

SHOP ORDER NO

BULL. NO.

HV176-816

NO OF PARTS LIST PER ASS'Y

1

ASSEMBLY REF

HVA-176-816

ER NO

CHG LTR

ER NO

CHG LTR

FVP - 176-816

ITEM	PART NUMBER	CHG LTR	NOTE	MATERIAL	PART NAME	QUANTITY		
						UNIT	REQ'D	DELVD
15	FV-178-091-1	A			DIAPHRAGM/DISC SUB-ASS'Y.	1		
	FV-178-092-1	A		ST. STEEL	RIVET	1		
	FV-103-889-1	L			DISC, SUB-ASS'Y.	2		
	FV-103-888-2	B		ST. STEEL	INSERT	2		
	GV-164-054-34	S		BUNA-N	DIAPHRAGM	1		
13	FV-178-114-1	B		ST. STEEL	STEM	1		
	GV-178-122-1	A		BRASS	BODY, MAIN	1		
	FV-178-247-1	C			BODY & BONNET SUB-ASS'Y.	1		
	FV-178-110-1	B		BRASS	BODY	1		
	GV-178-089-1	C		BRASS	BONNET	1		
10	FV-178-547	B		17-75	SPRING	1		
5	GV-180-817-31	F			SOL. BASE SUB-ASS'Y. A	1		
	FV 80-630-14	W			PLUGNUT SUB-ASS'Y.	1		
	FV 180-422-1	-		ST. STEEL	PLUGNUT	1		
	FV-158-247-1	F		COPPER	SHADING COIL	1		
	FV-180-536-4	A		BRASS	BONNET	1		
	FV-164-996-1	E		ST. ST.	CORETUBE	1		
4	FV-182-125-1	-			CORE ASS'Y. SOL. B	1		
	FV-162-970-1	B		ST. ST.	CORE	1		
	FV-162-968-2	A		BRASS	GUIDE, SPRING	1		
	FV-180-347	A		ST. ST.	SPRING, CORE	1		
	FV-162-969-1	C		BRASS	PLUG, CORE	1		
	FV-166-647-1	D		PLASTIC	LABELS A & B			

THIS INFORMATION IS SUPPLIED TO ACCORDANCE WITH ARTICLE VIII OF THE NUCLEAR STEAM SUPPLY SYSTEM CONTRACT BETWEEN GENERAL ELECTRIC COMPANY AND CLEVELAND ELECTRIC ILLUMINATING COMPANY DATED JUNE 2, 1972. THE USE OF THIS INFORMATION BY ANYONE OTHER THAN EMPLOYEES OF CLEVELAND ELECTRIC ILLUMINATING COMPANY FOR ANY PURPOSE OTHER THAN THE DESIGN, CONSTRUCTION, MAINTENANCE OR OPERATION OF THE PEABODY NUCLEAR POWER PLANT IS NOT AUTHORIZED BY THE GENERAL ELECTRIC COMPANY.

Automatic Switch Co.

FLORHAM PARK, NEW JERSEY

Printed in U S A

PRODUCTION SPECIFICATION

BILL OF MATERIAL

AE	CH
CA	AI
AL	EL
AM	EM
AN	EN

FVP-176-816

PAGE 3 OF 4 PAGE

CHG LTR

12	K		
72032	H		
714	G		
70577	F	1010	R
6029	E		
69132	D		
68347	C		
67826	E		

CATA. NO. HV 176-816-1 HV 176-816-2

SHOP ORDER NO

BULL. NO. HV 176-816

NO OF PARTS LIST PER ASSY

1

ASSEMBLY REF
HVA-176-816

ER NO

CHG LTR

ER NO

CHG LTR

FVP-176-816

ITEM	PART NUMBER	CHG LTR	NOTE	MATERIAL	PART NAME	QUANTITY		
						UNIT	RECD	DELVD

NOTES:

1. IN SOLENOID ASSEMBLY A, OMIT GROUND SCREW AND SUBSTITUTE THE FOLLOWING:

1C	GV-99-257-1G 115/60	AB		CATA HV 176-816-1 COIL - REMARK TO 115/60	1		
----	---------------------	----	--	--	---	--	--

1C	GV-99-257-25G 115/50	AB		CATA HV 176-816-2 COIL -	1		
----	----------------------	----	--	-----------------------------	---	--	--

1X	FV-172-444-6	C		HOUSING/CONDUIT ASSEMBLY	1		
----	--------------	---	--	--------------------------	---	--	--

	GV-168-736-6	H		STEEL HOUSING	1		
--	--------------	---	--	---------------	---	--	--

	FV-33-103-1	X		ALUMINUM CONDUIT CONNECTION	1		
--	-------------	---	--	-----------------------------	---	--	--

2. IN SOLENOID ASSEMBLY B, OMIT GROUND SCREW AND NAMEPLATE AND SUBSTITUTE THE FOLLOWING:

2G	GV-99-257-1G 115/60	AB		CATA HV 176-816-1 COIL - REMARK TO 115/60	1		
----	---------------------	----	--	--	---	--	--

2G	GV-99-257-25G 115/50	AB		CATA HV 176-816-2 COIL -	1		
----	----------------------	----	--	-----------------------------	---	--	--

2J	FV-172-444-6	C		HOUSING/CONDUIT ASSEMBLY	1		
----	--------------	---	--	--------------------------	---	--	--


	GV-168-736-6	H		STEEL HOUSING	1		
--	--------------	---	--	---------------	---	--	--

	FV-33-103-1	X		ALUMINUM CONDUIT CONNECTION	1		
--	-------------	---	--	-----------------------------	---	--	--

3. QUANTITY AS ORDERED BY CUSTOMER.

ATTENTION:

BEFORE PROCEEDING WITH ANY NEW OR RECURRING ORDERS A REVIEW OF EACH DETAIL PART AND DRAWING WILL HAVE TO BE MADE AND G. E.'S AGREEMENT OBTAINED FOR ANY CHANGE IN THESE PARTS.




STEAM LINE "D"

DETAIL - 1

1-14
 OII
 TO
 TEAM
 JRBINE

D-74
 D

"C" CLASSIFICATION



REFERENCE DOCUMENTS: -


D-302-602


REACTOR RECIRCULATION SYSTEM

NOTES: -

1. STEAM

"C" CLASSIFICATION






SINKENT

DRY WELL

ICAL NON-ADS VALVE EXCEPT FOR FOSID SEE DETAIL-1
R QTY SEE TABLE I (D-302-608)



"C" CLASS

SEE TABLE I P&ID DATA DWG
D-302-608

ELBOW TAP
SEE DETAIL THIS
DWG. (TYP OF 4)

PRIMARY STEAM

PIPING G001

"C" CLASS

SEE NOTE

A

B

C




FIG.

TATION OF SAFETY RELIEF VALVES AND ASSOCIATED

TMENT. F027 SHOULD BE ACCESSIBLE DURING NORMAL

BOILER SYSTEM PROCESS DIAGRAM AND PROCESS DATA G.F.

RUN OF PIPE DOWNSTREAM OF F027 WITH UPSTREAM AND
E TAP TO GIVE AS ACCURATE A PRESSURE MEASUREMENT AS
1964 "STEAM TURBINES" PARAGRAPH 4.74.

TRUMENT SENSING LINE BETWEEN POT (PART 0003) AND THE
TO DRYWELL REFUELING SEAL. THE EXPANSION LEG AND
ALLOW FOR MAXIMUM CHANGE OF VESSEL LENGTH WITH
IPING OR THE SEAL OR DAMAGE TO THE INSULATION AROUND
SHALL BE LOCATED ABOVE THE HEAD VENT CENTER LINE

HALL BE IN ACCORDANCE WITH CURRENT LICENSING PRACTICES.
STRUMENT LINE CONNECTED TO THE REACTOR COOLANT PRESSURE
BE AS FEASIBLE TO THE RCPB. ORIFICE SIZE IS 1/4" AND
E.

ARE TO OPERATED, UNLESS OTHERWISE SPECIFIED.
R VESSEL.

UNLESS OTHERWISE SPECIFIED.

FOR TAG IDENTIFICATION NUMBERS FOR INSTRUMENT, SEE THE

INSTRUMENT INDEX.

-003. FOR SOLENOID IDENTIFICATION NUMBERS, SEE

F VALVES POSITION SWITCHES.

D, AND D ARE D01BA 02, BA013, AND BA004 RESPECTIVELY.

ION INSTALLATION DWGS. D-814-065 AND D-814-066.

RECEIVED

E

F


G


H

S: -


- FOR RECIRCULATION SYSTEM
- ROL ROD DRIVE HYDRAULIC SYSTEM
- WATER CONTROL SYSTEM
- BY LIQUID CONTROL SYSTEM
- FOR PROTECTION SYSTEM
- DETECTION SYSTEM
- SYSTEM
- SYSTEM
- FOR SYSTEM OUTLINE DRAWINGS
- FOR WATER CLEANUP SYSTEM
- FOR ICD
- ATION VALVE INTERFACE CONTROL DRAWING
- ANICAL EQUIPMENT SEPARATION
- TE SHUTDOWN SYSTEM
- TRICAL EQUIPMENT SEPARATION
- I/O LIST
- COOLING SPRAY NOZZLE
- ORMANCE MONITORING SYSTEM
- LCS
- E PANEL DESIGN SPECIFICATION
- FOR RECIRCULATION SYSTEM P AND ID DATA
- PUMP ELEMENTARY
- EAR BOILER PROCESS INSTRUMENT ELEMENTARY
- DESIGN SPECIFICATION
- FOR RECIRCULATION SYSTEM ELEMENTARY
- STEAM SYSTEM
- REHEAT EXTRACTION, AND MISCELLANEOUS DRAINS
- DETECTION SYSTEM
- POOL COOLING AND CLEAN-UP SYSTEM
- FOR RECIRCULATION SYSTEM
- FOR RECIRCULATION SYSTEM
- LEAR BOILER PROCESS DIAGRAM
- UNDANT REACTIVITY CONTROL
- UNDANT REACTIVITY CONTROL
- STEM ELEMENTARY
- CESS INSTRUMENTATION
- SIGN SPEC.

NOTES: -

1. STEAM LINES, ENCLOSED IN BOXES NUMBERED UNLESS OTHERWISE NOTE. TAP IS ON LINE "B" OR "C" UNLESS OTHERWISE NOTE.
2. ALL EQUIPMENT AND INSTRUMENTS SYSTEM NUMBER 221 UNLESS OTHERWISE NOTE.
- 3.
4. SEE DWG. D-302-898 FOR QUANTITY OF EQUIPMENT.
5. LOCATE IN AREA SERVED BY STANBY OPERATION.
6. FOR OTHER MODES OF OPERATION, SEE DWGS. 131C7911 AND 131C7911C.
7.  TO BE CONNECTED INTO THE DOWNSTREAM STRAIGHT LEG IF FEASIBLE. TAPS TO MEET SPEC.
8. AN EXPANSION LEG SHALL BE PROVIDED AT EACH PENETRATION THROUGH THE VESSEL. THE COMPENSATING LEG SHALL BE INSTALLED IN ACCORDANCE WITH SPEC. AC.
9. PROVISION FOR INSTRUMENT LINE SHALL BE INSTALLED AT THE BOUNDARY (RCFB). ORIFICE SHALL BE INSTALLED AT THE BOUNDARY. MAXIMUM NUMBER OF ORIFICES PER PENETRATION SHALL BE TWO.
10. VALVE MOTOR OPERATORS AND PILL BOXES SHALL BE INSTALLED AS CLOSE AS POSSIBLE TO THE VALVE.
11. LOCATE TEE AS CLOSE AS POSSIBLE TO THE VALVE.
12. SEE TABLE 12 AND ID DATA, DWG. D-302-898.
13. ALL INDICATOR LAMPS LOCATED IN THE CONTROL ROOM.
14. FOR CONTROL ROOM, LOCAL OR REMOTE OPERATION SHALL BE INDICATED IN INSTRUMENT INDEX.
15. FOR SOLENOID IDENTIFICATION SHALL BE INDICATED IN INSTRUMENT INDEX.
16. VALVE CONTROL DIAGRAM SHOWN IN INSTRUMENT INDEX.
17. ANNUNCIATOR IS COMMON TO ALL VALVES.
18. COMPUTER POINT I.D. NUMBERS SHALL BE INDICATED IN INSTRUMENT INDEX.
19. FOR PENETRATION NUMBERS, SEE DWG. D-302-898.



- REFERENCE DOI
- D-302-602
 - D-302-872
 - B-208-025**
 - D-302-691
 - D-808-302
 - D-302-964
 - D-302-631
 - D-302-632
 - A62-2050
 - D-302-671
 - B13-2020
 - B21-F022/28
 - A62-4350
 - D-808-301
 - A62-4050
 - C94-4030
 - B13-0020
 - C91-4030
 - E32-1010
 - H22-4010
 - B33-1010
 - B33-1080
 - B21-1050
 - A62-4430
 - B-208-015
 - D-302-011
 - D-302-121
 - D-302-961
 - D-302-651
 - D-302-603
 - D-302-604
 - B21-1020
 - C22-4010
 - C22-0990
 - A62-4070



FOR NUMBER OF SAFETY/RELIEF VALVES & ASSOCIATED PARTS SEE NOTE 4 AND DETAIL STEAM LINE "A"

STEAM LINE "B" & LINE "A" UNLESS (SEE NOTE 1)


SEE NOTE STEAM LINE "B"

STEAM LINE "C" & LINE "A" UNLESS (SEE NOTE 1)


SEE NOTE STEAM LINE "B"

STEAM LINE "D" & LINE "A" UNLESS (SEE NOTE 1)

PROVIDE A SEPARATE DISCHARGE LINE FOR EACH SAFETY/RELIEF VALVE



REACTOR
VESSEL
B13-D003



SEE A62
FOR NOZ:
ORIENTA

LEADER DESIGN
WORK MANAGEMENT

G

RECEIVED

SEP 28 1987

DRAWING CONTROL

NUCLEAR SAFETY RELATED

H

NO	DATE	MADE	CHKD	APPROVALS	
REVISIONS					

DATE ON 1987
EXPIRES ON NOV 17 1987
WORKING COPY

	CONSTRUCTION	
	LIMITED CONSTRUCTION: AS NOTED	
	PRELIMINARY NOT FOR CONSTRUCTION	
	BIDDING PURPOSES	
DATE	RELEASED FOR	BY
	THE CLEVELAND ELECTRIC ILLUMINATING COMPANY	
	PERRY NUCLEAR POWER PLANT	UNIT 1
	PIPING SYSTEM DIAGRAM	
	NUCLEAR BOILER SYSTEM	

DATE ON 1987
EXPIRES ON

VALVES (C & D-10).
REMOVED FE-NO05
(C-7) & RELOCATED
TO (F-7), ADDED
2" LINE (G-9)

NO	DATE	MADE	CHKD	APPROVALS
A	8-9-80	N.Y.	R.B.	[Signature]

READING PA.	GILBERT ASSOCIATES, INC. ENGINEERS AND CONSULTANTS			
DRAFTING		ENGINEER APPROVALS		
MADE T.A.A.	CHECKED [Signature]	ARCHITECTURAL NH	CIVIL NA	STRUCTURAL NA
APPROVAL J.R. Gordon 1-26-87		MECHANICAL R.H. [Signature]	ENVIRONMENTAL NA	NUCLEAR NA
SCALE NONE	04	4548	D-302-6	
DRAWING NUMBER				

GE. DWG. NO. 7623000A

- 17. ANNUNCIATOR
- 18. COMPUTER F
- 19. FOR PENETR

GRAV
CONF
AS OF

SUPPORTING DOCUMENTS:-

- 1. PIPING AND INSTRUMENT SYMBOLS A42-1011
- 2. PRESSURE INTEGRITY OF NUCLEAR COMPONENTS A62-4031

EQUIPMENT



ISS
NOV

ISSU
NOV 0

FOUR (B-6). ADDED PXC (E-1)
 F-7) 3/4" TEST LINES W/VALVES
 FO/9B, C&D, FO/05, C&D @
 (E-F-G-7) 1/2" RDGRG (B-9) @
 MATCH COOR 271E (C-10) DOOR (C-10)

B	REC	JRC	2/8
---	-----	-----	-----

ADDED REDUCERS (E-10)
 ADDED ACCUM. ADD 4 IN
 AREA D-II
 REVISED ACCUM. TANKS
 AND ADDED RDCRS. IN AREA
 B-6 B-9 B-10 & D-10
 ADDED PEN. NO. 4 PLACES
 ADDED CROSS REF. AND INST.
 IN AREA B-4
 REVISED NOTE #4
 DELETED OPERATION
 AND DESIGN DATA.
 ADDED NOTES 12 THRU 16
 ADDED NOTES TO REF.
 ADDED NOTE 16 TO VALVE
 CONTROL DIAGRAM D21
 IN AREA B-6 AND B-8
 REVISED CROSS REF. 5
 TAB. E-F III WAS I IN 2
 PLACES
 ADDED PANEL NO.
 ADDED LIGHTS IN 6 PLACES
 ADDED PIPING SPEC. CHANGES
 REVISED REF. DOCUMENTS
 UPDATED NOTES & REF.
 ADDED LINE SPEC (TYPE 3)
 ADDED REFERENCE TO
 NOTES (TYP. 3). REMOVED
 ARROW (D-9). F025A
 BECAME LOCK CLOSED,
 F0279A BECAME
 NORMALLY CLOSED. ADDED
 LINE SIZE (C-8).
 REVISED DETAIL (H-6)



DETAIL
ELBOW TAP AND ASSOCIAT
(TYP. OF 4)

D020A/GH-5-7)PER EQUIS. JSS 19989-90-1603 B RFX 19354-44-6815	INTERFACE D G H M T R	ADDED P.S. N410(H,J-9,10) ADDED LINE SPEC. AND SIZE (C,D,E-9) ADDED VALVE F587 TO ANNUNCIATORS (C,D-9) REVISED G.E. DWG. NO. (K-1,2) ADDED COMPUTER POINT ELEMENTS (B-E-10) (C-11) REMOVED "D-302" IN 17 PLUS ADDED "BIRD BREAK-D" (B-9) REMOVED REDUCER (B-8,11) ADDED DETAIL-1 (A,B-1,2,3,4) ADDED (2) REDUCERS (C-4,5) ADDED NOTES 17, 19, 419 ADDED COORDINATES (D,E-13) G-12 (C-4). REMOVED (2) T.E. CONN. (E, F-7) ADDED MATCH MARKS FOR DWG -342 & COORD. IN AREA (F, G-7,8) 5. M.F.S. DOOR WAS DOOR 2 B. 8. 2. 4 DOOR WAS DOOR 2 B. 8. 2. 4	ADDED REDUCER (C-5) ADDED VALVES F556, A, B, C, D REVISED AREA R, C-4 ADDED VALVE F527A, B, C & D (C-5), E, F, 7) CHANGE B13-2020 TO B13-D003 (D-2), MATCH COORD. DWG NO'S 121 TO 341 C (G-8 (D-6), LINE SIZE 3/8) TO 1/2" (B-8 (15)) (COORD. MATCH DWG, NO. D-302-914 TO D-302-914 REMOVED 2-
---	---	--	---

POINTS (B-94D-6) PER DCN
 366 & ECN 29721-86-
 2923/-, CHANGED NOTE
 3 PER ECN 28396-86-
 2195/-



S.M.J.C
 B.P.P.X
 INTERFACE

BUILT FOR SYS. 1B13
 1B21A, B, C & 1B11B SCOPING
 PKG. ADDED 3'x2' REDUCER
 (C-12) PER ECN 16165-44-
 5131/C. ADDED PT N733,
 PT N734, ERIS PTS. EA360,
 EA361, & PIPING CLASS
 BREAK; VALVES F527B,
 F527D, F556B & F556D WERE
 SHOWN NORMALLY CLOSED,
 (E, G-8, 7) PER ECN
 26630-48-158/A.
 DELETED ZS N437, ZSN478
 COMPUTER POINT &
 NOTE 4 (TYP ~ 3 PLACES)
 (A, B, C, E-11, 10, 2, 1) PER ECN



25691-86-1050
 STEAM LINE 'D'
 WAS 'A' (C-2).

S.M.J.C
 B.P.P.X
 INTERFACE

ADDED POSITION INDICAT-
 ING SWITCHES 3 PLACES
 (C-6, C-8) & REV'D G.E. DWG.
 NR PER IDCI 883. ADDED
 SAFETY CLASSIFICATION
 TO PIPING AT (B-E-13, B-12)
 PER ECN 16165-44-5131.



SEE D-30.
BALANCE OF



DIVISION ORIENTATION
OF THE VESSEL
INSTRUMENTATION
& NOZZLES
(SEE A62-4350 & H22-4010)

AS-BUILT PER DCN 1841		J	28 87	M P H	HRK for CLP	DE
AS-BUILT PER DCN 1691 REMOVED NOTE 5, COORDINATE: E-8		H	8 87	JDM	RJT	INTERFACE
DESIGN CONFIGURATION MANAGEMENT AS-BUILT PER DCN 751 REF. ECN 2995-06-3105/- ADDED REFERENCE DOC- UMENTS; COORD. G-5/0; REVISED NOTE B & DELETED MATCH MARK IDENTIFICA- TION COORD. E-13		G	18 87	DLE JDM	RJT	INTERFACE
AS-BUILT REVISED		K. ANDER ERIC DAINTC (N.D.F. 12)				

H

5'-3"

W.P. EL 630'-
W.P. EL 628'-

J

3'-3"

MATCH LINE - SEE
AUX. PLAN "C"
DWG D-304-342

W.P. EL 630'
W.P. EL 628'-

K

AX
6

X-1-

H

5'-3"

W.P. EL 630'-
W.P. EL 628'-

3'-3"


MATCH LINE - SEE
AUX. PLAN "C"
DWG D-304-342

W.P. EL 630'-
W.P. EL 628'-


AX
6

K

M-r-



ROTATED VALVES F506 & F544E (D-10) TO VERTICAL POSITION PER ECN-18903
 44-649% CHANGED DIMENSIONS (4 PLACES G-10, A-10, B-8) TO ACCOMMODATE AS-BUILT CONDITIONS PER ECN-18660
 44-6336-A. ADDED CONN. WELD DETAIL (A-G, E-3) PER ECN-18926-44-6461-A.
 DELETED PIPE SUPPORT H092 (J-10). REVISED PIPE SUPPORT LOCATION H151 & H187 (D-8) ADDED
 DDC SHEET 11759



D.V.V. RUCK (E-2), PPA-17K
 3/4" B.W. TEE (E-2) 7. JGS
 PER ECN 12997- 8. N/I
 44-3299-A INTERFACE

3	H	7 27	E 84	L K	R D	C S	JET	PPA
---	---	---------	---------	--------	--------	--------	-----	-----

INDICATED TOP OR BOT. LINE ON THE FOLLOWING SUPPORTS H145, H227, H140, H139, H138, H137, H167, H154, H153, H152 & H151. INCORPORATED PIPE SUPPORTS 14 PLACES.

DELETED SUPPORT H099 (D-10), RELOCATED SUPPORT H150 (D-8). PPA-N/I 7. JET 8. N/I INTERFACE

3	G	6 23	C R	B R	R C	JET	PPA
---	---	---------	--------	--------	--------	-----	-----

DELETED NOTE 9 INCORPORATED PIPE SUPPORT LOCATION FOR H189 (B-3), H194 (D-6), H195 (H-7), H211 (D-13), H213 (D-12), H223 (B-14), H226 (D-7) & H227 (D-11), RELOCATED PIPE SUPPORTS H117 (G-11) & H152 (D-8). PPA-N/I 7. JET 8. N/I INTERFACE

3	F	5 33	T R	C R	D S	JET	PPA
---	---	---------	--------	--------	--------	-----	-----


REVISED 4" PIPING (D, E-11). ADDED LINE SPECS DI-1 & DI-2 @ (J-10), (C-1). ADDED VALVES F544J (J-10), F544A (G-10), F544N (F-10) & F544E (D-10). REMOVED LINE SPEC DI-2 & DI-1 AREA (C-2).


REVISED PIPE SUPPORT H104 AREA (F-10). PPA J T Z 7. JET 8. N/I

1) 5" M LINE VALVES
 3) 8" M LINE VALVES
 3) 4" S.W. CONN. (TYP 4)
 3) 4" S.W. CONN. (TYP 4)

PLAN ABOVE EL. 620'-6"

SCALE: 1/2" = 1'-0"





- REFERENCES: -
- D-302-341 MSIV LEA
 - D-302-342 MSIV LEA
 - D-302-605 NUCLEAR

FVA #
4871.44.582
6202.44.940
7898.44.1265

THIS DRAWING CONTAINS TECHNICAL INFORMATION FOR THE INCORPORATION OF THE CONTROL SYSTEM

& 614'-6"

FVA #
6066.44.906
8144.81.214

ECN #	REV
20234.44.7150	-
26176.44.8172	-
26177.45.2178	-

E 172	CB	JDS	JRG	SG	REMOVED HOLD ON BLOWER FLEX CONN.(B-II) REV PIPING IN AREA(B-II)
					PPAJTZ 7 JET 8.RPM=
					INTERFACE
					REROUTED 2" GI-2 PIPE AREA (D-10). REVISE SECTION 7-7.
					INTERFACE
					ADDED 8" PIPING (D-10). PIPE WAS 2" (C-1). ADDED DIM (C-1) INCORPORATED PIPE SUPPORT LOCATIONS. REMOVED HOLDS ON MCV-F001 A.E.J,N AND MCV-F002 A.E,J,N (D, M,J-10,11); MCV-F003 & F009 (D-7). REVISED 4" PIPING (D-5-11). NOTATED F506E (D-9).
					INTERFACE
					DWG REDRAWN & RECHECKED. REVISED GENERALLY REFERENCED TO REMOVE HOLD PLACED ON DWG BY DCN-2-633
					INTERFACE
					REMOVED 14.5" DIA/E PLANNED

IV LEAKAGE CONTROL

JUN 25 1986
DRAWING CONTROL

PRINTED
JUL 05 1986

CONTROL SYSTEM - FLOW DIAGRAM
CONTROL SYSTEM - FLOW DIAGRAM
- FLOW DIAGRAM

RECORD AS BUILT
This Dwg. May Not Reflect
The s Built Condition.
As Built information is
available in The Records
Management System

CEI CONTROL				
REV	DATE			CEI
K	6/28/86			GA
ADDED STAMP FOR DESIGN RESPONSIBILITY TRANSFER TO CEI				7 JGS for 8 N.I. INTERFACE
J	1-3-86	H R M	B P	JGS for RJS
NO	DATE	MADE	CHKD	APPROVALS
REVISIONS				

NUCLEAR SAFETY RELATED

~~NOT AS JUST
NO DOCUMENTS
AND
NOT BEEN
THE DRAWING
PORTED ONTO
DETAIL AS~~

NG UNDER
CONTROL AS
K

1/24/79	CONSTRUCTION			2 PK ONE REF
	LIMITED CONSTRUCTION: AS NOTED			
	PRELIMINARY NOT FOR CONSTRUCTION			
	BIDDING PURPOSES			
DATE	RELEASED FOR		ENGR.	
THE CLEVELAND ELECTRIC ILLUMINATING COMPANY				
PERRY NUCLEAR POWER PLANT			UNIT 1	
PIPING			SYSTEM E32	
MSIV LEAKAGE CONTROL SYSTEM				
AUX BLDG EL. 620'-6" AND EL. 614'-6" - PLAN AND SECTIONS				
READING PA.	GILBERT ASSOCIATES, INC. ENGINEERS AND CONSULTANTS			
DRAWING		ENGINEER APPROVALS		
MADE	CHECKED	ARCHITECTURAL	CIVIL	STRUCTURAL
TRESSLER	OR	1. NA	2. NA	3. NA
APPROVAL		MECHANICAL	ENVIRONMENTAL	7. NUCLEAR
J.R. Gordon		5. NA	6. NA	7. NA
DATE		DATE		
7-16-86		7-16-86		
SCALE	AS NOTED	04	4549	D-304-341
REV		K		
DRAWING NUMBER		REV		

VALVES. ADDED DIM. FOR
FI-R354 (C-4).
CORR DCN. 1-526
REVISED LOC. & DIMENSIONED
12 VALVES AS SHOWN.
CORRECTED PIPE FOR
THERMAL ANALYSIS AND
MISILE PROTECTION.

17 JUN 77

JPS	JRG	M	APPROVALS
A	M	M	APPROVALS
DATE	DATE	DATE	DATE

ITEM


PLSD.

D


E

F

G




MC FO
MC FO



28B

0'-3 3/4"

28D



3
-3 3/4"

STEAM LINE "A"



2'-0"

1'-6"

W.P. EL. 2001.3"

FL EL 620'-6"

H155

SLOPE DN

H201
H202

H158

H157

H199

H200

2" DI-2

H206

H205

2" DI-2

H203
H204

2 1/2" DI-2

H160

H159

H210
H209

H208
H207

2" DI-2


2 1/2" x 2" RDCR
(TYP 4)

SLOPE DN

H196

CO
TH

CO
DW
S



NOTES: -

1. A. PIPING IS SAFETY
2. B. PIPING IS SEISMI
3. FOR PIPE MATERIAL, SP-527-4549-00 (SAF
4. FOR INSULATION, SEE SP-354-4549-00 OUTS
5. FOR WELD END DETAIL
6. ALL VENT AND DRAIN WITH CAF.
7. SMALL PIPING FOR DR. DIAGRAMMATICALLY. MUST PROVIDE REQUIR
8. NO ALLOWANCE FOR WE.
9. THIS DRAWING TO BE

REFERENCES:


- D 22-341 - FLY LEAKAGE
- D 22-341 - FLY LEAKAGE
- D 22-341 - FLY LEAKAGE

WELD DETAIL "G"
 DWG. (A-6)

2 1/2" x 2" RDCR
 SLOPE

DI-1

WELDED ON
 304-501
 3-3 (J-11)



DETAIL "E"

SCALE: NONE

AS INDICATED.
 CATEGORY I.
 SPECIFICATION SP-350-4549-00 (NON-SAFETY),
 LINE CLASS AS INDICATED.
 SPECIFICATION SP-353-4549-00 INSIDE CONTAINMENT AND
 CONTAINMENT.
 SEE GAI DWGS. D-301-001 (NON-SAFETY), D-301-601 (SAFETY).
 DESIGNED TO HAVE T.O.E. (THREAD ONE END) NIPPLE AT THE OUTLET END,

FOR SAMPLE AND INSTRUMENT CONNECTION LINES, IS SHOWN
 THE INSTALLATION OF VALVES AND OTHER APPENDAGES, CONTRACTOR
 TO PROVIDE CLEARANCE FOR INSULATION.

IN CONJUNCTION WITH DWGS. D-304-342 AND D-304-343

RECEIVED
 JUN 25 1986
 DRAWING CONTROL

PRINTED
 JUL 05 1986

CONTROL SYSTEM - FLOW DIAGRAM
 CONTROL SYSTEM - FLOW DIAGRAM
 FLOW DIAGRAM

RECORD AS BUILT
 This Drawing May Not Reflect
 The As Built Condition.
 As Built Information Is
 Available in The Records
 Management System

CEI CONTROL			
REV.	DATE		CEI
K	6/28/86		[Signature]
ADDED STAMP FOR DESIGN RESPONSIBILITY TRANSFER TO CEI			7 JGS For 8 N.I. INTERFACE.
J	3/2/86	B/P	[Signature]

E



F

G


H

A

B


C

D



6"

AX
D



CONNECTION
SCALE:

ϕ E32-COO1

SUCTION
L 621'-2"

E32-COO2F

DISCHARGE
L 621'-2"
O4-343

13'-0"

8'-0"

5'-11 1/2"

3'-2 1/2"

1'-1"

2'-6"

7'-10 1/2"

5'-4 1/2"

3'-0"

3'-0"

ABOVE
LAN "D"
O-343 (A-12)

2'-10"

H163 EL.
626'-10 5/8"

THIS DWG.

1) 2 1/2" 2" 2 1/2"

2) H137(TOP)
H183(BOT)

W.P. EL. 622'-11 1/4" (TOP)

W.P. EL. 619'-4 1/4" (BOT)

H167(TOP)

H154(TOP)

H184(BOT)

SLOPE


H150(TOP)

H188(BOT)

H187(BOT)

H151(TOP)

H185(BOT)



VALVE BODY OF B21-F02B A,B,C,D,

SMOOTH BLENDED
TRANSITION, NO
UNDERCUT

WELD DETAIL "G"

NONE


AX
A

W.P. EL. 628'-10"

2 1/2" - D1-2

EL 624'-1"

W.P. EL 623'-2"



SECTION 1

SCALE: 1/2" = 1'

VALVE BODY

TRIM CONNECT
& PIPING TO S

2" P.E. PIPE CC

2"-6000# S.W.
COUPLING



W.P. EL 629'-

CONTINUED O
WG D-304.

AX
4

3'-6"

PT
405




KEY PLAN

G1-2

5

P. EL 623'-2 1/8"




1 1/2" S.W. CONN.

EL. 629'-8"

ORIENTATION OF PIPING
AND VALVES VARY
(SEE PLAN VIEW)

DETAIL "F"

SCALE: NONE





2" DI-2
SLOPE

12" X 1 1/2" RDCR
INSERT


MANAGEMENT									
HR	HR	H	DA	HR	L	DLE	MJC	HR	HR
AS-BUILT WITH CHG: DCP 85-2088/CUN 615 WAS INC. IN REV. E. REVISED REF. DWG. NO. (F,G,H-10,11)(G-13) & ADDED DWG. MATCH- MARK (G-13)	AS-BUILT REVISED ADDED VALVE OF-807(E-10), DWG. REF. (J-9) & PIPE SIZE (D-12) PER CUN 1533/-, 2268/- & 2787/-	5. MJC 8. PAX INTERFACE	5. MJC 8. PAX INTERFACE						
VALVE FT81 (H-7) N 17086-45-957/-; RELIEF VALVE F806 PER ECN 28306- 89/-; ADDED ERIS TS (H-8) PER ECN 1-86-2188/-									


- F-6
352-761
TO TEST POINT
- F-5
352-24:
- B-6
352-761
- G-4
352-24:





FOR CONTINUATION OF D-302-605 (B-11) (TYP II F)





TURBINE POWER COMPLEX

STEAM TUNNEL

DRYWELL WALL PEN.# PRB 3050

SET @ 65 PSI
SEE WOOLLEY
DWG # 37974
PEN. DRYWELL
PERSONNEL
EL. 603'-1 1/2"

AIR SUPPLY TO
ACCUMULATORS
IN STEAM TUNNEL


Y TO ACCUMULATORS IN DRYWELL




FOR CONTINUATION SEE

D-302-605 (B-7) (TYP 4 PLACES)

FOR CONTINUATION
D-302-605 (B-5)




ADDED J943 FJ944 (D-2) PER ECN 25370-45-2036-4	ADDED D0025 (G-11) PER ECN 20745-44-7262A-	ADDED D0026 (H-11) PER ECN 20661-44-7249 A-	ADDED VLV-F800 PER ECN 3921-86-3354-	ADDED F805 D0025-7) PER ECN 2531-45-1899 A/A	FOR VALVES	801, F802 & 3/4" TIE-IN (G-11) PER ECN 20383-45-1625, RE- LOCATED 3/4" TEST CONNEC- TION (G-10), RELOC.	LINE W/MATCH MARK 5 JSS R(H-10), 3/4" LINE W/ MATCH POINT (F)(F-9) INTERFACE	FOR VALVES	2 F703, F703 AND RE- STED PIPING (E-10, 11) PER CN 10891-45-740 ADDED OTE (H-8) PER ECN 16775- 6-279, ADDED ERIS POINTS PER IDC1 B26 , H-11), (G-9) AND (K-9, 10, 11) DELETED ACCUMULATOR 1U (J-9) ADDED AMERICAN T410 (B-12)
---	---	--	---	--	---------------	--	--	---------------	--



NOTATION SEE
 5-5 (TOP 4 PLACES)

40 (J-7) ADDED	MANIFOLD J412 (B-13)	5 LEG	INTERFACE	HP R
ADDED COAN	B-814	B-814		
'C-8) PER IDCI				
477				
(C)	RSB	RSB		
IS-BUILT FOR SYS. P52A+B				
ADDED VALVE F620				
(E-5) ADDED VALVES OF 77				
(OF 780 PER ECN				
3345-45-473/A(4-8)				
ADDED VALVE NUM-				
SER OF 612 (D-10)				
B	RSB	RSB		
14	83			

AUXILIARY BOILER ROOM



RECEIVED
DRAWING CONTROL

NOTES:-

1. INSTRUMENT AIR DISTRIBUTION MANIFOLDS ARE INDICATED BY LETTER "J" FOLLOWED BY THREE DIGITS.
2. AIR DISTRIBUTION MANIFOLD ASSIGNMENTS ARE SHOWN ON VARIOUS S-809 SERIES DRAWINGS
3. ENTIRE SYSTEM IN ACCORDANCE WITH LINE SPECIFICATION M9-4 EXCEPT WHERE NOTED OTHERWISE.
4. FOR OPERATING DATA AND DESIGN DATA, SEE DWG. 302-241

DRAWING UNDER DESIGN
CONFIGURATION MANAGEMENT
AS OF REV. L

NO	DATE	MADE	CHKD	APPROVALS
REVISIONS				

SAFETY RELATED

CONSTRUCTION		
LIMITED CONSTRUCTION: AS NOTED		
PRELIMINARY NOT FOR CONSTRUCTION		
BIDDING PURPOSES		
DATE	RELEASED FOR	ENGR.

ISSUED ON 04 1987
EXPIRES ON NOV 17 1987
WORKING COPY

THE CLEVELAND ELECTRIC ILLUMINATING COMPANY

PERRY NUCLEAR POWER PLANT UNIT 1

PIPING SYSTEM DIAGRAM P52

INSTRUMENT AIR

19c Jack	INTERFACE	E F M
AS-BUILT	M J C	APPROVALS
PER CUN 85231	M P H	NO DATE MADE CHKD
DCP 850067C.	N 87	NO DATE MADE CHKD APPROVALS




READING JAL	GILBERT ASSOCIATES, INC. ENGINEERS AND CONSULTANTS				
DRAFTING		ENGINEER APPROVALS			
MADE Bl-t	CHECKED RNJ	ARCHITECTURAL 1 NA	CIVIL 2 NA	STRUCTURAL 3 NA	ELECTRICAL 4 NA
APPROVAL J.R. Gordon		MECHANICAL 6 NA	ENVIRONMENTAL 7 NA	NUCLEAR 8 NA	OTHER 9 NA
DATE 9/17/79		DATE 9/23/79			
SCALE 04		0549		D-302-243 N	


G
H
J
K



D

E



F









AUXILIARY BLDG.







E
F
G

RECEIVED
MAY 19 1961
DRAWING CONTROL

NOTES:-

1. INSTRUMENT AIR DISTRIBUTION MANIFOLDS ARE INDICATED BY LETTER "J" FOLLOWED BY THREE DIGITS.
2. AIR DISTRIBUTION MANIFOLD ASSIGNMENTS ARE SHOWN ON

CIRC. WATER PUMP HOUSE

EMERG SERV. WATER

SEE DWG.
D-816-402

SEE DWG.
D-816-403

J409
621'-6"

J411
586'-8"

520'-4"
M9-4

A

B

SERVICE BLDG

DIES

304-488

INST.
LAB

OF779

OF780

CALIB.
ROOM

304-488

340-02

OF799
METROLOGY LAB

J412
620'-6"

2"

OF595

2"

J430
675'-6"

C

2"

A

B

C

JMP HOUSE

SERV. WATER PUMP HOUSE

SEE DWG.
D-816-401

J401
581'-4"




520'-4" M9-4

520'-4" M9-4

GENERATOR BLDG


CONTROL COMPLEX




FUTURE VOLUME
REDUCTION FACILITY


LATER

RADWASTE
BLDG.



OFF GA
BLDG





FG18

2"

3"

NCES: -

- 2-082 FEEDWATER SYSTEM N27
- 2-182 TURBINE PLANT SAMPLING SYSTEM P33
- 2-241 SERVICE AND INSTRUMENT AIR SUPPLY SYSTEM P51, P52
- 2-605 NUCLEAR BOILER SYSTEM R21
- 2-675 REACTOR WATER CLEAN-UP FILTER DEMINERALIZER SYSTEM G36
- 2-730 LRW - WASTE COLLECTOR FILTER AND FLOOR DRAINS SYSTEM G50
- 2-742 LRW - WASTE EVAPORATOR CONDENSERS SYSTEM G50
- 2-752 OFF-GAS SYSTEM N64
- 2-754 OFF-GAS SYSTEM N64
- 2-871 CONTROL ROD DRIVE HYDRAULIC SYSTEM C11
- 2-241 SERVICE AND INSTRUMENT AIR SUPPLY SYSTEM P51, P52
- 2-243 INSTRUMENT AIR SYSTEM P52
- 4-476 INSTRUMENT AIR SYSTEM P52 - INTERMEDIATE BUILDING
- 4-480 INSTRUMENT AIR DISTRIBUTION SYSTEM P52 - CONTROL COMPLEX
- 4-488 INSTRUMENT AIR SYSTEM P52 - DIESEL GENERATOR AND SERVICE BUILDING
- 4-761 PENETRATION PRESSURIZATION SYSTEM P53 - REACTOR BUILDING
- 4-762 PENETRATION PRESSURIZATION SYSTEM P53 - REACTOR BUILDING
- 4-762 PENETRATION PRESSURIZATION SYSTEM P53 - REACTOR BUILDING
- 1-420 FUEL OIL STORAGE TANK - LEVEL INSTRUMENTATION
- 4-438 COOLING TOWER BASIN - LEVEL INSTRUMENTATION
- 6-401 INSTRUMENT AIR TUBING INTERCONNECTION DIAGRAM - SERVICE WATER PUMP HOUSE
- 3-402 INSTRUMENT AIR TUBING INTERCONNECTION DIAGRAM - CIRCULATING WATER PUMP HOUSE
- 6-405 INSTRUMENT AIR TUBING INTERCONNECTION DIAGRAM - EMERGENCY SERVICE WATER
- 3-409 INSTRUMENT AIR TUBING INTERCONNECTION DIAGRAM - MISCELLANEOUS BUILDINGS

A

B

C