	NAME AND POST OF THE OWNERS OF	THE RESIDENCE OF THE PROPERTY
LDHR	REV 04 (MC)	AP-404

LOSS OF DECAY HEAT REMOVAL

1.0 ENTRY CONDITIONS

IF the running DHR train is lost.
THEN use this procedure.

2.0 IMMEDIATE ACTIONS

NOTE

There are no immediate actions for this procedure.

9901220327 990113 PDR ADOCK 05000302 PDR

Approved by MNPO MINE ON FILE) Date 1/12/99

AP-404 PAGE 1 of 123 LDHR

3.0 FOLLOW-UP ACTIONS

3.4 __ EXIT this procedure.

	ACTIONS		DETAILS
3.1	Notify personnel of plant conditions.	•	
		•	Plant operators
		•-	NSM (evaluate plant conditions for potential entry into the Emergency Plan)
3.2	<u>IF</u> either of the following exist:		
	Rx vessel level is < 132 ft		
	No DHR trains are available		
	THEN GO TO Step 3.5 in this procedure.		
3.3	Start available DHR train.	•	IF A DHR Train will be started. THEN PERFORM Enclosure 1. Starting A Train DHR, in this procedure.
		•-	IF B DHR Train will be started, THEN PERFORM Enclosure 2, Starting B Train DHR, in this procedure.

ACTIONS

DETAILS

STATUS

Either of the following conditions exists:

- Rx vessel level is < 132 ft.
- No DHR trains are available.
- 3.5 ___ Evacuate the RB.

 1 ___ Depress "RB EVACUATION" push button.

 2 ___ Notify personnel over PA.

 3 ___ Repeat PA announcement.
- 3.6 _____ IF in Modes 5 or 6. THEN establish containment closure.
- CONCURRENTLY PERFORM the following:
 - Enclosure 3, Containment Closure in Modes 5 or 6, in this procedure.
 - Penetrations Weekly Check During Refueling Operations.

ACTIONS

DETAILS

3.7 Werify RCS level is \geq 130.2 ft.

_____IF RCS level is < 130.2 ft.
THEN raise RCS level.

1 Determine RCS makeup sources:

___ RCBTs

___ SF pools

___ BASTs

___ BWST

2 ___ Align an available makeup source.

3 ___ Start addition to RCS to achieve \geq 130.2 ft.

AP-404 REV 04 (MC) PAGE 8 of 123 LDHR

ACTIONS

3.8	 IF SW cooling is available.	
	THEN ensure SW cooling	to
	RB cooling units.	

DETAILS

1 Ensure at least 1 Emergency is running:	SW Pump
SWP-1A	
SWP-1B	
2 <u>IF</u> an Emergency SW Pump available. <u>THEN</u> start SWP-1C	is <u>NOT</u>
3 Ensure at least one Emergency Pump is running:	y SW RW
RWP-2A	
RWP-2B	
4 <u>IF</u> an Emergency SW RW Pu <u>NOT</u> available, <u>THEN</u> start RWP-1	mp is
5 Ensure CI valves to RB cooli are closed:	ng units
SWV-151	
SWV-152	
SWV-355	
6 Ensure SW valves to RB cooli are open:	ng units
SWV-353	
SWV-354	

	pri	7	*	-		-
A		1	1	U	N	5

available. THEN ensure CI is operating and aligned to RB cooling units.

DETAILS

2 SW valves to RB cooling units are closed:

SWV-353

SWV-354

3 CI valves to RB cooling units are open:

SWV-151

SWV-152

SWV-355

3.10 ___ Ensure proper RB cooling unit operation.

- IF ES has NOT actuated, THEN ensure both ES selected RB cooling units are running in slow speed.
- IF ES has actuated. THEN ensure only 1 ES selected RB cooling unit is running in slow speed.

	200,00	-	*	m	6.1	-
- 70.			3.1		16. I	ĸ.
- 64			3.1		TM	- 75
A	\u		A.	w	17	4

3.11 $\underline{\hspace{0.5cm}}$ IF both DHR trains are 1 Ensure both DHPs are stopped: NOT available. THEN isolate DHR from RCS and GO TO Step 3.15 in this procedure.

DETAILS

DHP-1A

DHP-1B

2 Close the following valves:

DHV-41

DHV-3

DHV-4

DHV-5

DHV-6

3 ___ **GO TO** Step 3.15 in this procedure.

3.12 WHEN RCS level is ≥ 130.2 ft. THEN start available DHR train.

- IF previously running DHR train will be restarted, THEN PERFORM Enclosure 4. Venting DHR, in this procedure.
- IF A DHR Train will be started, THEN PERFORM Enclosure 1. Starting A Train DHR, in this procedure.
- IF B DHR Train will be started, THEN PERFORM Enclosure 2, Starting B Train DHR, in this procedure.
- is filled and vented as required.
 - Ensure shutdown DHR train Notify PPO to CONCURRENTLY PERFORM Enclosure 4, Venting DHR, in this procedure.

AP-404	REV 04 (MC)	PAGE 13 of 123	LDHR

ACTIONS

DETAILS

3.14 ___ EXIT this procedure.

<u>ACTIONS</u>

3.15 ___ Ensure available cooling method and GO TO applicable step.

DETAILS

Cooling Method and Step	Criteria
OTSG 3.16	<pre> RCS filled and vented PZR Htrs available OTSG FW available TBVs or ADVs available OTSG integrity exists Letdown available</pre>
Fill fuel transfer canal 3.36	Rx vessel head removed Fuel transfer canal integrity exists
HPI 3.51	HPI pump with suction from BWST available RCS vent path available
LPI 3.70	LPI pumps with suction from BWST available
CFTs 3.79	CFT PRESS < RCS NDT CFT level exists
Flood RB sump-LPI 3.84	RB sump can be flooded LPI pump with suction from RB sump available
Gravity feed 3.104	- RCS vented to atmosphere - BWST level > Rx vessel - Flow path from BWST to RCS available

AND DESCRIPTION OF THE PERSON	The same of the sa	NATE AND THE PERSON NAMED AND ADDRESS OF THE PERSON NAMED AND THE PERSON	manuscon man
AP-404	REV 04 (MC)	PAGE 17 of 123	LDHR

AP-404 REV 04 (MC) PAGE 18 of 123 LDHR

ACTIONS

DETAILS

S	~p		-	pro j		-
٧.		- 71	м			ĸ.
. ``	- 1	- 54		п		-31
~			ъ.		w	~

OTSG cooling is available.

- 3.16 ___ Ensure level in available OTSGs is at or trending towards > 90%.
- Establish FW flow to available OTSGs:
 - _____IF_EFP-1 is designated pump. THEN start EFP-1
 - THEN PERFORM EOP-14, Enclosure 7, EFP-2 Management, and start EFP-2
 - IF AFW is designated feed source,
 THEN PERFORM EOP-14, Enclosure 10, Alternate OTSG Feedwater Supply.
 - ____<u>IF</u> MFW is designated feed source, THEN PERFORM EOP-14, Enclosure 8, MFW Restoration.

See Table 1

- 3.17 <u>IF</u> TBVs are <u>NOT</u> available. <u>THEN</u> fully open ADVs for available OTSG.
- 3.18 ____ IF condenser vacuum exists.

 THEN fully open TBVs for available OTSG.
- 1 _____IF MSIVs are closed. THEN PERFORM EOP-14. Enclosure 5, MSIV Recovery.
- 2 __ Fully open TBVs.

ACTIONS

DETAILS

exist. AND a bubble is desired. THEN begin PZR heatup.

2 ___ Control PZR heatup rate < 100°F/hr.

3 ___ CONCURRENTLY PERFORM EOP-14. Enclosure 15, EOP Temperature Log (PZR TEMP).

3.20 IF a PZR steam bubble exists. THEN use PZR Htrs to maintain adequate SCM.

See Table 2

3.21 ___ IF makeup and letdown are in service, THEN GO TO Step 3.25 in this procedure.

ACTIONS

3.22			s available,
	THEN	place in	service.

DETAILS

	e the following to determine straints:
_	Scheduled maintenance activities
	_ Equipment Clearance Log
_	_ Equipment Out of Service Log
se Pu	NCURRENTLY PERFORM applicable ctions of OP-402. Makeup and rification System, to establish e following:
_	Suction flow path from MUT to suction of selected MUP
	- Recirc flow path from selected MUP to MUT
_	_ Selected MUP lube oil system available
_	Normal makeup flow path from selected MUP to RCS

AP-404 REV 04 (MC) PAGE 24 of 123 LDHR

	m	T	*	~	4 1	-
73	1	1	A.	w	13	1

3.23 ____ IF at any time, MU system alignments have been verified.

THEN start selected MUP.

DETAILS

- 1 ___ Ensure selected MUP cooling water system is aligned and operating.
- 2 Ensure selected MUP lube oil is properly aligned:
 - ___ Main lube oil pump in normal after start
 - Backup lube oil pump in normal after stop
 - Main and backup gear oil pumps selected to "AUTO"
- 3 Start selected MUP:
 - ___ MUP-1A
 - MUP-1B
 - ___ MUP-1C
- 3.24 ___ Ensure letdown flow is established and PZR level maintained.
- CONCURRENTLY PERFORM EOP-14, Enclosure 4, RCS Letdown Recovery.
- 3 ___ Maintain PZR level < 125 in.

Applicable carry-over steps:

3.23 IF MU system alignments have been verified, THEN start a MUP.

ACTIONS

DETAILS

 $\frac{1}{1}$ at any time, PZR TEMP $\frac{1}{1}$ Control RCS PRESS using PZR reaches $\frac{1}{1}$ Htrs. RCS PRESS.

THEN establish a PZR 2 Begin lowering PZR level to bubble. 2 Begin lowering PZR level to 100 in (80 to 120 in).

3.26 ____ IF RCP restart is NOT ____ CONCURRENTLY PERFORM EOP-14. desired. Aux spray and GO TO Step

THEN establish high PRESS Enclosure 13. High PRESS Aux Spray and 60 To Steel

3.35 in this procedure. 2 ___ GO TO Step 3.35 in this procedure.

3.27 WHEN MU system is in service. THEN ensure seal injection flows are > 3 gpm for each RCP.

3.28 ___ Determine which RCPs will be started.

- RCPs should be started in RCS loop with available OTSG.
- RCP-1B is preferred for maximum PZR spray capability.

3.29 __ Establish RCS PRESS for desired RCP combination.

> See OP-103B, Plant Operating Curves.

Applicable carry-over steps:

3.25 IF PZR TEMP is Tsat for RCS PRESS, THEN establish a PZR bubble...

ACTIONS

DETAILS

3.30 ___ Ensure RCP lift oil pump is operating for selected RCPs.

3.31 __ Ensure RCP start permissives are satisfied.

3.32 <u>WHEN</u> adequate RCP NPSH exists, THEN start 2 RCPs.

RCP-1A
RCP-1C
RCP-1B
RCP-1D

Applicable carry-over steps:

3.25 IF PZR TEMP is Tsat for RCS PRESS, THEN establish a PZR bubble...

ACTIONS

DETAILS

- Monitor operating RCP computer groups:

RCP	GROUP
RCP-1A	78
RCP-1B	79
RCP-1C	80
RCP-1D	81

Notify SPO to monitor RC-190-LI for RCP oil leakage (119 ft IB by East door).

RCP	UPPER CHANNEL	LOWER CHANNEL
RCP-1A	#1	#2
RCP-1B	#3	#4
RCP-1C	#5	#6
RCP-1D	#7	#8

- 3.34 ___ IF operating parameters are normal. THEN stop operating RCP lift oil pumps.
- 3.35 ___ WHEN DHR system is available, THEN notify TSC for additional guidance and EXIT this procedure.

Lawrence and the second			THE RESIDENCE OF THE PARTY OF T
AP-404	REV 04 (MC)	PAGE 31 of 123	LDHR

ACTIONS

DETAILS

STATUS

- Rx vessel head is removed.
- Fuel transfer canal can be flooded.
- DH pumps are not running.
- 3.36 ___ IF B DHR train will be aligned for fuel transfer canal fill. THEN GO TO Step 3.44 in this procedure.
- 3.37 ___ Align A DHR train for fuel Close the following valves: transfer canal fill.
 - - DHV-39
 - ___ DHV-42
 - ___ DHV-8
 - · Open the following valves:
 - DHV-34
 - DHV-5
- 3.38 ___ Start gravity fill from Throttle DHV-110 to maintain Tincore BWST.
 - < 200°F.

See Table 3

AP-404	REV 04 (MC)	PAGE 33 of 123	LDHR
--------	-------------	----------------	------

ACTIONS

DETAILS

CAUTION

Minimum level in BWST for DH pump operation is 4.5 ft.

- 3.39 IF DHP-1A is available,
 AND increased fill rate is desired,
 THEN start DHP-1A and required cooling pumps.
- 1 _ Select DHV-110 controller to "AUTO" and set for \leq 1500 gpm.
- 2 ___ Start DCP-1A
- 3 __ Start RWP-3A
- 4 ___ Start DHP-1A
- 3.40 ___ Monitor fuel transfer canal fill.
- Throttle DHV-110 to maintain Tincore < 200°F.
 - See Table 3
- Monitor DHP-1A for cavitation.
- 3.41 IF at any time, BWST level is \leq 5 ft.

 THEN select BWST Htr control switch to "LOCAL".

Applicable carry-over steps:

3.41 IF BWST level is \leq 5 ft, THEN select BWST Htr control to "LOCAL"...

ACTIONS

DETAILS

3.42 ____ $\frac{\text{IF}}{\text{transfer canal level is}}$ $\geq 158 \text{ ft,}$ $\frac{\text{THEN}}{\text{canal fill.}}$

1 ___ Stop DHP-1A

2 __ Stop DCP-1A

3 ___ Stop RWP-3A

4 __ Close DHV-5

5 ___ Close DHV-34

3.43 <u>WHEN</u> DHR system is available.

THEN notify TSC for additional guidance and EXIT this procedure.

ACTIONS

DETAILS

STATUS

- Rx vessel head is removed.
- Fuel transfer canal can be flooded.
- DH pumps are not running.
- B DHR train will be aligned for fuel transfer canal fill.
- 3.44 ___ Align B DHR train for fuel 1 ___ Close DHV-40 transfer canal fill.

2 Close DHV-43

3 Close DHV-7

4 Open DHV-35

5 ___ Open DHV-6

- 3.45 ___ Start gravity fill from Throttle DHV-111 to maintain Tincore BWST.
 - < 200°F.

See Table 3

CAUTION

Minimum level in BWST for DH pump operation is 4.5 ft.

3.46 ___ IF DHP-1B is available. desired.

AND increased fill rate is

THEN start DHP-1B and required cooling pumps. Select DHV-111 controller to "AUTO" and set for ≤ 1500 gpm.

2 Start DCP-1B

3 ___ Start RWP-3B

4 Start DHP-1B

A	n		4	2	A
A	P	-	41	ы	4
	12		7	~	79

ACTIONS

DETAILS

3.47 ___ Monitor fuel transfer canal fill.

Throttle DHV-111 to maintain Tincore < 200°F.

See Table 3

Monitor DHP-1B for cavitation.

3.48 ____ IF at any time, BWST level is \leq 5 ft. THEN select BWST Htr control switch to "LOCAL".

3.49 _____ $\frac{\text{IF}}{\text{transfer canal level is}}$ $\geq 158 \text{ ft},$ $\frac{\text{THEN}}{\text{canal fill}}$ stop fuel transfer canal fill.

1 __ Stop DHP-1B

2 __ Stop DCP-1B

3 ___ Stop RWP-3B

4 ___ Close DHV-6

5 __ Close DHV-35

3.50 <u>WHEN</u> DHR system is available.

THEN notify TSC for additional guidance and EXIT this procedure.

ACTIONS

DETAILS

S	~		-	48.4	-
		n			N.
		м		8.3	
~	9.1	-		\sim	~

- HPI cooling is available.
- RCS vent path is available.
- 3.51 ___ Isolate the RB sump.
- Select RB sump pumps to "PULL TO LOCK":

___ WDP-2A

WDP-2B

• Close RB sump discharge valves:

___ WDV-3

____WDV-4

3.52 ___ Close waste gas header isolation valves.

WDV-406

WDV-405

3.55

Energize HPI recirc to

sump valves.

ACTIONS	DETAILS
3.53 Establish MU system alignment for HPI cooling.	1 Align BWST to available MUP valves: MUV-73MUV-58 2 Ensure MUP cooling supply is established. 3 Ensure MUP lube oil is properly aligned for available MUP: Main lube oil pump running Backup lube oil pump in normal after stop Main and backup gear oil pumps selected to "AUTO"
3.54 Energize one set of HPI valves using "HPI VALVE EMERG POWER SEL" switches.	

Notify PPO to unlock and close DPDP 8A-4 "MUV-543, MUV-544"

Notify PPO to unlock and close DPDP 8B-8 "MUV-545, MUV-546"

(A ES 4160V SWGR Room).

(B ES 4160V SWGR Room).

	1	mar.	78	~	4.1	r
-20				10	PLI	۸.
A	L.,			1.7	11.74	
12	34	_	ж.		1.75	59

DETAILS

3.56 __ Open HPI recirc to sump valves.

 MUV-543
 MUV-544
 MUV-545
 MUV-546

3.57 __ Ensure MUP recirc to MUT valves are closed.

***************************************	MUV-53
	MUV-257

3.58 paths.

- Isolate MUP discharge flow Ensure the following valves are closed:
 - MUV-24
 - MUV-23
 - MUV-25
 - MUV-26
 - MUV-18
 - MUV-27

ACTIONS

DETAILS

- 3.59 <u>IF a MUP is NOT running.</u> THEN start available MUP.
- required.

[Rule 2, HPI Control]

3.60 ___ Open HPI valve as • Throttle HPI valve to maintain Tincore < 200 °F.

See Table 3

3.61 ___ IF at any time, RCS PRESS approaches NDT, THEN cycle PORV to maintain RCS PRESS < NDT limit.

See Figure 1

3.62 ___ Notify Chemistry to sample RB sump for boron.

Applicable carry-over steps:

3.61 IF RCS PRESS approaches NDT, THEN cycle PORV to maintain RCS PRESS...

AP-404 REV 04 (MC) PAGE 50 of 123 LDHR

ACTIONS

DETAILS

- 3.63 ______IF at any time, normal DHR is available, ______THEN notify TSC for additional guidance and EXIT this procedure.
- 3.64 _____ IF at any time, adequate SCM based on Tincore was lost. THEN notify TSC for boron precipitation guidance.

See Table 2

Applicable carry-over steps:

3.61 IF RCS PRESS approaches NDT, THEN cycle PORV to maintain RCS PRESS...

 $3.63\ \underline{\text{IF}}$ normal DHR is available, THEN notify TSC for additional...

3.64 IF adequate SCM based on Tincore was lost, THEN notify TSC...

AP-404 REV 04 (MC) PAGE 52 of 123 LDHR

ACTIONS

- 3.65 <u>WHEN all</u> the following conditions exist:
 - __ RB flood level ≥ 2.5 ft
 - ___ LPI pump associated with running MUP is available
 - RB sump boron ≥ that required for shut down margin

THEN establish LPI from RB sump on selected train.

DETAILS

1 Ensure BWST recirc valve is closed on selected train:

A Train	B Train
DHV-8	DHV-7

2 Ensure RB sump to DHP valve is open on selected train:

A Train	B Train
DHV-42	DHV-43

3 Ensure BWST to DHP valve is closed on selected train:

A Train	B Train
DHV-34	DHV - 35

4 Ensure LPI control is in "AUTO" and set for 1400 gpm on selected train:

A Train	B Train
DHV-110	DHV-111

Applicable carry-over steps:

- 3.61 IF RCS PRESS approaches NDT, THEN cycle PORV to maintain RCS PRESS...
- 3.63 IF normal DHR is available. THEN notify TSC for additional...
- 3.64 IF adequate SCM based on Tincore was lost, THEN notify TSC...

ACTIONS

3.66 ___ Start LPI pump and required cooling pumps. 1 Start pumps for selected train:

DETAILS

A Train	B Train
DCP-1A	DCP-1B
RWP-3A	RWP-3B
DHP-1A	DHP-1B

2 Throttle LPI flow to \leq 1400 gpm on selected train:

A Train	B Train
DHV-5	DHV-6

3.67 ___ Adjust DC cooling on selected train.

See Table 3

A Train	B Train		
DCV-177-MS	DCV-178-MS		

Applicable carry-over steps:

- 3.61 IF RCS PRESS approaches NDT, THEN cycle PORV to maintain RCS PRESS...
- 3.63 IF normal DHR is available, THEN notify TSC for additional...
- 3.64 IF adequate SCM based on Tincore was lost, THEN notify TSC...

ACTIONS

- 3.68 _____ IF at any time. all the following conditions exist:
 - __ At least 1 LPI pump is running
 - ___ LPI pump aligned to RB sump
 - Associated HPI pump running
 - ___ LPI to HPI alignment is desired OR BWST level is ≤ 4.5 ft

THEN align LPI to HPI suction.

DETAILS

- 1 Adjust LPI flow to ≤ 900 gpm.
- 2 Open LPI pump discharge to running MUP suction:

A Train	B Train
DHV-11	DHV-12

3 Close BWST to MUP valve:

A Train	B Train
MUV-73	MUV-58

3.69 WHEN normal DHR is available.
THEN notify TSC for additional guidance and EXIT this procedure.

ACTIONS

DETAILS

- 6	7	т	А	-	•	1.0	r
- 7	•		£1	м			٠,
- 14	5	٠.	r	١.		u.	ω

LPI cooling is available.

- 3.70 ___ Isolate the RB sump.
- Select RB sump pumps to "PULL TO LOCK":

___ WDP-2A

WDP-2B

• Close RB sump discharge valves:

WDV-3

___ WDV-4

3.71 ___ Close waste gas header isolation valves.

WDV-406

WDV-405

ACTION'S

3.72 ___ Align LPI for cooling.

DETAILS

1 Close the following valves for selected train:

A Train	B Train
DHV-8	DHV-7
DHV-5	DHV-6
DHV-75	DHV-76
DHV-105	DHV-106
DHV-11	DHV-12

2 Open the following valve for selected train:

A Train	B Train
DHV-34	DHV-35

3 Ensure LPI control valve for selected train is in "AUTO" and set for 1400 gpm:

A Train	B Train
DHV-110	DHV-111

4 Open the following valve for selected train:

A Train	B Train
DHV-5	DHV-6

ACTIONS

DETAILS

CAUTION

Minimum level in BWST for DH pump operation is 4.5 ft.

3.73 ___ Start selected LPI pump and cooling water pumps.

A Train	B Train
DCP-1A	DCP-1B
RWP-3A	RWP-3B
DHP-1A	DHP-1B

- 3.74 ___ Establish LPI flow.
- Throttle LPI control valve to maintain Tincore < 200°F:

A Train	B Train		
DHV-110	DHV-111		

See Table 3

Applicable carry-over steps:

3.75 IF additional LPI flow is required, reduce RCS PRESS.

ACTIONS

3.76 ____ IF at any time, RB flood level is \geq 2.5 ft, THEN transfer selected LPI pump suction to RB sump.

DETAILS

1 Throttle selected LPI train flow to ≤ 1400 gpm:

A Train	B Train	
DHV-110	DHV-111	

2 Open RB sump to DHP valve on selected train:

A Train	B Train
DHV-42	DHV-43

3 Close BWST to DHP valve on selected train:

A Train	B Train
DHV-34	DHV-35

4 Adjust DC cooling on selected train:

A Train	B Train
DCV-177-MS	DCV-178-MS

See Table 3

3.77 <u>IF</u> at any time, adequate SCM based on Tincore was lost, <u>THEN</u> notify TSC for boron precipitation guidance.

See Table 2

AP-404	REV 04 (MC)	PAGE 65 of 123	LDHR	
The same and the s				

Applicable carry-over steps:

- 3.75 IF additional LPI flow is required, reduce RCS PRESS.
- 3.76 IF RB flood level is \geq 2.5 ft, transfer selected LPI pump suction...
- 3.77 IF adequate SCM based on Tincore was lost, THEN notify TSC...

ACTIONS

DETAILS

3.78 <u>WHEN</u> normal DHR is available, <u>THEN</u> notify TSC for additional guidance and **EXIT** this procedure.

ACTIONS

DETAILS

STATUS

CFTs are available for core cooling.

- 1 Notify PPO to unlock and close CFT isolation valve Bkrs (119 ft AB):
 - ___ ES MCC 3AB-6B "CFV-5 A CFT Iso"
 - ES MCC 3AB-6C "CFV-6 B CFT Iso"
- Notify PPO to jog open one or both CFT isolation valves at respective breakers.
 - ___ CFV-5
 - ___ CFV-6
- 3 Adjust flow to maintain the following:
 - ___ Tincore < 200°F
 - ___ RCS PRESS < NDT curve
 - See Figure 1

ACTIONS

DETAILS

- AND RCS PRESS is < 100 psig, THEN align nitrogen system to applicable CFT.
 - IF at any time, additional Notify SPO to PERFORM Enclosure 6, Pressurizing Core Flood Tanks, in this procedure.
- 3.81 $\underline{\hspace{0.5cm}}$ IF at any time, RCS PRESS 1 $\underline{\hspace{0.5cm}}$ Ensure RCV-11 is open. OR additional CFT flow is 2 ___ Open the PORV. required. THEN reduce RCS PRESS.
- IF at any time, adequate SCM based on Tincore was lost. THEN notify TSC for boron precipitation guidance.

See Table 2

3.83 ___ WHEN normal DHR is available. THEN notify TSC for additional guidance and EXIT this procedure.

AP-404 REV 04 (MC) PAGE 72 of 123 LDHR

ACTIONS

DETAILS

STATUS

- RB sump can be flooded.
- LPI pump with suction from RB sump is available.
- 3.84 ___ Isolate the RB sump.
- Select RB sump pumps to "PULL TO LOCK":

___ WDP-2A

___ WDP-2B

· Close RB sump discharge valves:

WDV-3

___ WDV-4

3.85 ___ Open BWST to DHP valves on selected LPI Train.

A Train	B Train	
DHV-34	DHV-35	

3.86 <u>IF</u> alternate RB sump fill path is desired (BWST through fuel transfer canal deep end to RB sump), <u>THEN</u> **GO TO** Step 3.94 in this procedure.

3.0 FOLLOW-UP ACTIONS (CONT'D)

ACTIONS

DETAILS

3.87 ___ Open RB sump to DHP valves for selected train.

A Train	B Train
DHV-42	DHV-43

3.88 __ Close waste gas header isolation valves.

 WDV-406
 WDV-405

3.0 FOLLOW-UP ACTIONS (CONT'D)

ACTIONS

 $\frac{\text{WHEN RB flood level is}}{\geq 2.5 \text{ ft.}}$ 1 Ensure BWST recirc valve on selected train is closed: sump with selected train.

DETAILS

A Train	B Train	
DHV-8	DHV-7	

2 Open RB sump to DHP valve on selected train:

A Train	B Train
DHV-42	DHV-43

3 Ensure BWST to DHP valve is closed on selected train:

A Train	B Train
DHV-34	DHV-35

4 Open LPI injection valve on selected train:

A Train	B Train
DHV-5	DHV-6

3.0 FOLLOW-UP ACTIONS (CONT'D)

	-					
A	~	T	-	0	8:1	0
73.			-		IN.	١٩,
<i>p</i> ~,	ι.,		- 4	3. /	L A	

3.90 ___ Start LPI pump and 1 Start pumps for selected train: required cooling water pumps.

DETAILS

A Train	B Train
DCP-1A	DCP-1B
RWP-3A	RWP-3B
DHP-1A	DHP 1B

2 Throttle DHV-110 or DHV-111 to maintain the following:

Tincore < 200°F

Maximum DHR flow ≤ 1400 gpm

See Table 3

Cycle the PORV to maintain RCS PRESS ≤ NDT.

See Figure 1

 $3.92 \underline{\hspace{1cm}}$ IF at any time, adequate SCM based on Tincore is lost. THEN notify TSC for boron precipitation guidance.

See Table 2

3.93 ___ WHEN normal DHR is available. THEN notify TSC for additional guidance and EXIT this procedure.

AP-404	REV 04 (MC)	PAGE 79 of 123	LDHR

ACTIONS

DETAILS

*	*		-		-
		n	-	11	1
3	3.4	м		¶.J	3
~	24	_	1.2	-22	\simeq

Alternate RB sump flood method is desired.

- 3.94 Ensure SFP-2 is stopped.
- 3.95 ___ Notify PPO to PERFORM Enclosure 5. Valve Alignment for Fuel Transfer Canal Gravity Fill, in this procedure.
- 3.96 <u>WHEN</u> Enclosure 5 is Notify PPO to throttle open SFV-13 "BWST Supply Iso" for desired flow canal gravity fill.
 - "BWST Supply Iso" for desired flow THEN start fuel transfer rate (119 ft AB by SFPs).
- ≥ 2.5 ft. THEN restore lineup.
- 3.97 <u>WHEN</u> RB flood level is Notify PPO to close the following:
 - SFV-13 "BWST Supply Iso" (119 ft AB by SFPs)
 - SFV-19 "Fuel Transfer Canal AB Iso" (119 ft AB penetration area)
- 3.98 ___ Close waste gas header isolation valves.

WDV-406 WDV-405

3.0 FOLLOW-UP ACTIONS (CONT'D)

ACTIONS

DETAILS

A Train	B Train	
DHV-8	DHV-7	

2 Open RB sump to DHP valve on selected train:

A Train	B Train
DHV-42	DHV-43

3 Ensure BWST to DHP valve is closed on selected train:

A Train	B Train
DHV-34	DHV-35

4 Open LPI injection valve on selected train:

A Train	B Train
DHV-5	DHV-6

3.0 FOLLOW-UP ACTIONS (CONT'D)

	07	- 4	-	110	
Δ			$^{(1)}$	N۱٩	
	Sul		V	13 %	

3 100 ___ Start LPI pump and 1 Start pumps for selected train: required cooling water pumps.

DETAILS

A Train	B Train
DCP-1A	DCP-1B
RWP-3A	RWP-3B
DHP-1A	DHP-1B

2 Throttle DHV-110 or DHV-111 to maintain the following:

Tincore < 200°F

Maximum DHR flow ≤ 1400 gpm

See Table 3

3.101 ___ Cycle the PORV to maintain RCS PRESS ≤ NDT.

See Figure 1

3.102 $\underline{\hspace{0.3cm}}$ IF at any time, adequate SCM based on Tincore was lost. THEN notify TSC for boron precipitation guidance.

See Table 2

3.103 ___ WHEN normal DHR is available, THEN notify TSC for additional guidanc and EXIT this procedure.

AP-404	REV 04 (MC)	PAGE 85 of 123	LDHR
CONTRACTOR S. SOFTER SECURIOR STANDARDS AND ARREST ARREST AND ARREST AND ARREST AND ARREST AND ARREST ARREST AND ARREST AND ARREST AND ARREST AND ARREST AND ARREST AND ARREST A			

ACTIONS

DETAILS

STATUS

- Gravity feed from BWST to RCS is available.
- RCS vent path is available.
- 3.104 <u>IF B DHR train will be aligned for gravity feed.</u>

 THEN GO TO Step 3.110 in this procedure.
- 3.105 ___ Align A DHR train for gravity feed from BWST.

1 ___ Close DHV-39

2 Close DHV-42

3 ___ Close DHV-8

4 Open DHV-34

5 ___ Open DHV-5

- 3.106 _______IF RCS vent path is upper OTSG hand holes,
 OR upper primary manway,
 THEN start gravity fill from BWST.
- Throttle DHV-110 to maintain Tincore < 200°F during fill.

See Table 3

Monitor BWST level.

3.0 FOLLOW-UP ACTIONS (CONT'D)

ACTIONS

3.107 <u>IF</u> alternate vent paths exist, <u>THEN</u> start gravity fill.

DETAILS

 Throttle DHV-110 to maintain Tincore < 200°F during fill.

See Table 3

 Monitor applicable level instrumentation during fill:

____BWST level

___ PZR level

___ Rx vessel level

___ Hot leg level

3.108 $\underline{\hspace{0.1in}}$ IF at any time, adequate SCM based on Tincore was lost. $\underline{\hspace{0.1in}}$ THEN notify TSC for boron precipitation guidance.

See Table 2

3.109 <u>WHEN</u> normal DHR is available, <u>THEN</u> notify TSC for additional guidance and **EXIT** this procedure.

ACTIONS

DETAILS

C.	T	A	T	11	C
2	I	P	1	U	2

B DHR train will be aligned for gravity feed from BWST.

Section and Publishers of Persons Street, Square, Squa	THE RESIDENCE OF THE PROPERTY	
3.110	_ Align B DHR train for	1 Close DHV-40
	gravity feed from BWST.	
		2 Close DHV-43
		3 Close DHV-7
		4 Open DHV-35
		5 Open DHV-6
0.111	15,000	
3.111	IF RCS vent path is upper OTSG hand holes, OR upper primary manway,	 Throttle DHV-111 to maintain Tincore < 200°F during fill.
	THEN start gravity fill from BWST.	See Table 3
		• Monitor BWST level.
3 112	<u>IF</u> alternate vent paths	Throttle DUV 111 to maintain
0.112	exist. THEN start gravity fill.	 Throttle DHV-111 to maintain Tincore < 200 °F.
		See Table 3
		 Monitor applicable level instrumentation during fill:
		BWST level
		PZR level
		Rx vessel level
		Hot leg level

	A	D	1	10	1
1	4	P -	- 4	1	4

3.0 FOLLOW-UP ACTIONS (CONT'D)

ACTIONS

DETAILS

3.113 $\underline{\hspace{0.3cm}}$ IF at any time, adequate SCM based on Tincore was lost, $\underline{\hspace{0.3cm}}$ THEN notify TSC for boron precipitation guidance.

See Table 2

3.114 WHEN normal DHR is available.

THEN notify TSC for additional guidance and EXIT this procedure.

5.0 ENCLOSURE 1 STARTING A DHR TRAIN

	-	-	-	-		ı.	
Λ.	C	т	1	E	ı.	£	
59	A.		- 3	U		v.	

DETAILS

1.1 __ Ensure DHP-1B is not running.

1.2 ___ Position DCV-177-MS to "0" for minimum cooling.

1.3 ___ Align DHP-1A for DHR.

• Ensure the following valves are closed:

___ DHV-34

___ DHV-42

___ DHV-8

___ DHV-75

DHV-105

___ DHV-11

___ DHV-76

___ DHV-106

___ DHV-40

___ DHV-6

1.4 ___ Open DHP-1A isolation valves.

___ DHV-39 ___ DHV-5

4.0 ENCLOSURE 1 STARTING A DHR TRAIN (CONT'D)

	ACTIONS		DETAILS
1.5 _	.5 Align drop line for DHR		Open DHV-41
	operation.	2	Open DHV-3
		3	Open DHV-4
1.6	Stant A DUD thain	-	Charle DOD 14
1.0	_ Start A DHR train.		Start DCP-1A
		2	Start RWP-3A
		3	Start DHP-1A
		4	Throttle DHV-110 to maintain approximately 3000 gpm.
1.7 _	_ Stabilize RCS TEMP as desired for plant conditions.	•	Adjust DCV-177-MS for desired cooling.
	conditions.		See Table 3
		• _	Monitor "Cooler Outlet" TEMP (DH-2-TI1) to determine RCS cooling.

4.0 ENCLOSURE 2 STARTING B DHR TRAIN

A	n	T	T	n	. :	0
A	٤.	1	-	1.1	ŀΝ	1
F 3	Sec	_	A	1/	2.78	~

DETAILS

2.1 ___ Ensure DHP-1A is not running.

2.2 ___ Position DCV-178-MS to "0" for minimum cooling.

2.3 ___ Align DHP-1B for DHR.

• Ensure the following valves are closed:

DHV-35

___ DHV-43

___ DHV-7

___ DHV-76

___ DHV-106

__ DHV-12

___ DHV-75

___ DHV-105

___ DHV-39

DHV-5

2.4 ___ Open DHP-1B isolation valves.

___ DHV-40 ___ DHV-6

4.0 ENCLOSURE 2 STARTING B DHR TRAIN (CONT'D)

A	1	+	*	~		,
Δ	C		1	E 3	N	٦,
E 3	Sect.	1	A.	v	1.4	1

DETAILS

2.5 ___ Align drop line for DHR 1 ___ Open DHV-41 operation.

2 Open DHV-3

3 ___ Open DHV-4

2.6 ___ Start B DHR train.

1 Start DCP-1B

2 ___ Start RWP-3B

3 ___ Start DHP-1B

4 ___ Throttle DHV-111 to maintain approximately 3000 gpm.

2.7 ___ Stabilize RCS TEMP as desired for plant conditions.

 Adjust DCV-178-MS for desired cooling.

See Table 3

Monitor "Cooler Outlet" TEMP (DH-2-TI2) to determine RCS cooling.

2.8 ___ EXIT this enclosure.

4.0 ENCLOSURE 3 CONTAINMENT CLOSURE IN MODES 5 OR 6

	ACTIONS	DETAILS			
3.1 _	Ensure containment closure.	 Ensure equipment hatch is closed and held in place by ≥ 16 bolts. 			
		• Ensure ≥ 1 door in each air lock is closed.			
3.2 _	IF RB purge is in progress. THEN stop RB purge.	1 Notify SPO to ensure purge heaters are de-energized (Unit 480V SWGR Room):			
		480V HEATING AUX BUS 3-3A "AHHE-16A A RB Purge Heating Coil"			
		480V HEATING AUX BUS 3-4A "AHHE-16B B RB Purge Heating Coil"			
		2 Ensure <u>all</u> main purge valves are closed:			
		AHV-1C			
		AHV-1B			
		AHV-1D			
		AHV-1A			
		<pre>3 Ensure both RB purge supply fans are off:</pre>			
		AHF-6A			
		AHF-6B			
		4 Ensure both RB purge exhaust fans are off:			
		AHF-7A			
		AHF-7B			

4.0 ENCLOSURE 3 CONTAINMENT CLOSURE IN MODES 5 OR 6 (CONT'D)

ACTIONS

DETAILS

3.3 ___ Determine if in progress work involves open containment penetrations.

Determine if in progress • Review Containment Penetration log.

3.4 ____ Notify Shop Supervisors to initiate containment closure requirements.

4.0 ENCLOSURE 4 VENTING DHR

ACTIONS

DETAILS

- IF B DHR train will be filled and vented, THEN GO TO Step 4.9 in this enclosure.
- 4.2 ___ Isolate A DHP train. © Close the following valves:

DHV-39

DHV-5

4.3 __ Open DHV-8

NOTE

Opening DHV-19 may cause backflow from the BWST.

- Notify PPO to open DHV-10 "DH Recirc Iso Bypass" (95 ft AB Triangle Room).
- 4.5 WHEN DHV-10 is open. THEN notify PPO to cycle DHV-19 "DHP-1A vent" (75 ft AB A DH Room) to vent DHP-1A
- WHEN venting is complete THEN notify PPO to close DHV-10 "DH Recirc Iso Bypass" (95 ft AB Triangle Room).

AP-404

REV 04 (MC)

PAGE 107 of 123

LDHR

4.0 ENCLOSURE 4 VENTING DHR (CONT'D)

ACTIONS

DETAILS

4.7 __ Close DHV-8

4.8 ___ EXIT this enclosure.

ACTIONS

DETAILS

C	т	1	1	т	1	þ	c
0	1	r	١	1	ľ	J.	Q

Venting Train B DHR is desired.

- 4.9 ___ Isolate B DHR train. Close the following valves:

DHV-40

DHV-6

4.10 __ Open DHV-7

NOTE

Opening DHV-10 may cause backflow from the BWST.

- 4.11 ___ Notify PPO to open DHV-10 "DH Recirc Iso Bypass" (95 ft AB Triangle Room).
- 4.12 WHEN DHV-10 is open.
 THEN notify PPO to cycle
 DHV-30 "DHP-1B vent" (75 ft AB B DH Room) to vent DHP-1B

4.0 ENCLOSURE 4 VENTING DHR (CONT'D)

ACTIONS

DETAILS

4.13 WHEN venting is complete.
THEN notify PPO to close
DHV-10 "DH Recirc Iso
Bypass" (95 ft AB Triangle
Room).

4.14 __ Close DHV-7

4.15 ___ EXIT this enclosure.

4.0 ENCLOSURE 5 VALVE ALIGNMENT FOR FUEL TRANSFER CANAL GRAVITY FILL

Valve	Description	Position	Initial
	AUX BUILDING		
SFV-13	BWST Supply Iso (119 ft AB by SFPs)	Closed	
SFV-180	Fuel Transfer Tube Drain (119 ft AB under stairs behind SF AH units)	Locked Closed	12.000
SFV-181	Fuel Transfer Tube Drain (119 ft AB under stairs behind SF AH units)	Locked Closed	
SFV-20	SFP to Fuel Transfer Canal (119 ft AB by SFPs)	Closed	
SFV-88	Fuel Transfer Canal to SFP Suction (119 ft AB by SFPs)	Open	
SFV-19	Fuel Transfer Canal AB Iso (119 ft AB penetration area)	0pen	MICO ANAMONESMANIA AMA
SFV-21	SFP-2 Suction Iso (119 ft AB by SFPs)	Closed	
SFV-12	SFP Suction Iso (119 ft AB by SFPs on mezzanine)	Closed	
SFV-14	SF Cask Area Iso (119 ft AB by SFPs on mezzanine)	Closed	
	REACTOR BUILDING	47	A
SFV-18	18 Fuel Transfer Canal RB Iso (129 ft RB by B CFT Room)		
SFV-187	RB Header Drain (119 ft RB by SFV-18)	Closed	
SFV-5	Fuel Transfer Canal Iso (119 ft RB above CFT-1B)	0pen	
SFV-83	Fuel Transfer Canal Drain (95 ft RB by RB sum)	0pen	
SFV-84	Fuel Transfer Canal Drain (95 ft RB by RB sump)	Open	

AP-404	REV 04 (MC)	PAGE 115 of 123	LDHR
Parent processors and a consistency of the construction of the con			

4.0 ENCLOSURE 6 PRESSURIZING CORE FLOOD TANKS

	ACTIONS		DETAILS
6.1 _	_ Align the Nz system to pressurize CFTs.	1	_ Open "Low Pressure Nitrogen Header Iso" valves (119 ft TB by rollup door):
			NGV - 154
			NGV-156
		2	- Close breaker ACDP 4-18 for NGHE-1 (Unit 480V SWGR Room).
		3	Ensure NGV-9 "High Pressure Nitrogen Header Iso" is closed (95 ft TB by FWP-1A).
		4	Ensure NGHE-1 "Nitrogen Heater Control Switch" is in the "ON" position (95 ft IB by EFP-2).
		5	Unlock and open NGV-4 "Low Pressure Nitrogen Cross-Tie Iso" (95 ft IB by EFP-2).
6.2 _	IF pressurizing CFT-A, THEN notify Control Room to open CFV-28		
6.3	IF pressurizing CFT-B, THEN notify Control Room to open CFV-27		
6.4	WHEN pressurizing is complete, THEN notify Control Room to close CF isolation valves.		CFV-28 CFV-27

AP-404	REV 04 (MC)	PAGE 117 of 123	LDHR
THE STATE OF THE PARTY AND PARTY AND PERSONS ASSESSED AND ADDRESS OF THE PARTY AND ADDRESS OF TH	Annual control of the state of		


4.0 ENCLOSURE 6 PRESSURIZING CORE FLOOD TANKS (CONT'D)

ACTIONS

DETAILS

Select NGHE-1 "Nitrogen Heater Control Switch" to "OFF" (95 ft IB by EFP-2).

6.6 __ EXIT this enclosure.



AP-404	REV 04 (MC)	PAGE 121 of 123	LDHR

AP-404 REV 04 (MC) PAGE 122 of 123 LDHR

Table 1: Feedwater Source Limits

Parameter		Limit
MFW	Flow to the high nozzles	< 0.7 X 10 ⁶ lbm/hr
MFW	TEMP to the high nozzles	< 150°F
AFW	Pump flow limit	< 600 gpm with CST > 5 ft

Table 2: Adequate SCM

RCS	SCM	
> 1500 psig	≥ 30°F	
≤ 1500 to > 350 psig	≥ 50°F	
< 350 psig	SPDS	
≤ 160°F	N/A	

Table 3: Cooldown Rate Limits

RCP RCS TEMP Status		Cooldown Rate		
≥ 1 RCP	> 280°F	≤ 50°F/½ hr		
	280 to 150°F	≤ 25°F/½ hr		
No RCPs	> 150°F	≤ 25°F/½ hr		
	<150°F	≤ 5°F/½ hr		