

EVALUATION RESEARCH CORPORATION

CONTROLLED COPY

CONTROL NO. DF-001

COMANCHE PEAK RESPONSE TEAM

QUALITY INSTRUCTION FOR ISSUE-SPECIFIC ACTION PLAN VII.c

CHANGE NOTICE: 002

INSTRUCTION NO: QI-014

REVISION NO: 1

ISSUE DATE: 04/09/86

REINSPECTION OF CABLES/I-E-CABL

Prepared by: J.R. Perrino

Date: 4/8/86

Approved by: Albert A. Patters
Issue Coordinator

Date: 4/9/86

Approved by: E.C. Baiada
On-Site QA Representative

Date: 4/9/86

Approved by: J.Z. Haul
QA/QC Review Team Leader

Date: 4/9/86

8607170222 860711
PDR ADOCK 05000445
A PDR

1. Add the following notes to Paragraph 5.9.b

There may be cases where SBM is overlapped, folded-over or gaps filled and the minimum dimensions required for those configurations are not observable. In those cases, those dimensions need not be verified.

If repair for rips, holes or large tears is evident (sewing or patches), make a notation on the checklist for document review.

2. Add the following to the note under Paragraph 5.11.1:

Weidmuller terminal blocks used inside the reactor building shall be black in color.