

000190 3259

Sequoyah Nuclear Plant

DISTRIBUTIONMODIFICATION AND ADDITIONS INSTRUCTIONM2AI-7ELECTRICAL PENETRATION AND CABLE SPLICING
INSTRUCTIONS

10/31/79

Prepared By: Lynn CowanRevised By: :/ASubmitted By: C.P. Brimmer
SupervisorPORC Review: 11/8/79
DateApproved By: John J. Martine
SuperintendentDate Approved: 11/8/79

Rev. No.	Date	Revised Pages	Rev. No.	Date	Revised Pages
0	11/8/79	All			

8611050354 861031
PDR ADOCK 05000327
P PDRThe last page of this instruction is
Number 49.

1C Plant Master File
1C Superintendent
1C Assistant Superintendent (Oper.)
1C Assistant Superintendent (Maint.)
1C Administrative Supervisor
1C Maintenance Supervisor (M)
1C Assistant Maintenance Supervisor (M)
1C Maintenance Supervisor (E)
1C Assistant Maintenance Supervisor (E)
1C Maintenance Supervisor (I)
1C Results Supervisor
1C Operations Supervisor
1C Quality Assurance Supervisor
1C Health Physicist
1C Public Safety Services Supv.
1C Chief Storekeeper
1C Prep Test Program Coordinator
1C Outage Director
1C Chemical Engineer
1C Radiochem Laboratory
1C Instrument Shop
1C Reactor Engineer
1C Instrument Engineer
1C Mechanical Engineer
1C Staff Industrial Engineer
1C Training Center Coordinator
1C PCO - Chickamauga Engrg Unit - SNP
1C Public Safety Services - SNP
1C Shift Engineer Office
1C Unit Control Room
1C QA&A Rep. - SNP
1C Health Physics Laboratory
1C Chief, Nuclear Generation Branch
1C P Prod Central Office File
1C Superintendent, WBNP
1C Superintendent, BFNP
1C Superintendent, BENP
1C EN DES - MEB NEG
1C Supv., NPHPS ROB, MS
1C NRC-IE:II
1C Power Security Officer, 604 PRB-C
1C Nuclear Materials Coordinator
1C Manager, OP-QA&A Staff
1C P Prod Plant Eng. Branch
1C NSRS 307 G.B.K.
1C Asst. Outage Director
1C J.E. Gibbs, Outage Director, WBNP

1.0 PURPOSE

The purpose of this procedure is to provide a method of splicing cables on inboard and outboard sides of the electrical penetrations mounted in the reactor containment vessel walls and cables throughout the plant that are to be spliced.

2.0 SCOPE

This procedure includes splice details and requirements for non-CSSC splices to the electrical penetrations and other areas as well as CSSC.

3.0 REFERENCES

- A. Manuals - Westinghouse Specification E2526 dated June 11, 1974.
- B. Installation Instruction for Westinghouse Electronic Tube Division, Nuclear Reactor Containment Vessel, Electrical Penetrations; plant: Sequoyah #1 and #2, contract 72C61-75164 (TVA) (for 6.9-kV splicing only)
- C. See appropriate TVA and Westinghouse drawings.
TVA 45A860 Series Electrical Penetration drawings
Westinghouse E2492 through E2506
- D. G-38, "Installing Insulated Cables Rated Up to 15000 Volts Inclusive with Sequoyah Attachment"
- E. Figures
 - 1. Figure 1: Typical Butt Splice Preparation for Multiple Conductor Cable
 - 2. Figure 2: Cable Splicing Dimensions
 - 3. Figure 3: Multiple Conductor Cable Splice
 - 4. Figure 4: Butt Splice Single Conductor Cable
 - 5. Figure 5: Multiple Conductor/Single Conductor Cable
 - 6. Figure 5A: Multiple Conductor/Single Conductor Cable (Cascading)
 - 7. Figure 6: Multiple Conductor/Single Conductor Cable
 - 8. Figure 7: Multiple Conductor Cable-Shielded without Drain Wires
 - 9. Figure 8: Multiple Conductor Cable-Shielded without Drain Wires
 - 10. Figure 9: RAYCHEM Thermofit Cable Breakout Table
 - 11. Figure 10: Thermocoupling Wiring
 - 12. Figure 11: Type E Triax Connectors
 - 13. Figure 12: Type F Coax Connectors
- F. Attachments
 - 1. RAYCHEM WCSF In-Line Field Splice Installation Guide 1050
 - 2. RAYCHEM WCSF In-Line Multiconductor Field Splice Installation Guide 1060
 - 3. RAYCHEM Sleeve Selection Guide

4.0 DEFINITIONS

Cable Qualification - Cables shall be considered qualified when the continuity and megger tests have been completed in accordance with M&AI-12. These tests are to be accomplished after the cable penetration splices have been completed.

CATEGORY I STRUCTURES

The Category I structures other than the primary containment structures are listed as follows:

1. Auxiliary-Control Building
 - a. Control Bay Portion
 - b. Auxiliary Building Portion
 - c. Waste Packaging Area
 - d. Condensate Demineralizer Waste Evaporator Building Portion
2. Condenser Cooling Water Pumping Station and Retaining Walls
3. Auxiliary Essential Raw Cooling Water Structures
4. Diesel-Generator Building
5. CO₂ Storage Building
6. Refueling Water Tanks and Pipe Tunnels
7. Class IE Electrical Systems Structures
8. East Steam Valve Room
9. Essential Raw Cooling Water Pumping Station and Access Cells
10. ERCW Discharge Box

5.0 RESPONSIBILITIES

- A. The cognizant engineer shall be responsible for all decisions concerning substitutions and deviations as outlined in this procedure. He shall be responsible for preparing the workplan and indicating the need for QA inspections.
- B. The electricians shall be responsible for all installations and work performed.
- C. QA inspectors shall be responsible for inspections on all CSSC equipment and where stated by the cognizant engineer in the workplan.

0 0 0 1 9 0 1 3 2 6 2

SQNP
MSAI-7
Page 18 of 19
Rev. 0

6.0 PROCEDURE (Cont.)

6. Prepare the individual conductor lengths so that the butt splices are staggered. Remove the insulation on each conductor to one-half the length of each butt splice sleeve.
7. Crimp the correct size butt sleeve to each of the conductors.
8. Slide the correct size RAYCHEM WCSF Type N sleeve over each of the conductors.
9. Crimp the mating conductor to each butt splice connector.
10. Center the RAYCHEM sleeve over the butt splice and shrink in accordance with the manufacturer's instructions.
11. Slide the copper braid tubing over the cables as shown on Figure 8.
12. Center the RAYCHEM jacket over the splice as shown on Figure 8 and shrink in accordance with the manufacturer's instructions.

7.0 INSPECTION AND DOCUMENTATION REQUIREMENTS

A. General

Inspections on all CSSC cable splices and all cables spliced in enclosures affixed to CSSC equipment shall be inspected by QA inspectors. All other splices may be inspected by the cognizant engineer or whomever be so designated in the workplan.

All splices will be inspected and documented per this instruction and the applicable workplan. Each splice shall be documented on Data Sheet 1 or an equivalent and contained in the applicable workplan. Also, the cable pull card for the applicable cable shall have the information as given below entered on the back of the card and included in the workplan at the time it is submitted to document control for documentation.

This cable has been spliced in accordance with MSAI-7 R ____.
Under workplan _____.

Work Performed By

Location

Electrician

Box or Part/Col/Ele


Electrician

Inspected By


Foreman

Inspector

Date



STANDARD IN-LINE SPLICE



BOLT-TOGETHER CONNECTION

REVISIONS			
LTR	DESCRIPTION	DATE	APPROVED

Part Number	Minimum Expanded ID As Supplied	Maximum Recovered ID After Heating	Expanded Wall Thickness $\pm 20\%$	Nominal Recovered Wall Thickness	Standard Lengths	Application Diameter Range For In-Containment Applications	
						Minimum	Maximum
WCSF-070-N	.250	.070	.02	.08	6	.08	.14
WCSF-115-N	.350	.115	.03	.09	6	.13	.23
WCSF-200-N	.750	.200	.03	.11	6, 9, 12	.22	.40
WCSF-300-N	1.200	.300	.04	.17	6, 9, 12	.33	.60
WCSF-500-N	1.500	.500	.05	.17	6, 9, 12	.55	1.00
WCSF-650-N	2.000	.650	.05	.17	6, 9, 12	.72	1.30
WCSF-1000-N	3.000	1.000	.05	.17	12, 18	1.10	2.00
WCSF-1500-N	4.500	1.500	.05	.17	12, 18	1.65	3.00

NOTES:

1. Select sleeve no. 1 with a maximum application diameter larger than the connection diameter "D".
2. Use additional sleeve(s) no. 2, if necessary, to build up the wire diameter to the minimum application diameter of the no. 1 sleeve selected.
3. Use of largest size sleeve that will fit a given wire is recommended to obtain maximum as installed wall thickness.
4. Splice sleeve length selected should allow for 2" minimum overlap onto wire insulation.

DATE	BY	DESCRIPTION	REV	THIS DRAWING AND THE INFORMATION SET FORTH HEREON ARE THE PROPERTY OF RAYCHEM CORPORATION AND ARE TO BE HELD IN TRUST AND CONFIDENCE. PUBLICATION, REPRODUCTION, DISCLOSURE, OR USE FOR ANY PURPOSE NOT EXPRESSLY AUTHORIZED IN WRITING BY RAYCHEM CORPORATION IS PROHIBITED.	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND TOLERANCES ARE: .XXX ± .2 .XX ± .2 .X ± .2	DATE	BY	CHECKED	DESIGN APP'D	MFG APP'D	QC APP'D	PROJECT	47005-006	DATE	SCALE	SHEET	104

Raychem

RAYCHEM CORPORATION
300 CONSTITUTION DRIVE
MENLO PARK, CALIFORNIA 94025

TITLE
Cable Splicing Sleeve Selection Guide
Nuclear Power Plant In-Containment Use










CODE IDENT. NO. 0000
DWG. NO. 47005-006-03

PROJECT 47005-006


DATE

SCALE

SHEET 104

ACCEPT	TERMINALS	REJECT
   SIGHT HOLE OR STRAP TYPE	  	  
① Crimps centered. Crimps may be off center BUT NOT OFF END OF WIRE BARREL. ② Wire size being used matches wire size stamped on terminal, splice, and tool. ③ Wire is visible through inspection hole of butt splice, and extends beyond end of terminal wire barrel. ④ Insulation does not enter wire barrel. ⑤ On parallel splices, bare wire ends must be flush with or extend slightly beyond end of barrel.		① Crimped off end of splice or terminal. ② Wire size being used does not match wire size stamped on terminal, splice, or tool. ③ Wire not inserted far enough in terminal or splice. End of wire must be visible through inspection hole of butt splices, and extend beyond end of terminal wire barrel. ④ Insulation entered barrel of terminal or splice. CHECK FOR INCORRECT STRIP LENGTH. ⑤ Excessive "flash" on terminal or splice indicates wrong wire, splice, or tooling combination was used. ⑥ Nicked or missing strands.

PRE-INSULATED DIAMOND GRIP (PIDG) ACCEPTANCE CRITERIA



1. Proper terminal for wire size (Example: AMP 22-18 for AWG 20)
2. Proper crimp die used on terminal (1 dot-red, 2 dots-blue, 1 dot-yellow)
3. Crimp properly placed on terminal
4. Insulation crimp holding - gripping not cutting
5. Wire flush with tongue end of wire barrel
6. Proper strip length - wire barrel + 1/32-inch minimum to 3/64-inch maximum

UNITED STATES GOVERNMENT

Memorandum

TENNESSEE VALLEY AUTHORITY

B43 '86 0626 931

TO : Those listed

FROM : W. S. Raughley, Chief Electrical Engineer, W8 C126 C-K

DATE : June 23, 1986

860716S084C

(10)

SUBJECT: ELECTRICAL ISSUES - CABLE SIDEWALL PRESSURE (SWP)

PLEASE RESPOND BY JUNE 30, 1986

The purpose of this memorandum is to provide guidance for each Lead Engineer to determine the adequacy of the Class 1E cable installation with respect to cable SWP.

General construction specification G-38, presently defines the procedure for calculating the expected pulling force to ensure that cable sidewall pressure values are not exceeded (section 3.2.1.6). These requirements were incorporated into G-38 as outlined in Attachment A.

In July 1985, EEB-EP 22.29, "Procedure to Determine Acceptability of Sidewall Pressures Exerted on Class 1E Cables in Existing Conduit Installations at Watts Bar Nuclear Plant," was written to determine if the maximum allowable cable SWPs had been exceeded for Class 1E cables.

A design calculation to determine the acceptability of SWPs exerted on Class 1E cables in existing conduit installations at Watts Bar Nuclear Plant was initiated followed by a sampling program involving approximately 10,400 conduits. Screening calculations [Reference WBN Document "Sidewall Pressures of Class 1E Cables in Conduits" (B43 860310 936)] reduced the number of conduits to 1914 which were considered potential candidates for high sidewall bearing pressure. From these 1914 conduits, a field inspection team consisting of OE, OC, and QA/QC personnel conducted a walkdown of 778 conduits to determine the worst-cases and selected 82 conduits for analysis. The 82 conduits consisted of approximately 20 conduits each from voltage levels V2, V3, V4, and V5. Conduits from voltage level V1 were not considered as there are no Class 1E cables in voltage level V1.

Based on the isometric sketches furnished by OC for routing of these 82 conduits, tension and SWP calculations were performed analytically for the cables in each conduit to determine the worst-case SWP. The calculated SWPs were compared with the SWP limits recommended in the construction specification G-38. It was noted that 21 cables in 12 of the 82 conduits exceeded the SWP limits.

TVA cable SWP testing has just been completed at Central Labs, raising the cable SWP limits well above the present limits shown in G-38, which will eliminate the SWP violations at WBN. These results are applicable to the other projects provided you fall within the worst-case limits.


Each respective engineering project, with the exception of WBN, shall develop, issue, and implement a cable SWP sampling procedure using Attachment B as a guide consistent with your restart/fuel load schedules.



Those listed
June 23, 1986

ELECTRICAL ISSUES - CABLE SIDEWALL PRESSURE (SWP)

The fragnet for resolving the cable SWP issue is Attachment C. This effort should be started immediately to expedite completion of the cable SWP issue. Please submit your fragnet to me and the Project Engineer by June 23, 1986.


W. S. Raughley

J. D. Collins, P-205 SB-K*
G. T. Hall, DNE, DSC-A, Sequoyah
D. F. Faulkner, A7-BFM ENG
J. L. Springer, 9-111 SB-K

*Please proceed to revise the existing cable SWP calculation using the new cable SWP limits addressing each cable pull in each conduit and cable pulls through flexible conduit.

DLL:RB

DLL cc: RIMS, SL 26 C-K

 Principally Prepared By: D. L. Leckie, Extension 2081.

046162.03

ATTACHMENT A

Page 1 of 2

SQN (CP 5-27-70), WBN (CP 1-23-73), and BLN (CP 12-24-74)
Electrical Cable Issues

Issue: Cable Sidewall Pressure* In Conduit

<u>Time Frame</u>	<u>DNE Document (Section)</u>	<u>DNE Requirement</u>
7/25/73 to 10/22/75	G-38 R0 (Sect. 3.1.d)	Maximum force not to exceed 100 times the radius of curvature expressed in feet
10/22/75 to 9/15/85	G-38 R1 (Sect. 3.2.1.2.c) thru G-38 R5 (Sect. 3.2.1.3.a)	Specific instructions from vendor or 100 times bend radius in feet for small inst. cables and 300 times the bend radius in feet for shielded power cables
9-15-85 to 3/17/86	SRN-G-38-5, same as G-38 R6 (Sect. 3.2.1.6) thru G-38 R8 (Sect. 3.2.1.6)	NU CON required to calculate SWP; Use vendor's values, or 300 lb/ft for power and control and 100 lb/ft for signal cables

*Not specifically called cable sidewall pressure (SWP) until G-38 R6
(9-15-85).

066118.03

CHS: 5/12/86
4/20/86

BPM (CONST Permit 5/10/67)
Electrical Cable Issues

Issue: Cable Sidewall Pressure* In Conduit

<u>Time Frame</u>	<u>DNE Document (Section)</u>	<u>DNE Requirement</u>
5/10/67 to 1/9/73	G-4, revised 12/15/69 and earlier revisions	No specific requirement
1/9/73 to 1/15/86	G-4, revision dated 1-9-73 (Sect. B.1.d)	Max. strain at a bend not in excess of 100 times radius of curvature in feet
1/15/86 to 3/17/86	G-38 R7 and R8 (Sect. 3.2.1.6)	NU CON required to calculate SWP Use vendor's values or 300 lb/ft for power and control cables and 100 lb/ft for signal cables

*Not specifically called cable sidewall pressure until G-38 R6
(9-15-85).

066118.03

CHS: 5/12/86
4/28/86

PROCEDURE TO DETERMINE ACCEPTABILITY OF SIDEWALL
PRESSURES EXERTED ON CLASS 1E CABLES IN EXISTING
CONDUIT INSTALLATIONS AT _____ NUCLEAR PLANT

ISSUE DATE:

REVIEWED BY: _____

APPROVED BY: _____
Chief Electrical Engineer

1.0 PURPOSE AND SCOPE

1.1 Purpose

This procedure establishes a sampling program to determine whether maximum allowable cable sidewall pressures (SWP) have been exceeded for Class 1E cables in the environmental qualification program (10CFR50.49) at ____NP. The procedure also provides the method for resolution of any SWP violations.

1.2 Scope

The sampling program will be limited to Class 1E cables included in the environmental qualification program (10CFR50.49) routed in conduits for all units. The sample shall include a minimum of 2 conduits per voltage level per unit.

2.0 PROCEDURE

2.1 DNE shall:

2.1.1 Obtain a listing of all Class 1E cables in the scope of the environmental qualification program for all units.

2.1.2 Develop a list of all conduits containing the cables identified in 2.1.1.

PROCEDURE TO DETERMINE ACCEPTABILITY OF SIDEWALL
PRESSURES EXERTED ON CLASS 1E CABLES IN EXISTING
CONDUIT INSTALLATIONS AT _____ NUCLEAR PLANT

2.0 PROCEDURE (Continued)

2.1.3 By analysis of conduit lengths, conduit sizes, cable weights, number of cables, and maximum allowable pulling forces, and by use of G-38, Appendix F, reduce the conduit listing to a set defined as those conduits containing Class 1E cables whose maximum allowable SWPs have the potential of being exceeded.

2.1.4 Provide the defined set of conduits to a field inspection team consisting of personnel from ONP, DNE, and QA/QC, if possible.

2.2 Field inspection team shall:

2.2.1 Select the sample of conduits which meet the worst-case configurations as defined below. Conduit configurations having the following characteristics between pull points (boxes, condulets, termination points, etc.) should be considered for inclusion in the sample:

- o multiple bends - more than 360° between pullpoints.
- o long length - greater than lengths in G-38, Appendix F.
- o high percentage of cable fill - greater than 30% full.
- o elevation changes

The field inspection team shall keep records on the number of conduits walked down, those with a potential of exceeding SWP, and those with the potential of exceeding SWP which did not meet the above criteria.


PROCEDURE TO DETERMINE ACCEPTABILITY OF SIDEWALL
PRESSURES EXERTED ON CLASS 1E CABLES IN EXISTING
CONDUIT INSTALLATIONS AT _____ NUCLEAR PLANT

2.0 PROCEDURE (Continued)

- 2.2.2 Prepare isometric sketches (similar to figure 1) or provide a tabulation (attachment #1) showing the installed conduit configuration for each of the conduits selected for the sample:

NOTE

Field measurement tolerances shall be within the accuracy of standard measuring devices such as steel tapes, protractors, and slope indicators.



Conduit No: _____

Figure 1

PROCEDURE TO DETERMINE ACCEPTABILITY OF SIDEWALL
PRESSURES EXERTED ON CLASS 1E CABLES IN EXISTING
CONDUIT INSTALLATIONS AT _____ NUCLEAR PLANT

2.0 PROCEDURE (Continued)

2.2.3 Obtain pull cards for all cables in the selected conduits.

2.2.4 Provide pull cards and each isometric sketch or tabulation to the Engineering Project as it is completed.

2.3 DNE shall:

2.3.1 Calculate expected pulling force (T) and SWP for each pull in each conduit. The pull shall be assumed to have been made in the direction which will result in the higher expected pulling force, unless the direction of the pull is known.

2.3.2 Compare the calculated SWPs to maximum SWPs obtained from the SWP testing program.

2.3.3 Document the sampling program as a calculations document, as in OEP-07.

3.0 CONCLUSION

3.1 If no violations of maximum sidewall pressure are found in the sample of worst-case examples then it will be concluded that existing installations are adequate and no further evaluation will be required.

3.2 If one or more violations of maximum sidewall pressure are found, they will be corrected by reworking the configuration of the conduit system and installing new cables and further sampling will be initiated to determine the extent of the problem.

4.0 REFERENCE

OEP-07, Calculations

10 lb. = 2.823 ft.
11 lb. = 2.917 ft.
12 lb. = 1.609 ft.

Approved SLP Values _____ lbs./ft. Weight of Cable(s) _____ lbs./ft.

BEST FILMED FROM
BEST AVAILABLE COPY

Place an eye in block if cable is an extension.

(NAME)

(ADDRESS)


1. (cont'd)

11-12-68

ATTACHMENT C

CABLE SIDEWALL PRESSURE (SWP)

Sheet — of —
 Prepared by — date —
 Checked by — date —
 Reviewed by — date —



- * Field Inspection Team
- A Obtain pull cards for all cables in conduits
- B Provide pull cards and conduit tabulation or sketch to ENGGRJ as completed.
- C Calculate expected pulling force and SWP and compare SWPs with SWP limits from Testing Program. Document results

ITEM 3

If the worst-case conduits for tough pulls have not been established, determine the worst-case conduits and provide isometric drawings, pull cards, and work orders for the pulls. If isometric drawings are not available, the following may be provided in place of the drawings:

- o a listing of the pull points and type of pull point (condulet [90° or straight], pull box, etc.)
- o the number of turns between pull points in degrees
- o the estimated distances between pull points
- o a listing of any odd configurations in a pull such as flexible conduit
- o type of cable, size of cable, voltage levels
- o size of conduit
- o a listing of any long vertical drops following 90° condulets pull-by information

RESPONSE

SNQ is currently in the process of determining the final worst-case conduits. Isometric drawings and the associated and pertinent QA records will be provided in the near future. Two sample work orders are attached for your information. Work orders are not QA records; consequently, they are not readily retrievable for every cable pull. As discussed with your staff, we believe these work order samples are sufficient for the purpose of your review.

WORKPLAN INSTRUCTIONS

Workplan No. 10328
Page 7 of 23

MARCH 1984

Step Number	Description of Work, Inspections, or Tests
<u>Scope</u>	
The purpose of this work plan package is to provide instructions for installing cables associated with the Post Accident Sampling Facility (PASF), outside the primary containment. Implementation of this work plan must be co-ordinated with other work plans listed below.	
WP# 10144 - Install conduit & junction boxes for ECN 5200 (outside containment).	
WP# 9977 - Install conduit & junction boxes for ECN 5200 (inside containment).	
WP# 10031 - Install cables for ECN 5200 (inside containment).	
Cable terminations will be included under another work plan number.	
Cables to be installed by this instruction are listed on pages <u>12-1 thru 12-1</u> of <u>23</u> .	

WORKPLAN INSTRUCTIONS

Workplan No. 10328
Page 10-1 of 23

Step Number	Description of Work, Inspections, or Tests
<u>Work Instructions</u>	
1.	Obtain breaching permits as required for pulling cable through conduit and cable tray firestops & pressure boundaries. For Physci-13 breaching permits, see Index page <u>9</u> .
2.	Install all cables per applicable parts of M&AI-4. For M&AI-4 data sheets, delete ^{Deleted per T.C. 83-475} cable installation single line sketches (For the better to add structure drawings) see Index page <u>9</u> . BA inspection required when shown on data sheet
3.	Reseal Conduit/Cable Tray firestops and/or pressure boundaries per applicable parts of M&AI-13. For M&AI-13 data sheets see Index page <u>9</u> . <u>BA inspection required</u>

WORKPLAN INSTRUCTIONS

Workplan No. 10328
Page 10-2 of 23

Description of Work, Inspections, or Tests

Step
Number

Work Instructions (Cont)

4. Repair damaged cable (if damage should occur during installation) per applicable parts of M&AI-7. Notify the cognizant Engineer concerning this step before proceeding with cable repair instructions.

For M&AI-7 data sheets, see index page 9.

QA inspection required.

5. Apply flamastic to cables in cable trays if applicable per M&AI-13. For M&AI-13 data sheets, see index page 9.

QA inspection required.

6. Replace all conduit covers after cable installation is complete. Electrical foreman to verify.

19/12/84
Date

31

Temp
Change
84-0541

Step Number	Description	Ref. Document
8.	Tag out 1-FCV-87-9 Battery Bd II-B20 1-FCV-87-10 Battery Bd II-B37 1-FCV-87-11 Battery Bd II-A36	45N-687-2
9.	Lift cables IV3442B, IV3452B, IV3462B at JB 2780 (Additional Equip. Bldg). Cog. eng. to signoff below.	45N1630-51
10	Eric Legg / 3/23/84 206. JATEI Temporarily remove cables from conduit ^A back to cable tray NZ-B.	IV3469B
11.	Repull cables in conjunction with cables IM3471B, IM3472B, IM3473B per M+AI 4. QA req'd.	

W
1

WORKPLAN INSTRUCTIONS

Workplan No. 10328

Page 11 of 23

Step
Number

Description of Work, Inspections, or Tests

Responsibilities

1. The Electrical foreman is responsible for all QA signoffs associated with this instruction.
2. The Electrical foreman is responsible for obtaining bleaching permits for all cable installation. (Physi-13 Attachment F)
3. The Electrical foreman is responsible for verifying that all endulet covers are installed after cable installation is complete. See Work Instructions step 6 for signoff.
4. The Electrical foreman is responsible for obtaining all scaffold permits needed for cable installation.
5. The Electrical foreman is responsible for obtaining all cable card signoffs. Cognizant Engineer to verify Eric J. [Signature] 19/12/84
date
6. The Electrical foreman is responsible for co-ordinating the removal from service and return to service of the CO₂ system in areas needed.

1)	IM 31 80	21)	IM 33 89 A	51)	IM 34 38	81)	PL 55 11	110)	IM 34 72 B
2)	IM 31 82	30)	IM 33 93 A	52)	IM 34 39	82)	PL 55 18	111)	IM 34 73 B
3)	IM 31 83	31)	IM 33 97 A	53)	IM 34 41	83)	PL 55 22	112)	IM 34 74 B
4)	IM 31 84	32)	IM 33 99 A	54)	IM 34 42	84)	PL 55 23	113)	IM 34 77 B
5)	IM 31 85	33)	IM 34 01 A	55)	IM 34 43	85)	PL 55 24	114)	IV 34 42 B
6)	IM 31 86	34)	IM 34 02 A	56)	IM 34 44	86)	PL 55 25	115)	IV 34 52 B
7)	IM 31 87	35)	IM 34 03 A	57)	IM 34 45	87)	PL 55 26	116)	IV 34 62 B
8)	IM 31 88	36)	IM 34 04 A	58)	IM 34 46	88)	PL 55 30	117)	IM 34 80
9)	IM 31 89	37)	IM 34 05 B	59)	IM 34 47	89)	PL 55 31	118)	IM 34 81
10)	IM 31 90	38)	IM 34 06 B	60)	IM 34 48	90)	PL 55 32	119)	IM 34 82
11)	IM 31 91	39)	IM 34 07 B	61)	IM 34 49	91)	PL 55 33	120)	IM 34 85
12)	IM 31 92	40)	IM 34 08 B	62)	IM 34 50	92)	PL 55 34	121)	IM 34 81
13)	IM 31 93	41)	IM 34 09 B	63)	IM 34 51	93)	PL 55 35	122)	IM 34 81
14)	IM 31 94	42)	IM 34 13 B	64)	IM 34 52	94)	PL 55 36	123)	IM 34 81
15)	IM 31 95	43)	IM 34 17 B	65)	IM 34 53	95)	PL 55 37	124)	IM 34 81
16)	IM 31 96	44)	IM 34 21 B	66)	IM 34 54	96)	PL 55 38	125)	IM 34 81
17)	IM 31 97	45)	IM 34 23 B	67)	IM 34 55	97)	PL 55 39	126)	IM 34 81
18)	IM 31 98	46)	IM 34 25 B	68)	IM 34 56	98)	PL 55 40	127)	IM 34 81
19)	IM 31 99	47)	IM 34 26 B	69)	IM 34 57	99)	PL 55 41	128)	IM 34 81
20)	IM 32 00	48)	IM 34 27 B	70)	IM 34 58	100)	PL 55 42	129)	IM 34 81
21)	IM 32 01	49)	IM 34 28 B	71)	IM 34 59	101)	PL 55 43	130)	IM 34 81
22)	IM 33 15	50)	IM 34 29 B	72)	IM 34 60	102)	PL 55 44	131)	IM 34 81
23)	IM 33 80 A	51)	IM 34 30	73)	IM 34 61	103)	PL 55 45	132)	IM 34 81
24)	IM 33 81 A	52)	IM 34 31	74)	IM 34 62	104)	PL 55 46	133)	IM 34 81
25)	IM 33 82 A	53)	IM 34 32	75)	IM 34 63	105)	PL 55 47	134)	IM 34 81
26)	IM 33 83 A	54)	IM 34 33	76)	IM 34 64	106)	PL 55 48	135)	IM 34 81
27)	IM 33 84 A	55)	IM 34 34	77)	IM 34 65	107)	PL 55 49	136)	IM 34 81
28)	IM 33 85 A	56)	IM 34 35	78)	IM 34 66	108)	PL 55 50	137)	IM 34 81
				79)	IM 34 67	109)	PL 55 51	138)	IM 34 81
				80)	IM 34 68	110)	PL 55 52	139)	IM 34 81
				81)	IM 34 69	111)	PL 55 53	140)	IM 34 81
				82)	IM 34 70	112)	PL 55 54		
				83)	IM 34 71		PL 55 55		
				84)	IM 34 72		PL 55 56		
							PL 55 57		
							PL 55 58		
							PL 55 59		
							PL 55 60		
							PL 55 61		
							PL 55 62		
							PL 55 63		
							PL 55 64		
							PL 55 65		
							PL 55 66		
							PL 55 67		
							PL 55 68		
							PL 55 69		
							PL 55 70		
							PL 55 71		
							PL 55 72		
							PL 55 73		
							PL 55 74		
							PL 55 75		
							PL 55 76		
							PL 55 77		
							PL 55 78		
							PL 55 79		
							PL 55 80		
							PL 55 81		
							PL 55 82		
							PL 55 83		
							PL 55 84		
							PL 55 85		
							PL 55 86		
							PL 55 87		
							PL 55 88		
							PL 55 89		
							PL 55 90		
							PL 55 91		
							PL 55 92		
							PL 55 93		
							PL 55 94		
							PL 55 95		
							PL 55 96		
							PL 55 97		
							PL 55 98		
							PL 55 99		
							PL 55 100		
							PL 55 101		
							PL 55 102		
							PL 55 103		
							PL 55 104		
							PL 55 105		
							PL 55 106		
							PL 55 107		
							PL 55 108		
							PL 55 109		
							PL 55 110		
							PL 55 111		
							PL 55 112		
							PL 55 113		
							PL 55 114		
							PL 55 115		
							PL 55 116		
							PL 55 117		
							PL 55 118		
							PL 55 119		
							PL 55 120		
							PL 55 121		
							PL 55 122		
							PL 55 123		
							PL 55 124		
							PL 55 125		
							PL 55 126		
							PL 55 127		
							PL 55 128		
							PL 55 129		
							PL 55 130		
							PL 55 131		
							PL 55 132		
							PL 55 133		
							PL 55 134		
							PL 55 135		
							PL 55 136		
							PL 55 137		
							PL 55 138		
							PL 55 139		
							PL 55 140		
							PL 55 141		
							PL 55 142		
							PL 55 143		
							PL 55 144		
							PL 55 145		
							PL 55 146		
							PL 55 147		
							PL 55 148		
							PL 55 149		
							PL 55 150		
							PL 55 151		
							PL 55 152		
							PL 55 153		
							PL 55 154		
							PL 55 155		
							PL 55 156		
							PL 55 157		
							PL 55 158		
							PL 55 159		
							PL 55 160		
							PL 55 161		
							PL 55 162		
							PL 55 163		
							PL 55 164		
							PL 55 165		
							PL 55 166		
							PL 55 167		
							PL 55 168		
							PL 55 169		
							PL 55 170		
							PL 55 171		
							PL 55 172		
							PL 55 173		
							PL 55 174		
							PL 55 175		
							PL 55 176		
							PL 55 177		
							PL 55 178		
							PL 55 179		
							PL 55 180		
							PL 55 181		
							PL 55 182		
							PL 55 183		
							PL 55 184		
							PL 55 185		
							PL 55 186		
							PL 55 187		
							PL 55 188		
							PL 55 189		
							PL 55 190		
							PL 55 191		
							PL 55 192		
							PL 55 193		
							PL 55 194		
							PL 55 195		
							PL 55 196		
							PL 55 197		
							PL 55 198		
							PL 55 199		
							PL 55 200		

added per FCR 2033

deleted per sq-FCR-1953

1M3241B

SQNP
M&AI-4
Attachment 1
Page 1 of 1
Rev. 5

ATTACHMENT 1
CABLE INSTALLATION DATA SHEET

UTS
10328 4/11/83

Unit or
Number 1M3421B

Workplan Number 10144

From

NCS

SQ-FCR-2014

SQ-FCR-2059

El. 732

SQ-FCR-1845

1M3241B

1M3297B

1M3329B, 1M3330B

MC 3535B

MC 2598B

Very and
Conduit
Routing

N2-B

NX-B

LT-B

JA-B

JF-B

JE-B

1M3459B

From 745A03110019, 749A0300T022, 754A0300U00 TO CONDUIT 1M3241B.

4/5/84 011754

1-L-571

Pol 9

4/2/8/84

To

XA5

El. 706

No. of
Conductors

Size of
Conductors

Type
Insulation

Insulation
Voltage

1-4C

#10

PXMJ

600

Cable Mark

WFD

-1

no cuts

Cable
Length

226.0'

SQ-FCR-2014

Conduit
Length

Inspector Required: ☒ Yes ☐ No

NOTE: Foreman to complete below if no inspector is required.

1. Cable released to pull as routed.

Reel Number HAB-2008
or Contract
Number

[Signature]
Signature

01 19 84
Date

2. Verification that cable is pulled as specified above.

WP 10328

PAGE 13-44 OF 23

[Signature]
Signature

2/8/84
Date

IM3241B

SQNP
M&AI-4
Attachment 1
Page 1 of 1
Rev. 5

10328
PAGE 18-26 OF 23

ATTACHMENT 1
CABLE INSTALLATION DATA SHEET

UTS
10328 4/11/83

From Number IM3421B

Workplan Number 10144

1-M-10

NCS

EL. 732

SQ-FCR-1345

IM3241B, IM3328B, IM3329B, IM3330B, ~~MC3535B~~

NZ-B, NX-B, LT-B, JA-B, JF-B. MC3535B

1-L-571 Pol 9

XAS

EL. 706

No. of
Conductors

Size of
Conductors

Type
Insulation

Insulation
Voltage

1-4C

#10

Cable Mark WFD

Cable
Length 226.0'

Cable
Length

Inspector Required: ☒ Yes ☐ No

NOTE: Foreman to complete below if no inspector is required.

Cable released to pull as routed.

Reel Number
or Contract
Number

Signature

Date

Verification that cable is pulled as specified above.

WP 10328

PAGE 13-44 OF 23

Signature

Date

ACC. NO. _____, FOREMAN _____, DATE _____, ENGINEER _____

CONDUIT AND CABLE SCHEDULE SEQUOYAH NUCLEAR PLANT

CONDUIT OR
CABLE NO. CONDUIT SIZE NO. TYPE SCALED
1M 3413 B CABLE 1-7C 10 WFG -1 LENGTH REVISION
226.0 R00
VOLTAGE LEVEL 11
FROM: 1-M-10, NC5, 732
TO: 1-L-571, PNL 5, XA5, 706
FOR: POST ACD SMPLG
CONDUIT ROUTING: 1M3297B, 3298B, 3241B, MC2598B, CONT CARD 2
TRAY ROUTING: NZ-B NX-B LT-B
REEL NO. SNP _____, SNP _____, SNP _____; FIELD CABLE LENGTH _____
ACC. NO. _____, FIELD CONDUIT LENGTH I _____, A _____, FL _____
ACC. NO. _____, FOREMAN _____, DATE _____, ENGINEER _____

CONDUIT AND CABLE SCHEDULE SEQUOYAH NUCLEAR PLANT

CONDUIT OR
CABLE NO. CONDUIT SIZE NO. TYPE SCALED
1M 3417 B CABLE 1-7C 10 WFG -1 LENGTH REVISION
226.0 R00
VOLTAGE LEVEL 11
FROM: 1-M-10, NC5, 732
TO: 1-L-571, PNL 11, XA5, 706
FOR: POST ACD SMPLG
CONDUIT ROUTING: 1M3332B, 3331B, 3329B, 3328B, 3241B, CONT CARD 2
TRAY ROUTING: NZ-B NX-B LT-B
REEL NO. SNP _____, SNP _____, SNP _____; FIELD CABLE LENGTH _____
ACC. NO. _____, FIELD CONDUIT LENGTH I _____, A _____, FL _____
ACC. NO. _____, FOREMAN _____, DATE _____, ENGINEER _____

CONDUIT AND CABLE SCHEDULE SEQUOYAH NUCLEAR PLANT

PAGE 18-79 OF 23
CONDUIT OR
CABLE NO. CONDUIT SIZE NO. TYPE SCALED
1M 3421 B CABLE 1-4C 10 WFG -1 LENGTH REVISION
226.0 R00
VOLTAGE LEVEL 11
FROM: 1-M-10, NC5, 732
TO: 1-L-571, PNL 9, XA5, 706
FOR: POST ACD SMPLG
CONDUIT ROUTING: 1M3330B, 3329B, 3328B, 3241B, CONT CARD 2
TRAY ROUTING: NZ-B NX-B LT-B
REEL NO. SNP _____, SNP _____, SNP _____; FIELD CABLE LENGTH _____
ACC. NO. _____, FIELD CONDUIT LENGTH I _____, A _____, FL _____
ACC. NO. _____, FOREMAN _____, DATE _____, ENGINEER _____

CONDUIT AND CABLE SCHEDULE SEQUOYAH NUCLEAR PLANT

CONDUIT OR
CABLE NO. CONDUIT SIZE NO. TYPE SCALED
1M 3423 B CABLE 1-4C 10 WFG -1 LENGTH REVISION
226.0 R00
VOLTAGE LEVEL 11
FROM: 1-M-10, NC5, 732
TO: 1-L-571, PNL 13, XA5, 706
FOR: POST ACD SMPLG
CONDUIT ROUTING: 1M3333B, 3331B, 3329B, 3328B, 3241B, CONT CARD 2
TRAY ROUTING: NZ-B NX-B LT-B
REEL NO. SNP _____, SNP _____, SNP _____; FIELD CABLE LENGTH _____
ACC. NO. _____, FIELD CONDUIT LENGTH I _____, A _____, FL _____
ACC. NO. _____, FOREMAN _____, DATE _____, ENGINEER _____

CONDUIT OR CABLE NO.	CONDUIT SIZE	SYS- TEM	NUMBER CON- DUCTORS	NCM OR AWG	VOLTAGE LEVEL	TYPE OF CABLE	TOTAL LENGTH TRAY + CABLE	CONDUIT STATUS	ROUTING
1M 3416 B	CABLE	43	5-1C	12	11	WPB	0.0	R01	CONDUITS: 1M3332B, 3331B, 3329B, 3328B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 11, XAS, 706 FOR: POST ACD SMPLG CABLES: JA-B JF-B FROM: CARD 2 OF 2 TO: USE CARDS 182 FOR COMPLETE ROUTE
MASTER FILE SEQUENCE NO. 97737									
1M 3417 B	CABLE	43	1-7C	10	11	WFG	226.0	R01	CONDUITS: 1M3332B, 3331B, 3329B, 3328B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 11, XAS, 706 FOR: POST ACD SMPLG CABLES: JA-B JF-B FROM: CARD 2 OF 2 TO: USE CARDS 182 FOR COMPLETE ROUTE
MASTER FILE SEQUENCE NO. 97352									
1M 3417 B	CABLE	43	1-7C	10	11	WFG	142.0	R01	CONDUITS: 1M3332B, 3331B, 3329B, 3328B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 11, XAS, 706 FOR: POST ACD SMPLG CABLES: JA-B JF-B FROM: CARD 2 OF 2 TO: USE CARDS 182 FOR COMPLETE ROUTE
MASTER FILE SEQUENCE NO. 97353									
1M 3418 B	CABLE	43	1-7C	12	11	WGG	150.0	R00	CONDUITS: 1M3332B, 3331B, 3329B, 3328B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 11, XAS, 706 VIA: 1M3208B, 3202B TO: 1-FSV-43-318, AZ288, 699, VIA: 1M3203B FOR: POST ACD SMPLG CABLES: PF-B FROM: 1-L-571, PNL 11, XAS, 706 VIA: 1M3300B TO: PENT 37, AZ153, 698 FOR: POST ACD SMPLG CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 9, XAS, 706 FOR: POST ACD SMPLG
MASTER FILE SEQUENCE NO. 92201									
1M 3419 B	CABLE	43	1-5C	12	11	WGE	291.0	R00	CONDUITS: 1M3332B, 3331B, 3329B, 3328B, 3202B, 3204B CABLES: PF-B FROM: 1-L-571, PNL 11, XAS, 706 VIA: 1M3300B TO: PENT 37, AZ153, 698 FOR: POST ACD SMPLG CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 9, XAS, 706 FOR: POST ACD SMPLG
MASTER FILE SEQUENCE NO. 92202									
1M 3420 B	CABLE	43	5-1C	12	11	WPB	750.0	R00	CONDUITS: 1M3304B, 3312B, 3313B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 9, XAS, 706 FOR: POST ACD SMPLG
MASTER FILE SEQUENCE NO. 92203									
1M 3421 B	CABLE	43	1-4C	10	11	WFD	226.0	R01	CONDUITS: 1M3330B, 3329B, 3328B, 3241B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 9, XAS, 706 FOR: POST ACD SMPLG
MASTER FILE SEQUENCE NO. 97354									
1M 3421 B	CABLE	43	1-4C	10	11	WFD	142.0	R01	CONDUITS: 1M3330B, 3329B, 3328B, 3241B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 9, XAS, 706 FOR: POST ACD SMPLG
MASTER FILE SEQUENCE NO. 97355									
1M 3422 B	CABLE	43	1-5C	12	11	WGE	150.0	R00	CONDUITS: 1M3330B, 3329B, 3328B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 9, XAS, 706 VIA: 1M3202B, 3209B TO: 1-FSV-43-341, AZ288, 700 FOR: POST ACD SMPLG
MASTER FILE SEQUENCE NO. 92206									
1M 3423 B	CABLE	43	1-4C	10	11	WFD	226.0	R01	CONDUITS: 1M3330B, 3331B, 3329B, 3328B, 3202B, 3204B CABLES: NZ-B NX-B LT-B FROM: 1-M-10, NCS, 732 TO: 1-L-571, PNL 13, XAS, 706 FOR: POST ACD SMPLG
MASTER FILE SEQUENCE NO. 97356									

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

ECN L5200

FCR 1845

CONDUIT OR CABLE NO.	CONDUIT SIZE	NO. COND.	MCM	TYPE CABLE	SCALED LENGTH	REVISION
1M3459 B	3I	0		CON	0.0	R00
VOLTAGE LEVEL: 11 FROM: CABLE TRAY (JE-B) 706 TO: 1-M-10 RISER ,732 FOR: 1M3413B, 3417B, 3421B, 3423B, 3425B, 3405B						
CONDUIT ROUTING: TRAY ROUTING: REEL NO. SNP _____ SNP _____ FIELD CABLE LENGTH _____ FIELD CONDUIT LENGTH I _____ A _____ FI _____ FOREMAN _____ DATE _____						

SQ-FCR-2089

WP 10328

PAGE 18-106 OF 23

Calculations complete for route specified per conduit and cable schedule, and field may begin installation.

Verified by: *[Signature]*

Cognizant Engineer

Date

TO BE SPECIFIED BY COGNIZANT ENGINEER: Maximum allowable pulling force * lbs. (6.2)
Minimum pulling radius 13.4 inches. Minimum training radius 13.4 inches. (6.1.4)

1. Cable released to be pulled as routed. Verified by: *[Signature]*

Inspector

Date

Reel or Contract No(s). SNPM-85-0175 / CONTR. 80K8-827337

COMMENTS: * SEE ATTACHED FOR MAPS FOR SECTIONS OF ROUTE
SHEETS

*NOTE: FOREMAN TO FILL OUT FIELD CABLE LENGTH.

Cable No. IPP562B

No. of

Conductors 3-1C

AWG/

MCM 2/0

Voltage

Level 15

Type Cable

Field Cable

or Mark No. WNB-1

Length* 320' ft.

[Signature]

Foreman

Date

From: 6900 104 SD BD 1B-B, PNL 18, TA12, EL 734

To: CENTRIFUGAL CHARGING PMP MTR 1B-B, UA4, EL 669

For: CENTRIFUGAL CHARGING PMP 1B-B

Tray and Conduit Routing: IPP562B

PARTIAL SIGNOFFS (May be Continued on Back)

FROM	TO	INSPECTOR SIGNATURE	DATE
JB 607 ASES	1B-B (NOT IN FLEXIT MTR)	<u><i>[Signature]</i></u>	<u>04/786</u>
JB 607 To Shut Down Pump Room PNL 18	CENTRIFUGAL CHARGING PMP	<u><i>[Signature]</i></u>	<u>04/2986</u>

2. Verification that cable is pulled as specified above and meets the installation requirements of this procedure (6.5.1.5).

Inspector Signature

Date

3. Verification that all cable tray covers have been reinstalled, if applicable (6.5.1.6). QC inspections and signoffs required in Category I structures.

Inspector Signature

Date

WP No.

11783

Page VII-a-4 of VII-a-26

SQNP
AI-19 Part IV
ATTACHMENT 3
Page 2 of 4
Revision 10

Workplan No. 11783
Page II-21 of II-32

Step Number	Description	Ref. Document
<u>III</u>	WORK INSTRUCTIONS (CONT) H.) TERMINATE NEW CABLE PER M+AI-7. QA IS REQ'D TO INSPECT AND SIGNOFF M+AI-7 DATA SHEETS IN SECTION <u>VII-C</u> .	NOTE: ELECT FOREMAN WILL COORDINATE WITH DPSO TO HI POT 6.9KV CENT CHARGING PUMP CABLE AFTER TERMINALS ARE INSTALLED ON EACH END. DPSO TEST DATA WILL BE ADDED TO SECTION <u>X-e</u> OF WORKPLAN. DPSO WILL PERFORM TEST PER S&P INSTRUCTION II No. 11.
<u>IV</u>	ELECTRICAL FOREMAN SHALL SIGN WORKPLAN THAT ALL WORK AREAS HAVE BEEN LEFT CLEAN.	
	<u>U. R. Doherty</u> ELECT FOREMAN	<u>5/19/86</u> DATE

☒ CHECK BLOCK FIELD CABLE NO. IF QA INSPECTIONS & SIGOFFS ARE REQUIRED

SNP M1A1-7
CABLE TERMINATION/SPLICE
DATA SHEET 1 - ATTACHMENT III

WP OR NR NO. 11783
PAGE 2 OF 4

5.1.1 CABLE NO. OF PANEL 1PP562B
WIRE NOS. ☐

5.1.1 REFERENCE DWG(S) END 1 33-47035D 483-2
AND LOCATION(S) END 2 15-D, 18-B Panel #18
45N1724-2
Cent. Chg. Pmp. 18-B

5.1.4 METER NO./CALIB. DUE DATE N/A

5.1.4 CONTINUITY CHECKS ACCEPT. M. Burch 5/15/86
INSPECTOR /DATE

5.1.5 MUGGER NO/CAL. DUE DATE 463112 8/6/86

5.1.5 MECH-EE CHECKS ACCEPTABLE M. Burch 5/15/86
INSPECTOR /DATE

5.1.6 CHIMING TOOL NO.1 END 1 E01086 15-7-87 END 1
TOOL CALIB. DUE DATE END 2 E01086 15-7-87 END 2

5.1.6 SOLIDFIBER AND/OR CHIMES ACCEPTABLE END 1 M. Burch 5-8-86 END 1
INSPECTOR /DATE

END 2 M. Burch 5-12-86 END 2
INSPECTOR /DATE

5.1.7 RAYCHECK AND/OR END 1 M. Burch 5-8-86 END 1
INSPECTOR /DATE

TAPPING ACCEPTABLE END 2 WDEGL 5/16/86
INSPECTOR /DATE

5.1.8 CAME OR PANEL END 1 M. Burch 5/15/86
WIRE(S) PROPERLY IDENTIFIED, SECURED AND TERMINATED END 2 WDEGL 5/16/86
INSPECTOR /DATE

REMARKS: *Phones

*Verified installation of splice kit. Mte. leads to field cable. WDE 5/16/86

NOTES: FOR SPLICE LIST NUMBER OF CONDUCTORS AND SIZE (AWG/MCM) INSIDE CABLE NO. OF PANEL WIRE(S) AND FOR END 2 CONDUCTORS, PARTIAL SIGOFFS WILL BE MADE IN "REMARKS" SECTION AND MAY BE CONTINUED ON BACK OF DATA SHEET.

Step Number	Description	Ref. Document
<u>III</u>	WORK INSTRUCTIONS (CONT)	
	4) REMOVAL OF CABLE (CONT)	NOTE: SHOULD CONDUIT BEING
	5) (CONT) M+AI-13. QA INSPECTION	REMOVED PASS THROUGH WALLS OR
	REQ'D AND SIGNOFFS ON	FLOORS SEAL/CAP SLEEVES
	M+AI-13 DATA SHEETS IN	PER M+AI-13 (45N880-26).
	SECTION III-f.	
	6) REMOVE CONDUIT (EXISTING) 4I-	NOTE:
	IPP 562-B PER DRAWING	NEW CONDUIT
	45N828-14 R 40. FOREMAN	IPP562B COMES
	SHALL SIGN WORKPLAN VERIFYING	IN BOTTOM OF
	CONDUIT HAS BEEN REMOVED.	6900V SD BD 1B-B
	<u>D. R. Dahl</u>	PNL 18. REF
	ELECT FOREMAN	DRAWING 45N828-2.
	5/19/86	
	DATE	

Step Number	Description	Ref. Document
<u>III</u>	WORK INSTRUCTIONS (CONT)	
	4) REMOVAL OF CABLE (CONT)	NOTE: CRAFT SHALL
	3) CONT) NECESSARY WITH RTV	VERIFY MOTOR PHASE MARKINGS
	FOAM. REFERENCE WP STEPS	(A,B+C) or (T ₁ , T ₂ +T ₃) are
	III E.3.a through III E.5.	same as PNL MARKINGS
	4) REMOVE CABLE COMPLETELY IF	FOR THE POWER CABLES.
	POSSIBLE IF NOT, ABANDON	THIS SHOULD REASONABLY
	THE EXISTING CABLES AS	ASSURE THAT WHEN NEW
	FAR BACK AS POSSIBLE	POWER CABLES ARE HOOKED
	ON BOTH ENDS AND TAG	UP THE ROTATION WILL BE
	AS FOLLOWS: "WP11783"	CORRECT.
	CABLE #, "ABANDON". PLACE	
	RAYCHEM END CAP OVER	
	BOTH ENDS OF ABANDON	
	CABLE.	
	5) SEAL CONDUITS PER	

Step Number	Description	Ref. Document
<u>III</u>	<u>WORK INSTRUCTIONS (CONT)</u>	
	<u>F) INST OF TSI FIRE BARRIER (CONT)</u>	
	<u>6) ON CONDULETS THAT HAVE BEEN SEALED PLACE A TAG SAYING "SEALED WP 11783"</u>	
	<u>G) REMOVAL OF CABLE</u>	
	<u>1) LIFT EXISTING CABLES IPP562B, IPP564B, IPL3011B AND IPL3013B. NOTE: OBTAIN H.O. BEFORE LIFTING CABLES. ELECT FOREMAN SHALL VERIFY SE HAS SIGNED STEP XI ON PG</u>	<u>REF FOLLOWING TVA AND VENDOR DRAWINGS</u> <u>45N1760-1</u> <u>45N1760-7</u> <u>45N1724-2</u> <u>CONTRACT 54499</u>
	<u>2) OBTAIN PHYSI-13 PRIOR TO BREECHING FIRE BARRIER.</u>	<u>I-2. 33-47035-D463</u>
	<u>3) SEAL CONDUIT SEALS AS</u>	

-36-

1/2 # 1/2 1/2 1/2

SQNP
AI-19 Part IV
ATTACHMENT 3
Page 2 of 4
Revision 10

Workplan No. 11783
Page II-16 of II-32

Step Number	Description	Ref. Document
<u>III</u>	<u>WORK INSTRUCTIONS (CONT)</u>	
	<u>F) INST OF TSI FIRE BARRIER (CONT)</u>	
	<u>2) EN DES HANGER PERSONNEL</u>	
	<u>ARE TO APPROVE THE ASSEMBLING</u>	
	<u>OF FIRE BARRIER MATERIAL</u>	
	<u>AROUND CONDUIT AND HANGERS</u>	
	<u>PRIOR TO THE MATERIAL</u>	
	<u>BEING APPLIED. EN DES</u>	
	<u>SIGNOFFS ARE ON "SUPPORT</u>	
	<u>EVALUATION BY EN DES"</u>	
	<u>DATA SHEETS IN SECTION</u>	
	<u>III-h.</u>	
	<u>3) NELSON STUD SIGNOFFS</u>	
	<u>TO BE ON M+AI-11 DATA</u>	
	<u>SHEETS IN SECTION III-e.</u>	
	<u>GA INSPECTION IS REQ'D.</u>	

SQNP
AI-19 Part IV
ATTACHMENT 3
Page 2 of 4
Revision 10

Workplan No. 11783
Page II-15 of II-32

Step Number	Description	Ref. Document
<u>III</u>	WORK INSTRUCTIONS (CONT)	
	E) INSTALLATION OF CABLE (CONT)	
	G) SPLICE AND REPAIR CABLES	
	AS NECESSARY PER MAI-7	
	QA INSPECTION AND SIGNOFF	
	ON MAI-7 DATA SHEET	
	IN SECTION VII-C IS	
	REQUIRED.	
	F) INSTALLATION OF TSI FIRE	
	BARRIER	
	I) INSTALL TSI FIRE BARRIER	Ref: INTERACTION
	MATERIAL ON CONDUITS	68 SKETCHES
	PER CONDUIT AND GROUNDING	
	DRAWINGS AND INTERACTION	
	68 SKETCHES IN THE AUX	
	BUILDING. REF WP 11547.	

SQNP

AI-19 Part IV

ATTACHMENT 3

Page 2 of 4

Revision 10

Workplan No. 11783
Page II-14 of II-32

Step Number	Description	Ref. Document
<u>III</u>	<u>WORK INSTRUCTIONS (CONT)</u>	
	<u>E) INSTALLATION OF CABLE (CONT)</u>	
	<u>3) d) (CONT) one at a time thru</u>	
	<u>the conduit using a fish tape</u>	
	<u>4) AFTER CABLES ARE PULLED</u>	
	<u>THRU THE CONDUIT, REINSTALL</u>	
	<u>CERAFIBER AND RTV SEALANT</u>	
	<u>PER MAI-13. QA IS REQUIRED</u>	
	<u>TO INSPECT AND SIGN OFF</u>	
	<u>MAI-13 DATA SHEETS IN</u>	
	<u>SECTION III f.</u>	
	<u>5) CRAFT MAY REMOVE</u>	
	<u>ENOUGH RTV FOAM TO</u>	
	<u>ALLOW INSTALLATION OF</u>	
	<u>CERAFIBER AND RTV</u>	
	<u>SEALANT INTO CONDUIT.</u>	

SQNP
 AF-19 Part IV
 ATTACHMENT 3
 Page 2 of 4
 Revision 10

Workplan No. 11783
 Page 11-13 of 11-32

Step Number	Description	Ref. Document
III	WORK INSTRUCTIONS (CONT)	
	E) INSTALLATION OF CABLE (CONT)	
	3) WHERE CONDUIT PENETRATES ABSCÉ BOUNDARY FOLLOW THE PROCEEDING STEPS:	
	a) Remove the silicone RTV sealant and cerafiber from one side of the conduit.	
	b) Seal the conduit with silicone RTV foam (Sewkit). NO QA INSPECTION REQ'D.	
	c) After the RTV foam sets up, remove cerafiber & silicone RTV sealant from other side of sleeve.	
	d) Craft may then pull cable(s)	

Step Number	Description	Ref. Document
<u>III</u>	WORK INSTRUCTIONS (CONT)	
	D) 6) CORE DRILLING + BREACHING (CONT)	
	AND SEAL BOTH SIDES PER	
	M&AI-13. QA IS REQUIRED TO	
	INSPECT AND SIGNOFF M&AI-13	
	DATA SHEETS IN SECTION III-f	
	E) INSTALLATION OF CABLE	
	1) INSTALL CABLES AS REQ'D	Note: Cable #'s
	PER M&AI-4. QA IS REQ'D	to be installed
	TO INSPECT AND SIGNOFF	are as follows
	M&AI-4 DATA SHEETS IN	1PP562B
	SECTION III-a.	1PP564B
	2) OBTAIN A PHYSI-13 PRIOR	1PL3011B
	TO BREACHING FIRESTOP	1PL3013B
	PENETRATION FOR CABLE PULL	

SQNP
AI-19 Part IV
ATTACHMENT 3
Page 2 of 4
Revision 10

Workplan No. 11783
Page II-5 of II-32

Step Number	Description	Ref. Document
<u>III</u>	<u>WORK INSTRUCTIONS</u>	
	A) INSTALLATION OF CONDUIT	See Section <u>IV</u>
	1) INSTALL CONDUITS LISTED	of WP. for
	BELOW PER M+AI-6. REFERENCE	Conduit and
	INTERACTION 68 SKETCHES	Grounding
	(FOUND IN SECTION X-b of WP)	drawings.
	AND CONDUIT + GROUNDING	
	DRAWINGS. QA REQ'D TO INSPECT	
	AND SIGNOFF WP IN SECTION	
	<u>VII-b</u>	
	2) CONDUITS TO BE INSTALLED	
	ARE LISTED BELOW.	
	IPP562B IPL 3013B	
	IPP564B IPL 3018B	
	IPP3011B	

AI-19 Part IV
ATTACHMENT 3
Page 2 of 4
Revision 10

Workplan No.
Page II-2 of II-32 11783

ep ber	Description	Ref. Document
C.	<u>PURPOSE</u> The purpose of this workplan is to reroute cables IPP562B, IPP564B, IPL3011B and IPL3013B in accordance with 10 CFR 50 Appendix R Ecn 6235. This workplan will clear Appendix R interaction 68. The cables in this interaction are the power supply and control power to Centrifugal Charging Pump IB-B and the Centrifugal Charging Pump IB-B Room Coder.	

WORKPLAN - 11783

ECN - L6235

CONDUIT NUMBER - 1PP562B

CABLE IDENTIFIER NUMBER(S)	CABLE SIZE (AWG) O.D. (MCM) (In.)	LARGEST COND. OD (Inches)	NUMBER OF COND.	F _{max} (lbs.)	MPR (Inches)	MTR (Inches)
1PP562B	2/0 1.117	1.117	3-1C	2555.52	13.404	13.404

THE CALCULATED MAXIMUM ALLOWABLE PULLING FORCE FOR
YOUR 3 POWER & CONTROL CABLE(S) IS: 2555.52 lbs.

WORKPLAN - 11783

ECN - L6235

CONDUIT SIZE-NUMBER - 4I-1PP562B

FOR THE FOLLOWING CABLE(S): FROM PULL POINT B TO PULL POINT A

1PP562B

DE VALUE NO.	CASE	LENGTH, RADIUS, OR DEGREES	T _{exp}	SWP
T(1)	1	3.83 ft.	2.92460715 lbs.	0 lbs./ft.
T(2)	8	20 deg. R=1.17 ft.	2.741178425737 lbs.	1.236587759826 lbs./ft.
T(3)	2	.67 ft. 20 deg.	3.710036541353 lbs.	0 lbs./ft.
T(4)	5	20 deg. R=1.17 ft.	4.70121305657 lbs.	2.120789536173 lbs./ft.
T(5)	1	3.33 ft.	7.24401770657 lbs.	0 lbs./ft.

WP 11783
PAGE VII-a-6 OF VII-a-26

.6)	8	90 deg. R=1.17 ft.	14.30467068153 lbs.	6.453057016293 lbs./ft.
T(7)	2	6.92 ft. 90 deg.	29.04427068153 lbs.	0 lbs./ft.
T(8)	5	5 deg. R=1.17 ft.	30.05944788189 lbs.	13.56027939257 lbs./ft.
T(9)	2	2 ft. 85 deg.	34.43634241764 lbs.	0 lbs./ft.
T(10)	8	5 deg. R=1.17 ft.	35.05312464794 lbs.	15.81300380753 lbs./ft.
T(11)	2	7.83 ft. 90 deg.	51.73102464794 lbs.	0 lbs./ft.
T(12)	5	35 deg. R=1.17 ft.	65.49107594582 lbs.	29.54403191417 lbs./ft.
T(13)	2	5 ft. 55 deg.	76.4049743909 lbs.	0 lbs./ft.
T(14)	8	35 deg. R=1.17 ft.	94.63816586964 lbs.	42.69273259558 lbs./ft.
T(15)	2	2.5 ft. 90 deg.	99.96316586964 lbs.	0 lbs./ft.

Wc=1.195 , WEIGHT OF CABLE(S)= 2.13 , CONDUIT I.D.=4.03 , COEFF. OF FRICT.=.3585

YOUR SIDEWALL PRESSURE VALUE = 42.69273259558 lbs./ft.

MANUFACTURERS RECOMMENDED SWP=300 lbs./ft.

THE MAXIMUM ALLOWABLE PULLING TENSION FOR
THE 3 CABLE(S) IS = 664.6381658696 lbs.

WP 11783
PAGE VII-a-7 OF VII-a-26

WORKPLAN - 11783

ECN - L6235

CONDUIT SIZE-NUMBER - 41-1PP562B

FOR THE FOLLOWING CABLE(S): FROM PULL POINT C TO PULL POINT B

1PP562B

NODE VALUE NO.	CASE	LENGTH, RADIUS, OR DEGREES	Texp	SWP
T(1)	1	6.67 ft.	5.09324535 lbs.	0 lbs./ft.
T(2)	4	90 deg. R=1.17 ft.	8.944561588579 lbs.	4.035029341248 lbs./ft.
T(3)	3	4.58 ft. 10 deg.	10.69473304518 lbs.	0 lbs./ft.
T(4)	7	35 deg. R=1.17 ft.	13.78575238848 lbs.	6.218964990942 lbs./ft.
T(5)	3	3.75 ft. 45 deg.	10.16255049993 lbs.	0 lbs./ft.
6)	4	90 deg. R=1.17 ft.	17.84708031858 lbs.	8.051092502179 lbs./ft.
T(7)	1	14 ft.	28.53755031858 lbs.	0 lbs./ft.

Wc=1.195 , WEIGHT OF CABLE(S)= 2.13 , CONDUIT I.D.=4.03 , COEFF. OF FRICT.=.3585

YOUR SIDEWALL PRESSURE VALUE = 8.051092502179 lbs./ft.

MANUFACTURERS RECOMMENDED SWP=300 lbs./ft.

THE MAXIMUM ALLOWABLE PULLING TENSION FOR
THE 3 CABLE(S) IS = 664.8470803186 lbs.
 WP 11783
 PAGE III-a-8 III-a-26

WORKPLAN - 11783

ECN - L6235

CONDUIT SIZE-NUMBER - 41-1PP562B

FOR THE FOLLOWING CABLE(S): FROM PULL POINT D TO PULL POINT C

1PP562B

NODE VALUE NO.	CASE	LENGTH, RADIUS, OR DEGREES	Texp	SWP
T(1)	1	10.33 ft.	7.88803965 lbs.	0 lbs./ft.
T(2)	4	90 deg. R=1.17 ft.	10.45324948408 lbs.	4.71562166149 lbs./ft.
T(3)	2	2.8 ft. 30 deg.	15.28689320376 lbs.	0 lbs./ft.
T(4)	4	45 deg. R=1.17 ft.	20.25822835403 lbs.	9.138798475554 lbs./ft.
T(5)	1	17 ft.	33.23951335403 lbs.	0 lbs./ft.
T(6)	7	20 deg. R=1.17 ft.	38.24388068643 lbs.	17.25240294504 lbs./ft.
T(7)	3	2.58 ft. 20 deg.	38.21563246873 lbs.	0 lbs./ft.
T(8)	6	20 deg. R=1.17 ft.	42.81345061413 lbs.	19.31380624051 lbs./ft.
T(9)	1	3.83 ft.	45.73805776413 lbs.	0 lbs./ft.
T(10)	7	30 deg. R=1.17 ft.	55.71104567376 lbs.	25.13210979645 lbs./ft.
T(11)	3	1.75 ft. 30 deg.	55.00457299856 lbs.	0 lbs./ft.

WP 11783
 PAGE 11783-9 11783-20

T(12)	6	30 deg. R=1.17 ft.	65.48784367325 lbs.	29.54257378629 lbs./ft.
T(13)	1	3.25 ft.	67.96955992325 lbs.	0 lbs./ft.
T(14)	8	30 deg. R=1.17 ft.	81.47535057831 lbs.	36.75478411281 lbs./ft.
T(15)	2	3.25 ft. 30 deg.	87.0858298958 lbs.	0 lbs./ft.
T(16)	5	30 deg. R=1.17 ft.	105.9419225248 lbs.	47.79203112666 lbs./ft.
T(17)	1	1.75 ft.	107.2782312748 lbs.	0 lbs./ft.
T(18)	7	30 deg. R=1.17 ft.	129.9582667515 lbs.	58.62617348954 lbs./ft.
T(19)	3	3.25 ft. 30 deg.	128.646246069 lbs.	0 lbs./ft.
T(20)	6	30 deg. R=1.17 ft.	154.3353276675 lbs.	69.62304070045 lbs./ft.
T(21)	1	2 ft.	155.8625376675 lbs.	0 lbs./ft.

Wc=1.195 , WEIGHT OF CABLE(S)= 2.13 , CONDUIT I.D.=4.03 , COEFF. OF FRICT.=.3585

.....
YOUR SIDEWALL PRESSURE VALUE = 69.62304070045 lbs./ft.

.....
MANUFACTURERS RECOMMENDED SWP=300 lbs./ft.

.....
THE MAXIMUM ALLOWABLE PULLING TENSION FOR
THE 3 CABLE(S) IS = 664.3353276675 lbs.
.....

WORKPLAN - 11783

ECN - L6235

CONDUIT SIZE-NUMBER - 4I-1PP562B

FOR THE FOLLOWING CABLE(S): FROM PULL POINT E TO PULL POINT F

1PP562B

NODE VALUE NO.	CASE	LENGTH, RADIUS, OR DEGREES	Texp	SWP
T(1)	1	2 ft.	1.52721 lbs.	0 lbs./ft.
T(2)	7	10 deg. R=1.17 ft.	2.156091790939 lbs.	.9726461775353 lbs./ft.
T(3)	3	4.25 ft. 10 deg.	3.780159190624 lbs.	0 lbs./ft.
T(4)	7	80 deg. R=1.17 ft.	5.20437523157 lbs.	2.347773734272 lbs./ft.
T(5)	3	14 ft. 90 deg.	-24.61562476843 lbs.	0 lbs./ft.
T(6)	6	15 deg. R=1.17 ft.	-.3401885607395 lbs.	-.1534642934198 lbs./ft.
T(7)	3	2.33 ft. 75 deg.	-4.33330252883 lbs.	0 lbs./ft.
T(8)	7	15 deg. R=1.17 ft.	.5624311709223 lbs.	.2537213539903 lbs./ft.
T(9)	3	13.58 ft. 90 deg.	-28.36296882908 lbs.	0 lbs./ft.
T(10)	4	45 deg. R=1.17 ft.	0 lbs.	0 lbs./ft.
T(11)	3	3.33 ft.	-4.871229261503 lbs.	0 lbs./ft.

WP 11783
 PAGE VII-a-12 OF VII-a-26

60 deg.

T(12)	4	45 deg. R=1.17 ft.	0 lbs.	0 lbs./ft.
-------	---	-----------------------	--------	------------

T(13)	3	2 ft. 90 deg.	-4.26 lbs.	0 lbs./ft.
-------	---	------------------	------------	------------

Wc=1.195 , WEIGHT OF CABLE(S)= 2.13 , CONDUIT I.D.=4.03 , COEFF. OF FRICT.=.3585

YOUR SIDEWALL PRESSURE VALUE = 0 lbs./ft.

MANUFACTURERS RECOMMENDED SWP=300 lbs./ft.

THE MAXIMUM ALLOWABLE PULLING TENSION FOR
THE 3 CABLE(S) IS = 665 lbs.

WORKPLAN - 11783

ECN - L6235

CONDUIT SIZE-NUMBER - 41-1PP562B

FOR THE FOLLOWING CABLE(S): FROM PULL POINT F TO PULL POINT G

1PP562B

CODE VALUE NO.	CASE	LENGTH, RADIUS, OR DEGREES	Texp	SWP
T(1)	1	11.58 ft.	8.8425459 lbs.	0 lbs./ft.
T(2)	8	90 deg. R=1.17 ft.	17.11194441265 lbs.	7.719461385229 lbs./ft.
T(3)	2	2.83 ft. 90 deg.	23.13984441265 lbs.	0 lbs./ft.

Wc=1.195 , WEIGHT OF CABLE(S)= 2.13 , CONDUIT I.D.=4.03 , COEFF. OF FRICT.=.3585

YOUR SIDEWALL PRESSURE VALUE = 7.719461385229 lbs./ft.

MANUFACTURERS RECOMMENDED SWP=300 lbs./ft.

THE MAXIMUM ALLOWABLE PULLING TENSION FOR
THE 3 CABLE(S) IS = 664.1119444127 lbs.

COMMENTS

INITIAL CALCULATIONS DONE BY:

[Signature]
COGNIZANT ENGINEER

4/17/86
DATE

VERIFIED BY:

[Signature]
SIGNATURE

4/17/86
DATE

WP 11783
PAGE VII-a-14 OF VII-a-26

SUBJECT _____




PROJECT _____

COMPUTED BY _____

DATE _____

CHECKED BY _____

DATE _____



WP 11783

PAGE VII-a-18 OF VII-a-26

69

Workplan No. 11783

ECN No. L 6235

Conduit No. 41-1PP562B

#

max (Total for cable(s))

Approved SWP Value 100

lbs/ft.

Weight of Cable(s) 2.13

lbs/ft.

Weight Correction Factor (W_c) 1.195

K or K_{bar}

0.3585

Cable Identifier Number(s)	Cable O.D.	No. of Cond.	O.D. of Largest Conductor	I_{fac}	AWG or MCM	*MPR	*MIR	Node Value	Case No.	Length of Conduit	Angle from Horiz.	Angle of Bend	R-Radius of Bend (in ft.)	* T_{exp} or T_{out}
7 (1) 1PP562B	1.117	3/16	1.117	12	2/0			11	1	3.83	0°	—	—	—
7 (2)								12	8	—	—	20°	1.17	—
7 (3)								13	2	.67	20°	—	—	—
7 (4)								14	5	—	—	20°	1.17	—
7 (5)								15	1	3.33	0°	—	—	—
7 (6)								16	8	—	—	90°	1.17	—
7 (7)								17	2	6.92	90°	—	—	—
7 (8)								18	5	—	—	5°	1.17	—
7 (9)								19	2	2	85°	—	—	—
7 (10)								110	8	—	—	5°	1.17	—
7 (11)								111	2	7.83	90°	—	—	—
7 (12)								112	5	—	—	35°	1.17	—
7 (13)								113	2	5	55°	—	—	—
7 (14)								114	8	—	—	35°	1.17	—
7 (15)								115	2	2.5	90°	—	—	—

calculated SWP Value

lbs/ft.

*Maximum Allowable Pulling Tension

lbs.

7m: B

: A

le O.D. and O.D. of largest conductor should be entered in inches. Length of conduit runs and bend radius should be entered in feet. All angles should be entered in degrees. This is the F_{max} value which is the total F_{max} value for a single or group cable installation. These values may be written in by user during program initiation if desired.

Place "check" in block if cable is shielded.



Place an "X" in block if cable is an instrumentation-type cable.

FOR A STRAIGHT RUN ENTER (1)
FOR AN INCLINED RUN ENTER (2)
(UPWARD SLOPE) (2)
(DOWNWARD SLOPE) (3)

FOR A BEND

FOR A HORIZONTAL BEND ENTER (4)
FOR A VERTICAL BEND ENTER (5)

FIGURE A (5)
FIGURE B (6)
FIGURE C (7)
FIGURE D (8)
FOR A THREE POINT SADDLE ENTER (9)
FOR A ENDED CONDUIT RUN (10)



Workplan No. 11783ECN No. L 6235Conduit No. 4I-1PP562B#F max (Total for cable(s))Approved SWP Value 100 lbs/ft.Weight of Cable(s) 2.13 lbs/ft.Weight Correction Factor (W_c) 1.195K or K_{bar} 0.3585

Cable Identifier Number(s)	Cable O.D.	No. of Cond.	O.D. of Largest Conductor	I _{fac}	AWG or MCM	*MPR	*MTR	Node Value	Case No.	Length of Conduit	Angle from Horiz.	Angle of Bend	R=Radius of Bend (in ft.)	*T _{exp} or T _{out}
☐ (1) <u>1PP562B</u>	<u>1.117</u>	<u>3/1c</u>	<u>1.117</u>	<u>12</u>	<u>2/0</u>			<u>T1</u>	<u>1</u>	<u>6.67'</u>	<u>0°</u>	<u>—</u>	<u>—</u>	
☐ (2)								<u>T2</u>	<u>4</u>	<u>—</u>	<u>—</u>	<u>90°</u>	<u>1.17</u>	
☐ (3)								<u>T3</u>	<u>3</u>	<u>4.58'</u>	<u>10°</u>	<u>—</u>	<u>—</u>	
☐ (4)								<u>T4</u>	<u>7</u>	<u>—</u>	<u>35°</u>	<u>35°</u>	<u>1.17</u>	
☐ (5)								<u>T5</u>	<u>3</u>	<u>3.75'</u>	<u>45°</u>	<u>—</u>	<u>—</u>	
☐ (6)								<u>T6</u>	<u>4</u>	<u>—</u>	<u>—</u>	<u>90°</u>	<u>1.17</u>	
☐ (7)								<u>T7</u>	<u>1</u>	<u>14'</u>	<u>0°</u>	<u>—</u>	<u>—</u>	
☐ (8)								<u>T</u>						
☐ (9)								<u>T</u>						
☐ (10)								<u>T</u>						
☐ (11)								<u>T</u>						
☐ (12)								<u>T</u>						
☐ (13)								<u>T</u>						
☐ (14)								<u>T</u>						
☐ (15)								<u>T</u>						

*Calculated SWP Value _____ lbs/ft.

*Maximum Allowable Pulling Tension _____ lbs.

From: CTo: B

Cable O.D. and O.D. of largest conductor should be entered in inches. Length of conduit runs and bend radius should be entered in feet. All angles should be entered in degrees.

#This is the F_{max} value which is the total F_{max} value for a single or group cable installation.

*These values may be written in by user during program initiation if desired.

☒ Place "check" in block if cable is shielded.

☒ Place an "X" in block if cable is an instrumentation-type cable.

FOR A STRAIGHT RUN ENTER (1)

FOR AN INCLINED RUN ENTER

(UPWARD SLOPE)..... (2)

(DOWNWARD SLOPE)..... (3)

FOR A BEND

FOR A HORIZONTAL BEND ENTER (4)

FOR A VERTICAL BEND ENTER

FIGURE A (5)


FIGURE B (6)

FIGURE C (7)


FIGURE D (8)

FOR A THREE POINT SADDLE ENTER..... (9)


FOR AN EMBEDDED CONDUIT RUN..... (10)



(CASE 5)



(CASE 6)



(CASE 7)



(CASE 8)

--Expected Pulling Force Around a Vertical Bend

WP 11783PAGE VI-20 OF VI-26

Page _____ of _____

Workplan No. 11783ECN No. L 6235Conduit No. 4I-1PP562B#F_{max}

(Total for cable(s))

Approved SWP Value 100 lbs/ft.Weight of Cable(s) 2.13 lbs/ft.Weight Correction Factor (W_c) 1.195K or K_{bar} 0.3585

Cable Identifier Number(s)	Cable O.D.	No. of Cond.	O.D. of Largest Conductor	I _{fac}	AWG or MCM	*MPR	*MTR	Node Value	Case No.	Length of Conduit	Angle from Horiz.	Angle of Bend	R=Radius of Bend (in ft.)	*T _{exp} or T _{out}
☒ (1) <u>1PP562B</u>	<u>1.117</u>	<u>3/1C</u>	<u>1.117</u>	<u>12</u>	<u>2/0</u>			T 1	1	<u>10.33'</u>	<u>0°</u>	—	—	
☐ (2)								T 2	4	—	—	<u>45°</u>	<u>1.17</u>	
☐ (3)								T 3	2	<u>2.8'</u>	<u>30°</u>	—	—	
☐ (4)								T 4	4	—	—	<u>45°</u>	<u>1.17</u>	
☐ (5)								T 5	1	<u>17'</u>	<u>0°</u>	—	—	
☐ (6)								T 6	7	—	—	<u>20°</u>	<u>1.17</u>	
☐ (7)								T 7	3	<u>2.58'</u>	<u>20°</u>	—	—	
☐ (8)								T 8	6	—	—	<u>20°</u>	<u>1.17</u>	
☐ (9)								T 9	1	<u>3.83'</u>	<u>0°</u>	—	—	
☐ (10)								T 10	7	—	—	<u>30°</u>	<u>1.17</u>	
☐ (11)								T 11	3	<u>1.75'</u>	<u>30°</u>	—	—	
☐ (12)								T 12	6	—	—	<u>30°</u>	<u>1.17</u>	
☐ (13)								T 13	1	<u>3.25'</u>	<u>0°</u>	—	—	
☐ (14)								T 14	8	—	—	<u>30°</u>	<u>1.17</u>	
☐ (15)								T 15	2	<u>3.25'</u>	<u>30°</u>	—	—	

*Calculated SWP Value _____ lbs/ft.

*Maximum Allowable Pulling Tension _____ lbs.

From: DTo: C

Cable O.D. and O.D. of largest conductor should be entered in inches. Length of conduit runs and bend radius should be entered in feet. All angles should be entered in degrees.

*This is the F_{max} value which is the total F_{max} value for a single or group cable installation.

*These values may be written in by user during program initiation if desired.

☒ Place "check" in block if cable is shielded.

☒ Place an "X" in block if cable is an instrumentation-type cable.

FOR A STRAIGHT RUN ENTER (1)

FOR AN INCLINED RUN ENTER

(UPWARD SLOPE)..... (2)

(DOWNWARD SLOPE)..... (3)

FOR A BEND

FOR A HORIZONTAL BEND ENTER (4)

FOR A VERTICAL BEND ENTER

FIGURE A (5)


FIGURE B (6)

FIGURE C (7)


FIGURE D (8)

FOR A THREE POINT SADDLE ENTER..... (9)


FOR AN EMBEDDED CONDUIT RUN (10)




(CASE 5)



(CASE 6)



(CASE 7)



(CASE 8)

---Expected Pulling Force Around a Vertical Bend

WP 11783PAGE VII-a-21 OF VII-a-26

Page _____ of _____

Workplan No. 11783 ECN No. L 6235 Conduit No. 4I-1PD562B #F max (Total for cable(s))
 Approved SWP Value 100 lbs/ft. Weight of Cable(s) 2.13 lbs/ft. Weight Correction Factor (W_c) 1.195 K or K_{bar} 0.3585

Cable Identifier Number(s)	Cable O.D.	No. of Cond.	O.D. of Largest Conductor	I _{fac}	AWG or MCM	*MPR	*MTR	Node Value	Case No.	Length of Conduit	Angle from Horiz.	Angle of Bend	R=Radius of Bend (in ft.)	*T _{exp} or T _{out}
☒ (1) 1PP562B	1.117	3/1C	1.117	12	2/0			T 16	5	—	—	30°	1.17	
☐ (2)								T 17	1	1.75'	0°	—	—	
☐ (3)								T 18	7	—	—	30°	1.17	
☐ (4)								T 19	3	3.25°	30°	—	—	
☐ (5)								T 20	6	—	—	30°	1.17	
☐ (6)								T 21	1	2'	0°	—	—	
☐ (7)								T						
☐ (8)								T						
☐ (9)								T						
☐ (10)								T						
☐ (11)								T						
☐ (12)								T						
☐ (13)								T						
☐ (14)								T						
☐ (15)								T						


Calculated SWP Value _____ lbs/ft. *Maximum Allowable Pulling Tension _____ lbs.

rom: D
 o: C

Cable O.D. and O.D. of largest conductor should be entered in inches. Length of conduit runs and bend radius should be entered in feet. All angles should be entered in degrees. This is the F_{max} value which is the total F_{max} value for a single or group cable installation. These values may be written in by user during program initiation if desired.

- ☒ Place "check" in block if cable is shielded.
- ☒ Place an "X" in block if cable is an instrumentation-type cable.

- FOR A STRAIGHT RUN ENTER (1)
 FOR AN INCLINED RUN ENTER:
 (UPWARD SLOPE)..... (2)
 (DOWNWARD SLOPE)..... (3)
- FOR A BEND:
- FOR A HORIZONTAL BEND ENTER (4)
 FOR A VERTICAL BEND ENTER:
 FIGURE A (5)
 FIGURE B (6)
 FIGURE C (7)
 FIGURE D (8)
 FOR A THREE POINT SADDLE ENTER... (9)
 FOR AN EMBEDDED CONDUIT RUN.....(10)



WP 11783
 PAGE VII-a-22 VII-a-26

Workplan No. 11783 ECN No. L 6235 Conduit No. 4I-1PP562B #F max (Total for cable(s))
Approved SWP Value 100 lbs/ft. Weight of Cable(s) 2.13 lbs/ft. Weight Correction Factor (W_c) 1.195 K or K_{bar} 0.3585


Cable Identifier Number(s)	Cable O.D.	No. of Cond.	O.D. of Largest Conductor	I fac	AWG or MCM	*MPR	*MTR	Node Value	Case No.	Length of Conduit	Angle from Horiz.	Angle of Bend	R=Radius of Bend (in ft.)	*T _{exp} or T _{out}
7 (1) 1PP562B	1.117	3/10	1.117	12	2/0			T ₁	1	10.25	0°	-	-	
7 (2)								T ₂	4	-	-	90°	1.17	
7 (3)								T ₃	1	4.33'	0°	-	-	
7 (4)								T ₄	8	-	-	30°	1.17	
7 (5)								T ₅	2	2'	30°	-	-	
7 (6)								T ₆	5	-	-	30°	1.17	
7 (7)								T ₇	1	3.33'	0°	-	-	
7 (8)								T ₈	4	-	-	90°	1.17	
7 (9)								T ₉	1	3'	0°	-	-	
7 (10)								T						
7 (11)								T						
7 (12)								T						
7 (13)								T						
7 (14)								T						
7 (15)								T						

Calculated SWP Value _____ lbs/ft. *Maximum Allowable Pulling Tension _____ lbs.
from: D
to: E

able O.D. and O.D. of largest conductor should be entered in inches. Length of conduit runs and bend radius should be entered in feet. All angles should be entered in degrees.
This is the F_{max} value which is the total F_{max} value for a single or group cable installation.
These values may be written in by user during program initiation if desired.

Place "check" in block if cable is shielded.
Place an "X" in block if cable is an instrumentation-type cable.

- FOR A STRAIGHT RUN ENTER: (1)
FOR AN INCLINED RUN ENTER:
(UPWARD SLOPE).....: (2)
(DOWNWARD SLOPE).....: (3)
FOR A BEND:
FOR A HORIZONTAL BEND ENTER: (4)
FOR A VERTICAL BEND ENTER:
FIGURE A: (5)
FIGURE B: (6)
FIGURE C: (7)
FIGURE D: (8)
FOR A THREE POINT SADDLE ENTER.....: (9)
FOR AN EMBEDDED CONDUIT RUN.....: (10)



Workplan No. 11783

ECN No. L 6235

Conduit No. 4I-1PP5G2B

#F

(Total for cable(s))

Approved SWP Value 100 lbs/ft.

Weight of Cable(s) 2.13 lbs/ft.

Weight Correction Factor (W_c) 1.195

K or K_{bar}

0.3585

Cable Identifier Number(s)	Cable O.D.	No. of Cond.	O.D. of Largest Conductor	I_{fac}	AWG or MCM	*MPR	*MTR	Node Value	Case No.	Length of Conduit	Angle from Horiz.	Angle of Bend	R=Radius of Bend (in ft.)	*T _{exp} or T _{out}
☐ (1) <u>1PP5G2B</u>	<u>1.117</u>	<u>3/10</u>	<u>1.117</u>	<u>12</u>	<u>2/0</u>			<u>11</u>	<u>1</u>	<u>2</u>	<u>0°</u>			
☐ (2)								<u>12</u>	<u>7</u>			<u>10°</u>	<u>1.17</u>	
☐ (3)								<u>13</u>	<u>3</u>	<u>4.25</u>	<u>10°</u>			
☐ (4)								<u>14</u>	<u>3</u>			<u>80°</u>	<u>1.17</u>	
☐ (5)								<u>15</u>	<u>3</u>	<u>14'</u>	<u>90°</u>			
☐ (6)								<u>16</u>	<u>6</u>			<u>15°</u>	<u>1.17</u>	
☐ (7)								<u>17</u>	<u>3</u>	<u>2.33'</u>	<u>75°</u>			
☐ (8)								<u>18</u>	<u>7</u>			<u>15°</u>	<u>1.17</u>	
☐ (9)								<u>19</u>	<u>3</u>	<u>13.58'</u>	<u>90°</u>			
☐ (10)								<u>10</u>	<u>4</u>			<u>45°</u>	<u>1.17</u>	
☐ (11)								<u>11</u>	<u>3</u>	<u>3.33'</u>	<u>60°</u>			
☐ (12)								<u>12</u>	<u>4</u>			<u>45°</u>	<u>1.17</u>	
☐ (13)								<u>13</u>	<u>3</u>	<u>2'</u>	<u>90°</u>			
☐ (14)								<u>1</u>						
☐ (15)								<u>1</u>						

*Calculated SWP Value _____ lbs/ft. *Maximum Allowable Pulling Tension _____ lbs.

From: E

To: F

Cable O.D. and O.D. of largest conductor should be entered in inches. Length of conduit runs and bend radius should be entered in feet. All angles should be entered in degrees.

#This is the F_{max} value which is the total F_{max} value for a single or group cable installation.

*These values may be written in by user during program initiation if desired.


☒ Place "check" in block if cable is shielded.

☒ Place an "X" in block if cable is an instrumentation-type cable.

FOR A STRAIGHT RUN ENTER (1)
FOR AN INCLINED RUN ENTER (2)
(UPWARD SLOPE) (2)
(DOWNWARD SLOPE) (3)

FOR A BEND

FOR A HORIZONTAL BEND ENTER (4)
FOR A VERTICAL BEND ENTER (4)
FIGURE A (5)
FIGURE B (6)
FIGURE C (7)
FIGURE D (8)
FOR A THREE POINT SADDLE ENTER (9)
FOR A ENVELOPED CONDUIT RUN (10)



WP 11783

PAGE 11783-24 OF 11783-26

Page _____ of _____

Workplan No. 11783ECN No. 16235Conduit No. 4I-1PP562B#F_{max} _____ (Total for cable(s))Approved SWP Value 100 lbs/ft.Weight of Cable(s) 2.13 lbs/ft.Weight Correction Factor (W_c) 1.195K or K_{bar} 0.3585

Cable Identifier Number(s)	Cable O.D.	No. of Cond.	O.D. of Largest Conductor	I _{fac}	AWG or MCM	*MPR	*MTR	Node Value	Case No.	Length of Conduit	Angle from Horiz.	Angle of Bend	R=Radius of Bend (in ft.)	*T _{exp} or T _{out}
☐ (1) <u>1PP562B</u>	<u>1.117</u>	<u>3/1C</u>	<u>1.117</u>	<u>12</u>	<u>2/0</u>			T 1	1	<u>11.58'</u> <u>2.42'</u>	<u>0°</u>	<u>-</u>	<u>-</u>	
☐ (2) _____								T 2	8	<u>-</u>	<u>-</u>	<u>90°</u>	<u>1.17</u>	
☐ (3) _____								T 3	2	<u>2.83'</u>	<u>90°</u>	<u>-</u>	<u>-</u>	
☐ (4) _____								T						
☐ (5) _____								T						
☐ (6) _____								T						
☐ (7) _____								T						
☐ (8) _____								T						
☐ (9) _____								T						
☐ (10) _____								T						
☐ (11) _____								T						
☐ (12) _____								T						
☐ (13) _____								T						
☐ (14) _____								T						
☐ (15) _____								T						

*Calculated SWP Value _____ lbs/ft.

*Maximum Allowable Pulling Tension _____ lbs.

From: FTo: G

Cable O.D. and O.D. of largest conductor should be entered in inches. Length of conduit runs and bend radius should be entered in feet. All angles should be entered in degrees.

#This is the F_{max} value which is the total F_{max} value for a single or group cable installation.

*These values may be written in by user during program initiation if desired.

☒ Place "check" in block if cable is shielded.

☒ Place an "X" in block if cable is an instrumentation-type cable.

FOR A STRAIGHT RUN ENTER (1)

FOR AN INCLINED RUN ENTER

(UPWARD SLOPE)..... (2)

(DOWNWARD SLOPE)..... (3)

FOR A BEND

FOR A HORIZONTAL BEND ENTER (4)

FOR A VERTICAL BEND ENTER

FIGURE A (5)




FIGURE B (6)

FIGURE C (7)

FIGURE D (8)

FOR A THREE POINT SADDLE ENTER..... (9)

FOR AN EMBEDDED CONDUIT RUN..... (10)




--Expected Pulling Force Around a Vertical Bend

WP 11783
PAGE 11-a-25 OF 11-a-26

Page _____ of _____

734 PANEL



18" EAST OF S
12" N. N. on A12
LENGTH - 38"
CONDUIT - 32 1/2"

18" EAST OF S
3" SOUTH OF A11
LENGTH - 38"
CONDUIT - 33"

INSPECTION OF CONDUIT SEALS

MR # _____

WORKPLAN # _____

Conduit #, Column, Elev. and Building	EL 690 Floor (Top Side) (Condulet) IPP562B	EL 690 Ceiling (East side) IPP562B (JB# 608)	EL 690 Ceiling (South side) IPP562B (JB# 608)
6.E.4.b Cleanliness acceptable	<u>Climent 10/18/86</u>	<u>Climent 10/18/86</u>	<u>Climent 10/18/86</u>
6.E.4.c or f Cerafiber installed for minimum of 1 inch	<u>Climent 10/18/86</u>	<u>Climent 10/18/86</u>	<u>Climent 10/18/86</u>
6.E.4.d or g Conduit sealed per 45W880-26	<u>Climent 10/18/86</u>	<u>Climent 10/18/86</u>	<u>Climent 10/18/86</u>
Conduit #, Column, Elev. and Building	Thermolagged EL 690 Ceiling (North side) IPP562B (JB# 607)	Thermolagged EL 690 Ceiling (South side) IPP562 (JB# 607)	
6.E.4.b Cleanliness acceptable	<u>Climent 10/18/86</u>	<u>McBarrick 10/25/86</u>	<u>A</u>
6.E.4.c or f Cerafiber installed for minimum of 1 inch	<u>Climent 10/18/86</u>	<u>McBarrick 10/25/86</u>	<u>A</u>
6.E.4.d or g Conduit sealed per 45W880-26	<u>Climent 10/18/86</u>	<u>McBarrick 10/25/86</u>	<u>A</u>
Drawings:			

NOTE: All signature blanks to be signed and dated by QA Inspector.

These are all Thermolag Condulet seals DRD 4/18/86

WF 11783

PAGE 4 OF 17

INSPECTION OF CONDUIT SEALS

MR #	INSPECTION OF CONDUIT SEALS			WORKPLAN #
Conduit #, Column, Elev. and Building	5' south of A12, 2' west of T, el 714 Conduit IPP564B	10' west of T, 7' north of A12, el 714 Conduit IPP564B	9' west of T, 7' north of A12, el 714 Conduit IPP562B	
6.E.4.b Cleanliness acceptable	BSR 11/11/85	H. Barnett 12-12-86	H. Barnett 12-12-86	
6.E.4.c or f Cerafiber installed for minimum of 1 inch	BSR 11/11/85	H. Barnett 12-12-86	H. Barnett 12-12-86	
6.E.4.d or g Conduit sealed per 45W880-26	BSR 11/11/85	H. Barnett 12-12-86	H. Barnett 12-12-86	
Conduit #, Column, Elev. and Building	2' south of A3, R line of 114 Conduit IPL 3011B 2188	2' south of A3, 1' east of R, el 714 Conduit IPL 3013B 2186	Made Spare 10' S of A4 2' W of T EL 64 Deleted Conduit IPP562B Floor.	
6.E.4.b Cleanliness acceptable	H. Barnett 12-12-86	H. Barnett 12-12-86	W. E. Zell 15/14/86	
6.E.4.c or f Cerafiber installed for minimum of 1 inch	H. Barnett 12-12-86	H. Barnett 12-12-86	NA 1	
6.E.4.d or g Conduit sealed per 45W880-26	H. Barnett 12-12-86	H. Barnett 12-12-86	* W. E. Zell 15/14/86	
Drawings:	* Metal plug installed on both end of conduit per 45N822-2 Note 11			
NOTE: All signature blanks to be signed and dated by QA Inspector.				

W. E. Zell
5/14/86

WP 11783

PAGE III-2 C. III-17

INSPECTION OF CONDUIT SEALS

MR # _____	NEAR A3/Q LINE EL 734 FLOOR CONDUIT IPL3011B		NEAR A3/Q LINE EL 734 FLOOR CONDUIT IPL3013B		WORKPLAN # _____ 11' No. 2 of AS, 1' west of Thin, at 670 Conduit IPP562B
Conduit #, Column, Elev. and Building					
6.E.4.b Cleanliness acceptable	<u>H. Beal</u>	<u>1/10/7/85</u>	<u>H. Beal</u>	<u>1/10/7/85</u>	<u>M Beal</u> <u>1/3/8/86</u>
6.E.4.c or f Cerafiber installed for minimum of 1 inch	<u>H. Beal</u>	<u>1/10/7/85</u>	<u>H. Beal</u>	<u>1/10/7/85</u>	<u>M Beal</u> <u>1/3/8/86</u>
6.E.4.d or g Conduit sealed per 45W880-26	<u>H. Beal</u>	<u>1/10/7/85</u>	<u>H. Beal</u>	<u>1/10/7/85</u>	<u>M Beal</u> <u>1/3/8/86</u>
Conduit #, Column, Elev. and Building	NEAR A3/R LINE EL 714 FLOOR CONDUIT IPL3011B		NEAR A3/R LINE EL 714 FLOOR CONDUIT IPL3013B		5' N of A12, 2' W of T-Line EL 690 Casing Side ONLY (Plug Removed) Conduit IPP564B for Con. Inst.
6.E.4.b Cleanliness acceptable	<u>N/A</u>		<u>N/A</u>		<u>A. Barnett</u> <u>13-22-86</u>
6.E.4.c or f Cerafiber installed for minimum of 1 inch	<u>N/A</u>		<u>N/A</u>		<u>A. Barnett</u> <u>13-22-86</u>
6.E.4.d or g Conduit sealed per 45W880-26	<u>N/A</u>		<u>N/A</u>		<u>A. Barnett</u> <u>13-22-86</u>
Drawings: _____					

NOTE: All signature blanks to be signed and dated by QA Inspector.

11783

WP 11783PAGE III 1 OF III 20SQNP
M&AI-17
Data Sheet
Attachment A
Page 1 of 2
Rev. 5Date 10/9/85

To be filled in by cognizant engineer:

Workplan/MR No. 11783*I.D. No. 4I-IPDS62 B *For sleeve use mark number.Location/Orientation: AUX BLDG EL 734 G'N of A12 + S'W of TReference Drawings: 45N828-2, -7NOTE: IN
BACK SIDE
OF BD
1B-B
(MDT #18)

To be filled in by Mechanical QC inspector.

Section 6.A.1, 6.A.2

1. Concrete surfaces roughened/free of dirt, dust, foreign matter, etc. H.M. Kim 13-4-86
Inspector Date

Section 6.A.2

2. Surface wetting: H.M. Kim 13-4-86 1630 Complete Almeida 1030586 0515
Inspector Date Time Inspector Date Time

Section 6.B.1 and Attachment A

3. Orientation and alignment of baseplate/sleeve acc.: Almeida 1 030586
Inspector Date

Section 6.C.2, 7.B

4. Type of grout used: 5-STAR Almeida 1 050586
Inspector Date

Section 6.C.6, 6.C.7

5. Grout application completed: Almeida 1 0610 030586
Inspector Time Date

Section 6.D.1 EL 734

6. Forms removed: Side one Ray Smith 0105 13-6-86
Inspector Time Date
Side two 714 Ray Smith 10030 13-6-86
Inspector Time Date

Section 7.G

7. No visible voids: Side one Almeida 1 0615 030586
Inspector Time Date
Side two Ray Smith 10030 13-6-86
Inspector Time Date

Section 6.D.1 thru .8,7.D
8. Curing compound applied: Side one 734 R.L.H.* 0110 3-6-86
Inspector Elmunt Time 10035 Date 030586
and/or Side two 714 Ray L.H. 10055 3-6-86
Inspector Time Date
Wet burlap applied: Side one N/A Inspector Time Date
Side two N/A Inspector Time Date
Removed: Side one N/A Inspector Time Date
Side two N/A Inspector Time Date

NOTE: Any blocks not applicable to inspection require entry of NA.

Remarks: * CURING COMPOUND APPLIED TO TWO SMALL AREAS
COVERED BY UNISTRUT FORM FOR SLEEVE AFTER COSMETIC REPAIR.

PENETRATION FIRE BARRIER AND/OR ABSCE BOUNDARY DOOR BREACHING PERMIT

Unit No. 2 Permit No. 2694 Date of Issue: 24 APR 86 Expiration Date 1 MAY 86 PRO No. _____
Extension Date _____ *Date and time breach was actually made 4/23/86 12:30 Rev. Expiration Date _____
Date Time

The precautions and procedures listed below must be followed. No fire barrier (including fire doors, fire dampers, cable penetration barriers, or thermal fire barrier) shall be breached except under the controls and restrictions of this procedure. No ABSCE boundary doors shall be breached except under the controls and restrictions of this procedure and TI-77. This single permit can serve to control breaching of doors which are fire doors, ABSCE doors, or both. Signature and acceptance of this permit implies a confirmation of knowledge of these requirements as outlined in Physi-13, Attachment F and those outlined in TI-77. The foreman or supervisor is to return the original copy of this permit to the shift engineer after the satisfactory performance of SI-233 or SI-261, as applicable, and/or after maintenance as per M&AI-13 has been complete. If a fire door or ABSCE door was breached to provide accessibility (i.e. movement of equipment, running welding leads, etc.) and no door maintenance was required, the permit may be closed by a visual inspection that the door was returned to functional status and verified by signature on Attachment F. The foreman or supervisor shall promptly initiate a PRO if any Tech Spec fire barrier is breached for over seven (7) days or ABSCE door is breached outside the constraints of TI-77.

Penetration barrier identification: Fire Door No. _____ Fire Damper No. _____ Penetration No. _____
Other ABSCE Conduit IPPS42B ABSCE Door No. _____ Opposite Door No. Required Operable _____

Location (Building & Elevation) AB-EL 734 6th A12 5'WLT Purpose For Breach Wire Pull
Workplan or WR No.: 11783 Requested by: D.R. Dodd Section 1 Elec Mod Phone No. 6879 Date 4/24/86
Foreman or Supervisor

Check as Completed or as Appropriate:

1. Appropriate Entry Made in SE Log: ()
2. Continuous () OE roving () fire watch established as required by Tech Spec action statement 3.7.12.1.
3. PHYSI-12, Att. C is required if the door is in a CO₂ protected area. (LCO. 3/4.7.11.3)
4. Continuous door watch established: () Radios provided and doors capable of closure within four minutes of notification: ()
5. Authorized By: [Signature] 24 APR 86 0932c
Shift Engineer or his Representative Date Time
6. Penetration repaired and restoration verified by performance of SI-233 (), M&AI-13 (), SI-261 (), or visual inspection ().
Verified by: D.R. Dodd 4-28-86 7:30
Cognizant Maint. Representative Date Time
7. () Fire watch released and supplemental protection no longer required: () ABSCE door watch no longer required:
[Signature] 4-28-86 0635 cct
Shift Engineer or his Representative Date

NOTE: The responsible foreman, cognizant engineer, or supervisor shall place a copy of this permit, as provided by the shift engineer after restoration, in the files with the completed workplan or MR.

D. Dodd 4-24-86

WP/WR NO. 11783
PAGE VII

WP/WR NO. 11783
PAGE VIII c1

PENETRATION NO.	LOCATION	CONTROLLING INSTRUCTION	DATE/TIME BREACHED	QA INITIALS	DATE/TIME RETURN TO NORMAL	QA INITIALS	TOTAL BREACH AREA
1PL 3011B	A3Q 734EL	Physi 13	2/11/86 - 0200	H.R.C.	2-19-86 0500	H.R.C.	3" hole
1PL 3013B	A3Q 734EL	Physi 13	2/11/86 - 0200	H.R.C.	2-19-86 0500	H.R.C.	3" hole
1PP 562B	A-12att TAB 734	Physi 13 + 7L-17	2-27-86 - 0505	H.R.C.	3-5-86 0604	H.R.C.	6" hole
1PP 562B	A-12att AB 734	"	4-24-86 0910	Sam	5-4-86 0815	Sam	6" hole
1PP 564B	A-12att TAB 734	"	5-3-86 0830	EL	5-4-86 1530	Sam	4" hole
1PL 3011B	A3Q 734EL	Physi - 13	10/10/85 1006	Sam	10-16-85 1400	Sam	3" hole
1PL 3013B	A3Q 734EL	Physi - 13	10/10/85 1006	Sam	10-16-85 1400	Sam	3" hole

Safety Function/Unit: RCS INV CONT/Unit One
 Associated Interaction No(s): None
 Associated Safety Function(s): None
 Location: Auxiliary Building Elev 669, Common Area & Corridor A3-A6, S-T

Description: An interaction exists between Train A & Train B for centrifugal charging pumps. Train A: 1PP550A, 1PP552A, (CCP A-A); 1PL6145A, 1PL6149A (CCP Aux Lube Oil Pump A-A); 1PL3001A, 1PL3003A, 1PL3004A (CCP Cooler Fan A-A & FCV-67-168)
 Train B: 1PP562B, 1PP564B (CCP B-B); 1PL6152B, 1PL6156B (CCP Aux Lube Oil Pump B-B); 1PL3011B, 1PL3013B, 1PL3014B (CCP cooler fan B-B & FCV-67-170)

Corrective Action: A) Cables for CCP (1PP562B and 1PP564B) B-B and the CCP cooler fan B-B (1PL3011B and 1PL3013B) will be re-routed to provide adequate separation. Cable 1PL3014B does not require protection; it will be disconnected at junction box 1190.

B) Cables for FCV-67-168 (cable 1PL3004A) and FCV-67-170 (cable 1PL3014B) do not need protection. These valves will be permanently failed in the open position and the associated cables 1PL3004A and 1PL3014B will be disconnected at junction boxes JB1189 and JB1190 respectively.

C) Cables associated with the auxiliary lube oil pumps do not require protection. A bypass switch will be installed allowing the CCP's to be started without the auxiliary lube oil pumps running.

INTERACTIONS	
Date:	
Prepared	
Checked	
APPROVALS	
MEB	
NEB	
EEB	
NUC PWR FPE	
NUC PWR MOD	
NUC PWR R	

KEY 1

DTN-23-R2

SQN - Appendix R Project

INTERACTION IDENTIFICATION

WP 11783
PAGE X-a-2 OF X-12/20

No. 68
DATE 10/22/84
UNIT ONE

Location: ① A1 → A14/S → T LINE, ELEVATION 669, COMMON AREA & CORRIDOR

②
Description of Interaction (list cables/conduit/equipment):

AN INTERACTION EXISTS AT THE ABOVE LOCATION BETWEEN
PATH ONE AND PATH TWO FOR CENTRIFUGAL CHARGING PUMP
SEE ATTACHED SHEET FOR SPECIFIC CABLES THAT INTERFERE
THIS INTERACTION CONTINUES UP THE OPEN STAIRWAY TO ELEVATION 684 690.

PRO No:

Compensatory Action:

A FIRE WATCH HAS ALREADY BEEN ESTABLISHED IN THIS AREA

Suggestive Corrective Action:

UNRAIP OR REROUTE CABLES FOR ONE PATH

DCR/FCR No: 2133

Signature

10/22/84
Date

ECN No: L6308 / L6235

Date ECN scheduled to be issued

Date ECN actually issued

Description of Modification: REROUTED CABLES 1PP562E, 1PP564B, 1PL3011B
+ 1PL3013 AND ASSOCIATED CONDUIT. INSTALL TSI FIRE BARRIER
MATERIAL. THIS COMPLETED WORK ON CCP 1B-B & CCP 1BB RM CLR FA.

Date field work scheduled to start 10/4/85

Date field work scheduled to complete 5/26/86

List Workplan No., FCRs etc. associated with this modification: WP 115-29
Completed installation of ALOP hand sigs on 6.9KVSD Bds for all CCPs.
WP 11723 ECN 6235, FCR'S LISTED ON BACK.

Date field work actually complete 5-30-85 / 5/26/86

Item closed, Michael P. DeChant
Signature

6/19/86
Date

cc: H. B. Rankin, Sequoyah
R. W. Olsen (Attn: Don Maxwell), Sequoyah
J. P. Vineyard (Attn: Norm Black), Sequoyah

No. 66
DATE 10/22/84
UNIT ONE
DTN No. 20-R2

Location: 65KV S/D BOARD ROOM A (EL 734)

Safety Function PCS INVENTORY CONTROL

Description of Interaction (list cables/conduit/equipment):

AN INTERACTION EXISTS AT THE ABOVE LOCATION FOR BOTH PATHS FOR CHARGING PUMPS. SEE ATTACHED SHEET FOR SPECIFIC CABLES

PRO No:

Compensatory Action: A FIREWATCH HAS ALREADY BEEN ESTABLISHED IN THIS LOCATION.

Suggested Corrective Action: WRAP OR REROUTE CABLES FOR PATH ^{TO} (Trans B cables) Evaluate possibility of using CCS pump 1B-D or relocating C-pump transfer switches.

DCR/FCR No: 2133

Signature *James D. D. [Signature]*

10/22/84
Date

ECN No: L6308 / L 6235

Date ECN scheduled to be issued

Date ECN actually issued

Description of Modification: REROUTED CABLES IPPE22B IPPE64.8 IPL3011E + IPL3013 AND ASSOCIATED CONDUIT INSTALL TEE FIRE BARRIER MATERIAL. THIS COMPLETED WORK ON CCP 1B-B + CCP 1B-C ROOM COVER FAN.

Date field work scheduled to start 10/11/85

Date field work scheduled to complete 5/26/86

List Workplan No., FCRs etc. associated with this modification: WP 11529
NP 11783 ECN 6235, FCR'S LISTED ON BACK.

Date field work actually complete 5-30-85

Comments: Completed installation of ALOP Hand Sels on 6.9KV S/D Bd Panel for all CCPs.

Item closed, *[Signature]*

Signature

6/1/86
Date

- cc: H. B. Rankin, NUC PR, Sequoyah (please distribute as you feel necessary)
R. W. Olson (Attn: Don Maxwell), Sequoyah (please evaluate feasibility of modifica
J. P. Vineyard (Attn: Norm Black), Sequoyah (please evaluate feasibility of design change)
P. R. Wallace, (Attn: Ed Craigge), Sequoyah (please provide transient fire load protection)

Interaction Number: 66

WP/WR NO. 11783
PAGE X 4

Safety Function/Unit:

RCS Inventory Control/Unit 1

Associated Interaction No(s):

27

Associated Safety Function(s):

ERCW Heat Sink

Location:

Auxiliary Building, Elevation 734, 6.9 kV shutdown
board room A (A3-A4/R-U).

Description:

An interaction exists at the above location for both
identified CCP paths. The path 2 (B-Train) cables are
routed in trays at the north end of the room. The
following cables interact..

Path 1: CCP A-A - 1PP550A, 1PP552A, 1PP53A, 1PP554A, 1PP556A,
1PP557A, 1PP555A, CCP Auxiliary lube oil pump
A-A - 1PL6145A, 1PL6146A, 1PL6147A, PL6148A;
CCP Cooler Fan A-A and FCV-67-168 - 1PL3002A,
1PL3003A; CCS pump A-A 1PL4729A; Instrument
Loop L-70-63A - 1PM2236; FCV-67-146 - 1V2423A

Path 2: CCP B-B - 1PP564B; CCP Auxiliary lube oil pump B-B,
1PL6152B, 1PL6155B, 1PL6156B; CCP Cooler fan
B-B and FCV-67-170 - 1PL3013B; Instrument
Loop L-70-99A - 1PM2435; CCS pump C-S -
2PL4733B, 2PL4734B, 2PL4737B, 1PL4735S,
1PL4736S

INTERACTIONS	
Date:	11/10/85
Prepared	EDG
Checked	AWT
APPROVALS	
MEB	
NEB	
EEB	
NUC PWR FPE	
NUC PWR MOD	
NUC PWR R	

Corrective Action: 1.

CCP B-B cables will be rerouted and wrapped as necessary to provide adequate separation.

Cables associated with CCP auxiliary lube oil pumps do not require protection. A bypass switch will be installed allowing the CCP's to be started without the auxiliary lube oil pumps running.

The cable 1PL3013B for CCP cooler fan B-B will be rerouted to provide adequate separation.

Cables 2PL4733B and 2PL4734B will be wrapped in a one-hour fire-rated barrier until 20-foot separation is achieved from redundant Train A associated components.

CCP pump room cooler 1A-A cable 1PL3003A will be rerouted to provide adequate separation from cables and components associated with CCS pump C-S. Cable 1PL3002A is not required to operate the CCP 1A-A room cooler and does not require protection. Cable

2PL4737B is for an interlock function and will be disconnected at the shutdown board breaker.

This cable does not require protection.



5. The shutdown logic has determined that loops L-70-63A and L-70-99A are not required.

Cables for FCV-67-168 and -170 do not require protection. These valves will be permanently failed in the open position and associated cables 1PL3004A and 1PL3014B will be disconnected at junction boxes JB1189 and JB1190 respectively.

INTERACTIONS	
Date:	11/10/85
Prepared	FDG
Checked	W
APPROVALS	
MEB	APR
NEB	BKW
EEB	NCS
NUC PWR FPE	RET
NUC PWR MOD	RET
NUC PWR R	RET

SUBJECT Appendix "R" Interaction of anti-Charg. Pump IB PROJECT Sen

E1 734 Route to For Cables / PP5/2; 564 B, / PL3011B 3301X B


COMPUTED BY R1 XEADATE 4-30-86CHECKED BY R1 XEADATE 5-28-86

D. Mc Coy / 6/1/86
DATE

WP/WR NO. 11783
PAGE I.C.


SUBJECT APPENDIX F Interaction 68 Cont. Chrg. Pump 1B-R PROJECT S-a

Ely 724 Reorder For Cables 1PP562B, 564B, 1PL3011B, 3013B

COMPUTED BY LEBDATE 4-30-86CHECKED BY KXTDATE 5-28-86

DMC / 6/1/86
 Date

WP/WR NO. 11783PAGE X.7

SUBJECT Appendix "R" Interaction # 68 Cent. Chavo. Pump/B-B PROJECT SeeELV 714 Manhole for Cables 1PP562B-564B, 1P6301 B, 3013BCOMPUTED BY R1DATE 4-30-86CHECKED BY R1 KENDATE 5-28-86

R. McRae / 6/1/86
 Date

WP/WR NO. 11703
 PAGE 8

SUBJECT Appendix R* Intervention 68 for Chg. Pump 1B-B PROJECT S25

Elev 714 Re-route For Cables 1PPE62B, 564B, 1PL3011B, 3013B

COMPUTED BY
R1 ~~K2~~ K2 K2H


DATE 4-30-86

6-7-86

6-11-86

CHECKED BY
K1 K2H
R2 K2H
R3 K2H.DATE 5-28-86
6-7-86
6-11-86

R3 JRH



Notes: Denotes thermo lag wrapping

R3 = Added Support
I.D. NumbersWP/WR NO. 11783
PAGE 9

R1 D. Mc / 6/11/86
Date
R2 / 6/17/86
Date
R3 / Date

SUBJECT Appendix "R" Interaction "69" Cent. Charn. Pump 1B-B PROJECT Seq

Elev 690 Reroute For Cables IPF562B, 564B, IPF501B, 3013B

COMPUTED BY JEHDATE 4-3-86

CHECKED BY

DATE 5-28-86

R1

R2 KKH

R3 GRH

6-7-86

6-11-86


R1 KKH

R2 KKH

R3 KKH

6-7-86

6-11-86



HANGERS

① 1-370-11496

② 11497

③ 11498

④ 11499

⑤ 11500

①

②

③

④

⑤


WP/WR NO. 11783PAGE 1 of 10

R. D. Mac / 6/1/86
 N.E. FWR APP. NO. DATE

R. D. Mac / 6/1/86
 R. D. Mac / 6/1/86
 R3 / DATE:

SUBJECT Appendix R Interaction #4E Coil Pump 1B-B PROJECT Seq

ELV 690 Runway For Tailas (PP562B, 544B, PL3011B, 3013B)

COMPUTED BY
R1 ZEH
R2 JRH
R3 KZHDATE 4-30-86
6-11-86
6-24-86CHECKED BY
KZH
R2 KZH
R3 KZHDATE 5-28-86
6-11-86
6-24-86

Denotes thermo-lag wrapping
R2 = Added Support I.D. numbers
13 - Corrected Support I.D. on #B.


WP/WR NO. 11783
PAGE X-a-11

JOE WILLY
R2 / Date

10/1/86
12/1/86

SUBJECT Appendix "R" Interaction #63 Cont. Chng. Pump 1B-B PROJECT Seq

EJ 690 Re-route For Callas IPP 562B, 564B, 1P2011B, 3013B

COMPUTED BY LEA
RIDATE 4-30-86CHECKED BY KLN
RIDATE 5-28-86WP/WR NO. 11703
PAGE 12

SUBJECT APPENDIX "B" Interception #28 Cont Chavo Pump 1B-B PROJECT Seq

FR 690 Reroute For Cases: 1P5562B, 5L64B, 1PL3011B, 1PL3713B

COMPUTED BY FEV
R1 R2 JRH


DATE 4-30-86
6-11-86

CHECKED BY KRH
R2 KLA

DATE 5-28-86
6-11-86

HANGERS

- ① 1-370-12410
- ② 1-370-11552



Notes:

HHHHHH Denotes Hismo-Lag

(1) thermo Lag Stops 7' South of A6

R2 = Added Support I.D. Numbers

WP/WR NO. 11783
PAGE X of 13

6/11/86
R2 Date

6/11/86
R2 JRH

SUBJECT Appendix B: Interaction of Support Pump 12-2 PROJECT Seq

500 690 Portals for Gates 12-2 & 12-3, 12-4 & 12-5

COMPUTED BY RF
R1DATE 4-30-86CHECKED BY KLH
R2 KLH
R3 KINDATE 5-28-86
6-11-86
6-24-86R2 JKH

6-11-86

(5)

R3 KLH

6-24-86

411 Box JB608-MK JLB

411-1P562B

121-1P13018B

11-1P13011B

(T)

+++++ Denotes thermo-lag

R2 = Added Support

I.D. Numbers

R3 = Corrected Support Id#

① 1-370-12095-EI.705'

② 12096-EI.698'

⑫	1-370-12118
⑬	12119
⑭	12194
⑮	12215
⑯	12202

(A5)

+

(A6)

+

Hangers

Hangers	1-370-11506
①	11514
②	12200
③	12411
④	12412
⑤	12296
⑥	12192
⑦	12218
⑧	12438
⑨	12437
⑩	12193

112-3018B, 1P13018B
1P564B Tee together

121-1P564B

411 Box JB608-MK JLB

1P13018B, 1P13018B

J.P. McCh

6/1/86

WP/WR NO. 11783PAGE X-2-14R2 Date 6/15/86

DATE 5-25-86
6-11-86

Density: thermal - 2.4 g

$R^2 = \text{Added Support I.D. Numbers}$

J. D. McCarty

6/1/88



WP/WR NO. 11783
PAGE 8 of 15

INSPECTION DATA SHEET

Computer Identifier No. or
Cable No. 1PP562BTITLE: HIGH VOLTAGE INSULATION AND MEGGER INSPECTIONEQUIPMENT INSPECTED Cables for Centrifugal Charging Pump 1B-B

Inspection Results

System Electrical Engineer Billy J. McLean

2500-V Megger Inspection			Equipment Only 5.0 kV High Potential Inspection			
Phase	Accept. Criteria (Megohms)	Actual Value (Megohms)	Applied Voltage (kV)	Leakage Current Reading		
				Initial	After 1 min.	
A	6.9	4500		NA		
B	6.9	4500				
C	6.9	5000				

Cable or Penetration Only															
D. C. HIGH POTENTIAL INSPECTION															
Phase	Applied Voltage	Leakage Current vs. Time (Minutes)													
		Initial	1	2	3	4	5	6	7	8	9	10	11	12	13
A	35 kV	25 μ A	14	12	12	12	12	12	12	12	12	12	12	12	12
B															
C															

Test Equipment:

Description	TVA Tag No.	Model	Date Calib Due
<u>H.P.T. Test Set</u>	<u>201194</u>	<u>VNC-1</u>	<u>4-29-87</u>
<u>Megger</u>	<u>212703</u>	<u>Biddle</u>	<u>10-10-86</u>
<u>Timer</u>	<u>445740</u>	<u>Maylan 202</u>	<u>3-6-87</u>

Remarks Workplan No 11783PSC Report No. SNP-31-86

PSC Engineer Reviewing the Inspection Data

Date

5-16-86WP/WR NO. 11783
PAGE 111

B43 '86 0903 904

QA Record

TO : Those listed

FROM : W. S. Raughley, Chief Electrical Engineer, W8 C126 C-K

DATE : September 2, 1986

SUBJECT: ALL NUCLEAR PLANTS - ELECTRICAL ISSUES - CLASS 1E CABLE BEND RADIUS

The purpose of this memorandum is to provide advance direction concerning the project specific actions which are necessary to resolve the outstanding concerns on the bend radius of Class 1E cables. Resolution of these concerns has been tied to plant restart/fuel load and should be scheduled for implementation accordingly.

The Electrical Engineering Branch has evaluated the adequacy of the bend radius to which Class 1E cables were installed. The basis for the evaluation was the comprehensive investigation conducted by the Nuclear Safety Review Staff on the same subject during February to April 1985. The measures specified herein are expected to comprise the majority of any project specific corrective actions resulting from this investigation. EEB's final report documenting the evaluation and providing conclusions and recommendations based upon an independent review of our evaluation will be issued in September 1986.

Each project should proceed immediately to perform the following inspections, as applicable, and to forward the results to the respective engineering projects.

1. The Watts Bar and Bellefonte projects shall inspect the installed bend radius of all Class 1E medium voltage power cable furnished by The Okonite Company. The cable shall be verified to be installed to a radius equal to 8 times its outside diameter. This inspection need not address the bend radius in standard conduit bends as this has been addressed generically in PIRGENEEB8605. The inspection of the bend radius in condulets is covered in item 2 below. Therefore, provided the project establishes that all cable tray fittings were procured with a radius equal to or greater than 8 times the outside diameter of the largest cable in question and that all conduit bends meet the minimum requirements of DS-E13.1.7, this inspection may be limited to cables in free air (transitions from raceway to raceway or raceway to equipment) and to the points of termination.

All installations which do not conform to the specified 8 times factor shall be documented as a nonconformance and forwarded to the respective engineering project for disposition. The documentation shall include the cable and, if applicable, the raceway number, the location of the violation, the actual installed bend radius and the results of a visual inspection noting any discernible stress on the cable jacket in the area of the bend or any cuts or ripples in the cable jacket which could indicate shield deformation.

Those listed
September 2, 1986

ALL NUCLEAR PLANTS - ELECTRICAL ISSUES - CLASS 1E CABLE BEND RADIUS

Effective immediately, the Watts Bar and Bellefonte projects shall take the steps necessary to ensure that all medium voltage power cable furnished by The Okonite Company is installed to a bend radius of 8 times its outside diameter as opposed to the previous direction of DS-E12.1.5. This design standard is being revised accordingly.

2. All projects shall perform a field inspection of all conduits containing Class 1E medium voltage power cables for the existence of any straight-thru pull box or conduit type (C, ELL, TEE, etc.) raceway fitting or any conduit raceway fitting other than a standard conduit bend around which a cable is bent. The existence of any such fittings, including the raceway number and size, the fitting description, manufacturer (if available) and size, and the location shall be documented as a nonconformance and forwarded to the respective engineering project for disposition.
3. All projects shall determine the minimum size conduit that the following coaxial, triaxial, and twinaxial cables, if utilized in Class 1E applications and routed in conduit, are installed in. If any of these cables are installed in Class 1E applications and in a conduit smaller than indicated below, the project shall perform a field inspection for the existence of condulets of any type (ELL, TEE, etc) in which the cable is bent. The existence of any such fittings, including the raceway number and size, the fitting description, manufacturer (if available) and size and the location shall be documented as a nonconformance and forwarded to the respective engineering project for disposition. In addition, each project shall verify that the following list includes all coaxial, triaxial, and twinaxial cables installed in Class 1E applications. A positive statement to this effect or a list of additional cable mark numbers shall be addressed to my attention.

<u>Cable Mark No.</u>	<u>Description</u>	<u>Minimum Condulet Size (Inches)</u>
WTJ	Coax RG6A/U	2
WTJ-5	1/c #21 Coax Solid Cu Clad Steel	2
WTK	#22 Coax RG59B/U	1-1/2
WTK-1	Coax RG59B/U XLP	1-1/2
WTL	Coax RG216/U Except 3 Shlds	3
WTL-4	Coax 55 ohm #22 AWG	1-1/2
WTM	Coax RG114A/U Except 3 Shlds & ST	3
WTM-6	1/c Coax #26, 7 Strands, LOCA	3
WTY-1	#21 AWG, Coax, RG58C/U	1-1/2
WTU	#20 Triax RG 11/U	3
WTN	Triax RG-59U #22, 2 Shlds LOCA	2
WTN-1	Triax Similar to RG11/U LOCA	3
WTN-2	Twinax RG22B/U	3
WWK	TP #22 W/SH TP #20 2/c #22 2-Coax	3


Those listed
September 2, 1986

ALL NUCLEAR PLANTS - ELECTRICAL ISSUES - CLASS 1E CABLE BEND RADIUS

4. The Watts Bar project shall perform a field inspection of all Class 1E coaxial, twinaxial, and triaxial cables which were installed or modified during the period of May 25, 1979 to May 18, 1981, under the guidance of Design Information Request (DIR) No. E-9. In addition, all projects shall inspect all Class 1E coaxial and twinaxial cables which were installed or modified during the period of September 20, 1983 to April 23, 1986, under the direction of DS-E12.1.5 Rev 0. The cable shall be verified to be installed to a bend radius equal to 8 times its outside diameter. This inspection need not address the bend radius in standard conduit bends as this has been addressed generically in PIRGENEEB8605. The inspection of the bend radius in condulets is covered in item 3 above. Therefore, provided the project establishes that all cable tray fittings were procured with a radius equal to or greater than 8 times the outside diameter of the largest cable in question or that the cable was restricted to use in conduit and that all conduit bends meet the minimum requirements of DS-E13.1.7, this inspection may be limited to cables in free air (transitions from raceway to raceway or raceway to equipment) and to the points of termination.

All installations which do not conform to the specified 8 times factor shall be documented as a nonconformance and forwarded to the respective engineering project for disposition. The documentation shall include the cable and, if applicable, the raceway number, the location of the violation, the actual installed bend radius and the results of a visual inspection noting any discernible stress on the cable jacket in the area of the bend or any ripples in the cable jacket which could indicate shield deformation.

Each Lead Engineer should prepare a fragnet reflecting the individual project's approach and schedule for resolving these issues. Please submit a copy of this fragnet to me for my use and information.


W. S. Raughley

J. D. Collins, P-205 SB-K
G. T. Hall, DNE, DSC-A, Sequoyah
D. F. Faulkner, A7-BFN
J. L. Springer, 9-111 SB-K

JMS:TMS:TLT

cc: RIMS, SL 26 C-K
R. R. Hoesly, 9-113 SB-K
J. A. Kirkebo, W12 AB C-K
M. L. Rayfield, P-104 SB-K
J. P. Stapleton, DNE, A10 Browns Ferry
D. W. Wilson, DNE, DSC-A, Sequoyah
Principally Prepared By: T. M. Shea, Extension 2672

DNE1 - 0594W

ITEM 10

Describe the extent to which different classes of cables were intermixed within a conduit (e.g., V5 with V4, etc.).

RESPONSE

The design maintains separation of the cables by voltage classification.

Design Input Memorandum DIM-SQN-DC-V-11.3-5, issued March 13, 1986, to SQN Design Criteria SQN-DC-V-11.3, "Power, Control, and Signal Cables For Use In Category I Structures," states that cables routed in conduit shall be separated by voltage levels with two exceptions.

1. Cables of different voltage levels may be routed together when a piece of equipment has only one conduit opening. These cables should be separated with respect to voltage levels as soon as possible. Generally, these are very short lengths (less than three feet).
2. When the circuit protective device in a radial feeder is capable of interrupting both power and control circuits for a piece of equipment, the associated power and control cables may be routed together in the same conduit.

This DIM was issued to formally document the requirements for separation of voltage levels in conduits which had been explicitly stated for cable trays. However, the design reflects that the same voltage level separation has been maintained in conduits as in cable trays since the May 1971 initial issue of the design criteria (SQN-DC-V-11.3).