



UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D. C. 20555

DUKE POWER COMPANY
NORTH CAROLINA ELECTRIC MEMBERSHIP CORPORATION
SALUDA RIVER ELECTRIC COOPERATIVE, INC.
DOCKET NO. 50-413
CATAWBA NUCLEAR STATION, UNIT 1
AMENDMENT TO FACILITY OPERATING LICENSE

Amendment No. 64
License No. NPF-35

1. The Nuclear Regulatory Commission (the Commission) has found that:
 - A. The application for amendment to the Catawba Nuclear Station, Unit 1 (the facility) Facility Operating License No. NPF-35 filed by the Duke Power Company acting for itself, North Carolina Electric Membership Corporation and Saluda River Electric Cooperative, Inc., (licensees) dated April 6, 1989, as supplemented April 21, 1989, complies with the standards and requirements of the Atomic Energy Act of 1954, as amended (the Act), and the Commission's rules and regulations as set forth in 10 CFR Chapter 1;
 - B. The facility will operate in conformity with the application, the provisions of the Act, and the rules and regulations of the Commission;
 - C. There is reasonable assurance (i) that the activities authorized by this amendment can be conducted without endangering the health and safety of the public, and (ii) that such activities will be conducted in compliance with the Commission's regulations set forth in 10 CFR Chapter I;
 - D. The issuance of this amendment will not be inimical to the common defense and security or to the health and safety of the public; and
 - E. The issuance of this amendment is in accordance with 10 CFR Part 51 of the Commission's regulations and all applicable requirements have been satisfied.


2. Accordingly, the license is hereby amended by page changes to the Technical Specifications as indicated in the attachments to this license amendment, and Paragraph 2.C.(2) of Facility Operating License No. NPF-35 is hereby amended to read as follows:

(2) Technical Specifications

The Technical Specifications contained in Appendix A, as revised through Amendment No. 64, are hereby incorporated into the license. The licensee shall operate the facility in accordance with the Technical Specifications and the Environmental Protection Plan.

3. This license amendment is effective as of its date of issuance.

FOR THE NUCLEAR REGULATORY COMMISSION



for

David B. Matthews, Director
Project Directorate II-3
Division of Reactor Projects-I/II
Office of Nuclear Reactor Regulation

Attachment:
Technical Specification Changes

Date of Issuance: May 23, 1989



UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D. C. 20555

DUKE POWER COMPANY

NORTH CAROLINA MUNICIPAL POWER AGENCY NO. 1

PIEDMONT MUNICIPAL POWER AGENCY

DOCKET NO. 50-414

CATAWBA NUCLEAR STATION, UNIT 2

AMENDMENT TO FACILITY OPERATING LICENSE

Amendment No. 58
License No. NPF-52

1. The Nuclear Regulatory Commission (the Commission) has found that:
 - A. The application for amendment to the Catawba Nuclear Station, Unit 2 (the facility) Facility Operating License No. NPF-52 filed by the Duke Power Company acting for itself, North Carolina Municipal Power Agency No. 1 and Piedmont Municipal Power Agency, (licensees) dated April 6, 1989, as supplemented April 21, 1989, complies with the standards and requirements of the Atomic Energy Act of 1954, as amended (the Act), and the Commission's rules and regulations as set forth in 10 CFR Chapter I;
 - B. The facility will operate in conformity with the application, the provisions of the Act, and the rules and regulations of the Commission;
 - C. There is reasonable assurance (i) that the activities authorized by this amendment can be conducted without endangering the health and safety of the public, and (ii) that such activities will be conducted in compliance with the Commission's regulations set forth in 10 CFR Chapter I;
 - D. The issuance of this amendment will not be inimical to the common defense and security or to the health and safety of the public; and
 - E. The issuance of this amendment is in accordance with 10 CFR Part 51 of the Commission's regulations and all applicable requirements have been satisfied.


2. Accordingly, the license is hereby amended by page changes to the Technical Specifications as indicated in the attachments to this license amendment, and Paragraph 2.C.(2) of Facility Operating License No. NPF-52 is hereby amended to read as follows:

(2) Technical Specifications

The Technical Specifications contained in Appendix A, as revised through Amendment No. 58, are hereby incorporated into the license. The licensee shall operate the facility in accordance with the Technical Specifications and the Environmental Protection Plan.

3. This license amendment is effective as of its date of issuance.

FOR THE NUCLEAR REGULATORY COMMISSION



for David B. Matthews, Director
Project Directorate 11-3
Division of Reactor Projects-I/II
Office of Nuclear Reactor Regulation

Attachment:
Technical Specification Changes

Date of Issuance: May 23, 1989

ATTACHMENT TO LICENSE AMENDMENT NO. 64

FACILITY OPERATING LICENSE NO. NPF-35

DOCKET NO. 50-413

AND

TO LICENSE AMENDMENT NO. 58

FACILITY OPERATING LICENSE NO. NPF-52

DOCKET NO. 50-414

Replace the following page of the Appendix "A" Technical Specifications with the enclosed page. The revised page is identified by Amendment number and contains a vertical line indicating the area of change.

Amended Page

5-6

DESIGN FEATURES

DESIGN PRESSURE AND TEMPERATURE

5.2.2 The reactor containment vessel is designed and shall be maintained for a maximum internal pressure of 15 psig and a temperature of 328°F.

5.3 REACTOR CORE

FUEL ASSEMBLIES

5.3.1 The core shall contain 193 fuel assemblies with each fuel assembly nominally containing 264 fuel rods clad with Zircaloy-4, except that substitutions of fuel rods by filler rods consisting of Zircaloy-4 or stainless steel, or by vacancies, may be made in fuel assemblies if justified by cycle-specific reload analyses using NRC-approved methodology. Should more than 30 rods in the core, or 10 rods in any assembly, be replaced per refueling, a special report describing the number of rods replaced will be submitted to the commission pursuant to Specification 6.9.2 within 30 days after cycle startup. Each fuel rod shall have a nominal active fuel length of 144 inches. Reload fuel shall be similar in physical design to the initial core loading and shall have a maximum enrichment of 4.0 weight percent U-235 with a maximum enrichment tolerance of ± 0.05 weight percent U-235.

CONTROL ROD ASSEMBLIES

5.3.2 The core shall contain 53 full-length control rod assemblies. The full-length control rod assemblies shall contain a nominal 142 inches of absorber material of which 102 inches shall be 100% boron carbide and remaining 40-inch tip shall be 80% silver, 15% indium, and 5% cadmium.

For Unit 1, all control rods shall be clad with stainless steel tubing.

For Unit 2, all control rods, except for the control rods in one Rod Cluster Control Assembly (RCCA), shall be clad with stainless steel tubing. The remaining Rod Cluster Control Assembly control rods shall be clad with Inconel.

5.4 REACTOR COOLANT SYSTEM

DESIGN PRESSURE AND TEMPERATURE

5.4.1 The Reactor Coolant System is designed and shall be maintained:

- a. In accordance with the Code requirements specified in Section 5.2 of the FSA, with allowance for normal degradation pursuant to the applicable Surveillance Requirements,
- b. For a pressure a 2485 psig, and
- c. For a temperature of 650°F, except for the pressurizer which is 680°F.

VOLUME

5.4.2 The total water and steam volume of the Reactor Coolant System is 12,040 \pm 100 cubic feet at a nominal T_{avg} of 525°F.

5.5 METEOROLOGICAL TOWER LOCATION

5.5.1 The meteorological tower shall be located as shown in Figure 5.1-1.