

| BILL OF MATERIAL | | | | |
|------------------|-----|--|------------------------|----------------|
| ITEM | QTY | DESCRIPTION | MFG. | ACCESS. No. |
| 1 | 2 | MINI TYPE-A ENCLOSURES 700 No. 31-621 & 31-621 | HOFFMAN | A-248966L |
| 2 | 2 | PANELS 21" X 17" FOR ABOVE ENCLOSURES. | HOFFMAN | A-24890 |
| 3 | 4 | RELAY MODULE 700 SC SERIES FOR 0-1 MAMP INST CURRENT. TAG. No: 3'SH-1672A, 3'SH-1651A 3'SH-1672A, 3'SH-1651A | SCIENTIFIC COLLIERS | 700 SC RR, CA. |
| 4 | 4 | TIME DELAY RELAY TAG. No. 02A, 05A | ASBESTAT | 7000 AC. |
| 5 | 14 | TERMINAL BLOCKS 4 ROWS TAG. No. TB-1, TB-2 | BUCHANAN | 0381 |
| 6 | 4 | TERMINAL BLOCK END PLATE | BUCHANAN | 0380 |
| 7 | 4/R | Mounting CHANNEL PRE- PUNCHED ALUMINUM. | BUCHANAN | 07T-64 |
| 8 | 2 | SWITCH TERMINAL BLOCK | BUCHANAN | 0341 |
| 9 | 2 | FUSE TERMINAL BLOCK WITH 1 AMP FUSE. | BUCHANAN | 0351 |

DCP #2-6324.0 REV. 0 SHEET 55 OF 99

LAYOUT ARRANGEMENT
SCALE: 3" = 1'-0"

SI
APERTURE
CARD

THIS NEW DRAWING IS PART OF
DCP NO. 2-6324.03
AND DESCRIBES PHYSICAL WORK
TO BE ACCOMPLISHED UNDER
THE DCP.

This revised Vendor Document Incorporates
Changes requested with a Change Change Package
(CCP).
DCP Number 2-6324.0-1
 This Vendor Document revision does not reflect
any physical work modification and is not associated
with a DCP or CCP.
English checked by *[Signature]*
Revised by *[Signature]*
9/1/85

RESPONSIBILITY
If the price or schedule is affected by this document, Central must be
notified prior to this action or work claims are void.
Provision to proceed does not constitute acceptance or approval of
dimensions, including design details, calculations, quantities or test report
and is only an acceptance of the method used by the supplier. Supplier
retains full responsibility for design.
Issuance of this document does not release the supplier from full
responsibility for correct or purchase order requirements. Supplier,
but not limited to, shipping and installation of materials. Supplier
equipment replacement charges for the attached drawings.

DATE RECEIVED 10-8-85
DATE 12-9-85
BY [Signature]
REVISIONS
1 Manufacturer may proceed
2 Engineering as noted. Make changes
3 and re-submit. Manufacturer may proceed.
4 Correct and resubmit.
5 Information only. Distribution required.

QUALITY
ACCEPTABLE

SCE#4171
S023-502-2-388-0
QC IV UNIT 2 ON 1

| | | |
|--|------|----------|
| BECHTEL CORPORATION ENGINEERS & CONSTRUCTORS LOS ANGELES, CALIF. | | |
| JOB NO. 15692- A05 | DATE | APPROVED |


| | | | | | | | | | |
|-----|-------------------------|--------|-------|------|------|---------|---------|--------|--------|
| 0 | ISSUED FOR CONSTRUCTION | 9/1/85 | Genev | DR. | CHK. | EQS. | CHK. E. | P. E. | Q.A.E. |
| NO. | REVISIONS | DATE | DR. | CHK. | EQS. | CHK. E. | P. E. | Q.A.E. | |

| | |
|----------|---|
| I.Q. NO. | SAN ONOFRE NUCLEAR GENERATING STATION |
| FILE | MISC. PANELS 21-621 LAYOUT ARRANGEMENT & BILL OF MATERIALS |
| | SOUTHERN CALIFORNIA EDISON COMPANY SCALE AS SHOWN. LOS ANGELES, CALIF. DRAWING No. 39913 REV: 0 |

MICROFILMED FROM BEST AVAILABLE COPY



88LL290332



PDR RIDS

8811290332

