



NO.	DESCRIPTION	DATE	BY	CHKD.	APPV.
1	REVISION				
2	REVISION				
3	REVISION				
4	REVISION				
5	REVISION				
6	REVISION				
7	REVISION				
8	REVISION				
9	REVISION				
10	REVISION				

- NOTES:**
- SCALE: 1/8" = 1'-0"
  - AREAS SHOWN THIS [X] ARE REMOVABLE SLABS WHICH ARE TO BE LEFT OFF DURING NORMAL OPERATION TO PROVIDE PRESSURE RELIEF AND VENTILATION SPACE. SLABS ARE TO BE STORED ON THE 291'-10" & 262'-10" LEVELS.
  - AREAS SHOWN THIS [O] ARE REMOVABLE SLABS FOR MAINTENANCE OR REFUELING. ALL GRATING AT EL. 291'-10" TO BE REMOVABLE. PROVIDE REMOVABLE GUARD RAIL AROUND CAVITY AND HOISTING SPACE AND NOTICES NOTED WITH THE LETTER "M" OR THE LETTER "R".
  - NOTES MINIMUM THICKNESS ALLOWED FOR RADIATION PROTECTION.
  - NOTES MINIMUM THICKNESS ALLOWED FOR TORNADO PROTECTION.
  - NOTES MINIMUM THICKNESS ALLOWED FOR TORNADO PROTECTION. DURING NORMAL PLANT OPERATION MANIPULATOR CRANE TO BE STORED AT EAST CRANE STOP.
- REFERENCE DRAWINGS:**
- |   |                                  |         |
|---|----------------------------------|---------|
| MACH. LOC. - REACTOR CONTAINMENT            | SH. 2 PLAN EL. 262'-10"          | FM-1B   |
| MACH. LOC. - REACTOR CONTAINMENT            | SH. 3 PLAN EL. 241'-0"           | FM-1C   |
| MACH. LOC. - REACTOR CONTAINMENT            | SH. 4 PLAN EL. 216'-11"          | FM-1D   |
| MACH. LOC. - REACTOR CONTAINMENT            | SH. 5 SECTS. 1-1, 6-8, & 9-9     | FM-1E   |
| MACH. LOC. - REACTOR CONTAINMENT            | SH. 6 SECTS. 2-2, 5-5, 6-6 & 7-7 | FM-1F   |
| MACH. LOC. - REACTOR CONTAINMENT            | SH. 7 SECTS. 3-3 & 4-4           | FM-1G   |
| ARRG. T. - REACTOR INSTALLATION             |                                  | FF-1A   |
| ARRG. T. - STEAM GENERATOR INSTALLATION     |                                  | FF-2A18 |
| ARRG. T. - PRESSURIZER INSTALLATION         |                                  | FF-2C   |
| ARRG. T. - NEUTRON SHIELD TANK INSTALLATION |                                  | FF-2D   |

8.5"

8.5"

11"

17"

8000250 300

DDR

8006250300

