



NOTES: (CONTINUED)
 9 FOR GENERAL ASST. # 8/H SEE DWG. 33253

- NOTES:
- MAT'L: SA516 GR70 AS NOTED IN SPEC 219.710
 - DESIGN TEMP: 185°
 - PAINT: KEELER LONG EPXY PRIMER #4654B
 - WEIGHT: 36,500 APPROX. DOOR SWING WEIGHT = 3,500 (APPROX)
 - ELECTRICAL POWER: 480V 3PH 60HZ POWER FOR PUMP IF REQUIRED: 120V 1PH 60HZ FOR SOLENOID PILOT VALVES
 - DESIGN PRESSURE: 15 P.S.I.
 - DOOR SEALS CANNOT BE INFLATED UNLESS DOOR IS CLOSED & LATCHED
 - TEST PRESSURE: 17.25 P.S.I.

REV.	DATE	BY	CHKD.	FNCT.	NO.	APPD.	DESCRIPTION
1	02/28/81	LS	MM	PER			GENERAL REVISION
2	03/31/81	LS	MM	PER			ADDED PRESSURE RELIEF & REVISED STATIONS
3	07/26/81	LS	MM	PER			REVISED & REDRAWN
4	08/17/81	LS	MM	PER			FIRST ISSUE

CONTRACT NO. RB-219-700066 CONTAINMENT PERSONNEL AIR LOCKS
 MARK NO. LOWER 8 13 AB & DRA2
 SERIAL NO. LOWER 33041
 JOB NO. 12210 RIVER BEND STATION UNIT-1
 GULF STATES UTILITIES CO. WEST FELICIANA PARISH, LOUISIANA

W. J. WOOLLEY CO.
 RIVER FOREST, ILLINOIS

GENERAL ARRANGEMENT
 LOWER CONTAINMENT
 PERSONNEL AIR LOCK

DATE: 1-7-81
 REV: SEE ABOVE
 33041

APPROVED FOR FABRICATION	DATE: 1-7-81
APPROVED AS REVISED	DATE: 1-7-81
APPROVED FOR MATERIAL PURCHASE	DATE: 1-7-81
APPROVED FOR REVIEW	DATE: 1-7-81
APPROVED FOR RECORD	DATE: 1-7-81
APPROVED FOR RELEASE	DATE: 1-7-81

REVISIONS:

NO.	DESCRIPTION	DATE
1	GENERAL REVISION	02/28/81
2	ADDED PRESSURE RELIEF & REVISED STATIONS	03/31/81
3	REVISED & REDRAWN	07/26/81
4	FIRST ISSUE	08/17/81

APERTURE CARD

8202230659

RIDS

8202230659

