



QTY	DWG. No.	DESCRIPTION	MAT'L	NOTE
1	1	COUAX PENETRATION ASSEMBLY CONSISTING OF: (1) 9" DIA. PLATE (2) 18 GA. 20W WIRES EACH FEED THRU 24" LG. PIGTAILS EACH END (1) 12 GA. 13 WIRES FEED THRU 24 LG. PIGTAILS EACH END (1) 16 GA. 5 WIRES TWISTED SHIELDED 5'0" LG. PIGTAILS EACH END (1) PLUG		YES
2	1	O-RING # 264 7 3/4" O.D. x 1/2" I.D. x 1/8" CS.	EPDM E603	YES
3	1	O-RING # 267 8 1/2" O.D. x 8 1/2" I.D. x 1/8" CS.	EPDM E603	YES
4	186	AMP UNINSULATED BUTT SPICE CAT. NO. 321280		NO
5	8	1/2" BUNK. HEAT. HD BOLT x 1 1/2" LG.	SA-43, B8	YES
6	16	SLOTTED HEK. HD SCR #10-24 x 1/2" LG.	65T	NO
7	2	LOCKWASHER 1/2"	"	YES
8	16	LOCKWASHER #10 (1.90)	"	NO
9	2	37877-1 GASKET	SEE DWG.	NO
10	2	37877-2 COVER BOX	"	NO
11	-	-	"	-
12	1	1/4" N.P.T. PIPE PLUG	SA-106	YES
13	6	AMP THINWALL HEAT SHRINKABLE TUBING 1/4" DIA. x 1/2" LG. CAT. NO. 003326-1		NO

BILL OF MATERIAL FOR ONE ASSY
CONDUIT LOCATED AT ASSY

W. J. WOOLLEY CO.
RIVER FOREST, ILLINOIS

ELECTRICAL PENETRATION CONTAINMENT PERSONNEL AIR LOCK

Scale: 1/2" = 1' 1055
Date: 1-30-81
Red: SEE ABOVE 33266

THIS DOCUMENT IS THE EXCLUSIVE PROPERTY OF W. J. WOOLLEY CO.

POOR ORIGINAL

STONE & WESTER ENGINEERING CORPORATION
RIVER BEND STATION UNIT
GULF STATES UTILITIES COMPANY
DATA FORM

MANUFACTURER'S DRAWING

DESIGNED BY: N. METZNER (EIT)
CHECKED BY: J. KANE (EIT)
DATE: 8-13-81

DATE TO DESIGN: 8-13-81
REQUIRED RETURN DATE: 9-3-81

DESIGN ENGINEER'S DATE STAMP (EIT): J. KANE
DESIGN GROUP ROUTING (P):

ARCHITECTURE
CIVIL
CONCRETE
STEEL
BUILDING SERVICE
INSTRUMENT
MECHANICAL
PIPE SUPPORT
STRESS
ELECTRICAL
LIGHTING
MODEL SHOP
EXTENSION OFFICE
CONTROL
N. METZNER

NOTE: AUG 28 1981 9.00 AM

8202230686

RIDS

8202230686

