



This drawing and the design it covers is the property of the United States Government. It is loaned to the contractor for his use only and shall not be reproduced, copied, loaned, exhibited, or used except in the limited way and under the limited conditions set forth in the contract. It is to be returned to the contractor at the completion of the project.

- NOTES**
1. FOR GENERAL NOTES, SEE DWG. NO. A-001.
 2. ALL VERTICAL REINFORCING SHALL CONSIST OF 1-#8 @ 12" UNO AND EXTEND 5'-0" MIN BEYOND EDGES OF OPENINGS (WHY).
 3. ALL HORIZONTAL REINFORCING SHALL CONSIST OF 1-#8 @ 12" UNO AND EXTEND 5'-0" MIN BEYOND EDGES OF OPENINGS (WHY).
 4. ALL REINFORCING SHALL BE IN ACCORD TO TYPICAL WALL REINFORCING, SEE DWG. NO. A-005.
 5. ALL WALLS SHALL BE STANDARD 8" CMU.
 6. (A) ETC. DENOTES TYPICAL WALL REINFORCING PATTERNS - SEE DWG. NO. A-005.
 7. WHERE THE SUPPLEMENTAL REINFORCING SHOWN AROUND PENETRATIONS COLLIDES WITH LOCATIONS OF THE TYPICAL REINFORCING, ONLY THE LATTER IS REQUIRED, EXCEPT THAT ALL 8" CMU SHALL BE PROVIDED.
 8. AT THE OWNER'S OPTION, BLOCK WALLS SHOWN ON THIS DRAWING MAY BE CHANGED TO REINFORCED CONCRETE, U.M.C. DETAILS FOR REINFORCED CONCRETE SHALL BE AS SHOWN ON DRAWING NO. A-0318 & A-0325.
 9. REINFORCING AROUND DOOR OPENINGS SHALL BE PROVIDED PER SCHEDULE ON DWG. A-0005 UNO ON THIS DRAWING.
 10. SEE NOTES 10 AND 11, DWG. A-0362.

TEMP APERTURE CARD

REFERENCE DRAWINGS

ARCHITECTURAL: A-0315 - FLOOR PLANS
A-0304 & A-0005 - MASONRY DETAILS

NOTICE: ALTERATION OF THIS DOCUMENT BY ANY PERSON OTHER THAN THE LICENSED ARCHITECT OR ENGINEER IS ILLEGAL.

THE UNDERSIGNED HEREBY DECLARES ANY RESPONSIBILITY FOR ANY ERRORS OR OMISSIONS IN THIS DRAWING TO BE HIS OWN AND NOT THAT OF THE ARCHITECT OR ENGINEER WHOSE NAME IS SET FORTH HEREIN. THE UNDERSIGNED FURTHER DECLARES THAT HE IS A LICENSED ARCHITECT OR ENGINEER IN THE STATE OF MARYLAND AND THAT HE IS NOT PROVIDING PROFESSIONAL SERVICES TO ANY OTHER PERSON OR ENTITY AT THE SAME TIME AS HE IS PROVIDING SUCH SERVICES TO THE CLIENT.

Professional seals for the Architect and Engineer, including the name **BECHTEL** and the location **BALTIMORE, MARYLAND**.

NO.	DATE	REVISIONS	BY	CHK	APP
1		ISSUED FOR CONSTRUCTION			
2		REVISED AS NOTED			
3		REVISIONS			

SCALE: 1/4" = 1'-0" (DATE: 06-17-2010)

BECHTEL
ARCHITECTURAL
CMU WALL PENETRATIONS
CONTROL BLDG. & COMMUNICATION CORRIDOR

UTILITY DRAWING NO. _____

DATE: 06-17-2010

10466 A-0341 5

I certify that the image contained on this frame was made in the normal and regular course of business on the date stated below and that it is an accurate reproduction of the document(s) submitted for microphotography.

DATE: 12-01-2010 OPERATOR: [Name] SUPERVISOR: [Name]

30X

800 2800 534

PDR

8007300535

