



INSERVICE INSPECTION

REVISIONS BLOCK

GRID	REV. NO.	DESCRIPTION	CHKD. DATE	CHKD. BY	APPROV. DATE
	0	REL. FOR CONST. V.N. 16050	6-2-78	HAW	6-20-78
	1	REVISED TO CHANGE ITEM NOS FOR VALVES, IRV 317, IRV 318, ADDED FL. JT. NOS 143, WELD RVIF 114	8-28-78	HAW	8-28-78
B-3	2	REVISED TO CHANGE ITEM NOS FOR VALVES, IRV 317, IRV 318, ADDED FL. JT. NOS 143, WELD RVIF 114	8-28-78	HAW	8-28-78
	3	DELETED VALV. IRV 178, IRV 317 & WELD RVIF 250, VALV. IRV 178, ADD'D RVIF 174, 1750	7-11-78	HAW	7-11-78
	4	ADD MAT. I.D. AT VALV. IRV 324	8-14-78	HAW	8-14-78
	5	CORRECT ITEM NO. ON IRV 226 & IRV 130	7-17-80	HAW	7-17-80
	6	RE: TO CORRECT FLAG AT VALV. IRV 32A	8-14-78	HAW	8-14-78
	7	CHANGE ITEM NOS FOR VALVES IRV 327, IRV 328, IRV 329, AND IRV 330, ADD WELDS RVIF 31-1, RVIF 31-2, RVIF 31-3, WELDED SHIRT IRV 31-1, IRV 31-2, IRV 31-3, WELDED SHIRT IRV 31-1, IRV 31-2, IRV 31-3, WELDED SHIRT IRV 31-1, IRV 31-2, IRV 31-3	3-20-81	HKS	8-6-91

INFORMATION ONLY

ITEM	SIZE	DES.	SPEC./GRADE	SPEC./GRADE	SCH./RATE	REMARKS
(F)	3/4"	VALV. IRV 446 (M. MRY-239)				SS, SW
(E)	3/4"	VALV. IRV 445 (M. MRY-239)				SS, SW
(D)	3/4"	90° ELL	SA-182/P-304	SA-182/P-304	3000'	SS, PS/GW
(C)	3/4"	PIPE	SA-312/TP-304	SA-312/TP-304	80'	4, SMLS W/ EPW
(B)	12"	FLANGE	SA-105	SA-105, 10R11	150° STD	W.N., R.F.
(A)	12"	PIPE	SA-106, B		STD. WALL	SMLB., .375" WALL

BILL OF MATERIAL BA CONDITION 1

LAST WELD NO. RVIFW 31-3 DUKE POWER COMPANY LAST FL. NO. IRV 31-FL 4

McGUIRE NUCLEAR STATION

NUCLEAR SAFETY RELATED YES NO BUILDING: R-3 ZONE: A-3

PIPE SPEC: <u>PS 150-2</u>	SYS. SYMBOL: <u>RV</u>	SEC. NO: <u>08</u>	DRAWING NO: <u>MC-1418-22-43-01</u>	EL: <u>734'-1"</u>
APPLICABLE CODE: <u>ASME SECT. III</u>	CLASS: <u>B</u>	ISO. NO: <u>MCFI-IRV 31</u>	REV: <u>7</u>	

DUGAN-PHILLIPS, INC. CHARLOTTE, N.C.

SI
APERTURE
CARD

* DO I.A.W. 1965-55-16

PDR RIDS

9301140041

