



**NOTE:**  
 INTERIOR REMOVABLE WALL OPENINGS  
 TO BE CONSTRUCTED WHERE SHOWN  
 WITH HORIZONTAL & VERTICAL KEYS  
 AS SHOWN IN TYPICAL DETAILS  
 WITH DOWELS OMITTED. OPENINGS  
 TO BE FILLED LATER WITH SOLID  
 CONCRETE BLOCKS OF 150 LBS.  
 PER CU. FT. DENSITY WITH  
 MORTAR JOINTS. REINFORCED  
 WITH DURAWALL OR EQUAL  
 REINFORCEMENT EVERY OTHER  
 JOINT AS PER APPENDIX NO. 4  
 OF SPECIFICATION 9321-05-29-1.

P.R.C.  
 APERTURE  
 CARD

ENGINEER	DATE
STATE REG.	NO.
PASNY MASONRY WALL NO. 5 PAB ELEV. 15'-0	
SCALE: 1/4" = 1'-0	6604.210-6

REF. DWG 9321-F-11663  
 11773

NO.	DATE	DESCRIPTION	ENGR.	SUP. ENGR.
1	10/31/80	FIRST ISSUE	HBP	



RIDS

8208180175

