

CONDUIT SIZE	APPELTON PTC NO (STRAIGHT)	SIZE (L x D x D)
3/4" - 1"	1200	12 x 2 1/4 x 2 1/8
1 1/2"	1212	18 x 2 1/2 x 2 1/16
2"	1215	18 x 3 1/2 x 2 3/16
3"	1225	24 x 4 1/2 x 4 1/4
4"	1247	36 x 6 1/2 x 6 3/16

NOTE:

"PT" TYPE PTC FITTINGS MAY BE USED FOR CLASS I & NON-CLASS II APPLICATIONS FIELD ENGINEERING TO ASSURE MIN. BEND RADIUS OF CABLE IS NOT VIOLATED DURING PULLING.

PT TYPE FITTINGS

6-7-80	INCORPORATED	DCN # 120	D.H.	20	REG	20	INC/LL	
5-2-80	INCORP FCN	E-3936 REV DIMENSION	702	PLM	REG	20	SW/LL	
2-1-79	ISSUED FOR CONST.	INCORP RR E-1476	PPP	BC	10/8	20	SW/LL	
No.	DATE	REVISIONS	BY	CHK'D	GROUP LEAD	GROUP SUPV.	PROJ. ENGR.	CHIEF ENGR.
SCALE		DESIGNED		DRAWN		JOB No. 7220		
ORIGIN		HIGHLAND PLANT UNITS 1 AND 2		CONSUMERS POWER COMPANY		DRAWING No.		REV
		CONDUIT AND TRAY		NOTES, SYMBOLS, AND DETAILS		E-42(1) Sh 42A		3

TERA
APERTURE
CARD

16X

I certify that the image contained on this frame was made in the normal and regular course of business, on the date stated below and that it is an accurate reproduction of the document submitted to reprographics.

2-12-81 M. C. CROSBY
DATE CAMERA OPERATOR SUPERVISOR OF REPROGRAPHICS

G-1348

RIDS

807210498

