



1. USE FOR BOXES WITH A MAX. DIMENSION OF 24".
MIN. OF 4-3/8" Ø BOLTS (ONE PER CORNER).
2. DISTANCE FROM 6 OF BOLTS TO EDGE OF BOX
SHALL BE ≤ 3 INCHES OR PER DETAIL FOR
TYPE 9B AS APPLICABLE.
3. MAX. WT. IS 350 LBS. PER SH. (302, NOTE 3i).
4. FOR SUPPORTS LOCATED IN AUX. BLDG. ABOVE EL. 70'-0".
5. FOR BRACING SEE SHT. 6082, BRACING IS ALWAYS REQUIRED.
6. MIN. FLANGE WIDTH IS 8" FOR ATTACHMENT OF SUPPORT.
7. ONE BOX SUPPORT PER BEAM.
8. FOR TP MAX DISTANCE FROM THE BOX TO THE FIRST CONDUIT SUPPORT SEE
TABLE 5 SH. 311.

5/18-54 REV. FOR REGULATION ANALYSIS		5/13/81 ISSUED FOR CONSTR. PER FCN #E3236		TO	FROM				
NO.	DATE	REVISIONS	BY	CHK'D.	GROUP	SUPP.	PROJ. ENGR.	CHIEF ENGR.	
SCALE		DESIGNS		DRAWN		JOB NO.		REV.	
		MIDLAND PLANT UNITS 1 AND 2 CONSUMERS POWER COMPANY SECURITY AND TRAY NOTES, SYMBOLS, AND DETAILS		7220 DRAWING NO.		566 REV.		E-424(1) RET. 608A	

PRC
APERTURE
CARD

"I certify that the image contained on this frame was made in the normal and regular course of business on the date stated below and that it is an accurate reproduction of the document submitted to the contractor for filming by Bechtel Power Corporation."

4/11/83 Rose Spikes Sue Crockett
 Date Camera Operator Cont. Supvr.

PDR RIDS

8401100058

